



C HOW TO PROGRAM

SIXTH EDITION



C PROCEDURAL PROGRAMMING:

Control Statements
Program Development
Functions • Arrays
Pointers • Strings • I/O
Files • Structures • Unions
"Making a Difference" Exercises
Bit Manipulation • Enumerations
Data Structures • Game Programming
C99 • GNU gdb and Visual C++® Debuggers

C++ OBJECT-ORIENTED PROGRAMMING:

I/O • C++ as a "Better C" • Classes
Objects • Overloading • Inheritance
Polymorphism • Templates • Exception Handling

PAUL DEITEL
HARVEY DEITEL



HOW TO PROGRAM

SIXTH EDITION

Deitel® Series Page

How To Program Series

C How to Program, 6/E

C++ How to Program, 7/E

Java How to Program, 8/E, Early Objects Version

Java How to Program, 8/E, Late Objects Version

Internet & World Wide Web How to Program, 4/E

Visual Basic® 2008 How to Program

Visual C#® 2008 How to Program, 3/E

Visual C++® 2008 How to Program, 2/E

Small Java™ How to Program, 6/E

Small C++ How to Program, 5/E

Simply Series

Simply C++: An Application-Driven
Tutorial Approach

Simply Java™ Programming: An
Application-Driven Tutorial
Approach

Simply C#: An Application-Driven
Tutorial Approach

Simply Visual Basic® 2008, 3/E: An
Application-Driven Tutorial
Approach

CourseSmart Web Books

www.deitel.com/books/CourseSmart.html

C++ How to Program, 5/E, 6/E & 7/E

Java How to Program, 6/E, 7/E & 8/E

Simply C++: An Application-Driven
Tutorial Approach

Simply Visual Basic 2008: An
Application-Driven Tutorial
Approach, 3/E

Small C++ How to Program, 5/E

Small Java How to Program, 6/E

Visual Basic® 2008 How to Program

Visual C#® 2008 How to Program, 3/E

Deitel® Developer Series

AJAX, Rich Internet Applications and
Web Development for Programmers

C++ for Programmers

C# 2008 for Programmers, 3/E

iPhone for Programmers:
An App-Driven Approach

Java for Programmers

Javascript for Programmers

LiveLessons Video Learning Products

www.deitel.com/books/LiveLessons/

Java Fundamentals Parts 1 and 2

C# Fundamentals Parts 1 and 2

C++ Fundamentals Parts 1 and 2

JavaScript Fundamentals Parts 1 and 2

To receive updates on Deitel publications, Resource Centers, training courses, partner offers and more, please register for the free *Deitel® Buzz Online* e-mail newsletter at:

www.deitel.com/newsletter/subscribe.html

follow us on Twitter®

@deitel

and Facebook®

www.deitel.com/deitelfan/

To communicate with the authors, send e-mail to:

deitel@deitel.com

For information on government and corporate *Dive-Into® Series* on-site seminars offered by Deitel & Associates, Inc. worldwide, visit:

www.deitel.com/training/

or write to

deitel@deitel.com

For continuing updates on Prentice Hall/Deitel publications visit:

www.deitel.com

www.pearsonhighered.com/deitel

Check out our Resource Centers for valuable web resources that will help you master Java, other important programming languages, software and Internet- and web-related topics:

www.deitel.com/ResourceCenters.html

Library of Congress Cataloging-in-Publication Data
On file

Vice President and Editorial Director, ECS: **Marcia J. Horton**
Editor-in-Chief, Computer Science: **Michael Hirsch**
Associate Editor: **Carole Snyder**
Supervisor/Editorial Assistant: **Dolores Mars**
Director of Team-Based Project Management: **Vince O'Brien**
Senior Managing Editor: **Scott Disanno**
Managing Editor: **Robert Engelhardt**
A/V Production Editor: **Greg Dulles**
Art Director: **Kristine Carney**
Cover Design: **Abbey S. Deitel, Harvey M. Deitel, Francesco Santalucia, Kristine Carney**
Interior Design: **Harvey M. Deitel, Kristine Carney**
Manufacturing Manager: **Alexis Heydt-Long**
Manufacturing Buyer: **Lisa McDowell**
Director of Marketing: **Margaret Waples**
Marketing Manager: **Erin Davis**



© 2010 by Pearson Education, Inc.
Upper Saddle River, New Jersey 07458

The authors and publisher of this book have used their best efforts in preparing this book. These efforts include the development, research, and testing of the theories and programs to determine their effectiveness. The authors and publisher make no warranty of any kind, expressed or implied, with regard to these programs or to the documentation contained in this book. The authors and publisher shall not be liable in any event for incidental or consequential damages in connection with, or arising out of, the furnishing, performance, or use of these programs.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks and registered trademarks. Where those designations appear in this book, and Prentice Hall and the authors were aware of a trademark claim, the designations have been printed in initial caps or all caps. All product names mentioned remain trademarks or registered trademarks of their respective owners.

All rights reserved. No part of this book may be reproduced, in any form or by any means, without permission in writing from the publisher.

Printed in the United States of America

10 9 8 7 6 5 4 3 2 1

ISBN-10: 0-13-612356-2

ISBN-13: 978-0-13-612356-9

Pearson Education Ltd., *London*
Pearson Education Australia Pty. Ltd., *Sydney*
Pearson Education Singapore, Pte. Ltd.
Pearson Education North Asia Ltd., *Hong Kong*
Pearson Education Canada, Inc., *Toronto*
Pearson Educación de Mexico, S.A. de C.V.
Pearson Education-Japan, *Tokyo*
Pearson Education Malaysia, Pte. Ltd.
Pearson Education, Inc., *Upper Saddle River, New Jersey*



HOW TO PROGRAM

SIXTH EDITION

P. J. Deitel

Deitel & Associates, Inc.

H. M. Deitel

Deitel & Associates, Inc.



Upper Saddle River, New Jersey 07458

Trademarks

DEITEL, the double-thumbs-up bug and DIVE INTO are registered trademarks of Deitel and Associates, Inc.

Microsoft, Visual C++, Internet Explorer and the Windows logo are either registered trademarks or trademarks of Microsoft Corporation in the United States and/or other countries.

In Memory of Clifford Stephens:

*Your friendship, bright smile and
infectious laugh will be truly missed.*

Paul and Harvey Deitel

Deitel Resource Centers

Our Resource Centers focus on the vast amounts of free content available online. Find resources, downloads, tutorials, documentation, books, e-books, journals, articles, blogs, RSS feeds and more on many of today's hottest programming and technology topics. For the most up-to-date list of our Resource Centers, visit:

www.deitel.com/ResourceCenters.html

Let us know what other Resource Centers you'd like to see! Also, please register for the free *Deitel® Buzz Online* e-mail newsletter at:

www.deitel.com/newsletter/subscribe.html

Computer Science

Functional Programming
Regular Expressions

Programming

ASP.NET 3.5
Adobe Flex
Ajax
Apex
ASP.NET Ajax
ASP.NET
C
C++
C++ Boost Libraries
C++ Game Programming
C#
Code Search Engines and Code Sites
Computer Game Programming
CSS 2.1
Dojo
Facebook Developer Platform
Flash 9
Functional Programming Java
Java Certification and Assessment Testing
Java Design Patterns
Java EE 5
Java SE 6
Java SE 7 (Dolphin) Resource Center
JavaFX
JavaScript
JSON
Microsoft LINQ
Microsoft Popfly
.NET
.NET 3.0
.NET 3.5
OpenGL
Perl
PHP
Programming Projects
Python
Regular Expressions
Ruby
Ruby on Rails
Silverlight

UML
Visual Basic
Visual C++
Visual Studio Team System
Web 3D Technologies
Web Services
Windows Presentation Foundation
XHTML
XML

Apple

iPhone
Objective-C
Cocoa

Games and Game Programming

Computer Game Programming
Computer Games
Mobile Gaming
Sudoku

Internet Business

Affiliate Programs
Competitive Analysis
Facebook Social Ads
Google AdSense
Google Analytics
Google Services
Internet Advertising
Internet Business Initiative
Internet Public Relations
Link Building
Location-Based Services
Online Lead Generation
Podcasting
Search Engine Optimization
Selling Digital Content
Sitemaps
Web Analytics
Website Monetization
YouTube and AdSense

Java

Java
Java Certification and Assessment Testing

Java Design Patterns
Java EE 5
Java SE 6
Java SE 7 (Dolphin) Resource Center
JavaFX

Microsoft

ASP.NET
ASP.NET 3.5
ASP.NET Ajax
C#
DotNetNuke (DNN)
Internet Explorer 7 (IE7)
Microsoft LINQ
.NET
.NET 3.0
.NET 3.5
SharePoint
Silverlight
Visual Basic
Visual C++
Visual Studio Team System
Windows Presentation Foundation
Windows Vista
Microsoft Popfly

Open Source & LAMP Stack

Apache
DotNetNuke (DNN)
Eclipse
Firefox
Linux
MySQL
Open Source
Perl
PHP
Python
Ruby

Software

Apache
DotNetNuke (DNN)
Eclipse
Firefox
Internet Explorer 7 (IE7)
Linux
MySQL

Open Source
Search Engines
SharePoint
Skype
Web Servers
Wikis
Windows Vista

Web 2.0

Alert Services
Attention Economy
Blogging
Building Web Communities
Community Generated Content
Facebook Developer Platform
Facebook Social Ads
Google Base
Google Video
Google Web Toolkit (GWT)
Internet Video
Joost
Location-Based Services
Mashups
Microformats
Recommender Systems
RSS
Social Graph
Social Media
Social Networking
Software as a Service (SaaS)
Virtual Worlds
Web 2.0
Web 3.0
Widgets

Dive Into® Web 2.0 eBook

Web 2 eBook

Other Topics

Computer Games
Computing Jobs
Gadgets and Gizmos
Ring Tones
Sudoku

Contents

Appendices E through I are PDF documents posted online at the book's Companion Website (located at www.pearsonhighered.com/deitel).

Preface

xxi

I Introduction to Computers, the Internet and the Web **I**

1.1	Introduction	2
1.2	Computers: Hardware and Software	3
1.3	Computer Organization	4
1.4	Personal, Distributed and Client/Server Computing	5
1.5	The Internet and the World Wide Web	5
1.6	Machine Languages, Assembly Languages and High-Level Languages	6
1.7	History of C	7
1.8	C Standard Library	8
1.9	C++	9
1.10	Java	9
1.11	Fortran, COBOL, Pascal and Ada	10
1.12	BASIC, Visual Basic, Visual C++, C# and .NET	10
1.13	Key Software Trend: Object Technology	11
1.14	Typical C Program Development Environment	12
1.15	Hardware Trends	14
1.16	Notes About C and This Book	15
1.17	Web Resources	16

2 Introduction to C Programming **23**

2.1	Introduction	24
2.2	A Simple C Program: Printing a Line of Text	24
2.3	Another Simple C Program: Adding Two Integers	28
2.4	Memory Concepts	33
2.5	Arithmetic in C	34
2.6	Decision Making: Equality and Relational Operators	38

3 Structured Program Development in C **54**

3.1	Introduction	55
3.2	Algorithms	55

3.3	Pseudocode	55
3.4	Control Structures	56
3.5	The <code>if</code> Selection Statement	58
3.6	The <code>if...else</code> Selection Statement	59
3.7	The <code>while</code> Repetition Statement	63
3.8	Formulating Algorithms Case Study 1: Counter-Controlled Repetition	64
3.9	Formulating Algorithms with Top-Down, Stepwise Refinement Case Study 2: Sentinel-Controlled Repetition	66
3.10	Formulating Algorithms with Top-Down, Stepwise Refinement Case Study 3: Nested Control Structures	73
3.11	Assignment Operators	77
3.12	Increment and Decrement Operators	78

4 **C Program Control** **97**

4.1	Introduction	98
4.2	Repetition Essentials	98
4.3	Counter-Controlled Repetition	99
4.4	<code>for</code> Repetition Statement	100
4.5	<code>for</code> Statement: Notes and Observations	103
4.6	Examples Using the <code>for</code> Statement	103
4.7	<code>switch</code> Multiple-Selection Statement	107
4.8	<code>do...while</code> Repetition Statement	113
4.9	<code>break</code> and <code>continue</code> Statements	114
4.10	Logical Operators	116
4.11	Confusing Equality (<code>==</code>) and Assignment (<code>=</code>) Operators	119
4.12	Structured Programming Summary	121

5 **C Functions** **140**

5.1	Introduction	141
5.2	Program Modules in C	141
5.3	Math Library Functions	142
5.4	Functions	144
5.5	Function Definitions	144
5.6	Function Prototypes	148
5.7	Function Call Stack and Activation Records	151
5.8	Headers	151
5.9	Calling Functions By Value and By Reference	152
5.10	Random Number Generation	153
5.11	Example: A Game of Chance	158
5.12	Storage Classes	161
5.13	Scope Rules	164
5.14	Recursion	167
5.15	Example Using Recursion: Fibonacci Series	170
5.16	Recursion vs. Iteration	174

6	C Arrays	195
6.1	Introduction	196
6.2	Arrays	196
6.3	Defining Arrays	198
6.4	Array Examples	198
6.5	Passing Arrays to Functions	212
6.6	Sorting Arrays	216
6.7	Case Study: Computing Mean, Median and Mode Using Arrays	218
6.8	Searching Arrays	223
6.9	Multiple-Subscripted Arrays	229
7	C Pointers	253
7.1	Introduction	254
7.2	Pointer Variable Definitions and Initialization	254
7.3	Pointer Operators	255
7.4	Passing Arguments to Functions by Reference	257
7.5	Using the <code>const</code> Qualifier with Pointers	261
7.6	Bubble Sort Using Call-by-Reference	267
7.7	<code>sizeof</code> Operator	270
7.8	Pointer Expressions and Pointer Arithmetic	273
7.9	Relationship between Pointers and Arrays	275
7.10	Arrays of Pointers	280
7.11	Case Study: Card Shuffling and Dealing Simulation	280
7.12	Pointers to Functions	285
8	C Characters and Strings	309
8.1	Introduction	310
8.2	Fundamentals of Strings and Characters	310
8.3	Character-Handling Library	312
8.4	String-Conversion Functions	317
8.5	Standard Input/Output Library Functions	322
8.6	String-Manipulation Functions of the String-Handling Library	326
8.7	Comparison Functions of the String-Handling Library	329
8.8	Search Functions of the String-Handling Library	331
8.9	Memory Functions of the String-Handling Library	337
8.10	Other Functions of the String-Handling Library	341
9	C Formatted Input/Output	356
9.1	Introduction	357
9.2	Streams	357
9.3	Formatting Output with <code>printf</code>	357
9.4	Printing Integers	358
9.5	Printing Floating-Point Numbers	359

9.6	Printing Strings and Characters	361
9.7	Other Conversion Specifiers	362
9.8	Printing with Field Widths and Precision	363
9.9	Using Flags in the <code>printf</code> Format Control String	366
9.10	Printing Literals and Escape Sequences	368
9.11	Reading Formatted Input with <code>scanf</code>	369

10 C Structures, Unions, Bit Manipulations and Enumerations **382**

10.1	Introduction	383
10.2	Structure Definitions	383
10.3	Initializing Structures	386
10.4	Accessing Structure Members	386
10.5	Using Structures with Functions	388
10.6	<code>typedef</code>	388
10.7	Example: High-Performance Card Shuffling and Dealing Simulation	389
10.8	Unions	391
10.9	Bitwise Operators	394
10.10	Bit Fields	403
10.11	Enumeration Constants	406

11 C File Processing **417**

11.1	Introduction	418
11.2	Data Hierarchy	418
11.3	Files and Streams	420
11.4	Creating a Sequential-Access File	421
11.5	Reading Data from a Sequential-Access File	426
11.6	Random-Access Files	430
11.7	Creating a Random-Access File	431
11.8	Writing Data Randomly to a Random-Access File	433
11.9	Reading Data from a Random-Access File	436
11.10	Case Study: Transaction-Processing Program	437

12 C Data Structures **454**

12.1	Introduction	455
12.2	Self-Referential Structures	456
12.3	Dynamic Memory Allocation	456
12.4	Linked Lists	458
12.5	Stacks	466
12.6	Queues	472
12.7	Trees	478

13 C Preprocessor **495**

13.1	Introduction	496
------	--------------	-----

13.2	<code>#include</code> Preprocessor Directive	496
13.3	<code>#define</code> Preprocessor Directive: Symbolic Constants	496
13.4	<code>#define</code> Preprocessor Directive: Macros	497
13.5	Conditional Compilation	499
13.6	<code>#error</code> and <code>#pragma</code> Preprocessor Directives	500
13.7	<code>#</code> and <code>##</code> Operators	500
13.8	Line Numbers	501
13.9	Predefined Symbolic Constants	501
13.10	Assertions	502

14 Other C Topics **507**

14.1	Introduction	508
14.2	Redirecting I/O	508
14.3	Variable-Length Argument Lists	509
14.4	Using Command-Line Arguments	511
14.5	Notes on Compiling Multiple-Source-File Programs	512
14.6	Program Termination with <code>exit</code> and <code>atexit</code>	514
14.7	<code>volatile</code> Type Qualifier	515
14.8	Suffixes for Integer and Floating-Point Constants	516
14.9	More on Files	516
14.10	Signal Handling	518
14.11	Dynamic Memory Allocation: Functions <code>calloc</code> and <code>realloc</code>	520
14.12	Unconditional Branching with <code>goto</code>	521

15 C++ as a Better C; Introducing Object Technology **528**

15.1	Introduction	529
15.2	C++	529
15.3	A Simple Program: Adding Two Integers	530
15.4	C++ Standard Library	532
15.5	Header Files	533
15.6	Inline Functions	535
15.7	References and Reference Parameters	537
15.8	Empty Parameter Lists	542
15.9	Default Arguments	542
15.10	Unary Scope Resolution Operator	544
15.11	Function Overloading	545
15.12	Function Templates	548
15.13	Introduction to Object Technology and the UML	551
15.14	Wrap-Up	554

16 Introduction to Classes and Objects **560**

16.1	Introduction	561
16.2	Classes, Objects, Member Functions and Data Members	561

16.3	Defining a Class with a Member Function	562
16.4	Defining a Member Function with a Parameter	566
16.5	Data Members, <i>set</i> Functions and <i>get</i> Functions	569
16.6	Initializing Objects with Constructors	576
16.7	Placing a Class in a Separate File for Reusability	579
16.8	Separating Interface from Implementation	583
16.9	Validating Data with <i>set</i> Functions	589
16.10	Wrap-Up	594

17 **Classes: A Deeper Look, Part 1** **601**

17.1	Introduction	602
17.2	Time Class Case Study	603
17.3	Class Scope and Accessing Class Members	609
17.4	Separating Interface from Implementation	611
17.5	Access Functions and Utility Functions	612
17.6	Time Class Case Study: Constructors with Default Arguments	615
17.7	Destructors	620
17.8	When Constructors and Destructors are Called	621
17.9	Time Class Case Study: A Subtle Trap—Returning a Reference to a private Data Member	624
17.10	Default Memberwise Assignment	627
17.11	Wrap-Up	629

18 **Classes: A Deeper Look, Part 2** **635**

18.1	Introduction	636
18.2	<code>const</code> (Constant) Objects and <code>const</code> Member Functions	636
18.3	Composition: Objects as Members of Classes	645
18.4	<code>friend</code> Functions and <code>friend</code> Classes	651
18.5	Using the <code>this</code> Pointer	654
18.6	<code>static</code> Class Members	659
18.7	Data Abstraction and Information Hiding	664
18.8	Wrap-Up	666

19 **Operator Overloading** **672**

19.1	Introduction	673
19.2	Fundamentals of Operator Overloading	674
19.3	Restrictions on Operator Overloading	675
19.4	Operator Functions as Class Members vs. Global Function	676
19.5	Overloading Stream Insertion and Stream Extraction Operators	678
19.6	Overloading Unary Operators	681
19.7	Overloading Binary Operators	682
19.8	Dynamic Memory Management	682
19.9	Case Study: Array Class	684
19.10	Converting between Types	696

19.11	Building a String Class	697
19.12	Overloading ++ and --	698
19.13	Case Study: A Date Class	700
19.14	Standard Library Class string	704
19.15	explicit Constructors	708
19.16	Proxy Classes	711
19.17	Wrap-Up	715

20 Object-Oriented Programming: Inheritance 727

20.1	Introduction	728
20.2	Base Classes and Derived Classes	729
20.3	protected Members	732
20.4	Relationship between Base Classes and Derived Classes	732
20.4.1	Creating and Using a CommissionEmployee Class	733
20.4.2	Creating a BasePlusCommissionEmployee Class Without Using Inheritance	738
20.4.3	Creating a CommissionEmployee–BasePlusCommissionEmployee Inheritance Hierarchy	743
20.4.4	CommissionEmployee–BasePlusCommissionEmployee Inheritance Hierarchy Using protected Data	748
20.4.5	CommissionEmployee–BasePlusCommissionEmployee Inheritance Hierarchy Using private Data	755
20.5	Constructors and Destructors in Derived Classes	762
20.6	public, protected and private Inheritance	770
20.7	Software Engineering with Inheritance	771
20.8	Wrap-Up	772

21 Object-Oriented Programming: Polymorphism 778

21.1	Introduction	779
21.2	Polymorphism Examples	780
21.3	Relationships Among Objects in an Inheritance Hierarchy	781
21.3.1	Invoking Base-Class Functions from Derived-Class Objects	782
21.3.2	Aiming Derived-Class Pointers at Base-Class Objects	789
21.3.3	Derived-Class Member-Function Calls via Base-Class Pointers	790
21.3.4	Virtual Functions	792
21.3.5	Summary of the Allowed Assignments Between Base-Class and Derived-Class Objects and Pointers	798
21.4	Type Fields and switch Statements	799
21.5	Abstract Classes and Pure virtual Functions	799
21.6	Case Study: Payroll System Using Polymorphism	801
21.6.1	Creating Abstract Base Class Employee	803
21.6.2	Creating Concrete Derived Class SalariedEmployee	806
21.6.3	Creating Concrete Derived Class HourlyEmployee	808
21.6.4	Creating Concrete Derived Class CommissionEmployee	811

21.6.5	Creating Indirect Concrete Derived Class BasePlusCommissionEmployee	813
21.6.6	Demonstrating Polymorphic Processing	814
21.7	(Optional) Polymorphism, Virtual Functions and Dynamic Binding “Under the Hood”	818
21.8	Case Study: Payroll System Using Polymorphism and Runtime Type Information with Downcasting, <code>dynamic_cast</code> , <code>typeid</code> and <code>type_info</code>	822
21.9	Virtual Destructors	826
21.10	Wrap-Up	826

22 Templates 832

22.1	Introduction	833
22.2	Function Templates	833
22.3	Overloading Function Templates	837
22.4	Class Templates	837
22.5	Nontype Parameters and Default Types for Class Templates	844
22.6	Notes on Templates and Inheritance	845
22.7	Notes on Templates and Friends	845
22.8	Notes on Templates and <code>static</code> Members	846
22.9	Wrap-Up	846

23 Stream Input/Output 851

23.1	Introduction	852
23.2	Streams	853
23.2.1	Classic Streams vs. Standard Streams	853
23.2.2	<code>iostream</code> Library Header Files	854
23.2.3	Stream Input/Output Classes and Objects	854
23.3	Stream Output	857
23.3.1	Output of <code>char *</code> Variables	857
23.3.2	Character Output Using Member Function <code>put</code>	857
23.4	Stream Input	858
23.4.1	<code>get</code> and <code>getline</code> Member Functions	858
23.4.2	<code>istream</code> Member Functions <code>peek</code> , <code>putback</code> and <code>ignore</code>	861
23.4.3	Type-Safe I/O	861
23.5	Unformatted I/O Using <code>read</code> , <code>write</code> and <code>gcount</code>	861
23.6	Introduction to Stream Manipulators	862
23.6.1	Integral Stream Base: <code>dec</code> , <code>oct</code> , <code>hex</code> and <code>setbase</code>	863
23.6.2	Floating-Point Precision (<code>precision</code> , <code>setprecision</code>)	864
23.6.3	Field Width (<code>width</code> , <code>setw</code>)	865
23.6.4	User-Defined Output Stream Manipulators	866
23.7	Stream Format States and Stream Manipulators	868
23.7.1	Trailing Zeros and Decimal Points (<code>showpoint</code>)	868
23.7.2	Justification (<code>left</code> , <code>right</code> and <code>internal</code>)	869
23.7.3	Padding (<code>fill</code> , <code>setfill</code>)	871
23.7.4	Integral Stream Base (<code>dec</code> , <code>oct</code> , <code>hex</code> , <code>showbase</code>)	872

23.7.5	Floating-Point Numbers; Scientific and Fixed Notation (scientific, fixed)	873
23.7.6	Uppercase/Lowercase Control (uppercase)	874
23.7.7	Specifying Boolean Format (boolalpha)	874
23.7.8	Setting and Resetting the Format State via Member Function flags	875
23.8	Stream Error States	877
23.9	Tying an Output Stream to an Input Stream	879
23.10	Wrap-Up	879

24 Exception Handling **889**

24.1	Introduction	890
24.2	Exception-Handling Overview	891
24.3	Example: Handling an Attempt to Divide by Zero	891
24.4	When to Use Exception Handling	897
24.5	Rethrowing an Exception	898
24.6	Exception Specifications	900
24.7	Processing Unexpected Exceptions	901
24.8	Stack Unwinding	901
24.9	Constructors, Destructors and Exception Handling	903
24.10	Exceptions and Inheritance	904
24.11	Processing new Failures	904
24.12	Class <code>auto_ptr</code> and Dynamic Memory Allocation	907
24.13	Standard Library Exception Hierarchy	909
24.14	Other Error-Handling Techniques	911
24.15	Wrap-Up	912

A Operator Precedence Charts **919**

B ASCII Character Set **923**

C Number Systems **924**

C.1	Introduction	925
C.2	Abbreviating Binary Numbers as Octal and Hexadecimal Numbers	928
C.3	Converting Octal and Hexadecimal Numbers to Binary Numbers	929
C.4	Converting from Binary, Octal or Hexadecimal to Decimal	929
C.5	Converting from Decimal to Binary, Octal or Hexadecimal	930
C.6	Negative Binary Numbers: Two's Complement Notation	932

D Game Programming: Solving Sudoku **937**

D.1	Introduction	937
D.2	Deitel Sudoku Resource Center	938
D.3	Solution Strategies	938

D.4	Programming Sudoku Puzzle Solvers	942
D.5	Generating New Sudoku Puzzles	943
D.6	Conclusion	945

Appendices on the Web 946

Appendices E through I are PDF documents posted online at the book's Companion Website (located at www.pearsonhighered.com/deitel).

E Game Programming with the Allegro C Library I

E.1	Introduction	II
E.2	Installing Allegro	II
E.3	A Simple Allegro Program	III
E.4	Simple Graphics: Importing Bitmaps and Blitting	IV
E.5	Animation with Double Buffering	IX
E.6	Importing and Playing Sounds	XVI
E.7	Keyboard Input	XX
E.8	Fonts and Displaying Text	XXV
E.9	Implementing the Game of Pong	XXXI
E.10	Timers in Allegro	XXXVII
E.11	The Grabber and Allegro Datafiles	XLII
E.12	Other Allegro Capabilities	LI
E.13	Allegro Resource Center	LII

F Sorting: A Deeper Look LVIII

F.1	Introduction	LIX
F.2	Big O Notation	LIX
F.3	Selection Sort	LX
F.4	Insertion Sort	LXIV
F.5	Merge Sort	LXVII

G Introduction to C99 LXXVIII

G.1	Introduction	LXXIX
G.2	Support for C99	LXXIX
G.3	New C99 Headers	LXXX
G.4	// Comments	LXXX
G.5	Mixing Declarations and Executable Code	LXXXI
G.6	Declaring a Variable in a for Statement Header	LXXXII
G.7	Designated Initializers and Compound Literals	LXXXIV
G.8	Type <code>bool</code>	LXXXVII
G.9	Implicit <code>int</code> in Function Declarations	LXXXVIII
G.10	Complex Numbers	LXXXIX
G.11	Variable-Length Arrays	XC

G.12	The <code>sprintf</code> Function: Helping Avoid Hacker Attacks	XCIII
G.13	Additions to the Preprocessor	XCV
G.14	Other C99 Features	XCVI
G.15	Web Resources	XCIX

H Using the Visual Studio Debugger **CIV**

H.1	Introduction	CV
H.2	Breakpoints and the Continue Command	CV
H.3	Locals and Watch Windows	CIX
H.4	Controlling Execution Using the Step Into , Step Over , Step Out and Continue Commands	CXII
H.5	Autos Window	CXIV
H.6	Wrap-Up	CXVI

I Using the GNU Debugger **CXVIII**

I.1	Introduction	CXIX
I.2	Breakpoints and the <code>run</code> , <code>stop</code> , <code>continue</code> and <code>print</code> Commands	CXIX
I.3	<code>print</code> and <code>set</code> Commands	CXXIV
I.4	Controlling Execution Using the <code>step</code> , <code>finish</code> and <code>next</code> Commands	CXXVI
I.5	<code>watch</code> Command	CXXVIII
I.6	Wrap-Up	CXXX

This page intentionally left blank



Preface

Welcome to the C programming language—and to C++, too! This book presents leading-edge computing technologies for students, instructors and software development professionals.

At the heart of the book is the Deitel signature “live-code approach.” Concepts are presented in the context of complete working programs, rather than in code snippets. Each code example is immediately followed by one or more sample executions. All the source code is available at www.deitel.com/books/cht6/.

We believe that this book and its support materials will give you an informative, interesting, challenging and entertaining introduction to C.

As you read the book, if you have questions, send an e-mail to deitel@deitel.com; we’ll respond promptly. For updates on this book and its supporting C and C++ software, and for the latest news on all Deitel publications and services, visit www.deitel.com.

New and Updated Features

Here are the updates we’ve made for *C How to Program, 6/e*:

- **“Making a Difference” Exercises Set.** We encourage you to use computers and the Internet to research and solve problems that really matter. These new exercises are meant to increase awareness of important issues the world is facing. We hope you’ll approach them with your own values, politics and beliefs.
- **Tested All Code on Windows and Linux.** We’ve tested every program (the examples and the exercises) using both Visual C++ 2008 and GNU GCC 4.3. The code examples and exercise code solutions were also tested using Visual Studio 2010 Beta.
- **New Design.** The book has a new interior design that graphically serves to organize, clarify and highlight the information, and enhances the book’s pedagogy.
- **Improved Terminology Sections.** We’ve added page numbers for the defining occurrences of all terms in the terminology lists for easy reference.
- **Updated Coverage of C++ and Object-Oriented Programming.** We updated Chapters 15–24 on object-oriented programming in C++ with material from our just published *C++ How to Program, 7/e*.
- **Titled Programming Exercises.** We’ve titled all the programming exercises. This helps instructors tune assignments for their classes.
- **New Web Appendices.** Chapters 15–17 from the previous edition are now searchable PDF Appendices E–G, available on the Companion Website (see the access card at the front of the book).

- *New Debugger Appendices.* We also added new debugging appendices for Visual C++[®] 2008 and GNU gdb.
- *Order of Evaluation.* We added cautions about order of evaluation issues.
- We replaced all uses of `gets` (from `<stdio.h>`) with `fgets`, because `gets` is now deprecated.
- *Additional Exercises.* We added more function pointer exercises. We also added the Fibonacci exercise project that improves the Fibonacci recursion example (tail recursion).
- *Secure C Programming Resource Center.* We've posted a new Secure C Programming Resource Center at www.deitel.com/SecureC/. We've also added notes about secure C programming to the introductions in Chapter 7, Pointers, and Chapter 8, Strings.
- *Game Programming with Allegro.* We updated the chapter on game programming with the Allegro C library. In particular, we added instructions on installing the Allegro libraries for use with Visual C++[®] 2008 and GNU GCC 4.3.
- *Coverage of the C99 Standard.* We updated and enhanced the detailed appendix on C99, which was reviewed by John Benito, Convener of ISO WG14—the Working Group responsible for the C Programming Language Standard. Each C99 concept is now keyed to the section where it can be taught earlier in the book. C99 is not incorporated throughout the book because Microsoft does not yet support it and a large percentage of C courses use Microsoft's Visual C++[®] compiler. For additional information, check out the C99 Standard section in our C Resource center at www.deitel.com/C/. You'll find features of C99, articles from experts, the differences between Standard C and C99, FAQs, downloads and more.
- *C++-Style // Comments.* We discuss C++-style `//` comments early for instructors and students who'd prefer to use them. Although Microsoft C does not yet support C99, it does support C99's comments, which are borrowed from C++.
- *C Standard Library.* Section 1.8 now references P.J. Plauger's Dinkumware website (www.dinkumware.com/manuals/default.aspx) where students can find thorough searchable documentation for the C Standard Library functions.

Other Features

Other features of *C How to Program, 6/e*, include:

Game Programming with the Allegro C Game Programming Library

Appendix E introduces the Allegro game programming C library. This library—originally developed by Climax game programmer Shawn Hargreaves—was created to be a powerful tool for programming games in C while still remaining relatively simple compared to other, more complicated graphics libraries such as DirectX and OpenGL. In Appendix E, we use Allegro's capabilities to create the simple game of Pong. Along the way, we demonstrate how to display graphics, play sounds, receive input from the keyboard and create timed events—features you can use to create games of your own. Students and instructors

alike will find Allegro challenging and entertaining. We include extensive web resources in our Allegro Resource Center (www.deitel.com/allegro), one of which offers more than 1000 open-source Allegro games.

Sorting: A Deeper Look

Sorting places data in order, based on one or more sort keys. We begin our presentation of sorting with a simple algorithm in Chapter 6. In Appendix F, we present a deeper look at sorting. We consider several algorithms and compare them with regard to their memory consumption and processor demands. For this purpose, we introduce Big O notation, which indicates how hard an algorithm may have to work to solve a problem. Through examples and exercises, Appendix F discusses the selection sort, insertion sort, recursive merge sort, recursive selection sort, bucket sort and recursive Quicksort.

Web-Based Materials

This book is supported by substantial online materials. The book's Companion Website (www.pearsonhighered.com/deitel; see the access card at the front of the book) contains the following appendices in *searchable* PDF format:

- Appendix E, Game Programming with the Allegro C Library
- Appendix F, Sorting: A Deeper Look
- Appendix G, Introduction to C99
- Appendix H, Using the Visual Studio Debugger
- Appendix I, Using the GNU Debugger

Dependency Charts

The dependency charts in Figs. 1–2 show the dependencies among the chapters to help instructors plan their syllabi. *C How to Program, 6/e* is appropriate for CS1 and CS2 courses, and intermediate-level C and C++ programming courses. The C++ part of the book assumes that you have studied the C part.

Teaching Approach

C How to Program, 6/e, contains a rich collection of examples. We concentrate on demonstrating the principles of good software engineering and stressing program clarity.

Live-Code Approach. *C How to Program, 6/e*, is loaded with “live-code” examples. Most new concepts are presented in the context of complete working C applications, followed by one or more executions showing program inputs and outputs.

Syntax Shading

For readability, we syntax shade the code, similar to the way most integrated-development environments and code editors syntax color code. Our syntax-shading conventions are:

```

comments appear like this
keywords appear like this
constants and literal values appear like this
all other code appears in black
  
```

C Chapter Dependency Chart

[Note: Arrows pointing into a chapter indicate that chapter's dependencies.]




Fig. 1 | C chapter dependency chart.

Code Highlighting

We place gray rectangles around the key code.

Using Fonts for Emphasis. We place the key terms and the index's page reference for each defining occurrence in **bold blue** text for easy reference. We emphasize on-screen components in the **bold Helvetica** font (e.g., the **File** menu) and C program text in the **Lucida** font (for example, `int x = 5;`).

Web Access. All of the source-code examples are available for download from:

www.deitel.com/books/cht6/

C++ Chapter Dependency Chart

[Note: Arrows pointing into a chapter indicate that chapter's dependencies.]




Fig. 2 | C++ chapter dependency chart.

Quotations. Each chapter begins with quotations. We hope that you enjoy relating these to the chapter material.

Objectives. The quotes are followed by a list of chapter objectives.

Illustrations/Figures. Abundant charts, tables, line drawings, UML diagrams, programs and program output are included.

Programming Tips

We include programming tips to help you focus on important aspects of program development. These tips and practices represent the best we've gleaned from a combined seven decades of programming and teaching experience.



Good Programming Practice

The Good Programming Practices call attention to techniques that will help you produce programs that are clearer, more understandable and more maintainable.



Common Programming Error

Pointing out these Common Programming Errors reduces the likelihood that you'll make them.



Error-Prevention Tip

These tips contain suggestions for exposing and removing bugs from your programs; many describe aspects of C that prevent bugs from getting into programs in the first place.



Performance Tip

These tips highlight opportunities for making your programs run faster or minimizing the amount of memory that they occupy.



Portability Tip

The Portability Tips help you write code that will run on a variety of platforms.



Software Engineering Observation

The Software Engineering Observations highlight architectural and design issues that affect the construction of software systems, especially large-scale systems.

Summary Bullets. We present a section-by-section, bullet-list summary of the chapter.

Terminology. We include an alphabetized list of the important terms defined in each chapter with the page number of each term's defining occurrence for easy reference.

Self-Review Exercises and Answers. Extensive self-review exercises *and* answers are included for self-study.

Exercises. Each chapter concludes with a substantial set of exercises including:

- simple recall of important terminology and concepts,
- identifying the errors in code samples,
- writing individual C statements,
- writing small portions of functions and classes,
- writing complete C functions, classes and programs, and
- major projects.

Instructors can use these exercises to form homework assignments, short quizzes, major examinations and term projects. [NOTE: Please do not write to us requesting access to the Pearson Instructor's Resource Center which contains the book's instructor supplements, including the exercise solutions. Access is limited strictly to college instructors teaching from the book. Instructors may obtain access only through their Pearson representatives. Solutions are *not* provided for "project" exercises.] Check out our Programming Projects Resource Center (www.deitel.com/ProgrammingProjects/) for lots of additional exercise and project possibilities.

Index. We've included an extensive index, which is especially useful when you use the book as a reference. Defining occurrences of key terms are highlighted with a **bold blue** page number.

Student Resources

Many C and C++ development tools are available. We wrote *C How to Program*, 6/e primarily using Microsoft's free Visual C++[®] Express Edition (which is available free for download at www.microsoft.com/express/vc/) and the free GNU C++ (gcc.gnu.org/install/binaries.html), which is already installed on most Linux systems and can be installed on

Mac OS X and Windows systems as well. You can learn more about Visual C++[®] Express at msdn.microsoft.com/vstudio/express/visualc. You can learn more about GNU C++ at gcc.gnu.org. Apple includes GNU C++ in their Xcode development tools, which Mac OS X users can download from developer.apple.com/tools/xcode.

You can download the book's examples and additional resources from:

www.deitel.com/books/cht6/

For additional resources and software downloads see our C Resource Center:

www.deitel.com/c/

For other C and C++ compilers that are available free for download:

www.thefreecountry.com/development/ccompilers.shtml
www.compilers.net/Dir/Compilers/CCpp.htm

CourseSmart Web Books

Today's students and instructors have increasing demands on their time and money. Pearson has responded to that need by offering digital texts and course materials online through CourseSmart. CourseSmart allows faculty to review course materials online saving time and costs. It is also environmentally sound and offers students a high-quality digital version of the text for as much as 50% off the cost of a print copy of the text. Students receive the same content offered in the print textbook enhanced by search, note-taking, and printing tools. For more information, visit www.coursesmart.com.

Software for the Book

This book includes the Microsoft[®] Visual Studio[®] 2008 Express Editions All-in-One DVD, which contains the Visual C++[®] 2008 Express Edition (and other Microsoft development tools). You can also download the latest version of Visual C++ Express Edition from:

www.microsoft.com/express/vc

Per Microsoft's website, Express Editions are "lightweight, easy-to-use and easy-to-learn tools for the hobbyist, novice and student developer." They are appropriate for academic courses and for professionals who do not have access to a complete version of Visual Studio 2008.

With the exception of one example in Chapter 9, C Formatted Input/Output, and the examples in Appendix G, Introduction to C99, all of the examples in this book compile and run in Visual C++[®] 2008 and the beta version of Visual C++[®] 2010. All of the examples compile and run in GNU GCC 4.3. GCC is available for most platforms, including Linux, Mac OS X (via Xcode) and Windows—via tools like Cygwin (www.cygwin.com) and MinGW (www.mingw.org).

Instructor Supplements

The following supplements are available to qualified instructors only through Pearson Education's Instructor Resource Center (www.pearsonhighered.com/irc):

- *Solutions Manual* with solutions to most of the end-of-chapter exercises.

- *Test Item File* of multiple-choice questions (approximately two per book section)
- Customizable PowerPoint® slides containing all the code and figures in the text, plus bulleted items that summarize key points in the text

If you are not already a registered faculty member, contact your Pearson representative or visit www.pearsonhighered.com/educator/relocator/.

Deitel® Buzz Online Free E-mail Newsletter

The *Deitel® Buzz Online* e-mail newsletter will keep you posted about issues related to *C How to Program, 6/e*. It also includes commentary on industry trends and developments, links to free articles and resources from our published books and upcoming publications, product-release schedules, errata, challenges, anecdotes, information on our corporate instructor-led training courses and more. To subscribe, visit

www.deitel.com/newsletter/subscribe.html

The Deitel Online Resource Centers

Our website www.deitel.com provides more than 100 Resource Centers on various topics including programming languages, software development, Web 2.0, Internet business and open-source projects—see the list of Resource Centers in the first few pages of this book and visit www.deitel.com/ResourceCenters.html. We've found many exceptional resources online, including tutorials, documentation, software downloads, articles, blogs, podcasts, videos, code samples, books, e-books and more—most of them are free. Each week we announce our latest Resource Centers in our newsletter, the *Deitel® Buzz Online*. Some of the Resource Centers you might find helpful while studying this book are C, C++, C++ Boost Libraries, C++ Game Programming, Visual C++, UML, Code Search Engines and Code Sites, Game Programming and Programming Projects.

Follow Deitel on Twitter and Facebook

To receive updates on Deitel publications, Resource Centers, training courses, partner offers and more, follow us on Twitter®

@deitel

and join the Deitel & Associates group on Facebook®

www.deitel.com/deitelfan/

Acknowledgments

It's a pleasure to acknowledge the efforts of people whose names do not appear on the cover, but whose hard work, cooperation, friendship and understanding were crucial to the book's production. Many people at Deitel & Associates, Inc., devoted long hours to this project—thanks especially to Abbey Deitel and Barbara Deitel.

We would also like to thank the participants of our Honors Internship program who contributed to this publication—Christine Chen, an Operations Research and Information Engineering major at Cornell University; and Matthew Pearson, a Computer Science graduate of Cornell University.

We are fortunate to have worked on this project with the dedicated team of publishing professionals at Pearson. We appreciate the efforts of Marcia Horton, Editorial Director of Pearson's Engineering and Computer Science Division, and Michael Hirsch, Editor-in-Chief of Computer Science. Carole Snyder recruited the book's review team and managed the review process. Francesco Santalucia (an independent artist) and Kristine Carney of Pearson designed the book's cover—we provided the concept, and they made it happen. Scott Disanno and Bob Engelhardt managed the book's production. Erin Davis and Margaret Waples marketed the book through academic and professional channels.

C How to Program, 6/e Reviewers

We wish to acknowledge the efforts of our reviewers. Adhering to a tight time schedule, they scrutinized the text and the programs and provided countless suggestions for improving the accuracy and completeness of the presentation:

- John Benito, Blue Pilot Consulting, Inc. and Convener of ISO WG14—the Working Group responsible for the C Programming Language Standard.
- Xiaolong Li, Indiana State University
- Tom Rethard, The University of Texas at Arlington

C How to Program, 5/e Reviewers

- Alireza Fazelpour (Palm Beach Community College)
- Don Kostuch (Independent Consultant)
- Ed James Beckham (Altera)
- Gary Sibbitts (St. Louis Community College at Meramec)
- Ian Barland (Radford University)
- Kevin Mark Jones (Hewlett Packard)
- Mahesh Hariharan (Microsoft)
- William Mike Miller (Edison Design Group, Inc.)
- Benjamin Seyfarth (University of Southern Mississippi)
- William Albrecht (University of South Florida)
- William Smith (Tulsa Community College)

Allegro Reviewers for C How to Program, 5/e

- Shawn Hargreaves (Software Design Engineer, Microsoft Xbox)
- Matthew Levertton (Founder and Webmaster of Allegro.cc)
- Ryan Patterson (Independent Consultant)
- Douglas Walls (Senior Staff Engineer, C compiler, Sun Microsystems)

C99 Reviewers for C How to Program, 5/e

- Lawrence Jones, (UGS Corp.)
- Douglas Walls (Senior Staff Engineer, C compiler, Sun Microsystems)

Well, there you have it! C is a powerful programming language that will help you write programs quickly and effectively. C scales nicely into the realm of enterprise systems development to help organizations build their business-critical and mission-critical information systems. As you read the book, we would sincerely appreciate your comments, criticisms, corrections and suggestions for improving the text. Please address all correspondence to:

`deitel@deitel.com`

We'll respond promptly, and post corrections and clarifications on:

`www.deitel.com/books/chtp6/`

We hope you enjoy working with *C How to Program, Sixth Edition* as much as we enjoyed writing it!

Paul Deitel

Harvey Deitel

Maynard, Massachusetts

August 2009

About the Authors

Paul J. Deitel, CEO and Chief Technical Officer of Deitel & Associates, Inc., is a graduate of MIT's Sloan School of Management, where he studied Information Technology. Through Deitel & Associates, Inc., he has delivered C, C++, Java, C#, Visual Basic and Internet programming courses to industry clients, including Cisco, IBM, Sun Microsystems, Dell, Lucent Technologies, Fidelity, NASA at the Kennedy Space Center, the National Severe Storm Laboratory, White Sands Missile Range, Rogue Wave Software, Boeing, SunGard Higher Education, Stratus, Cambridge Technology Partners, Open Environment Corporation, One Wave, Hyperion Software, Adra Systems, Entergy, Cable-Data Systems, Nortel Networks, Puma, iRobot, Invensys and many more. He holds the Java Certified Programmer and Java Certified Developer certifications and has been designated by Sun Microsystems as a Java Champion. He has also lectured on Java and C++ for the Boston Chapter of the Association for Computing Machinery. He and his co-author, Dr. Harvey M. Deitel, are the world's best-selling programming-language textbook authors.

Dr. Harvey M. Deitel, Chairman and Chief Strategy Officer of Deitel & Associates, Inc., has 48 years of academic and industry experience in the computer field. Dr. Deitel earned B.S. and M.S. degrees from MIT and a Ph.D. from Boston University. He has extensive college teaching experience, including earning tenure and serving as the Chairman of the Computer Science Department at Boston College before founding Deitel & Associates, Inc., with his son, Paul J. Deitel. He and Paul are the co-authors of dozens of books and multimedia packages and they are writing many more. With translations published in Japanese, German, Russian, Traditional Chinese, Simplified Chinese, Spanish, Korean, French, Polish, Italian, Portuguese, Greek, Urdu and Turkish, the Deitels' texts have earned international recognition. Dr. Deitel has delivered hundreds of professional seminars to major corporations, academic institutions, government organizations and the military.

About Deitel & Associates, Inc.

Deitel & Associates, Inc., is an internationally recognized authoring and corporate training organization specializing in computer programming languages, Internet and web software technology, object-technology education and iPhone applications development. The company provides instructor-led courses delivered at client sites worldwide on major programming languages and platforms, such as C, C++, Visual C++[®], Java[™], Visual C#[®], Visual Basic[®], XML[®], Python[®], object technology, Internet and web programming, iPhone programming and a growing list of additional programming and software-development-related courses. The founders of Deitel & Associates, Inc., are Paul J. Deitel and Dr. Harvey M. Deitel. The company's clients include many of the world's largest companies, government agencies, branches of the military, and academic institutions. Through its 33-year publishing partnership with Prentice Hall/Pearson, Deitel & Associates, Inc., publishes leading-edge programming textbooks, professional books, interactive multimedia *Cyber Classrooms*, *LiveLessons* video courses (online at www.safaribooksonline.com and on DVD at www.deitel.com/books/livelessons/), and e-content for popular course-management systems.

Deitel & Associates, Inc., and the authors can be reached via e-mail at:

deitel@deitel.com

To learn more about Deitel & Associates, Inc., its publications and its *Dive Into*[®] *Series* Corporate Training curriculum delivered at client locations worldwide, visit:

www.deitel.com/training/

and subscribe to the free *Deitel*[®] *Buzz Online* e-mail newsletter at:

www.deitel.com/newsletter/subscribe.html

Individuals wishing to purchase Deitel books, and *LiveLessons* DVD and web-based training courses can do so through www.deitel.com. Bulk orders by corporations, the government, the military and academic institutions should be placed directly with Pearson. For more information, visit www.prenhall.com/mishtml/support.html#order.

This page intentionally left blank

Introduction to Computers, the Internet and the Web

1

The chief merit of language is clearness.

—Galen

Our life is frittered away by detail. ... Simplify, simplify.

—Henry David Thoreau

He had a wonderful talent for packing thought close, and rendering it portable.

—Thomas B. Macaulay

Man is still the most extraordinary computer of all.

—John F. Kennedy

Objectives

In this chapter, you'll learn:

- Basic computer concepts.
- The different types of programming languages.
- The history of the C programming language.
- The purpose of the C Standard Library.
- The elements of a typical C program development environment.
- How C provides a foundation for further study of programming languages in general and of C++, Java and C# in particular.
- The history of the Internet and the World Wide Web.

- | | |
|---|--|
| 1.1 Introduction | 1.10 Java |
| 1.2 Computers: Hardware and Software | 1.11 Fortran, COBOL, Pascal and Ada |
| 1.3 Computer Organization | 1.12 BASIC, Visual Basic, Visual C++, C# and .NET |
| 1.4 Personal, Distributed and Client/Server Computing | 1.13 Key Software Trend: Object Technology |
| 1.5 The Internet and the World Wide Web | 1.14 Typical C Program Development Environment |
| 1.6 Machine Languages, Assembly Languages and High-Level Languages | 1.15 Hardware Trends |
| 1.7 History of C | 1.16 Notes About C and This Book |
| 1.8 C Standard Library | 1.17 Web Resources |
| 1.9 C++ | |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

1.1 Introduction

Welcome to C and C++! We've worked hard to create what we hope you'll find to be an informative, entertaining and challenging learning experience. C is a powerful computer programming language that is appropriate for technically oriented people with little or no programming experience and for experienced programmers to use in building substantial information systems. *C How to Program, Sixth Edition*, is an effective learning tool for each of these audiences.

The core of the book emphasizes achieving program clarity through the proven techniques of structured programming. You'll learn programming the right way from the beginning. We've attempted to write in a clear and straightforward manner. The book is abundantly illustrated. Perhaps most important, the book presents hundreds of complete working programs and shows the outputs produced when those programs are run on a computer. We call this the "live-code approach." All of these example programs may be downloaded from our website www.deitel.com/books/cht6/.

Most people are familiar with the exciting tasks computers perform. Using this textbook, you'll learn how to command computers to perform those tasks. It's **software** (i.e., the instructions you write to command computers to perform **actions** and make **decisions**) that controls computers (often referred to as **hardware**). This text introduces programming in C, which was standardized in 1989 as ANSI X3.159-1989 in the United States through the **American National Standards Institute (ANSI)**, then worldwide through the efforts of the **International Standards Organization (ISO)**. We call this Standard C. We also introduce C99 (ISO/IEC 9899:1999)—the latest version of the C standard. C99 has not yet been universally adopted, so we chose to discuss it in (optional) Appendix G. A new C standard, which has been informally named C1X, is under development and likely to be published around 2012.

Optional Appendix E presents the **Allegro** game programming C library. The appendix shows how to use Allegro to create a simple game. We show how to display graphics and smoothly animate objects, and we explain additional features such as sound,

keyboard input and text output. The appendix includes web links and resources that point you to over 1000 Allegro games and to tutorials on advanced Allegro techniques.

Computer use is increasing in most fields of endeavor. Computing costs have decreased dramatically due to rapid developments in both hardware and software technologies. Computers that might have filled large rooms and cost millions of dollars a few decades ago can now be inscribed on silicon chips smaller than a fingernail, costing a few dollars each. Those large computers were called **mainframes** and current versions are widely used today in business, government and industry. Fortunately, silicon is one of the most abundant materials on earth—it's an ingredient in common sand. Silicon chip technology has made computing so economical that more than a billion general-purpose computers are in use worldwide, helping people in business, industry and government, and in their personal lives. Billions more special purpose computers are used in intelligent electronic devices like car navigation systems, energy-saving appliances and game controllers.

C++, an object-oriented programming language based on C, is of such interest today that we've included a detailed introduction to C++ and object-oriented programming in Chapters 15–24. In the programming languages marketplace, many key vendors market a combined C/C++ product rather than offering separate products. This enables users to continue programming in C if they wish, then gradually migrate to C++ when it's appropriate.

To keep up to date with C and C++ developments at Deitel & Associates, register for our free e-mail newsletter, the *Deitel® Buzz Online*, at

www.deitel.com/newsletter/subscribe.html

Check out our growing list of C and related Resource Centers at

www.deitel.com/ResourceCenters.html

Some Resource Centers that will be valuable to you as you read the C portion of this book are C, Code Search Engines and Code Sites, Computer Game Programming and Programming Projects. Each week we announce our latest Resource Centers in the newsletter. Errata and updates for this book are posted at

www.deitel.com/books/cht6/

You're embarking on a challenging and rewarding path. As you proceed, if you have any questions, send e-mail to

deitel@deitel.com

We'll respond promptly. We hope that you'll enjoy *C How to Program, Sixth Edition*.

1.2 Computers: Hardware and Software

A **computer** is a device that can perform computations and make logical decisions billions of times faster than human beings can. For example, many of today's personal computers can perform several billion additions per second. A person operating a desk calculator could spend an entire lifetime performing calculations and still not complete as many calculations as a powerful personal computer can perform in one second! (Points to ponder: How would you know whether the person added the numbers correctly? How would you know whether the computer added the numbers correctly?) Today's fastest **supercomputers** can perform *thousands of trillions (quadrillions)* of instructions per second! To put that

in perspective, a quadrillion-instruction-per-second computer can perform more than 100,000 calculations per second for every person on the planet!

Computers process **data** under the control of sets of instructions called **computer programs**. These programs guide the computer through orderly sets of actions specified by people called **computer programmers**.

A computer consists of various devices referred to as hardware (e.g., the keyboard, screen, mouse, hard disk, memory, DVDs and processing units). The programs that run on a computer are referred to as software. Hardware costs have been declining dramatically in recent years, to the point that personal computers have become a commodity. In this book, you'll learn proven methods that are reducing software development costs—structured programming (in the C chapters) and object-oriented programming (in the C++ chapters).

1.3 Computer Organization

Regardless of differences in physical appearance, virtually every computer may be envisioned as divided into six **logical units** or sections:

1. **Input unit.** This “receiving” section obtains information (data and computer programs) from **input devices** and places it at the disposal of the other units so that it can be processed. Humans typically enter information into computers through keyboards and mouse devices. Information also can be entered in many other ways, including by speaking to your computer, scanning images and barcodes, reading from secondary storage devices (like hard drives, CD drives, DVD drives and USB drives—also called “thumb drives”) and having your computer receive information from the Internet (such as when you download videos from YouTube™, e-books from Amazon and the like).
2. **Output unit.** This “shipping” section takes information that the computer has processed and places it on various **output devices** to make it available for use outside the computer. Most information that is output from computers today is displayed on screens, printed on paper, played on audio players (such as Apple's popular iPods), or used to control other devices. Computers also can output their information to networks, such as the Internet.
3. **Memory unit.** This rapid-access, relatively low-capacity “warehouse” section retains information that has been entered through the input unit, making it immediately available for processing when needed. The memory unit also retains processed information until it can be placed on output devices by the output unit. Information in the memory unit is **volatile**—it's typically lost when the computer's power is turned off. The memory unit is often called either **memory** or **primary memory**.
4. **Arithmetic and logic unit (ALU).** This “manufacturing” section performs calculations, such as addition, subtraction, multiplication and division. It also contains the decision mechanisms that allow the computer, for example, to compare two items from the memory unit to determine whether they're equal. In today's systems, the ALU is usually implemented as part of the next logical unit, the CPU.
5. **Central processing unit (CPU).** This “administrative” section coordinates and supervises the operation of the other sections. The CPU tells the input unit when to

read information into the memory unit, tells the ALU when information from the memory unit should be used in calculations and tells the output unit when to send information from the memory unit to certain output devices. Many of today's computers have multiple CPUs and, hence, can perform many operations simultaneously—such computers are called **multiprocessors**. A **multi-core processor** implements multiprocessing on a single integrated circuit chip—for example a dual-core processor has two CPUs and a quad-core processor has four CPUs.

6. **Secondary storage unit.** This is the long-term, high-capacity “warehousing” section. Programs or data not actively being used by the other units normally are placed on secondary storage devices (e.g., your hard drive) until they're again needed, possibly hours, days, months or even years later. Therefore, information on secondary storage devices is said to be **persistent**—it is preserved even when the computer's power is turned off. Secondary storage information takes much longer to access than information in primary memory, but the cost per unit of secondary storage is much less than that of primary memory. Examples of secondary storage devices include CDs, DVDs and flash drives (sometimes called memory sticks), which can hold hundreds of millions to billions of characters.

1.4 Personal, Distributed and Client/Server Computing

In 1977, Apple Computer popularized **personal computing**. Computers became so economical that people could buy them for their own personal or business use. In 1981, IBM, the world's largest computer vendor, introduced the IBM Personal Computer (PC). This quickly legitimized personal computing in business, industry and government organizations, where IBM mainframes were heavily used.

These computers were “stand-alone” units—people transported disks back and forth between them to share information (this was often called “sneakernet”). These machines could be linked together in computer networks, sometimes over telephone lines and sometimes in **local area networks (LANs)** within an organization. This led to the phenomenon of **distributed computing**, in which an organization's computing, instead of being performed only at some central computer installation, is distributed over networks to the sites where the organization's work is performed. Personal computers were powerful enough to handle the computing requirements of individual users as well as the basic communications tasks of passing information between computers electronically.

Today's personal computers are as powerful as the million-dollar machines of just a few decades ago. Information is shared easily across computer networks, where computers called **servers** (file servers, database servers, web servers, etc.) offer capabilities that may be used by **client** computers distributed throughout the network, hence the term **client/server computing**. C is widely used for writing software for operating systems, for computer networking and for distributed client/server applications. Today's popular operating systems such as UNIX, Linux, Mac OS X and Microsoft's Windows-based systems provide the kinds of capabilities discussed in this section.

1.5 The Internet and the World Wide Web

The **Internet**—a global network of computers—was initiated in the late 1960s with funding supplied by the U.S. Department of Defense. Originally designed to connect the main

computer systems of about a dozen universities and research organizations, the Internet today is accessible by computers worldwide.

With the introduction of the **World Wide Web**—which allows computer users to locate and view multimedia-based documents on almost any subject over the Internet—the Internet has exploded into the world’s premier communication mechanism.

The Internet and the World Wide Web are surely among humankind’s most important and profound creations. In the past, most computer applications ran on computers that were not connected to one another. Today’s applications can be written to communicate among the world’s computers. The Internet mixes computing and communications technologies. It makes our work easier. It makes information instantly and conveniently accessible worldwide. It enables individuals and local small businesses to get worldwide exposure. It’s changing the way business is done. People can search for the best prices on virtually any product or service. Special-interest communities can stay in touch with one another. Researchers can be made instantly aware of the latest breakthroughs.

1.6 Machine Languages, Assembly Languages and High-Level Languages

Programmers write instructions in various programming languages, some directly understandable by computers and others requiring intermediate **translation** steps. Hundreds of computer languages are in use today. These may be divided into three general types:

1. Machine languages
2. Assembly languages
3. High-level languages

Any computer can directly understand only its own **machine language**. Machine language is the “natural language” of a computer and as such is defined by its hardware design. [Note: Machine language is often referred to as object code. This term predates “object-oriented programming.” These two uses of “object” are unrelated.] Machine languages generally consist of strings of numbers (ultimately reduced to 1s and 0s) that instruct computers to perform their most elementary operations one at a time. Machine languages are **machine dependent** (i.e., a particular machine language can be used on only one type of computer). Such languages are cumbersome for humans, as illustrated by the following section of an early machine-language program that adds overtime pay to base pay and stores the result in gross pay:

```
+1300042774
+1400593419
+1200274027
```

Machine-language programming was simply too slow, tedious and error prone for most programmers. Instead of using the strings of numbers that computers could directly understand, programmers began using English-like abbreviations to represent elementary operations. These abbreviations formed the basis of **assembly languages**. **Translator programs** called **assemblers** were developed to convert early assembly-language programs to machine language at computer speeds. The following section of an assembly-language program also adds overtime pay to base pay and stores the result in gross pay:

load	basepay
add	overpay
store	grosspay

Although such code is clearer to humans, it's incomprehensible to computers until translated to machine language.

Computer usage increased rapidly with the advent of assembly languages, but programmers still had to use many instructions to accomplish even the simplest tasks. To speed the programming process, **high-level languages** were developed in which single statements could be written to accomplish substantial tasks. Translator programs called **compilers** convert high-level language programs into machine language. High-level languages allow programmers to write instructions that look almost like everyday English and contain commonly used mathematical notations. A payroll program written in a high-level language might contain a statement such as

```
grossPay = basePay + overTimePay;
```

From your standpoint, obviously, high-level languages are preferable to machine and assembly language. C, C++, Microsoft's .NET languages (e.g., Visual Basic, Visual C++ and Visual C#) and Java are among the most widely used high-level programming languages.

The process of compiling a high-level language program into machine language can take a considerable amount of computer time. **Interpreter** programs were developed to execute high-level language programs directly (without the delay of compilation), although slower than compiled programs run.

1.7 History of C

C evolved from two previous languages, BCPL and B. BCPL was developed in 1967 by Martin Richards as a language for writing operating-systems software and compilers. Ken Thompson modeled many features in his B language after their counterparts in BCPL, and in 1970 he used B to create early versions of the UNIX operating system at Bell Laboratories. Both BCPL and B were “typeless” languages—every data item occupied one “word” in memory, and the burden of typing variables fell on the shoulders of the programmer.

The C language was evolved from B by Dennis Ritchie at Bell Laboratories and was originally implemented on a DEC PDP-11 computer in 1972. C uses many of the important concepts of BCPL and B while adding data typing and other powerful features. C initially became widely known as the development language of the UNIX operating system. Today, virtually all new major operating systems are written in C and/or C++. C is available for most computers. C is mostly hardware independent. With careful design, it's possible to write C programs that are **portable** to most computers.

By the late 1970s, C had evolved into what is now referred to as “traditional C.” The publication in 1978 of Kernighan and Ritchie's book, *The C Programming Language*, drew wide attention to the language. This became one of the most successful computer science books of all time.

The rapid expansion of C over various types of computers (sometimes called **hardware platforms**) led to many variations that were similar but often incompatible. This was a serious problem for programmers who needed to develop code that would run on several platforms. It became clear that a standard version of C was needed. In 1983, the X3J11

technical committee was created under the American National Standards Committee on Computers and Information Processing (X3) to “provide an unambiguous and machine-independent definition of the language.” In 1989, the standard was approved; this standard was updated in 1999. The standards document is referred to as *INCITS/ISO/IEC 9899-1999*. Copies may be ordered from the American National Standards Institute (www.ansi.org) at webstore.ansi.org/ansidocstore.

C99 is a revised standard for the C programming language that refines and expands the capabilities of C. Not all popular C compilers support C99. Of those that do, most implement only a subset of the new features. Chapters 1–14 of this book are based on the widely adopted international Standard (ANSI/ISO) C. Appendix G introduces C99 and provides links to popular C99 compilers and IDEs.



Portability Tip 1.1

Because C is a hardware-independent, widely available language, applications written in C can run with little or no modifications on a wide range of different computer systems.

1.8 C Standard Library

As you’ll learn in Chapter 5, C programs consist of modules or pieces called **functions**. You can program all the functions you need to form a C program, but most C programmers take advantage of a rich collection of existing functions called the **C Standard Library**. Thus, there are really two pieces to learning how to program in C. The first is learning the C language itself, and the second is learning how to use the functions in the C Standard Library. Throughout the book, we discuss many of these functions. P.J. Plauger’s book *The Standard C Library* is must reading for programmers who need a deep understanding of the library functions, how to implement them and how to use them to write portable code. We use and explain many C library functions throughout this text. Visit the following website for the complete C Standard Library documentation, including the C99 features:

www.dinkumware.com/manuals/default.aspx#Standard%20C%20Library

This textbook encourages a **building-block approach** to creating programs. Avoid reinventing the wheel. Instead, use existing pieces—this is called **software reusability**, and it’s a key to the field of object-oriented programming, as you’ll see in our treatment of C++ beginning in Chapter 15. When programming in C you’ll typically use the following building blocks:

- C Standard Library functions
- Functions you create yourself
- Functions other people have created and made available to you

The advantage of creating your own yfunctions is that you’ll know exactly how they work. You’ll be able to examine the C code. The disadvantage is the time-consuming effort that goes into designing, developing and debugging new functions.

If you use existing functions, you can avoid reinventing the wheel. In the case of the Standard C functions, you know that they’re carefully written, and you know that because you’re using functions that are available on virtually all Standard C implementations, your programs will have a greater chance of being portable and error-free.



Performance Tip 1.1

Using Standard C library functions instead of writing your own comparable versions can improve program performance, because these functions are carefully written to perform efficiently.



Performance Tip 1.2

Using Standard C library functions instead of writing your own comparable versions can improve program portability, because these functions are used in virtually all Standard C implementations.

1.9 C++

C++ was developed by Bjarne Stroustrup at Bell Laboratories. It has its roots in C, providing a number of features that “spruce up” the C language. More important, it provides capabilities for **object-oriented programming**. C++ has become a dominant language in both industry and the colleges.

Objects are essentially reusable software **components** that model items in the real world. Using a modular, object-oriented design and implementation approach can make software development groups much more productive than is possible with previous programming techniques.

Many people feel that the best educational strategy today is to master C, then study C++. Therefore, in Chapters 15–24 of *C How to Program, 6/e*, we present a condensed treatment of C++ selected from our book *C++ How to Program, 7/e*. As you study C++, check out our online C++ Resource Center at www.deitel.com/cplusplus/.

1.10 Java

Microprocessors are having a profound impact in intelligent consumer electronic devices. Recognizing this, Sun Microsystems in 1991 funded an internal corporate research project code-named Green. The project resulted in the development of a C++-based language that its creator, James Gosling, called Oak after an oak tree outside his window at Sun. It was later discovered that there already was a computer language called Oak. When a group of Sun people visited a local coffee shop, the name **Java** was suggested and it stuck.

The Green project ran into some difficulties. The marketplace for intelligent consumer electronic devices did not develop in the early 1990s as quickly as Sun had anticipated. The project was in danger of being canceled. By sheer good fortune, the World Wide Web exploded in popularity in 1993, and Sun saw the immediate potential of using Java to add **dynamic content** (e.g., interactivity, animations and the like) to web pages. This breathed new life into the project.

Sun formally announced Java at an industry conference in May 1995. Java garnered the attention of the business community because of the phenomenal interest in the World Wide Web. Java is now used to develop large-scale enterprise applications, to enhance the functionality of web servers (the computers that provide the content we see in our web browsers), to provide applications for consumer devices (e.g., cell phones, pagers and personal digital assistants) and for many other purposes.

1.11 Fortran, COBOL, Pascal and Ada

Hundreds of high-level languages have been developed, but few have achieved broad acceptance. **FORTTRAN** (FORmula TRANslator) was developed by IBM Corporation in the mid-1950s to be used for scientific and engineering applications that require complex mathematical computations. Fortran is still widely used in engineering applications.

COBOL (COmmon Business Oriented Language) was developed in the late 1950s by computer manufacturers, the U.S. government and industrial computer users. COBOL is used for commercial applications that require precise and efficient manipulation of large amounts of data. Much business software is still programmed in COBOL.

During the 1960s, many large software development efforts encountered severe difficulties. Software deliveries were often late, costs greatly exceeded budgets and the finished products were unreliable. People realized that software development was a more complex activity than they had imagined. Research in the 1960s resulted in the evolution of **structured programming**—a disciplined approach to writing programs that are clearer and easier to test, debug and modify than large programs produced with previous techniques.

One of the more tangible results of this research was the development of the **Pascal** programming language by Professor Niklaus Wirth in 1971. Named after the seventeenth-century mathematician and philosopher Blaise Pascal, it was designed for teaching structured programming and rapidly became the preferred programming language in most colleges. Pascal lacked many features needed in commercial, industrial and government applications, so it was not widely accepted outside academia.

The **Ada** language was developed under the sponsorship of the U.S. Department of Defense (DoD) during the 1970s and early 1980s. Hundreds of separate languages were being used to produce the DoD's massive command-and-control software systems. The DoD wanted one language that would fill most of its needs. The Ada language was named after Lady Ada Lovelace, daughter of the poet Lord Byron. Lady Lovelace is credited with writing the world's first computer program in the early 1800s (for the Analytical Engine mechanical computing device designed by Charles Babbage). One important capability of Ada, called **multitasking**, allows programmers to specify that many activities are to occur in parallel. Although multithreading is not part of standard C, it's available through various add-on libraries.

1.12 BASIC, Visual Basic, Visual C++, C# and .NET

The **BASIC** (Beginner's All-purpose Symbolic Instruction Code) programming language was developed in the mid-1960s at Dartmouth College as a means of writing simple programs. BASIC's primary purpose was to familiarize novices with programming techniques. Microsoft's Visual Basic language, introduced in the early 1990s to simplify the development of Microsoft Windows applications, has become one of the most popular programming languages in the world.

Microsoft's latest development tools are part of its corporate-wide strategy for integrating the Internet and the web into computer applications. This strategy is implemented in Microsoft's **.NET platform**, which provides the capabilities developers need to create and run computer applications that can execute on computers distributed across the Internet. Microsoft's three primary programming languages are **Visual Basic** (based on the original BASIC), **Visual C++** (based on C++) and **Visual C#** (a new language based on

C++ and Java that was developed expressly for the .NET platform). Visual C++ can also be used to compile and run C programs.

1.13 Key Software Trend: Object Technology

One of the authors, Harvey Deitel, remembers the great frustration felt in the 1960s by software development organizations, especially those working on large-scale projects. During his undergraduate years at MIT, he worked summers at a leading computer vendor on the teams developing timesharing, virtual memory operating systems. This was a great experience for a college student. But, in the summer of 1967, reality set in when the company “decommitted” from producing as a commercial product the particular system on which hundreds of people had been working for many years. It was difficult to get this software right—software is “complex stuff.”

Improvements to software technology did emerge, with the benefits of structured programming (and the related disciplines of structured systems analysis and design) being realized in the 1970s. Not until the technology of object-oriented programming became widely used in the 1990s, though, did software developers feel they had the necessary tools for making major strides in the software development process.

Actually, object technology dates back to the mid 1960s. The C++ programming language, developed at AT&T by Bjarne Stroustrup in the early 1980s, is based on two languages—C and Simula 67, a simulation programming language developed at the Norwegian Computing Center and released in 1967. C++ absorbed the features of C and added Simula’s capabilities for creating and manipulating objects. Neither C nor C++ was originally intended for wide use beyond the AT&T research laboratories. But grass roots support rapidly developed for each.

Object technology is a packaging scheme that helps us create meaningful software units. There are date objects, time objects, paycheck objects, invoice objects, audio objects, video objects, file objects, record objects and so on. In fact, almost any *noun* can be reasonably represented as an object.

We live in a world of objects. There are cars, planes, people, animals, buildings, traffic lights, elevators and the like. Before object-oriented languages appeared, procedural programming languages (such as Fortran, COBOL, Pascal, BASIC and C) were focused on actions (verbs) rather than on things or objects (nouns). Programmers living in a world of objects programmed primarily using verbs. This made it awkward to write programs. Now, with the availability of popular object-oriented languages such as C++, Java and C#, programmers continue to live in an object-oriented world and can program in an object-oriented manner. This is a more natural process than procedural programming and has resulted in significant productivity gains.

A key problem with procedural programming is that the program units do not effectively mirror real-world entities, so these units are not particularly reusable. It isn’t unusual for programmers to “start fresh” on each new project and have to write similar software “from scratch.” This wastes time and money, as people repeatedly “reinvent the wheel.” With object technology, the software entities created (called [classes](#)), if properly designed, tend to be reusable on future projects. Using libraries of reusable componentry can greatly reduce effort required to implement certain kinds of systems (compared to the effort that would be required to reinvent these capabilities on new projects).



Software Engineering Observation 1.1

Extensive class libraries of reusable software components are available on the Internet. Many of these libraries are free.

Some organizations report that the key benefit of object-oriented programming is not software reuse but, rather, that the software they produce is more understandable, better organized and easier to maintain, modify and debug. This can be significant, because perhaps as much as 80 percent of software costs are associated not with the original efforts to develop the software, but with the continued evolution and maintenance of that software throughout its lifetime. Whatever the perceived benefits, it's clear that object-oriented programming will be the key programming methodology for the next several decades.

1.14 Typical C Program Development Environment

C systems generally consist of several parts: a program development environment, the language and the C Standard Library. The following discussion explains the typical C development environment shown in Fig. 1.1.

C programs typically go through six phases to be executed (Fig. 1.1). These are: **edit**, **preprocess**, **compile**, **link**, **load** and **execute**. Although *C How to Program, 6/e* is a generic C textbook (written independently of the details of any particular operating system), we concentrate in this section on a typical Linux-based C system. [Note: The programs in this book will run with little or no modification on most current C systems, including Microsoft Windows-based systems.] If you're not using a Linux system, refer to the manuals for your system or ask your instructor how to accomplish these tasks in your environment. Check out our C Resource Center at www.deitel.com/C to locate "getting started" tutorials for popular C compilers and development environments.

Phase 1: Creating a Program

Phase 1 consists of editing a file. This is accomplished with an **editor program**. Two editors widely used on Linux systems are **vi** and **emacs**. Software packages for the C/C++ integrated program development environments such as Eclipse and Microsoft Visual Studio have editors that are integrated into the programming environment. You type a C program with the editor, make corrections if necessary, then store the program on a secondary storage device such as a hard disk. C program file names should end with the **.c** extension.

Phases 2 and 3: Preprocessing and Compiling a C Program

In Phase 2, you give the command to **compile** the program. The compiler translates the C program into machine language-code (also referred to as **object code**). In a C system, a **preprocessor** program executes automatically before the compiler's translation phase begins. The **C preprocessor** obeys special commands called **preprocessor directives**, which indicate that certain manipulations are to be performed on the program before compilation. These manipulations usually consist of including other files in the file to be compiled and performing various text replacements. The most common preprocessor directives are discussed in the early chapters; a detailed discussion of preprocessor features appears in Chapter 13. In Phase 3, the compiler translates the C program into machine-language code.




Fig. I.1 | Typical C development environment.

Phase 4: Linking

The next phase is called **linking**. C programs typically contain references to functions defined elsewhere, such as in the standard libraries or in the private libraries of groups of programmers working on a particular project. The object code produced by the C compiler typically contains “holes” due to these missing parts. A **linker** links the object code with

the code for the missing functions to produce an **executable image** (with no missing pieces). On a typical Linux system, the command to compile and link a program is called **cc** (or **gcc**). To compile and link a program named `welcome.c` type

```
cc welcome.c
```

at the Linux prompt and press the *Enter* key (or *Return* key). [Note: Linux commands are case sensitive; make sure that you type lowercase c's and that the letters in the filename are in the appropriate case.] If the program compiles and links correctly, a file called `a.out` is produced. This is the executable image of our `welcome.c` program.

Phase 5: Loading

The next phase is called **loading**. Before a program can be executed, the program must first be placed in memory. This is done by the **loader**, which takes the executable image from disk and transfers it to memory. Additional components from shared libraries that support the program are also loaded.

Phase 6: Execution

Finally, the computer, under the control of its CPU, **executes** the program one instruction at a time. To load and execute the program on a Linux system, type `./a.out` at the Linux prompt and press *Enter*.

Problems That May Occur at Execution Time

Programs do not always work on the first try. Each of the preceding phases can fail because of various errors that we'll discuss. For example, an executing program might attempt to divide by zero (an illegal operation on computers just as in arithmetic). This would cause the computer to display an error message. You would then return to the edit phase, make the necessary corrections and proceed through the remaining phases again to determine that the corrections work properly.

Most C programs input and/or output data. Certain C functions take their input from **stdin** (the **standard input stream**), which is normally the keyboard, but `stdin` can be connected to another stream. Data is often output to **stdout** (the **standard output stream**), which is normally the computer screen, but `stdout` can be connected to another stream. When we say that a program prints a result, we normally mean that the result is displayed on a screen. Data may be output to devices such as disks and printers. There is also a **standard error stream** referred to as **stderr**. The `stderr` stream (normally connected to the screen) is used for displaying error messages. It's common to route regular output data, i.e., `stdout`, to a device other than the screen while keeping `stderr` assigned to the screen so that the user can be immediately informed of errors.



Common Programming Error 1.1

Errors like division-by-zero occur as a program runs, so these errors are called runtime errors or execution-time errors. Divide-by-zero is generally a fatal error, i.e., an error that causes the program to terminate immediately without successfully performing its job. Non-fatal errors allow programs to run to completion, often producing incorrect results.

1.15 Hardware Trends

Every year, people generally expect to pay at least a little more for most products and services. The opposite has been the case in the computer and communications fields, espe-

cially with regard to the costs of hardware supporting these technologies. For many decades, hardware costs have fallen rapidly, if not precipitously. Every year or two, the capacities of computers have approximately doubled without any increase in price. This often is called **Moore's Law**, named after the person who first identified and explained the trend, Gordon Moore, cofounder of Intel—the company that manufactures the vast majority of the processors in today's personal computers. Moore's Law and similar trends are especially true in relation to the amount of memory that computers have for programs, the amount of secondary storage (such as disk storage) they have to hold programs and data over longer periods of time, and their processor speeds—the speeds at which computers execute programs (i.e., do their work). Similar growth has occurred in the communications field, in which costs have plummeted as soaring demand for communications bandwidth has attracted intense competition. We know of no other fields in which technology improves so quickly and costs fall so rapidly. Such improvement in the computing and communications fields is truly fostering the so-called Information Revolution.

I.16 Notes About C and This Book

Experienced C programmers sometimes take pride in creating weird, contorted, convoluted usages of the language. This is a poor programming practice. It makes programs more difficult to read, more likely to behave strangely, more difficult to test and debug and more difficult to adapt to changing requirements. This book is geared for novice programmers, so we stress **program clarity**. The following is our first “good programming practice.”



Good Programming Practice 1.1

Write your C programs in a simple and straightforward manner. This is sometimes referred to as KIS (“keep it simple”). Do not “stretch” the language by trying bizarre usages.

You may have heard that C is a portable language and that programs written in C can run on many different computers. *Portability is an elusive goal*. The Standard C document contains a lengthy list of portability issues, and complete books have been written that discuss portability.



Portability Tip 1.2

Although it's possible to write portable C programs, there are many problems between different C compilers and different computers that make portability difficult to achieve. Simply writing programs in C does not guarantee portability. You'll often need to deal directly with computer variations.

We've done a careful walkthrough of the C Standard and audited our presentation against it for completeness and accuracy. However, C is a rich language, and there are some subtleties in the language and some advanced subjects we have not covered. If you need additional technical details on C, we suggest that you read the C Standard document itself or the book by Kernighan and Ritchie (*The C Programming Language, Second Edition*).



Software Engineering Observation 1.2

Read the manuals for the version of C you're using. Reference these manuals frequently to be sure you're aware of the rich collection of C features and that you're using these features correctly.



Software Engineering Observation 1.3

Your computer and compiler are good teachers. If you're not sure how a C feature works, write a program with that feature, compile and run the program and see what happens.

1.17 Web Resources

This section provides links to our C and related Resource Centers that will be useful to you as you learn C. These Resource Centers include various C resources, including, blogs, articles, whitepapers, compilers, development tools, downloads, FAQs, tutorials, webcasts, wikis and links to resources for C game programming with the Allegro libraries.

Deitel & Associates Websites

www.deitel.com/books/cht6/

The Deitel & Associates *C How to Program, 6/e* site. Here you'll find links to the book's examples and other resources.

www.deitel.com/C/

www.deitel.com/visualcplusplus/

www.deitel.com/codesearchengines/

www.deitel.com/programmingprojects/

Check these Resource Centers for compilers, code downloads, tutorials, documentation, books, e-books, articles, blogs, RSS feeds and more that will help you develop C applications.

www.deitel.com

Check this site for updates, corrections and additional resources for all Deitel publications.

www.deitel.com/newsletter/subscribe.html

Subscribe here for the *Deitel® Buzz Online* e-mail newsletter to follow the Deitel & Associates publishing program, including updates and errata to *C How to Program, 6/e*.

Summary

Section 1.1 Introduction

- Software (i.e., the instructions you write to command computers to perform actions and make decisions) controls computers (often referred to as hardware).
- C was standardized in 1989 in the United States through the American National Standards Institute (ANSI) then worldwide through the International Standards Organization (ISO).
- Silicon-chip technology has made computing so economical that more than a billion general-purpose computers are in use worldwide.

Section 1.2 Computers: Hardware and Software

- A computer is capable of performing computations and making logical decisions at speeds billions of times faster than human beings can.
- Computers process data under the control of sets of instructions called computer programs, which guide the computer through orderly sets of actions specified by computer programmers.
- The various devices that comprise a computer system are referred to as hardware.
- The computer programs that run on a computer are referred to as software.

Section 1.3 Computer Organization

- The input unit is the “receiving” section of the computer. It obtains information from input devices and places it at the disposal of the other units for processing.

- The output unit is the “shipping” section of the computer. It takes information processed by the computer and places it on output devices to make it available for use outside the computer.
- The memory unit is the rapid-access, relatively low-capacity “warehouse” section of the computer. It retains information that has been entered through the input unit, making it immediately available for processing when needed, and retains information that has already been processed until it can be placed on output devices by the output unit.
- The arithmetic and logic unit (ALU) is the “manufacturing” section of the computer. It’s responsible for performing calculations and making decisions.
- The central processing unit (CPU) is the “administrative” section of the computer. It coordinates and supervises the operation of the other sections.
- The secondary storage unit is the long-term, high-capacity “warehousing” section of the computer. Programs or data not being used by the other units are normally placed on secondary storage devices (e.g., disks) until they’re needed, possibly hours, days, months or even years later.

Section 1.4 Personal, Distributed and Client/Server Computing

- Apple Computer popularized personal computing.
- IBM’s Personal Computer quickly legitimized personal computing in business, industry and government organizations, where IBM mainframes are heavily used.
- Early personal computers could be linked together in computer networks. This led to the phenomenon of distributed computing.
- Information is shared easily across networks, where computers called servers (file servers, database servers, web servers, etc.) offer capabilities that may be used by client computers distributed throughout the network, hence the term client/server computing.
- C has become widely used for writing software for operating systems, for computer networking and for distributed client/server applications.

Section 1.5 The Internet and the World Wide Web

- The Internet—a global network of computers—was initiated almost four decades ago with funding supplied by the U.S. Department of Defense.
- With the introduction of the World Wide Web—which allows computer users to locate and view multimedia-based documents on almost any subject over the Internet—the Internet has exploded into the world’s premier communication mechanism.

Section 1.6 Machine Languages, Assembly Languages and High-Level Languages

- Any computer can directly understand only its own machine language, which generally consists of strings of numbers that instruct computers to perform their most elementary operations.
- English-like abbreviations form the basis of assembly languages. Translator programs called assemblers convert assembly-language programs to machine language.
- Compilers translate high-level language programs into machine-language programs. High-level languages (like C) contain English words and conventional mathematical notations.
- Interpreter programs directly execute high-level language programs, eliminating the need to compile them into machine language.

Section 1.7 History of C

- C evolved from two previous languages, BCPL and B. BCPL was developed in 1967 by Martin Richards as a language for writing operating systems software and compilers. Ken Thompson modeled many features in his B language after their counterparts in BCPL and used B to create early versions of the UNIX operating system.

- The C language was evolved from B by Dennis Ritchie at Bell Laboratories. C uses many of the important concepts of BCPL and B while adding data typing and other powerful features.
- C initially became widely known as the development language of the UNIX operating system.
- C is available for most computers. C is mostly hardware independent.
- The publication in 1978 of Kernighan and Ritchie's book, *The C Programming Language*, drew wide attention to the language.
- In 1989, the C standard was approved; this standard was updated in 1999. The standards document is referred to as INCITS/ISO/IEC 9899-1999.
- C99 is a revised standard for the C programming language that refines and expands the capabilities of C, but it has not been universally adopted.

Section 1.8 C Standard Library

- When programming in C you'll typically use C Standard Library functions, functions you create yourself and functions other people have created and made available to you.

Section 1.9 C++

- C++ was developed by Bjarne Stroustrup at Bell Laboratories. It has its roots in C and provides capabilities for object-oriented programming.
- Objects are essentially reusable software components that model items in the real world.
- Using a modular, object-oriented design and implementation approach makes software development groups much more productive than is possible with conventional programming techniques.

Section 1.10 Java

- Java is used to create dynamic and interactive content for web pages, develop enterprise applications, enhance web server functionality, provide applications for consumer devices and more.

Section 1.11 Fortran, COBOL, Pascal and Ada

- FORTRAN was developed by IBM Corporation in the 1950s for scientific and engineering applications that require complex mathematical computations.
- COBOL was developed in the 1950s for commercial applications that require precise and efficient data manipulation.
- Pascal was designed for teaching structured programming.
- Ada was developed under the sponsorship of the United States Department of Defense (DoD) during the 1970s and early 1980s. Ada provides multitasking, which allows programmers to specify that many activities are to occur in parallel.

Section 1.12 BASIC, Visual Basic, Visual C++, C# and .NET

- BASIC was developed in the 1960s at Dartmouth College for programming novices.
- Visual Basic was introduced in the 1990s to simplify developing Windows applications.
- Microsoft has a corporate-wide strategy for integrating the Internet and the web into computer applications. This strategy is implemented in Microsoft's .NET platform.
- The .NET platform's three primary programming languages are Visual Basic (based on the original BASIC), Visual C++ (based on C++) and Visual C# (a new language based on C++ and Java that was developed expressly for the .NET platform).

Section 1.13 Key Software Trend: Object Technology

- Not until object-oriented programming became widely used in the 1990s did software developers feel they had the tools to make major strides in the software development process.
- C++ absorbed the features of C and added Simula's object capabilities.

- Object technology is a packaging scheme that helps us create meaningful software units.
- With object technology, the software entities created (called classes), if properly designed, tend to be reusable on future projects.
- Some organizations report the key benefit of object-oriented programming is the production of software which is more understandable, better organized and easier to maintain and debug.

Section 1.14 Typical C Program Development Environment

- You create a program by editing a file with an editor program. Software packages for the C/C++ integrated program development environments such as Eclipse and Microsoft Visual Studio have editors that are integrated into the programming environment.
- C program file names should end with the .c extension.
- Compilers translate programs into machine-language code (also referred to as object code).
- A preprocessor program executes automatically before the compiler's translation phase begins. The C preprocessor obeys special commands called preprocessor directives that usually consist of including other files in the file to be compiled and performing various text replacements.
- A linker links object code with the code for library functions to produce an executable image.
- Before a program can execute, it must first be placed in memory. This is done by the loader. Additional components from shared libraries that support the program are also loaded.
- The computer, under the control of its CPU, executes a program one instruction at a time.

Section 1.15 Hardware Trends

- Every year, people generally expect to pay at least a little more for most products and services. The opposite has been the case in the computer and communications fields, especially with regard to the costs of hardware supporting these technologies. For many decades, hardware costs have fallen rapidly, if not precipitously.
- Every year or two, the capacities of computers have approximately doubled without any increase in price. This often is called Moore's Law, named after the person who first identified and explained the trend, Gordon Moore, cofounder of Intel—the company that manufactures the vast majority of the processors in today's personal computers.
- Moore's Law is especially true in relation to the amount of memory that computers have for programs, the amount of secondary storage they have to hold programs and data over longer periods of time, and their processor speeds—the speeds at which computers execute their programs.

Terminology

actions (computers perform) 2	class 11
Ada programming language 10	client computer 5
Allegro 2	client/server computing 5
American National Standards Institute (ANSI) 2	COBOL (COMmon Business Oriented Language) 10
arithmetic and logic unit (ALU) 4	compile 12
assembler 6	compile phase 12
assembly language 6	compiler 7
BASIC (Beginner's All-Purpose Symbolic Instruction Code) 10	components (software) 9
building-block approach 8	computer 3
C preprocessor 12	computer program 4
C Standard Library 8	computer programmer 4
cc compilation command 14	data 4
central processing unit (CPU) 4	decisions (made by computers) 2

distributed computing 5
dynamic content 9
edit phase 12
editor program 12
executable image 14
execute 14
execute phase 12
FORTRAN (FORmula TRANslator) 10
function 8
gcc compilation command 14
hardware 2
hardware platform 7
high-level language 7
input device 4
input unit 4
International Standards Organization (ISO) 2
Internet 5
interpreter 7
Java 9
link phase 12
linker 13
linking 13
load phase 12
loader 14
loading 14
local area network (LAN) 5
logical unit 4
machine dependent 6
machine language 6
mainframe 3
memory 4
memory unit 4
Moore's Law 15
multi-core processor 5
multiprocessor 5
multitasking 10
.NET platform 10
object 9
object code 12
object-oriented programming (OOP) 9
output device 4
output unit 4
Pascal 10
persistent information 5
personal computing 5
portable program 7
preprocess phase 12
preprocessor 12
preprocessor directive 12
primary memory 4
program clarity 15
secondary storage unit 5
server 5
software 2
software reusability 8
standard error stream (stderr) 14
standard input stream (stdin) 14
standard output stream (stdout) 14
structured programming 10
supercomputer 3
translation 6
translator programs 6
Visual Basic 10
Visual C++ 10
Visual C# 10
volatile information 4
World Wide Web 6

Self-Review Exercises

1.1 Fill in the blanks in each of the following:

- The company that popularized personal computing was _____.
- The computer that made personal computing legitimate in business and industry was the _____.
- Computers process data under the control of sets of instructions called computer _____.
- The six key logical units of the computer are the _____, _____, _____, _____, _____ and the _____.
- The three types of languages we discussed are _____, _____, and _____.
- The programs that translate high-level language programs into machine language are called _____.
- C is widely known as the development language of the _____ operating system.
- The Department of Defense developed the Ada language with a capability called _____, which allows programmers to specify activities that can proceed in parallel.

- 1.2** Fill in the blanks in each of the following sentences about the C environment.
- C programs are normally typed into a computer using a(n) _____ program.
 - In a C system, a(n) _____ program automatically executes before the translation phase begins.
 - The two most common kinds of preprocessor directives are _____ and _____.
 - The _____ program combines the output of the compiler with various library functions to produce an executable image.
 - The _____ program transfers the executable image from disk to memory.
 - To load and execute the most recently compiled program on a Linux system, type _____.

Answers to Self-Review Exercises

- 1.1** a) Apple. b) IBM Personal Computer. c) programs. d) input unit, output unit, memory unit, arithmetic and logic unit, central processing unit, secondary storage unit. e) machine languages, assembly languages and high-level languages. f) compilers. g) UNIX. h) multitasking.
- 1.2** a) editor. b) preprocessor. c) including other files in the file to be compiled, replacing special symbols with program text. d) linker. e) loader. f) ./a.out.

Exercises

- 1.3** Categorize each of the following items as either hardware or software:
- CPU
 - C++ compiler
 - ALU
 - C++ preprocessor
 - input unit
 - an editor program
- 1.4** Why might you want to write a program in a machine-independent language instead of a machine-dependent language? Why might a machine-dependent language be more appropriate for writing certain types of programs?
- 1.5** Fill in the blanks in each of the following statements:
- Which logical unit of the computer receives information from outside the computer for use by the computer? _____.
 - The process of instructing the computer to solve specific problems is called _____.
 - What type of computer language uses English-like abbreviations for machine-language instructions? _____.
 - Which logical unit of the computer sends information that has already been processed by the computer to various devices so that the information may be used outside the computer? _____.
 - Which logical units of the computer retain information? _____.
 - Which logical unit of the computer performs calculations? _____.
 - Which logical unit of the computer makes logical decisions? _____.
 - The level of computer language most convenient for you to write programs quickly and easily is _____.
 - The only language that a computer directly understands is called that computer's _____.
 - Which logical unit of the computer coordinates the activities of all the other logical units? _____.

- 1.6** State whether each of the following is *true* or *false*. If *false*, explain your answer.
- Machine languages are generally machine dependent.
 - Like other high-level languages, C is generally considered to be machine independent.
- 1.7** Discuss the meaning of each of the following names:
- `stdin`
 - `stdout`
 - `stderr`
- 1.8** Why is so much attention today focused on object-oriented programming?
- 1.9** Which programming language is best described by each of the following?
- Developed by IBM for scientific and engineering applications.
 - Developed specifically for business applications.
 - Developed for teaching structured programming.
 - Named after the world's first computer programmer.
 - Developed to familiarize novices with programming techniques.
 - Specifically developed to help programmers migrate to .NET.
 - Known as the development language of UNIX.
 - Formed primarily by adding object-oriented programming to C.
 - Succeeded initially because of its ability to create web pages with dynamic content.

Making a Difference

1.10 (*Test-Drive: Carbon Footprint Calculator*) Some scientists believe that carbon emissions, especially from the burning of fossil fuels, contribute significantly to global warming and that this can be combatted if individuals take steps to limit their use of carbon-based fuels. Organizations and individuals are increasingly concerned about their “carbon footprints.” Websites such as TerraPass

www.terrapass.com/carbon-footprint-calculator/

and Carbon Footprint

www.carbonfootprint.com/calculator.aspx

provide carbon footprint calculators. Test-drive these calculators to estimate your carbon footprint. Exercises in later chapters will ask you to program your own carbon footprint calculator. To prepare for this, use the web to research the formulas for calculating carbon footprints.

1.11 (*Test-Drive: Body Mass Index Calculator*) By recent estimates, two-thirds of the people in the United States are overweight and about half of those are obese. This causes significant increases in illnesses such as diabetes and heart disease. To determine whether a person is overweight or obese, you can use a measure called the body mass index (BMI). The United States Department of Health and Human Services provides a BMI calculator at www.nhlbi.support.com/bmi/. Use it to calculate your own BMI. An exercise in Chapter 2 will ask you to program your own BMI calculator. To prepare for this, use the web to research the formulas for calculating BMI.

1.12 (*Gender Neutrality*) Many people want to eliminate sexism in all forms of communication. You've been asked to create a program that can process a paragraph of text and replace gender-specific words with gender-neutral ones. Assuming that you've been given a list of gender-specific words and their gender-neutral replacements (e.g., replace “wife” with “spouse,” “man” with “person,” “daughter” with “child” and so on), explain the procedure you'd use to read through a paragraph of text and manually perform these replacements. How might your procedure generate a strange term like “woperchild,” which is actually listed in the Urban Dictionary (www.urbandictionary.com)? In Chapter 4, you'll learn that a more formal term for “procedure” is “algorithm,” and that an algorithm specifies the steps to be performed and the order in which to perform them.

Introduction to C Programming

2

*What's in a name? That which we call a rose
By any other name would smell as sweet.*

—William Shakespeare

When faced with a decision, I always ask, "What would be the most fun?"

—Peggy Walker

"Take some more tea," the March Hare said to Alice, very earnestly. "I've had nothing yet," Alice replied in an offended tone: "so I can't take more." "You mean you can't take less," said the Hatter: "it's very easy to take more than nothing."

—Lewis Carroll

High thoughts must have high language.

—Aristophanes

Objectives

In this chapter, you'll learn

- To write simple computer programs in C.
- To use simple input and output statements.
- To use the fundamental data types.
- Computer memory concepts.
- To use arithmetic operators.
- The precedence of arithmetic operators.
- To write simple decision-making statements.

- | | |
|--|---|
| 2.1 Introduction | 2.4 Memory Concepts |
| 2.2 A Simple C Program: Printing a Line of Text | 2.5 Arithmetic in C |
| 2.3 Another Simple C Program: Adding Two Integers | 2.6 Decision Making: Equality and Relational Operators |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

2.1 Introduction

The C language facilitates a structured and disciplined approach to computer program design. In this chapter we introduce C programming and present several examples that illustrate many important features of C. Each example is analyzed one statement at a time. In Chapters 3 and 4 we present an introduction to **structured programming** in C. We then use the structured approach throughout the remainder of the C portion of the text.

2.2 A Simple C Program: Printing a Line of Text

C uses some notations that may appear strange to people who have not programmed computers. We begin by considering a simple C program. Our first example prints a line of text. The program and its screen output are shown in Fig. 2.1.

```

1  /* Fig. 2.1: fig02_01.c
2     A first program in C */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     printf( "Welcome to C!\n" );
9
10     return 0; /* indicate that program ended successfully */
11 } /* end function main */

```

```
Welcome to C!
```

Fig. 2.1 | A first program in C.

Even though this program is simple, it illustrates several important features of the C language. Lines 1 and 2

```

/* Fig. 2.1: fig02_01.c
A first program in C */

```

begin with `/*` and end with `*/` indicating that these two lines are a **comment**. You insert comments to **document programs** and improve program readability. Comments do not cause the computer to perform any action when the program is run. Comments are ignored by the C compiler and do not cause any machine-language object code to be

generated. The preceding comment simply describes the figure number, file name and purpose of the program. Comments also help other people read and understand your program, but too many comments can make a program difficult to read.



Common Programming Error 2.1

*Forgetting to terminate a comment with */.*



Common Programming Error 2.2

*Starting a comment with the characters */ or ending a comment with the characters /*.*

C99 also includes the C++ language's **// single-line comments** in which everything from // to the end of the line is a comment. These can be used as standalone comments on lines by themselves or as end-of-line comments to the right of a partial line of code. Some programmers prefer // comments because they're shorter and they eliminate the common programming errors that occur with /* */ comments.

Line 3

```
#include <stdio.h>
```

is a directive to the **C preprocessor**. Lines beginning with # are processed by the preprocessor before the program is compiled. Line 3 tells the preprocessor to include the contents of the **standard input/output header** (**<stdio.h>**) in the program. This header contains information used by the compiler when compiling calls to standard input/output library functions such as printf. We explain the contents of headers in more detail in Chapter 5.

Line 6

```
int main( void )
```

is a part of every C program. The parentheses after main indicate that main is a program building block called a **function**. C programs contain one or more functions, one of which must be main. Every program in C begins executing at the function main. Functions can return information. The keyword int to the left of main indicates that main “returns” an integer (whole number) value. We'll explain what it means for a function to “return a value” when we demonstrate how to create your own functions in Chapter 5. For now, simply include the keyword int to the left of main in each of your programs. Functions also can receive information when they're called upon to execute. The void in parentheses here means that main does not receive any information. In Chapter 14, Other C Topics, we'll show an example of main receiving information.



Good Programming Practice 2.1

Every function should be preceded by a comment describing the purpose of the function.

A left brace, {, begins the **body** of every function (line 7). A corresponding **right brace** ends each function (line 11). This pair of braces and the portion of the program between the braces is called a block. The block is an important program unit in C.

Line 8

```
printf( "Welcome to C!\n" );
```

instructs the computer to perform an **action**, namely to print on the screen the **string** of characters marked by the quotation marks. A string is sometimes called a **character string**, a **message** or a **literal**. The entire line, including `printf`, its **argument** within the parentheses and the semicolon (`;`), is called a **statement**. Every statement must end with a semicolon (also known as the **statement terminator**). When the preceding `printf` statement is executed, it prints the message `Welcome to C!` on the screen. The characters normally print exactly as they appear between the double quotes in the `printf` statement. Notice that the characters `\n` were not printed on the screen. The backslash (`\`) is called an **escape character**. It indicates that `printf` is supposed to do something out of the ordinary. When encountering a backslash in a string, the compiler looks ahead at the next character and combines it with the backslash to form an **escape sequence**. The escape sequence `\n` means **newline**. When a newline appears in the string output by a `printf`, the newline causes the cursor to position to the beginning of the next line on the screen. Some common escape sequences are listed in Fig. 2.2.

Escape sequence	Description
<code>\n</code>	Newline. Position the cursor at the beginning of the next line.
<code>\t</code>	Horizontal tab. Move the cursor to the next tab stop.
<code>\a</code>	Alert. Sound the system bell.
<code>\\</code>	Backslash. Insert a backslash character in a string.
<code>\"</code>	Double quote. Insert a double-quote character in a string.

Fig. 2.2 | Some common escape sequences .

The last two escape sequences in Fig. 2.2 may seem strange. Because the backslash has special meaning in a string, i.e., the compiler recognizes it as an escape character, we use a double backslash (`\\`) to place a single backslash in a string. Printing a double quote also presents a problem because double quotes mark the boundary of a string—such quotes are not printed. By using the escape sequence `\"` in a string to be output by `printf`, we indicate that `printf` should display a double quote.

Line 10

```
return 0; /* indicate that program ended successfully */
```

is included at the end of every `main` function. The keyword `return` is one of several means we'll use to **exit a function**. When the `return` statement is used at the end of `main` as shown here, the value `0` indicates that the program has terminated successfully. In Chapter 5 we discuss functions in detail, and the reasons for including this statement will become clear. For now, simply include this statement in each program, or the compiler might produce a warning on some systems. The right brace, `}`, (line 12) indicates that the end of `main` has been reached.



Good Programming Practice 2.2

Add a comment to the line containing the right brace, `}`, that closes every function, including `main`.

We said that `printf` causes the computer to perform an action. As any program executes, it performs a variety of actions and makes **decisions**. At the end of this chapter, we discuss decision making. In Chapter 3, we discuss this **action/decision model** of programming in depth.



Common Programming Error 2.3

Typing the name of the output function `printf` as `print` in a program.

Standard library functions like `printf` and `scanf` are not part of the C programming language. For example, the compiler cannot find a spelling error in `printf` or `scanf`. When the compiler compiles a `printf` statement, it merely provides space in the object program for a “call” to the library function. But the compiler does not know where the library functions are—the linker does. When the linker runs, it locates the library functions and inserts the proper calls to these library functions in the object program. Now the object program is complete and ready to be executed. For this reason, the linked program is called an **executable**. If the function name is misspelled, it is the linker which will spot the error, because it will not be able to match the name in the C program with the name of any known function in the libraries.



Good Programming Practice 2.3

Indent the entire body of each function one level of indentation (we recommend three spaces) within the braces that define the body of the function. This indentation emphasizes the functional structure of programs and helps make programs easier to read.



Good Programming Practice 2.4

Set a convention for the size of indent you prefer and then uniformly apply that convention. The tab key may be used to create indents, but tab stops may vary. We recommend using three spaces per level of indent.

The `printf` function can print `Welcome to C!` several different ways. For example, the program of Fig. 2.3 produces the same output as the program of Fig. 2.1. This works because each `printf` resumes printing where the previous `printf` stopped printing. The first `printf` (line 8) prints `Welcome` followed by a space and the second `printf` (line 9) begins printing on the same line immediately following the space.

```

1  /* Fig. 2.3: fig02_03.c
2     Printing on one line with two printf statements */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     printf( "Welcome " );
9     printf( "to C!\n" );
10
11     return 0; /* indicate that program ended successfully */
12 } /* end function main */

```

Fig. 2.3 | Printing on one line with two `printf` statements. (Part 1 of 2.)

```
Welcome to C!
```

Fig. 2.3 | Printing on one line with two `printf` statements. (Part 2 of 2.)

One `printf` can print several lines by using additional newline characters as in Fig. 2.4. Each time the `\n` (newline) escape sequence is encountered, output continues at the beginning of the next line.

```
1  /* Fig. 2.4: fig02_04.c
2     Printing multiple lines with a single printf */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     printf( "Welcome\n to\n C!\n" );
9
10     return 0; /* indicate that program ended successfully */
11 } /* end function main */
```

```
Welcome
to
C!
```

Fig. 2.4 | Printing multiple lines with a single `printf`.

2.3 Another Simple C Program: Adding Two Integers

Our next program uses the Standard Library function `scanf` to obtain two integers typed by a user at the keyboard, computes the sum of these values and prints the result using `printf`. The program and sample output are shown in Fig. 2.8. [In the input/output dialog of Fig. 2.8, we emphasize the numbers input by the user in bold.]

```
1  /* Fig. 2.5: fig02_05.c
2     Addition program */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     int integer1; /* first number to be input by user */
9     int integer2; /* second number to be input by user */
10    int sum; /* variable in which sum will be stored */
11
12    printf( "Enter first integer\n" ); /* prompt */
13    scanf( "%d", &integer1 ); /* read an integer */
14
15    printf( "Enter second integer\n" ); /* prompt */
16    scanf( "%d", &integer2 ); /* read an integer */
```

Fig. 2.5 | Addition program. (Part 1 of 2.)


```
17
18     sum = integer1 + integer2; /* assign total to sum */
19
20     printf( "Sum is %d\n", sum ); /* print sum */
21
22     return 0; /* indicate that program ended successfully */
23 }
```

```
Enter first integer
45
Enter second integer
72
Sum is 117
```

Fig. 2.5 | Addition program. (Part 2 of 2.)

The comment in lines 1–2 states the purpose of the program. As we stated earlier, every program begins execution with `main`. The left brace `{` (line 7) marks the beginning of the body of `main` and the corresponding right brace `}` (line 24) marks the end of `main`.

Lines 8–10

```
int integer1; /* first number to be input by user */
int integer2; /* second number to be input by user */
int sum; /* variable in which sum will be stored */
```

are **definitions**. The names `integer1`, `integer2` and `sum` are the names of **variables**. A variable is a location in memory where a value can be stored for use by a program. These definitions specify that the variables `integer1`, `integer2` and `sum` are of type `int`, which means that these variables will hold **integer** values, i.e., whole numbers such as 7, -11, 0, 31914 and the like. All variables must be defined with a name and a data type immediately after the left brace that begins the body of `main` before they can be used in a program. There are other data types besides `int` in C. The preceding definitions could have been combined into a single definition statement as follows:

```
int integer1, integer2, sum;
```

but that would have made it difficult to describe the variables in corresponding comments as we did in lines 8–10.

A variable name in C is any valid **identifier**. An identifier is a series of characters consisting of letters, digits and underscores (`_`) that does not begin with a digit. An identifier can be of any length, but only the first 31 characters are required to be recognized by C compilers according to the C standard. C is **case sensitive**—uppercase and lowercase letters are different in C, so `a1` and `A1` are different identifiers.



Common Programming Error 2.4

Using a capital letter where a lowercase letter should be used (for example, typing `Main` instead of `main`).



Error-Prevention Tip 2.1

Avoid starting identifiers with the underscore character (`_`) to prevent conflicts with compiler-generated identifiers and standard library identifiers.

**Portability Tip 2.1**

Use identifiers of 31 or fewer characters. This helps ensure portability and can avoid some subtle programming errors.

**Good Programming Practice 2.5**

Choosing meaningful variable names helps make a program self-documenting, i.e., fewer comments are needed.

**Good Programming Practice 2.6**

The first letter of an identifier used as a simple variable name should be a lowercase letter. Later in the text we'll assign special significance to identifiers that begin with a capital letter and to identifiers that use all capital letters.

**Good Programming Practice 2.7**

Multiple-word variable names can help make a program more readable. Avoid running the separate words together as in `totalcommissions`. Rather, separate the words with underscores as in `total_commissions`, or, if you do wish to run the words together, begin each word after the first with a capital letter as in `totalCommissions`. The latter style is preferred.

Definitions must be placed after the left brace of a function and before *any* executable statements. For example, in the program illustrated in Fig. 2.5, inserting the definitions after the first `printf` would cause a syntax error. A **syntax error** is caused when the compiler cannot recognize a statement. The compiler normally issues an error message to help you locate and fix the incorrect statement. Syntax errors are violations of the language. Syntax errors are also called **compile errors**, or **compile-time errors**.

**Common Programming Error 2.5**

Placing variable definitions among executable statements causes syntax errors.

**Good Programming Practice 2.8**

Separate the definitions and executable statements in a function with one blank line to emphasize where the definitions end and the executable statements begin.

Line 12

```
printf( "Enter first integer\n" ); /* prompt */
```

prints the literal `Enter first integer` on the screen and positions the cursor to the beginning of the next line. This message is called a **prompt** because it tells the user to take a specific action.

The next statement

```
scanf( "%d", &integer1 ); /* read an integer */
```

uses **scanf** to obtain a value from the user. The `scanf` function reads from the standard input, which is usually the keyboard. This `scanf` has two arguments, `"%d"` and `&integer1`. The first argument, the **format control string**, indicates the type of data that should be input by the user. The **%d conversion specifier** indicates that the data should be an integer

(the letter `d` stands for “decimal integer”). The `%` in this context is treated by `scanf` (and `printf` as we’ll see) as a special character that begins a conversion specifier. The second argument of `scanf` begins with an ampersand (`&`)—called the **address operator** in C—followed by the variable name. The ampersand, when combined with the variable name, tells `scanf` the location (or address) in memory at which the variable `integer1` is stored. The computer then stores the value for `integer1` at that location. The use of ampersand (`&`) is often confusing to novice programmers or to people who have programmed in other languages that do not require this notation. For now, just remember to precede each variable in every call to `scanf` with an ampersand. Some exceptions to this rule are discussed in Chapters 6 and 7. The use of the ampersand will become clear after we study pointers in Chapter 7.



Good Programming Practice 2.9

Place a space after each comma (,) to make programs more readable.

When the computer executes the preceding `scanf`, it waits for the user to enter a value for variable `integer1`. The user responds by typing an integer, then pressing the **Enter key** to send the number to the computer. The computer then assigns this number, or value, to the variable `integer1`. Any subsequent references to `integer1` in this program will use this same value. Functions `printf` and `scanf` facilitate interaction between the user and the computer. Because this interaction resembles a dialogue, it is often called **conversational computing** or **interactive computing**.

Line 15

```
printf( "Enter second integer\n" ); /* prompt */
```

displays the message `Enter second integer` on the screen, then positions the cursor to the beginning of the next line. This `printf` also prompts the user to take action.

The statement

```
scanf( "%d", &integer2 ); /* read an integer */
```

obtains a value for variable `integer2` from the user. The **assignment statement** in line 18

```
sum = integer1 + integer2; /* assign total to sum */
```

calculates the sum of variables `integer1` and `integer2` and assigns the result to variable `sum` using the assignment operator `=`. The statement is read as, “`sum` gets the value of `integer1 + integer2`.” Most calculations are performed in assignments. The `=` operator and the `+` operator are called binary operators because each has two **operands**. The `+` operator’s two operands are `integer1` and `integer2`. The `=` operator’s two operands are `sum` and the value of the expression `integer1 + integer2`.



Good Programming Practice 2.10

Place spaces on either side of a binary operator. This makes the operator stand out and makes the program more readable.



Common Programming Error 2.6

A calculation in an assignment statement must be on the right side of the `=` operator. It is a compilation error to place a calculation on the left side of an assignment operator.

Line 20

```
printf( "Sum is %d\n", sum ); /* print sum */
```

calls function `printf` to print the literal `Sum is` followed by the numerical value of variable `sum` on the screen. This `printf` has two arguments, `"Sum is %d\n"` and `sum`. The first argument is the format control string. It contains some literal characters to be displayed, and it contains the conversion specifier `%d` indicating that an integer will be printed. The second argument specifies the value to be printed. Notice that the conversion specifier for an integer is the same in both `printf` and `scanf`. This is the case for most C data types.

Calculations can also be performed inside `printf` statements. We could have combined the previous two statements into the statement

```
printf( "Sum is %d\n", integer1 + integer2 );
```

Line 22

```
return 0; /* indicate that program ended successfully */
```

passes the value 0 back to the operating-system environment in which the program is being executed. This value indicates to the operating system that the program executed successfully. For information on how to report a program failure, see the manuals for your particular operating-system environment. The right brace, `}`, at line 24 indicates that the end of function `main` has been reached.



Common Programming Error 2.7

Forgetting one or both of the double quotes surrounding the format control string in a `printf` or `scanf`.



Common Programming Error 2.8

Forgetting the `%` in a conversion specification in the format control string of a `printf` or `scanf`.



Common Programming Error 2.9

Placing an escape sequence such as `\n` outside the format control string of a `printf` or `scanf`.



Common Programming Error 2.10

Forgetting to include the expressions whose values are to be printed in a `printf` containing conversion specifiers.



Common Programming Error 2.11

Not providing a conversion specifier when one is needed in a `printf` format control string to print the value of an expression.



Common Programming Error 2.12

Placing inside the format control string the comma that is supposed to separate the format control string from the expressions to be printed.

**Common Programming Error 2.13***Using the incorrect format conversion specifier when reading data with `scanf`.***Common Programming Error 2.14***Forgetting to precede a variable in a `scanf` statement with an ampersand when that variable should, in fact, be preceded by an ampersand.*

On many systems, the preceding execution-time error causes a “segmentation fault” or “access violation.” Such an error occurs when a user’s program attempts to access a part of the computer’s memory to which it does not have access privileges. The precise cause of this error will be explained in Chapter 7.

**Common Programming Error 2.15***Preceding a variable included in a `printf` statement with an ampersand when, in fact, that variable should not be preceded by an ampersand.*

2.4 Memory Concepts

Variable names such as `integer1`, `integer2` and `sum` actually correspond to locations in the computer’s memory. Every variable has a name, a **type** and a **value**.

In the addition program of Fig. 2.5, when the statement (line 13)

```
scanf( "%d", &integer1 ); /* read an integer */
```

is executed, the value typed by the user is placed into a memory location to which the name `integer1` has been assigned. Suppose the user enters the number 45 as the value for `integer1`. The computer will place 45 into location `integer1` as shown in Fig. 2.6.

integer1	45
----------	----

Fig. 2.6 | Memory location showing the name and value of a variable.

Whenever a value is placed in a memory location, the value replaces the previous value in that location; thus, placing a new value into a memory location is said to be **destructive**.

Returning to our addition program again, when the statement (line 16)

```
scanf( "%d", &integer2 ); /* read an integer */
```

executes, suppose the user enters the value 72. This value is placed into location `integer2`, and memory appears as in Fig. 2.7. These locations are not necessarily adjacent in memory.

Once the program has obtained values for `integer1` and `integer2`, it adds these values and places the sum into variable `sum`. The statement (line 18)

```
sum = integer1 + integer2; /* assign total to sum */
```

that performs the addition also replaces whatever value was stored in `sum`. This occurs when the calculated sum of `integer1` and `integer2` is placed into location `sum` (destroying the value already in `sum`). After `sum` is calculated, memory appears as in Fig. 2.8. The values of




Fig. 2.7 | Memory locations after both variables are input.




Fig. 2.8 | Memory locations after a calculation.

`integer1` and `integer2` appear exactly as they did before they were used in the calculation. They were used, but not destroyed, as the computer performed the calculation. Thus, when a value is read from a memory location, the process is said to be **nondestructive**.

2.5 Arithmetic in C

Most C programs perform arithmetic calculations. The C **arithmetic operators** are summarized in Fig. 2.9. Note the use of various special symbols not used in algebra. The **asterisk** (`*`) indicates multiplication and the **percent sign** (`%`) denotes the remainder operator, which is introduced below. In algebra, if we want to multiply a times b , we can simply place these single-letter variable names side by side as in ab . In C, however, if we were to do this, ab would be interpreted as a single, two-letter name (or identifier). Therefore, C (and other programming languages, in general) require that multiplication be explicitly denoted by using the `*` operator as in $a * b$.

C operation	Arithmetic operator	Algebraic expression	C expression
Addition	+	$f + 7$	<code>f + 7</code>
Subtraction	-	$p - c$	<code>p - c</code>
Multiplication	*	bm	<code>b * m</code>
Division	/	x / y or $\frac{x}{y}$ or $x \div y$	<code>x / y</code>
Remainder	%	$r \bmod s$	<code>r % s</code>

Fig. 2.9 | Arithmetic operators.

The arithmetic operators are all binary operators. For example, the expression $3 + 7$ contains the binary operator `+` and the operands 3 and 7.

Integer division yields an integer result. For example, the expression $7 / 4$ evaluates to 1 and the expression $17 / 5$ evaluates to 3. C provides the **remainder operator**, `%`, which

yields the remainder after integer division. The remainder operator is an integer operator that can be used only with integer operands. The expression $x \% y$ yields the remainder after x is divided by y . Thus, $7 \% 4$ yields 3 and $17 \% 5$ yields 2. We'll discuss many interesting applications of the remainder operator.



Common Programming Error 2.16

An attempt to divide by zero is normally undefined on computer systems and generally results in a fatal error, i.e., an error that causes the program to terminate immediately without having successfully performed its job. Nonfatal errors allow programs to run to completion, often producing incorrect results.

Arithmetic Expressions in Straight-Line Form

Arithmetic expressions in C must be written in **straight-line form** to facilitate entering programs into the computer. Thus, expressions such as “a divided by b” must be written as a/b so that all operators and operands appear in a straight line. The algebraic notation

$$\frac{a}{b}$$

is generally not acceptable to compilers, although some special-purpose software packages do support more natural notation for complex mathematical expressions.

Parentheses for Grouping Subexpressions

Parentheses are used in C expressions in the same manner as in algebraic expressions. For example, to multiply a times the quantity $b + c$ we write $a * (b + c)$.

Rules of Operator Precedence

C applies the operators in arithmetic expressions in a precise sequence determined by the following **rules of operator precedence**, which are generally the same as those in algebra:

1. Operators in expressions contained within pairs of parentheses are evaluated first. Thus, *parentheses may be used to force the order of evaluation to occur in any sequence you desire*. Parentheses are said to be at the “highest level of precedence.” In cases of **nested**, or **embedded**, **parentheses**, such as

$$((a + b) + c)$$

the operators in the innermost pair of parentheses are applied first.

2. Multiplication, division and remainder operations are applied first. If an expression contains several multiplication, division and remainder operations, evaluation proceeds from left to right. Multiplication, division and remainder are said to be on the same level of precedence.
3. Addition and subtraction operations are evaluated next. If an expression contains several addition and subtraction operations, evaluation proceeds from left to right. Addition and subtraction also have the same level of precedence, which is lower than the precedence of the multiplication, division and remainder operations.

The rules of operator precedence specify the order C uses to evaluate expressions.¹ When we say evaluation proceeds from left to right, we're referring to the **associativity** of the operators. We'll see that some operators associate from right to left. Figure 2.10 summarizes these rules of operator precedence.

Operator(s)	Operation(s)	Order of evaluation (precedence)
()	Parentheses	Evaluated first. If the parentheses are nested, the expression in the innermost pair is evaluated first. If there are several pairs of parentheses “on the same level” (i.e., not nested), they’re evaluated left to right.
*	Multiplication	Evaluated second. If there are several, they’re evaluated left to right.
/	Division	
%	Remainder	
+	Addition	Evaluated last. If there are several, they’re evaluated left to right.
-	Subtraction	

Fig. 2.10 | Precedence of arithmetic operators.

Sample Algebraic and C Expressions

Now let’s consider several expressions in light of the rules of operator precedence. Each example lists an algebraic expression and its C equivalent. The following example calculates the arithmetic mean (average) of five terms.

Algebra: $m = \frac{a + b + c + d + e}{5}$

Java: `m = ( a + b + c + d + e ) / 5;`

The parentheses are required to group the additions because division has higher precedence than addition. The entire quantity (a + b + c + d + e) should be divided by 5. If the parentheses are erroneously omitted, we obtain a + b + c + d + e / 5 which evaluates incorrectly as

$$a + b + c + d + \frac{e}{5}$$

The following example is the equation of a straight line:

Algebra: $y = mx + b$

C: `y = m * x + b;`

No parentheses are required. The multiplication is evaluated first because multiplication has a higher precedence than addition.

The following example contains remainder (%), multiplication, division, addition, subtraction and assignment operations:

Algebra: $z = pr \% q + w / x - y$

C: `z = p * r % q + w / x - y;`

6

1

2

4

3

5

1. We use simple examples to explain the order of evaluation of expressions. Subtle issues occur in more complex expressions that you’ll encounter later in the book. We’ll discuss these issues as they arise.

The circled numbers indicate the order in which C evaluates the operators. The multiplication, remainder and division are evaluated first in left-to-right order (i.e., they associate from left to right) since they have higher precedence than addition and subtraction. The addition and subtraction are evaluated next. They're also evaluated left to right.

Not all expressions with several pairs of parentheses contain nested parentheses. For example, the following expression does not contain nested parentheses—instead, the parentheses are said to be “on the same level.”

```
a * ( b + c ) + c * ( d + e )
```

Evaluation of a Second-Degree Polynomial

To develop a better understanding of the rules of operator precedence, let's see how C evaluates a second-degree polynomial.

```
y = a * x * x + b * x + c;
```

6
1
2
4
3
5

The circled numbers under the statement indicate the order in which C performs the operations. There is no arithmetic operator for exponentiation in C, so we have represented x^2 as $x * x$. The C Standard Library includes the `pow` (“power”) function to perform exponentiation. Because of some subtle issues related to the data types required by `pow`, we defer a detailed explanation of `pow` until Chapter 4.

Suppose variables `a`, `b`, `c` and `x` in the preceding second-degree polynomial are initialized as follows: `a = 2`, `b = 3`, `c = 7` and `x = 5`. Figure 2.11 illustrates the order in which the operators are applied.




Fig. 2.11 | Order in which a second-degree polynomial is evaluated.

As in algebra, it is acceptable to place unnecessary parentheses in an expression to make the expression clearer. These are called **redundant parentheses**. For example, the preceding statement could be parenthesized as follows:

```
y = ( a * x * x ) + ( b * x ) + c;
```



Good Programming Practice 2.11
Using redundant parentheses in complex arithmetic expressions can make the expressions clearer.

2.6 Decision Making: Equality and Relational Operators

Executable C statements either perform actions (such as calculations or input or output of data) or make **decisions** (we’ll soon see several examples of these). We might make a decision in a program, for example, to determine if a person’s grade on an exam is greater than or equal to 60 and if it is to print the message “Congratulations! You passed.” This section introduces a simple version of C’s **if statement** that allows a program to make a decision based on the truth or falsity of a statement of fact called a **condition**. If the condition is met (i.e., the condition is **true**) the statement in the body of the **if** statement is executed. If the condition is not met (i.e., the condition is **false**) the body statement is not executed. Whether the body statement is executed or not, after the **if** statement completes, execution proceeds with the next statement after the **if** statement.

Conditions in **if** statements are formed by using the **equality operators** and **relational operators** summarized in Fig. 2.12. The relational operators all have the same level of precedence and they associate left to right. The equality operators have a lower level of precedence than the relational operators and they also associate left to right. [Note: In C, a condition may actually be any expression that generates a zero (false) or nonzero (true) value. We’ll see many applications of this throughout the book.]

Algebraic equality or relational operator	C equality or relational operator	Example of C condition	Meaning of C condition
<i>Equality operators</i>			
=	==	x == y	x is equal to y
≠	!=	x != y	x is not equal to y
<i>Relational operators</i>			
>	>	x > y	x is greater than y
<	<	x < y	x is less than y
≥	>=	x >= y	x is greater than or equal to y
≤	<=	x <= y	x is less than or equal to y

Fig. 2.12 | Equality and relational operators.



Common Programming Error 2.17
A syntax error occurs if the two symbols in any of the operators ==, !=, >= and <= are separated by spaces.

**Common Programming Error 2.18**

A syntax error occurs if the two symbols in any of the operators `!=`, `>=` and `<=` are reversed as in `=!`, `=>` and `=<`, respectively.

**Common Programming Error 2.19**

Confusing the equality operator `==` with the assignment operator.

To avoid this confusion, the equality operator should be read “double equals” and the assignment operator should be read “gets” or “is assigned the value of.” As we’ll soon see, confusing these operators may not necessarily cause an easy-to-recognize compilation error, but may cause extremely subtle logic errors.

**Common Programming Error 2.20**

Placing a semicolon immediately to the right of the right parenthesis after the condition in an `if` statement.

Figure 2.13 uses six `if` statements to compare two numbers input by the user. If the condition in any of these `if` statements is true, the `printf` statement associated with that `if` executes. The program and three sample execution outputs are shown in the figure.

```

1  /* Fig. 2.13: fig02_13.c
2     Using if statements, relational
3     operators, and equality operators */
4  #include <stdio.h>
5
6  /* function main begins program execution */
7  int main( void )
8  {
9      int num1; /* first number to be read from user */
10     int num2; /* second number to be read from user */
11
12     printf( "Enter two integers, and I will tell you\n" );
13     printf( "the relationships they satisfy: " );
14
15     scanf( "%d%d", &num1, &num2 ); /* read two integers */
16
17     if ( num1 == num2 ) {
18         printf( "%d is equal to %d\n", num1, num2 );
19     } /* end if */
20
21     if ( num1 != num2 ) {
22         printf( "%d is not equal to %d\n", num1, num2 );
23     } /* end if */
24
25     if ( num1 < num2 ) {
26         printf( "%d is less than %d\n", num1, num2 );
27     } /* end if */
28

```

Fig. 2.13 | Using `if` statements, relational operators, and equality operators. (Part I of 2.)

```

29     if ( num1 > num2 ) {
30         printf( "%d is greater than %d\n", num1, num2 );
31     } /* end if */
32
33     if ( num1 <= num2 ) {
34         printf( "%d is less than or equal to %d\n", num1, num2 );
35     } /* end if */
36
37     if ( num1 >= num2 ) {
38         printf( "%d is greater than or equal to %d\n", num1, num2 );
39     } /* end if */
40
41     return 0; /* indicate that program ended successfully */
42 } /* end function main */

```

Enter two integers, and I will tell you
the relationships they satisfy: 3 7
3 is not equal to 7
3 is less than 7
3 is less than or equal to 7

Enter two integers, and I will tell you
the relationships they satisfy: 12 12
22 is not equal to 12
22 is greater than 12
22 is greater than or equal to 12

Enter two integers, and I will tell you
the relationships they satisfy: 7 7
7 is equal to 7
7 is less than or equal to 7
7 is greater than or equal to 7

Fig. 2.13 | Using `if` statements, relational operators, and equality operators. (Part 2 of 2.)

The program uses `scanf` (line 15) to input two numbers. Each conversion specifier has a corresponding argument in which a value will be stored. The first `%d` converts a value to be stored in variable `num1`, and the second `%d` converts a value to be stored in variable `num2`. Indenting the body of each `if` statement and placing blank lines above and below each `if` statement enhances program readability.



Good Programming Practice 2.12

Indent the statement(s) in the body of an `if` statement.



Good Programming Practice 2.13

Place a blank line before and after every `if` statement in a program for readability.



Good Programming Practice 2.14

Although it is allowed, there should be no more than one statement per line in a program.



Common Programming Error 2.21

Placing commas (when none are needed) between conversion specifiers in the format control string of a `scanf` statement.

A left brace, `{`, begins the body of each `if` statement (e.g., line 17). A corresponding right brace, `}`, ends each `if` statement's body (e.g., line 19). Any number of statements can be placed in the body of an `if` statement.²

The comment (lines 1–3) in Fig. 2.13 is split over three lines. In C programs, **white space** characters such as tabs, newlines and spaces are normally ignored. So, statements and comments may be split over several lines. It is not correct, however, to split identifiers.



Good Programming Practice 2.15

A lengthy statement may be spread over several lines. If a statement must be split across lines, choose breaking points that make sense (such as after a comma in a comma-separated list). If a statement is split across two or more lines, indent all subsequent lines.

Figure 2.14 lists the precedence of the operators introduced in this chapter. Operators are shown top to bottom in decreasing order of precedence. The equals sign is also an operator. All these operators, with the exception of the assignment operator `=`, associate from left to right. The assignment operator (`=`) associates from right to left.



Good Programming Practice 2.16

Refer to the operator precedence chart when writing expressions containing many operators. Confirm that the operators in the expression are applied in the proper order. If you're uncertain about the order of evaluation in a complex expression, use parentheses to group expressions or break the statement into several simpler statements. Be sure to observe that some of C's operators such as the assignment operator (`=`) associate from right to left rather than from left to right.

Operators	Associativity
<code>()</code>	left to right
<code>*</code> <code>/</code> <code>%</code>	left to right
<code>+</code> <code>-</code>	left to right
<code><</code> <code><=</code> <code>></code> <code>>=</code>	left to right
<code>==</code> <code>!=</code>	left to right
<code>=</code>	right to left

Fig. 2.14 | Precedence and associativity of the operators discussed so far.

- Using braces to delimit the body of an `if` statement is optional when the body contains only one statement. Many programmers consider it good practice to always use these braces. In Chapter 3, we'll explain the issues.

Some of the words we have used in the C programs in this chapter—in particular `int`, `return` and `if`—are **keywords** or reserved words of the language. Figure 2.15 contains the C keywords. These words have special meaning to the C compiler, so you must be careful not to use these as identifiers such as variable names. In this book, we discuss all these keywords.

Keywords			
<code>auto</code>	<code>double</code>	<code>int</code>	<code>struct</code>
<code>break</code>	<code>else</code>	<code>long</code>	<code>switch</code>
<code>case</code>	<code>enum</code>	<code>register</code>	<code>typedef</code>
<code>char</code>	<code>extern</code>	<code>return</code>	<code>union</code>
<code>const</code>	<code>float</code>	<code>short</code>	<code>unsigned</code>
<code>continue</code>	<code>for</code>	<code>signed</code>	<code>void</code>
<code>default</code>	<code>goto</code>	<code>sizeof</code>	<code>volatile</code>
<code>do</code>	<code>if</code>	<code>static</code>	<code>while</code>
<i>Keywords added in C99</i>			
<code>_Bool</code> <code>_Complex</code> <code>_Imaginary</code> <code>inline</code> <code>restrict</code>			

Fig. 2.15 | C’s keywords.

In this chapter, we have introduced many important features of the C programming language, including printing data on the screen, inputting data from the user, performing calculations and making decisions. In the next chapter, we build upon these techniques as we introduce structured programming. You’ll become more familiar with indentation techniques. We’ll study how to specify the order in which statements are executed—this is called **flow of control**.

Summary

Section 2.1 Introduction

- The C language facilitates a structured and disciplined approach to computer program design.

Section 2.2 A Simple C Program: Printing a Line of Text

- Comments begin with `/*` and end with `*/`. Comments document programs and improve program readability. C99 also supports C++’s single-line comments that begin with `//`.
- Comments do not cause the computer to perform any action when the program is run. They’re ignored by the C compiler and do not cause any machine-language object code to be generated.
- Lines beginning with `#` are processed by the preprocessor before the program is compiled. The `#include` directive tells the preprocessor to include the contents of another file (typically a header file such as `<stdio.h>`).
- The `<stdio.h>` header contains information used by the compiler when compiling calls to standard input/output library functions such as `printf`.

- The function `main` is a part of every C program. The parentheses after `main` indicate that `main` is a program building block called a function. C programs contain one or more functions, one of which must be `main`. Every program in C begins executing at the function `main`.
- Functions can return information. The keyword `int` to the left of `main` indicates that `main` “returns” an integer (whole number) value.
- Functions can receive information when they’re called upon to execute. The `void` in parentheses after `main` indicates that `main` does not receive any information.
- A left brace, `{`, begins the body of every function. A corresponding right brace, `}`, ends each function. This pair of braces and the portion of the program between the braces is called a block.
- The `printf` function instructs the computer to display information on the screen.
- A string is sometimes called a character string, a message or a literal.
- Every statement must end with a semicolon (also known as the statement terminator).
- The characters `\n` do not display characters on the screen. The backslash (`\`) is called an escape character. When encountering a backslash in a string, the compiler looks ahead at the next character and combines it with the backslash to form an escape sequence. The escape sequence `\n` means newline.
- When a newline appears in the string output by a `printf`, the newline causes the cursor to position to the beginning of the next line on the screen.
- The double backslash (`\\`) escape sequence can be used to place a single backslash in a string.
- The escape sequence `\"` represents a literal double-quote character.
- The keyword `return` is one of several means to exit a function. When the `return` statement is used at the end of `main`, the value `0` indicates that the program has terminated successfully.

Section 2.3 Another Simple C Program: Adding Two Integers

- A variable is a location in memory where a value can be stored for use by a program.
- Variables of type `int` hold integer values, i.e., whole numbers such as 7, -11, 0, 31914.
- All variables must be defined with a name and a data type immediately after the left brace that begins the body of `main` before they can be used in a program.
- A variable name in C is any valid identifier. An identifier is a series of characters consisting of letters, digits and underscores (`_`) that does not begin with a digit. An identifier can be any length, but only the first 31 characters are required to be recognized by C compilers according to the C standard.
- C is case sensitive—uppercase and lowercase letters are different in C.
- Definitions must be placed after the left brace of a function and before *any* executable statements.
- A syntax error is caused when the compiler cannot recognize a statement. The compiler normally issues an error message to help you locate and fix the incorrect statement. Syntax errors are violations of the language. Syntax errors are also called compile errors, or compile-time errors.
- Standard Library function `scanf` can be used to obtain input from the standard input, which is usually the keyboard.
- The `scanf` format control string indicates the type(s) of data that should be input.
- The `%d` conversion specifier indicates that the data should be an integer (the letter `d` stands for “decimal integer”). The `%` in this context is treated by `scanf` (and `printf`) as a special character that begins a conversion specifier.
- The other arguments of `scanf` begin with an ampersand (`&`)—called the address operator in C—followed by a variable name. The ampersand, when combined with a variable name, tells `scanf`

the location in memory at which the variable is located. The computer then stores the value for the variable at that location.

- Most calculations are performed in assignment statements.
- The = operator and the + operator are binary operators—each has two operands.
- Function `printf` also can use a format control string as its first argument. This string contains some literal characters to be displayed and the conversion specifiers that indicate place holders for data to output.

Section 2.4 Memory Concepts

- Variable names correspond to locations in the computer's memory. Every variable has a name, a type and a value.
- Whenever a value is placed in a memory location, the value replaces the previous value in that location; thus, placing a new value into a memory location is said to be destructive.
- When a value is read out of a memory location, the process is said to be nondestructive.

Section 2.5 Arithmetic in C

- In algebra, if we want to multiply a times b , we can simply place these single-letter variable names side by side as in ab . In C, however, if we were to do this, ab would be interpreted as a single, two-letter name (or identifier). Therefore, C (like other programming languages, in general) requires that multiplication be explicitly denoted by using the `*` operator, as in $a * b$.
- The arithmetic operators are all binary operators.
- Integer division yields an integer result. For example, the expression $7 / 4$ evaluates to 1 and the expression $17 / 5$ evaluates to 3.
- C provides the remainder operator, `%`, which yields the remainder after integer division. The remainder operator is an integer operator that can be used only with integer operands. The expression $x \% y$ yields the remainder after x is divided by y . Thus, $7 \% 4$ yields 3 and $17 \% 5$ yields 2.
- An attempt to divide by zero is normally undefined on computer systems and generally results in a fatal error that causes the program to terminate immediately. Nonfatal errors allow programs to run to completion, often producing incorrect results.
- Arithmetic expressions in C must be written in straight-line form to facilitate entering programs into the computer. Thus, expressions such as “ a divided by b ” must be written as a/b so that all operators and operands appear in a straight line.
- Parentheses are used to group terms in C expressions in much the same manner as in algebraic expressions.
- C evaluates arithmetic expressions in a precise sequence determined by the following rules of operator precedence, which are generally the same as those followed in algebra.
- Multiplication, division and remainder operations are applied first. If an expression contains several multiplication, division and remainder operations, evaluation proceeds from left to right. Multiplication, division and remainder are said to be on the same level of precedence.
- Addition and subtraction operations are evaluated next. If an expression contains several addition and subtraction operations, evaluation proceeds from left to right. Addition and subtraction also have the same level of precedence, which is lower than the precedence of the multiplication, division and remainder operators.
- The rules of operator precedence specify the order C uses to evaluate expressions. When we say evaluation proceeds from left to right, we're referring to the associativity of the operators. Some operators associate from right to left.

Section 2.6 Decision Making: Equality and Relational Operators

- Executable C statements either perform actions or make decisions.
- C's `if` statement allows a program to make a decision based on the truth or falsity of a statement of fact called a condition. If the condition is met (i.e., the condition is true) the statement in the body of the `if` statement executes. If the condition is not met (i.e., the condition is false) the body statement does not execute. Whether the body statement is executed or not, after the `if` statement completes, execution proceeds with the next statement after the `if` statement.
- Conditions in `if` statements are formed by using the equality operators and relational operators.
- The relational operators all have the same level of precedence and associate left to right. The equality operators have a lower level of precedence than the relational operators and they also associate left to right.
- To avoid confusing assignment (`=`) and equality (`==`), the assignment operator should be read “gets” and the equality operator should be read “double equals.”
- In C programs, white-space characters such as tabs, newlines and spaces are normally ignored. So, statements and comments may be split over several lines. It is not correct to split identifiers.
- Some of the words in C programs—such as `int`, `return` and `if`—are keywords or reserved words of the language. These words have special meaning to the C compiler, so you cannot use them as identifiers such as variable names.

Terminology

- * multiplication operator 34
- % remainder operator 34
- %d conversion specifier 30
- action 26
- action/decision model 27
- address operator (&) 31
- argument 26
- arithmetic operators 34
- assignment statement 31
- associativity 35
- body 25
- C preprocessor 25
- case sensitive 29
- character string 26
- comment (`/* */`) 24
- compile error 30
- compile-time error 30
- condition 38
- conversational computing 31
- decision 38
- definition 29
- destructive 33
- document a program 24
- embedded parentheses 35
- Enter* key 31
- equality operator 38
- escape character 26
- escape sequence 26
- executable 27
- exit a function 26
- false 38
- flow of control 42
- format control string 30
- function 25
- identifier 29
- `if` statement 38
- integer 29
- integer division 34
- interactive computing 31
- keyword 42
- literal 26
- message 26
- nested parentheses 35
- newline (`\n`) 26
- nondestructive 34
- operand 31
- percent sign (%) 34
- prompt 30
- redundant parentheses 38
- relational operator 38
- right brace `}` 25
- rules of operator precedence 35
- `scanf` function 30
- single-line comment (`//`) 25
- standard input/output header 25
- statement 26

statement terminator (;) 26	true 38
<stdio.h> header 25	type 33
straight-line form 35	value 33
string 26	variable 29
structured programming 24	white space 41
syntax error 30	

Self-Review Exercises

2.1 Fill in the blanks in each of the following.

- Every C program begins execution at the function _____.
- The _____ begins the body of every function and the _____ ends the body of every function.
- Every statement ends with a(n) _____.
- The _____ standard library function displays information on the screen.
- The escape sequence `\n` represents the _____ character, which causes the cursor to position to the beginning of the next line on the screen.
- The _____ Standard Library function is used to obtain data from the keyboard.
- The conversion specifier _____ is used in a `scanf` format control string to indicate that an integer will be input and in a `printf` format control string to indicate that an integer will be output.
- Whenever a new value is placed in a memory location, that value overrides the previous value in that location. This process is said to be _____.
- When a value is read out of a memory location, the value in that location is preserved; this process is said to be _____.
- The _____ statement is used to make decisions.

2.2 State whether each of the following is *true* or *false*. If *false*, explain why.

- Function `printf` always begins printing at the beginning of a new line.
- Comments cause the computer to print the text enclosed between `/*` and `*/` on the screen when the program is executed.
- The escape sequence `\n` when used in a `printf` format control string causes the cursor to position to the beginning of the next line on the screen.
- All variables must be defined before they're used.
- All variables must be given a type when they're defined.
- C considers the variables `number` and `NumBEr` to be identical.
- Definitions can appear anywhere in the body of a function.
- All arguments following the format control string in a `printf` function must be preceded by an ampersand (`&`).
- The remainder operator (`%`) can be used only with integer operands.
- The arithmetic operators `*`, `/`, `%`, `+` and `-` all have the same level of precedence.
- The following variable names are identical on all Standard C systems.

```
thisisasuperduperlongname1234567
thisisasuperduperlongname1234568
```

- A program that prints three lines of output must contain three `printf` statements.

2.3 Write a single C statement to accomplish each of the following:

- Define the variables `c`, `thisVariable`, `q76354` and `number` to be of type `int`.
- Prompt the user to enter an integer. End your prompting message with a colon (`:`) followed by a space and leave the cursor positioned after the space.
- Read an integer from the keyboard and store the value entered in integer variable `a`.
- If `number` is not equal to 7, print "The variable `number` is not equal to 7."

- e) Print the message "This is a C program." on one line.
- f) Print the message "This is a C program." on two lines so that the first line ends with C.
- g) Print the message "This is a C program." with each word on a separate line.
- h) Print the message "This is a C program." with the words separated by tabs.

2.4 Write a statement (or comment) to accomplish each of the following:

- a) State that a program will calculate the product of three integers.
- b) Define the variables x, y, z and result to be of type int.
- c) Prompt the user to enter three integers.
- d) Read three integers from the keyboard and store them in the variables x, y and z.
- e) Compute the product of the three integers contained in variables x, y and z, and assign the result to the variable result.
- f) Print "The product is" followed by the value of the integer variable result.

2.5 Using the statements you wrote in Exercise 2.4, write a complete program that calculates the product of three integers.

2.6 Identify and correct the errors in each of the following statements:

- a) `printf( "The value is %d\n", &number );`
- b) `scanf( "%d%d", &number1, number2 );`
- c) `if ( c < 7 );{`
`printf( "C is less than 7\n" );`
`}`
- d) `if ( c == 7 ) {`
`printf( "C is equal to or less than 7\n" );`
`}`

Answers to Self-Review Exercises

2.1 a) main. b) left brace ({), right brace (}). c) semicolon. d) printf. e) newline. f) scanf. g) %d. h) destructive. i) nondestructive. j) if.

- 2.2**
- a) False. Function printf always begins printing where the cursor is positioned, and this may be anywhere on a line of the screen.
 - b) False. Comments do not cause any action to be performed when the program is executed. They're used to document programs and improve their readability.
 - c) True.
 - d) True.
 - e) True.
 - f) False. C is case sensitive, so these variables are unique.
 - g) False. The definitions must appear after the left brace of the body of a function and before any executable statements.
 - h) False. Arguments in a printf function ordinarily should not be preceded by an ampersand. Arguments following the format control string in a scanf function ordinarily should be preceded by an ampersand. We'll discuss exceptions to these rules in Chapter 6 and Chapter 7.
 - i) True.
 - j) False. The operators *, / and % are on the same level of precedence, and the operators + and - are on a lower level of precedence.
 - k) False. Some systems may distinguish between identifiers longer than 31 characters.
 - l) False. A printf statement with multiple \n escape sequences can print several lines.

- 2.3**
- a) `int c, thisVariable, q76354, number;`
 - b) `printf( "Enter an integer: " );`

- c) `scanf( "%d", &a );`
- d) `if ( number != 7 )`
`{`
`printf( "The variable number is not equal to 7.\n" );`
`}`
- e) `printf( "This is a C program.\n" );`
- f) `printf( "This is a C\nprogram.\n" );`
- g) `printf( "This\nis\nna\nC\nprogram.\n" );`
- h) `printf( "This\tis\ta\tC\tprogram.\n" );`

- 2.4**
- a) `/* Calculate the product of three integers */`
 - b) `int x, y, z, result;`
 - c) `printf( "Enter three integers: " );`
 - d) `scanf( "%d%d%d", &x, &y, &z );`
 - e) `result = x * y * z;`
 - f) `printf( "The product is %d\n", result );`

- 2.5** See below.

```

1  /* Calculate the product of three integers */
2  #include <stdio.h>
3
4  int main( void )
5  {
6      int x, y, z, result; /* declare variables */
7
8      printf( "Enter three integers: " ); /* prompt */
9      scanf( "%d%d%d", &x, &y, &z ); /* read three integers */
10     result = x * y * z; /* multiply values */
11     printf( "The product is %d\n", result ); /* display result */
12     return 0;
13 } /* end function main */

```

- 2.6**
- a) Error: `&number`. Correction: Eliminate the `&`. We discuss exceptions to this later.
 - b) Error: `number2` does not have an ampersand. Correction: `number2` should be `&number2`. Later in the text we discuss exceptions to this.
 - c) Error: Semicolon after the right parenthesis of the condition in the `if` statement. Correction: Remove the semicolon after the right parenthesis. [Note: The result of this error is that the `printf` statement will be executed whether or not the condition in the `if` statement is true. The semicolon after the right parenthesis is considered an empty statement—a statement that does nothing.]
 - d) Error: The relational operator `=>` should be changed to `>=` (greater than or equal to).

Exercises

- 2.7** Identify and correct the errors in each of the following statements. (Note: There may be more than one error per statement.)

- a) `scanf( "d", value );`
- b) `printf( "The product of %d and %d is %d\n", x, y );`
- c) `firstNumber + secondNumber = sumOfNumbers`
- d) `if ( number => largest )`
`largest == number;`
- e) `/* Program to determine the largest of three integers */`
- f) `Scanf( "%d", anInteger );`

- g) `printf( "Remainder of %d divided by %d is\n", x, y, x % y );`
- h) `if ( x = y );`
`printf( %d is equal to %d\n", x, y );`
- i) `print( "The sum is %d\n," x + y );`
- j) `Printf( "The value you entered is: %d\n, &value );`

2.8 Fill in the blanks in each of the following:

- a) _____ are used to document a program and improve its readability.
- b) The function used to display information on the screen is _____.
- c) A C statement that makes a decision is _____.
- d) Calculations are normally performed by _____ statements.
- e) The _____ function inputs values from the keyboard.

2.9 Write a single C statement or line that accomplishes each of the following:

- a) Print the message "Enter two numbers."
- b) Assign the product of variables b and c to variable a.
- c) State that a program performs a sample payroll calculation (i.e., use text that helps to document a program).
- d) Input three integer values from the keyboard and place these values in integer variables a, b and c.

2.10 State which of the following are *true* and which are *false*. If *false*, explain your answer.

- a) C operators are evaluated from left to right.
- b) The following are all valid variable names: `_under_bar_`, `m928134`, `t5`, `j7`, `her_sales`, `his_account_total`, `a`, `b`, `c`, `z`, `z2`.
- c) The statement `printf("a = 5;");` is a typical example of an assignment statement.
- d) A valid arithmetic expression containing no parentheses is evaluated from left to right.
- e) The following are all invalid variable names: `3g`, `87`, `67h2`, `h22`, `2h`.

2.11 Fill in the blanks in each of the following:

- a) What arithmetic operations are on the same level of precedence as multiplication?
 _____.
- b) When parentheses are nested, which set of parentheses is evaluated first in an arithmetic expression? _____.
- c) A location in the computer's memory that may contain different values at various times throughout the execution of a program is called a _____.

2.12 What, if anything, prints when each of the following statements is performed? If nothing prints, then answer "Nothing." Assume `x = 2` and `y = 3`.

- a) `printf( "%d", x );`
- b) `printf( "%d", x + x );`
- c) `printf( "x=" );`
- d) `printf( "x=%d", x );`
- e) `printf( "%d = %d", x + y, y + x );`
- f) `z = x + y;`
- g) `scanf( "%d%d", &x, &y );`
- h) `/* printf( "x + y = %d", x + y ); */`
- i) `printf( "\n" );`

2.13 Which, if any, of the following C statements contain variables whose values are replaced?

- a) `scanf( "%d%d%d%d%d", &b, &c, &d, &e, &f );`
- b) `p = i + j + k + 7;`
- c) `printf( "Values are replaced" );`
- d) `printf( "a = 5" );`

2.14 Given the equation $y = ax^3 + 7$, which of the following, if any, are correct C statements for this equation?

- a) `y = a * x * x * x + 7;`
- b) `y = a * x * x * ( x + 7 );`
- c) `y = ( a * x ) * x * ( x + 7 );`
- d) `y = ( a * x ) * x * x + 7;`
- e) `y = a * ( x * x * x ) + 7;`
- f) `y = a * x * ( x * x + 7 );`

2.15 State the order of evaluation of the operators in each of the following C statements and show the value of x after each statement is performed.

- a) `x = 7 + 3 * 6 / 2 - 1;`
- b) `x = 2 % 2 + 2 * 2 - 2 / 2;`
- c) `x = ( 3 * 9 * ( 3 + ( 9 * 3 / ( 3 ) ) ) );`

2.16 (*Arithmetic*) Write a program that asks the user to enter two numbers, obtains them from the user and prints their sum, product, difference, quotient and remainder.

2.17 (*Printing Values with printf*) Write a program that prints the numbers 1 to 4 on the same line. Write the program using the following methods.

- a) Using one `printf` statement with no conversion specifiers.
- b) Using one `printf` statement with four conversion specifiers.
- c) Using four `printf` statements.

2.18 (*Comparing Integers*) Write a program that asks the user to enter two integers, obtains the numbers from the user, then prints the larger number followed by the words “is larger.” If the numbers are equal, print the message “These numbers are equal.” Use only the single-selection form of the `if` statement you learned in this chapter.

2.19 (*Arithmetic, Largest Value and Smallest Value*) Write a program that inputs three different integers from the keyboard, then prints the sum, the average, the product, the smallest and the largest of these numbers. Use only the single-selection form of the `if` statement you learned in this chapter. The screen dialogue should appear as follows:

```
Input three different integers: 13 27 14
Sum is 54
Average is 18
Product is 4914
Smallest is 13
Largest is 27
```

2.20 (*Diameter, Circumference and Area of a Circle*) Write a program that reads in the radius of a circle and prints the circle’s diameter, circumference and area. Use the constant value 3.14159 for π . Perform each of these calculations inside the `printf` statement(s) and use the conversion specifier `%f`. [Note: In this chapter, we have discussed only integer constants and variables. In Chapter 3 we’ll discuss floating-point numbers, i.e., values that can have decimal points.]

2.21 (*Shapes with Asterisks*) Write a program that prints the following shapes with asterisks.

```
*****          ***          *          *
*              *          *          * *
*            *          *          * *
*          *          *          * *
*        *          *          * *
*      *          *          * *
*    *          *          * *
*  *          *          * *
* *          *          * *
* *          *          * *
*****          ***          *          *
```

2.22 What does the following code print?

```
printf( "\n*\n*\n*\n*\n*\n*\n*\n" );
```

2.23 (*Largest and Smallest Integers*) Write a program that reads in five integers and then determines and prints the largest and the smallest integers in the group. Use only the programming techniques you have learned in this chapter.

2.24 (*Odd or Even*) Write a program that reads an integer and determines and prints whether it is odd or even. [Hint: Use the remainder operator. An even number is a multiple of two. Any multiple of two leaves a remainder of zero when divided by 2.]

2.25 Print your initials in block letters down the page. Construct each block letter out of the letter it represents as shown below.

```
PPPPPPPP
 P  P
 P  P
 P  P
  P P

 JJ
 J
 J
 J
 JJJJJJ

 DDDDDDDD
 D      D
 D      D
 D      D
 DDDDD
```

2.26 (*Multiples*) Write a program that reads in two integers and determines and prints if the first is a multiple of the second. [Hint: Use the remainder operator.]

2.27 (*Checkerboard Pattern of Asterisks*) Display the following checkerboard pattern with eight printf statements and then display the same pattern with as few printf statements as possible.

```
* * * * *
* * * * *
* * * * *
* * * * *
* * * * *
* * * * *
* * * * *
* * * * *
```

2.28 Distinguish between the terms fatal error and nonfatal error. Why might you prefer to experience a fatal error rather than a nonfatal error?

2.29 (*Integer Value of a Character*) Here's a peek ahead. In this chapter you learned about integers and the type int. C can also represent uppercase letters, lowercase letters and a considerable variety of special symbols. C uses small integers internally to represent each different character. The set of characters a computer uses together with the corresponding integer representations for those characters is called that computer's character set. You can print the integer equivalent of uppercase A, for example, by executing the statement

```
printf( "%d", 'A' );
```

Write a C program that prints the integer equivalents of some uppercase letters, lowercase letters, digits and special symbols. As a minimum, determine the integer equivalents of the following: A B C a b c 0 1 2 \$ * + / and the blank character.

2.30 (*Separating Digits in an Integer*) Write a program that inputs one five-digit number, separates the number into its individual digits and prints the digits separated from one another by three spaces each. [Hint: Use combinations of integer division and the remainder operation.] For example, if the user types in 42139, the program should print

```
4   2   1   3   9
```

2.31 (*Table of Squares and Cubes*) Using only the techniques you learned in this chapter, write a program that calculates the squares and cubes of the numbers from 0 to 10 and uses tabs to print the following table of values:

number	square	cube
0	0	0
1	1	1
2	4	8
3	9	27
4	16	64
5	25	125
6	36	216
7	49	343
8	64	512
9	81	729
10	100	1000

Making a Difference

2.32 (*Body Mass Index Calculator*) We introduced the body mass index (BMI) calculator in Exercise 1.11. The formulas for calculating BMI are

$$BMI = \frac{weightInPounds \times 703}{heightInInches \times heightInInches}$$

or

$$BMI = \frac{weightInKilograms}{heightInMeters \times heightInMeters}$$

Create a BMI calculator application that reads the user's weight in pounds and height in inches (or, if you prefer, the user's weight in kilograms and height in meters), then calculates and displays the user's body mass index. Also, the application should display the following information from the Department of Health and Human Services/National Institutes of Health so the user can evaluate his/her BMI:

```
BMI VALUES
Underweight: less than 18.5
Normal:      between 18.5 and 24.9
Overweight:  between 25 and 29.9
Obese:       30 or greater
```

[Note: In this chapter, you learned to use the `int` type to represent whole numbers. The BMI calculations when done with `int` values will both produce whole-number results. In Chapter 4 you'll learn to use the `double` type to represent numbers with decimal points. When the BMI calculations are performed with `doubles`, they'll both produce numbers with decimal points—these are called “floating-point” numbers.]

2.33 (*Car-Pool Savings Calculator*) Research several car-pooling websites. Create an application that calculates your daily driving cost, so that you can estimate how much money could be saved by car pooling, which also has other advantages such as reducing carbon emissions and reducing traffic congestion. The application should input the following information and display the user's cost per day of driving to work:

- a) Total miles driven per day.
- b) Cost per gallon of gasoline.
- c) Average miles per gallon.
- d) Parking fees per day.
- e) Tolls per day.

3

Structured Program Development in C

Let's all move one place on.

—Lewis Carroll

The wheel is come full circle.

—William Shakespeare

*How many apples fell on
Newton's head before he took the
hint!*

—Robert Frost

*All the evolution we know of
proceeds from the vague to the
definite.*

—Charles Sanders Peirce

Objectives

In this chapter, you'll learn:

- Basic problem-solving techniques.
- To develop algorithms through the process of top-down, stepwise refinement.
- To use the `if` selection statement and the `if...else` selection statement to select actions.
- To use the `while` repetition statement to execute statements in a program repeatedly.
- Counter-controlled repetition and sentinel-controlled repetition.
- Structured programming.
- The increment, decrement and assignment operators.



- | | |
|---|---|
| 3.1 Introduction | 3.9 Formulating Algorithms with Top-Down, Stepwise Refinement Case Study 2: Sentinel-Controlled Repetition |
| 3.2 Algorithms | 3.10 Formulating Algorithms with Top-Down, Stepwise Refinement Case Study 3: Nested Control Structures |
| 3.3 Pseudocode | 3.11 Assignment Operators |
| 3.4 Control Structures | 3.12 Increment and Decrement Operators |
| 3.5 The <code>if</code> Selection Statement | |
| 3.6 The <code>if...else</code> Selection Statement | |
| 3.7 The <code>while</code> Repetition Statement | |
| 3.8 Formulating Algorithms Case Study 1: Counter-Controlled Repetition | |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

3.1 Introduction

Before writing a program to solve a particular problem, it's essential to have a thorough understanding of the problem and a carefully planned approach to solving the problem. The next two chapters discuss techniques that facilitate the development of structured computer programs. In Section 4.12, we present a summary of structured programming that ties together the techniques developed here and in Chapter 4.

3.2 Algorithms

The solution to any computing problem involves executing a series of actions in a specific order. A **procedure** for solving a problem in terms of

1. the **actions** to be executed, and
2. the **order** in which these actions are to be executed

is called an **algorithm**. The following example demonstrates that correctly specifying the order in which the actions are to be executed is important.

Consider the “rise-and-shine algorithm” followed by one junior executive for getting out of bed and going to work: Consider the “rise-and-shine algorithm” followed by one junior executive for getting out of bed and going to work: (1) Get out of bed, (2) take off pajamas, (3) take a shower, (4) get dressed, (5) eat breakfast, (6) carpool to work. This routine gets the executive to work well prepared to make critical decisions. Suppose that the same steps are performed in a slightly different order: (1) Get out of bed, (2) take off pajamas, (3) get dressed, (4) take a shower, (5) eat breakfast, (6) carpool to work. In this case, our junior executive shows up for work soaking wet. Specifying the order in which statements are to be executed in a computer program is called **program control**. In this and the next chapter, we investigate the program control capabilities of C.

3.3 Pseudocode

Pseudocode is an artificial and informal language that helps you develop algorithms. The pseudocode we present here is particularly useful for developing algorithms that will be converted to structured C programs. Pseudocode is similar to everyday English; it's convenient and user friendly although it's not an actual computer programming language.

Pseudocode programs are not executed on computers. Rather, they merely help you “think out” a program before attempting to write it in a programming language such as C. In this chapter, we give several examples of how pseudocode may be used effectively in developing structured C programs.

Pseudocode consists purely of characters, so you may conveniently type pseudocode programs into a computer using an editor program. The computer can display or print a fresh copy of a pseudocode program on demand. A carefully prepared pseudocode program may be converted easily to a corresponding C program. This is done in many cases simply by replacing pseudocode statements with their C equivalents.

Pseudocode consists only of action statements—those that are executed when the program has been converted from pseudocode to C and is run in C. Definitions are not executable statements. They’re messages to the compiler. For example, the definition

```
int i;
```

simply tells the compiler the type of variable `i` and instructs the compiler to reserve space in memory for the variable. But this definition does not cause any action—such as input, output, or a calculation—to occur when the program is executed. Some programmers choose to list each variable and briefly mention the purpose of each at the beginning of a pseudocode program.

3.4 Control Structures

Normally, statements in a program are executed one after the other in the order in which they’re written. This is called **sequential execution**. Various C statements we’ll soon discuss enable you to specify that the next statement to be executed may be other than the next one in sequence. This is called **transfer of control**.

During the 1960s, it became clear that the indiscriminate use of transfers of control was the root of a great deal of difficulty experienced by software development groups. The finger of blame was pointed at the **goto statement** that allows programmers to specify a transfer of control to one of many possible destinations in a program. The notion of so-called structured programming became almost synonymous with “**goto elimination**.”

The research of Bohm and Jacopini¹ had demonstrated that programs could be written without any goto statements. The challenge of the era was for programmers to shift their styles to “goto-less programming.” It was not until well into the 1970s that the programming profession started taking structured programming seriously. The results were impressive, as software development groups reported reduced development times, more frequent on-time delivery of systems and more frequent within-budget completion of software projects. Programs produced with structured techniques were clearer, easier to debug and modify and more likely to be bug free in the first place.

Bohm and Jacopini’s work demonstrated that all programs could be written in terms of only three **control structures**, namely the **sequence structure**, the **selection structure** and the **repetition structure**. The sequence structure is built into C. Unless directed otherwise, the computer executes C statements one after the other in the order in which they’re written. The **flowchart** segment of Fig. 3.1 illustrates C’s sequence structure.

1. Bohm, C., and G. Jacopini, “Flow Diagrams, Turing Machines, and Languages with Only Two Formation Rules,” *Communications of the ACM*, Vol. 9, No. 5, May 1966, pp. 336–371.

A flowchart is a graphical representation of an algorithm or of a portion of an algorithm. Flowcharts are drawn using certain special-purpose symbols such as rectangles, diamonds, ovals, and small circles; these symbols are connected by arrows called **flowlines**.

Like pseudocode, flowcharts are useful for developing and representing algorithms, although pseudocode is preferred by most programmers. Flowcharts clearly show how control structures operate; that is all we use them for in this text.

Consider the flowchart for the sequence structure in Fig. 3.1. We use the **rectangle symbol**, also called the **action symbol**, to indicate any type of action including a calculation or an input/output operation. The flowlines in the figure indicate the order in which the actions are performed—first, grade is added to total, then 1 is added to counter. C allows us to have as many actions as we want in a sequence structure. As we'll soon see, anywhere a single action may be placed, we may place several actions in sequence.




Fig. 3.1 | Flowcharting C's sequence structure.

When drawing a flowchart that represents a complete algorithm, an **oval symbol** containing the word “Begin” is the first symbol used in the flowchart; an oval symbol containing the word “End” is the last symbol used. When drawing only a portion of an algorithm as in Fig. 3.1, the oval symbols are omitted in favor of using **small circle symbols**, also called **connector symbols**.

Perhaps the most important flowcharting symbol is the **diamond symbol**, also called the **decision symbol**, which indicates that a decision is to be made. We'll discuss the diamond symbol in the next section.

C provides three types of selection structures in the form of statements. The **if** selection statement (Section 3.5) either performs (selects) an action if a condition is true or skips the action if the condition is false. The **if...else** selection statement (Section 3.6) performs an action if a condition is true and performs a different action if the condition is false. The **switch** selection statement (discussed in Chapter 4) performs one of many different actions depending on the value of an expression. The **if** statement is called a **single-selection statement** because it selects or ignores a single action. The **if...else** statement is called a **double-selection statement** because it selects between two different actions. The **switch** statement is called a **multiple-selection statement** because it selects among many different actions.

C provides three types of repetition structures in the form of statements, namely **while** (Section 3.7), **do...while**, and **for** (both discussed in Chapter 4).

That is all there is. C has only seven control statements: sequence, three types of selection and three types of repetition. Each C program is formed by combining as many of each type of control statement as is appropriate for the algorithm the program implements. As with the sequence structure of Fig. 3.1, we'll see that the flowchart representation of each control statement has two small circle symbols, one at the entry point to the control statement and one at the exit point. These **single-entry/single-exit control statements** make it easy to build programs. The control-statement flowchart segments can be attached to one another by connecting the exit point of one control statement to the entry point of the next. This is much like the way in which a child stacks building blocks, so we call this **control-statement stacking**. We'll learn that there is only one other way control statements may be connected—a method called control-statement nesting. Thus, any C program we'll ever need to build can be constructed from only seven different types of control statements combined in only two ways. This is the essence of simplicity.

3.5 The `if` Selection Statement

Selection structures are used to choose among alternative courses of action. For example, suppose the passing grade on an exam is 60. The pseudocode statement

*If student's grade is greater than or equal to 60
Print "Passed"*

determines if the condition “student's grade is greater than or equal to 60” is true or false. If the condition is true, then “Passed” is printed, and the next pseudocode statement in order is “performed” (remember that pseudocode is not a real programming language). If the condition is false, the printing is ignored, and the next pseudocode statement in order is performed. The second line of this selection structure is indented. Such indentation is optional, but it's highly recommended as it helps emphasize the inherent structure of structured programs. We'll apply indentation conventions carefully throughout this text. The C compiler ignores **white-space characters** like blanks, tabs and newlines used for indentation and vertical spacing.



Good Programming Practice 3.1

Consistently applying responsible indentation conventions greatly improves program readability. We suggest a fixed-size tab of about 1/4 inch or three blanks per indent. In this book, we use three blanks per indent.

The preceding pseudocode *If* statement may be written in C as

```
if ( grade >= 60 ) {
    printf( "Passed\n" );
} /* end if */
```

Notice that the C code corresponds closely to the pseudocode. This is one of the properties of pseudocode that makes it such a useful program development tool.



Good Programming Practice 3.2

Pseudocode is often used to “think out” a program during the program design process. Then the pseudocode program is converted to C.

The flowchart of Fig. 3.2 illustrates the single-selection if statement. This flowchart contains what is perhaps the most important flowcharting symbol—the diamond symbol, also called the decision symbol, which indicates that a decision is to be made. The decision symbol contains an expression, such as a condition, that can be either true or false. The decision symbol has two flowlines emerging from it. One indicates the direction to take when the expression in the symbol is true; the other indicates the direction to take when the expression is false. Decisions can be based on conditions containing relational or equality operators. In fact, a decision can be based on any expression—if the expression evaluates to zero, it's treated as false, and if it evaluates to nonzero, it's treated as true.




Fig. 3.2 | Flowcharting the single-selection if statement.

The if statement, too, is a single-entry/single-exit structure. We'll soon learn that the flowcharts for the remaining control structures can also contain (besides small circle symbols and flowlines) only rectangle symbols to indicate the actions to be performed, and diamond symbols to indicate decisions to be made. This is the action/decision model of programming we've been emphasizing.

We can envision seven bins, each containing only control-statement flowcharts of one of the seven types. These flowchart segments are empty—nothing is written in the rectangles and nothing is written in the diamonds. Your task, then, is assembling a program from as many of each type of control statement as the algorithm demands, combining those control statements in only two possible ways (stacking or nesting), and then filling in the actions and decisions in a manner appropriate for the algorithm. We'll discuss the variety of ways in which actions and decisions may be written.

3.6 The if...else Selection Statement

The if selection statement performs an indicated action only when the condition is true; otherwise the action is skipped. The if...else selection statement allows you to specify that different actions are to be performed when the condition is true than when the condition is false. For example, the pseudocode statement

```

If student's grade is greater than or equal to 60
    Print "Passed"
else
    Print "Failed"
  
```

prints *Passed* if the student's grade is greater than or equal to 60 and prints *Failed* if the student's grade is less than 60. In either case, after printing occurs, the next pseudocode

statement in sequence is “performed.” The body of the *else* is also indented. Whatever indentation convention you choose should be carefully applied throughout your programs. It’s difficult to read a program that does not obey uniform spacing conventions.



Good Programming Practice 3.3

Indent both body statements of an if...else statement.



Good Programming Practice 3.4

If there are several levels of indentation, each level should be indented the same additional amount of space.

The preceding pseudocode *If...else* statement may be written in C as

```
if ( grade >= 60 ) {
    printf( "Passed\n" );
} /* end if */
else {
    printf( "Failed\n" );
} /* end else */
```

The flowchart of Fig. 3.3 nicely illustrates the flow of control in the *if...else* statement. Once again, note that (besides small circles and arrows) the only symbols in the flowchart are rectangles (for actions) and a diamond (for a decision). We continue to emphasize this action/decision model of computing. Imagine again a deep bin containing as many empty double-selection statements (represented as flowchart segments) as might be needed to build any C program. Your job, again, is to assemble these selection statements (by stacking and nesting) with any other control statements required by the algorithm, and to fill in the empty rectangles and empty diamonds with actions and decisions appropriate to the algorithm being implemented.




Fig. 3.3 | Flowcharting the double-selection *if...else* statement.

C provides the **conditional operator** (`?:`) which is closely related to the *if...else* statement. The conditional operator is C’s only ternary operator—it takes three operands. The operands together with the conditional operator form a **conditional expression**. The first operand is a condition. The second operand is the value for the entire conditional expression if the condition is true and the third operand is the value for the entire conditional expression if the condition is false. For example, the `printf` statement

```
printf( "%s\n", grade >= 60 ? "Passed" : "Failed" );
```

contains a conditional expression that evaluates to the string literal "Passed" if the condition `grade >= 60` is true and evaluates to the string literal "Failed" if the condition is false. The format control string of the `printf` contains the conversion specification `%s` for printing a character string. So the preceding `printf` statement performs in essentially the same way as the preceding `if...else` statement.

The second and third operands in a conditional expression can also be actions to be executed. For example, the conditional expression

```
grade >= 60 ? printf( "Passed\n" ) : printf( "Failed\n" );
```

is read, "If grade is greater than or equal to 60 then `printf("Passed\n")`, otherwise `printf("Failed\n")`." This, too, is comparable to the preceding `if...else` statement. We'll see that conditional operators can be used in some situations where `if...else` statements cannot.

Nested if...else statements test for multiple cases by placing `if...else` statements inside `if...else` statements. For example, the following pseudocode statement will print A for exam grades greater than or equal to 90, B for grades greater than or equal to 80, C for grades greater than or equal to 70, D for grades greater than or equal to 60, and F for all other grades.

```
If student's grade is greater than or equal to 90
    Print "A"
else
    If student's grade is greater than or equal to 80
        Print "B"
    else
        If student's grade is greater than or equal to 70
            Print "C"
        else
            If student's grade is greater than or equal to 60
                Print "D"
            else
                Print "F"
```

This pseudocode may be written in C as

```
if ( grade >= 90 )
    printf( "A\n" );
else
    if ( grade >= 80 )
        printf("B\n");
    else
        if ( grade >= 70 )
            printf("C\n");
        else
            if ( grade >= 60 )
                printf( "D\n" );
            else
                printf( "F\n" );
```


If the variable `grade` is greater than or equal to 90, the first four conditions will be true, but only the `printf` statement after the first test will be executed. After that `printf` is executed, the `else` part of the “outer” `if...else` statement is skipped. Many C programmers prefer to write the preceding `if` statement as

```
if ( grade >= 90 )
    printf( "A\n" );
else if ( grade >= 80 )
    printf( "B\n" );
else if ( grade >= 70 )
    printf( "C\n" );
else if ( grade >= 60 )
    printf( "D\n" );
else
    printf( "F\n" );
```

As far as the C compiler is concerned, both forms are equivalent. The latter form is popular because it avoids the deep indentation of the code to the right. Such indentation often leaves little room on a line, forcing lines to be split and decreasing program readability.

The `if` selection statement expects only one statement in its body. To include several statements in the body of an `if`, enclose the set of statements in braces (`{` and `}`). A set of statements contained within a pair of braces is called a **compound statement** or a **block**.



Software Engineering Observation 3.1

A compound statement can be placed anywhere in a program that a single statement can be placed.

The following example includes a compound statement in the `else` part of an `if...else` statement.

```
if ( grade >= 60 ) {
    printf( "Passed.\n" );
} /* end if */
else {
    printf( "Failed.\n" );
    printf( "You must take this course again.\n" );
} /* end else */
```

In this case, if `grade` is less than 60, the program executes both `printf` statements in the body of the `else` and prints

```
Failed.
You must take this course again.
```

Notice the braces surrounding the two statements in the `else` clause. These braces are important. Without the braces, the statement

```
printf( "You must take this course again.\n" );
```

would be outside the body of the `else` part of the `if`, and would execute regardless of whether the `grade` was less than 60.



Common Programming Error 3.1

Forgetting one or both of the braces that delimit a compound statement.

A syntax error is caught by the compiler. A logic error has its effect at execution time. A fatal logic error causes a program to fail and terminate prematurely. A nonfatal logic error allows a program to continue executing but to produce incorrect results.



Software Engineering Observation 3.2

Just as a compound statement can be placed anywhere a single statement can be placed, it's also possible to have no statement at all, i.e., the empty statement. The empty statement is represented by placing a semicolon (;) where a statement would normally be.



Common Programming Error 3.2

Placing a semicolon after the condition in an if statement as in `if ( grade >= 60 );` leads to a logic error in single-selection if statements and a syntax error in double-selection if statements.



Error-Prevention Tip 3.1

Typing the beginning and ending braces of compound statements before typing the individual statements within the braces helps avoid omitting one or both of the braces, preventing syntax errors and logic errors (where both braces are indeed required).

3.7 The while Repetition Statement

A **repetition statement** allows you to specify that an action is to be repeated while some condition remains true. The pseudocode statement

*While there are more items on my shopping list
Purchase next item and cross it off my list*

describes the repetition that occurs during a shopping trip. The condition, “there are more items on my shopping list” may be true or false. If it’s true, then the action, “Purchase next item and cross it off my list” is performed. This action will be performed repeatedly while the condition remains true. The statement(s) contained in the *while* repetition statement constitute the body of the *while*. The *while* statement body may be a single statement or a compound statement.

Eventually, the condition will become false (when the last item on the shopping list has been purchased and crossed off the list). At this point, the repetition terminates, and the first pseudocode statement after the repetition structure is executed.



Common Programming Error 3.3

Not providing the body of a while statement with an action that eventually causes the condition in the while to become false. Normally, such a repetition structure will never terminate—an error called an “infinite loop.”



Common Programming Error 3.4

Spelling the keyword while with an uppercase W as in While (remember that C is a case-sensitive language). All of C’s reserved keywords such as while, if and else contain only lowercase letters.

As an example of an actual **while**, consider a program segment designed to find the first power of 3 larger than 100. Suppose the integer variable `product` has been initialized

to 3. When the following `while` repetition statement finishes executing, `product` will contain the desired answer:

```
product = 3;
while ( product <= 100 ) {
    product = 3 * product;
} /* end while */
```

The flowchart of Fig. 3.4 nicely illustrates the flow of control in the `while` repetition statement. Once again, note that (besides small circles and arrows) the flowchart contains only a rectangle symbol and a diamond symbol. The flowchart clearly shows the repetition. The flowline emerging from the rectangle wraps back to the decision, which is tested each time through the loop until the decision eventually becomes false. At this point, the `while` statement is exited and control passes to the next statement in the program.




Fig. 3.4 | Flowcharting the `while` repetition statement.

When the `while` statement is entered, the value of `product` is 3. The variable `product` is repeatedly multiplied by 3, taking on the values 9, 27 and 81 successively. When `product` becomes 243, the condition in the `while` statement, `product <= 100`, becomes false. This terminates the repetition, and the final value of `product` is 243. Program execution continues with the next statement after the `while`.

3.8 Formulating Algorithms Case Study I: Counter-Controlled Repetition

To illustrate how algorithms are developed, we solve several variations of a class averaging problem. Consider the following problem statement:

A class of ten students took a quiz. The grades (integers in the range 0 to 100) for this quiz are available to you. Determine the class average on the quiz.

The class average is equal to the sum of the grades divided by the number of students. The algorithm for solving this problem on a computer must input each of the grades, perform the averaging calculation, and print the result.

Let's use pseudocode to list the actions to execute and specify the order in which these actions should execute. We use **counter-controlled repetition** to input the grades one at a time. This technique uses a variable called a **counter** to specify the number of times a set of statements should execute. In this example, repetition terminates when the counter exceeds 10. In this section we simply present the pseudocode algorithm (Fig. 3.5) and the corresponding C program (Fig. 3.6). In the next section we show how pseudocode algo-

gorithms are developed. Counter-controlled repetition is often called **definite repetition** because the number of repetitions is known before the loop begins executing.

```

1  Set total to zero
2  Set grade counter to one
3
4  While grade counter is less than or equal to ten
5      Input the next grade
6      Add the grade into the total
7      Add one to the grade counter
8
9  Set the class average to the total divided by ten
10 Print the class average

```

Fig. 3.5 | Pseudocode algorithm that uses counter-controlled repetition to solve the class average problem.

```

1  /* Fig. 3.6: fig03_06.c
2     Class average program with counter-controlled repetition */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8      int counter; /* number of grade to be entered next */
9      int grade; /* grade value */
10     int total; /* sum of grades input by user */
11     int average; /* average of grades */
12
13     /* initialization phase */
14     total = 0; /* initialize total */
15     counter = 1; /* initialize loop counter */
16
17     /* processing phase */
18     while ( counter <= 10 ) { /* loop 10 times */
19         printf( "Enter grade: " ); /* prompt for input */
20         scanf( "%d", &grade ); /* read grade from user */
21         total = total + grade; /* add grade to total */
22         counter = counter + 1; /* increment counter */
23     } /* end while */
24
25     /* termination phase */
26     average = total / 10; /* integer division */
27
28     printf( "Class average is %d\n", average ); /* display result */
29     return 0; /* indicate program ended successfully */
30 } /* end function main */

```

Fig. 3.6 | C program and sample execution for the class average problem with counter-controlled repetition. (Part I of 2.)

```

Enter grade: 98
Enter grade: 76
Enter grade: 71
Enter grade: 87
Enter grade: 83
Enter grade: 90
Enter grade: 57
Enter grade: 79
Enter grade: 82
Enter grade: 94
Class average is 81

```

Fig. 3.6 | C program and sample execution for the class average problem with counter-controlled repetition. (Part 2 of 2.)

Note the references in the algorithm to a total and a counter. A **total** is a variable used to accumulate the sum of a series of values. A counter is a variable used to count—in this case, to count the number of grades entered. Variables used to store totals should normally be initialized to zero before being used in a program; otherwise the sum would include the previous value stored in the total’s memory location. Counter variables are normally initialized to zero or one, depending on their use (we’ll present examples showing each of these uses). An uninitialized variable contains a “garbage” value—the value last stored in the memory location reserved for that variable.



Common Programming Error 3.5

If a counter or total is not initialized, the results of your program will probably be incorrect. This is an example of a logic error.



Error-Prevention Tip 3.2

Initialize all counters and totals.

The averaging calculation in the program produced an integer result of 81. Actually, the sum of the grades in this example is 817, which when divided by 10 should yield 81.7, i.e., a number with a decimal point. We’ll see how to deal with such numbers (called floating-point numbers) in the next section.

3.9 Formulating Algorithms with Top-Down, Stepwise Refinement Case Study 2: Sentinel-Controlled Repetition

Let’s generalize the class average problem. Consider the following problem:

Develop a class averaging program that will process an arbitrary number of grades each time the program is run.

In the first class average example, the number of grades (10) was known in advance. In this example, no indication is given of how many grades are to be entered. The program must process an arbitrary number of grades. How can the program determine when to stop the input of grades? How will it know when to calculate and print the class average?

One way to solve this problem is to use a special value called a **sentinel value** (also called a **signal value**, a **dummy value**, or a **flag value**) to indicate “end of data entry.” The user types in grades until all legitimate grades have been entered. The user then types the sentinel value to indicate that the last grade has been entered. Sentinel-controlled repetition is often called **indefinite repetition** because the number of repetitions is not known before the loop begins executing.

Clearly, the sentinel value must be chosen so that it cannot be confused with an acceptable input value. Since grades on a quiz are normally nonnegative integers, -1 is an acceptable sentinel value for this problem. Thus, a run of the class average program might process a stream of inputs such as 95, 96, 75, 74, 89 and -1 . The program would then compute and print the class average for the grades 95, 96, 75, 74, and 89 (-1 is the sentinel value, so it should not enter into the averaging calculation).



Common Programming Error 3.6

Choosing a sentinel value that is also a legitimate data value.

We approach the class average program with a technique called **top-down, stepwise refinement**, a technique that is essential to the development of well-structured programs. We begin with a pseudocode representation of the **top**:

Determine the class average for the quiz

The top is a single statement that conveys the program’s overall function. As such, the top is, in effect, a complete representation of a program. Unfortunately, the top rarely conveys a sufficient amount of detail for writing the C program. So we now begin the refinement process. We divide the top into a series of smaller tasks and list these in the order in which they need to be performed. This results in the following **first refinement**.

Initialize variables

Input, sum, and count the quiz grades

Calculate and print the class average

Here, only the sequence structure has been used—the steps listed are to be executed in order, one after the other.



Software Engineering Observation 3.3

Each refinement, as well as the top itself, is a complete specification of the algorithm; only the level of detail varies.

To proceed to the next level of refinement, i.e., the **second refinement**, we commit to specific variables. We need a running total of the numbers, a count of how many numbers have been processed, a variable to receive the value of each grade as it’s input and a variable to hold the calculated average. The pseudocode statement

Initialize variables

may be refined as follows:

Initialize total to zero

Initialize counter to zero

Notice that only `total` and `counter` need to be initialized; the variables `average` and `grade` (for the calculated average and the user input, respectively) need not be initialized because their values will be written over by the process of destructive read-in discussed in Chapter 2. The pseudocode statement

Input, sum, and count the quiz grades

requires a repetition structure (i.e., a loop) that successively inputs each grade. Since we do not know in advance how many grades are to be processed, we'll use sentinel-controlled repetition. The user will type legitimate grades in one at a time. After the last legitimate grade is typed, the user will type the sentinel value. The program will test for this value after each grade is input and will terminate the loop when the sentinel is entered. The refinement of the preceding pseudocode statement is then

Input the first grade
While the user has not as yet entered the sentinel
 Add this grade into the running total
 Add one to the grade counter
 Input the next grade (possibly the sentinel)

Notice that in pseudocode, we do not use braces around the set of statements that form the body of the *while* statement. We simply indent all these statements under the *while* to show that they all belong to the *while*. Again, pseudocode is only an informal program development aid.

The pseudocode statement

Calculate and print the class average

may be refined as follows:

If the counter is not equal to zero
 Set the average to the total divided by the counter
 Print the average
else
 Print "No grades were entered"

Notice that we're being careful here to test for the possibility of division by zero—a **fatal error** that if undetected would cause the program to fail (often called “**bombing**” or “**crashing**”). The complete second refinement is shown in Fig. 3.7.



Common Programming Error 3.7

An attempt to divide by zero causes a fatal error.



Good Programming Practice 3.5

When performing division by an expression whose value could be zero, explicitly test for this case and handle it appropriately in your program (such as printing an error message) rather than allowing the fatal error to occur.

In Fig. 3.5 and Fig. 3.7, we include some completely blank lines in the pseudocode for readability. Actually, the blank lines separate these programs into their various phases.

```

1  Initialize total to zero
2  Initialize counter to zero
3
4  Input the first grade
5  While the user has not as yet entered the sentinel
6      Add this grade into the running total
7      Add one to the grade counter
8      Input the next grade (possibly the sentinel)
9
10 If the counter is not equal to zero
11     Set the average to the total divided by the counter
12     Print the average
13 else
14     Print "No grades were entered"

```

Fig. 3.7 | Pseudocode algorithm that uses sentinel-controlled repetition to solve the class average problem.



Software Engineering Observation 3.4

Many programs can be divided logically into three phases: an initialization phase that initializes the program variables; a processing phase that inputs data values and adjusts program variables accordingly; and a termination phase that calculates and prints the final results.

The pseudocode algorithm in Fig. 3.7 solves the more general class averaging problem. This algorithm was developed after only two levels of refinement. Sometimes more levels are necessary.



Software Engineering Observation 3.5

You terminate the top-down, stepwise refinement process when the pseudocode algorithm is specified in sufficient detail for you to be able to convert the pseudocode to C. Implementing the C program is then normally straightforward.

The C program and a sample execution are shown in Fig. 3.8. Although only integer grades are entered, the averaging calculation is likely to produce a decimal number with a decimal point. The type `int` cannot represent such a number. The program introduces the data type **float** to handle numbers with decimal points (called **floating-point numbers**) and introduces a special operator called a cast operator to handle the averaging calculation. These features are explained in detail after the program is presented.

```

1  /* Fig. 3.8: fig03_08.c
2     Class average program with sentinel-controlled repetition */
3  #include <stdio.h>
4

```

Fig. 3.8 | C program and sample execution for the class average problem with sentinel-controlled repetition. (Part I of 3.)


```

5  /* function main begins program execution */
6  int main( void )
7  {
8      int counter; /* number of grades entered */
9      int grade; /* grade value */
10     int total; /* sum of grades */
11
12     float average; /* number with decimal point for average */
13
14     /* initialization phase */
15     total = 0; /* initialize total */
16     counter = 0; /* initialize loop counter */
17
18     /* processing phase */
19     /* get first grade from user */
20     printf( "Enter grade, -1 to end: " ); /* prompt for input */
21     scanf( "%d", &grade ); /* read grade from user */
22
23     /* loop while sentinel value not yet read from user */
24     while ( grade != -1 ) {
25         total = total + grade; /* add grade to total */
26         counter = counter + 1; /* increment counter */
27
28         /* get next grade from user */
29         printf( "Enter grade, -1 to end: " ); /* prompt for input */
30         scanf( "%d", &grade ); /* read next grade */
31     } /* end while */
32
33     /* termination phase */
34     /* if user entered at least one grade */
35     if ( counter != 0 ) {
36
37         /* calculate average of all grades entered */
38         average = ( float ) total / counter; /* avoid truncation */
39
40         /* display average with two digits of precision */
41         printf( "Class average is %.2f\n", average );
42     } /* end if */
43     else { /* if no grades were entered, output message */
44         printf( "No grades were entered\n" );
45     } /* end else */
46
47     return 0; /* indicate program ended successfully */
48 } /* end function main */

```

```

Enter grade, -1 to end: 75
Enter grade, -1 to end: 94
Enter grade, -1 to end: 97
Enter grade, -1 to end: 88
Enter grade, -1 to end: 70
Enter grade, -1 to end: 64

```

Fig. 3.8 | C program and sample execution for the class average problem with sentinel-controlled repetition. (Part 2 of 3.)

```
Enter grade, -1 to end: 83
Enter grade, -1 to end: 89
Enter grade, -1 to end: -1
Class average is 82.50
```

```
Enter grade, -1 to end: -1
No grades were entered
```

Fig. 3.8 | C program and sample execution for the class average problem with sentinel-controlled repetition. (Part 3 of 3.)

Notice the compound statement in the `while` loop (line 24) in Fig. 3.8. Once again, the braces are necessary for all four statements to be executed within the loop. Without the braces, the last three statements in the body of the loop would fall outside the loop, causing the computer to interpret this code incorrectly as follows.

```
while ( grade != -1 )
    total = total + grade; /* add grade to total */
    counter = counter + 1; /* increment counter */
    printf( "Enter grade, -1 to end: " ); /* prompt for input */
    scanf( "%d", &grade ); /* read next grade */
```

This would cause an infinite loop if the user did not input -1 for the first grade.



Good Programming Practice 3.6

In a sentinel-controlled loop, the prompts requesting data entry should explicitly remind the user what the sentinel value is.

Averages do not always evaluate to integer values. Often, an average is a value such as 7.2 or -93.5 that contains a fractional part. These values are referred to as floating-point numbers and are represented by the data type `float`. The variable `average` is defined to be of type `float` (line 12) to capture the fractional result of our calculation. However, the result of the calculation `total / counter` is an integer because `total` and `counter` are both integer variables. Dividing two integers results in **integer division** in which any fractional part of the calculation is lost (i.e., **truncated**). Since the calculation is performed first, the fractional part is lost before the result is assigned to `average`. To produce a floating-point calculation with integer values, we must create temporary values that are floating-point numbers. C provides the unary **cast operator** to accomplish this task. Line 38

```
average = ( float ) total / counter;
```

includes the cast operator (`float`), which creates a temporary floating-point copy of its operand, `total`. The value stored in `total` is still an integer. Using a cast operator in this manner is called **explicit conversion**. The calculation now consists of a floating-point value (the temporary `float` version of `total`) divided by the integer value stored in `counter`. Most computers can evaluate arithmetic expressions only in which the data types of the operands are identical. To ensure that the operands are of the same type, the compiler performs an operation called **promotion** (also called **implicit conversion**) on selected oper-

ands. For example, in an expression containing the data types `int` and `float`, copies of `int` operands are made and promoted to `float`. In our example, after a copy of `counter` is made and promoted to `float`, the calculation is performed and the result of the floating-point division is assigned to `average`. C provides a set of rules for promotion of operands of different types. Chapter 5 presents a discussion of all the standard data types and their order of promotion.

Cast operators are available for most data types. The cast operator is formed by placing parentheses around a data type name. The cast operator is a **unary operator**, i.e., an operator that takes only one operand. In Chapter 2, we studied the binary arithmetic operators. C also supports unary versions of the plus (+) and minus (-) operators, so you can write expressions like `-7` or `+5`. Cast operators associate from right to left and have the same precedence as other unary operators such as unary + and unary -. This precedence is one level higher than that of the **multiplicative operators** `*`, `/` and `%`.

Figure 3.8 uses the `printf` conversion specifier `%.2f` (line 41) to print the value of `average`. The `f` specifies that a floating-point value will be printed. The `.2` is the **precision** with which the value will be displayed—with 2 digits to the right of the decimal point. If the `%f` conversion specifier is used (without specifying the precision), the **default precision** of 6 is used—exactly as if the conversion specifier `%.6f` had been used. When floating-point values are printed with precision, the printed value is **rounded** to the indicated number of decimal positions. The value in memory is unaltered. When the following statements are executed, the values 3.45 and 3.4 are printed.

```
printf( "%.2f\n", 3.446 ); /* prints 3.45 */
printf( "%.1f\n", 3.446 ); /* prints 3.4  */
```



Common Programming Error 3.8

Using precision in a conversion specification in the format control string of a `scanf` statement is wrong. Precisions are used only in `printf` conversion specifications.



Common Programming Error 3.9

Using floating-point numbers in a manner that assumes they're represented precisely can lead to incorrect results. Floating-point numbers are represented only approximately by most computers.



Error-Prevention Tip 3.3

Do not compare floating-point values for equality.

Despite the fact that floating-point numbers are not always “100% precise,” they have numerous applications. For example, when we speak of a “normal” body temperature of 98.6, we do not need to be precise to a large number of digits. When we view the temperature on a thermometer and read it as 98.6, it may actually be 98.5999473210643. The point here is that calling this number simply 98.6 is fine for most applications. We'll say more about this issue later.

Another way floating-point numbers develop is through division. When we divide 10 by 3, the result is 3.333333... with the sequence of 3s repeating infinitely. The computer allocates only a fixed amount of space to hold such a value, so clearly the stored floating-point value can be only an approximation.

3.10 Formulating Algorithms with Top-Down, Stepwise Refinement Case Study 3: Nested Control Structures

Let's work another complete problem. We'll once again formulate the algorithm using pseudocode and top-down, stepwise refinement, and write a corresponding C program. We've seen that control statements may be stacked on top of one another (in sequence) just as a child stacks building blocks. In this case study we'll see the only other structured way control statements may be connected in C, namely through **nesting** of one control statement within another.

Consider the following problem statement:

A college offers a course that prepares students for the state licensing exam for real estate brokers. Last year, 10 of the students who completed this course took the licensing examination. Naturally, the college wants to know how well its students did on the exam. You have been asked to write a program to summarize the results. You have been given a list of these 10 students. Next to each name a 1 is written if the student passed the exam and a 2 if the student failed.

Your program should analyze the results of the exam as follows:

1. *Input each test result (i.e., a 1 or a 2). Display the prompting message "Enter result" each time the program requests another test result.*
2. *Count the number of test results of each type.*
3. *Display a summary of the test results indicating the number of students who passed and the number who failed.*
4. *If more than eight students passed the exam, print the message "Bonus to instructor!"*

After reading the problem statement carefully, we make the following observations:

1. The program must process 10 test results. A counter-controlled loop will be used.
2. Each test result is a number—either a 1 or a 2. Each time the program reads a test result, the program must determine if the number is a 1 or a 2. We test for a 1 in our algorithm. If the number is not a 1, we assume that it's a 2. (An exercise at the end of the chapter considers the consequences of this assumption.)
3. Two counters are used—one to count the number of students who passed the exam and one to count the number of students who failed the exam.
4. After the program has processed all the results, it must decide if more than 8 students passed the exam.

Let's proceed with top-down, stepwise refinement. We begin with a pseudocode representation of the top:

Analyze exam results and decide if instructor should receive a bonus

Once again, it's important to emphasize that the top is a complete representation of the program, but several refinements are likely to be needed before the pseudocode can be naturally evolved into a C program. Our first refinement is

Initialize variables

Input the ten quiz grades and count passes and failures

Print a summary of the exam results and decide if instructor should receive a bonus

Here, too, even though we have a complete representation of the entire program, further refinement is necessary. We now commit to specific variables. Counters are needed to record the passes and failures, a counter will be used to control the looping process, and a variable is needed to store the user input. The pseudocode statement

Initialize variables

may be refined as follows:

Initialize passes to zero
Initialize failures to zero
Initialize student to one

Notice that only the counters and totals are initialized. The pseudocode statement

Input the ten quiz grades and count passes and failures

requires a loop that successively inputs the result of each exam. Here it's known in advance that there are precisely ten exam results, so counter-controlled looping is appropriate. Inside the loop (i.e., **nested** within the loop) a double-selection statement will determine whether each exam result is a pass or a failure, and will increment the appropriate counters accordingly. The refinement of the preceding pseudocode statement is then

While student counter is less than or equal to ten
 Input the next exam result

 If the student passed
 Add one to passes
 else
 Add one to failures

 Add one to student counter

Notice the use of blank lines to set off the *If...else* to improve program readability. The pseudocode statement

Print a summary of the exam results and decide if instructor should receive a bonus

may be refined as follows:

Print the number of passes
Print the number of failures
If more than eight students passed
 Print "Bonus to instructor!"

The complete second refinement appears in Fig. 3.9. Notice that blank lines are also used to set off the **while** statement for program readability.

This pseudocode is now sufficiently refined for conversion to C. The C program and two sample executions are shown in Fig. 3.10. We've taken advantage of a feature of C that allows initialization to be incorporated into definitions. Such initialization occurs at compile time.

```

1  Initialize passes to zero
2  Initialize failures to zero
3  Initialize student to one
4
5  While student counter is less than or equal to ten
6      Input the next exam result
7
8      If the student passed
9          Add one to passes
10     else
11         Add one to failures
12
13     Add one to student counter
14
15 Print the number of passes
16 Print the number of failures
17 If more than eight students passed
18     Print "Bonus to instructor!"

```

Fig. 3.9 | Pseudocode for examination results problem.



Performance Tip 3.1

Initializing variables when they're defined can help reduce a program's execution time.



Performance Tip 3.2

Many of the performance tips we mention in this text result in nominal improvements, so the reader may be tempted to ignore them. The cumulative effect of all these performance enhancements can make a program perform significantly faster. Also, significant improvement is realized when a supposedly nominal improvement is placed in a loop that may repeat a large number of times.

```

1  /* Fig. 3.10: fig03_10.c
2     Analysis of examination results */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8      /* initialize variables in definitions */
9      int passes = 0; /* number of passes */
10     int failures = 0; /* number of failures */
11     int student = 1; /* student counter */
12     int result; /* one exam result */
13

```

Fig. 3.10 | C program and sample executions for examination results problem. (Part I of 3.)

```

14  /* process 10 students using counter-controlled loop */
15  while ( student <= 10 ) {
16
17      /* prompt user for input and obtain value from user */
18      printf( "Enter result ( 1=pass,2=fail ): " );
19      scanf( "%d", &result );
20
21      /* if result 1, increment passes */
22      if ( result == 1 ) {
23          passes = passes + 1;
24      } /* end if */
25      else { /* otherwise, increment failures */
26          failures = failures + 1;
27      } /* end else */
28
29      student = student + 1; /* increment student counter */
30  } /* end while */
31
32  /* termination phase; display number of passes and failures */
33  printf( "Passed %d\n", passes );
34  printf( "Failed %d\n", failures );
35
36  /* if more than eight students passed, print "Bonus to instructor!" */
37  if ( passes > 8 ) {
38      printf( "Bonus to instructor!\n" );
39  } /* end if */
40
41  return 0; /* indicate program ended successfully */
42 } /* end function main */

```

```

Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 2
Enter Result (1=pass,2=fail): 2
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 2
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 2
Passed 6
Failed 4

```

```

Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 2
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1
Enter Result (1=pass,2=fail): 1

```

Fig. 3.10 | C program and sample executions for examination results problem. (Part 2 of 3.)

Passed 9
Failed 1
Bonus to instructor!

Fig. 3.10 | C program and sample executions for examination results problem. (Part 3 of 3.)



Software Engineering Observation 3.6

Experience has shown that the most difficult part of solving a problem on a computer is developing the algorithm for the solution. Once a correct algorithm has been specified, the process of producing a working C program is normally straightforward.



Software Engineering Observation 3.7

Many programmers write programs without ever using program development tools such as pseudocode. They feel that their ultimate goal is to solve the problem on a computer and that writing pseudocode merely delays the production of final outputs.

3.11 Assignment Operators

C provides several assignment operators for abbreviating assignment expressions. For example, the statement

```
c = c + 3;
```

can be abbreviated with the **addition assignment operator** `+=` as

```
c += 3;
```

The `+=` operator adds the value of the expression on the right of the operator to the value of the variable on the left of the operator and stores the result in the variable on the left of the operator. Any statement of the form

```
variable = variable operator expression;
```

where *operator* is one of the binary operators `+`, `-`, `*`, `/` or `%` (or others we'll discuss in Chapter 10), can be written in the form

```
variable operator= expression;
```

Thus the assignment `c += 3` adds 3 to `c`. Figure 3.11 shows the arithmetic assignment operators, sample expressions using these operators and explanations.

Assignment operator	Sample expression	Explanation	Assigns
Assume: <code>int c = 3, d = 5, e = 4, f = 6, g = 12;</code>			
<code>+=</code>	<code>c += 7</code>	<code>c = c + 7</code>	10 to c
<code>-=</code>	<code>d -= 4</code>	<code>d = d - 4</code>	1 to d
<code>*=</code>	<code>e *= 5</code>	<code>e = e * 5</code>	20 to e
<code>/=</code>	<code>f /= 3</code>	<code>f = f / 3</code>	2 to f
<code>%=</code>	<code>g %= 9</code>	<code>g = g % 9</code>	3 to g

Fig. 3.11 | Arithmetic assignment operators.

3.12 Increment and Decrement Operators

C also provides the unary **increment operator**, `++`, and the unary **decrement operator**, `--`, which are summarized in Fig. 3.12. If a variable `c` is incremented by 1, the increment operator `++` can be used rather than the expressions `c = c + 1` or `c += 1`. If increment or decrement operators are placed before a variable (i.e., prefixed), they're referred to as the **pre-increment** or **predecrement operators**, respectively. If increment or decrement operators are placed after a variable (i.e., postfixed), they're referred to as the **postincrement** or **post-decrement operators**, respectively. Preincrementing (predecrementing) a variable causes the variable to be incremented (decremented) by 1, then the new value of the variable is used in the expression in which it appears. Postincrementing (postdecrementing) the variable causes the current value of the variable to be used in the expression in which it appears, then the variable value is incremented (decremented) by 1.

Operator	Sample expression	Explanation
<code>++</code>	<code>++a</code>	Increment <code>a</code> by 1, then use the new value of <code>a</code> in the expression in which <code>a</code> resides.
<code>++</code>	<code>a++</code>	Use the current value of <code>a</code> in the expression in which <code>a</code> resides, then increment <code>a</code> by 1.
<code>--</code>	<code>--b</code>	Decrement <code>b</code> by 1, then use the new value of <code>b</code> in the expression in which <code>b</code> resides.
<code>--</code>	<code>b--</code>	Use the current value of <code>b</code> in the expression in which <code>b</code> resides, then decrement <code>b</code> by 1.

Fig. 3.12 | Increment and decrement operators

Figure 3.13 demonstrates the difference between the preincrementing and the postincrementing versions of the `++` operator. Postincrementing the variable `c` causes it to be incremented after it's used in the `printf` statement. Preincrementing the variable `c` causes it to be incremented before it's used in the `printf` statement.

```
1  /* Fig. 3.13: fig03_13.c
2     Preincrementing and postincrementing */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     int c; /* define variable */
9
10    /* demonstrate postincrement */
11    c = 5; /* assign 5 to c */
12    printf( "%d\n", c ); /* print 5 */
13    printf( "%d\n", c++ ); /* print 5 then postincrement */
14    printf( "%d\n\n", c ); /* print 6 */
```

Fig. 3.13 | Preincrementing vs. postincrementing. (Part I of 2.)

```

15
16      /* demonstrate preincrement */
17      c = 5; /* assign 5 to c */
18      printf( "%d\n", c ); /* print 5 */
19      printf( "%d\n", ++c ); /* preincrement then print 6 */
20      printf( "%d\n", c ); /* print 6 */
21      return 0; /* indicate program ended successfully */
22  } /* end function main */

```

```

5
5
6
5
5
6
6
6

```

Fig. 3.13 | Preincrementing vs. postincrementing. (Part 2 of 2.)

The program displays the value of `c` before and after the `++` operator is used. The decrement operator (`--`) works similarly.



Good Programming Practice 3.7

Unary operators should be placed directly next to their operands with no intervening spaces.

The three assignment statements in Fig. 3.10

```

passes = passes + 1;
failures = failures + 1;
student = student + 1;

```

can be written more concisely with assignment operators as

```

passes += 1;
failures += 1;
student += 1;

```

with preincrement operators as

```

++passes;
++failures;
++student;

```

or with postincrement operators as

```

passes++;
failures++;
student++;

```

It's important to note here that when incrementing or decrementing a variable in a statement by itself, the preincrement and postincrement forms have the same effect. It's only when a variable appears in the context of a larger expression that preincrementing and postincrementing have different effects (and similarly for predecrementing and postdecrementing). Of the expressions we've studied thus far, only a simple variable name may be used as the operand of an increment or decrement operator.



Common Programming Error 3.10

Attempting to use the increment or decrement operator on an expression other than a simple variable name is a syntax error, e.g., writing `++(x + 1)`.



Error-Prevention Tip 3.4

C generally does not specify the order in which an operator's operands will be evaluated (although we'll see exceptions to this for a few operators in Chapter 4). Therefore you should avoid using statements with increment or decrement operators in which a particular variable being incremented or decremented appears more than once.

Figure 3.14 lists the precedence and associativity of the operators introduced to this point. The operators are shown top to bottom in decreasing order of precedence. The second column describes the associativity of the operators at each level of precedence. Notice that the conditional operator (`?:`), the unary operators increment (`++`), decrement (`--`), plus (`+`), minus (`-`) and casts, and the assignment operators `=`, `+=`, `-=`, `*=`, `/=` and `%=` associate from right to left. The third column names the various groups of operators. All other operators in Fig. 3.14 associate from left to right.

Operators	Associativity	Type
<code>++ (postfix)</code> <code>-- (postfix)</code>	right to left	postfix
<code>+</code> <code>- (type)</code> <code>++ (prefix)</code> <code>-- (prefix)</code>	right to left	unary
<code>*</code> <code>/</code> <code>%</code>	left to right	multiplicative
<code>+</code> <code>-</code>	left to right	additive
<code><</code> <code><=</code> <code>></code> <code>>=</code>	left to right	relational
<code>==</code> <code>!=</code>	left to right	equality
<code>?:</code>	right to left	conditional
<code>=</code> <code>+=</code> <code>-=</code> <code>*=</code> <code>/=</code> <code>%=</code>	right to left	assignment

Fig. 3.14 | Precedence and associativity of the operators encountered so far in the text.

Summary

Section 3.1 Introduction

- Before writing a program to solve a particular problem, it's essential to have a thorough understanding of the problem and a carefully planned approach to solving the problem.

Section 3.2 Algorithms

- The solution to any computing problem involves executing a series of actions in a specific order.
- A procedure for solving a problem in terms of the actions to be executed, and the order in which these actions are to be executed, is called an algorithm.
- The order in which actions are to be executed is important.

Section 3.3 Pseudocode

- Pseudocode is an artificial and informal language that helps you develop algorithms.

- Pseudocode is similar to everyday English; it's not an actual computer programming language.
- Pseudocode programs help you “think out” a program before attempting to write it in a programming language such as C.
- Pseudocode consists purely of characters; you may type pseudocode using an editor.
- Carefully prepared pseudocode programs may be converted easily to corresponding C programs.
- Pseudocode consists only of action statements.

Section 3.4 Control Structures

- Normally, statements in a program execute one after the other in the order in which they're written. This is called sequential execution.
- Various C statements enable you to specify that the next statement to execute may be other than the next one in sequence. This is called transfer of control.
- Structured programming has become almost synonymous with “goto elimination.”
- Structured programs are clearer, easier to debug and modify and more likely to be bug free.
- All programs can be written in terms of only three control structures—sequence, selection and repetition.
- Unless directed otherwise, the computer automatically executes C statements in sequence.
- A flowchart is a graphical representation of an algorithm. They're drawn using rectangles, diamonds, ovals and small circles, connected by arrows called flowlines.
- The rectangle (action) symbol indicates any type of action including a calculation or an input/output operation.
- Flowlines indicate the order in which the actions are performed.
- When drawing a flowchart that represents a complete algorithm, an oval symbol containing the word “Begin” is the first symbol used in the flowchart; an oval symbol containing the word “End” is the last symbol used. When drawing only a portion of an algorithm, the oval symbols are omitted in favor of using small circle symbols also called connector symbols.
- The diamond (decision) symbol indicates that a decision is to be made.
- C provides three types of selection structures in the form of statements. The `if` selection statement either performs (selects) an action if a condition is true or skips the action if the condition is false. The `if...else` selection statement performs an action if a condition is true and performs a different action if the condition is false. The `switch` selection statement performs one of many different actions depending on the value of an expression.
- The `if` statement is called a single-selection statement because it selects or ignores a single action.
- The `if...else` statement is called a double-selection statement because it selects between two different actions.
- The `switch` statement is called a multiple-selection statement because it selects among many different actions.
- C provides three types of repetition structures in the form of statements, namely `while`, `do...while` and `for`.
- Control statement flowchart segments can be attached to one another with control-statement stacking—connecting the exit point of one control statement to the entry point of the next.
- There is only one other way control statements may be connected—control-statement nesting.

Section 3.5 The if Selection Statement

- Selection structures are used to choose among alternative courses of action.

- The decision symbol contains an expression, such as a condition, that can be either true or false. The decision symbol has two flowlines emerging from it. One indicates the direction to be taken when the expression is true; the other indicates the direction when the expression is false.
- A decision can be based on any expression—if the expression evaluates to zero, it's treated as false, and if the expression evaluates to nonzero, it's treated as true.
- The `if` statement is a single-entry/single-exit structure.

Section 3.6 The `if...else` Selection Statement

- C provides the conditional operator (`?:`) which is closely related to the `if...else` statement.
- The conditional operator is C's only ternary operator—it takes three operands. The operands together with the conditional operator form a conditional expression. The first operand is a condition. The second operand is the value for the conditional expression if the condition is true, and the third operand is the value for the conditional expression if the condition is false.
- The values in a conditional expression can also be actions to execute.
- Nested `if...else` statements test for multiple cases by placing `if...else` statements inside `if...else` statements.
- The `if` selection statement expects only one statement in its body. To include several statements in the body of an `if`, enclose the set of statements in braces (`{` and `}`).
- A set of statements contained within a pair of braces is called a compound statement or a block.
- A syntax error is caught by the compiler. A logic error has its effect at execution time. A fatal logic error causes a program to fail and terminate prematurely. A nonfatal logic error allows a program to continue executing but to produce incorrect results.

Section 3.7 The `while` Repetition Statement

- The `while` repetition statement specifies that an action is to be repeated while a condition is true. Eventually, the condition will become false. At this point, the repetition terminates, and the first statement after the repetition statement executes.

Section 3.8 Formulating Algorithms Case Study 1: Counter-Controlled Repetition

- Counter-controlled repetition uses a variable called a counter to specify the number of times a set of statements should execute.
- Counter-controlled repetition is often called definite repetition because the number of repetitions is known before the loop begins executing.
- A total is a variable used to accumulate the sum of a series of values. Variables used to store totals should normally be initialized to zero before being used in a program; otherwise the sum would include the previous value stored in the total's memory location.
- A counter is a variable used to count. Counter variables are normally initialized to zero or one, depending on their use.
- An uninitialized variable contains a “garbage” value—the value last stored in the memory location reserved for that variable.

Section 3.9 Formulating Algorithms with Top-Down, Stepwise Refinement Case Study 2: Sentinel-Controlled Repetition

- A sentinel value (also called a signal value, a dummy value, or a flag value) is used in a sentinel-controlled loop to indicate the “end of data entry.”
- Sentinel-controlled repetition is often called indefinite repetition because the number of repetitions is not known before the loop begins executing.
- The sentinel value must be chosen so that it cannot be confused with an acceptable input value.

- Top-down, stepwise refinement is essential to the development of well-structured programs.
- The top is a statement that conveys the program's overall function. It's a complete representation of a program. The top rarely conveys a sufficient amount of detail for writing a C program. In the refinement process, we divide the top into smaller tasks and list these in execution order.
- The type `float` represents numbers with decimal points (called floating-point numbers).
- When dividing two integers any fractional part of the result is truncated.
- To produce a floating-point calculation with integer values, you must cast the integers to floating-point numbers. C provides the unary cast operator (`float`) to accomplish this task.
- Cast operators perform explicit conversions.
- Most computers can evaluate arithmetic expressions only in which the operands' data types are identical. To ensure this, the compiler performs an operation called promotion (also called implicit conversion) on selected operands. For example, in an expression containing the data types `int` and `float`, copies of `int` operands are made and promoted to `float`.
- Cast operators are available for most data types. A cast operator is formed by placing parentheses around a data type name. The cast operator is a unary operator, i.e., it takes only one operand.
- Cast operators associate from right to left and have the same precedence as other unary operators such as unary `+` and unary `-`. This precedence is one level higher than that of `*`, `/` and `%`.
- The `printf` conversion specifier `%.2f` specifies that a floating-point value will be displayed with two digits to the right of the decimal point. If the `%f` conversion specifier is used (without specifying the precision), the default precision of 6 is used.
- When floating-point values are printed with precision, the printed value is rounded to the indicated number of decimal positions for display purposes.

Section 3.11 Assignment Operators

- C provides several assignment operators for abbreviating assignment expressions.
- The `+=` operator adds the value of the expression on the right of the operator to the value of the variable on the left of the operator and stores the result in the variable on the left of the operator.
- Any statement of the form

variable = *variable operator expression*;

where *operator* is one of the binary operators `+`, `-`, `*`, `/` or `%` (or others we'll discuss in Chapter 10), can be written in the form

variable operator = *expression*;

Section 3.12 Increment and Decrement Operators

- C provides the unary increment operator, `++`, and the unary decrement operator, `--`.
- If increment or decrement operators are placed before a variable, they're referred to as the preincrement or predecrement operators, respectively. If increment or decrement operators are placed after a variable, they're referred to as the postincrement or postdecrement operators, respectively.
- Preincrementing (predecrementing) a variable causes the variable to be incremented (decremented) by 1, then the new value of the variable is used in the expression in which it appears.
- Postincrementing (postdecrementing) a variable uses the current value of the variable in the expression in which it appears, then the variable value is incremented (decremented) by 1.
- When incrementing or decrementing a variable in a statement by itself, the preincrement and postincrement forms have the same effect. When a variable appears in the context of a larger expression, preincrementing and postincrementing have different effects (and similarly for predecrementing and postdecrementing).

Terminology

- ?: conditional operator 60
- * multiplication operator 72
- *= multiplication assignment operator 77
- / division operator 72
- /= division assignment operator 77
- % remainder operator 72
- %= remainder assignment operator 77
- decrement operator 78
- ++ increment operator 78
- += addition assignment operator 77
- = subtraction assignment operator 77
- action 55
- action symbol 57
- addition assignment operator (+=) 77
- algorithm 55
- block 62
- “bombing” 68
- cast operator 71
- compound statement 62
- conditional expression 60
- conditional operator (?:) 60
- connector symbol 57
- control statement stacking 58
- control structure 56
- counter 64
- counter-controlled repetition 64
- “crashing” 68
- decision symbol 57
- default precision 72
- definite repetition 65
- diamond symbol 57, 59
- double-selection statement 57
- dummy value 67
- explicit conversion 71
- fatal error 68
- first refinement 67
- flag value 67
- float 69
- floating-point number 69
- flowchart 56
- flowline 57
- “garbage value” 66
- goto elimination 56
- goto statement 56
- implicit conversion 71
- indefinite repetition 67
- integer division 71
- multiple-selection statement 57
- multiplicative operator 72
- nested statements 74
- nested if...else statement 61
- nesting statements 73
- order 55
- oval symbol 57
- postdecrement operator (--) 78
- postincrement operator (++) 78
- precision 72
- predecrement operator (--) 78
- preincrement operator(++) 78
- procedure 55
- program control 55
- promotion 71
- pseudocode 55
- rectangle symbol 57
- repetition statement 63
- repetition structure 56
- rounded 72
- second refinement 67
- selection structure 56
- sentinel value 67
- sequence structure 56
- sequential execution 56
- signal value 67
- single-selection statement 57
- single-entry/single-exit control statement 58
- small circle symbols 57
- top 67
- top-down, stepwise refinement 67
- total 66
- transfer of control 56
- truncated 71
- unary operator 72
- while repetition statement 63
- white-space character 58

Self-Review Exercises

- 3.1** Fill in the blanks in each of the following questions.
- a) A procedure for solving a problem in terms of the actions to be executed and the order in which the actions should be executed is called a(n) _____.
 - b) Specifying the execution order of statements by the computer is called _____.

- c) All programs can be written in terms of three types of control statements: _____, _____ and _____.
- d) The _____ selection statement is used to execute one action when a condition is true and another action when that condition is false.
- e) Several statements grouped together in braces ({ and }) are called a(n) _____.
- f) The _____ repetition statement specifies that a statement or group of statements is to be executed repeatedly while some condition remains true.
- g) Repetition of a set of instructions a specific number of times is called _____ repetition.
- h) When it's not known in advance how many times a set of statements will be repeated, a(n) _____ value can be used to terminate the repetition.

3.2 Write four different C statements that each add 1 to integer variable `x`.

3.3 Write a single C statement to accomplish each of the following:

- a) Assign the sum of `x` and `y` to `z` and increment the value of `x` by 1 after the calculation.
- b) Multiply the variable `product` by 2 using the `*=` operator.
- c) Multiply the variable `product` by 2 using the `=` and `*` operators.
- d) Test if the value of the variable `count` is greater than 10. If it is, print "Count is greater than 10."
- e) Decrement the variable `x` by 1, then subtract it from the variable `total`.
- f) Add the variable `x` to the variable `total`, then decrement `x` by 1.
- g) Calculate the remainder after `q` is divided by `divisor` and assign the result to `q`. Write this statement two different ways.
- h) Print the value 123.4567 with 2 digits of precision. What value is printed?
- i) Print the floating-point value 3.14159 with three digits to the right of the decimal point. What value is printed?

3.4 Write a C statement to accomplish each of the following tasks.

- a) Define variables `sum` and `x` to be of type `int`.
- b) Initialize variable `x` to 1.
- c) Initialize variable `sum` to 0.
- d) Add variable `x` to variable `sum` and assign the result to variable `sum`.
- e) Print "The sum is: " followed by the value of variable `sum`.

3.5 Combine the statements that you wrote in Exercise 3.4 into a program that calculates the sum of the integers from 1 to 10. Use the `while` statement to loop through the calculation and increment statements. The loop should terminate when the value of `x` becomes 11.

3.6 Determine the values of variables `product` and `x` after the following calculation is performed. Assume that `product` and `x` each have the value 5 when the statement begins executing.

```
product *= x++;
```

3.7 Write single C statements that

- a) Input integer variable `x` with `scanf`.
- b) Input integer variable `y` with `scanf`.
- c) Initialize integer variable `i` to 1.
- d) Initialize integer variable `power` to 1.
- e) Multiply variable `power` by `x` and assign the result to `power`.
- f) Increment variable `i` by 1.
- g) Test `i` to see if it's less than or equal to `y` in the condition of a `while` statement.
- h) Output integer variable `power` with `printf`.

3.8 Write a C program that uses the statements in Exercise 3.7 to calculate `x` raised to the `y` power. The program should have a `while` repetition control statement.

3.9 Identify and correct the errors in each of the following:

- a) `while ( c <= 5 ) {`
`product *= c;`
`++c;`
- b) `scanf( "%.4f", &value );`
- c) `if ( gender == 1 )`
`printf( "Woman\n" );`
`else;`
`printf( "Man\n" );`

3.10 What is wrong with the following `while` repetition statement (assume `z` has value 100), which is supposed to calculate the sum of the integers from 100 down to 1:

```
while ( z >= 0 )
    sum += z;
```

Answers to Self-Review Exercises

3.1 a) Algorithm. b) Program control. c) Sequence, selection, repetition. d) `if...else`. e) Compound statement. f) `while`. g) Counter-controlled. h) Sentinel.

3.2 `x = x + 1;`
`x += 1;`
`++x;`
`x++;`

3.3 a) `z = x++ + y;`
b) `product *= 2;`
c) `product = product * 2;`
d) `if ( count > 10 )`
`printf( "Count is greater than 10.\n" );`
e) `total -= --x;`
f) `total += x--;`
g) `q %= divisor;`
`q = q % divisor;`
h) `printf( "%.2f", 123.4567 );`
123.46 is displayed.
i) `printf( "%.3f\n", 3.14159 );`
3.142 is displayed.

3.4 a) `int sum, x;`
b) `x = 1;`
c) `sum = 0;`
d) `sum += x; or sum = sum + x;`
e) `printf( "The sum is: %d\n", sum );`

3.5 See top of next page.

```
1  /* Calculate the sum of the integers from 1 to 10 */
2  #include <stdio.h>
3
4  int main( void )
5  {
6      int sum, x; /* define variables sum and x */
7
```

```

8     x = 1; /* initialize x */
9     sum = 0; /* initialize sum */
10
11     while ( x <= 10 ) { /* loop while x is less than or equal to 10 */
12         sum += x; /* add x to sum */
13         ++x; /* increment x */
14     } /* end while */
15
16     printf( "The sum is: %d\n", sum ); /* display sum */
17     return 0;
18 } /* end main function */

```

3.6 product = 25, x = 6;

- 3.7**
- a) scanf("%d", &x);
 - b) scanf("%d", &y);
 - c) i = 1;
 - d) power = 1;
 - e) power *= x;
 - f) i++;
 - g) if (i <= y)
 - h) printf("%d", power);

3.8 See below.

```

1  /* raise x to the y power */
2  #include <stdio.h>
3
4  int main( void )
5  {
6      int x, y, i, power; /* define variables */
7
8      i = 1; /* initialize i */
9      power = 1; /* initialize power */
10     scanf( "%d", &x ); /* read value for x from user */
11     scanf( "%d", &y ); /* read value for y from user */
12
13     while ( i <= y ) { /* loop while i is less than or equal to y */
14         power *= x; /* multiply power by x */
15         ++i; /* increment i */
16     } /* end while */
17
18     printf( "%d", power ); /* display power */
19     return 0;
20 } /* end main function */

```

- 3.9**
- a) Error: Missing the closing right brace of the while body.
Correction: Add closing right brace after the statement ++c;.
 - b) Error: Precision used in a scanf conversion specification.
Correction: Remove .4 from the conversion specification.
 - c) Error: Semicolon after the else part of the if...else statement results in a logic error.
The second printf will always be executed.
Correction: Remove the semicolon after else.

3.10 The value of the variable z is never changed in the while statement. Therefore, an infinite loop is created. To prevent the infinite loop, z must be decremented so that it eventually becomes 0.

Exercises

3.11 Identify and correct the errors in each of the following. [Note: There may be more than one error in each piece of code.]

- a) `if ( age >= 65 );`
 `printf( "Age is greater than or equal to 65\n" );`
 `else`
 `printf( "Age is less than 65\n" );`
- b) `int x = 1, total;`
 `while ( x <= 10 ) {`
 `total += x;`
 `++x;`
 `}`
- c) `While ( x <= 100 )`
 `total += x;`
 `++x;`
- d) `while ( y > 0 ) {`
 `printf( "%d\n", y );`
 `++y;`
 `}`

3.12 Fill in the blanks in each of the following:

- a) The solution to any problem involves performing a series of actions in a specific _____.
- b) A synonym for procedure is _____.
- c) A variable that accumulates the sum of several numbers is a(n) _____.
- d) Setting certain variables to specific values at the beginning of a program is called _____.
- e) A special value used to indicate “end of data entry” is called a(n) _____, a(n) _____, a(n) _____ or a(n) _____ value.
- f) A(n) _____ is a graphical representation of an algorithm.
- g) In a flowchart, the order in which the steps should be performed is indicated by _____ symbols.
- h) The termination symbol indicates the _____ and _____ of every algorithm.
- i) Rectangle symbols correspond to calculations that are normally performed by statements and input/output operations that are normally performed by calls to the _____ and _____ Standard Library functions.
- j) The item written inside a decision symbol is called a(n) _____.

3.13 What does the following program print?

```

1  #include <stdio.h>
2
3  int main( void )
4  {
5      int x = 1, total = 0, y;
6
7      while ( x <= 10 ) {
8          y = x * x;
9          printf( "%d\n", y );
10         total += y;
11         ++x;
12     } /* end while */
13

```

```

14     printf("Total is %d\n", total);
15     return 0;
16 } /* end main */

```

- 3.14** Write a single pseudocode statement that indicates each of the following:
- Display the message "Enter two numbers".
 - Assign the sum of variables *x*, *y*, and *z* to variable *p*.
 - The following condition is to be tested in an *if...else* selection statement: The current value of variable *m* is greater than twice the current value of variable *v*.
 - Obtain values for variables *s*, *r*, and *t* from the keyboard.
- 3.15** Formulate a pseudocode algorithm for each of the following:
- Obtain two numbers from the keyboard, compute their sum and display the result.
 - Obtain two numbers from the keyboard, and determine and display which (if either) is the larger of the two numbers.
 - Obtain a series of positive numbers from the keyboard, and determine and display their sum. Assume that the user types the sentinel value -1 to indicate "end of data entry."
- 3.16** State which of the following are *true* and which are *false*. If a statement is *false*, explain why.
- Experience has shown that the most difficult part of solving a problem on a computer is producing a working C program.
 - A sentinel value must be a value that cannot be confused with a legitimate data value.
 - Flowlines indicate the actions to be performed.
 - Conditions written inside decision symbols always contain arithmetic operators (i.e., +, -, *, /, and %).
 - In top-down, stepwise refinement, each refinement is a complete representation of the algorithm.

For Exercises 3.17 to 3.21, perform each of these steps:

- Read the problem statement.
- Formulate the algorithm using pseudocode and top-down, stepwise refinement.
- Write a C program.
- Test, debug and execute the C program.

3.17 (*Gas Mileage*) Drivers are concerned with the mileage obtained by their automobiles. One driver has kept track of several tankfuls of gasoline by recording miles driven and gallons used for each tankful. Develop a program that will input the miles driven and gallons used for each tankful. The program should calculate and display the miles per gallon obtained for each tankful. After processing all input information, the program should calculate and print the combined miles per gallon obtained for all tankfuls. Here is a sample input/output dialog:

```

Enter the gallons used (-1 to end): 12.8
Enter the miles driven: 287
The miles / gallon for this tank was 22.421875

Enter the gallons used (-1 to end): 10.3
Enter the miles driven: 200
The miles / gallon for this tank was 19.417475

Enter the gallons used (-1 to end): 5
Enter the miles driven: 120
The miles / gallon for this tank was 24.000000

Enter the gallons used (-1 to end): -1
The overall average miles/gallon was 21.601423

```

3.18 (Credit Limit Calculator) Develop a C program that will determine if a department store customer has exceeded the credit limit on a charge account. For each customer, the following facts are available:

- a) Account number
- b) Balance at the beginning of the month
- c) Total of all items charged by this customer this month
- d) Total of all credits applied to this customer's account this month
- e) Allowed credit limit

The program should input each of these facts, calculate the new balance ($= \text{beginning balance} + \text{charges} - \text{credits}$), and determine if the new balance exceeds the customer's credit limit. For those customers whose credit limit is exceeded, the program should display the customer's account number, credit limit, new balance and the message "Credit limit exceeded." Here is a sample input/output dialog:

```
Enter account number (-1 to end): 100
Enter beginning balance: 5394.78
Enter total charges: 1000.00
Enter total credits: 500.00
Enter credit limit: 5500.00
Account: 100
Credit limit: 5500.00
Balance: 5894.78
Credit Limit Exceeded.

Enter account number (-1 to end): 200
Enter beginning balance: 1000.00
Enter total charges: 123.45
Enter total credits: 321.00
Enter credit limit: 1500.00

Enter account number (-1 to end): 300
Enter beginning balance: 500.00
Enter total charges: 274.73
Enter total credits: 100.00
Enter credit limit: 800.00

Enter account number (-1 to end): -1
```

3.19 (Sales Commission Calculator) One large chemical company pays its salespeople on a commission basis. The salespeople receive \$200 per week plus 9% of their gross sales for that week. For example, a salesperson who sells \$5000 worth of chemicals in a week receives \$200 plus 9% of \$5000, or a total of \$650. Develop a program that will input each salesperson's gross sales for last week and will calculate and display that salesperson's earnings. Process one salesperson's figures at a time. Here is a sample input/output dialog:

```
Enter sales in dollars (-1 to end): 5000.00
Salary is: $650.00

Enter sales in dollars (-1 to end): 1234.56
Salary is: $311.11

Enter sales in dollars (-1 to end): 1088.89
Salary is: $298.00

Enter sales in dollars (-1 to end): -1
```

3.20 (Interest Calculator) The simple interest on a loan is calculated by the formula

$\text{interest} = \text{principal} * \text{rate} * \text{days} / 365;$

The preceding formula assumes that rate is the annual interest rate, and therefore includes the division by 365 (days). Develop a program that will input principal, rate and days for several loans, and will calculate and display the simple interest for each loan, using the preceding formula. Here is a sample input/output dialog:

```
Enter loan principal (-1 to end): 1000.00
Enter interest rate: .1
Enter term of the loan in days: 365
The interest charge is $100.00

Enter loan principal (-1 to end): 1000.00
Enter interest rate: .08375
Enter term of the loan in days: 224
The interest charge is $51.40

Enter loan principal (-1 to end): 10000.00
Enter interest rate: .09
Enter term of the loan in days: 1460
The interest charge is $3600.00

Enter loan principal (-1 to end): -1
```

3.21 (Salary Calculator) Develop a program that will determine the gross pay for each of several employees. The company pays “straight time” for the first 40 hours worked by each employee and pays “time-and-a-half” for all hours worked in excess of 40 hours. You’re given a list of the employees of the company, the number of hours each employee worked last week and the hourly rate of each employee. Your program should input this information for each employee, and should determine and display the employee’s gross pay. Here is a sample input/output dialog:

```
Enter # of hours worked (-1 to end): 39
Enter hourly rate of the worker ($00.00): 10.00
Salary is $390.00

Enter # of hours worked (-1 to end): 40
Enter hourly rate of the worker ($00.00): 10.00
Salary is $400.00

Enter # of hours worked (-1 to end): 41
Enter hourly rate of the worker ($00.00): 10.00
Salary is $415.00

Enter # of hours worked (-1 to end): -1
```

3.22 (Predecrementing vs. Postdecrementing) Write a program that demonstrates the difference between predecrementing and postdecrementing using the decrement operator --.

3.23 (Printing Numbers from a Loop) Write a program that utilizes looping to print the numbers from 1 to 10 side by side on the same line with three spaces between numbers.

3.24 (Find the Largest Number) The process of finding the largest number (i.e., the maximum of a group of numbers) is used frequently in computer applications. For example, a program that determines the winner of a sales contest would input the number of units sold by each salesperson. The salesperson who sold the most units wins the contest. Write a pseudocode program and then a program that inputs a series of 10 numbers and determines and prints the largest of the numbers. [Hint: Your program should use three variables as follows]:

counter:	A counter to count to 10 (i.e., to keep track of how many numbers have been input and to determine when all 10 numbers have been processed)
number:	The current number input to the program
largest:	The largest number found so far

3.25 (Tabular Output) Write a program that uses looping to print the following table of values. Use the tab escape sequence, `\t`, in the `printf` statement to separate the columns with tabs.

N	10*N	100*N	1000*N
1	10	100	1000
2	20	200	2000
3	30	300	3000
4	40	400	4000
5	50	500	5000
6	60	600	6000
7	70	700	7000
8	80	800	8000
9	90	900	9000
10	100	1000	10000

3.26 (Tabular Output) Write a program that utilizes looping to produce the following table of values:

A	A+2	A+4	A+6
3	5	7	9
6	8	10	12
9	11	13	15
12	14	16	18
15	17	19	21

3.27 (Find the Two Largest Numbers) Using an approach similar to Exercise 3.24, find the *two* largest values of the 10 numbers. [Note: You may input each number only once.]

3.28 (Validating User Input) Modify the program in Figure 3.10 to validate its inputs. On any input, if the value entered is other than 1 or 2, keep looping until the user enters a correct value.

3.29 What does the following program print?

```

1  #include <stdio.h>
2
3  int main( void )
4  {
5      int count = 1; /* initialize count */
6
7      while ( count <= 10 ) { /* loop 10 times */
8
9          /* output line of text */
10         printf( "%s\n", count % 2 ? "*****" : "+++++++" );
11         count++; /* increment count */
12     } /* end while */
13
14     return 0; /* indicate program ended successfully */
15 } /* end function main */

```

3.30 What does the following program print?

```

1  #include <stdio.h>
2
3  int main( void )
4  {
5      int row = 10; /* initialize row */
6      int column; /* define column */

```

```

7
8   while ( row >= 1 ) { /* loop until row < 1 */
9       column = 1; /* set column to 1 as iteration begins */
10
11       while ( column <= 10 ) { /* loop 10 times */
12           printf( "%5", row % 2 ? "<": ">" ); /* output */
13           column++; /* increment column */
14       } /* end inner while */
15
16       row--; /* decrement row */
17       printf( "\n" ); /* begin new output line */
18   } /* end outer while */
19
20   return 0; /* indicate program ended successfully */
21 } /* end function main */

```

3.31 (Dangling Else Problem) Determine the output for each of the following when x is 9 and y is 11, and when x is 11 and y is 9. The compiler ignores the indentation in a C program. Also, the compiler always associates an `else` with the previous `if` unless told to do otherwise by the placement of braces `{}`. Because, on first glance, you may not be sure which `if` an `else` matches, this is referred to as the “dangling else” problem. We eliminated the indentation from the following code to make the problem more challenging. [Hint: Apply indentation conventions you have learned.]

```

a) if ( x < 10 )
    if ( y > 10 )
        printf( "*****\n" );
    else
        printf( "####\n" );
        printf( "$$$$ \n" );
b) if ( x < 10 ) {
    if ( y > 10 )
        printf( "*****\n" );
    }
    else {
        printf( "####\n" );
        printf( "$$$$ \n" );
    }

```

3.32 (Another Dangling Else Problem) Modify the following code to produce the output shown. Use proper indentation techniques. You may not make any changes other than inserting braces. The compiler ignores the indentation in a program. We eliminated the indentation from the following code to make the problem more challenging. [Note: It’s possible that no modification is necessary.]

```

if ( y == 8 )
if ( x == 5 )
    printf( "@@@@\n" );
else
    printf( "####\n" );
    printf( "$$$$ \n" );
    printf( "&&&&\n" );

```

a) Assuming $x = 5$ and $y = 8$, the following output is produced.

```

@@@@
$$$$
&&&&

```


- b) Assuming $x = 5$ and $y = 8$, the following output is produced.

```
@@@@@
```

- c) Assuming $x = 5$ and $y = 8$, the following output is produced.

```
@@@@@
&&&&&
```

- d) Assuming $x = 5$ and $y = 7$, the following output is produced. [Note: The last three `printf` statements are all part of a compound statement.]

```
#####
$$$$$
&&&&&
```

3.33 (*Square of Asterisks*) Write a program that reads in the side of a square and then prints that square out of asterisks. Your program should work for squares of all side sizes between 1 and 20. For example, if your program reads a size of 4, it should print

```
****
****
****
****
```

3.34 (*Hollow Square of Asterisks*) Modify the program you wrote in Exercise 3.33 so that it prints a hollow square. For example, if your program reads a size of 5, it should print

```
*****
*   *
*   *
*   *
*   *
*****
```

3.35 (*Palindrome Tester*) A palindrome is a number or a text phrase that reads the same backward as forward. For example, each of the following five-digit integers is a palindrome: 12321, 55555, 45554 and 11611. Write a program that reads in a five-digit integer and determines whether or not it's a palindrome. [Hint: Use the division and remainder operators to separate the number into its individual digits.]

3.36 (*Printing the Decimal Equivalent of a Binary Number*) Input an integer containing only 0s and 1s (i.e., a “binary” integer) and print its decimal equivalent. [Hint: Use the remainder and division operators to pick off the “binary” number's digits one at a time from right to left. Just as in the decimal number system, in which the rightmost digit has a positional value of 1, and the next digit left has a positional value of 10, then 100, then 1000, and so on, in the binary number system the rightmost digit has a positional value of 1, the next digit left has a positional value of 2, then 4, then 8, and so on. Thus the decimal number 234 can be interpreted as $4 * 1 + 3 * 10 + 2 * 100$. The decimal equivalent of binary 1101 is $1 * 1 + 0 * 2 + 1 * 4 + 1 * 8$ or $1 + 0 + 4 + 8$ or 13.]

3.37 (*How Fast is Your Computer?*) How can you determine how fast your own computer really operates? Write a program with a `while` loop that counts from 1 to 300,000,000 by 1s. Every time the count reaches a multiple of 100,000,000, print that number on the screen. Use your watch to time how long each 100 million repetitions of the loop takes.

3.38 Write a program that prints 100 asterisks, one at a time. After every tenth asterisk, your program should print a newline character. [*Hint:* Count from 1 to 100. Use the remainder operator to recognize each time the counter reaches a multiple of 10.]

3.39 (*Counting 7s*) Write a program that reads an integer and determines and prints how many digits in the integer are 7s.

3.40 (*Checkerboard Pattern of Asterisks*) Write a program that displays the following checkerboard pattern:

```
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
 * * * * *
* * * * *
```

Your program must use only three output statements, one of each of the following forms:

```
printf( "%* " );
printf( " " );
printf( "\n" );
```

3.41 (*Multiples of 2 with an Infinite Loop*) Write a program that keeps printing the multiples of the integer 2, namely 2, 4, 8, 16, 32, 64, and so on. Your loop should not terminate (i.e., you should create an infinite loop). What happens when you run this program?

3.42 (*Diameter, Circumference and Area of a Circle*) Write a program that reads the radius of a circle (as a `float` value) and computes and prints the diameter, the circumference and the area. Use the value 3.14159 for π .

3.43 What is wrong with the following statement? Rewrite the statement to accomplish what the programmer was probably trying to do.

```
printf( "%d", ++( x + y ) );
```

3.44 (*Sides of a Triangle*) Write a program that reads three nonzero `float` values and determines and prints if they could represent the sides of a triangle.

3.45 (*Sides of a Right Triangle*) Write a program that reads three nonzero integers and determines and prints if they could be the sides of a right triangle.

3.46 (*Factorial*) The factorial of a nonnegative integer n is written $n!$ (pronounced “ n factorial”) and is defined as follows:

$$n! = n \cdot (n - 1) \cdot (n - 2) \cdot \dots \cdot 1 \quad (\text{for values of } n \text{ greater than or equal to } 1)$$

and

$$n! = 1 \quad (\text{for } n = 0).$$

For example, $5! = 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1$, which is 120.

- Write a program that reads a nonnegative integer and computes and prints its factorial.
- Write a program that estimates the value of the mathematical constant e by using the formula:

$$e = 1 + \frac{1}{1!} + \frac{1}{2!} + \frac{1}{3!} + \dots$$

- Write a program that computes the value of e^x by using the formula

$$e^x = 1 + \frac{x}{1!} + \frac{x^2}{2!} + \frac{x^3}{3!} + \dots$$

Making a Difference

3.47 (*World Population Growth Calculator*) Use the web to determine the current world population and the annual world population growth rate. Write an application that inputs these values, then displays the estimated world population after one, two, three, four and five years.

3.48 (*Target-Heart-Rate Calculator*) While exercising, you can use a heart-rate monitor to see that your heart rate stays within a safe range suggested by your trainers and doctors. According to the American Heart Association (AHA) (www.americanheart.org/presenter.jhtml?identifier=4736), the formula for calculating your *maximum heart rate* in beats per minute is 220 minus your age in years. Your *target heart rate* is a range that is 50–85% of your maximum heart rate. [Note: These formulas are estimates provided by the AHA. Maximum and target heart rates may vary based on the health, fitness and gender of the individual. Always consult a physician or qualified health care professional before beginning or modifying an exercise program.] Create a program that reads the user's birthday and the current day (each consisting of the month, day and year). Your program should calculate and display the person's age (in years), the person's maximum heart rate and the person's target heart rate range.

3.49 (*Enforcing Privacy with Cryptography*) The explosive growth of Internet communications and data storage on Internet-connected computers has greatly increased privacy concerns. The field of cryptography is concerned with coding data to make it difficult (and hopefully—with the most advanced schemes—impossible) for unauthorized users to read. In this exercise you'll investigate a simple scheme for encrypting and decrypting data. A company that wants to send data over the Internet has asked you to write a program that will encrypt it so that it may be transmitted more securely. All the data is transmitted as four-digit integers. Your application should read a four-digit integer entered by the user and encrypt it as follows: Replace each digit with the result of adding 7 to the digit and getting the remainder after dividing the new value by 10. Then swap the first digit with the third, and swap the second digit with the fourth. Then print the encrypted integer. Write a separate application that inputs an encrypted four-digit integer and decrypts it (by reversing the encryption scheme) to form the original number. [Optional reading project: Research “public key cryptography” in general and the PGP (Pretty Good Privacy) specific public key scheme. You may also want to investigate the RSA scheme, which is widely used in industrial-strength applications.]

C Program Control

4

Not everything that can be counted counts, and not every thing that counts can be counted.

—Albert Einstein

Who can control his fate?

—William Shakespeare

The used key is always bright.

—Benjamin Franklin

Every advantage in the past is judged in the light of the final issue.

—Demosthenes

Objectives

In this chapter, you'll learn:

- The essentials of counter-controlled repetition.
- To use the **for** and **do...while** repetition statements to execute statements repeatedly.
- To understand multiple selection using the **switch** selection statement.
- To use the **break** and **continue** statements to alter the flow of control.
- To use the logical operators to form complex conditional expressions in control statements.
- To avoid the consequences of confusing the equality and assignment operators.

4.1 Introduction	4.7 <code>switch</code> Multiple-Selection Statement
4.2 Repetition Essentials	4.8 <code>do...while</code> Repetition Statement
4.3 Counter-Controlled Repetition	4.9 <code>break</code> and <code>continue</code> Statements
4.4 <code>for</code> Repetition Statement	4.10 Logical Operators
4.5 <code>for</code> Statement: Notes and Observations	4.11 Confusing Equality (<code>==</code>) and Assignment (<code>=</code>) Operators
4.6 Examples Using the <code>for</code> Statement	4.12 Structured Programming Summary

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

4.1 Introduction

You should now be comfortable with writing simple but complete C programs. In this chapter, repetition is considered in greater detail, and additional repetition control statements, namely the `for` and the `do...while`, are presented. The `switch` multiple-selection statement is introduced. We discuss the `break` statement for exiting immediately from certain control statements, and the `continue` statement for skipping the remainder of the body of a repetition statement and proceeding with the next iteration of the loop. The chapter discusses logical operators used for combining conditions, and summarizes the principles of structured programming as presented in Chapter 3 and 4.

4.2 Repetition Essentials

Most programs involve repetition, or looping. A loop is a group of instructions the computer executes repeatedly while some **loop-continuation condition** remains true. We have discussed two means of repetition:

1. Counter-controlled repetition
2. Sentinel-controlled repetition

Counter-controlled repetition is sometimes called **definite repetition** because we know in advance exactly how many times the loop will be executed. Sentinel-controlled repetition is sometimes called **indefinite repetition** because it's not known in advance how many times the loop will be executed.

In counter-controlled repetition, a **control variable** is used to count the number of repetitions. The control variable is incremented (usually by 1) each time the group of instructions is performed. When the value of the control variable indicates that the correct number of repetitions has been performed, the loop terminates and the computer continues executing with the statement after the repetition statement.

Sentinel values are used to control repetition when:

1. The precise number of repetitions is not known in advance, and
2. The loop includes statements that obtain data each time the loop is performed.

The sentinel value indicates “end of data.” The sentinel is entered after all regular data items have been supplied to the program. Sentinels must be distinct from regular data items.

4.3 Counter-Controlled Repetition

Counter-controlled repetition requires:

1. The **name** of a control variable (or loop counter).
2. The **initial value** of the control variable.
3. The **increment** (or **decrement**) by which the control variable is modified each time through the loop.
4. The condition that tests for the **final value** of the control variable (i.e., whether looping should continue).

Consider the simple program shown in Fig. 4.1, which prints the numbers from 1 to 10. The definition

```
int counter = 1; /* initialization */
```

names the control variable (counter), defines it to be an integer, reserves memory space for it, and sets it to an initial value of 1. This definition is not an executable statement.

```
1  /* Fig. 4.1: fig04_01.c
2     Counter-controlled repetition */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     int counter = 1; /* initialization */
9
10    while ( counter <= 10 ) { /* repetition condition */
11        printf ( "%d\n", counter ); /* display counter */
12        ++counter; /* increment */
13    } /* end while */
14
15    return 0; /* indicate program ended successfully */
16 } /* end function main */
```

```
1
2
3
4
5
6
7
8
9
10
```

Fig. 4.1 | Counter-controlled repetition.

The definition and initialization of counter could also have been written as

```
int counter;
counter = 1;
```

The definition is not executable, but the assignment is. We use both methods of initializing variables.

The statement

```
++counter; /* increment */
```

increments the loop counter by 1 each time the loop is performed. The loop-continuation condition in the `while` statement tests if the value of the control variable is less than or equal to 10 (the last value for which the condition is true). The body of this `while` is performed even when the control variable is 10. The loop terminates when the control variable exceeds 10 (i.e., counter becomes 11).

You could make the program in Fig. 4.1 more concise by initializing counter to 0 and by replacing the `while` statement with

```
while ( ++counter <= 10 )
    printf( "%d\n", counter );
```

This code saves a statement because the incrementing is done directly in the `while` condition before the condition is tested. Also, this code eliminates the need for the braces around the body of the `while` because the `while` now contains only one statement. Coding in such a condensed fashion takes some practice. Some programmers feel that this makes the code too cryptic and error prone,



Common Programming Error 4.1

Floating-point values may be approximate, so controlling counting loops with floating-point variables may result in imprecise counter values and inaccurate termination tests.



Error-Prevention Tip 4.1

Control counting loops with integer values.



Good Programming Practice 4.1

Too many levels of nesting can make a program difficult to understand. As a rule, try to avoid using more than three levels of nesting.



Good Programming Practice 4.2

The combination of vertical spacing before and after control statements and indentation of the bodies of control statements within the control-statement headers gives programs a two-dimensional appearance that greatly improves program readability.

4.4 for Repetition Statement

The `for` repetition statement handles all the details of counter-controlled repetition. To illustrate its power, let's rewrite the program of Fig. 4.1. The result is shown in Fig. 4.2.

```
1  /* Fig. 4.2: fig04_02.c
2     Counter-controlled repetition with the for statement */
3  #include <stdio.h>
```

Fig. 4.2 | Counter-controlled repetition with the `for` statement. (Part I of 2.)


```

4
5  /* function main begins program execution */
6  int main( void )
7  {
8      int counter; /* define counter */
9
10     /* initialization, repetition condition, and increment
11        are all included in the for statement header. */
12     for ( counter = 1; counter <= 10; counter++ ) {
13         printf( "%d\n", counter );
14     } /* end for */
15
16     return 0; /* indicate program ended successfully */
17 } /* end function main */

```

Fig. 4.2 | Counter-controlled repetition with the for statement. (Part 2 of 2.)

The program operates as follows. When the for statement begins executing, the control variable counter is initialized to 1. Then, the loop-continuation condition counter <= 10 is checked. Because the initial value of counter is 1, the condition is satisfied, so the printf statement (line 13) prints the value of counter, namely 1. The control variable counter is then incremented by the expression counter++, and the loop begins again with the loop-continuation test. Since the control variable is now equal to 2, the final value is not exceeded, so the program performs the printf statement again. This process continues until the control variable counter is incremented to its final value of 11—this causes the loop-continuation test to fail, and repetition terminates. The program continues by performing the first statement after the for statement (in this case, the return statement at the end of the program).

Figure 4.3 takes a closer look at the for statement of Fig. 4.2. Notice that the for statement “does it all”—it specifies each of the items needed for counter-controlled repetition with a control variable. If there is more than one statement in the body of the for, braces are required to define the body of the loop.




Fig. 4.3 | for statement header components.

Notice that Fig. 4.2 uses the loop-continuation condition counter <= 10. If you incorrectly wrote counter < 10, then the loop would be executed only 9 times. This is a common logic error called an **off-by-one error**.



Common Programming Error 4.2

Using an incorrect relational operator or using an incorrect initial or final value of a loop counter in the condition of a `while` or `for` statement can cause off-by-one errors.



Error-Prevention Tip 4.2

Using the final value in the condition of a `while` or `for` statement and using the `<=` relational operator will help avoid off-by-one errors. For a loop used to print the values 1 to 10, for example, the loop-continuation condition should be `counter <= 10` rather than `counter < 11` or `counter < 10`.

The general format of the `for` statement is

```
for ( expression1; expression2; expression3 )
    statement
```

where *expression1* initializes the loop-control variable, *expression2* is the loop-continuation condition, and *expression3* increments the control variable. In most cases, the `for` statement can be represented with an equivalent `while` statement as follows:

```
expression1;
while ( expression2 ) {
    statement
    expression3;
}
```

There is an exception to this rule, which we discuss in Section 4.9.

Often, *expression1* and *expression3* are comma-separated lists of expressions. The commas as used here are actually **comma operators** that guarantee that lists of expressions evaluate from left to right. The value and type of a comma-separated list of expressions are the value and type of the right-most expression in the list. The comma operator is most often used in the `for` statement. Its primary use is to enable you to use multiple initialization and/or multiple increment expressions. For example, there may be two control variables in a single `for` statement that must be initialized and incremented.



Software Engineering Observation 4.1

Place only expressions involving the control variables in the initialization and increment sections of a `for` statement. Manipulations of other variables should appear either before the loop (if they execute only once, like initialization statements) or in the loop body (if they execute once per repetition, like incrementing or decrementing statements).

The three expressions in the `for` statement are optional. If *expression2* is omitted, C assumes that the condition is true, thus creating an infinite loop. One may omit *expression1* if the control variable is initialized elsewhere in the program. *expression3* may be omitted if the increment is calculated by statements in the body of the `for` statement or if no increment is needed. The increment expression in the `for` statement acts like a stand-alone C statement at the end of the body of the `for`. Therefore, the expressions

```
counter = counter + 1
counter += 1
++counter
counter++
```

are all equivalent in the increment part of the for statement. Many C programmers prefer the form `counter++` because the incrementing occurs after the loop body is executed, and the postincrementing form seems more natural. Because the variable being preincremented or postincremented here does not appear in a larger expression, both forms of incrementing have the same effect. The two semicolons in the for statement are required.



Common Programming Error 4.3

Using commas instead of semicolons in a for header is a syntax error.



Common Programming Error 4.4

Placing a semicolon immediately to the right of a for header makes the body of that for statement an empty statement. This is normally a logic error.

4.5 for Statement: Notes and Observations

1. The initialization, loop-continuation condition and increment can contain arithmetic expressions. For example, if $x = 2$ and $y = 10$, the statement

```
for ( j = x; j <= 4 * x * y; j += y / x )
```

is equivalent to the statement

```
for ( j = 2; j <= 80; j += 5 )
```

2. The “increment” may be negative (in which case it’s really a decrement and the loop actually counts downward).
3. If the loop-continuation condition is initially false, the loop body does not execute. Instead, execution proceeds with the statement following the for statement.
4. The control variable is frequently printed or used in calculations in the body of a loop, but it need not be. It’s common to use the control variable for controlling repetition while never mentioning it in the body of the loop.
5. The for statement is flowcharted much like the while statement. For example, Fig. 4.4 shows the flowchart of the for statement

```
for ( counter = 1; counter <= 10; counter++ )  
    printf( "%d", counter );
```

This flowchart makes it clear that the initialization occurs only once and that incrementing occurs after the body statement is performed.



Error-Prevention Tip 4.3

Although the value of the control variable can be changed in the body of a for loop, this can lead to subtle errors. It’s best not to change it.

4.6 Examples Using the for Statement

The following examples show methods of varying the control variable in a for statement.

1. Vary the control variable from 1 to 100 in increments of 1.

```
for ( i = 1; i <= 100; i++ )
```




Fig. 4.4 | Flowcharting a typical for repetition statement.

2. Vary the control variable from 100 to 1 in increments of -1 (decrements of 1).

```
for ( i = 100; i >= 1; i-- )
```

3. Vary the control variable from 7 to 77 in steps of 7.

```
for ( i = 7; i <= 77; i += 7 )
```

4. Vary the control variable from 20 to 2 in steps of -2.

```
for ( i = 20; i >= 2; i -= 2 )
```

5. Vary the control variable over the following sequence of values: 2, 5, 8, 11, 14, 17.

```
for ( j = 2; j <= 17; j += 3 )
```

6. Vary the control variable over the following sequence of values: 44, 33, 22, 11, 0.

```
for ( j = 44; j >= 0; j -= 11 )
```

The next two examples provide simple applications of the for statement. Figure 4.5 uses the for statement to sum all the even integers from 2 to 100.

```

1  /* Fig. 4.5: fig04_05.c
2     Summation with for */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8      int sum = 0; /* initialize sum */
9      int number; /* number to be added to sum */
10
11     for ( number = 2; number <= 100; number += 2 ) {
12         sum += number; /* add number to sum */
13     } /* end for */
  
```

Fig. 4.5 | Using for to sum numbers. (Part I of 2.)

```

14
15     printf( "Sum is %d\n", sum ); /* output sum */
16     return 0; /* indicate program ended successfully */
17 } /* end function main */

```

Sum is 2550

Fig. 4.5 | Using for to sum numbers. (Part 2 of 2.)

The body of the for statement in Fig. 4.5 could actually be merged into the rightmost portion of the for header by using the comma operator as follows:

```

for ( number = 2; number <= 100; sum += number, number += 2 )
    ; /* empty statement */

```

The initialization `sum = 0` could also be merged into the initialization section of the for.



Good Programming Practice 4.3

Although statements preceding a for and statements in the body of a for can often be merged into the for header, avoid doing so because it makes the program more difficult to read.



Good Programming Practice 4.4

Limit the size of control-statement headers to a single line if possible.

The next example computes compound interest using the for statement. Consider the following problem statement:

A person invests \$1000.00 in a savings account yielding 5% interest. Assuming that all interest is left on deposit in the account, calculate and print the amount of money in the account at the end of each year for 10 years. Use the following formula for determining these amounts:

$$a = p(1 + r)^n$$

where

p is the original amount invested (i.e., the principal)

r is the annual interest rate

n is the number of years

a is the amount on deposit at the end of the n^{th} year.

This problem involves a loop that performs the indicated calculation for each of the 10 years the money remains on deposit. The solution is shown in Fig. 4.6.

```

1  /* Fig. 4.6: fig04_06.c
2     Calculating compound interest */
3  #include <stdio.h>
4  #include <math.h>

```

Fig. 4.6 | Calculating compound interest with for. (Part 1 of 2.)

```

5
6  /* function main begins program execution */
7  int main( void )
8  {
9      double amount; /* amount on deposit */
10     double principal = 1000.0; /* starting principal */
11     double rate = .05; /* annual interest rate */
12     int year; /* year counter */
13
14     /* output table column head */
15     printf( "%4s%21s\n", "Year", "Amount on deposit" );
16
17     /* calculate amount on deposit for each of ten years */
18     for ( year = 1; year <= 10; year++ ) {
19
20         /* calculate new amount for specified year */
21         amount = principal * pow( 1.0 + rate, year );
22
23         /* output one table row */
24         printf( "%4d%21.2f\n", year, amount );
25     } /* end for */
26
27     return 0; /* indicate program ended successfully */
28 } /* end function main */

```

Year	Amount on deposit
1	1050.00
2	1102.50
3	1157.63
4	1215.51
5	1276.28
6	1340.10
7	1407.10
8	1477.46
9	1551.33
10	1628.89

Fig. 4.6 | Calculating compound interest with `for`. (Part 2 of 2.)

The `for` statement executes the body of the loop 10 times, varying a control variable from 1 to 10 in increments of 1. Although C does not include an exponentiation operator, we can use the Standard Library function `pow` for this purpose. The function `pow(x, y)` calculates the value of `x` raised to the `y`th power. It takes two arguments of type `double` and returns a `double` value. Type `double` is a floating-point type much like `float`, but typically a variable of type `double` can store a value of much greater magnitude with greater precision than `float`. The header `<math.h>` (line 4) should be included whenever a math function such as `pow` is used. Actually, this program would malfunction without the inclusion of `math.h`, as the linker would be unable to find the `pow` function.¹ Function `pow` requires

1. On many Linux/UNIX C compilers, you must include the `-lm` option (e.g., `cc -lm fig04_06.c`) when compiling Fig. 4.6. This links the math library to the program.

two `double` arguments, but variable `year` is an integer. The `math.h` file includes information that tells the compiler to convert the value of `year` to a temporary `double` representation before calling the function. This information is contained in something called `pow`'s **function prototype**. Function prototypes are explained in Chapter 5. We also provide a summary of the `pow` function and other math library functions in Chapter 5.

Notice that we defined the variables `amount`, `principal` and `rate` to be of type `double`. We did this for simplicity because we're dealing with fractional parts of dollars.



Error-Prevention Tip 4.4

Do not use variables of type `float` or `double` to perform monetary calculations. The impreciseness of floating-point numbers can cause errors that will result in incorrect monetary values. [In this chapter's exercises, we explore the use of integers to perform monetary calculations.]

Here is a simple explanation of what can go wrong when using `float` or `double` to represent dollar amounts. Two `float` dollar amounts stored in the machine could be 14.234 (which with `%.2f` prints as 14.23) and 18.673 (which with `%.2f` prints as 18.67). When these amounts are added, they produce the sum 32.907, which with `%.2f` prints as 32.91. Thus your `printf` output could appear as

```

14.23
+ 18.67
-----
32.91

```

Clearly the sum of the individual numbers as printed should be 32.90! You've been warned!

The conversion specifier `%21.2f` is used to print the value of the variable `amount` in the program. The 21 in the conversion specifier denotes the field width in which the value will be printed. A field width of 21 specifies that the value printed will appear in 21 print positions. The 2 specifies the precision (i.e., the number of decimal positions). If the number of characters displayed is less than the field width, then the value will automatically be right justified in the field. This is particularly useful for aligning floating-point values with the same precision (so that their decimal points align vertically). To left justify a value in a field, place a - (minus sign) between the % and the field width. The minus sign may also be used to left justify integers (such as in `%-6d`) and character strings (such as in `%-8s`). We'll discuss the powerful formatting capabilities of `printf` and `scanf` in detail in Chapter 9.

4.7 `switch` Multiple-Selection Statement

In Chapter 3, we discussed the `if` single-selection statement and the `if...else` double-selection statement. Occasionally, an algorithm will contain a series of decisions in which a variable or expression is tested separately for each of the constant integral values it may assume, and different actions are taken. This is called multiple selection. C provides the `switch` multiple-selection statement to handle such decision making.

The `switch` statement consists of a series of case labels, an optional `default` case and statements to execute for each case. Figure 4.7 uses `switch` to count the number of each different letter grade students earned on an exam.

```

1  /* Fig. 4.7: fig04_07.c
2     Counting letter grades */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     int grade; /* one grade */
9     int aCount = 0; /* number of As */
10    int bCount = 0; /* number of Bs */
11    int cCount = 0; /* number of Cs */
12    int dCount = 0; /* number of Ds */
13    int fCount = 0; /* number of Fs */
14
15    printf( "Enter the letter grades.\n" );
16    printf( "Enter the EOF character to end input.\n" );
17
18    /* loop until user types end-of-file key sequence */
19    while ( ( grade = getchar() ) != EOF ) {
20
21        /* determine which grade was input */
22        switch ( grade ) { /* switch nested in while */
23
24            case 'A': /* grade was uppercase A */
25            case 'a': /* or lowercase a */
26                ++aCount; /* increment aCount */
27                break; /* necessary to exit switch */
28
29            case 'B': /* grade was uppercase B */
30            case 'b': /* or lowercase b */
31                ++bCount; /* increment bCount */
32                break; /* exit switch */
33
34            case 'C': /* grade was uppercase C */
35            case 'c': /* or lowercase c */
36                ++cCount; /* increment cCount */
37                break; /* exit switch */
38
39            case 'D': /* grade was uppercase D */
40            case 'd': /* or lowercase d */
41                ++dCount; /* increment dCount */
42                break; /* exit switch */
43
44            case 'F': /* grade was uppercase F */
45            case 'f': /* or lowercase f */
46                ++fCount; /* increment fCount */
47                break; /* exit switch */
48
49            case '\n': /* ignore newlines, */
50            case '\t': /* tabs, */
51            case ' ': /* and spaces in input */
52                break; /* exit switch */
53

```

Fig. 4.7 | switch example. (Part I of 2.)

```

54     default: /* catch all other characters */
55         printf( "Incorrect letter grade entered." );
56         printf( " Enter a new grade.\n" );
57         break; /* optional; will exit switch anyway */
58     } /* end switch */
59 } /* end while */
60
61 /* output summary of results */
62 printf( "\nTotals for each letter grade are:\n" );
63 printf( "A: %d\n", aCount ); /* display number of A grades */
64 printf( "B: %d\n", bCount ); /* display number of B grades */
65 printf( "C: %d\n", cCount ); /* display number of C grades */
66 printf( "D: %d\n", dCount ); /* display number of D grades */
67 printf( "F: %d\n", fCount ); /* display number of F grades */
68 return 0; /* indicate program ended successfully */
69 } /* end function main */

```

```

Enter the letter grades.
Enter the EOF character to end input.
a
b
c
C
A
d
f
C
E
Incorrect letter grade entered. Enter a new grade.
D
A
b
^Z ——— Not all systems display a representation of the EOF character

Totals for each letter grade are:
A: 3
B: 2
C: 3
D: 2
F: 1

```

Fig. 4.7 | switch example. (Part 2 of 2.)

In the program, the user enters letter grades for a class. In the `while` header (line 19),

```
while ( ( grade = getchar() ) != EOF )
```

the parenthesized assignment (`grade = getchar()`) executes first. The `getchar` function (from `<stdio.h>`) reads one character from the keyboard and stores that character in the integer variable `grade`. Characters are normally stored in variables of type `char`. However, an important feature of C is that characters can be stored in any integer data type because they're usually represented as one-byte integers in the computer. Thus, we can treat a character as either an integer or a character, depending on its use. For example, the statement

```
printf( "The character (%c) has the value %d.\n", 'a', 'a' );
```


uses the conversion specifiers `%c` and `%d` to print the character `a` and its integer value, respectively. The result is

The character (a) has the value 97.

The integer 97 is the character's numerical representation in the computer. Many computers today use the **ASCII (American Standard Code for Information Interchange) character set** in which 97 represents the lowercase letter 'a'. A list of the ASCII characters and their decimal values is presented in Appendix B. Characters can be read with `scanf` by using the conversion specifier `%c`.

Assignments as a whole actually have a value. This value is assigned to the variable on the left side of the `=`. The value of the assignment expression `grade = getchar()` is the character that is returned by `getchar` and assigned to the variable `grade`.

The fact that assignments have values can be useful for setting several variables to the same value. For example,

```
a = b = c = 0;
```

first evaluates the assignment `c = 0` (because the `=` operator associates from right to left). The variable `b` is then assigned the value of the assignment `c = 0` (which is 0). Then, the variable `a` is assigned the value of the assignment `b = (c = 0)` (which is also 0). In the program, the value of the assignment `grade = getchar()` is compared with the value of `EOF` (a symbol whose acronym stands for “end of file”). We use `EOF` (which normally has the value `-1`) as the sentinel value. The user types a system-dependent keystroke combination to mean “end of file”—i.e., “I have no more data to enter.” `EOF` is a symbolic integer constant defined in the `<stdio.h>` header (we'll see how symbolic constants are defined in Chapter 6). If the value assigned to `grade` is equal to `EOF`, the program terminates. We have chosen to represent characters in this program as `ints` because `EOF` has an integer value (again, normally `-1`).



Portability Tip 4.1

The keystroke combinations for entering EOF (end of file) are system dependent.



Portability Tip 4.2

Testing for the symbolic constant EOF rather than `-1` makes programs more portable. The C standard states that EOF is a negative integral value (but not necessarily `-1`). Thus, EOF could have different values on different systems.

On Linux/UNIX/Mac OS X systems, the EOF indicator is entered by typing

```
<Ctrl> d
```

on a line by itself. This notation `<Ctrl> d` means to press the *Enter* key and then simultaneously press both the *Ctrl* key and the *d* key. On other systems, such as Microsoft Windows, the EOF indicator can be entered by typing

```
<Ctrl> z
```

You may also need to press *Enter* on Windows.

The user enters grades at the keyboard. When the *Enter* key is pressed, the characters are read by function `getchar` one character at a time. If the character entered is not equal

to EOF, the switch statement (line 22) is entered. Keyword `switch` is followed by the variable name `grade` in parentheses. This is called the **controlling expression**. The value of this expression is compared with each of the **case labels**. Assume the user has entered the letter C as a grade. C is automatically compared to each case in the switch. If a match occurs (case 'C':), the statements for that case are executed. In the case of the letter C, `cCount` is incremented by 1 (line 36), and the switch statement is exited immediately with the `break` statement.

The `break` statement causes program control to continue with the first statement after the switch statement. The `break` statement is used because the cases in a switch statement would otherwise run together. If `break` is not used anywhere in a switch statement, then each time a match occurs in the statement, the statements for all the remaining cases will be executed. (This feature is rarely useful, although it's perfect for programming the iterative song *The Twelve Days of Christmas*!) If no match occurs, the default case is executed, and an error message is printed.

Each case can have one or more actions. The switch statement is different from all other control statements in that braces are not required around multiple actions in a case of a switch. The general switch multiple-selection statement (using a `break` in each case) is flowcharted in Fig. 4.8. The flowchart makes it clear that each `break` statement at the end of a case causes control to immediately exit the switch statement.




Fig. 4.8 | switch multiple-selection statement with breaks.



Common Programming Error 4.5

Forgetting a break statement when one is needed in a switch statement is a logic error.



Good Programming Practice 4.5

Provide a default case in switch statements. Cases not explicitly tested in a switch are ignored. The default case helps prevent this by focusing the programmer on the need to process exceptional conditions. Sometimes no default processing is needed.



Good Programming Practice 4.6

Although the case clauses and the default case clause in a switch statement can occur in any order, it's considered good programming practice to place the default clause last.



Good Programming Practice 4.7

In a switch statement when the default clause is last, the break statement is not required. Some programmers include this break for clarity and symmetry with other cases.

In the switch statement of Fig. 4.7, the lines

```
case '\n': /* ignore newlines, */
case '\t': /* tabs, */
case ' ': /* and spaces in input */
    break; /* exit switch */
```

cause the program to skip newline, tab and blank characters. Reading characters one at a time can cause some problems. To have the program read the characters, they must be sent to the computer by pressing the *Enter* key. This causes the newline character to be placed in the input after the character we wish to process. Often, this newline character must be specially processed to make the program work correctly. By including the preceding cases in our switch statement, we prevent the error message in the default case from being printed each time a newline, tab or space is encountered in the input.



Common Programming Error 4.6

Not processing newline characters in the input when reading characters one at a time can cause logic errors.



Error-Prevention Tip 4.5

Remember to provide processing capabilities for newline (and possibly other white-space) characters in the input when processing characters one at a time.

Listing several case labels together (such as `case 'D': case 'd':` in Fig. 4.7) simply means that the same set of actions is to occur for either of these cases.

When using the `switch` statement, remember that each individual case can test only a **constant integral expression**—i.e., any combination of character constants and integer constants that evaluates to a constant integer value. A character constant is represented as the specific character in single quotes, such as `'A'`. Characters must be enclosed within single quotes to be recognized as character constants—characters in double quotes are recognized as strings. Integer constants are simply integer values. In our example, we have used character constants. Remember that characters are represented as small integer values.

Notes on Integral Types

Portable languages like C must have flexible data type sizes. Different applications may need integers of different sizes. C provides several data types to represent integers. The range of values for each type depends on the particular computer's hardware. In addition to `int` and `char`, C provides types `short` (an abbreviation of short `int`) and `long` (an abbreviation of long `int`). C specifies that the minimum range of values for short integers is -32768 to $+32767$. For the vast majority of integer calculations, long integers are sufficient. The standard specifies that the minimum range of values for long integers is -2147483648 to $+2147483647$. The standard states that the range of values for an `int` is at least the same as the range for short integers and no larger than the range for long integers. The data type `signed char` can be used to represent integers in the range -128 to $+127$ or any of the characters in the computer's character set.

4.8 do...while Repetition Statement

The `do...while` repetition statement is similar to the `while` statement. In the `while` statement, the loop-continuation condition is tested at the beginning of the loop before the body of the loop is performed. The `do...while` statement tests the loop-continuation condition *after* the loop body is performed. Therefore, the loop body will be executed at least once. When a `do...while` terminates, execution continues with the statement after the `while` clause. It's not necessary to use braces in the `do...while` statement if there is only one statement in the body. However, the braces are usually included to avoid confusion between the `while` and `do...while` statements. For example,

```
while ( condition )
```

is normally regarded as the header to a `while` statement. A `do...while` with no braces around the single-statement body appears as

```
do
    statement
while ( condition );
```

which can be confusing. The last line—`while( condition );`—may be misinterpreted by as a `while` statement containing an empty statement. Thus, to avoid confusion, the `do...while` with one statement is often written as follows:

```
do {
    statement
} while ( condition );
```



Good Programming Practice 4.8

To eliminate the potential for ambiguity, some programmers always include braces in a `do...while` statement, even if the braces are not necessary.



Common Programming Error 4.7

Infinite loops are caused when the loop-continuation condition in a `while`, `for` or `do...while` statement never becomes false. To prevent this, make sure there is not a semicolon immediately after the header of a `while` or `for` statement. In a counter-controlled loop, make sure the control variable is incremented (or decremented) in the loop. In a sentinel-controlled loop, make sure the sentinel value is eventually input.

Figure 4.9 uses a `do...while` statement to print the numbers from 1 to 10. The control variable `counter` is preincremented in the loop-continuation test. Note also the use of the braces to enclose the single-statement body of the `do...while`.

```

1  /* Fig. 4.9: fig04_09.c
2     Using the do/while repetition statement */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8     int counter = 1; /* initialize counter */
9
10    do {
11        printf( "%d ", counter ); /* display counter */
12    } while ( ++counter <= 10 ); /* end do...while */
13
14    return 0; /* indicate program ended successfully */
15 } /* end function main */

```

```
1 2 3 4 5 6 7 8 9 10
```

Fig. 4.9 | `do...while` statement example.

Figure 4.10 shows the `do...while` statement flowchart, which makes it clear that the loop-continuation condition does not execute until after the action is performed at least once.




Fig. 4.10 | Flowcharting the `do...while` repetition statement.

4.9 break and continue Statements

The `break` and `continue` statements are used to alter the flow of control. The `break` statement, when executed in a `while`, `for`, `do...while` or `switch` statement, causes an immediate exit from that statement. Program execution continues with the next statement. Common uses of the `break` statement are to escape early from a loop or to skip the remainder of a `switch` statement (as in Fig. 4.7). Figure 4.11 demonstrates the `break` statement

in a for repetition statement. When the if statement detects that x has become 5, break is executed. This terminates the for statement, and the program continues with the printf after the for. The loop fully executes only four times.

```

1  /* Fig. 4.11: fig04_11.c
2     Using the break statement in a for statement */
3  #include <stdio.h>
4
5  /* function main begins program execution */
6  int main( void )
7  {
8      int x; /* counter */
9
10     /* loop 10 times */
11     for ( x = 1; x <= 10; x++ ) {
12
13         /* if x is 5, terminate loop */
14         if ( x == 5 ) {
15             break; /* break loop only if x is 5 */
16         } /* end if */
17
18         printf( "%d ", x ); /* display value of x */
19     } /* end for */
20
21     printf( "\nBroke out of loop at x == %d\n", x );
22     return 0; /* indicate program ended successfully */
23 } /* end function main */

```

```

1 2 3 4
Broke out of loop at x == 5

```

Fig. 4.11 | Using the break statement in a for statement.

The continue statement, when executed in a while, for or do...while statement, skips the remaining statements in the body of that control statement and performs the next iteration of the loop. In while and do...while statements, the loop-continuation test is evaluated immediately after the continue statement is executed. In the for statement, the increment expression is executed, then the loop-continuation test is evaluated. Earlier, we said that the while statement could be used in most cases to represent the for statement. The one exception occurs when the increment expression in the while statement follows the continue statement. In this case, the increment is not executed before the repetition-continuation condition is tested, and the while does not execute in the same manner as the for. Figure 4.12 uses the continue statement in a for statement to skip the printf statement and begin the next iteration of the loop.

```

1  /* Fig. 4.12: fig04_12.c
2     Using the continue statement in a for statement */
3  #include <stdio.h>
4

```

Fig. 4.12 | Using the continue statement in a for statement. (Part I of 2.)

```

5  /* function main begins program execution */
6  int main( void )
7  {
8      int x; /* counter */
9
10     /* loop 10 times */
11     for ( x = 1; x <= 10; x++ ) {
12
13         /* if x is 5, continue with next iteration of loop */
14         if ( x == 5 ) {
15             continue; /* skip remaining code in loop body */
16         } /* end if */
17
18         printf( "%d ", x ); /* display value of x */
19     } /* end for */
20
21     printf( "\nUsed continue to skip printing the value 5\n" );
22     return 0; /* indicate program ended successfully */
23 } /* end function main */

```

```

1 2 3 4 6 7 8 9 10
Used continue to skip printing the value 5

```

Fig. 4.12 | Using the `continue` statement in a `for` statement. (Part 2 of 2.)



Software Engineering Observation 4.2

Some programmers feel that `break` and `continue` violate the norms of structured programming. The effects of these statements can be achieved by structured programming techniques we'll soon learn, so these programmers do not use `break` and `continue`.



Performance Tip 4.1

The `break` and `continue` statements, when used properly, perform faster than the corresponding structured techniques that we'll soon learn.



Software Engineering Observation 4.3

There is a tension between achieving quality software engineering and achieving the best-performing software. Often one of these goals is achieved at the expense of the other.

4.10 Logical Operators

So far we have studied only simple conditions, such as `counter <= 10`, `total > 1000`, and `number != sentinelValue`. We've expressed these conditions in terms of the relational operators, `>`, `<`, `>=` and `<=`, and the equality operators, `==` and `!=`. Each decision tested precisely one condition. To test multiple conditions in the process of making a decision, we had to perform these tests in separate statements or in nested `if` or `if...else` statements.

C provides logical operators that may be used to form more complex conditions by combining simple conditions. The logical operators are `&&` (logical AND), `||` (logical

OR) and **!** (**logical NOT** also called **logical negation**). We'll consider examples of each of these operators.

Suppose we wish to ensure that two conditions are *both* true before we choose a certain path of execution. In this case, we can use the logical operator **&&** as follows:

```
if ( gender == 1 && age >= 65 )
    ++seniorFemales;
```

This **if** statement contains two simple conditions. The condition `gender == 1` might be evaluated, for example, to determine if a person is a female. The condition `age >= 65` is evaluated to determine if a person is a senior citizen. The two simple conditions are evaluated first because the precedences of `==` and `>=` are both higher than the precedence of `&&`. The **if** statement then considers the combined condition

```
gender == 1 && age >= 65
```

This condition is true if and only if both of the simple conditions are true. Finally, if this combined condition is indeed true, then the count of `seniorFemales` is incremented by 1. If either or both of the simple conditions are false, then the program skips the incrementing and proceeds to the statement following the **if**.

Figure 4.13 summarizes the **&& operator**. The table shows all four possible combinations of zero (false) and nonzero (true) values for `expression1` and `expression2`. Such tables are often called **truth tables**. C evaluates all expressions that include relational operators, equality operators, and/or logical operators to 0 or 1. Although C sets a true value to 1, it accepts *any* nonzero value as true.

expression1	expression2	expression1 && expression2
0	0	0
0	nonzero	0
nonzero	0	0
nonzero	nonzero	1

Fig. 4.13 | Truth table for the logical AND (**&&**) operator.

Now let's consider the **||** (logical OR) operator. Suppose we wish to ensure at some point in a program that either *or* both of two conditions are true before we choose a certain path of execution. In this case, we use the **||** operator as in the following program segment:

```
if ( semesterAverage >= 90 || finalExam >= 90 )
    printf( "Student grade is A\n" );
```

This statement also contains two simple conditions. The condition `semesterAverage >= 90` is evaluated to determine if the student deserves an "A" in the course because of a solid performance throughout the semester. The condition `finalExam >= 90` is evaluated to determine if the student deserves an "A" in the course because of an outstanding performance on the final exam. The **if** statement then considers the combined condition

```
semesterAverage >= 90 || finalExam >= 90
```


and awards the student an “A” if either or both of the simple conditions are true. The message “Student grade is A” is not printed only when both of the simple conditions are false (zero). Figure 4.14 is a truth table for the logical OR operator (| |).

expression1	expression2	expression1 expression2
0	0	0
0	nonzero	1
nonzero	0	1
nonzero	nonzero	1

Fig. 4.14 | Truth table for the logical OR (| |) operator.

The && operator has a higher precedence than | |. Both operators associate from left to right. An expression containing && or | | operators is evaluated only until truth or falsehood is known. Thus, evaluation of the condition

```
gender == 1 && age >= 65
```

will stop if gender is not equal to 1 (i.e., the entire expression is false), and continue if gender is equal to 1 (i.e., the entire expression could still be true if age >= 65). This performance feature for the evaluation of logical AND and logical OR expressions is called **short-circuit evaluation**.



Performance Tip 4.2

In expressions using operator &&, make the condition that is most likely to be false the leftmost condition. In expressions using operator | |, make the condition that is most likely to be true the leftmost condition. This can reduce a program's execution time.

C provides ! (logical negation) to enable a programmer to “reverse” the meaning of a condition. Unlike operators && and | |, which combine two conditions (and are therefore binary operators), the logical negation operator has only a single condition as an operand (and is therefore a unary operator). The logical negation operator is placed before a condition when we're interested in choosing a path of execution if the original condition (without the logical negation operator) is false, such as in the following program segment:

```
if ( !( grade == sentinelValue ) )
    printf( "The next grade is %f\n", grade );
```

The parentheses around the condition `grade == sentinelValue` are needed because the logical negation operator has a higher precedence than the equality operator. Figure 4.15 is a truth table for the logical negation operator.

expression	! expression
0	1
nonzero	0

Fig. 4.15 | Truth table for operator ! (logical negation).

In most cases, you can avoid using logical negation by expressing the condition differently with an appropriate relational operator. For example, the preceding statement may also be written as follows:

```
if ( grade != sentinelValue )
    printf( "The next grade is %f\n", grade );
```

Figure 4.16 shows the precedence and associativity of the operators introduced to this point. The operators are shown from top to bottom in decreasing order of precedence.

Operators	Associativity	Type
++ (<i>postfix</i>) -- (<i>postfix</i>)	right to left	postfix
+ - ! ++ (<i>prefix</i>) -- (<i>prefix</i>) (<i>type</i>)	right to left	unary
* / %	left to right	multiplicative
+ -	left to right	additive
< <= > >=	left to right	relational
== !=	left to right	equality
&&	left to right	logical AND
	left to right	logical OR
?:	right to left	conditional
= += -= *= /= %=	right to left	assignment
,	left to right	comma

Fig. 4.16 | Operator precedence and associativity.

4.11 Confusing Equality (==) and Assignment (=) Operators

There is one type of error that C programmers, no matter how experienced, tend to make so frequently that we felt it was worth a separate section. That error is accidentally swapping the operators == (equality) and = (assignment). What makes these swaps so damaging is the fact that they do not ordinarily cause compilation errors. Rather, statements with these errors ordinarily compile correctly, allowing programs to run to completion while likely generating incorrect results through runtime logic errors.

Two aspects of C cause these problems. One is that any expression in C that produces a value can be used in the decision portion of any control statement. If the value is 0, it's treated as false, and if the value is nonzero, it's treated as true. The second is that assignments in C produce a value, namely the value that is assigned to the variable on the left side of the assignment operator. For example, suppose we intend to write

```
if ( payCode == 4 )
    printf( "You get a bonus!" );
```

but we accidentally write

```
if ( payCode = 4 )
    printf( "You get a bonus!" );
```

The first `if` statement properly awards a bonus to the person whose `paycode` is equal to 4. The second `if` statement—the one with the error—evaluates the assignment expression in the `if` condition. This expression is a simple assignment whose value is the constant 4. Because any nonzero value is interpreted as “true,” the condition in this `if` statement is always true, and not only is the value of `payCode` inadvertently set to 4, but the person always receives a bonus regardless of what the actual `paycode` is!



Common Programming Error 4.8

Using operator `==` for assignment or using operator `=` for equality is a logic error.

Programmers normally write conditions such as `x == 7` with the variable name on the left and the constant on the right. By reversing these terms so that the constant is on the left and the variable name is on the right, as in `7 == x`, the programmer who accidentally replaces the `==` operator with `=` is protected by the compiler. The compiler will treat this as a syntax error, because only a variable name can be placed on the left-hand side of an assignment expression. At least this will prevent the potential devastation of a runtime logic error.

Variable names are said to be *lvalues* (for “left values”) because they can be used on the left side of an assignment operator. Constants are said to be *rvalues* (for “right values”) because they can be used on only the right side of an assignment operator. *Lvalues* can also be used as *rvalues*, but not vice versa.



Good Programming Practice 4.9

When an equality expression has a variable and a constant, as in `x == 1`, some programmers prefer to write the expression with the constant on the left and the variable name on the right (e.g. `1 == x` as protection against the logic error that occurs when you accidentally replace operator `==` with `=`).

The other side of the coin can be equally unpleasant. Suppose you want to assign a value to a variable with a simple statement like

```
x = 1;
```

but instead write

```
x == 1;
```

Here, too, this is not a syntax error. Rather the compiler simply evaluates the conditional expression. If `x` is equal to 1, the condition is true and the expression returns the value 1. If `x` is not equal to 1, the condition is false and the expression returns the value 0. Regardless of what value is returned, there is no assignment operator, so the value is simply lost, and the value of `x` remains unaltered, probably causing an execution-time logic error. Unfortunately, we do not have a handy trick available to help you with this problem! Many compilers, however, will issue a warning on such a statement.



Error-Prevention Tip 4.6

After you write a program, text search it for every `=` and check that it's used properly.

4.12 Structured Programming Summary

Just as architects design buildings by employing the collective wisdom of their profession, so should programmers design programs. Our field is younger than architecture is, and our collective wisdom is considerably sparser. We have learned a great deal in a mere six decades. Perhaps most important, we have learned that structured programming produces programs that are easier (than unstructured programs) to understand and hence are easier to test, debug, modify, and even prove correct in a mathematical sense.

Chapters 3 and 4 have concentrated on C's control statements. Each statement has been presented, flowcharted and discussed separately with examples. Now, we summarize the results of Chapters 3 and 4 and introduce a simple set of rules for the formation and properties of structured programs.

Figure 4.17 summarizes the control statements discussed in Chapters 3 and 4. Small circles are used in the figure to indicate the single entry point and the single exit point of each statement. Connecting individual flowchart symbols arbitrarily can lead to unstructured programs. Therefore, the programming profession has chosen to combine flowchart symbols to form a limited set of control statements, and to build only structured programs by properly combining control statements in two simple ways. For simplicity, only single-entry/single-exit control statements are used—there is only one way to enter and only one way to exit each control statement. Connecting control statements in sequence to form structured programs is simple—the exit point of one control statement is connected directly to the entry point of the next, i.e., the control statements are simply placed one after another in a program—we have called this “control-statement stacking.” The rules for forming structured programs also allow for control statements to be nested.

Figure 4.18 shows the rules for forming structured programs. The rules assume that the rectangle flowchart symbol may be used to indicate any action including input/output. Figure 4.19 shows the simplest flowchart.

Applying the rules of Fig. 4.18 always results in a structured flowchart with a neat, building-block appearance. Repeatedly applying Rule 2 to the simplest flowchart (Fig. 4.19) results in a structured flowchart containing many rectangles in sequence (Fig. 4.20). Notice that Rule 2 generates a stack of control statements; so we call Rule 2 the **stacking rule**.

Rule 3 is called the **nesting rule**. Repeatedly applying Rule 3 to the simplest flowchart results in a flowchart with neatly nested control statements. For example, in Fig. 4.21, the rectangle in the simplest flowchart is first replaced with a double-selection (`if...else`) statement. Then Rule 3 is applied again to both of the rectangles in the double-selection statement, replacing each of these rectangles with double-selection statements. The dashed box around each of the double-selection statements represents the rectangle that was replaced in the original flowchart.

Rule 4 generates larger, more involved, and more deeply nested structures. The flowcharts that emerge from applying the rules in Fig. 4.18 constitute the set of all possible structured flowcharts and hence the set of all possible structured programs.

It's because of the elimination of the `goto` statement that these building blocks never overlap one another. The beauty of the structured approach is that we use only a small number of simple single-entry/single-exit pieces, and we assemble them in only two simple ways. Figure 4.22 shows the kinds of stacked building blocks that emerge from applying Rule 2 and the kinds of nested building blocks that emerge from applying Rule 3. The




Fig. 4.17 | C's single-entry/single-exit sequence, selection and repetition statements.

figure also shows the kind of overlapped building blocks that cannot appear in structured flowcharts (because of the elimination of the goto statement).

Rules for Forming Structured Programs

- 1) Begin with the “simplest flowchart” (Fig. 4.19).
- 2) Any rectangle (action) can be replaced by two rectangles (actions) in sequence.
- 3) Any rectangle (action) can be replaced by any control statement (sequence, if, if...else, switch, while, do...while or for).
- 4) Rules 2 and 3 may be applied as often as you like and in any order.

Fig. 4.18 | Rules for forming structured programs.




Fig. 4.19 | Simplest flowchart.




Fig. 4.20 | Repeatedly applying Rule 2 of Fig. 4.18 to the simplest flowchart.




Fig. 4.21 | Applying Rule 3 of Fig. 4.18 to the simplest flowchart.

If the rules in Fig. 4.18 are followed, an unstructured flowchart (such as that in Fig. 4.23) cannot be created. If you're uncertain whether a particular flowchart is structured, apply the rules of Fig. 4.18 in reverse to try to reduce the flowchart to the simplest flowchart. If you succeed, the original flowchart is structured; otherwise, it's not.

Structured programming promotes simplicity. Bohm and Jacopini showed that only three forms of control are needed:

- Sequence
- Selection
- Repetition




Fig. 4.22 | Stacked, nested and overlapped building blocks.




Fig. 4.23 | An unstructured flowchart.

Sequence is straightforward. Selection is implemented in one of three ways:

- `if` statement (single selection)
- `if...else` statement (double selection)
- `switch` statement (multiple selection)

In fact, it's straightforward to prove that the simple `if` statement is sufficient to provide any form of selection—everything that can be done with the `if...else` statement and the `switch` statement can be implemented with one or more `if` statements.

Repetition is implemented in one of three ways:

- `while` statement

- `do...while` statement
- `for` statement

It's straightforward to prove that the `while` statement is sufficient to provide any form of repetition. Everything that can be done with the `do...while` statement and the `for` statement can be done with the `while` statement.

Combining these results illustrates that any form of control ever needed in a C program can be expressed in terms of only three forms of control:

- sequence
- `if` statement (selection)
- `while` statement (repetition)

And these control statements can be combined in only two ways—stacking and nesting. Indeed, structured programming promotes simplicity.

In Chapters 3 and 4, we discussed how to compose programs from control statements containing actions and decisions. In Chapter 5, we introduce another program structuring unit called the function. We'll learn to compose large programs by combining functions, which, in turn, are composed of control statements. We'll also discuss how using functions promotes software reusability.

Summary

Section 4.2 Repetition Essentials

- Most programs involve repetition, or looping. A loop is a group of instructions the computer executes repeatedly while some loop-continuation condition remains true.
- Counter-controlled repetition is sometimes called definite repetition because we know in advance exactly how many times the loop will execute.
- Sentinel-controlled repetition is sometimes called indefinite repetition because it's not known in advance how many times the loop will execute.
- In counter-controlled repetition, a control variable is used to count the number of repetitions. The control variable is incremented (usually by 1) each time the group of instructions is performed. When the correct number of repetitions has been performed, the loop terminates, and the program resumes execution with the statement after the repetition statement.
- Sentinel values are used to control repetition when the number of repetitions is not known in advance, and the loop includes statements that obtain data each time the loop is performed.
- The sentinel value indicates “end of data.” The sentinel is entered after all regular data items have been supplied to the program. Sentinels must be distinct from regular data items.

Section 4.3 Counter-Controlled Repetition

- Counter-controlled repetition requires the name of a control variable (or loop counter), the initial value of the control variable, the increment (or decrement) by which the control variable is modified each time through the loop, and the condition that tests for the final value of the control variable (i.e., whether looping should continue).

Section 4.4 for Repetition Statement

- The `for` repetition statement handles all the details of counter-controlled repetition.

- When the `for` statement begins executing, its control variable is initialized. Then, the loop-continuation condition is checked. If the condition is true, the loop's body executes. The control variable is then incremented, and the loop begins again with the loop-continuation condition. This process continues until the loop-continuation condition fails.
- The general format of the `for` statement is

```
for ( expression1; expression2; expression3 )
    statement
```

where *expression1* initializes the loop-control variable, *expression2* is the loop-continuation condition, and *expression3* increments the control variable.

- In most cases, the `for` statement can be represented with an equivalent `while` statement as in:

```
expression1;
while ( expression2 ) {
    statement
    expression3;
}
```

- The comma operator guarantees that lists of expressions evaluate from left to right. The value of the entire expression is that of the rightmost expression.
- The three expressions in the `for` statement are optional. If *expression2* is omitted, C assumes that the condition is true, thus creating an infinite loop. One might omit *expression1* if the control variable is initialized elsewhere in the program. *expression3* might be omitted if the increment is calculated by statements in the body of the `for` statement or if no increment is needed.
- The increment expression in the `for` statement acts like a stand-alone C statement at the end of the body of the `for`.
- The two semicolons in the `for` statement are required.

Section 4.5 *for* Statement: Notes and Observations

- The initialization, loop-continuation condition and increment can contain arithmetic expressions.
- The “increment” may be negative (in which case it's really a decrement and the loop actually counts downward).
- If the loop-continuation condition is initially false, the body portion of the loop is not performed. Instead, execution proceeds with the statement following the `for` statement.

Section 4.6 Examples Using the *for* Statement

- Function `pow` performs exponentiation. The function `pow(x, y)` calculates the value of `x` raised to the `y`th power. It takes two arguments of type `double` and returns a `double` value.
- Type `double` is a floating-point type much like `float`, but typically a variable of type `double` can store a value of much greater magnitude with greater precision than `float`.
- The header `<math.h>` should be included whenever a math function such as `pow` is used.
- The conversion specifier `%21.2f` denotes that a floating-point value will be displayed right justified in a field of 21 characters with two digits to the right of the decimal point.
- To left justify a value in a field, place a `-` (minus sign) between the `%` and the field width.

Section 4.7 *switch* Multiple-Selection Statement

- Occasionally, an algorithm will contain a series of decisions in which a variable or expression is tested separately for each of the constant integral values it may assume, and different actions are taken. This is called multiple selection. C provides the `switch` statement to handle this.
- The `switch` statement consists of a series of case labels, an optional `default` case and statements to execute for each case.

- The `getchar` function (from the standard input/output library) reads and returns one character from the keyboard.
- Characters are normally stored in variables of type `char`. Characters can be stored in any integer data type because they're usually represented as one-byte integers in the computer. Thus, we can treat a character as either an integer or a character, depending on its use.
- Many computers today use the ASCII (American Standard Code for Information Interchange) character set in which 97 represents the lowercase letter 'a'.
- Characters can be read with `scanf` by using the conversion specifier `%c`.
- Assignment expressions as a whole actually have a value. This value is assigned to the variable on the left side of the `=`.
- The fact that assignment statements have values can be useful for setting several variables to the same value, as in `a = b = c = 0;`.
- EOF is often used as a sentinel value. EOF is a symbolic integer constant defined in `<stdio.h>`.
- On Linux/UNIX systems and many others, the EOF indicator is entered by typing `<Ctrl> d`. On other systems, such as Microsoft Windows, the EOF indicator can be entered by typing `<Ctrl> z`.
- Keyword `switch` is followed by the controlling expression in parentheses. The value of this expression is compared with each of the case labels. If a match occurs, the statements for that case execute. If no match occurs, the default case executes.
- The `break` statement causes program control to continue with the statement after the `switch`. The `break` statement prevents the cases in a `switch` statement from running together.
- Each case can have one or more actions. The `switch` statement is different from all other control statements in that braces are not required around multiple actions in a case of a `switch`.
- Listing several case labels together simply means that the same set of actions is to occur for any of these cases.
- Remember that the `switch` statement can be used only for testing a constant integral expression—i.e., any combination of character constants and integer constants that evaluates to a constant integer value. A character constant is represented as the specific character in single quotes, such as 'A'. Characters must be enclosed within single quotes to be recognized as character constants. Integer constants are simply integer values.
- C provides several data types to represent integers. The range of integer values for each type depends on the particular computer's hardware. In addition to the types `int` and `char`, C provides types `short` (an abbreviation of short `int`) and `long` (an abbreviation of long `int`). The minimum range of values for short integers is `-32768` to `+32767`. For the vast majority of integer calculations, long integers are sufficient. The standard specifies that the minimum range of values for long integers is `-2147483648` to `+2147483647`. The standard states that the range of values for an `int` is at least the same as the range for short integers and no larger than the range for long integers. The data type `signed char` can be used to represent integers in the range `-128` to `+127` or any of the characters in the computer's character set.

Section 4.8 *do...while Repetition Statement*

- The `do...while` statement tests the loop-continuation condition *after* the loop body is performed. Therefore, the loop body will be executed at least once. When a `do...while` terminates, execution continues with the statement after the `while` clause.

Section 4.9 *break and continue Statements*

- The `break` statement, when executed in a `while`, `for`, `do...while` or `switch` statement, causes immediate exit from that statement. Program execution continues with the next statement.

- The `continue` statement, when executed in a `while`, `for` or `do...while` statement, skips the remaining statements in the body of that control statement and performs the next iteration of the loop. In `while` and `do...while` statements, the loop-continuation test is evaluated immediately after the `continue` statement is executed. In the `for` statement, the increment expression is executed, then the loop-continuation test is evaluated.

Section 4.10 Logical Operators

- Logical operators may be used to form complex conditions by combining simple conditions. The logical operators are `&&` (logical AND), `||` (logical OR) and `!` (logical NOT, or logical negation).
- A condition containing the `&&` (logical AND) operator is true if and only if both of the simple conditions are true.
- C evaluates all expressions that include relational operators, equality operators, and/or logical operators to 0 or 1. Although C sets a true value to 1, it accepts *any* nonzero value as true.
- A condition containing the `||` (logical OR) operator is true if either or both of the simple conditions are true.
- The `&&` operator has a higher precedence than `||`. Both operators associate from left to right.
- An expression containing `&&` or `||` operators is evaluated only until truth or falsehood is known.
- C provides `!` (logical negation) to enable a programmer to “reverse” the meaning of a condition. Unlike the binary operators `&&` and `||`, which combine two conditions, the unary logical negation operator has only a single condition as an operand.
- The logical negation operator is placed before a condition when we’re interested in choosing a path of execution if the original condition (without the logical negation operator) is false.
- In most cases, you can avoid using logical negation by expressing the condition differently with an appropriate relational operator.

Section 4.11 Confusing Equality (==) and Assignment (=) Operators

- Programmers often accidentally swap the operators `==` (equality) and `=` (assignment). What makes these swaps so damaging is that they do not ordinarily cause syntax errors. Rather, statements with these errors ordinarily compile correctly, allowing programs to run to completion while likely generating incorrect results through runtime logic errors.
- Programmers normally write conditions such as `x == 7` with the variable name on the left and the constant on the right. By reversing these terms so that the constant is on the left and the variable name is on the right, as in `7 == x`, the programmer who accidentally replaces the `==` operator with `=` will be protected by the compiler. The compiler will treat this as a syntax error, because only a variable name can be placed on the left-hand side of an assignment statement.
- Variable names are said to be *lvalues* (for “left values”) because they *can* be used on the left side of an assignment operator.
- Constants are said to be *rvalues* (for “right values”) because they can be used *only* on the right side of an assignment operator. *Lvalues* can also be used as *rvalues*, but not vice versa.

Terminology

ASCII (American Standard Code for Information Interchange) character set 110
 case label 111
 char primitive type 109
 comma operator 102
 constant integral expression 112

control variable 98
 controlling expression in a switch 111
 decrement a control variable 99
 definite repetition 98
 final value of a control variable 99
 function prototype 107

- increment a control variable 99
- indefinite repetition 98
- initial value of a control variable 99
- logical AND operator (&&) 116
- logical negation operator (!) 117
- logical OR operator (||) 117
- logical NOT operator (!) 117
- loop-continuation condition 98
- lvalue* (“left value”) 120
- name of a control variable 99
- nesting rule 121
- off-by-one error 101
- pow (power) function 107
- rvalue* (“right value”) 120
- short-circuit evaluation 118
- stacking rule 121
- truth table 117

Self-Review Exercises

- 4.1** Fill in the blanks in each of the following statements.
- Counter-controlled repetition is also known as _____ repetition because it’s known in advance how many times the loop will be executed.
 - Sentinel-controlled repetition is also known as _____ repetition because it’s not known in advance how many times the loop will be executed.
 - In counter-controlled repetition, a(n) _____ is used to count the number of times a group of instructions should be repeated.
 - The _____ statement, when executed in a repetition statement, causes the next iteration of the loop to be performed immediately.
 - The _____ statement, when executed in a repetition statement or a switch, causes an immediate exit from the statement.
 - The _____ is used to test a particular variable or expression for each of the constant integral values it may assume.
- 4.2** State whether the following are *true* or *false*. If the answer is *false*, explain why.
- The default case is required in the switch selection statement.
 - The break statement is required in the default case of a switch selection statement.
 - The expression $(x > y \ \&\& \ a < b)$ is true if either $x > y$ is true or $a < b$ is true.
 - An expression containing the || operator is true if either or both of its operands is true.
- 4.3** Write a statement or a set of statements to accomplish each of the following tasks:
- Sum the odd integers between 1 and 99 using a for statement. Assume the integer variables sum and count have been defined.
 - Print the value 333.546372 in a field width of 15 characters with precisions of 1, 2, 3, 4 and 5. Left justify the output. What are the five values that print?
 - Calculate the value of 2.5 raised to the power of 3 using the pow function. Print the result with a precision of 2 in a field width of 10 positions. What is the value that prints?
 - Print the integers from 1 to 20 using a while loop and the counter variable x. Assume that the variable x has been defined, but not initialized. Print only five integers per line. [Hint: Use the calculation $x \% 5$. When the value of this is 0, print a newline character, otherwise print a tab character.]
 - Repeat Exercise 4.3 (d) using a for statement.
- 4.4** Find the error in each of the following code segments and explain how to correct it.
- ```

x = 1;
while (x <= 10);
 x++;
 }

```
  - ```

for ( y = .1; y != 1.0; y += .1 )
    printf( "%f\n", y );

```

- c)

```
switch ( n ) {
    case 1:
        printf( "The number is 1\n" );
    case 2:
        printf( "The number is 2\n" );
        break;
    default:
        printf( "The number is not 1 or 2\n" );
        break;
}
```
- d) The following code should print the values 1 to 10.
- ```
n = 1;
while (n < 10)
 printf("%d ", n++);
```

## Answers to Self-Review Exercises

**4.1** a) definite. b) indefinite. c) control variable or counter. d) continue. e) break. f) switch selection statement.

- 4.2** a) False. The default case is optional. If no default action is needed, then there is no need for a default case.  
 b) False. The break statement is used to exit the switch statement. The break statement is not required when the default case is the last case.  
 c) False. Both of the relational expressions must be true in order for the entire expression to be true when using the && operator.  
 d) True.

- 4.3** a) 

```
sum = 0;
for (count = 1; count <= 99; count += 2) {
 sum += count;
}
```
- b) 

```
printf("%-15.1f\n", 333.546372); /* prints 333.5 */
printf("%-15.2f\n", 333.546372); /* prints 333.55 */
printf("%-15.3f\n", 333.546372); /* prints 333.546 */
printf("%-15.4f\n", 333.546372); /* prints 333.5464 */
printf("%-15.5f\n", 333.546372); /* prints 333.54637 */
```
- c) 

```
printf("%10.2f\n", pow(2.5, 3)); /* prints 15.63 */
```
- d) 

```
x = 1;
while (x <= 20) {
 printf("%d", x);
 if (x % 5 == 0) {
 printf("\n");
 }
 else {
 printf("\t");
 }
 x++;
}
```

or

```

x = 1;
while (x <= 20) {
 if (x % 5 == 0) {
 printf("%d\n", x++);
 }
 else {
 printf("%d\t", x++);
 }
}

```

or

```

x = 0;
while (++x <= 20) {
 if (x % 5 == 0) {
 printf("%d\n", x);
 }
 else {
 printf("%d\t", x);
 }
}

```

```

e) for (x = 1; x <= 20; x++) {
 printf("%d", x);
 if (x % 5 == 0) {
 printf("\n");
 }
 else {
 printf("\t");
 }
}

```

or

```

for (x = 1; x <= 20; x++) {
 if (x % 5 == 0) {
 printf("%d\n", x);
 }
 else {
 printf("%d\t", x);
 }
}

```

- 4.4** a) Error: The semicolon after the while header causes an infinite loop.  
Correction: Replace the semicolon with a { or remove both the ; and the }.
- b) Error: Using a floating-point number to control a for repetition statement.  
Correction: Use an integer, and perform the proper calculation to get the values you desire.

```

for (y = 1; y != 10; y++)
 printf("%f\n", (float) y / 10);

```

- c) Error: Missing break statement in the statements for the first case.

Correction: Add a break statement at the end of the statements for the first case. This is not necessarily an error if you want the statement of case 2: to execute every time the case 1: statement executes.

- d) Error: Improper relational operator used in the while repetition-continuation condition.

Correction: Use <= rather than <.

## Exercises

**4.5** Find the error in each of the following. (*Note:* There may be more than one error.)

- a) `For ( x = 100, x >= 1, x++ )`

```
printf("%d\n", x);
```

- b) The following code should print whether a given integer is odd or even:

```
switch (value % 2) {
 case 0:
 printf("Even integer\n");
 case 1:
 printf("Odd integer\n");
}
```

- c) The following code should input an integer and a character and print them. Assume the user types as input 100 A.

```
scanf("%d", &intVal);
charVal = getchar();
printf("Integer: %d\nCharacter: %c\n", intVal, charVal);
```

- d) `for ( x = .000001; x == .0001; x += .000001 ) {`  
`printf( "%.7f\n", x );`

```
}
```

- e) The following code should output the odd integers from 999 to 1:

```
for (x = 999; x >= 1; x += 2) {
 printf("%d\n", x);
}
```

- f) The following code should output the even integers from 2 to 100:

```
counter = 2;

Do {
 if (counter % 2 == 0) {
 printf("%d\n", counter);
 }

 counter += 2;
} While (counter < 100);
```

- g) The following code should sum the integers from 100 to 150 (assume total is initialized to 0):

```
for (x = 100; x <= 150; x++); {
 total += x;
}
```

**4.6** State which values of the control variable x are printed by each of the following for statements:

- a) `for ( x = 2; x <= 13; x += 2 ) {`  
`printf( "%d\n", x );`  
`}`



- b) `for ( x = 5; x <= 22; x += 7 ) {  
    printf( "%d\n", x );  
}`
- c) `for ( x = 3; x <= 15; x += 3 ) {  
    printf( "%d\n", x );  
}`
- d) `for ( x = 1; x <= 5; x += 7 ) {  
    printf( "%d\n", x );  
}`
- e) `for ( x = 12; x >= 2; x -= 3 ) {  
    printf( "%d\n", x );  
}`

**4.7** Write for statements that print the following sequences of values:

- a) 1, 2, 3, 4, 5, 6, 7
- b) 3, 8, 13, 18, 23
- c) 20, 14, 8, 2, -4, -10
- d) 19, 27, 35, 43, 51

**4.8** What does the following program do?

```
1 #include <stdio.h>
2
3 /* function main begins program execution */
4 int main(void)
5 {
6 int x;
7 int y;
8 int i;
9 int j;
10
11 /* prompt user for input */
12 printf("Enter two integers in the range 1-20: ");
13 scanf("%d%d", &x, &y); /* read values for x and y */
14
15 for (i = 1; i <= y; i++) { /* count from 1 to y */
16
17 for (j = 1; j <= x; j++) { /* count from 1 to x */
18 printf("@"); /* output @ */
19 } /* end inner for */
20
21 printf("\n"); /* begin new line */
22 } /* end outer for */
23
24 return 0; /* indicate program ended successfully */
25 } /* end function main */
```

**4.9** (*Sum a Sequence of Integers*) Write a program that sums a sequence of integers. Assume that the first integer read with `scanf` specifies the number of values remaining to be entered. Your program should read only one value each time `scanf` is executed. A typical input sequence might be

5 100 200 300 400 500

where the 5 indicates that the subsequent five values are to be summed.

**4.10** (*Average a Sequence of Integers*) Write a program that calculates and prints the average of several integers. Assume the last value read with `scanf` is the sentinel 9999. A typical input sequence might be



| Product number | Retail price |
|----------------|--------------|
| 1              | \$ 2.98      |
| 2              | \$ 4.50      |
| 3              | \$ 9.98      |
| 4              | \$ 4.49      |
| 5              | \$ 6.87      |

Write a program that reads a series of pairs of numbers as follows:

- a) Product number
- b) Quantity sold for one day

Your program should use a switch statement to help determine the retail price for each product. Your program should calculate and display the total retail value of all products sold last week.

**4.20 (Truth Tables)** Complete the following truth tables by filling in each blank with 0 or 1.

| Condition1 | Condition2 | Condition1 && Condition2 |
|------------|------------|--------------------------|
| 0          | 0          | 0                        |
| 0          | nonzero    | 0                        |
| nonzero    | 0          | _____                    |
| nonzero    | nonzero    | _____                    |

| Condition1 | Condition2 | Condition1    Condition2 |
|------------|------------|--------------------------|
| 0          | 0          | 0                        |
| 0          | nonzero    | 1                        |
| nonzero    | 0          | _____                    |
| nonzero    | nonzero    | _____                    |

| Condition1 | !Condition1 |
|------------|-------------|
| 0          | 1           |
| nonzero    | _____       |

**4.21** Rewrite the program of Fig. 4.2 so that the initialization of the variable counter is done in the definition rather than in the for statement.

**4.22 (Average Grade)** Modify the program of Fig. 4.7 so that it calculates the average grade for the class.

**4.23 (Calculating the Compound Interest with Integers)** Modify the program of Fig. 4.6 so that it uses only integers to calculate the compound interest. [Hint: Treat all monetary amounts as inte-

gral numbers of pennies. Then “break” the result into its dollar portion and cents portion by using the division and remainder operations, respectively. Insert a period.]

**4.24** Assume  $i = 1$ ,  $j = 2$ ,  $k = 3$  and  $m = 2$ . What does each of the following statements print?

- a) `printf( "%d", i == 1 );`
- b) `printf( "%d", j == 3 );`
- c) `printf( "%d", i >= 1 && j < 4 );`
- d) `printf( "%d", m <= 99 && k < m );`
- e) `printf( "%d", j >= i || k == m );`
- f) `printf( "%d", k + m < j || 3 - j >= k );`
- g) `printf( "%d", !m );`
- h) `printf( "%d", !( j - m ) );`
- i) `printf( "%d", !( k > m ) );`
- j) `printf( "%d", !( j > k ) );`

**4.25** (*Table of Decimal, Binary, Octal and Hexadecimal Equivalents*) Write a program that prints a table of the binary, octal and hexadecimal equivalents of the decimal numbers in the range 1 through 256. If you’re not familiar with these number systems, read Appendix C before you attempt this exercise.

**4.26** (*Calculating the Value of  $\pi$* ) Calculate the value of  $\pi$  from the infinite series

$$\pi = 4 - \frac{4}{3} + \frac{4}{5} - \frac{4}{7} + \frac{4}{9} - \frac{4}{11} + \cdots$$

Print a table that shows the value of  $\pi$  approximated by one term of this series, by two terms, by three terms, and so on. How many terms of this series do you have to use before you first get 3.14? 3.141? 3.1415? 3.14159?

**4.27** (*Pythagorean Triples*) A right triangle can have sides that are all integers. The set of three integer values for the sides of a right triangle is called a Pythagorean triple. These three sides must satisfy the relationship that the sum of the squares of two of the sides is equal to the square of the hypotenuse. Find all Pythagorean triples for side1, side2, and the hypotenuse all no larger than 500. Use a triple-nested for loop that simply tries all possibilities. This is an example of “brute-force” computing. It’s not aesthetically pleasing to many people. But there are many reasons why these techniques are important. First, with computing power increasing at such a phenomenal pace, solutions that would have taken years or even centuries of computer time to produce with the technology of just a few years ago can now be produced in hours, minutes or even seconds. Recent microprocessor chips can process a billion instructions per second! Second, as you’ll learn in more advanced computer science courses, there are large numbers of interesting problems for which there is no known algorithmic approach other than sheer brute force. We investigate many kinds of problem-solving methodologies in this book. We’ll consider many brute-force approaches to various interesting problems.

**4.28** (*Calculating Weekly Pay*) A company pays its employees as managers (who receive a fixed weekly salary), hourly workers (who receive a fixed hourly wage for up to the first 40 hours they work and “time-and-a-half”—i.e., 1.5 times their hourly wage—for overtime hours worked), commission workers (who receive \$250 plus 5.7% of their gross weekly sales), or pieceworkers (who receive a fixed amount of money for each of the items they produce—each pieceworker in this company works on only one type of item). Write a program to compute the weekly pay for each employee. You do not know the number of employees in advance. Each type of employee has its own pay code: Managers have paycode 1, hourly workers have code 2, commission workers have code 3 and pieceworkers have code 4. Use a `switch` to compute each employee’s pay based on that employee’s paycode. Within the `switch`, prompt the user (i.e., the payroll clerk) to enter the appropriate facts your program needs to calculate each employee’s pay based on that employee’s paycode.

**4.29 (De Morgan's Laws)** In this chapter, we discussed the logical operators `&&`, `||`, and `!`. De Morgan's Laws can sometimes make it more convenient for us to express a logical expression. These laws state that the expression `!(condition1 && condition2)` is logically equivalent to the expression `!(condition1 || !condition2)`. Also, the expression `!(condition1 || condition2)` is logically equivalent to the expression `!(condition1 && !condition2)`. Use De Morgan's Laws to write equivalent expressions for each of the following, and then write a program to show that both the original expression and the new expression in each case are equivalent.

- a) `!( x < 5 ) && !( y >= 7 )`
- b) `!( a == b ) || !( g != 5 )`
- c) `!( ( x <= 8 ) && ( y > 4 ) )`
- d) `!( ( i > 4 ) || ( j <= 6 ) )`

**4.30 (Replacing switch with if...else)** Rewrite the program of Fig. 4.7 by replacing the switch statement with a nested `if...else` statement; be careful to deal with the default case properly. Then rewrite this new version by replacing the nested `if...else` statement with a series of `if` statements; here, too, be careful to deal with the default case properly (this is more difficult than in the nested `if...else` version). This exercise demonstrates that switch is a convenience and that any switch statement can be written with only single-selection statements.

**4.31 (Diamond Printing Program)** Write a program that prints the following diamond shape. You may use `printf` statements that print either a single asterisk (`*`) or a single blank. Maximize your use of repetition (with nested `for` statements) and minimize the number of `printf` statements.

```

 *
 **

 *
```

**4.32 (Modified Diamond Printing Program)** Modify the program you wrote in Exercise 4.31 to read an odd number in the range 1 to 19 to specify the number of rows in the diamond. Your program should then display a diamond of the appropriate size.

**4.33 (Roman Numeral Equivalent of Decimal Values)** Write a program that prints a table of all the Roman numeral equivalents of the decimal numbers in the range 1 to 100.

**4.34** Describe the process you would use to replace a `do...while` loop with an equivalent `while` loop. What problem occurs when you try to replace a `while` loop with an equivalent `do...while` loop? Suppose you have been told that you must remove a `while` loop and replace it with a `do...while`. What additional control statement would you need to use and how would you use it to ensure that the resulting program behaves exactly as the original?

**4.35** A criticism of the `break` statement and the `continue` statement is that each is unstructured. Actually, `break` statements and `continue` statements can always be replaced by structured statements, although doing so can be awkward. Describe in general how you would remove any `break` statement from a loop in a program and replace that statement with some structured equivalent. [Hint: The `break` statement leaves a loop from within the body of the loop. The other way to leave is by failing the loop-continuation test. Consider using in the loop-continuation test a second test that indicates "early exit because of a 'break' condition."] Use the technique you developed here to remove the `break` statement from the program of Fig. 4.11.

**4.36** What does the following program segment do?

```

1 for (i = 1; i <= 5; i++) {
2 for (j = 1; j <= 3; j++) {
3 for (k = 1; k <= 4; k++)
4 printf("*");
5 printf("\n");
6 }
7 printf("\n");
8 }

```

**4.37** Describe in general how you would remove any `continue` statement from a loop in a program and replace that statement with some structured equivalent. Use the technique you developed here to remove the `continue` statement from the program of Fig. 4.12.

## Making a Difference

**4.38** (*World Population Growth*) World population has grown considerably over the centuries. Continued growth could eventually challenge the limits of breathable air, drinkable water, arable cropland and other limited resources. There is evidence that growth has been slowing in recent years and that world population could peak some time this century, then start to decline.

For this exercise, research world population growth issues online. *Be sure to investigate various viewpoints.* Get estimates for the current world population and its growth rate (the percentage by which it's likely to increase this year). Write a program that calculates world population growth each year for the next 75 years, *using the simplifying assumption that the current growth rate will stay constant.* Print the results in a table. The first column should display the year from year 1 to year 75. The second column should display the anticipated world population at the end of that year. The third column should display the numerical increase in the world population that would occur that year. Using your results, determine the year in which the population would be double what it is today, if this year's growth rate were to persist.

**4.39** (*Tax Plan Alternatives; The "FairTax"*) There are many proposals to make taxation fairer. Check out the FairTax initiative in the United States at

[www.fairtax.org/site/PageServer?pagename=calculator](http://www.fairtax.org/site/PageServer?pagename=calculator)

Research how the proposed FairTax works. One suggestion is to eliminate income taxes and most other taxes in favor of a 23% consumption tax on all products and services that you buy. Some FairTax opponents question the 23% figure and say that because of the way the tax is calculated, it would be more accurate to say the rate is 30%—check this carefully. Write a program that prompts the user to enter expenses in various expense categories they have (e.g., housing, food, clothing, transportation, education, health care, vacations), then prints the estimated FairTax that person would pay.



# 5

## C Functions

*Form ever follows function.*

—Louis Henri Sullivan

*E pluribus unum.*  
(*One composed of many.*)

—Virgil

*O! call back yesterday, bid time return.*

—William Shakespeare

*Answer me in one word.*

—William Shakespeare

*There is a point at which  
methods devour themselves.*

—Frantz Fanon

### Objectives

In this chapter, you'll learn:

- To construct programs modularly from small pieces called functions.
- Common math functions in the C Standard Library.
- To create new functions.
- The mechanisms used to pass information between functions.
- How the function call/return mechanism is supported by the function call stack and activation records.
- Simulation techniques using random number generation.
- How to write and use functions that call themselves.



- |                                                       |                                                        |
|-------------------------------------------------------|--------------------------------------------------------|
| <b>5.1</b> Introduction                               | <b>5.9</b> Calling Functions By Value and By Reference |
| <b>5.2</b> Program Modules in C                       | <b>5.10</b> Random Number Generation                   |
| <b>5.3</b> Math Library Functions                     | <b>5.11</b> Example: A Game of Chance                  |
| <b>5.4</b> Functions                                  | <b>5.12</b> Storage Classes                            |
| <b>5.5</b> Function Definitions                       | <b>5.13</b> Scope Rules                                |
| <b>5.6</b> Function Prototypes                        | <b>5.14</b> Recursion                                  |
| <b>5.7</b> Function Call Stack and Activation Records | <b>5.15</b> Example Using Recursion: Fibonacci Series  |
| <b>5.8</b> Headers                                    | <b>5.16</b> Recursion vs. Iteration                    |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 5.1 Introduction

Most computer programs that solve real-world problems are much larger than the programs presented in the first few chapters. Experience has shown that the best way to develop and maintain a large program is to construct it from smaller pieces or **modules**, each of which is more manageable than the original program. This technique is called **divide and conquer**. This chapter describes the features of the C language that facilitate the design, implementation, operation and maintenance of large programs.

## 5.2 Program Modules in C

Modules in C are called **functions**. C programs are typically written by combining new functions you write with “prepackaged” functions available in the **C Standard Library**. We discuss both kinds of functions in this chapter. The C Standard Library provides a rich collection of functions for performing common mathematical calculations, string manipulations, character manipulations, input/output, and many other useful operations. This makes your job easier, because these functions provide many of the capabilities you need.



### Good Programming Practice 5.1

*Familiarize yourself with the rich collection of functions in the C Standard Library.*



### Software Engineering Observation 5.1

*Avoid reinventing the wheel. When possible, use C Standard Library functions instead of writing new functions. This can reduce program development time.*



### Portability Tip 5.1


*Using the functions in the C Standard Library helps make programs more portable.*

Although the Standard Library functions are technically not a part of the C language, they're provided with standard C systems. The functions `printf`, `scanf` and `pow` that we've used in previous chapters are Standard Library functions.



You can write functions to define specific tasks that may be used at many points in a program. These are sometimes referred to as **programmer-defined functions**. The actual statements defining the function are written only once, and the statements are hidden from other functions.

Functions are **invoked** by a **function call**, which specifies the function name and provides information (as **arguments**) that the called function needs to perform its designated task. A common analogy for this is the hierarchical form of management. A boss (the **calling function** or **caller**) asks a worker (the **called function**) to perform a task and report back when the task is done (Fig. 5.1). For example, a function needing to display information on the screen calls the worker function `printf` to perform that task, then `printf` displays the information and reports back—or **returns**—to the calling function when its task is completed. The boss function does not know how the worker function performs its designated tasks. The worker may call other worker functions, and the boss will be unaware of this. We'll soon see how this “hiding” of implementation details promotes good software engineering. Figure 5.1 shows the `main` function communicating with several worker functions in a hierarchical manner. Note that `worker1` acts as a boss function to `worker4` and `worker5`. Relationships among functions may differ from the hierarchical structure shown in this figure.



**Fig. 5.1** | Hierarchical boss function/worker function relationship.

## 5.3 Math Library Functions

Math library functions allow you to perform certain common mathematical calculations. We use various math library functions here to introduce the concept of functions. Later in the book, we'll discuss many of the other functions in the C Standard Library.

Functions are normally used in a program by writing the name of the function followed by a left parenthesis followed by the **argument** (or a comma-separated list of arguments) of the function followed by a right parenthesis. For example, a programmer desiring to calculate and print the square root of 900.0 might write

```
printf("%.2f", sqrt(900.0));
```

When this statement executes, the math library function `sqrt` is called to calculate the square root of the number contained in the parentheses (900.0). The number 900.0 is the

argument of the `sqrt` function. The preceding statement would print 30.00. The `sqrt` function takes an argument of type `double` and returns a result of type `double`. All functions in the math library that return floating point values return the data type `double`. Note that `double` values, like `float` values, can be output using the `%f` conversion specification.



#### Error-Prevention Tip 5.1

Include the math header by using the preprocessor directive `#include <math.h>` when using functions in the math library.

Function arguments may be constants, variables, or expressions. If `c1 = 13.0`, `d = 3.0` and `f = 4.0`, then the statement

```
printf("%.2f", sqrt(c1 + d * f));
```

calculates and prints the square root of  $13.0 + 3.0 * 4.0 = 25.0$ , namely 5.00.

Some C math library functions are summarized in Fig. 5.2. In the figure, the variables `x` and `y` are of type `double`.

| Function                  | Description                                            | Example                                                                                                     |
|---------------------------|--------------------------------------------------------|-------------------------------------------------------------------------------------------------------------|
| <code>sqrt( x )</code>    | square root of $x$                                     | <code>sqrt( 900.0 )</code> is 30.0<br><code>sqrt( 9.0 )</code> is 3.0                                       |
| <code>exp( x )</code>     | exponential function $e^x$                             | <code>exp( 1.0 )</code> is 2.718282<br><code>exp( 2.0 )</code> is 7.389056                                  |
| <code>log( x )</code>     | natural logarithm of $x$ (base $e$ )                   | <code>log( 2.718282 )</code> is 1.0<br><code>log( 7.389056 )</code> is 2.0                                  |
| <code>log10( x )</code>   | logarithm of $x$ (base 10)                             | <code>log10( 1.0 )</code> is 0.0<br><code>log10( 10.0 )</code> is 1.0<br><code>log10( 100.0 )</code> is 2.0 |
| <code>fabs( x )</code>    | absolute value of $x$                                  | <code>fabs( 13.5 )</code> is 13.5<br><code>fabs( 0.0 )</code> is 0.0<br><code>fabs( -13.5 )</code> is 13.5  |
| <code>ceil( x )</code>    | rounds $x$ to the smallest integer not less than $x$   | <code>ceil( 9.2 )</code> is 10.0<br><code>ceil( -9.8 )</code> is -9.0                                       |
| <code>floor( x )</code>   | rounds $x$ to the largest integer not greater than $x$ | <code>floor( 9.2 )</code> is 9.0<br><code>floor( -9.8 )</code> is -10.0                                     |
| <code>pow( x, y )</code>  | $x$ raised to power $y$ ( $x^y$ )                      | <code>pow( 2, 7 )</code> is 128.0<br><code>pow( 9, .5 )</code> is 3.0                                       |
| <code>fmod( x, y )</code> | remainder of $x/y$ as a floating-point number          | <code>fmod( 13.657, 2.333 )</code> is 1.992                                                                 |
| <code>sin( x )</code>     | trigonometric sine of $x$ ( $x$ in radians)            | <code>sin( 0.0 )</code> is 0.0                                                                              |
| <code>cos( x )</code>     | trigonometric cosine of $x$ ( $x$ in radians)          | <code>cos( 0.0 )</code> is 1.0                                                                              |
| <code>tan( x )</code>     | trigonometric tangent of $x$ ( $x$ in radians)         | <code>tan( 0.0 )</code> is 0.0                                                                              |

**Fig. 5.2** | Commonly used math library functions.

## 5.4 Functions

Functions allow you to modularize a program. All variables defined in function definitions are **local variables**—they’re known only in the function in which they’re defined. Most functions have a list of **parameters** that provide the means for communicating information between functions. A function’s parameters are also local variables of that function.



### Software Engineering Observation 5.2

*In programs containing many functions, main is often implemented as a group of calls to functions that perform the bulk of the program’s work.*

There are several motivations for “functionalizing” a program. The divide-and-conquer approach makes program development more manageable. Another motivation is **software reusability**—using existing functions as building-blocks to create new programs. Software reusability is a major factor in the object-oriented programming movement that you’ll learn more about when you study languages derived from C, such as C++, Java and C# (pronounced “C sharp”). With good function naming and definition, programs can be created from standardized functions that accomplish specific tasks, rather than being built by using customized code. This is known as **abstraction**. We use abstraction each time we use standard library functions like `printf`, `scanf` and `pow`. A third motivation is to avoid repeating code in a program. Packaging code as a function allows the code to be executed from several locations in a program simply by calling the function.



### Software Engineering Observation 5.3

*Each function should be limited to performing a single, well-defined task, and the function name should express that task. This facilitates abstraction and promotes software reusability.*



### Software Engineering Observation 5.4

*If you cannot choose a concise name that expresses what the function does, it’s possible that your function is attempting to perform too many diverse tasks. It’s usually best to break such a function into several smaller functions—sometimes called decomposition.*

## 5.5 Function Definitions

Each program we’ve presented has consisted of a function called `main` that called standard library functions to accomplish its tasks. We now consider how to write custom functions. Consider a program that uses a function `square` to calculate and print the squares of the integers from 1 to 10 (Fig. 5.3).



### Good Programming Practice 5.2

*Place a blank line between function definitions to separate the functions and enhance program readability.*

```
1 /* Fig. 5.3: fig05_03.c
2 Creating and using a programmer-defined function */
3 #include <stdio.h>
```

```

4
5 int square(int y); /* function prototype */
6
7 /* function main begins program execution */
8 int main(void)
9 {
10 int x; /* counter */
11
12 /* loop 10 times and calculate and output square of x each time */
13 for (x = 1; x <= 10; x++) {
14 printf("%d ", square(x)); /* function call */
15 } /* end for */
16
17 printf("\n");
18 return 0; /* indicates successful termination */
19 } /* end main */
20
21 /* square function definition returns square of parameter */
22 int square(int y) /* y is a copy of argument to function */
23 {
24 return y * y; /* returns square of y as an int */
25 } /* end function square */

```

```
1 4 9 16 25 36 49 64 81 100
```

**Fig. 5.3** | Using a programmer-defined function. (Part 2 of 2.)

Function square is **invoked** or **called** in main within the printf statement (line 14)

```
printf("%d ", square(x)); /* function call */
```

Function square receives a copy of the value of x in the parameter y (line 22). Then square calculates y \* y (line 24). The result is passed back to function printf in main where square was invoked (line 14), and printf displays the result. This process is repeated 10 times using the for repetition statement.

The definition of function square shows that square expects an integer parameter y. The keyword int preceding the function name (line 22) indicates that square returns an integer result. The return statement in square passes the result of the calculation back to the calling function.

Line 5

```
int square(int y); /* function prototype */
```

is a **function prototype**. The int in parentheses informs the compiler that square expects to receive an integer value from the caller. The int to the left of the function name square informs the compiler that square returns an integer result to the caller. The compiler refers to the function prototype to check that calls to square (line 14) contain the correct return type, the correct number of arguments, the correct argument types, and that the arguments are in the correct order. Function prototypes are discussed in detail in Section 5.6.

The format of a function definition is

```
return-value-type function-name(parameter-list)
{
 definitions
 statements
}
```

The *function-name* is any valid identifier. The *return-value-type* is the data type of the result returned to the caller. The *return-value-type* `void` indicates that a function does not return a value. Together, the *return-value-type*, *function-name* and *parameter-list* are sometimes referred to as the function **header**.



### Common Programming Error 5.1

*Forgetting to return a value from a function that is supposed to return a value can lead to unexpected errors. The C standard states that the result of this omission is undefined.*



### Common Programming Error 5.2

*Returning a value from a function with a void return type is a compilation error.*

The *parameter-list* is a comma-separated list that specifies the parameters received by the function when it's called. If a function does not receive any values, *parameter-list* is `void`. A type must be listed explicitly for each parameter.



### Common Programming Error 5.3

*Specifying function parameters of the same type as `double x, y` instead of `double x, double y` results in a compilation error.*



### Common Programming Error 5.4

*Placing a semicolon after the right parenthesis enclosing the parameter list of a function definition is a syntax error.*



### Common Programming Error 5.5

*Defining a parameter again as a local variable in a function is a compilation error.*



### Good Programming Practice 5.3

*Although it's not incorrect to do so, do not use the same names for a function's arguments and the corresponding parameters in the function definition. This helps avoid ambiguity.*

The *definitions* and *statements* within braces form the **function body**. The function body is also referred to as a **block**. Variables can be declared in any block, and blocks can be nested. *A function cannot be defined inside another function.*



### Common Programming Error 5.6

*Defining a function inside another function is a syntax error.*



### Good Programming Practice 5.4

*Choosing meaningful function names and meaningful parameter names makes programs more readable and helps avoid excessive use of comments.*

**Software Engineering Observation 5.5**

*A function should generally be no longer than one page. Better yet, functions should generally be no longer than half a page. Small functions promote software reusability.*

**Software Engineering Observation 5.6**

*Programs should be written as collections of small functions. This makes programs easier to write, debug, maintain and modify.*

**Software Engineering Observation 5.7**

*A function requiring a large number of parameters may be performing too many tasks. Consider dividing the function into smaller functions that perform the separate tasks. The function header should fit on one line if possible.*

**Software Engineering Observation 5.8**

*The function prototype, function header and function calls should all agree in the number, type, and order of arguments and parameters, and in the type of return value.*

There are three ways to return control from a called function to the point at which a function was invoked. If the function does not return a result, control is returned simply when the function-ending right brace is reached, or by executing the statement

```
return;
```

If the function does return a result, the statement

```
return expression;
```

returns the value of *expression* to the caller.

**Function maximum**

Our second example uses a programmer-defined function `maximum` to determine and return the largest of three integers (Fig. 5.4). The three integers are input with `scanf`<sup>1</sup> (line 15). Next, the integers are passed to `maximum` (line 19), which determines the largest integer. This value is returned to main by the return statement in `maximum` (line 37). The value returned is then printed in the `printf` statement (line 19).

```
1 /* Fig. 5.4: fig05_04.c
2 Finding the maximum of three integers */
3 #include <stdio.h>
4
5 int maximum(int x, int y, int z); /* function prototype */
6
```

**Fig. 5.4** | Finding the maximum of three integers. (Part 1 of 2.)

1. Many C library functions, like `scanf`, return values indicating whether they performed their task successfully. In production code, you should test these return values to ensure that your program is operating properly. Read the documentation for each library function you use to learn about its return values. The site [wpo1lock.com/CPlus/PrintfRef.htm#scanfRetCode](http://wpo1lock.com/CPlus/PrintfRef.htm#scanfRetCode) discusses how to process return values from function `scanf`.

```

7 /* function main begins program execution */
8 int main(void)
9 {
10 int number1; /* first integer */
11 int number2; /* second integer */
12 int number3; /* third integer */
13
14 printf("Enter three integers: ");
15 scanf("%d%d%d", &number1, &number2, &number3);
16
17 /* number1, number2 and number3 are arguments
18 to the maximum function call */
19 printf("Maximum is: %d\n", maximum(number1, number2, number3));
20 return 0; /* indicates successful termination */
21 } /* end main */
22
23 /* Function maximum definition */
24 /* x, y and z are parameters */
25 int maximum(int x, int y, int z)
26 {
27 int max = x; /* assume x is largest */
28
29 if (y > max) { /* if y is larger than max, assign y to max */
30 max = y;
31 } /* end if */
32
33 if (z > max) { /* if z is larger than max, assign z to max */
34 max = z;
35 } /* end if */
36
37 return max; /* max is largest value */
38 } /* end function maximum */

```

```

Enter three integers: 22 85 17
Maximum is: 85

```

```

Enter three integers: 85 22 17
Maximum is: 85

```

```

Enter three integers: 22 17 85
Maximum is: 85

```

**Fig. 5.4** | Finding the maximum of three integers. (Part 2 of 2.)

## 5.6 Function Prototypes

One of the most important features of C is the function prototype. This feature was borrowed by the C standard committee from the developers of C++. A function prototype tells the compiler the type of data returned by the function, the number of parameters the function expects to receive, the types of the parameters, and the order in which these parameters are expected. The compiler uses function prototypes to validate function calls.

Previous versions of C did not perform this kind of checking, so it was possible to call functions improperly without the compiler detecting the errors. Such calls could result in fatal execution-time errors or nonfatal errors that caused subtle, difficult-to-detect logic errors. Function prototypes correct this deficiency.



### Good Programming Practice 5.5

*Include function prototypes for all functions to take advantage of C's type-checking capabilities. Use `#include` preprocessor directives to obtain function prototypes for the standard library functions from the headers for the appropriate libraries, or to obtain headers containing function prototypes for functions developed by you and/or your group members.*

The function prototype for `maximum` in Fig. 5.4 (line 5) is

```
int maximum(int x, int y, int z); /* function prototype */
```

This function prototype states that `maximum` takes three arguments of type `int` and returns a result of type `int`. Notice that the function prototype is the same as the first line of the function definition of `maximum`.



### Good Programming Practice 5.6

*Parameter names are sometimes included in function prototypes (our preference) for documentation purposes. The compiler ignores these names.*



### Common Programming Error 5.7

*Forgetting the semicolon at the end of a function prototype is a syntax error.*

A function call that does not match the function prototype is a compilation error. An error is also generated if the function prototype and the function definition disagree. For example, in Fig. 5.4, if the function prototype had been written

```
void maximum(int x, int y, int z);
```

the compiler would generate an error because the `void` return type in the function prototype would differ from the `int` return type in the function header.

Another important feature of function prototypes is the **coercion of arguments**, i.e., the forcing of arguments to the appropriate type. For example, the math library function `sqrt` can be called with an integer argument even though the function prototype in `<math.h>` specifies a `double` argument, and the function will still work correctly. The statement

```
printf("%.3f\n", sqrt(4));
```

correctly evaluates `sqrt( 4 )`, and prints the value 2.000. The function prototype causes the compiler to convert the integer value 4 to the `double` value 4.0 before the value is passed to `sqrt`. In general, argument values that do not correspond precisely to the parameter types in the function prototype are converted to the proper type before the function is called. These conversions can lead to incorrect results if C's **promotion rules** are not followed. The promotion rules specify how types can be converted to other types without losing data. In our `sqrt` example above, an `int` is automatically converted to a `double`



without changing its value. However, a `double` converted to an `int` truncates the fractional part of the `double` value. Converting large integer types to small integer types (e.g., `long` to `short`) may also result in changed values.

The promotion rules automatically apply to expressions containing values of two or more data types (also referred to as **mixed-type expressions**). The type of each value in a mixed-type expression is automatically promoted to the “highest” type in the expression (actually a temporary version of each value is created and used for the expression—the original values remain unchanged). Figure 5.5 lists the data types in order from highest type to lowest type with each type’s `printf` and `scanf` conversion specifications.

| Data type                      | <code>printf</code> conversion specification | <code>scanf</code> conversion specification |
|--------------------------------|----------------------------------------------|---------------------------------------------|
| <code>long double</code>       | <code>%Lf</code>                             | <code>%Lf</code>                            |
| <code>double</code>            | <code>%f</code>                              | <code>%lf</code>                            |
| <code>float</code>             | <code>%f</code>                              | <code>%f</code>                             |
| <code>unsigned long int</code> | <code>%lu</code>                             | <code>%lu</code>                            |
| <code>long int</code>          | <code>%ld</code>                             | <code>%ld</code>                            |
| <code>unsigned int</code>      | <code>%u</code>                              | <code>%u</code>                             |
| <code>int</code>               | <code>%d</code>                              | <code>%d</code>                             |
| <code>unsigned short</code>    | <code>%hu</code>                             | <code>%hu</code>                            |
| <code>short</code>             | <code>%hd</code>                             | <code>%hd</code>                            |
| <code>char</code>              | <code>%c</code>                              | <code>%c</code>                             |

**Fig. 5.5** | Promotion hierarchy for data types.

Converting values to lower types normally results in an incorrect value. Therefore, a value can be converted to a lower type only by explicitly assigning the value to a variable of lower type, or by using a cast operator. Function argument values are converted to the parameter types in a function prototype as if they were being assigned directly to variables of those types. If our `square` function that uses an integer parameter (Fig. 5.3) is called with a floating-point argument, the argument is converted to `int` (a lower type), and `square` usually returns an incorrect value. For example, `square( 4.5 )` returns 16, not 20.25.



#### Common Programming Error 5.8

*Converting from a higher data type in the promotion hierarchy to a lower type can change the data value. Many compilers issue warnings in such cases.*

If there is no function prototype for a function, the compiler forms its own function prototype using the first occurrence of the function—either the function definition or a call to the function. This typically leads to warnings or errors, depending on the compiler.



#### Error-Prevention Tip 5.2

*Always include function prototypes for the functions you define or use in your program to help prevent compilation errors and warnings.*



### Software Engineering Observation 5.9

*A function prototype placed outside any function definition applies to all calls to the function appearing after the function prototype in the file. A function prototype placed in a function applies only to calls made in that function.*

## 5.7 Function Call Stack and Activation Records

To understand how C performs function calls, we first need to consider a data structure (i.e., collection of related data items) known as a **stack**. Students can think of a stack as analogous to a pile of dishes. When a dish is placed on the pile, it's normally placed at the top (referred to as **pushing** the dish onto the stack). Similarly, when a dish is removed from the pile, it's always removed from the top (referred to as **popping** the dish off the stack). Stacks are known as **last-in, first-out (LIFO)** data structures—the last item pushed (inserted) on the stack is the first item popped (removed) from the stack.

When a program calls a function, the called function must know how to return to its caller, so the return address of the calling function is pushed onto the **program execution stack** (sometimes referred to as the **function call stack**). If a series of function calls occurs, the successive return addresses are pushed onto the stack in last-in, first-out order so that each function can return to its caller.

The program execution stack also contains the memory for the local variables used in each invocation of a function during a program's execution. This data, stored as a portion of the program execution stack, is known as the **activation record** or **stack frame** of the function call. When a function call is made, the activation record for that function call is pushed onto the program execution stack. When the function returns to its caller, the activation record for this function call is popped off the stack and those local variables are no longer known to the program.

Of course, the amount of memory in a computer is finite, so only a certain amount of memory can be used to store activation records on the program execution stack. If more function calls occur than can have their activation records stored on the program execution stack, an error known as a **stack overflow** occurs.

## 5.8 Headers

Each standard library has a corresponding **header** containing the function prototypes for all the functions in that library and definitions of various data types and constants needed by those functions. Figure 5.6 lists alphabetically some of the standard library headers that may be included in programs. The term “macros” that is used several times in Fig. 5.6 is discussed in detail in Chapter 13, C Preprocessor.

You can create custom headers. Programmer-defined headers should also use the `.h` filename extension. A programmer-defined header can be included by using the `#include` preprocessor directive. For example, if the prototype for our square function was located in the header `square.h`, we'd include that header in our program by using the following directive at the top of the program:

```
#include "square.h"
```

Section 13.2 presents additional information on including headers.

| Header                        | Explanation                                                                                                                                                                                                                                                                                                           |
|-------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>&lt;assert.h&gt;</code> | Contains macros and information for adding diagnostics that aid program debugging.                                                                                                                                                                                                                                    |
| <code>&lt;ctype.h&gt;</code>  | Contains function prototypes for functions that test characters for certain properties, and function prototypes for functions that can be used to convert lowercase letters to uppercase letters and vice versa.                                                                                                      |
| <code>&lt;errno.h&gt;</code>  | Defines macros that are useful for reporting error conditions.                                                                                                                                                                                                                                                        |
| <code>&lt;float.h&gt;</code>  | Contains the floating-point size limits of the system.                                                                                                                                                                                                                                                                |
| <code>&lt;limits.h&gt;</code> | Contains the integral size limits of the system.                                                                                                                                                                                                                                                                      |
| <code>&lt;locale.h&gt;</code> | Contains function prototypes and other information that enables a program to be modified for the current locale on which it's running. The notion of locale enables the computer system to handle different conventions for expressing data like dates, times, dollar amounts and large numbers throughout the world. |
| <code>&lt;math.h&gt;</code>   | Contains function prototypes for math library functions.                                                                                                                                                                                                                                                              |
| <code>&lt;setjmp.h&gt;</code> | Contains function prototypes for functions that allow bypassing of the usual function call and return sequence.                                                                                                                                                                                                       |
| <code>&lt;signal.h&gt;</code> | Contains function prototypes and macros to handle various conditions that may arise during program execution.                                                                                                                                                                                                         |
| <code>&lt;stdarg.h&gt;</code> | Defines macros for dealing with a list of arguments to a function whose number and types are unknown.                                                                                                                                                                                                                 |
| <code>&lt;stddef.h&gt;</code> | Contains common type definitions used by C for performing calculations.                                                                                                                                                                                                                                               |
| <code>&lt;stdio.h&gt;</code>  | Contains function prototypes for the standard input/output library functions, and information used by them.                                                                                                                                                                                                           |
| <code>&lt;stdlib.h&gt;</code> | Contains function prototypes for conversions of numbers to text and text to numbers, memory allocation, random numbers, and other utility functions.                                                                                                                                                                  |
| <code>&lt;string.h&gt;</code> | Contains function prototypes for string-processing functions.                                                                                                                                                                                                                                                         |
| <code>&lt;time.h&gt;</code>   | Contains function prototypes and types for manipulating the time and date.                                                                                                                                                                                                                                            |

**Fig. 5.6** | Some of the standard library headers.

## 5.9 Calling Functions By Value and By Reference

There are two ways to invoke functions in many programming languages—**call-by-value** and **call-by-reference**. When arguments are passed by value, a *copy* of the argument's value is made and passed to the called function. Changes to the copy do not affect an original variable's value in the caller. When an argument is passed by reference, the caller allows the called function to modify the original variable's value.

Call-by-value should be used whenever the called function does not need to modify the value of the caller's original variable. This prevents the accidental **side effects** (variable modifications) that so greatly hinder the development of correct and reliable software systems. Call-by-reference should be used only with trusted called functions that need to modify the original variable.

In C, all calls are by value. As we'll see in Chapter 7, it's possible to **simulate** call-by-reference by using address operators and indirection operators. In Chapter 6, we'll see that

arrays are automatically passed by reference. We'll have to wait until Chapter 7 for a full understanding of this complex issue. For now, we concentrate on call-by-value.

## 5.10 Random Number Generation

We now take a brief and, hopefully, entertaining diversion into a popular programming application, namely simulation and game playing. In this and the next section, we'll develop a nicely structured game-playing program that includes multiple functions. The program uses most of the control structures we've studied. The element of chance can be introduced into computer applications by using the C Standard Library function `rand` from the `<stdlib.h>` header.

Consider the following statement:

```
i = rand();
```

The `rand` function generates an integer between 0 and `RAND_MAX` (a symbolic constant defined in the `<stdlib.h>` header). Standard C states that the value of `RAND_MAX` must be at least 32767, which is the maximum value for a two-byte (i.e., 16-bit) integer. The programs in this section were tested on a C system with a maximum value of 32767 for `RAND_MAX`. If `rand` truly produces integers at random, every number between 0 and `RAND_MAX` has an equal chance (or probability) of being chosen each time `rand` is called.

The range of values produced directly by `rand` is often different from what is needed in a specific application. For example, a program that simulates coin tossing might require only 0 for “heads” and 1 for “tails.” A dice-rolling program that simulates a six-sided die would require random integers from 1 to 6.

### *Rolling a Six-Sided Die*

To demonstrate `rand`, let's develop a program to simulate 20 rolls of a six-sided die and print the value of each roll. The function prototype for function `rand` is in `<stdlib.h>`. We use the remainder operator (%) in conjunction with `rand` as follows

```
rand() % 6
```

to produce integers in the range 0 to 5. This is called **scaling**. The number 6 is called the **scaling factor**. We then **shift** the range of numbers produced by adding 1 to our previous result. The output of Fig. 5.7 confirms that the results are in the range 1 to 6—the output might vary by compiler.

```
1 /* Fig. 5.7: fig05_07.c
2 Shifted, scaled integers produced by 1 + rand() % 6 */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 int i; /* counter */
10
```

**Fig. 5.7** | Shifted, scaled random integers produced by `1 + rand() % 6`. (Part I of 2.)

```

11 /* loop 20 times */
12 for (i = 1; i <= 20; i++) {
13
14 /* pick random number from 1 to 6 and output it */
15 printf("%10d", 1 + (rand() % 6));
16
17 /* if counter is divisible by 5, begin new line of output */
18 if (i % 5 == 0) {
19 printf("\n");
20 } /* end if */
21 } /* end for */
22
23 return 0; /* indicates successful termination */
24 } /* end main */

```

|   |   |   |   |   |
|---|---|---|---|---|
| 6 | 6 | 5 | 5 | 6 |
| 5 | 1 | 1 | 5 | 3 |
| 6 | 6 | 2 | 4 | 2 |
| 6 | 2 | 3 | 4 | 1 |

**Fig. 5.7** | Shifted, scaled random integers produced by `1 + rand() % 6`. (Part 2 of 2.)

### *Rolling a Six-Sided Die 6000 Times*

To show that these numbers occur approximately with equal likelihood, let's simulate 6000 rolls of a die with the program of Fig. 5.8. Each integer from 1 to 6 should appear approximately 1000 times.

As the program output shows, by scaling and shifting we've used the `rand` function to realistically simulate the rolling of a six-sided die. *No default case* is provided in the switch statement. Also note the use of the `%s` conversion specifier to print the character strings "Face" and "Frequency" as column headers (line 53). After we study arrays in Chapter 6, we'll show how to replace this entire switch statement elegantly with a single-line statement.

```

1 /* Fig. 5.8: fig05_08.c
2 Roll a six-sided die 6000 times */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 int frequency1 = 0; /* rolled 1 counter */
10 int frequency2 = 0; /* rolled 2 counter */
11 int frequency3 = 0; /* rolled 3 counter */
12 int frequency4 = 0; /* rolled 4 counter */
13 int frequency5 = 0; /* rolled 5 counter */
14 int frequency6 = 0; /* rolled 6 counter */
15
16 int roll; /* roll counter, value 1 to 6000 */

```

**Fig. 5.8** | Rolling a six-sided die 6000 times. (Part 1 of 2.)

```

17 int face; /* represents one roll of the die, value 1 to 6 */
18
19 /* loop 6000 times and summarize results */
20 for (roll = 1; roll <= 6000; roll++) {
21 face = 1 + rand() % 6; /* random number from 1 to 6 */
22
23 /* determine face value and increment appropriate counter */
24 switch (face) {
25
26 case 1: /* rolled 1 */
27 ++frequency1;
28 break;
29
30 case 2: /* rolled 2 */
31 ++frequency2;
32 break;
33
34 case 3: /* rolled 3 */
35 ++frequency3;
36 break;
37
38 case 4: /* rolled 4 */
39 ++frequency4;
40 break;
41
42 case 5: /* rolled 5 */
43 ++frequency5;
44 break;
45
46 case 6: /* rolled 6 */
47 ++frequency6;
48 break; /* optional */
49 } /* end switch */
50 } /* end for */
51
52 /* display results in tabular format */
53 printf("%s%13s\n", "Face", "Frequency");
54 printf(" 1%13d\n", frequency1);
55 printf(" 2%13d\n", frequency2);
56 printf(" 3%13d\n", frequency3);
57 printf(" 4%13d\n", frequency4);
58 printf(" 5%13d\n", frequency5);
59 printf(" 6%13d\n", frequency6);
60 return 0; /* indicates successful termination */
61 } /* end main */

```

| Face | Frequency |
|------|-----------|
| 1    | 1003      |
| 2    | 1017      |
| 3    | 983       |
| 4    | 994       |
| 5    | 1004      |
| 6    | 999       |

**Fig. 5.8** | Rolling a six-sided die 6000 times. (Part 2 of 2.)

*Randomizing the Random Number Generator*

Executing the program of Fig. 5.7 again produces

|   |   |   |   |   |
|---|---|---|---|---|
| 6 | 6 | 5 | 5 | 6 |
| 5 | 1 | 1 | 5 | 3 |
| 6 | 6 | 2 | 4 | 2 |
| 6 | 2 | 3 | 4 | 1 |

Notice that exactly the same sequence of values was printed. How can these be random numbers? Ironically, this repeatability is an important characteristic of function `rand`. When debugging a program, this repeatability is essential for proving that corrections to a program work properly.

Function `rand` actually generates **pseudorandom numbers**. Calling `rand` repeatedly produces a sequence of numbers that appears to be random. However, the sequence repeats itself each time the program is executed. Once a program has been thoroughly debugged, it can be conditioned to produce a different sequence of random numbers for each execution. This is called **randomizing** and is accomplished with the standard library function `srand`. Function `srand` takes an unsigned integer argument and **seeds** function `rand` to produce a different sequence of random numbers for each execution of the program.

We demonstrate `srand` in Fig. 5.9. In the program, we use the data type `unsigned`, which is short for unsigned int. An `int` is stored in at least two bytes of memory and can have positive and negative values. A variable of type `unsigned` is also stored in at least two bytes of memory. A two-byte unsigned int can have only positive values in the range 0 to 65535. A four-byte unsigned int can have only positive values in the range 0 to 4294967295. Function `srand` takes an unsigned value as an argument. The conversion specifier `%u` is used to read an unsigned value with `scanf`. The function prototype for `srand` is found in `<stdlib.h>`.

```

1 /* Fig. 5.9: fig05_09.c
2 Randomizing die-rolling program */
3 #include <stdlib.h>
4 #include <stdio.h>
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 int i; /* counter */
10 unsigned seed; /* number used to seed random number generator */
11
12 printf("Enter seed: ");
13 scanf("%u", &seed); /* note %u for unsigned */
14
15 srand(seed); /* seed random number generator */
16

```

**Fig. 5.9** | Randomizing the die-rolling program. (Part I of 2.)

```

17 /* loop 10 times */
18 for (i = 1; i <= 10; i++) {
19
20 /* pick a random number from 1 to 6 and output it */
21 printf("%10d", 1 + (rand() % 6));
22
23 /* if counter is divisible by 5, begin a new line of output */
24 if (i % 5 == 0) {
25 printf("\n");
26 } /* end if */
27 } /* end for */
28
29 return 0; /* indicates successful termination */
30 } /* end main */

```

Enter seed: 67

|   |   |   |   |   |
|---|---|---|---|---|
| 6 | 1 | 4 | 6 | 2 |
| 1 | 6 | 1 | 6 | 4 |

Enter seed: 867

|   |   |   |   |   |
|---|---|---|---|---|
| 2 | 4 | 6 | 1 | 6 |
| 1 | 1 | 3 | 6 | 2 |

Enter seed: 67

|   |   |   |   |   |
|---|---|---|---|---|
| 6 | 1 | 4 | 6 | 2 |
| 1 | 6 | 1 | 6 | 4 |

**Fig. 5.9** | Randomizing the die-rolling program. (Part 2 of 2.)

Let's run the program several times and observe the results. Notice that a *different* sequence of random numbers is obtained each time the program is run, provided that a different seed is supplied.

To randomize without entering a seed each time, use a statement like

```
srand(time(NULL));
```

This causes the computer to read its clock to obtain the value for the seed automatically. Function `time` returns the number of seconds that have passed since midnight on January 1, 1970. This value is converted to an unsigned integer and used as the seed to the random number generator. Function `time` takes `NULL` as an argument (`time` is capable of providing you with a string representing the value it returns; `NULL` disables this capability for a specific call to `time`). The function prototype for `time` is in `<time.h>`.

### *Generalized Scaling and Shifting of Random Numbers*

The values produced directly by `rand` are always in the range:

```
0 ≤ rand() ≤ RAND_MAX
```



As you know, the following statement simulates rolling a six-sided die:

```
face = 1 + rand() % 6;
```

This statement always assigns an integer value (at random) to the variable `face` in the range  $1 \leq \text{face} \leq 6$ . The width of this range (i.e., the number of consecutive integers in the range) is 6 and the starting number in the range is 1. Referring to the preceding statement, we see that the width of the range is determined by the number used to scale `rand` with the remainder operator (i.e., 6), and the starting number of the range is equal to the number (i.e., 1) that is added to `rand % 6`. We can generalize this result as follows

```
n = a + rand() % b;
```

where `a` is the **shifting value** (which is equal to the first number in the desired range of consecutive integers) and `b` is the scaling factor (which is equal to the width of the desired range of consecutive integers). In the exercises, we'll see that it's possible to choose integers at random from sets of values other than ranges of consecutive integers.



### Common Programming Error 5.9

Using `srand` in place of `rand` to generate random numbers.

## 5.11 Example: A Game of Chance

One of the most popular games of chance is a dice game known as “craps,” which is played in casinos and back alleys throughout the world. The rules of the game are straightforward:

*A player rolls two dice. Each die has six faces. These faces contain 1, 2, 3, 4, 5, and 6 spots. After the dice have come to rest, the sum of the spots on the two upward faces is calculated. If the sum is 7 or 11 on the first throw, the player wins. If the sum is 2, 3, or 12 on the first throw (called “craps”), the player loses (i.e., the “house” wins). If the sum is 4, 5, 6, 8, 9, or 10 on the first throw, then that sum becomes the player’s “point.” To win, you must continue rolling the dice until you “make your point.” The player loses by rolling a 7 before making the point.*

Figure 5.10 simulates the game of craps and Fig. 5.11 shows several sample executions.

```
1 /* Fig. 5.10: fig05_10.c
2 Craps */
3 #include <stdio.h>
4 #include <stdlib.h>
5 #include <time.h> /* contains prototype for function time */
6
7 /* enumeration constants represent game status */
8 enum Status { CONTINUE, WON, LOST };
9
10 int rollDice(void); /* function prototype */
11
12 /* function main begins program execution */
13 int main(void)
14 {
```

**Fig. 5.10** | Program to simulate the game of craps. (Part I of 3.)

---

```

15 int sum; /* sum of rolled dice */
16 int myPoint; /* point earned */
17
18 enum Status gameStatus; /* can contain CONTINUE, WON, or LOST */
19
20 /* randomize random number generator using current time */
21 srand(time(NULL));
22
23 sum = rollDice(); /* first roll of the dice */
24
25 /* determine game status based on sum of dice */
26 switch(sum) {
27
28 /* win on first roll */
29 case 7:
30 case 11:
31 gameStatus = WON;
32 break;
33
34 /* lose on first roll */
35 case 2:
36 case 3:
37 case 12:
38 gameStatus = LOST;
39 break;
40
41 /* remember point */
42 default:
43 gameStatus = CONTINUE;
44 myPoint = sum;
45 printf("Point is %d\n", myPoint);
46 break; /* optional */
47 } /* end switch */
48
49 /* while game not complete */
50 while (gameStatus == CONTINUE) {
51 sum = rollDice(); /* roll dice again */
52
53 /* determine game status */
54 if (sum == myPoint) { /* win by making point */
55 gameStatus = WON; /* game over, player won */
56 } /* end if */
57 else {
58 if (sum == 7) { /* lose by rolling 7 */
59 gameStatus = LOST; /* game over, player lost */
60 } /* end if */
61 } /* end else */
62 } /* end while */
63
64 /* display won or lost message */
65 if (gameStatus == WON) { /* did player win? */
66 printf("Player wins\n");
67 } /* end if */

```

---

**Fig. 5.10** | Program to simulate the game of craps. (Part 2 of 3.)

```

68 else { /* player lost */
69 printf("Player loses\n");
70 } /* end else */
71
72 return 0; /* indicates successful termination */
73 } /* end main */
74
75 /* roll dice, calculate sum and display results */
76 int rollDice(void)
77 {
78 int die1; /* first die */
79 int die2; /* second die */
80 int workSum; /* sum of dice */
81
82 die1 = 1 + (rand() % 6); /* pick random die1 value */
83 die2 = 1 + (rand() % 6); /* pick random die2 value */
84 workSum = die1 + die2; /* sum die1 and die2 */
85
86 /* display results of this roll */
87 printf("Player rolled %d + %d = %d\n", die1, die2, workSum);
88 return workSum; /* return sum of dice */
89 } /* end function rollDice */

```

**Fig. 5.10** | Program to simulate the game of craps. (Part 3 of 3.)

Player rolled 5 + 6 = 11  
Player wins

Player rolled 4 + 1 = 5  
Point is 5  
Player rolled 6 + 2 = 8  
Player rolled 2 + 1 = 3  
Player rolled 3 + 2 = 5  
Player wins

Player rolled 1 + 1 = 2  
Player loses

Player rolled 6 + 4 = 10  
Point is 10  
Player rolled 3 + 4 = 7  
Player loses

**Fig. 5.11** | Sample runs for the game of craps.

In the rules of the game, notice that the player must roll two dice on the first roll, and must do so later on all subsequent rolls. We define a function `rollDice` to roll the dice and compute and print their sum. Function `rollDice` is defined once, but it's called from

two places in the program (lines 23 and 51). Interestingly, `rollDice` takes no arguments, so we've indicated `void` in the parameter list (line 76). Function `rollDice` does return the sum of the two dice, so a return type of `int` is indicated in the function header.

The game is reasonably involved. The player may win or lose on the first roll, or may win or lose on any subsequent roll. Variable `gameStatus`, defined to be of a new type—`enum Status`—stores the current status. Line 8 creates a programmer-defined type called an **enumeration**. An enumeration, introduced by the keyword `enum`, is a set of integer constants represented by identifiers. **Enumeration constants** are sometimes called symbolic constants. Values in an `enum` start with 0 and are incremented by 1. In line 8, the constant `CONTINUE` has the value 0, `WON` has the value 1 and `LOST` has the value 2. It's also possible to assign an integer value to each identifier in an `enum` (see Chapter 10). The identifiers in an enumeration must be unique, but the values may be duplicated.



### Common Programming Error 5.10

*Assigning a value to an enumeration constant after it has been defined is a syntax error.*



### Common Programming Error 5.11

*Use only uppercase letters in the names of enumeration constants to make these constants stand out in a program and to indicate that enumeration constants are not variables.*

When the game is won, either on the first roll or on a subsequent roll, `gameStatus` is set to `WON`. When the game is lost, either on the first roll or on a subsequent roll, `gameStatus` is set to `LOST`. Otherwise `gameStatus` is set to `CONTINUE` and the game continues.

After the first roll, if the game is over, the `while` statement (line 50) is skipped because `gameStatus` is not `CONTINUE`. The program proceeds to the `if...else` statement at line 65, which prints "Player wins" if `gameStatus` is `WON` and "Player loses" otherwise.

After the first roll, if the game is not over, then `sum` is saved in `myPoint`. Execution proceeds with the `while` statement (line 50) because `gameStatus` is `CONTINUE`. Each time through the `while`, `rollDice` is called to produce a new `sum`. If `sum` matches `myPoint`, `gameStatus` is set to `WON` to indicate that the player won, the `while`-test fails, the `if...else` statement (line 65) prints "Player wins" and execution terminates. If `sum` is equal to 7 (line 58), `gameStatus` is set to `LOST` to indicate that the player lost, the `while`-test fails, the `if...else` statement (line 65) prints "Player loses" and execution terminates.

Note the program's interesting control architecture. We've used two functions—`main` and `rollDice`—and the `switch`, `while`, nested `if...else` and nested `if` statements. In the exercises, we'll investigate various interesting characteristics of the game of craps.

## 5.12 Storage Classes

In Chapters 2–4, we used identifiers for variable names. The attributes of variables include name, type, size and value. In this chapter, we also use identifiers as names for user-defined functions. Actually, each identifier in a program has other attributes, including **storage class**, **storage duration**, **scope** and **linkage**.

C provides four storage classes, indicated by the **storage class specifiers**: `auto`, `register`, `extern` and **`static`**. An identifier's **storage class** determines its storage duration, scope and linkage. An identifier's **storage duration** is the period during which the identifier exists in memory. Some exist briefly, some are repeatedly created and destroyed, and

others exist for the entire execution of a program. An identifier's **scope** is *where* the identifier can be referenced in a program. Some can be referenced throughout a program, others from only portions of a program. An identifier's **linkage** determines for a multiple-source-file program (a topic we'll investigate in Chapter 14) whether the identifier is known only in the current source file or in any source file with proper declarations. This section discusses storage classes and storage duration. Section 5.13 discusses scope. Chapter 14 discusses identifier linkage and programming with multiple source files.

The four storage-class specifiers can be split into two storage durations: **automatic storage duration** and **static storage duration**. Keywords `auto` and `register` are used to declare variables of automatic storage duration. Variables with automatic storage duration are created when the block in which they're defined is entered; they exist while the block is active, and they're destroyed when the block is exited.

### Local Variables

Only variables can have automatic storage duration. A function's local variables (those declared in the parameter list or function body) normally have automatic storage duration. Keyword `auto` explicitly declares variables of automatic storage duration. For example, the following declaration indicates that `double` variables `x` and `y` are automatic local variables and they exist only in the body of the function in which the declaration appears:

```
auto double x, y;
```

Local variables have automatic storage duration by default, so keyword `auto` is rarely used. For the remainder of the text, we'll refer to variables with automatic storage duration simply as **automatic variables**.



#### Performance Tip 5.1

*Automatic storage is a means of conserving memory, because automatic variables exist only when they're needed. They're created when a function is entered and destroyed when the function is exited.*



#### Software Engineering Observation 5.10

*Automatic storage is an example of the **principle of least privilege**—allowing access to data only when it's absolutely needed. Why have variables stored in memory and accessible when in fact they're not needed?*

### Register Variables

Data in the machine-language version of a program is normally loaded into registers for calculations and other processing.



#### Performance Tip 5.2

*The storage-class specifier `register` can be placed before an automatic variable declaration to suggest that the compiler maintain the variable in one of the computer's high-speed hardware registers. If intensely used variables such as counters or totals can be maintained in hardware registers, the overhead of repeatedly loading the variables from memory into the registers and storing the results back into memory can be eliminated.*

The compiler may ignore `register` declarations. For example, there may not be a sufficient number of registers available for the compiler to use. The following declaration sug-

gests that the integer variable `counter` be placed in one of the computer's registers and initialized to 1:

```
register int counter = 1;
```

Keyword `register` can be used only with variables of automatic storage duration.



### Performance Tip 5.3

*Often, register declarations are unnecessary. Today's optimizing compilers are capable of recognizing frequently used variables and can decide to place them in registers without the need for a register declaration.*

### Static Storage Class

Keywords `extern` and `static` are used in the declarations of identifiers for variables and functions of static storage duration. Identifiers of static storage duration exist from the time at which the program begins execution. For static variables, storage is allocated and initialized once, when the program begins execution. For functions, the name of the function exists when the program begins execution. However, even though the variables and the function names exist from the start of program execution, this does not mean that these identifiers can be accessed throughout the program. Storage duration and scope (where a name can be used) are separate issues, as we'll see in Section 5.13.

There are two types of identifiers with static storage duration: external identifiers (such as global variables and function names) and local variables declared with the storage-class specifier `static`. Global variables and function names are of storage class `extern` by default. Global variables are created by placing variable declarations outside any function definition, and they retain their values throughout the execution of the program. Global variables and functions can be referenced by any function that follows their declarations or definitions in the file. This is one reason for using function prototypes—when we include `stdio.h` in a program that calls `printf`, the function prototype is placed at the start of our file to make the name `printf` known to the rest of the file.



### Software Engineering Observation 5.11

*Defining a variable as global rather than local allows unintended side effects to occur when a function that does not need access to the variable accidentally or maliciously modifies it. In general, use of global variables should be avoided except in certain situations with unique performance requirements (as discussed in Chapter 14).*



### Software Engineering Observation 5.12

*Variables used only in a particular function should be defined as local variables in that function rather than as external variables.*

Local variables declared with the keyword `static` are still known only in the function in which they're defined, but unlike automatic variables, `static` local variables retain their value when the function is exited. The next time the function is called, the `static` local variable contains the value it had when the function last exited. The following statement declares local variable `count` to be `static` and to be initialized to 1.

```
static int count = 1;
```

All numeric variables of static storage duration are initialized to zero if you do not explicitly initialize them.

Keywords `extern` and `static` have special meaning when explicitly applied to external identifiers. In Chapter 14 we discuss the explicit use of `extern` and `static` with external identifiers and multiple-source-file programs.

## 5.13 Scope Rules

The **scope of an identifier** is the portion of the program in which the identifier can be referenced. For example, when we define a local variable in a block, it can be referenced only following its definition in that block or in blocks nested within that block. The four identifier scopes are **function scope**, **file scope**, **block scope**, and **function-prototype scope**.

Labels (an identifier followed by a colon such as `start:`) are the only identifiers with **function scope**. Labels can be used anywhere in the function in which they appear, but cannot be referenced outside the function body. Labels are used in `switch` statements (as case labels) and in `goto` statements (see Chapter 14). Labels are implementation details that functions hide from one another. This hiding—more formally called **information hiding**—is a means of implementing the **principle of least privilege**, one of the most fundamental principles of good software engineering.

An identifier declared outside any function has **file scope**. Such an identifier is “known” (i.e., accessible) in all functions from the point at which the identifier is declared until the end of the file. Global variables, function definitions, and function prototypes placed outside a function all have file scope.

Identifiers defined inside a block have **block scope**. Block scope ends at the terminating right brace (`}`) of the block. Local variables defined at the beginning of a function have block scope as do function parameters, which are considered local variables by the function. Any block may contain variable definitions. When blocks are nested, and an identifier in an outer block has the same name as an identifier in an inner block, the identifier in the outer block is “hidden” until the inner block terminates. This means that while executing in the inner block, the inner block sees the value of its own local identifier and not the value of the identically named identifier in the enclosing block. Local variables declared `static` still have block scope, even though they exist from the time the program begins execution. Thus, storage duration does not affect the scope of an identifier.

The only identifiers with **function-prototype scope** are those used in the parameter list of a function prototype. As mentioned previously, function prototypes do not require names in the parameter list—only types are required. If a name is used in the parameter list of a function prototype, the compiler ignores the name. Identifiers used in a function prototype can be reused elsewhere in the program without ambiguity.



### Common Programming Error 5.12

*Accidentally using the same name for an identifier in an inner block as is used for an identifier in an outer block, when in fact you want the identifier in the outer block to be active for the duration of the inner block.*



### Error-Prevention Tip 5.3

*Avoid variable names that hide names in outer scopes. This can be accomplished simply by avoiding the use of duplicate identifiers in a program.*

Figure 5.12 demonstrates scoping issues with global variables, automatic local variables, and static local variables. A global variable `x` is defined and initialized to 1 (line 9). This global variable is hidden in any block (or function) in which a variable named `x` is defined. In `main`, a local variable `x` is defined and initialized to 5 (line 14). This variable is then printed to show that the global `x` is hidden in `main`. Next, a new block is defined in `main` with another local variable `x` initialized to 7 (line 19). This variable is printed to show that it hides `x` in the outer block of `main`. The variable `x` with value 7 is automatically destroyed when the block is exited, and the local variable `x` in the outer block of `main` is printed again to show that it's no longer hidden. The program defines three functions that each take no arguments and return nothing. Function `useLocal` defines an automatic variable `x` and initializes it to 25 (line 40). When `useLocal` is called, the variable is printed, incremented, and printed again before exiting the function. Each time this function is called, automatic variable `x` is reinitialized to 25. Function `useStaticLocal` defines a static variable `x` and initializes it to 50 (line 53). Local variables declared as static retain their values even when they're out of scope. When `useStaticLocal` is called, `x` is printed, incremented, and printed again before exiting the function. In the next call to this function, static local variable `x` will contain the value 51. Function `useGlobal` does not define any variables. Therefore, when it refers to variable `x`, the global `x` (line 9) is used. When `useGlobal` is called, the global variable is printed, multiplied by 10, and printed again before exiting the function. The next time function `useGlobal` is called, the global variable still has its modified value, 10. Finally, the program prints the local variable `x` in `main` again (line 33) to show that none of the function calls modified the value of `x` because the functions all referred to variables in other scopes.

---

```

1 /* Fig. 5.12: fig05_12.c
2 A scoping example */
3 #include <stdio.h>
4
5 void useLocal(void); /* function prototype */
6 void useStaticLocal(void); /* function prototype */
7 void useGlobal(void); /* function prototype */
8
9 int x = 1; /* global variable */
10
11 /* function main begins program execution */
12 int main(void)
13 {
14 int x = 5; /* local variable to main */
15
16 printf("local x in outer scope of main is %d\n", x);
17
18 { /* start new scope */
19 int x = 7; /* local variable to new scope */
20
21 printf("local x in inner scope of main is %d\n", x);
22 } /* end new scope */
23
24 printf("local x in outer scope of main is %d\n", x);

```

---

**Fig. 5.12** | Scoping example. (Part I of 3.)



```

25
26 useLocal(); /* useLocal has automatic local x */
27 useStaticLocal(); /* useStaticLocal has static local x */
28 useGlobal(); /* useGlobal uses global x */
29 useLocal(); /* useLocal reinitializes automatic local x */
30 useStaticLocal(); /* static local x retains its prior value */
31 useGlobal(); /* global x also retains its value */
32
33 printf("\nlocal x in main is %d\n", x);
34 return 0; /* indicates successful termination */
35 } /* end main */
36
37 /* useLocal reinitializes local variable x during each call */
38 void useLocal(void)
39 {
40 int x = 25; /* initialized each time useLocal is called */
41
42 printf("\nlocal x in useLocal is %d after entering useLocal\n", x);
43 x++;
44 printf("local x in useLocal is %d before exiting useLocal\n", x);
45 } /* end function useLocal */
46
47 /* useStaticLocal initializes static local variable x only the first time
48 the function is called; value of x is saved between calls to this
49 function */
50 void useStaticLocal(void)
51 {
52 /* initialized only first time useStaticLocal is called */
53 static int x = 50;
54
55 printf("\nlocal static x is %d on entering useStaticLocal\n", x);
56 x++;
57 printf("local static x is %d on exiting useStaticLocal\n", x);
58 } /* end function useStaticLocal */
59
60 /* function useGlobal modifies global variable x during each call */
61 void useGlobal(void)
62 {
63 printf("\nglobal x is %d on entering useGlobal\n", x);
64 x *= 10;
65 printf("global x is %d on exiting useGlobal\n", x);
66 } /* end function useGlobal */

```

```

local x in outer scope of main is 5
local x in inner scope of main is 7
local x in outer scope of main is 5

local x in useLocal is 25 after entering useLocal
local x in useLocal is 26 before exiting useLocal

local static x is 50 on entering useStaticLocal
local static x is 51 on exiting useStaticLocal

```

**Fig. 5.12** | Scoping example. (Part 2 of 3.)

```

global x is 1 on entering useGlobal
global x is 10 on exiting useGlobal

local x in useLocal is 25 after entering useLocal
local x in useLocal is 26 before exiting useLocal

local static x is 51 on entering useStaticLocal
local static x is 52 on exiting useStaticLocal

global x is 10 on entering useGlobal
global x is 100 on exiting useGlobal

local x in main is 5

```

**Fig. 5.12** | Scoping example. (Part 3 of 3.)

## 5.14 Recursion

The programs we've discussed are generally structured as functions that call one another in a disciplined, hierarchical manner. For some types of problems, it's useful to have functions call themselves. A **recursive function** is a function that calls itself either directly or indirectly through another function. Recursion is a complex topic discussed at length in upper-level computer science courses. In this section and the next, simple examples of recursion are presented. This book contains an extensive treatment of recursion, which is spread throughout Chapters 5–8, 12 and Appendix F. Figure 5.17, in Section 5.16, summarizes the 31 recursion examples and exercises in the book.

We consider recursion conceptually first, and then examine several programs containing recursive functions. Recursive problem-solving approaches have a number of elements in common. A recursive function is called to solve a problem. The function actually knows how to solve only the simplest case(s), or so-called **base case(s)**. If the function is called with a base case, the function simply returns a result. If the function is called with a more complex problem, the function divides the problem into two conceptual pieces: a piece that the function knows how to do and a piece that it does not know how to do. To make recursion feasible, the latter piece must resemble the original problem, but be a slightly simpler or slightly smaller version. Because this new problem looks like the original problem, the function launches (calls) a fresh copy of itself to go to work on the smaller problem—this is referred to as a **recursive call** and is also called the **recursion step**. The recursion step also includes the keyword **return**, because its result will be combined with the portion of the problem the function knew how to solve to form a result that will be passed back to the original caller, possibly **main**.

The recursion step executes while the original call to the function is still open, i.e., it has not yet finished executing. The recursion step can result in many more such recursive calls, as the function keeps dividing each problem it's called with into two conceptual pieces. In order for the recursion to terminate, each time the function calls itself with a slightly simpler version of the original problem, this sequence of smaller problems must eventually converge on the base case. At that point, the function recognizes the base case, returns a result to the previous copy of the function, and a sequence of returns ensues all the way up the line until the original call of the function eventually returns the final result

to main. All of this sounds quite exotic compared to the kind of problem solving we've been using with conventional function calls to this point. Indeed, it takes a great deal of practice writing recursive programs before the process will appear natural. As an example of these concepts at work, let's write a recursive program to perform a popular mathematical calculation.

### *Recursively Calculating Factorials*

The factorial of a nonnegative integer  $n$ , written  $n!$  (and pronounced " $n$  factorial"), is the product

$$n \cdot (n-1) \cdot (n-2) \cdot \dots \cdot 1$$

with  $1!$  equal to 1, and  $0!$  defined to be 1. For example,  $5!$  is the product  $5 * 4 * 3 * 2 * 1$ , which is equal to 120.

The factorial of an integer, number, greater than or equal to 0 can be calculated iteratively (nonrecursively) using a for statement as follows:

```
factorial = 1;
for (counter = number; counter >= 1; counter--)
 factorial *= counter;
```

A recursive definition of the factorial function is arrived at by observing the following relationship:

$$n! = n \cdot (n-1)!$$

For example,  $5!$  is clearly equal to  $5 * 4!$  as is shown by the following:

$$\begin{aligned} 5! &= 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1 \\ 5! &= 5 \cdot (4 \cdot 3 \cdot 2 \cdot 1) \\ 5! &= 5 \cdot (4!) \end{aligned}$$


The evaluation of  $5!$  would proceed as shown in Fig. 5.13. Figure 5.13(a) shows how the succession of recursive calls proceeds until  $1!$  is evaluated to be 1, which terminates the recursion. Figure 5.13(b) shows the values returned from each recursive call to its caller until the final value is calculated and returned.

Figure 5.14 uses recursion to calculate and print the factorials of the integers 0–10 (the choice of the type `long` will be explained momentarily). The recursive `factorial` function first tests whether a terminating condition is true, i.e., whether `number` is less than or equal to 1. If `number` is indeed less than or equal to 1, `factorial` returns 1, no further recursion is necessary, and the program terminates. If `number` is greater than 1, the statement

```
return number * factorial(number - 1);
```

expresses the problem as the product of `number` and a recursive call to `factorial` evaluating the factorial of `number - 1`. The call `factorial( number - 1 )` is a slightly simpler problem than the original calculation `factorial( number )`.

Function `factorial` (line 22) has been declared to receive a parameter of type `long` and return a result of type `long`. This is shorthand notation for `long int`. The C standard specifies that a variable of type `long int` is stored in at least 4 bytes, and thus may hold a value as large as +2147483647. As can be seen in Fig. 5.14, factorial values become large quickly. We've chosen the data type `long` so the program can calculate factorials greater



**Fig. 5.13** | Recursive evaluation of  $5!$ .

```

1 /* Fig. 5.14: fig05_14.c
2 Recursive factorial function */
3 #include <stdio.h>
4
5 long factorial(long number); /* function prototype */
6
7 /* function main begins program execution */
8 int main(void)
9 {
10 int i; /* counter */
11
12 /* loop 11 times; during each iteration, calculate
13 factorial(i) and display result */
14 for (i = 0; i <= 10; i++) {
15 printf("%2d! = %ld\n", i, factorial(i));
16 } /* end for */
17
18 return 0; /* indicates successful termination */
19 } /* end main */
20
21 /* recursive definition of function factorial */
22 long factorial(long number)
23 {
24 /* base case */
25 if (number <= 1) {
26 return 1;
27 } /* end if */

```

**Fig. 5.14** | Calculating factorials with a recursive function. (Part I of 2.)

```

28 else { /* recursive step */
29 return (number * factorial(number - 1));
30 } /* end else */
31 } /* end function factorial */

```

```

0! = 1
1! = 1
2! = 2
3! = 6
4! = 24
5! = 120
6! = 720
7! = 5040
8! = 40320
9! = 362880
10! = 3628800

```

**Fig. 5.14** | Calculating factorials with a recursive function. (Part 2 of 2.)

than 7! on computers with small (such as 2-byte) integers. The conversion specifier %ld is used to print long values. Unfortunately, the factorial function produces large values so quickly that even long int does not help us print many factorial values before the size of a long int variable is exceeded.

As we'll explore in the exercises, double may ultimately be needed by the user desiring to calculate factorials of larger numbers. This points to a weakness in C (and most other procedural programming languages), namely that the language is not easily extended to handle the unique requirements of various applications. As we'll see later in the book, C++ is an extensible language that, through "classes," allows us to create arbitrarily large integers if we wish.



#### Common Programming Error 5.13

*Forgetting to return a value from a recursive function when one is needed.*



#### Common Programming Error 5.14

*Either omitting the base case, or writing the recursion step incorrectly so that it does not converge on the base case, will cause infinite recursion, eventually exhausting memory. This is analogous to the problem of an infinite loop in an iterative (nonrecursive) solution. Infinite recursion can also be caused by providing an unexpected input.*

## 5.15 Example Using Recursion: Fibonacci Series

The Fibonacci series

```
0, 1, 1, 2, 3, 5, 8, 13, 21, ...
```

begins with 0 and 1 and has the property that each subsequent Fibonacci number is the sum of the previous two Fibonacci numbers.

The series occurs in nature and, in particular, describes a form of spiral. The ratio of successive Fibonacci numbers converges to a constant value of 1.618.... This number, too,

repeatedly occurs in nature and has been called the golden ratio or the golden mean. Humans tend to find the golden mean aesthetically pleasing. Architects often design windows, rooms, and buildings whose length and width are in the ratio of the golden mean. Postcards are often designed with a golden mean length/width ratio.

The Fibonacci series may be defined recursively as follows:

```
fibonacci(0) = 0
fibonacci(1) = 1
fibonacci(n) = fibonacci(n - 1) + fibonacci(n - 2)
```

Figure 5.15 calculates the  $n^{\text{th}}$  Fibonacci number recursively using function `fibonacci`. Notice that Fibonacci numbers tend to become large quickly. Therefore, we've chosen the data type `long` for the parameter type and the return type in function `fibonacci`. In Fig. 5.15, each pair of output lines shows a separate run of the program.

---

```
1 /* Fig. 5.15: fig05_15.c
2 Recursive fibonacci function */
3 #include <stdio.h>
4
5 long fibonacci(long n); /* function prototype */
6
7 /* function main begins program execution */
8 int main(void)
9 {
10 long result; /* fibonacci value */
11 long number; /* number input by user */
12
13 /* obtain integer from user */
14 printf("Enter an integer: ");
15 scanf("%ld", &number);
16
17 /* calculate fibonacci value for number input by user */
18 result = fibonacci(number);
19
20 /* display result */
21 printf("Fibonacci(%ld) = %ld\n", number, result);
22 return 0; /* indicates successful termination */
23 } /* end main */
24
25 /* Recursive definition of function fibonacci */
26 long fibonacci(long n)
27 {
28 /* base case */
29 if (n == 0 || n == 1) {
30 return n;
31 } /* end if */
32 else { /* recursive step */
33 return fibonacci(n - 1) + fibonacci(n - 2);
34 } /* end else */
35 } /* end function fibonacci */
```

---

**Fig. 5.15** | Recursively generating Fibonacci numbers. (Part I of 2.)

```
Enter an integer: 0
Fibonacci(0) = 0
```

```
Enter an integer: 1
Fibonacci(1) = 1
```

```
Enter an integer: 2
Fibonacci(2) = 1
```

```
Enter an integer: 3
Fibonacci(3) = 2
```

```
Enter an integer: 4
Fibonacci(4) = 3
```

```
Enter an integer: 5
Fibonacci(5) = 5
```

```
Enter an integer: 6
Fibonacci(6) = 8
```

```
Enter an integer: 10
Fibonacci(10) = 55
```

```
Enter an integer: 20
Fibonacci(20) = 6765
```

```
Enter an integer: 30
Fibonacci(30) = 832040
```

```
Enter an integer: 35
Fibonacci(35) = 9227465
```

**Fig. 5.15** | Recursively generating Fibonacci numbers. (Part 2 of 2.)

The call to `fibonacci` from `main` is not a recursive call (line 18), but all subsequent calls to `fibonacci` are recursive (line 33). Each time `fibonacci` is invoked, it immediately tests for the base case—`n` is equal to 0 or 1. If this is true, `n` is returned. Interestingly, if `n` is greater than 1, the recursion step generates *two* recursive calls, each of which is for a slightly simpler problem than the original call to `fibonacci`. Figure 5.16 shows how function `fibonacci` would evaluate `fibonacci(3)`.


### Order of Evaluation of Operands

This figure raises some interesting issues about the order in which C compilers will evaluate the operands of operators. This is a different issue from the order in which operators are applied to their operands, namely the order dictated by the rules of operator precedence. From Fig. 5.16 it appears that while evaluating `fibonacci(3)`, two recursive calls will be made, namely `fibonacci(2)` and `fibonacci(1)`. But in what order will these calls be made? Most programmers simply assume the operands will be evaluated left to right. Strangely, Standard C does not specify the order in which the operands of most operators (including `+`) are to be evaluated. Therefore, you may make no assumption about the order in which these calls will execute. The calls could in fact execute `fibonacci(2)` first and then `fibonacci(1)`, or the calls could execute in the reverse order, `fibonacci(1)` then `fibonacci(2)`. In this program and in most other programs, it turns out the final result would be the same. But in some programs the evaluation of an operand may have side effects that could affect the final result of the expression. Of C's many operators, Standard C specifies the order of evaluation of the operands of only four operators—namely `&&`, `||`, the comma `(,)` operator and `?:`. The first three of these are binary operators whose two operands are guaranteed to be evaluated left to right. [Note: The commas used to separate the arguments in a function call are not comma operators.] The last operator is C's only ternary operator. Its leftmost operand is always evaluated first; if the leftmost operand evaluates to nonzero, the middle operand is evaluated next and the last operand is ignored; if the leftmost operand evaluates to zero, the third operand is evaluated next and the middle operand is ignored.



#### Common Programming Error 5.15

*Writing programs that depend on the order of evaluation of the operands of operators other than `&&`, `||`, `?:`, and the comma `(,)` operator can lead to errors because compilers may not necessarily evaluate the operands in the order you expect.*



**Fig. 5.16** | Set of recursive calls for `fibonacci(3)`.





### Portability Tip 5.2

*Programs that depend on the order of evaluation of the operands of operators other than `&&`, `||`, `?:`, and the comma `(,)` operator can function differently on systems with different compilers.*

### Exponential Complexity

A word of caution is in order about recursive programs like the one we use here to generate Fibonacci numbers. Each level of recursion in the `fibonacci` function has a doubling effect on the number of calls; i.e., the number of recursive calls that will be executed to calculate the  $n^{\text{th}}$  Fibonacci number is on the order of  $2^n$ . This rapidly gets out of hand. Calculating only the 20<sup>th</sup> Fibonacci number would require on the order of  $2^{20}$  or about a million calls, calculating the 30<sup>th</sup> Fibonacci number would require on the order of  $2^{30}$  or about a billion calls, and so on. Computer scientists refer to this as exponential complexity. Problems of this nature humble even the world's most powerful computers! Complexity issues in general, and exponential complexity in particular, are discussed in detail in the upper-level computer science curriculum course generally called "Algorithms."



### Performance Tip 5.4

*Avoid Fibonacci-style recursive programs which result in an exponential "explosion" of calls.*

The example we showed in this section used an intuitively appealing solution to calculate Fibonacci numbers, but there are better approaches. Exercise 5.48 asks you to investigate recursion in more depth and propose alternate approaches to implementing the recursive Fibonacci algorithm.

## 5.16 Recursion vs. Iteration

In the previous sections, we studied two functions that can easily be implemented either recursively or iteratively. In this section, we compare the two approaches and discuss why you might choose one approach over the other in a particular situation.

Both iteration and recursion are based on a control structure: Iteration uses a repetition structure; recursion uses a selection structure. Both iteration and recursion involve repetition: Iteration explicitly uses a repetition structure; recursion achieves repetition through repeated function calls. Iteration and recursion each involve a termination test: Iteration terminates when the loop-continuation condition fails; recursion terminates when a base case is recognized. Iteration with counter-controlled repetition and recursion each gradually approach termination: Iteration keeps modifying a counter until the counter assumes a value that makes the loop-continuation condition fail; recursion keeps producing simpler versions of the original problem until the base case is reached. Both iteration and recursion can occur infinitely: An infinite loop occurs with iteration if the loop-continuation test never becomes false; infinite recursion occurs if the recursion step does not reduce the problem each time in a manner that converges on the base case.

Recursion has many negatives. It repeatedly invokes the mechanism, and consequently the overhead, of function calls. This can be expensive in both processor time and memory space. Each recursive call causes another copy of the function (actually only the function's variables) to be created; this can consume considerable memory. Iteration nor-

mally occurs within a function, so the overhead of repeated function calls and extra memory assignment is omitted. So why choose recursion?



### Software Engineering Observation 5.13

*Any problem that can be solved recursively can also be solved iteratively (nonrecursively). A recursive approach is normally chosen in preference to an iterative approach when the recursive approach more naturally mirrors the problem and results in a program that is easier to understand and debug. Another reason to choose a recursive solution is that an iterative solution may not be apparent.*



### Performance Tip 5.5

*Avoid using recursion in performance situations. Recursive calls take time and consume additional memory.*



### Common Programming Error 5.16

*Accidentally having a nonrecursive function call itself either directly, or indirectly through another function.*

Most programming textbooks introduce recursion much later than we've done here. We feel that recursion is a sufficiently rich and complex topic that it's better to introduce it earlier and spread the examples over the remainder of the text. Figure 5.17 summarizes by chapter the 31 recursion examples and exercises in the text.

| Chapter          | Recursion examples and exercises                                                                                                                                                                                                                                   |
|------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>Chapter 5</i> | Factorial function<br>Fibonacci function<br>Greatest common divisor<br>Sum of two integers<br>Multiply two integers<br>Raising an integer to an integer power<br>Towers of Hanoi<br>Recursive main<br>Printing keyboard inputs in reverse<br>Visualizing recursion |
| <i>Chapter 6</i> | Sum the elements of an array<br>Print an array<br>Print an array backward<br>Print a string backward<br>Check if a string is a palindrome<br>Minimum value in an array<br>Linear search<br>Binary search                                                           |
| <i>Chapter 7</i> | Eight Queens<br>Maze traversal                                                                                                                                                                                                                                     |
| <i>Chapter 8</i> | Printing a string input at the keyboard backward                                                                                                                                                                                                                   |

**Fig. 5.17** | Recursion examples and exercises in the text. (Part I of 2.)

| Chapter           | Recursion examples and exercises                                                                                                                                                                                                            |
|-------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>Chapter 12</i> | Linked list insert<br>Linked list delete<br>Search a linked list<br>Print a linked list backward<br>Binary tree insert<br>Preorder traversal of a binary tree<br>Inorder traversal of a binary tree<br>Postorder traversal of a binary tree |
| <i>Appendix F</i> | Selection sort<br>Quicksort                                                                                                                                                                                                                 |

**Fig. 5.17** | Recursion examples and exercises in the text. (Part 2 of 2.)

Let's close this chapter with some observations that we make repeatedly throughout the book. Good software engineering is important. High performance is important. Unfortunately, these goals are often at odds with one another. Good software engineering is key to making more manageable the task of developing the larger and more complex software systems we need. High performance is key to realizing the systems of the future that will place ever greater computing demands on hardware. Where do functions fit in here?



### Performance Tip 5.6

*Functionalizing programs in a neat, hierarchical manner promotes good software engineering. But it has a price. A heavily functionalized program—as compared to a monolithic (i.e., one-piece) program without functions—makes potentially large numbers of function calls, and these consume execution time on a computer's processor(s). So, although monolithic programs may perform better, they're more difficult to program, test, debug, maintain, and evolve.*

## Summary

### Section 5.1 Introduction

- The best way to develop and maintain a large program is to divide it into several smaller program modules, each of which is more manageable than the original program. Modules are written as functions in C.

### Section 5.2 Program Modules in C

- A function is invoked by a function call. The function call mentions the function by name and provides information (as arguments) that the called function needs to perform its task.
- The purpose of information hiding is for functions to have access only to the information they need to complete their tasks. This is a means of implementing the principle of least privilege, one of the most important principles of good software engineering.

### Section 5.3 Math Library Functions

- Functions are normally invoked in a program by writing the name of the function followed by a left parenthesis followed by the argument (or a comma-separated list of arguments) of the function followed by a right parenthesis.

- Data type `double` is a floating-point type like `float`. A variable of type `double` can store a value of much greater magnitude and precision than `float` can store.
- Each argument of a function may be a constant, a variable, or an expression.

### Section 5.4 Functions

- A local variable is known only in a function definition. Other functions are not allowed to know the names of a function's local variables, nor is any function allowed to know the implementation details of any other function.

### Section 5.5 Function Definitions

- The general format for a function definition is

```
return-value-type function-name(parameter-list)
{
 definitions
 statements
}
```

The *return-value-type* states the type of the value returned to the calling function. If a function does not return a value, the *return-value-type* is declared as `void`. The *function-name* is any valid identifier. The *parameter-list* is a comma-separated list containing the definitions of the variables that will be passed to the function. If a function does not receive any values, *parameter-list* is declared as `void`. The *function-body* is the set of definitions and statements that constitute the function.

- The arguments passed to a function should match in number, type and order with the parameters in the function definition.
- When a program encounters a function call, control is transferred from the point of invocation to the called function, the statements of the called function are executed and control returns to the caller.
- A called function can return control to the caller in one of three ways. If the function does not return a value, control is returned when the function-ending right brace is reached, or by executing the statement

```
return;
```

If the function does return a value, the statement

```
return expression;
```

returns the value of *expression*.

### Section 5.6 Function Prototypes

- A function prototype declares the return type of the function and declares the number, the types, and order of the parameters the function expects to receive.
- Function prototypes enable the compiler to verify that functions are called correctly.
- The compiler ignores variable names mentioned in the function prototype.

### Section 5.7 Function Call Stack and Activation Records

- Stacks are known as last-in, first-out (LIFO) data structures—the last item pushed (inserted) on the stack is the first item popped (removed) from the stack.
- A called function must know how to return to its caller, so the return address of the calling function is pushed onto the program execution stack when the function is called. If a series of function calls occurs, the successive return addresses are pushed onto the stack in last-in, first-out order so that the last function to execute will be the first to return to its caller.

- The program execution stack contains the memory for the local variables used in each invocation of a function during a program's execution. This data is known as the activation record or stack frame of the function call. When a function call is made, the activation record for that function call is pushed onto the program execution stack. When the function returns to its caller, the activation record for this function call is popped off the stack and those local variables are no longer known to the program.
- The amount of memory in a computer is finite, so only a certain amount of memory can be used to store activation records on the program execution stack. If there are more function calls than can have their activation records stored on the program execution stack, an error known as a stack overflow occurs. The application will compile correctly, but its execution causes a stack overflow.

### *Section 5.8 Headers*

- Each standard library has a corresponding header containing the function prototypes for all the functions in that library, as well as definitions of various symbolic constants needed by those functions.
- You can create and include your own headers.

### *Section 5.9 Calling Functions By Value and By Reference*

- When an argument is passed by value, a copy of the variable's value is made and the copy is passed to the called function. Changes to the copy in the called function do not affect the original variable's value.
- All calls in C are call-by-value.
- It's possible to simulate call-by-reference by using address operators and indirection operators.

### *Section 5.10 Random Number Generation*

- Function `rand` generates an integer between 0 and `RAND_MAX` which is defined by the C standard to be at least 32767.
- The function prototypes for `rand` and `srand` are contained in `<stdlib.h>`.
- Values produced by `rand` can be scaled and shifted to produce values in a specific range.
- To randomize a program, use the C Standard Library function `srand`.
- The `srand` function call is ordinarily inserted in a program only after it has been thoroughly debugged. While debugging, it's better to omit `srand`. This ensures repeatability, which is essential to proving that corrections to a random number generation program work properly.
- To randomize without the need for entering a seed each time, we use `srand(time(NULL))`.
- The general equation for scaling and shifting a random number is

$$n = a + \text{rand}() \% b;$$

where *a* is the shifting value (i.e., the first number in the desired range of consecutive integers) and *b* is the scaling factor (i.e., the width of the desired range of consecutive integers).

### *Section 5.11 Example: A Game of Chance*

- An enumeration, introduced by the keyword `enum`, is a set of integer constants represented by identifiers. Values in an `enum` start with 0 and are incremented by 1. It's also possible to assign an integer value to each identifier in an `enum`. The identifiers in an enumeration must be unique, but the values may be duplicated.

### *Section 5.12 Storage Classes*

- Each identifier in a program has the attributes storage class, storage duration, scope and linkage.

- C provides four storage classes indicated by the storage class specifiers: `auto`, `register`, `extern` and `static`; only one storage class specifier can be used for a given declaration.
- An identifier's storage duration is when that identifier exists in memory.

### Section 5.13 Scope Rules

- An identifier's scope is where the identifier can be referenced in a program.
- An identifier's linkage determines for a multiple-source-file program whether an identifier is known only in the current source file or in any source file with proper declarations.
- Variables with automatic storage duration are created when the block in which they're defined is entered, exist while the block is active and are destroyed when the block is exited. A function's local variables normally have automatic storage duration.
- The storage class specifier `register` can be placed before an automatic variable declaration to suggest that the compiler maintain the variable in one of the computer's high-speed hardware registers. The compiler may ignore `register` declarations. Keyword `register` can be used only with variables of automatic storage duration.
- Keywords `extern` and `static` are used to declare identifiers for variables and functions of static storage duration.
- Variables with static storage duration are allocated and initialized once, when the program begins execution.
- There are two types of identifiers with static storage duration: external identifiers (such as global variables and function names) and local variables declared with the storage-class specifier `static`.
- Global variables are created by placing variable definitions outside any function definition. Global variables retain their values throughout the execution of the program.
- Local variables declared `static` retain their value between calls to the function in which they're defined.
- All numeric variables of static storage duration are initialized to zero if you do not explicitly initialize them.
- The four scopes for an identifier are function scope, file scope, block scope and function-prototype scope.
- Labels are the only identifiers with function scope. Labels can be used anywhere in the function in which they appear but cannot be referenced outside the function body.
- An identifier declared outside any function has file scope. Such an identifier is "known" in all functions from the point at which the identifier is declared until the end of the file.
- Identifiers defined inside a block have block scope. Block scope ends at the terminating right brace `}` of the block.
- Local variables defined at the beginning of a function have block scope, as do function parameters, which are considered local variables by the function.
- Any block may contain variable definitions. When blocks are nested, and an identifier in an outer block has the same name as an identifier in an inner block, the identifier in the outer block is "hidden" until the inner block terminates.
- The only identifiers with function-prototype scope are those used in the parameter list of a function prototype. Identifiers used in a function prototype can be reused elsewhere in the program without ambiguity.

### Section 5.14 Recursion

- A recursive function is a function that calls itself either directly or indirectly.

- If a recursive function is called with a base case, the function simply returns a result. If the function is called with a more complex problem, the function divides the problem into two conceptual pieces: a piece that the function knows how to do and a slightly smaller version of the original problem. Because this new problem looks like the original problem, the function launches a recursive call to work on the smaller problem.
- For recursion to terminate, each time the recursive function calls itself with a slightly simpler version of the original problem, the sequence of smaller and smaller problems must converge on the base case. When the function recognizes the base case, the result is returned to the previous function call, and a sequence of returns ensues all the way up the line until the original call of the function eventually returns the final result.
- Standard C does not specify the order in which the operands of most operators (including `+`) are to be evaluated. Of C's many operators, the standard specifies the order of evaluation of the operands of only the operators `&&`, `||`, the comma `(,)` operator and `?:`. The first three of these are binary operators whose two operands are evaluated left to right. The last operator is C's only ternary operator. Its leftmost operand is evaluated first; if the leftmost operand evaluates to nonzero, the middle operand is evaluated next and the last operand is ignored; if the leftmost operand evaluates to zero, the third operand is evaluated next and the middle operand is ignored.

### Section 5.16 Recursion vs. Iteration

- Both iteration and recursion are based on a control structure: Iteration uses a repetition structure; recursion uses a selection structure.
- Both iteration and recursion involve repetition: Iteration explicitly uses a repetition structure; recursion achieves repetition through repeated function calls.
- Iteration and recursion each involve a termination test: Iteration terminates when the loop-continuation condition fails; recursion terminates when a base case is recognized.
- Iteration and recursion can occur infinitely: An infinite loop occurs with iteration if the loop-continuation test never becomes false; infinite recursion occurs if the recursion step does not reduce the problem in a manner that converges on the base case.
- Recursion repeatedly invokes the mechanism, and consequently the overhead, of function calls. This can be expensive in both processor time and memory space.

## Terminology

abstraction 144  
 activation record 151  
 argument (of a function) 142  
 auto 161  
 automatic storage duration 162  
 automatic variable 162  
 base case 167  
 block 146  
 block scope 164  
 C Standard Library 141  
 call a function 142  
 call-by-reference 152  
 call-by-value 152  
 called 145  
 called function 142  
 caller 142  
 calling function 142

coercion of arguments 149  
 divide and conquer 141  
 enum 161  
 enumeration 161  
 enumeration constant 161  
 file scope 164  
 function 141  
 function body 146  
 function call 142  
 function call stack 151  
 function prototype 145  
 function-prototype scope 164  
 function scope 164  
 header 146  
 information hiding 164  
 invoke a function 142  
 invoked 142

last-in-first-out (LIFO) 151  
 linkage 161  
 linkage of an identifier 162  
 local variable 144  
 mixed-type expression 150  
 module 141  
 parameter 144  
 parameter-list 146  
 pop off a stack 151  
 principle of least privilege 164  
 program execution stack 151  
 programmer-defined function 142  
 promotion rule 149  
 pseudorandom numbers 156  
 push onto a stack 151  
 randomizing 156  
 recursion step 167  
 recursive call 167  
 recursive function 167  
 return from a function 142  
 return value type 146  
 scaling 153  
 scaling factor 153  
 scope 162  
 scope of an identifier 164  
 seed the rand function 156  
 shift 153  
 shifting value 158  
 side effect 152  
 simulate 152  
 software reusability 144  
 stack 151  
 stack frame 151  
 stack overflow 151  
 standard library header 151  
 static 161  
 static storage duration 162  
 storage class 161  
 storage class of an identifier 161  
 storage class specifier 161  
 storage duration 161

## Self-Review Exercises

**5.1** Answer each of the following:

- a) A program module in C is called a(n) \_\_\_\_\_.
- b) A function is invoked with a(n) \_\_\_\_\_.
- c) A variable that is known only within the function in which it's defined is called a(n) \_\_\_\_\_.
- d) The \_\_\_\_\_ statement in a called function is used to pass the value of an expression back to the calling function.
- e) Keyword \_\_\_\_\_ is used in a function header to indicate that a function does not return a value or to indicate that a function contains no parameters.
- f) The \_\_\_\_\_ of an identifier is the portion of the program in which the identifier can be used.
- g) The three ways to return control from a called function to a caller are \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- h) A(n) \_\_\_\_\_ allows the compiler to check the number, types, and order of the arguments passed to a function.
- i) The \_\_\_\_\_ function is used to produce random numbers.
- j) The \_\_\_\_\_ function is used to set the random number seed to randomize a program.
- k) The storage-class specifiers are \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- l) Variables declared in a block or in the parameter list of a function are assumed to be of storage class \_\_\_\_\_ unless specified otherwise.
- m) The storage-class specifier \_\_\_\_\_ is a recommendation to the compiler to store a variable in one of the computer's registers.
- n) A non-static variable defined outside any block or function is a(n) \_\_\_\_\_ variable.
- o) For a local variable in a function to retain its value between calls to the function, it must be declared with the \_\_\_\_\_ storage-class specifier.
- p) The four possible scopes of an identifier are \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.



- q) A function that calls itself either directly or indirectly is a(n) \_\_\_\_\_ function.
- r) A recursive function typically has two components: one that provides a means for the recursion to terminate by testing for a(n) \_\_\_\_\_ case, and one that expresses the problem as a recursive call for a slightly simpler problem than the original call.

**5.2** For the following program, state the scope (either function scope, file scope, block scope or function prototype scope) of each of the following elements.

- a) The variable `x` in `main`.
- b) The variable `y` in `cube`.
- c) The function `cube`.
- d) The function `main`.
- e) The function prototype for `cube`.
- f) The identifier `y` in the function prototype for `cube`.

```

1 #include <stdio.h>
2 int cube(int y);
3
4 int main(void)
5 {
6 int x;
7
8 for (x = 1; x <= 10; x++)
9 printf("%d\n", cube(x));
10 return 0;
11 }
12
13 int cube(int y)
14 {
15 return y * y * y;
16 }
```

**5.3** Write a program that tests whether the examples of the math library function calls shown in Fig. 5.2 actually produce the indicated results.

**5.4** Give the function header for each of the following functions.

- a) Function `hypotenuse` that takes two double-precision floating-point arguments, `side1` and `side2`, and returns a double-precision floating-point result.
- b) Function `smallest` that takes three integers, `x`, `y`, `z`, and returns an integer.
- c) Function `instructions` that does not receive any arguments and does not return a value. [*Note:* Such functions are commonly used to display instructions to a user.]
- d) Function `intToFloat` that takes an integer argument, `number`, and returns a floating-point result.

**5.5** Give the function prototype for each of the following:

- a) The function described in Exercise 5.4(a).
- b) The function described in Exercise 5.4(b).
- c) The function described in Exercise 5.4(c).
- d) The function described in Exercise 5.4(d).

**5.6** Write a declaration for each of the following:

- a) Integer count that should be maintained in a register. Initialize count to 0.
- b) Floating-point variable `lastVal` that is to retain its value between calls to the function in which it's defined.
- c) External integer number whose scope should be restricted to the remainder of the file in which it's defined.

**5.7** Find the error in each of the following program segments and explain how the error can be corrected (see also Exercise 5.46):

- a) `int g( void )`  
 {  
     printf( "Inside function g\n" );  
     int h( void )  
     {  
         printf( "Inside function h\n" );  
     }  
 }
- b) `int sum( int x, int y )`  
 {  
     int result;  
     result = x + y;  
 }
- c) `int sum( int n )`  
 {  
     if ( n == 0 ) {  
         return 0;  
     }  
     else {  
         n + sum( n - 1 );  
     }  
 }
- d) `void f( float a );`  
 {  
     float a;  
     printf( "%f", a );  
 }
- e) `void product( void )`  
 {  
     int a, b, c, result;  
     printf( "Enter three integers: " );  
     scanf( "%d%d%d", &a, &b, &c );  
     result = a \* b \* c;  
     printf( "Result is %d", result );  
     return result;  
 }

## Answers to Self-Review Exercises

**5.1** a) Function. b) Function call. c) Local variable. d) return. e) void. f) Scope. g) return; or return expression; or encountering the closing right brace of a function. h) Function prototype. i) rand. j) srand. k) auto, register, extern, static. l) auto. m) register. n) External, global. o) static. p) Function scope, file scope, block scope, function prototype scope. q) Recursive. r) Base.

**5.2** a) Block scope. b) Block Scope. c) File scope. d) File scope. e) File scope. f) Function-prototype scope.

**5.3** See below. [Note: On most Linux systems, you must use the `-lm` option when compiling this program.]

```

1 /* ex05_03.c */
2 /* Testing the math library functions */
3 #include <stdio.h>
4 #include <math.h>
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 /* calculates and outputs the square root */
10 printf("sqrt(%.1f) = %.1f\n", 900.0, sqrt(900.0));
11 printf("sqrt(%.1f) = %.1f\n", 9.0, sqrt(9.0));
12
13 /* calculates and outputs the exponential function e to the x */
14 printf("exp(%.1f) = %f\n", 1.0, exp(1.0));
15 printf("exp(%.1f) = %f\n", 2.0, exp(2.0));
16
17 /* calculates and outputs the logarithm (base e) */
18 printf("log(%f) = %.1f\n", 2.718282, log(2.718282));
19 printf("log(%f) = %.1f\n", 7.389056, log(7.389056));
20
21 /* calculates and outputs the logarithm (base 10) */
22 printf("log10(%.1f) = %.1f\n", 1.0, log10(1.0));
23 printf("log10(%.1f) = %.1f\n", 10.0, log10(10.0));
24 printf("log10(%.1f) = %.1f\n", 100.0, log10(100.0));
25
26 /* calculates and outputs the absolute value */
27 printf("fabs(%.1f) = %.1f\n", 13.5, fabs(13.5));
28 printf("fabs(%.1f) = %.1f\n", 0.0, fabs(0.0));
29 printf("fabs(%.1f) = %.1f\n", -13.5, fabs(-13.5));
30
31 /* calculates and outputs ceil(x) */
32 printf("ceil(%.1f) = %.1f\n", 9.2, ceil(9.2));
33 printf("ceil(%.1f) = %.1f\n", -9.8, ceil(-9.8));
34
35 /* calculates and outputs floor(x) */
36 printf("floor(%.1f) = %.1f\n", 9.2, floor(9.2));
37 printf("floor(%.1f) = %.1f\n", -9.8, floor(-9.8));
38
39 /* calculates and outputs pow(x, y) */
40 printf("pow(%.1f, %.1f) = %.1f\n", 2.0, 7.0, pow(2.0, 7.0));
41 printf("pow(%.1f, %.1f) = %.1f\n", 9.0, 0.5, pow(9.0, 0.5));
42
43 /* calculates and outputs fmod(x, y) */
44 printf("fmod(%.3f/%.3f) = %.3f\n", 13.675, 2.333,
45 fmod(13.675, 2.333));
46
47 /* calculates and outputs sin(x) */
48 printf("sin(%.1f) = %.1f\n", 0.0, sin(0.0));
49
50 /* calculates and outputs cos(x) */
51 printf("cos(%.1f) = %.1f\n", 0.0, cos(0.0));
52
53 /* calculates and outputs tan(x) */
54 printf("tan(%.1f) = %.1f\n", 0.0, tan(0.0));
55 return 0; /* indicates successful termination */
56 } /* end main */

```

```

sqrt(900.0) = 30.0
sqrt(9.0) = 3.0
exp(1.0) = 2.718282
exp(2.0) = 7.389056
log(2.718282) = 1.0
log(7.389056) = 2.0
log10(1.0) = 0.0
log10(10.0) = 1.0
log10(100.0) = 2.0
fabs(13.5) = 13.5
fabs(0.0) = 0.0
fabs(-13.5) = 13.5
ceil(9.2) = 10.0
ceil(-9.8) = -9.0
floor(9.2) = 9.0
floor(-9.8) = -10.0
pow(2.0, 7.0) = 128.0
pow(9.0, 0.5) = 3.0
fmod(13.675/2.333) = 2.010
sin(0.0) = 0.0
cos(0.0) = 1.0
tan(0.0) = 0.0

```

- 5.4 a) `double` hypotenuse( `double` side1, `double` side2 )  
 b) `int` smallest( `int` x, `int` y, `int` z )  
 c) `void` instructions( `void` )  
 d) `float` intToFloat( `int` number )

- 5.5 a) `double` hypotenuse( `double` side1, `double` side2 );  
 b) `int` smallest( `int` x, `int` y, `int` z );  
 c) `void` instructions( `void` );  
 d) `float` intToFloat( `int` number );

- 5.6 a) `register int` count = 0;  
 b) `static float` lastVal;  
 c) `static int` number;  
 [Note: This would appear outside any function definition.]

- 5.7 a) Error: Function h is defined in function g.  
 Correction: Move the definition of h out of the definition of g.  
 b) Error: The body of the function is supposed to return an integer, but does not.  
 Correction: Delete variable result and place the following statement in the function:

```
return x + y;
```

- c) Error: The result of `n + sum( n - 1 )` is not returned; sum returns an improper result.  
 Correction: Rewrite the statement in the else clause as

```
return n + sum(n - 1);
```

- d) Error: Semicolon after the right parenthesis that encloses the parameter list, and re-defining the parameter a in the function definition.  
 Correction: Delete the semicolon after the right parenthesis of the parameter list, and delete the declaration `float a;` in the function body.  
 e) Error: The function returns a value when it's not supposed to.  
 Correction: Eliminate the return statement.

## Exercises

**5.8** Show the value of `x` after each of the following statements is performed:

- a) `x = fabs( 7.5 );`
- b) `x = floor( 7.5 );`
- c) `x = fabs( 0.0 );`
- d) `x = ceil( 0.0 );`
- e) `x = fabs( -6.4 );`
- f) `x = ceil( -6.4 );`
- g) `x = ceil( -fabs( -8 + floor( -5.5 ) ) );`

**5.9** (*Parking Charges*) A parking garage charges a \$2.00 minimum fee to park for up to three hours and an additional \$0.50 per hour for each hour *or part thereof* over three hours. The maximum charge for any given 24-hour period is \$10.00. Assume that no car parks for longer than 24 hours at a time. Write a program that will calculate and print the parking charges for each of three customers who parked their cars in this garage yesterday. You should enter the hours parked for each customer. Your program should print the results in a neat tabular format, and should calculate and print the total of yesterday's receipts. The program should use the function `calculateCharges` to determine the charge for each customer. Your outputs should appear in the following format:

| Car   | Hours | Charge |
|-------|-------|--------|
| 1     | 1.5   | 2.00   |
| 2     | 4.0   | 2.50   |
| 3     | 24.0  | 10.00  |
| TOTAL | 29.5  | 14.50  |

**5.10** (*Rounding Numbers*) An application of function `floor` is rounding a value to the nearest integer. The statement

```
y = floor(x + .5);
```

will round the number `x` to the nearest integer and assign the result to `y`. Write a program that reads several numbers and uses the preceding statement to round each of these numbers to the nearest integer. For each number processed, print both the original number and the rounded number.

**5.11** (*Rounding Numbers*) Function `floor` may be used to round a number to a specific decimal place. The statement

```
y = floor(x * 10 + .5) / 10;
```

rounds `x` to the tenths position (the first position to the right of the decimal point). The statement

```
y = floor(x * 100 + .5) / 100;
```

rounds `x` to the hundredths position (the second position to the right of the decimal point). Write a program that defines four functions to round a number `x` in various ways

- a) `roundToInteger( number )`
- b) `roundToTenths( number )`
- c) `roundToHundredths( number )`
- d) `roundToThousandths( number )`

For each value read, your program should print the original value, the number rounded to the nearest integer, the number rounded to the nearest tenth, the number rounded to the nearest hundredth, and the number rounded to the nearest thousandth.

**5.12** Answer each of the following questions.

- a) What does it mean to choose numbers “at random”?
- b) Why is the `rand` function useful for simulating games of chance?
- c) Why would you randomize a program by using `srand`? Under what circumstances is it desirable not to randomize?

- d) Why is it often necessary to scale and/or shift the values produced by `rand`?
- e) Why is computerized simulation of real-world situations a useful technique?

**5.13** Write statements that assign random integers to the variable  $n$  in the following ranges:

- a)  $1 \leq n \leq 2$
- b)  $1 \leq n \leq 100$
- c)  $0 \leq n \leq 9$
- d)  $1000 \leq n \leq 1112$
- e)  $-1 \leq n \leq 1$
- f)  $-3 \leq n \leq 11$

**5.14** For each of the following sets of integers, write a single statement that will print a number at random from the set.

- a) 2, 4, 6, 8, 10.
- b) 3, 5, 7, 9, 11.
- c) 6, 10, 14, 18, 22.

**5.15** (*Hypotenuse Calculations*) Define a function called `hypotenuse` that calculates the length of the hypotenuse of a right triangle when the other two sides are given. Use this function in a program to determine the length of the hypotenuse for each of the following triangles. The function should take two arguments of type `double` and return the hypotenuse as a `double`. Test your program with the side values specified in Fig. 5.18.

**5.16** (*Exponentiation*) Write a function `integerPower(base, exponent)` that returns the value of  $\text{base}^{\text{exponent}}$

For example, `integerPower(3, 4) = 3 * 3 * 3 * 3`. Assume that `exponent` is a positive, nonzero integer, and `base` is an integer. Function `integerPower` should use `for` to control the calculation. Do not use any math library functions.

**5.17** (*Multiples*) Write a function `multiple` that determines for a pair of integers whether the second integer is a multiple of the first. The function should take two integer arguments and return 1 (true) if the second is a multiple of the first, and 0 (false) otherwise. Use this function in a program that inputs a series of pairs of integers.

**5.18** (*Even or Odd*) Write a program that inputs a series of integers and passes them one at a time to function `even`, which uses the remainder operator to determine if an integer is even. The function should take an integer argument and return 1 if the integer is even and 0 otherwise.

**5.19** (*Parking Charges*) Write a function that displays a solid square of asterisks whose side is specified in integer parameter `side`. For example, if `side` is 4, the function displays:

```



```

**5.20** (*Displaying a Square of Any Character*) Modify the function created in Exercise 5.19 to form the square out of whatever character is contained in character parameter `fillCharacter`. Thus if `side` is 5 and `fillCharacter` is “#” then this function should print:

```
#####
#####
#####
#####
#####
```

| Triangle | Side 1 | Side 2 |
|----------|--------|--------|
| 1        | 3.0    | 4.0    |
| 2        | 5.0    | 12.0   |
| 3        | 8.0    | 15.0   |

**Fig. 5.18** | Sample triangle side values for Exercise 5.15.

**5.21** (*Project: Drawing Shapes with Characters*) Use techniques similar to those developed in Exercises 5.19–5.20 to produce a program that graphs a wide range of shapes.

**5.22** (*Separating Digits*) Write program segments that accomplish each of the following:

- Calculate the integer part of the quotient when integer *a* is divided by integer *b*.
- Calculate the integer remainder when integer *a* is divided by integer *b*.
- Use the program pieces developed in a) and b) to write a function that inputs an integer between 1 and 32767 and prints it as a series of digits, with two spaces between each digit. For example, the integer 4562 should be printed as:

```
4 5 6 2
```

**5.23** (*Time in Seconds*) Write a function that takes the time as three integer arguments (for hours, minutes, and seconds) and returns the number of seconds since the last time the clock “struck 12.” Use this function to calculate the amount of time in seconds between two times, both of which are within one 12-hour cycle of the clock.

**5.24** (*Temperature Conversions*) Implement the following integer functions:

- Function `celsius` returns the Celsius equivalent of a Fahrenheit temperature.
- Function `fahrenheit` returns the Fahrenheit equivalent of a Celsius temperature.
- Use these functions to write a program that prints charts showing the Fahrenheit equivalents of all Celsius temperatures from 0 to 100 degrees, and the Celsius equivalents of all Fahrenheit temperatures from 32 to 212 degrees. Print the outputs in a neat tabular format that minimizes the number of lines of output while remaining readable.

**5.25** (*Find the Minimum*) Write a function that returns the smallest of three floating-point numbers.

**5.26** (*Perfect Numbers*) An integer number is said to be a *perfect number* if its factors, including 1 (but not the number itself), sum to the number. For example, 6 is a perfect number because  $6 = 1 + 2 + 3$ . Write a function `perfect` that determines if parameter `number` is a perfect number. Use this function in a program that determines and prints all the perfect numbers between 1 and 1000. Print the factors of each perfect number to confirm that the number is indeed perfect. Challenge the power of your computer by testing numbers much larger than 1000.

**5.27** (*Prime Numbers*) An integer is said to be *prime* if it’s divisible by only 1 and itself. For example, 2, 3, 5 and 7 are prime, but 4, 6, 8 and 9 are not.

- Write a function that determines if a number is prime.
- Use this function in a program that determines and prints all the prime numbers between 1 and 10,000. How many of these 10,000 numbers do you really have to test before being sure that you have found all the primes?
- Initially you might think that  $n/2$  is the upper limit for which you must test to see if a number is prime, but you need go only as high as the square root of  $n$ . Why? Rewrite the program, and run it both ways. Estimate the performance improvement.

**5.28 (Reversing Digits)** Write a function that takes an integer value and returns the number with its digits reversed. For example, given the number 7631, the function should return 1367.

**5.29 (Greatest Common Divisor)** The *greatest common divisor (GCD)* of two integers is the largest integer that evenly divides each of the two numbers. Write function `gcd` that returns the greatest common divisor of two integers.

**5.30** Write a function `qualityPoints` that inputs a student's average and returns 4 if a student's average is 90–100, 3 if the average is 80–89, 2 if the average is 70–79, 1 if the average is 60–69, and 0 if the average is lower than 60.

**5.31 (Coin Tossing)** Write a program that simulates coin tossing. For each toss of the coin the program should print `Heads` or `Tails`. Let the program toss the coin 100 times, and count the number of times each side of the coin appears. Print the results. The program should call a separate function `flip` that takes no arguments and returns 0 for tails and 1 for heads. [Note: If the program realistically simulates the coin tossing, then each side of the coin should appear approximately half the time for a total of approximately 50 heads and 50 tails.]

**5.32 (Guess the Number)** Write a C program that plays the game of “guess the number” as follows: Your program chooses the number to be guessed by selecting an integer at random in the range 1 to 1000. The program then types:

I have a number between 1 and 1000.  
Can you guess my number?  
Please type your first guess.

The player then types a first guess. The program responds with one of the following:

1. Excellent! You guessed the number!  
    Would you like to play again (y or n)?
2. Too low. Try again.
3. Too high. Try again.

If the player's guess is incorrect, your program should loop until the player finally gets the number right. Your program should keep telling the player `Too high` or `Too low` to help the player “zero in” on the correct answer. [Note: The searching technique employed in this problem is called binary search. We'll say more about this in the next problem.]

**5.33 (Guess the Number Modification)** Modify the program of Exercise 5.32 to count the number of guesses the player makes. If the number is 10 or fewer, print `Either you know the secret or you got lucky!` If the player guesses the number in 10 tries, then print `Ahah! You know the secret!` If the player makes more than 10 guesses, then print `You should be able to do better!` Why should it take no more than 10 guesses? Well, with each “good guess” the player should be able to eliminate half of the numbers. Now show why any number 1 to 1000 can be guessed in 10 or fewer tries.

**5.34 (Recursive Exponentiation)** Write a recursive function `power( base, exponent )` that when invoked returns

$$\text{base}^{\text{exponent}}$$

For example, `power( 3, 4 ) = 3 * 3 * 3 * 3`. Assume that `exponent` is an integer greater than or equal to 1. *Hint:* The recursion step would use the relationship

$$\text{base}^{\text{exponent}} = \text{base} * \text{base}^{\text{exponent}-1}$$

and the terminating condition occurs when `exponent` is equal to 1 because

$$\text{base}^1 = \text{base}$$




**5.35 (Fibonacci)** The Fibonacci series

0, 1, 1, 2, 3, 5, 8, 13, 21, ...

begins with the terms 0 and 1 and has the property that each succeeding term is the sum of the two preceding terms. a) Write a *nonrecursive* function `fibonacci(n)` that calculates the  $n^{\text{th}}$  Fibonacci number. b) Determine the largest Fibonacci number that can be printed on your system. Modify the program of part a) to use `double` instead of `int` to calculate and return Fibonacci numbers. Let the program loop until it fails because of an excessively high value.

**5.36 (Towers of Hanoi)** Every budding computer scientist must grapple with certain classic problems, and the Towers of Hanoi (see Fig. 5.19) is one of the most famous of these. Legend has it that in a temple in the Far East, priests are attempting to move a stack of disks from one peg to another. The initial stack had 64 disks threaded onto one peg and arranged from bottom to top by decreasing size. The priests are attempting to move the stack from this peg to a second peg under the constraints that exactly one disk is moved at a time, and at no time may a larger disk be placed above a smaller disk. A third peg is available for temporarily holding the disks. Supposedly the world will end when the priests complete their task, so there is little incentive for us to facilitate their efforts.



**Fig. 5.19** | Towers of Hanoi for the case with four disks.

Let's assume that the priests are attempting to move the disks from peg 1 to peg 3. We wish to develop an algorithm that will print the precise sequence of disk-to-disk peg transfers.

If we were to approach this problem with conventional methods, we'd rapidly find ourselves hopelessly knotted up in managing the disks. Instead, if we attack the problem with recursion in mind, it immediately becomes tractable. Moving  $n$  disks can be viewed in terms of moving only  $n - 1$  disks (and hence the recursion) as follows:

- a) Move  $n - 1$  disks from peg 1 to peg 2, using peg 3 as a temporary holding area.
- b) Move the last disk (the largest) from peg 1 to peg 3.
- c) Move the  $n - 1$  disks from peg 2 to peg 3, using peg 1 as a temporary holding area.

The process ends when the last task involves moving  $n = 1$  disk, i.e., the base case. This is accomplished by trivially moving the disk without the need for a temporary holding area.

Write a program to solve the Towers of Hanoi problem. Use a recursive function with four parameters:

- a) The number of disks to be moved
- b) The peg on which these disks are initially threaded
- c) The peg to which this stack of disks is to be moved
- d) The peg to be used as a temporary holding area

Your program should print the precise instructions it will take to move the disks from the starting peg to the destination peg. For example, to move a stack of three disks from peg 1 to peg 3, your program should print the following series of moves:

```
1 → 3 (This means move one disk from peg 1 to peg 3.)
1 → 2
3 → 2
1 → 3
2 → 1
2 → 3
1 → 3
```

**5.37 (Towers of Hanoi: Iterative Solution)** Any program that can be implemented recursively can be implemented iteratively, although sometimes with considerably more difficulty and considerably less clarity. Try writing an iterative version of the Towers of Hanoi. If you succeed, compare your iterative version with the recursive version you developed in Exercise 5.36. Investigate issues of performance, clarity, and your ability to demonstrate the correctness of the programs.

**5.38 (Visualizing Recursion)** It's interesting to watch recursion "in action." Modify the factorial function of Fig. 5.14 to print its local variable and recursive call parameter. For each recursive call, display the outputs on a separate line and add a level of indentation. Do your utmost to make the outputs clear, interesting and meaningful. Your goal here is to design and implement an output format that helps a person understand recursion better. You may want to add such display capabilities to the many other recursion examples and exercises throughout the text.

**5.39 (Recursive Greatest Common Divisor)** The greatest common divisor of integers  $x$  and  $y$  is the largest integer that evenly divides both  $x$  and  $y$ . Write a recursive function `gcd` that returns the greatest common divisor of  $x$  and  $y$ . The `gcd` of  $x$  and  $y$  is defined recursively as follows: If  $y$  is equal to 0, then `gcd(x, y)` is  $x$ ; otherwise `gcd(x, y)` is `gcd(y, x % y)` where `%` is the remainder operator.

**5.40 (Recursive main)** Can `main` be called recursively? Write a program containing a function `main`. Include static local variable `count` initialized to 1. Postincrement and print the value of `count` each time `main` is called. Run your program. What happens?

**5.41 (Distance Between Points)** Write function `distance` that calculates the distance between two points  $(x1, y1)$  and  $(x2, y2)$ . All numbers and return values should be of type `double`.

**5.42** What does the following program do?

```
1 #include <stdio.h>
2
3 /* function main begins program execution */
4 int main(void)
5 {
6 int c; /* variable to hold character input by user */
7
8 if ((c = getchar()) != EOF) {
9 main();
10 printf("%c", c);
11 } /* end if */
12
13 return 0; /* indicates successful termination */
14 } /* end main */
```

**5.43** What does the following program do?

```
1 #include <stdio.h>
2
3 int mystery(int a, int b); /* function prototype */
```

```

4
5 /* function main begins program execution */
6 int main(void)
7 {
8 int x; /* first integer */
9 int y; /* second integer */
10
11 printf("Enter two integers: ");
12 scanf("%d%d", &x, &y);
13
14 printf("The result is %d\n", mystery(x, y));
15 return 0; /* indicates successful termination */
16 } /* end main */
17
18 /* Parameter b must be a positive integer
19 to prevent infinite recursion */
20 int mystery(int a, int b)
21 {
22 /* base case */
23 if (b == 1) {
24 return a;
25 } /* end if */
26 else { /* recursive step */
27 return a + mystery(a, b - 1);
28 } /* end else */
29 } /* end function mystery */

```

**5.44** After you determine what the program of Exercise 5.43 does, modify the program to function properly after removing the restriction of the second argument being nonnegative.

**5.45** (*Testing Math Library Functions*) Write a program that tests as many of the math library functions in Fig. 5.2 as you can. Exercise each of these functions by having your program print out tables of return values for a diversity of argument values.

**5.46** Find the error in each of the following program segments and explain how to correct it:

- a) `double cube( float );` /\* function prototype \*/  
`cube( float number )` /\* function definition \*/  
`{`  
`return number * number * number;`  
`}`
- b) `register auto int x = 7;`
- c) `int randomNumber = srand();`
- d) `double y = 123.45678;`  
`int x;`  
`x = y;`  
`printf( "%f\n", (double) x );`
- e) `double square( double number )`  
`{`  
`double number;`  
`return number * number;`  
`}`
- f) `int sum( int n )`  
`{`  
`if ( n == 0 ) {`  
`return 0;`  
`}`

```

else {
 return n + sum(n);
}
}

```

**5.47 (Craps Game Modification)** Modify the craps program of Fig. 5.10 to allow wagering. Package as a function the portion of the program that runs one game of craps. Initialize variable `bankBalance` to 1000 dollars. Prompt the player to enter a wager. Use a `while` loop to check that wager is less than or equal to `bankBalance`, and if not, prompt the user to reenter wager until a valid wager is entered. After a correct wager is entered, run one game of craps. If the player wins, increase `bankBalance` by wager and print the new `bankBalance`. If the player loses, decrease `bankBalance` by wager, print the new `bankBalance`, check if `bankBalance` has become zero, and if so print the message, "Sorry. You busted!" As the game progresses, print various messages to create some "chatter" such as, "Oh, you're going for broke, huh?" or "Aw cmon, take a chance!" or "You're up big. Now's the time to cash in your chips!"

**5.48 (Research Project: Improving the Recursive Fibonacci Implementation)** In Section 5.15, the recursive algorithm we used to calculate Fibonacci numbers was intuitively appealing. However, recall that the algorithm resulted in the exponential explosion of recursive function calls. Research the recursive Fibonacci implementation online. Study the various approaches, including the iterative version in Exercise 5.35 and versions that use only so-called "tail recursion." Discuss the relative merits of each.

## Making a Difference

**5.49 (Global Warming Facts Quiz)** The controversial issue of global warming has been widely publicized by the film *An Inconvenient Truth*, featuring former Vice President Al Gore. Mr. Gore and a U.N. network of scientists, the Intergovernmental Panel on Climate Change, shared the 2007 Nobel Peace Prize in recognition of "their efforts to build up and disseminate greater knowledge about man-made climate change." Research *both* sides of the global warming issue online (you might want to search for phrases like "global warming skeptics"). Create a five-question multiple-choice quiz on global warming, each question having four possible answers (numbered 1–4). Be objective and try to fairly represent both sides of the issue. Next, write an application that administers the quiz, calculates the number of correct answers (zero through five) and returns a message to the user. If the user correctly answers five questions, print "Excellent"; if four, print "Very good"; if three or fewer, print "Time to brush up on your knowledge of global warming," and include a list of some of the websites where you found your facts.

## Computer Assisted Instruction

As computer costs decline, it becomes feasible for every student, regardless of economic circumstance, to have a computer and use it in school. This creates exciting possibilities for improving the educational experience of all students worldwide as suggested by the next five exercises. [Note: Check out initiatives such as the One Laptop Per Child Project ([www.1laptop.org](http://www.1laptop.org)). Also, research "green" laptops—what are some key "going green" characteristics of these devices? Look into the Electronic Product Environmental Assessment Tool ([www.epeat.net](http://www.epeat.net)) which can help you assess the "greenness" of desktops, notebooks and monitors to help you decide which products to purchase.]

**5.50 (Computer-Assisted Instruction)** The use of computers in education is referred to as *computer-assisted instruction* (CAI). Write a program that will help an elementary school student learn multiplication. Use the `rand` function to produce two positive one-digit integers. The program should then prompt the user with a question, such as

How much is 6 times 7?

The student then inputs the answer. Next, the program checks the student's answer. If it's correct, display the message "Very good!" and ask another multiplication question. If the answer is wrong, display the message "No. Please try again." and let the student try the same question repeatedly until the student finally gets it right. A separate function should be used to generate each new question. This function should be called once when the application begins execution and each time the user answers the question correctly.

**5.51** (*Computer-Assisted Instruction: Reducing Student Fatigue*) One problem in CAI environments is student fatigue. This can be reduced by varying the computer's responses to hold the student's attention. Modify the program of Exercise 5.50 so that various comments are displayed for each answer as follows:

Possible responses to a correct answer:

```
Very good!
Excellent!
Nice work!
Keep up the good work!
```

Possible responses to an incorrect answer:

```
No. Please try again.
Wrong. Try once more.
Don't give up!
No. Keep trying.
```

Use random-number generation to choose a number from 1 to 4 that will be used to select one of the four appropriate responses to each correct or incorrect answer. Use a `switch` statement to issue the responses.

**5.52** (*Computer-Assisted Instruction: Monitoring Student Performance*) More sophisticated computer-assisted instruction systems monitor the student's performance over a period of time. The decision to begin a new topic is often based on the student's success with previous topics. Modify the program of Exercise 5.51 to count the number of correct and incorrect responses typed by the student. After the student types 10 answers, your program should calculate the percentage that are correct. If the percentage is lower than 75%, display "Please ask your teacher for extra help.", then reset the program so another student can try it. If the percentage is 75% or higher, display "Congratulations, you are ready to go to the next level!", then reset the program so another student can try it.

**5.53** (*Computer-Assisted Instruction: Difficulty Levels*) Exercise 5.50 through Exercise 5.52 developed a computer-assisted instruction program to help teach an elementary school student multiplication. Modify the program to allow the user to enter a difficulty level. At a difficulty level of 1, the program should use only single-digit numbers in the problems; at a difficulty level of 2, numbers as large as two digits, and so on.

**5.54** (*Computer-Assisted Instruction: Varying the Types of Problems*) Modify the program of Exercise 5.53 to allow the user to pick a type of arithmetic problem to study. An option of 1 means addition problems only, 2 means subtraction problems only, 3 means multiplication problems only and 4 means a random mixture of all these types.

# C Arrays

# 6

*Now go, write it  
before them in a table,  
and note it in a book.*

—Isaiah 30:8

*To go beyond is as  
wrong as to fall short.*

—Confucius

*Begin at the beginning, ... and  
go on till you come to the end:  
then stop.*

—Lewis Carroll

## Objectives

In this chapter, you'll learn:

- To use the array data structure to represent lists and tables of values.
- To define an array, initialize an array and refer to individual elements of an array.
- To define symbolic constants.
- To pass arrays to functions.
- To use arrays to store, sort and search lists and tables of values.
- To define and manipulate multiple-subscripted arrays.



- |                                        |                                                                     |
|----------------------------------------|---------------------------------------------------------------------|
| <b>6.1</b> Introduction                | <b>6.6</b> Sorting Arrays                                           |
| <b>6.2</b> Arrays                      | <b>6.7</b> Case Study: Computing Mean, Median and Mode Using Arrays |
| <b>6.3</b> Defining Arrays             | <b>6.8</b> Searching Arrays                                         |
| <b>6.4</b> Array Examples              | <b>6.9</b> Multiple-Subscripted Arrays                              |
| <b>6.5</b> Passing Arrays to Functions |                                                                     |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises  
 Recursion Exercises | Special Section: Sudoku

## 6.1 Introduction

This chapter serves as an introduction to the important topic of data structures. **Arrays** are data structures consisting of related data items of the same type. In Chapter 10, we discuss C's notion of **struct** (structure)—a data structure consisting of related data items of possibly different types. Arrays and structures are “static” entities in that they remain the same size throughout program execution (they may, of course, be of automatic storage class and hence created and destroyed each time the blocks in which they are defined are entered and exited). In Chapter 12, we introduce dynamic data structures such as lists, queues, stacks and trees that may grow and shrink as programs execute.

## 6.2 Arrays

An array is a group of memory locations related by the fact that they all have the same name and the same type. To refer to a particular location or element in the array, we specify the name of the array and the **position number** of the particular element in the array.

Figure 6.1 shows an integer array called *c*. This array contains 12 **elements**. Any one of these elements may be referred to by giving the name of the array followed by the position number of the particular element in square brackets (`[]`). The first element in every array is the **zeroth element**. Thus, the first element of array *c* is referred to as `c[0]`, the second element of array *c* is referred to as `c[1]`, the seventh element of array *c* is referred to as `c[6]`, and, in general, the *i*th element of array *c* is referred to as `c[i - 1]`. Array names, like other variable names, can contain only letters, digits and underscores. Array names cannot begin with a digit.

The position number contained within square brackets is more formally called a **subscript** (or **index**). A subscript must be an integer or an integer expression. If a program uses an expression as a subscript, then the expression is evaluated to determine the subscript. For example, if *a* = 5 and *b* = 6, then the statement

```
c[a + b] += 2;
```

adds 2 to array element `c[11]`. A subscripted array name is an *lvalue*—it can be used on the left side of an assignment.

Let's examine array *c* (Fig. 6.1) more closely. The array's **name** is *c*. Its 12 elements are referred to as `c[0]`, `c[1]`, `c[2]`, ..., `c[11]`. The **value** stored in `c[0]` is -45, the value of `c[1]` is 6, the value of `c[2]` is 0, the value of `c[7]` is 62 and the value of `c[11]` is 78. To print the sum of the values contained in the first three elements of array *c*, we'd write

```
printf("%d", c[0] + c[1] + c[2]);
```

Name of array (note that all elements of this array have the same name, c)

|         |      |
|---------|------|
| c[ 0 ]  | -45  |
| c[ 1 ]  | 6    |
| c[ 2 ]  | 0    |
| c[ 3 ]  | 72   |
| c[ 4 ]  | 1543 |
| c[ 5 ]  | -89  |
| c[ 6 ]  | 0    |
| c[ 7 ]  | 62   |
| c[ 8 ]  | -3   |
| c[ 9 ]  | 1    |
| c[ 10 ] | 6453 |
| c[ 11 ] | 78   |

Position number of the element within array c

**Fig. 6.1** | 12-element array.

To divide the value of the seventh element of array c by 2 and assign the result to the variable x, we'd write

```
x = c[6] / 2;
```



### Common Programming Error 6.1

*It's important to note the difference between the “seventh element of the array” and “array element seven.” Because array subscripts begin at 0, the “seventh element of the array” has a subscript of 6, while “array element seven” has a subscript of 7 and is actually the eighth element of the array. This is a source of “off-by-one” errors.*

The brackets used to enclose the subscript of an array are actually considered to be an operator in C. They have the same level of precedence as the function call operator (i.e., the parentheses that are placed following a function name to call that function). Figure 6.2 shows the precedence and associativity of the operators introduced to this point in the text.

| Operators |    |   |        | Associativity | Type           |
|-----------|----|---|--------|---------------|----------------|
| [ ]       | () |   |        | left to right | highest        |
| ++        | -- | ! | (type) | right to left | unary          |
| *         | /  | % |        | left to right | multiplicative |

**Fig. 6.2** | Operator precedence and associativity. (Part I of 2.)



| Operators |                | Associativity | Type        |
|-----------|----------------|---------------|-------------|
| +         | -              | left to right | additive    |
| <         | <= > >=        | left to right | relational  |
| ==        | !=             | left to right | equality    |
| &&        |                | left to right | logical AND |
|           |                | left to right | logical OR  |
| ?:        |                | right to left | conditional |
| =         | += -= *= /= %= | right to left | assignment  |
| ,         |                | left to right | comma       |

Fig. 6.2 | Operator precedence and associativity. (Part 2 of 2.)

### 6.3 Defining Arrays

Arrays occupy space in memory. You specify the type of each element and the number of elements required by each array so that the computer may reserve the appropriate amount of memory. To tell the computer to reserve 12 elements for integer array `c`, the definition

```
int c[12];
```

is used. The following definition

```
int b[100], x[27];
```

reserves 100 elements for integer array `b` and 27 elements for integer array `x`.

Arrays may contain other data types. For example, an array of type `char` can be used to store a character string. Character strings and their similarity to arrays are discussed in Chapter 8. The relationship between pointers and arrays is discussed in Chapter 7.

### 6.4 Array Examples

This section presents several examples that demonstrate how to define arrays, how to initialize arrays and how to perform many common array manipulations.

#### *Defining an Array and Using a Loop to Initialize the Array's Elements*

Figure 6.3 uses `for` statements to initialize the elements of a 10-element integer array `n` to zeros and print the array in tabular format. The first `printf` statement (line 16) displays the column heads for the two columns printed in the subsequent `for` statement.

```
1 /* Fig. 6.3: fig06_03.c
2 initializing an array */
3 #include <stdio.h>
4
5 /* function main begins program execution */
6 int main(void)
7 {
```

Fig. 6.3 | Initializing the elements of an array to zeros. (Part 1 of 2.)

```

8 int n[10]; /* n is an array of 10 integers */
9 int i; /* counter */
10
11 /* initialize elements of array n to 0 */
12 for (i = 0; i < 10; i++) {
13 n[i] = 0; /* set element at location i to 0 */
14 } /* end for */
15
16 printf("%s%13s\n", "Element", "Value");
17
18 /* output contents of array n in tabular format */
19 for (i = 0; i < 10; i++) {
20 printf("%7d%13d\n", i, n[i]);
21 } /* end for */
22
23 return 0; /* indicates successful termination */
24 } /* end main */

```

| Element | Value |
|---------|-------|
| 0       | 0     |
| 1       | 0     |
| 2       | 0     |
| 3       | 0     |
| 4       | 0     |
| 5       | 0     |
| 6       | 0     |
| 7       | 0     |
| 8       | 0     |
| 9       | 0     |

**Fig. 6.3** | Initializing the elements of an array to zeros. (Part 2 of 2.)

### *Initializing an Array in a Definition with an Initializer List*

The elements of an array can also be initialized when the array is defined by following the definition with an equals sign and braces, {}, containing a comma-separated list of **initializers**. Figure 6.4 initializes an integer array with 10 values (line 9) and prints the array in tabular format.

```

1 /* Fig. 6.4: fig06_04.c
2 Initializing an array with an initializer list */
3 #include <stdio.h>
4
5 /* function main begins program execution */
6 int main(void)
7 {
8 /* use initializer list to initialize array n */
9 int n[10] = { 32, 27, 64, 18, 95, 14, 90, 70, 60, 37 };
10 int i; /* counter */
11
12 printf("%s%13s\n", "Element", "Value");
13

```

**Fig. 6.4** | Initializing the elements of an array with an initializer list. (Part 1 of 2.)

```

14 /* output contents of array in tabular format */
15 for (i = 0; i < 10; i++) {
16 printf("%7d%13d\n", i, n[i]);
17 } /* end for */
18
19 return 0; /* indicates successful termination */
20 } /* end main */

```

| Element | Value |
|---------|-------|
| 0       | 32    |
| 1       | 27    |
| 2       | 64    |
| 3       | 18    |
| 4       | 95    |
| 5       | 14    |
| 6       | 90    |
| 7       | 70    |
| 8       | 60    |
| 9       | 37    |

**Fig. 6.4** | Initializing the elements of an array with an initializer list. (Part 2 of 2.)

If there are fewer initializers than elements in the array, the remaining elements are initialized to zero. For example, the elements of the array `n` in Fig. 6.3 could have been initialized to zero as follows:

```
int n[10] = { 0 };
```

This explicitly initializes the first element to zero and initializes the remaining nine elements to zero because there are fewer initializers than there are elements in the array. It's important to remember that arrays are not automatically initialized to zero. You must at least initialize the first element to zero for the remaining elements to be automatically zeroed. This method of initializing the array elements to 0 is performed at compile time for static arrays and at runtime for automatic arrays.



### Common Programming Error 6.2

*Forgetting to initialize the elements of an array whose elements should be initialized.*

The array definition

```
int n[5] = { 32, 27, 64, 18, 95, 14 };
```

causes a syntax error because there are six initializers and only five array elements.



### Common Programming Error 6.3

*Providing more initializers in an array initializer list than there are elements in the array is a syntax error.*

If the array size is omitted from a definition with an initializer list, the number of elements in the array will be the number of elements in the initializer list. For example,

```
int n[] = { 1, 2, 3, 4, 5 };
```

would create a five-element array.

### *Specifying an Array's Size with a Symbolic Constant and Initializing Array Elements with Calculations*

Figure 6.5 initializes the elements of a 10-element array *s* to the values 2, 4, 6, ..., 20 and prints the array in tabular format. The values are generated by multiplying the loop counter by 2 and adding 2.

```

1 /* Fig. 6.5: fig06_05.c
2 Initialize the elements of array s to the even integers from 2 to 20 */
3 #include <stdio.h>
4 #define SIZE 10 /* maximum size of array */
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 /* symbolic constant SIZE can be used to specify array size */
10 int s[SIZE]; /* array s has SIZE elements */
11 int j; /* counter */
12
13 for (j = 0; j < SIZE; j++) { /* set the values */
14 s[j] = 2 + 2 * j;
15 } /* end for */
16
17 printf("%s%13s\n", "Element", "Value");
18
19 /* output contents of array s in tabular format */
20 for (j = 0; j < SIZE; j++) {
21 printf("%7d%13d\n", j, s[j]);
22 } /* end for */
23
24 return 0; /* indicates successful termination */
25 } /* end main */

```

| Element | Value |
|---------|-------|
| 0       | 2     |
| 1       | 4     |
| 2       | 6     |
| 3       | 8     |
| 4       | 10    |
| 5       | 12    |
| 6       | 14    |
| 7       | 16    |
| 8       | 18    |
| 9       | 20    |

**Fig. 6.5** | Initialize the elements of array *s* to the even integers from 2 to 20.

The `#define` preprocessor directive is introduced in this program. Line 4

```
#define SIZE 10
```

defines a **symbolic constant** `SIZE` whose value is 10. A symbolic constant is an identifier that is replaced with **replacement text** by the C preprocessor before the program is compiled. When the program is preprocessed, all occurrences of the symbolic constant `SIZE`

are replaced with the replacement text 10. Using symbolic constants to specify array sizes makes programs more **scalable**. In Fig. 6.5, we could have the first for loop (line 13) fill a 1000-element array by simply changing the value of SIZE in the `#define` directive from 10 to 1000. If the symbolic constant SIZE had not been used, we'd have to change the program in three separate places to scale the program to handle 1000 array elements. As programs get larger, this technique becomes more useful for writing clear programs.



#### Common Programming Error 6.4

*Ending a `#define` or `#include` preprocessor directive with a semicolon. Remember that preprocessor directives are not C statements.*

If the `#define` preprocessor directive in line 4 is terminated with a semicolon, all occurrences of the symbolic constant SIZE in the program are replaced with the text 10; by the preprocessor. This may lead to syntax errors at compile time, or logic errors at execution time. Remember that the preprocessor is not C—it's only a text manipulator.



#### Common Programming Error 6.5

*Assigning a value to a symbolic constant in an executable statement is a syntax error. A symbolic constant is not a variable. No space is reserved for it by the compiler as with variables that hold values at execution time.*



#### Software Engineering Observation 6.1

*Defining the size of each array as a symbolic constant makes programs more scalable.*



#### Good Programming Practice 6.1

*Use only uppercase letters for symbolic constant names. This makes these constants stand out in a program and reminds you that symbolic constants are not variables.*



#### Good Programming Practice 6.2

*In multiword symbolic constant names, use underscores to separate the words for readability.*

### Summing the Elements of an Array

Figure 6.6 sums the values contained in the 12-element integer array `a`. The for statement's body (line 16) does the totaling.

```
1 /* Fig. 6.6: fig06_06.c
2 Compute the sum of the elements of the array */
3 #include <stdio.h>
4 #define SIZE 12
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 /* use initializer list to initialize array */
10 int a[SIZE] = { 1, 3, 5, 4, 7, 2, 99, 16, 45, 67, 89, 45 };
```

**Fig. 6.6** | Computing the sum of the elements of an array. (Part I of 2.)

```

11 int i; /* counter */
12 int total = 0; /* sum of array */
13
14 /* sum contents of array a */
15 for (i = 0; i < SIZE; i++) {
16 total += a[i];
17 } /* end for */
18
19 printf("Total of array element values is %d\n", total);
20 return 0; /* indicates successful termination */
21 } /* end main */

```

Total of array element values is 383

**Fig. 6.6** | Computing the sum of the elements of an array. (Part 2 of 2.)

### Using Arrays to Summarize Survey Results

Our next example uses arrays to summarize the results of data collected in a survey. Consider the problem statement.

*Forty students were asked to rate the quality of the food in the student cafeteria on a scale of 1 to 10 (1 means awful and 10 means excellent). Place the 40 responses in an integer array and summarize the results of the poll.*

This is a typical array application (see Fig. 6.7). We wish to summarize the number of responses of each type (i.e., 1 through 10). The array `responses` (line 17) is a 40-element array of the students' responses. We use an 11-element array `frequency` (line 14) to count the number of occurrences of each response. We ignore `frequency[0]` because it's logical to have response 1 increment `frequency[1]` rather than `frequency[0]`. This allows us to use each response directly as the subscript in the frequency array.

```

1 /* Fig. 6.7: fig06_07.c
2 Student poll program */
3 #include <stdio.h>
4 #define RESPONSE_SIZE 40 /* define array sizes */
5 #define FREQUENCY_SIZE 11
6
7 /* function main begins program execution */
8 int main(void)
9 {
10 int answer; /* counter to loop through 40 responses */
11 int rating; /* counter to loop through frequencies 1-10 */
12
13 /* initialize frequency counters to 0 */
14 int frequency[FREQUENCY_SIZE] = { 0 };
15
16 /* place the survey responses in the responses array */
17 int responses[RESPONSE_SIZE] = { 1, 2, 6, 4, 8, 5, 9, 7, 8, 10,
18 1, 6, 3, 8, 6, 10, 3, 8, 2, 7, 6, 5, 7, 6, 8, 6, 7, 5, 6, 6,
19 5, 6, 7, 5, 6, 4, 8, 6, 8, 10 };

```

**Fig. 6.7** | Student poll analysis program. (Part 1 of 2.)

```

20
21 /* for each answer, select value of an element of array responses
22 and use that value as subscript in array frequency to
23 determine element to increment */
24 for (answer = 0; answer < RESPONSE_SIZE; answer++) {
25 ++frequency[responses [answer]];
26 } /* end for */
27
28 /* display results */
29 printf("%s%17s\n", "Rating", "Frequency");
30
31 /* output the frequencies in a tabular format */
32 for (rating = 1; rating < FREQUENCY_SIZE; rating++) {
33 printf("%6d%17d\n", rating, frequency[rating]);
34 } /* end for */
35
36 return 0; /* indicates successful termination */
37 } /* end main */

```

| Rating | Frequency |
|--------|-----------|
| 1      | 2         |
| 2      | 2         |
| 3      | 2         |
| 4      | 2         |
| 5      | 5         |
| 6      | 11        |
| 7      | 5         |
| 8      | 7         |
| 9      | 1         |
| 10     | 3         |

**Fig. 6.7** | Student poll analysis program. (Part 2 of 2.)



### Good Programming Practice 6.3

*Strive for program clarity. Sometimes it may be worthwhile to trade off the most efficient use of memory or processor time in favor of writing clearer programs.*



### Performance Tip 6.1

*Sometimes performance considerations far outweigh clarity considerations.*

The for loop (line 24) takes the responses one at a time from the array `responses` and increments one of the 10 counters (`frequency[1]` to `frequency[10]`) in the frequency array. The key statement in the loop is line 25

```
++frequency[responses[answer]];
```

which increments the appropriate frequency counter depending on the value of `responses[answer]`. When the counter variable `answer` is 0, `responses[answer]` is 1, so `++frequency[ responses[answer] ]`; is interpreted as

```
++frequency[1];
```

which increments array element one. When `answer` is 1, `responses[answer]` is 2, so `++frequency[responses[answer]]`; is interpreted as

```
++frequency[2];
```

which increments array element two. When `answer` is 2, `responses[answer]` is 6, so `++frequency[responses[answer]]`; is actually interpreted as

```
++frequency[6];
```

which increments array element six, and so on. Regardless of the number of responses processed in the survey, only an 11-element array is required (ignoring element zero) to summarize the results. If the data contained invalid values such as 13, the program would attempt to add 1 to `frequency[13]`. This would be outside the bounds of the array. *C has no array bounds checking to prevent the program from referring to an element that does not exist.* Thus, an executing program can “walk off” the end of an array without warning. You should ensure that all array references remain within the bounds of the array.



### Common Programming Error 6.6

*Referring to an element outside the array bounds.*



### Error-Prevention Tip 6.1

*When looping through an array, the array subscript should never go below 0 and should always be less than the total number of elements in the array (size - 1). Make sure the loop-terminating condition prevents accessing elements outside this range.*



### Error-Prevention Tip 6.2

*Programs should validate the correctness of all input values to prevent erroneous information from affecting a program's calculations.*

## Graphing Array Element Values with Histograms

Our next example (Fig. 6.8) reads numbers from an array and graphs the information in the form of a bar chart or histogram—each number is printed, then a bar consisting of that many asterisks is printed beside the number. The nested for statement (line 20) draws the bars. Note the use of `printf( "\n" )` to end a histogram bar (line 24).

```
1 /* Fig. 6.8: fig06_08.c
2 Histogram printing program */
3 #include <stdio.h>
4 #define SIZE 10
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 /* use initializer list to initialize array n */
10 int n[SIZE] = { 19, 3, 15, 7, 11, 9, 13, 5, 17, 1 };
11 int i; /* outer for counter for array elements */
12 int j; /* inner for counter counts *s in each histogram bar */
```

**Fig. 6.8** | Histogram printing. (Part I of 2.)



```

13
14 printf("%s%13s%17s\n", "Element", "Value", "Histogram");
15
16 /* for each element of array n, output a bar of the histogram */
17 for (i = 0; i < SIZE; i++) {
18 printf("%7d%13d", i, n[i]);
19
20 for (j = 1; j <= n[i]; j++) { /* print one bar */
21 printf("%C", '*');
22 } /* end inner for */
23
24 printf("\n"); /* end a histogram bar */
25 } /* end outer for */
26
27 return 0; /* indicates successful termination */
28 } /* end main */

```

| Element | Value | Histogram |
|---------|-------|-----------|
| 0       | 19    | *****     |
| 1       | 3     | ***       |
| 2       | 15    | *****     |
| 3       | 7     | *****     |
| 4       | 11    | *****     |
| 5       | 9     | *****     |
| 6       | 13    | *****     |
| 7       | 5     | *****     |
| 8       | 17    | *****     |
| 9       | 1     | *         |

**Fig. 6.8** | Histogram printing. (Part 2 of 2.)

### *Rolling a Die 6000 Times and Summarizing the Results in an Array*

In Chapter 5, we stated that we'd show a more elegant method of writing the dice-rolling program of Fig. 5.8. The problem was to roll a single six-sided die 6000 times to test whether the random number generator actually produces random numbers. An array version of this program is shown in Fig. 6.9.

```

1 /* Fig. 6.9: fig06_09.c
2 Roll a six-sided die 6000 times */
3 #include <stdio.h>
4 #include <stdlib.h>
5 #include <time.h>
6 #define SIZE 7
7
8 /* function main begins program execution */
9 int main(void)
10 {
11 int face; /* random die value 1 - 6 */
12 int roll; /* roll counter 1-6000 */
13 int frequency[SIZE] = { 0 }; /* clear counts */
14

```

**Fig. 6.9** | Dice-rolling program using an array instead of switch. (Part 1 of 2.)

```

15 srand(time(NULL)); /* seed random-number generator */
16
17 /* roll die 6000 times */
18 for (roll = 1; roll <= 6000; roll++) {
19 face = 1 + rand() % 6;
20 ++frequency[face]; /* replaces 26-line switch of Fig. 5.8 */
21 } /* end for */
22
23 printf("%s%17s\n", "Face", "Frequency");
24
25 /* output frequency elements 1-6 in tabular format */
26 for (face = 1; face < SIZE; face++) {
27 printf("%4d%17d\n", face, frequency[face]);
28 } /* end for */
29
30 return 0; /* indicates successful termination */
31 } /* end main */

```

| Face | Frequency |
|------|-----------|
| 1    | 1029      |
| 2    | 951       |
| 3    | 987       |
| 4    | 1033      |
| 5    | 1010      |
| 6    | 990       |

**Fig. 6.9** | Dice-rolling program using an array instead of switch. (Part 2 of 2.)

### *Using Character Arrays to Store and Manipulate Strings*

We have discussed only integer arrays. However, arrays are capable of holding data of any type. We now discuss storing strings in character arrays. So far, the only string-processing capability we have is outputting a string with `printf`. A string such as "hello" is really a static array of individual characters in C.

Character arrays have several unique features. A character array can be initialized using a string literal. For example,

```
char string1[] = "first";
```

initializes the elements of array `string1` to the individual characters in the string literal "first". In this case, the size of array `string1` is determined by the compiler based on the length of the string. The string "first" contains five characters *plus* a special string-termination character called the **null character**. Thus, array `string1` actually contains six elements. The character constant representing the null character is `'\0'`. All strings in C end with this character. A character array representing a string should always be defined large enough to hold the number of characters in the string and the terminating null character.

Character arrays also can be initialized with individual character constants in an initializer list. The preceding definition is equivalent to

```
char string1[] = { 'f', 'i', 'r', 's', 't', '\0' };
```

Because a string is really an array of characters, we can access individual characters in a string directly using array subscript notation. For example, `string1[0]` is the character 'f' and `string1[3]` is the character 's'.

We also can input a string directly into a character array from the keyboard using `scanf` and the conversion specifier `%s`. For example,

```
char string2[20];
```

creates a character array capable of storing a string of at most 19 characters and a terminating null character. The statement

```
scanf("%s", string2);
```

reads a string from the keyboard into `string2`. The name of the array is passed to `scanf` without the preceding `&` used with nonstring variables. The `&` is normally used to provide `scanf` with a variable's location in memory so that a value can be stored there. In Section 6.5, when we discuss passing arrays to functions, we'll see that the value of an array name is the address of the start of the array; therefore, the `&` is not necessary. Function `scanf` will read characters until a space, tab, newline or end-of-file indicator is encountered. The string should be no longer than 19 characters to leave room for the terminating null character. If the user types 20 or more characters, your program may crash! For this reason, use the conversion specifier `%19s` so that `scanf` does not write characters into memory beyond the end of the array `s`.

It's your responsibility to ensure that the array into which the string is read is capable of holding any string that the user types at the keyboard. Function `scanf` reads characters from the keyboard until the first white-space character is encountered—it does not check how large the array is. Thus, `scanf` can write beyond the end of the array.



### Common Programming Error 6.7

*Not providing `scanf` with a character array large enough to store a string typed at the keyboard can result in destruction of data in a program and other runtime errors. This can also make a system susceptible to worm and virus attacks.*

A character array representing a string can be output with `printf` and the `%s` conversion specifier. The array `string2` is printed with the statement

```
printf("%s\n", string2);
```

Function `printf`, like `scanf`, does not check how large the character array is. The characters of the string are printed until a terminating null character is encountered.

Figure 6.10 demonstrates initializing a character array with a string literal, reading a string into a character array, printing a character array as a string and accessing individual characters of a string.

```
1 /* Fig. 6.10: fig06_10.c
2 Treating character arrays as strings */
3 #include <stdio.h>
4
5 /* function main begins program execution */
6 int main(void)
7 {
8 char string1[20]; /* reserves 20 characters */
9 char string2[] = "string literal"; /* reserves 15 characters */
```

**Fig. 6.10** | Treating character arrays as strings. (Part I of 2.)

```

10 int i; /* counter */
11
12 /* read string from user into array string1 */
13 printf("Enter a string: ");
14 scanf("%s", string1); /* input ended by whitespace character */
15
16 /* output strings */
17 printf("string1 is: %s\nstring2 is: %s\n"
18 "string1 with spaces between characters is:\n",
19 string1, string2);
20
21 /* output characters until null character is reached */
22 for (i = 0; string1[i] != '\0'; i++) {
23 printf("%c ", string1[i]);
24 } /* end for */
25
26 printf("\n");
27 return 0; /* indicates successful termination */
28 } /* end main */

```

```

Enter a string: Hello there
string1 is: Hello
string2 is: string literal
string1 with spaces between characters is:
H e l l o

```

**Fig. 6.10** | Treating character arrays as strings. (Part 2 of 2.)

Figure 6.10 uses a `for` statement (line 22) to loop through the `string1` array and print the individual characters separated by spaces, using the `%c` conversion specifier. The condition in the `for` statement, `string1[i] != '\0'`, is true while the terminating null character has not been encountered in the string.

### *Static Local Arrays and Automatic Local Arrays*

Chapter 5 discussed the storage-class specifier `static`. A static local variable exists for the duration of the program, but is visible only in the function body. We can apply `static` to a local array definition so the array is not created and initialized each time the function is called and the array is not destroyed each time the function is exited in the program. This reduces program execution time, particularly for programs with frequently called functions that contain large arrays.



### **Performance Tip 6.2**

*In functions that contain automatic arrays where the function is in and out of scope frequently, make the array static so it's not created each time the function is called.*

Arrays that are `static` are initialized once at compile time. If you do not explicitly initialize a static array, that array's elements are initialized to zero by the compiler.

Figure 6.11 demonstrates function `staticArrayInit` (line 22) with a local static array (line 25) and function `automaticArrayInit` (line 44) with a local automatic array

(line 47). Function `staticArrayInit` is called twice (lines 12 and 16). The local static array in the function is initialized to zero by the compiler (line 25). The function prints the array, adds 5 to each element and prints the array again. The second time the function is called, the static array contains the values stored during the first function call. Function `automaticArrayInit` is also called twice (lines 13 and 17). The elements of the automatic local array in the function are initialized with the values 1, 2 and 3 (line 47). The function prints the array, adds 5 to each element and prints the array again. The second time the function is called, the array elements are initialized to 1, 2 and 3 again because the array has automatic storage duration.



### Common Programming Error 6.8

*Assuming that elements of a local static array are initialized to zero every time the function in which the array is defined is called.*

```

1 /* Fig. 6.11: fig06_11.c
2 Static arrays are initialized to zero */
3 #include <stdio.h>
4
5 void staticArrayInit(void); /* function prototype */
6 void automaticArrayInit(void); /* function prototype */
7
8 /* function main begins program execution */
9 int main(void)
10 {
11 printf("First call to each function:\n");
12 staticArrayInit();
13 automaticArrayInit();
14
15 printf("\n\nSecond call to each function:\n");
16 staticArrayInit();
17 automaticArrayInit();
18 return 0; /* indicates successful termination */
19 } /* end main */
20
21 /* function to demonstrate a static local array */
22 void staticArrayInit(void)
23 {
24 /* initializes elements to 0 first time function is called */
25 static int array1[3];
26 int i; /* counter */
27
28 printf("\nValues on entering staticArrayInit:\n");
29
30 /* output contents of array1 */
31 for (i = 0; i <= 2; i++) {
32 printf("array1[%d] = %d ", i, array1[i]);
33 } /* end for */
34
35 printf("\nValues on exiting staticArrayInit:\n");

```

**Fig. 6.11** | Static arrays are initialized to zero if not explicitly initialized. (Part 1 of 2.)

```

36
37 /* modify and output contents of array1 */
38 for (i = 0; i <= 2; i++) {
39 printf("array1[%d] = %d ", i, array1[i] += 5);
40 } /* end for */
41 } /* end function staticArrayInit */
42
43 /* function to demonstrate an automatic local array */
44 void automaticArrayInit(void)
45 {
46 /* initializes elements each time function is called */
47 int array2[3] = { 1, 2, 3 };
48 int i; /* counter */
49
50 printf("\n\nValues on entering automaticArrayInit:\n");
51
52 /* output contents of array2 */
53 for (i = 0; i <= 2; i++) {
54 printf("array2[%d] = %d ", i, array2[i]);
55 } /* end for */
56
57 printf("\n\nValues on exiting automaticArrayInit:\n");
58
59 /* modify and output contents of array2 */
60 for (i = 0; i <= 2; i++) {
61 printf("array2[%d] = %d ", i, array2[i] += 5);
62 } /* end for */
63 } /* end function automaticArrayInit */

```

First call to each function:

Values on entering staticArrayInit:  
array1[ 0 ] = 0 array1[ 1 ] = 0 array1[ 2 ] = 0  
Values on exiting staticArrayInit:  
array1[ 0 ] = 5 array1[ 1 ] = 5 array1[ 2 ] = 5

Values on entering automaticArrayInit:  
array2[ 0 ] = 1 array2[ 1 ] = 2 array2[ 2 ] = 3  
Values on exiting automaticArrayInit:  
array2[ 0 ] = 6 array2[ 1 ] = 7 array2[ 2 ] = 8

Second call to each function:

Values on entering staticArrayInit:  
array1[ 0 ] = 5 array1[ 1 ] = 5 array1[ 2 ] = 5  
Values on exiting staticArrayInit:  
array1[ 0 ] = 10 array1[ 1 ] = 10 array1[ 2 ] = 10

Values on entering automaticArrayInit:  
array2[ 0 ] = 1 array2[ 1 ] = 2 array2[ 2 ] = 3  
Values on exiting automaticArrayInit:  
array2[ 0 ] = 6 array2[ 1 ] = 7 array2[ 2 ] = 8

**Fig. 6.11** | Static arrays are initialized to zero if not explicitly initialized. (Part 2 of 2.)

## 6.5 Passing Arrays to Functions

To pass an array argument to a function, specify the name of the array without any brackets. For example, if array `hourlyTemperatures` has been defined as

```
int hourlyTemperatures[24];
```

the function call

```
modifyArray(hourlyTemperatures, 24)
```

passes array `hourlyTemperatures` and its size to function `modifyArray`. Unlike char arrays that contain strings, other array types do not have a special terminator. For this reason, the size of an array is passed to the function, so that the function can process the proper number of elements.

C automatically passes arrays to functions by reference—the called functions can modify the element values in the callers' original arrays. The name of the array evaluates to the address of the first element of the array. Because the starting address of the array is passed, the called function knows precisely where the array is stored. Therefore, when the called function modifies array elements in its function body, it's modifying the actual elements of the array in their original memory locations.

Figure 6.12 demonstrates that an array name is really the address of the first element of an array by printing `array`, `&array[0]` and `&array` using the `%p` conversion specifier—a special conversion specifier for printing addresses. The `%p` conversion specifier normally outputs addresses as hexadecimal numbers. Hexadecimal (base 16) numbers consist of the digits 0 through 9 and the letters A through F (these letters are the hexadecimal equivalents of the numbers 10–15). They are often used as shorthand notation for large integer values. Appendix C, Number Systems, provides an in-depth discussion of the relationships among binary (base 2), octal (base 8), decimal (base 10; standard integers) and hexadecimal integers. The output shows that both `array` and `&array[0]` have the same value, namely 0012FF78. The output of this program is system dependent, but the addresses are always identical for a particular execution of this program on a particular computer.



### Performance Tip 6.3

*Passing arrays by reference makes sense for performance reasons. If arrays were passed by value, a copy of each element would be passed. For large, frequently passed arrays, this would be time consuming and would consume storage for the copies of the arrays.*



### Software Engineering Observation 6.2

*It's possible to pass an array by value (by using a simple trick we explain in Chapter 10).*

Although entire arrays are passed by reference, individual array elements are passed by value exactly as simple variables are. Such simple single pieces of data (such as individual ints, floats and chars) are called **scalars**. To pass an element of an array to a function, use the subscripted name of the array element as an argument in the function call. In Chapter 7, we show how to pass scalars (i.e., individual variables and array elements) to functions by reference.

```

1 /* Fig. 6.12: fig06_12.c
2 The name of an array is the same as &array[0] */
3 #include <stdio.h>
4
5 /* function main begins program execution */
6 int main(void)
7 {
8 char array[5]; /* define an array of size 5 */
9
10 printf(" array = %p\n&array[0] = %p\n &array = %p\n",
11 array, &array[0], &array);
12 return 0; /* indicates successful termination */
13 } /* end main */

```

```

 array = 0012FF78
 &array[0] = 0012FF78
 &array = 0012FF78

```

**Fig. 6.12** | Array name is the same as the address of the array's first element.

For a function to receive an array through a function call, the function's parameter list must specify that an array will be received. For example, the function header for function `modifyArray` (that we called earlier in this section) might be written as

```
void modifyArray(int b[], int size)
```

indicating that `modifyArray` expects to receive an array of integers in parameter `b` and the number of array elements in parameter `size`. The size of the array is not required between the array brackets. If it's included, the compiler checks that it's greater than zero, then ignores it. Specifying a negative size is a compilation error. Because arrays are automatically passed by reference, when the called function uses the array name `b`, it will be referring to the array in the caller (array `hourlyTemperatures` in the preceding call). In Chapter 7, we introduce other notations for indicating that an array is being received by a function. As we'll see, these notations are based on the intimate relationship between arrays and pointers in C.

Figure 6.13 demonstrates the difference between passing an entire array and passing an array element. The program first prints the five elements of integer array `a` (lines 20–22). Next, `a` and its size are passed to function `modifyArray` (line 27), where each of `a`'s elements is multiplied by 2 (lines 54–55). Then `a` is reprinted in `main` (lines 32–34). As the output shows, the elements of `a` are indeed modified by `modifyArray`. Now the program prints the value of `a[3]` (line 38) and passes it to function `modifyElement` (line 40). Function `modifyElement` multiplies its argument by 2 (line 64) and prints the new value. When `a[3]` is reprinted in `main` (line 43), it has not been modified, because individual array elements are passed by value.

```

1 /* Fig. 6.13: fig06_13.c
2 Passing arrays and individual array elements to functions */
3 #include <stdio.h>
4 #define SIZE 5

```

**Fig. 6.13** | Passing arrays and individual array elements to functions. (Part I of 3.)



```

5
6 /* function prototypes */
7 void modifyArray(int b[], int size);
8 void modifyElement(int e);
9
10 /* function main begins program execution */
11 int main(void)
12 {
13 int a[SIZE] = { 0, 1, 2, 3, 4 }; /* initialize a */
14 int i; /* counter */
15
16 printf("Effects of passing entire array by reference:\n\nThe "
17 "values of the original array are:\n");
18
19 /* output original array */
20 for (i = 0; i < SIZE; i++) {
21 printf("%3d", a[i]);
22 } /* end for */
23
24 printf("\n");
25
26 /* pass array a to modifyArray by reference */
27 modifyArray(a, SIZE);
28
29 printf("The values of the modified array are:\n");
30
31 /* output modified array */
32 for (i = 0; i < SIZE; i++) {
33 printf("%3d", a[i]);
34 } /* end for */
35
36 /* output value of a[3] */
37 printf("\n\nEffects of passing array element "
38 "by value:\n\nThe value of a[3] is %d\n", a[3]);
39
40 modifyElement(a[3]); /* pass array element a[3] by value */
41
42 /* output value of a[3] */
43 printf("The value of a[3] is %d\n", a[3]);
44 return 0; /* indicates successful termination */
45 } /* end main */
46
47 /* in function modifyArray, "b" points to the original array "a"
48 in memory */
49 void modifyArray(int b[], int size)
50 {
51 int j; /* counter */
52
53 /* multiply each array element by 2 */
54 for (j = 0; j < size; j++) {
55 b[j] *= 2;
56 } /* end for */
57 } /* end function modifyArray */

```

**Fig. 6.13** | Passing arrays and individual array elements to functions. (Part 2 of 3.)

```

58
59 /* in function modifyElement, "e" is a local copy of array element
60 a[3] passed from main */
61 void modifyElement(int e)
62 {
63 /* multiply parameter by 2 */
64 printf("Value in modifyElement is %d\n", e *= 2);
65 } /* end function modifyElement */

```

Effects of passing entire array by reference:

The values of the original array are:

0 1 2 3 4

The values of the modified array are:

0 2 4 6 8

Effects of passing array element by value:

The value of a[3] is 6

Value in modifyElement is 12

The value of a[ 3 ] is 6

**Fig. 6.13** | Passing arrays and individual array elements to functions. (Part 3 of 3.)

There may be situations in your programs in which a function should not be allowed to modify array elements. Because arrays are always passed by reference, modification of values in an array is difficult to control. C provides the type qualifier **const** to prevent modification of array values in a function. When an array parameter is preceded by the **const** qualifier, the array elements become constant in the function body, and any attempt to modify an element of the array in the function body results in a compile-time error. This enables you to correct a program so it does not attempt to modify array elements.

Figure 6.14 demonstrates the **const** qualifier. Function `tryToModifyArray` (line 20) is defined with parameter `const int b[]`, which specifies that array `b` is constant and cannot be modified. The output shows the error messages produced by the compiler—the errors may be different on your system. Each of the three attempts by the function to modify array elements results in the compiler error “l-value specifies a const object.” The **const** qualifier is discussed again in Chapter 7.

```

1 /* Fig. 6.14: fig06_14.c
2 Demonstrating the const type qualifier with arrays */
3 #include <stdio.h>
4
5 void tryToModifyArray(const int b[]); /* function prototype */
6
7 /* function main begins program execution */
8 int main(void)
9 {
10 int a[] = { 10, 20, 30 }; /* initialize a */

```

**Fig. 6.14** | **const** type qualifier. (Part 1 of 2.)

```

11
12 tryToModifyArray(a);
13
14 printf("%d %d %d\n", a[0], a[1], a[2]);
15 return 0; /* indicates successful termination */
16 } /* end main */
17
18 /* in function tryToModifyArray, array b is const, so it cannot be
19 used to modify the original array a in main. */
20 void tryToModifyArray(const int b[])
21 {
22 b[0] /= 2; /* error */
23 b[1] /= 2; /* error */
24 b[2] /= 2; /* error */
25 } /* end function tryToModifyArray */

```

Compiling...

FIG06\_14.C

fig06\_14.c(22) : error C2166: l-value specifies const object

fig06\_14.c(23) : error C2166: l-value specifies const object

fig06\_14.c(24) : error C2166: l-value specifies const object

**Fig. 6.14** | `const` type qualifier. (Part 2 of 2.)



### Software Engineering Observation 6.3

*The `const` type qualifier can be applied to an array parameter in a function definition to prevent the original array from being modified in the function body. This is another example of the principle of least privilege. Functions should not be given the capability to modify an array unless it's absolutely necessary.*

## 6.6 Sorting Arrays

Sorting data (i.e., placing the data into a particular order such as ascending or descending) is one of the most important computing applications. A bank sorts all checks by account number so that it can prepare individual bank statements at the end of each month. Telephone companies sort their lists of accounts by last name and, within that, by first name to make it easy to find phone numbers. Virtually every organization must sort some data and in many cases massive amounts of data. Sorting data is an intriguing problem which has attracted some of the most intense research efforts in the field of computer science. In this chapter we discuss what is perhaps the simplest known sorting scheme. In Chapter 12 and Appendix F, we investigate more complex schemes that yield superior performance.



### Performance Tip 6.4

*Often, the simplest algorithms perform poorly. Their virtue is that they are easy to write, test and debug. More complex algorithms are often needed to realize maximum performance.*

Figure 6.15 sorts the values in the elements of the 10-element array `a` (line 10) into ascending order. The technique we use is called the **bubble sort** or the **sinking sort** because the smaller values gradually “bubble” their way upward to the top of the array like air bubbles rising in water, while the larger values sink to the bottom of the array. The technique

is to make several passes through the array. On each pass, successive pairs of elements are compared. If a pair is in increasing order (or if the values are identical), we leave the values as they are. If a pair is in decreasing order, their values are swapped in the array.

---

```

1 /* Fig. 6.15: fig06_15.c
2 This program sorts an array's values into ascending order */
3 #include <stdio.h>
4 #define SIZE 10
5
6 /* function main begins program execution */
7 int main(void)
8 {
9 /* initialize a */
10 int a[SIZE] = { 2, 6, 4, 8, 10, 12, 89, 68, 45, 37 };
11 int pass; /* passes counter */
12 int i; /* comparisons counter */
13 int hold; /* temporary location used to swap array elements */
14
15 printf("Data items in original order\n");
16
17 /* output original array */
18 for (i = 0; i < SIZE; i++) {
19 printf("%4d", a[i]);
20 } /* end for */
21
22 /* bubble sort */
23 /* loop to control number of passes */
24 for (pass = 1; pass < SIZE; pass++) {
25
26 /* loop to control number of comparisons per pass */
27 for (i = 0; i < SIZE - 1; i++) {
28
29 /* compare adjacent elements and swap them if first
30 element is greater than second element */
31 if (a[i] > a[i + 1]) {
32 hold = a[i];
33 a[i] = a[i + 1];
34 a[i + 1] = hold;
35 } /* end if */
36 } /* end inner for */
37 } /* end outer for */
38
39 printf("\nData items in ascending order\n");
40
41 /* output sorted array */
42 for (i = 0; i < SIZE; i++) {
43 printf("%4d", a[i]);
44 } /* end for */
45
46 printf("\n");
47 return 0; /* indicates successful termination */
48 } /* end main */

```

---

**Fig. 6.15** | Sorting an array with bubble sort. (Part I of 2.)

|                               |   |   |   |    |    |    |    |    |    |  |
|-------------------------------|---|---|---|----|----|----|----|----|----|--|
| Data items in original order  |   |   |   |    |    |    |    |    |    |  |
| 2                             | 6 | 4 | 8 | 10 | 12 | 89 | 68 | 45 | 37 |  |
| Data items in ascending order |   |   |   |    |    |    |    |    |    |  |
| 2                             | 4 | 6 | 8 | 10 | 12 | 37 | 45 | 68 | 89 |  |

**Fig. 6.15** | Sorting an array with bubble sort. (Part 2 of 2.)

First the program compares `a[0]` to `a[1]`, then `a[1]` to `a[2]`, then `a[2]` to `a[3]`, and so on until it completes the pass by comparing `a[8]` to `a[9]`. Although there are 10 elements, only nine comparisons are performed. Because of the way the successive comparisons are made, a large value may move down the array many positions on a single pass, but a small value may move up only one position. On the first pass, the largest value is guaranteed to sink to the bottom element of the array, `a[9]`. On the second pass, the second-largest value is guaranteed to sink to `a[8]`. On the ninth pass, the ninth-largest value sinks to `a[1]`. This leaves the smallest value in `a[0]`, so only nine passes of the array are needed to sort the array, even though there are ten elements.

The sorting is performed by the nested for loop (lines 24–37). If a swap is necessary, it's performed by the three assignments

```
hold = a[i];
a[i] = a[i + 1];
a[i + 1] = hold;
```

where the extra variable `hold` temporarily stores one of the two values being swapped. The swap cannot be performed with only the two assignments

```
a[i] = a[i + 1];
a[i + 1] = a[i];
```

If, for example, `a[i]` is 7 and `a[i + 1]` is 5, after the first assignment both values will be 5 and the value 7 will be lost. Hence the need for the extra variable `hold`.

The chief virtue of the bubble sort is that it's easy to program. However, the bubble sort runs slowly because every exchange moves an element only one position closer to its final destination. This becomes apparent when sorting large arrays. In the exercises, we'll develop more efficient versions of the bubble sort. Far more efficient sorts than the bubble sort have been developed. We'll investigate a few of these in the exercises. More advanced courses investigate sorting and searching in greater depth.

## 6.7 Case Study: Computing Mean, Median and Mode Using Arrays

We now consider a larger example. Computers are commonly used for [survey data analysis](#) to compile and analyze the results of surveys and opinion polls. Figure 6.16 uses array response initialized with 99 responses to a survey. Each response is a number from 1 to 9. The program computes the mean, median and mode of the 99 values.

The mean is the arithmetic average of the 99 values. Function `mean` (line 40) computes the mean by totaling the 99 elements and dividing the result by 99.

The median is the “middle value.” Function `median` (line 61) determines the median by calling function `bubbleSort` (defined in line 133) to sort the array of responses into

ascending order, then picking the middle element, `answer[SIZE / 2]`, of the sorted array. When there is an even number of elements, the median should be calculated as the mean of the two middle elements. Function `median` does not currently provide this capability. Function `printArray` (line 156) is called to output the response array.

The mode is the value that occurs most frequently among the 99 responses. Function `mode` (line 82) determines the mode by counting the number of responses of each type, then selecting the value with the greatest count. This version of function `mode` does not handle a tie (see Exercise 6.14). Function `mode` also produces a histogram to aid in determining the mode graphically. Figure 6.17 contains a sample run of this program. This example includes most of the common manipulations usually required in array problems, including passing arrays to functions.

---

```

1 /* Fig. 6.16: fig06_16.c
2 This program introduces the topic of survey data analysis.
3 It computes the mean, median and mode of the data */
4 #include <stdio.h>
5 #define SIZE 99
6
7 /* function prototypes */
8 void mean(const int answer[]);
9 void median(int answer[]);
10 void mode(int freq[], const int answer[]);
11 void bubbleSort(int a[]);
12 void printArray(const int a[]);
13
14 /* function main begins program execution */
15 int main(void)
16 {
17 int frequency[10] = { 0 }; /* initialize array frequency */
18
19 /* initialize array response */
20 int response[SIZE] =
21 { 6, 7, 8, 9, 8, 7, 8, 9, 8, 9,
22 7, 8, 9, 5, 9, 8, 7, 8, 7, 8,
23 6, 7, 8, 9, 3, 9, 8, 7, 8, 7,
24 7, 8, 9, 8, 9, 8, 9, 7, 8, 9,
25 6, 7, 8, 7, 8, 7, 9, 8, 9, 2,
26 7, 8, 9, 8, 9, 8, 9, 7, 5, 3,
27 5, 6, 7, 2, 5, 3, 9, 4, 6, 4,
28 7, 8, 9, 6, 8, 7, 8, 9, 7, 8,
29 7, 4, 4, 2, 5, 3, 8, 7, 5, 6,
30 4, 5, 6, 1, 6, 5, 7, 8, 7 };
31
32 /* process responses */
33 mean(response);
34 median(response);
35 mode(frequency, response);
36 return 0; /* indicates successful termination */
37 } /* end main */
38

```

---

**Fig. 6.16** | Survey data analysis program. (Part I of 4.)

---

```

39 /* calculate average of all response values */
40 void mean(const int answer[])
41 {
42 int j; /* counter for totaling array elements */
43 int total = 0; /* variable to hold sum of array elements */
44
45 printf("%s\n%s\n%s\n", "*****", " Mean", "*****");
46
47 /* total response values */
48 for (j = 0; j < SIZE; j++) {
49 total += answer[j];
50 } /* end for */
51
52 printf("The mean is the average value of the data\n"
53 "items. The mean is equal to the total of\n"
54 "all the data items divided by the number\n"
55 "of data items (%d). The mean value for\n"
56 "this run is: %d / %d = %.4f\n",
57 SIZE, total, SIZE, (double) total / SIZE);
58 } /* end function mean */
59
60 /* sort array and determine median element's value */
61 void median(int answer[])
62 {
63 printf("\n%s\n%s\n%s\n",
64 "*****", " Median", "*****",
65 "The unsorted array of responses is");
66
67 printArray(answer); /* output unsorted array */
68
69 bubbleSort(answer); /* sort array */
70
71 printf("\n\nThe sorted array is");
72 printArray(answer); /* output sorted array */
73
74 /* display median element */
75 printf("\n\nThe median is element %d of\n"
76 "the sorted %d element array.\n"
77 "For this run the median is %d\n",
78 SIZE / 2, SIZE, answer[SIZE / 2]);
79 } /* end function median */
80
81 /* determine most frequent response */
82 void mode(int freq[], const int answer[])
83 {
84 int rating; /* counter for accessing elements 1-9 of array freq */
85 int j; /* counter for summarizing elements 0-98 of array answer */
86 int h; /* counter for displaying histograms of elements in array freq */
87 int largest = 0; /* represents largest frequency */
88 int modeValue = 0; /* represents most frequent response */
89
90 printf("\n%s\n%s\n%s\n",
91 "*****", " Mode", "*****");

```

---

**Fig. 6.16** | Survey data analysis program. (Part 2 of 4.)

```

92
93 /* initialize frequencies to 0 */
94 for (rating = 1; rating <= 9; rating++) {
95 freq[rating] = 0;
96 } /* end for */
97
98 /* summarize frequencies */
99 for (j = 0; j < SIZE; j++) {
100 ++freq[answer[j]];
101 } /* end for */
102
103 /* output headers for result columns */
104 printf("%s%11s%19s\n\n%54s\n%54s\n\n",
105 "Response", "Frequency", "Histogram",
106 "1 1 2 2", "5 0 5 0 5");
107
108 /* output results */
109 for (rating = 1; rating <= 9; rating++) {
110 printf("%8d%11d", rating, freq[rating]);
111
112 /* keep track of mode value and largest frequency value */
113 if (freq[rating] > largest) {
114 largest = freq[rating];
115 modeValue = rating;
116 } /* end if */
117
118 /* output histogram bar representing frequency value */
119 for (h = 1; h <= freq[rating]; h++) {
120 printf("*");
121 } /* end inner for */
122
123 printf("\n"); /* being new line of output */
124 } /* end outer for */
125
126 /* display the mode value */
127 printf("The mode is the most frequent value.\n"
128 "For this run the mode is %d which occurred"
129 " %d times.\n", modeValue, largest);
130 } /* end function mode */
131
132 /* function that sorts an array with bubble sort algorithm */
133 void bubbleSort(int a[])
134 {
135 int pass; /* pass counter */
136 int j; /* comparison counter */
137 int hold; /* temporary location used to swap elements */
138
139 /* loop to control number of passes */
140 for (pass = 1; pass < SIZE; pass++) {
141
142 /* loop to control number of comparisons per pass */
143 for (j = 0; j < SIZE - 1; j++) {
144

```

**Fig. 6.16** | Survey data analysis program. (Part 3 of 4.)



```

145 /* swap elements if out of order */
146 if (a[j] > a[j + 1]) {
147 hold = a[j];
148 a[j] = a[j + 1];
149 a[j + 1] = hold;
150 } /* end if */
151 } /* end inner for */
152 } /* end outer for */
153 } /* end function bubbleSort */
154
155 /* output array contents (20 values per row) */
156 void printArray(const int a[])
157 {
158 int j; /* counter */
159
160 /* output array contents */
161 for (j = 0; j < SIZE; j++) {
162
163 if (j % 20 == 0) { /* begin new line every 20 values */
164 printf("\n");
165 } /* end if */
166
167 printf("%2d", a[j]);
168 } /* end for */
169 } /* end function printArray */

```

**Fig. 6.16** | Survey data analysis program. (Part 4 of 4.)

```

Mean

The mean is the average value of the data
items. The mean is equal to the total of
all the data items divided by the number
of data items (99). The mean value for
this run is: 681 / 99 = 6.8788

Median

The unsorted array of responses is
6 7 8 9 8 7 8 9 8 9 7 8 9 5 9 8 7 8 7 8
6 7 8 9 3 9 8 7 8 7 7 8 9 8 9 8 9 7 8 9
6 7 8 7 8 7 9 8 9 2 7 8 9 8 9 8 9 7 5 3
5 6 7 2 5 3 9 4 6 4 7 8 9 6 8 7 8 9 7 8
7 4 4 2 5 3 8 7 5 6 4 5 6 1 6 5 7 8 7

The sorted array is
1 2 2 2 3 3 3 3 4 4 4 4 4 5 5 5 5 5 5 5
5 6 6 6 6 6 6 6 6 7 7 7 7 7 7 7 7 7 7 7
7 7 7 7 7 7 7 7 7 7 7 7 8 8 8 8 8 8 8 8

```

**Fig. 6.17** | Sample run for the survey data analysis program. (Part 1 of 2.)

```

8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8
9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9

```

The median is element 49 of  
the sorted 99 element array.  
For this run the median is 7

```

```

```
Mode
```

```

```

```
Response Frequency
```

```
Histogram
```

```

 1 1 2 2
 5 0 5 0 5

```

```

1 1 *
2 3 ***
3 4 ****
4 5 *****
5 8 *********
6 9 *********
7 23 *****************
8 27 *****************
9 19 *****************

```

The mode is the most frequent value.  
For this run the mode is 8 which occurred 27 times.

**Fig. 6.17** | Sample run for the survey data analysis program. (Part 2 of 2.)

## 6.8 Searching Arrays

You'll often work with large amounts of data stored in arrays. It may be necessary to determine whether an array contains a value that matches a certain **key value**. The process of finding a particular element of an array is called **searching**. In this section we discuss two searching techniques—the simple **linear search** technique and the more efficient (but more complex) **binary search** technique. Exercise 6.32 and Exercise 6.33 at the end of this chapter ask you to implement recursive versions of the linear search and the binary search.

### *Searching an Array with Linear Search*

The linear search (Fig. 6.18) compares each element of the array with the **search key**. Since the array is not in any particular order, it's just as likely that the value will be found in the first element as in the last. On average, therefore, the program will have to compare the search key with half the elements of the array.

```

1 /* Fig. 6.18: fig06_18.c
2 Linear search of an array */
3 #include <stdio.h>
4 #define SIZE 100

```

**Fig. 6.18** | Linear search of an array. (Part 1 of 3.)

```

5
6 /* function prototype */
7 int linearSearch(const int array[], int key, int size);
8
9 /* function main begins program execution */
10 int main(void)
11 {
12 int a[SIZE]; /* create array a */
13 int x; /* counter for initializing elements 0-99 of array a */
14 int searchKey; /* value to locate in array a */
15 int element; /* variable to hold location of searchKey or -1 */
16
17 /* create data */
18 for (x = 0; x < SIZE; x++) {
19 a[x] = 2 * x;
20 } /* end for */
21
22 printf("Enter integer search key:\n");
23 scanf("%d", &searchKey);
24
25 /* attempt to locate searchKey in array a */
26 element = linearSearch(a, searchKey, SIZE);
27
28 /* display results */
29 if (element != -1) {
30 printf("Found value in element %d\n", element);
31 } /* end if */
32 else {
33 printf("Value not found\n");
34 } /* end else */
35
36 return 0; /* indicates successful termination */
37 } /* end main */
38
39 /* compare key to every element of array until the location is found
40 or until the end of array is reached; return subscript of element
41 if key or -1 if key is not found */
42 int linearSearch(const int array[], int key, int size)
43 {
44 int n; /* counter */
45
46 /* loop through array */
47 for (n = 0; n < size; ++n) {
48
49 if (array[n] == key) {
50 return n; /* return location of key */
51 } /* end if */
52 } /* end for */
53
54 return -1; /* key not found */
55 } /* end function linearSearch */

```

**Fig. 6.18** | Linear search of an array. (Part 2 of 3.)

```
Enter integer search key:
36
Found value in element 18
```

```
Enter integer search key:
37
Value not found
```

**Fig. 6.18** | Linear search of an array. (Part 3 of 3.)

### *Searching an Array with Binary Search*

The linear searching method works well for small or unsorted arrays. However, for large arrays linear searching is inefficient. If the array is sorted, the high-speed binary search technique can be used.

The binary search algorithm eliminates from consideration one-half of the elements in a sorted array after each comparison. The algorithm locates the middle element of the array and compares it to the search key. If they are equal, the search key is found and the array subscript of that element is returned. If they are not equal, the problem is reduced to searching one-half of the array. If the search key is less than the middle element of the array, the first half of the array is searched, otherwise the second half of the array is searched. If the search key is not found in the specified subarray (piece of the original array), the algorithm is repeated on one-quarter of the original array. The search continues until the search key is equal to the middle element of a subarray, or until the subarray consists of one element that is not equal to the search key (i.e., the search key is not found).

In a worst case-scenario, searching an array of 1023 elements takes only 10 comparisons using a binary search. Repeatedly dividing 1024 by 2 yields the values 512, 256, 128, 64, 32, 16, 8, 4, 2 and 1. The number 1024 ( $2^{10}$ ) is divided by 2 only 10 times to get the value 1. Dividing by 2 is equivalent to one comparison in the binary search algorithm. An array of 1048576 ( $2^{20}$ ) elements takes a maximum of 20 comparisons to find the search key. An array of one billion elements takes a maximum of 30 comparisons to find the search key. This is a tremendous increase in performance over the linear search that required comparing the search key to an average of half of the array elements. For a one-billion-element array, this is a difference between an average of 500 million comparisons and a maximum of 30 comparisons! The maximum comparisons for any array can be determined by finding the first power of 2 greater than the number of array elements.

Figure 6.19 presents the iterative version of function `binarySearch` (lines 44–74). The function receives four arguments—an integer array `b` to be searched, an integer `searchKey`, the `low` array subscript and the `high` array subscript (these define the portion of the array to be searched). If the search key does not match the middle element of a subarray, the `low` subscript or `high` subscript is modified so that a smaller subarray can be searched. If the search key is less than the middle element, the `high` subscript is set to `middle - 1` and the search is continued on the elements from `low` to `middle - 1`. If the search key is greater than the middle element, the `low` subscript is set to `middle + 1` and the search is continued on the elements from `middle + 1` to `high`. The program uses an array of 15 elements. The first power of 2 greater than the number of elements in this array

is  $16 (2^4)$ , so a maximum of 4 comparisons are required to find the search key. The program uses function `printHeader` (lines 77–96) to output the array subscripts and function `printRow` (lines 100–120) to output each subarray during the binary search process. The middle element in each subarray is marked with an asterisk (\*) to indicate the element to which the search key is compared.

---

```

1 /* Fig. 6.19: fig06_19.c
2 Binary search of a sorted array */
3 #include <stdio.h>
4 #define SIZE 15
5
6 /* function prototypes */
7 int binarySearch(const int b[], int searchKey, int low, int high);
8 void printHeader(void);
9 void printRow(const int b[], int low, int mid, int high);
10
11 /* function main begins program execution */
12 int main(void)
13 {
14 int a[SIZE]; /* create array a */
15 int i; /* counter for initializing elements 0-14 of array a */
16 int key; /* value to locate in array a */
17 int result; /* variable to hold location of key or -1 */
18
19 /* create data */
20 for (i = 0; i < SIZE; i++) {
21 a[i] = 2 * i;
22 } /* end for */
23
24 printf("Enter a number between 0 and 28: ");
25 scanf("%d", &key);
26
27 printHeader();
28
29 /* search for key in array a */
30 result = binarySearch(a, key, 0, SIZE - 1);
31
32 /* display results */
33 if (result != -1) {
34 printf("\n%d found in array element %d\n", key, result);
35 } /* end if */
36 else {
37 printf("\n%d not found\n", key);
38 } /* end else */
39
40 return 0; /* indicates successful termination */
41 } /* end main */
42
43 /* function to perform binary search of an array */
44 int binarySearch(const int b[], int searchKey, int low, int high)
45 {

```

---

**Fig. 6.19** | Binary search of a sorted array. (Part I of 4.)

```

46 int middle; /* variable to hold middle element of array */
47
48 /* loop until low subscript is greater than high subscript */
49 while (low <= high) {
50
51 /* determine middle element of subarray being searched */
52 middle = (low + high) / 2;
53
54 /* display subarray used in this loop iteration */
55 printRow(b, low, middle, high);
56
57 /* if searchKey matched middle element, return middle */
58 if (searchKey == b[middle]) {
59 return middle;
60 } /* end if */
61
62 /* if searchKey less than middle element, set new high */
63 else if (searchKey < b[middle]) {
64 high = middle - 1; /* search low end of array */
65 } /* end else if */
66
67 /* if searchKey greater than middle element, set new low */
68 else {
69 low = middle + 1; /* search high end of array */
70 } /* end else */
71 } /* end while */
72
73 return -1; /* searchKey not found */
74 } /* end function binarySearch */
75
76 /* Print a header for the output */
77 void printHeader(void)
78 {
79 int i; /* counter */
80
81 printf("\nSubscripts:\n");
82
83 /* output column head */
84 for (i = 0; i < SIZE; i++) {
85 printf("%3d ", i);
86 } /* end for */
87
88 printf("\n"); /* start new line of output */
89
90 /* output line of - characters */
91 for (i = 1; i <= 4 * SIZE; i++) {
92 printf("-");
93 } /* end for */
94
95 printf("\n"); /* start new line of output */
96 } /* end function printHeader */
97

```

**Fig. 6.19** | Binary search of a sorted array. (Part 2 of 4.)

```

98 /* Print one row of output showing the current
99 part of the array being processed. */
100 void printRow(const int b[], int low, int mid, int high)
101 {
102 int i; /* counter for iterating through array b */
103
104 /* loop through entire array */
105 for (i = 0; i < SIZE; i++) {
106
107 /* display spaces if outside current subarray range */
108 if (i < low || i > high) {
109 printf(" ");
110 } /* end if */
111 else if (i == mid) { /* display middle element */
112 printf("%3d*", b[i]); /* mark middle value */
113 } /* end else if */
114 else { /* display other elements in subarray */
115 printf("%3d ", b[i]);
116 } /* end else */
117 } /* end for */
118
119 printf("\n"); /* start new line of output */
120 } /* end function printRow */

```

Enter a number between 0 and 28: 25

Subscripts:

|       |   |   |   |   |    |    |     |    |    |    |     |     |     |    |
|-------|---|---|---|---|----|----|-----|----|----|----|-----|-----|-----|----|
| 0     | 1 | 2 | 3 | 4 | 5  | 6  | 7   | 8  | 9  | 10 | 11  | 12  | 13  | 14 |
| ----- |   |   |   |   |    |    |     |    |    |    |     |     |     |    |
| 0     | 2 | 4 | 6 | 8 | 10 | 12 | 14* | 16 | 18 | 20 | 22  | 24  | 26  | 28 |
|       |   |   |   |   |    |    |     | 16 | 18 | 20 | 22* | 24  | 26  | 28 |
|       |   |   |   |   |    |    |     |    |    |    |     | 24  | 26* | 28 |
|       |   |   |   |   |    |    |     |    |    |    |     | 24* |     |    |

25 not found

Enter a number between 0 and 28: 8

Subscripts:

|       |   |   |    |    |     |    |     |    |    |    |    |    |    |    |
|-------|---|---|----|----|-----|----|-----|----|----|----|----|----|----|----|
| 0     | 1 | 2 | 3  | 4  | 5   | 6  | 7   | 8  | 9  | 10 | 11 | 12 | 13 | 14 |
| ----- |   |   |    |    |     |    |     |    |    |    |    |    |    |    |
| 0     | 2 | 4 | 6  | 8  | 10  | 12 | 14* | 16 | 18 | 20 | 22 | 24 | 26 | 28 |
| 0     | 2 | 4 | 6* | 8  | 10  | 12 |     |    |    |    |    |    |    |    |
|       |   |   |    | 8  | 10* | 12 |     |    |    |    |    |    |    |    |
|       |   |   |    | 8* |     |    |     |    |    |    |    |    |    |    |

8 found in array element 4

**Fig. 6.19** | Binary search of a sorted array. (Part 3 of 4.)

Enter a number between 0 and 28: 6

Subscripts:

|   |   |   |    |   |    |    |     |    |    |    |    |    |    |    |
|---|---|---|----|---|----|----|-----|----|----|----|----|----|----|----|
| 0 | 1 | 2 | 3  | 4 | 5  | 6  | 7   | 8  | 9  | 10 | 11 | 12 | 13 | 14 |
| 0 | 2 | 4 | 6  | 8 | 10 | 12 | 14* | 16 | 18 | 20 | 22 | 24 | 26 | 28 |
| 0 | 2 | 4 | 6* | 8 | 10 | 12 |     |    |    |    |    |    |    |    |


6 found in array element 3

**Fig. 6.19** | Binary search of a sorted array. (Part 4 of 4.)

## 6.9 Multiple-Subscripted Arrays

Arrays in C can have multiple subscripts. A common use of **multiple-subscripted arrays** (also called **multidimensional arrays**) is to represent **tables** of values consisting of information arranged in rows and columns. To identify a particular table element, we must specify two subscripts: The first (by convention) identifies the element's row and the second (by convention) identifies the element's column. Tables or arrays that require two subscripts to identify a particular element are called **double-subscripted arrays**. Multiple-subscripted arrays can have more than two subscripts.

Figure 6.20 illustrates a double-subscripted array, **a**. The array contains three rows and four columns, so it's said to be a 3-by-4 array. In general, an array with  $m$  rows and  $n$  columns is called an  **$m$ -by- $n$  array**.



**Fig. 6.20** | Double-subscripted array with three rows and four columns.

Every element in array **a** is identified in Fig. 6.20 by an element name of the form **a[i][j]**; **a** is the name of the array, and **i** and **j** are the subscripts that uniquely identify each element in **a**. The names of the elements in the first row all have a first subscript of 0; the names of the elements in the fourth column all have a second subscript of 3.



### Common Programming Error 6.9

*Referencing a double-subscripted array element as **a[ x, y ]** instead of **a[ x ][ y ]**. C interprets **a[ x, y ]** as **a[ y ]**, and as such it does not cause a compilation error.*



A multiple-subscripted array can be initialized when it's defined, much like a single-subscripted array. For example, a double-subscripted array `int b[2][2]` could be defined and initialized with

```
int b[2][2] = { { 1, 2 }, { 3, 4 } };
```

The values are grouped by row in braces. The values in the first set of braces initialize row 0 and the values in the second set of braces initialize row 1. So, the values 1 and 2 initialize elements `b[0][0]` and `b[0][1]`, respectively, and the values 3 and 4 initialize elements `b[1][0]` and `b[1][1]`, respectively. *If there are not enough initializers for a given row, the remaining elements of that row are initialized to 0.* Thus,

```
int b[2][2] = { { 1 }, { 3, 4 } };
```

would initialize `b[0][0]` to 1, `b[0][1]` to 0, `b[1][0]` to 3 and `b[1][1]` to 4. Figure 6.21 demonstrates defining and initializing double-subscripted arrays.

The program defines three arrays of two rows and three columns (six elements each). The definition of `array1` (line 11) provides six initializers in two sublists. The first sublist initializes the first row (i.e., row 0) of the array to the values 1, 2 and 3; and the second sublist initializes the second row (i.e., row 1) of the array to the values 4, 5 and 6.

---

```

1 /* Fig. 6.21: fig06_21.c
2 Initializing multidimensional arrays */
3 #include <stdio.h>
4
5 void printArray(const int a[][3]); /* function prototype */
6
7 /* function main begins program execution */
8 int main(void)
9 {
10 /* initialize array1, array2, array3 */
11 int array1[2][3] = { { 1, 2, 3 }, { 4, 5, 6 } };
12 int array2[2][3] = { 1, 2, 3, 4, 5 };
13 int array3[2][3] = { { 1, 2 }, { 4 } };
14
15 printf("Values in array1 by row are:\n");
16 printArray(array1);
17
18 printf("Values in array2 by row are:\n");
19 printArray(array2);
20
21 printf("Values in array3 by row are:\n");
22 printArray(array3);
23 return 0; /* indicates successful termination */
24 } /* end main */
25
26 /* function to output array with two rows and three columns */
27 void printArray(const int a[][3])
28 {
29 int i; /* row counter */
30 int j; /* column counter */
31
```

---

**Fig. 6.21** | Initializing multidimensional arrays. (Part I of 2.)

```

32 /* loop through rows */
33 for (i = 0; i <= 1; i++) {
34
35 /* output column values */
36 for (j = 0; j <= 2; j++) {
37 printf("%d ", a[i][j]);
38 } /* end inner for */
39
40 printf("\n"); /* start new line of output */
41 } /* end outer for */
42 } /* end function printArray */

```

Values in array1 by row are:

1 2 3

4 5 6

Values in array2 by row are:

1 2 3

4 5 0

Values in array3 by row are:

1 2 0

4 0 0

**Fig. 6.21** | Initializing multidimensional arrays. (Part 2 of 2.)

If the braces around each sublist are removed from the array1 initializer list, the compiler initializes the elements of the first row followed by the elements of the second row. The definition of array2 (line 12) provides five initializers. The initializers are assigned to the first row, then the second row. Any elements that do not have an explicit initializer are initialized to zero automatically, so array2[1][2] is initialized to 0.

The definition of array3 (line 13) provides three initializers in two sublists. The sublist for the first row explicitly initializes the first two elements of the first row to 1 and 2. The third element is initialized to zero. The sublist for the second row explicitly initializes the first element to 4. The last two elements are initialized to zero.

The program calls printArray (lines 27–43) to output each array's elements. The function definition specifies the array parameter as `const int a[][3]`. When we receive a single-subscripted array as a parameter, the array brackets are empty in the function's parameter list. The first subscript of a multiple-subscripted array is not required either, but all subsequent subscripts are required. The compiler uses these subscripts to determine the locations in memory of elements in multiple-subscripted arrays. All array elements are stored consecutively in memory regardless of the number of subscripts. In a double-subscripted array, the first row is stored in memory followed by the second row.

Providing the subscript values in a parameter declaration enables the compiler to tell the function how to locate an element in the array. In a double-subscripted array, each row is basically a single-subscripted array. To locate an element in a particular row, the compiler must know how many elements are in each row so that it can skip the proper number of memory locations when accessing the array. Thus, when accessing a[1][2] in our example, the compiler knows to skip the three elements of the first row to get to the second row (row 1). Then, the compiler accesses the third element of that row (element 2).

Many common array manipulations use for repetition statements. For example, the following statement sets all the elements in the third row of array a in Fig. 6.20 to zero:

```

for (column = 0; column <= 3; column++) {
 a[2][column] = 0;
}

```

We specified the *third* row, therefore we know that the first subscript is always 2 (again, 0 is the first row and 1 is the second). The loop varies only the second subscript (i.e., the column). The preceding for statement is equivalent to the assignment statements:

```

a[2][0] = 0;
a[2][1] = 0;
a[2][2] = 0;
a[2][3] = 0;

```

The following nested for statement determines the total of all the elements in array a.

```

total = 0;
for (row = 0; row <= 2; row++) {
 for (column = 0; column <= 3; column++) {
 total += a[row][column];
 }
}

```

The for statement totals the elements of the array one row at a time. The outer for statement begins by setting row (i.e., the row subscript) to 0 so that the elements of the first row may be totaled by the inner for statement. The outer for statement then increments row to 1, so the elements of the second row can be totaled. Then, the outer for statement increments row to 2, so the elements of the third row can be totaled. The result is printed when the nested for statement terminates.

### *Two-Dimensional Array Manipulations*

Figure 6.22 performs several other common array manipulations on 3-by-4 array `studentGrades` using for statements. Each row of the array represents a student and each column represents a grade on one of the four exams the students took during the semester. The array manipulations are performed by four functions. Function `minimum` (lines 43–62) determines the lowest grade of any student for the semester. Function `maximum` (lines 65–84) determines the highest grade of any student for the semester. Function `average` (lines 87–98) determines a particular student's semester average. Function `printArray` (lines 101–120) outputs the double-subscripted array in a neat, tabular format.

---

```

1 /* Fig. 6.22: fig06_22.c
2 Double-subscripted array example */
3 #include <stdio.h>
4 #define STUDENTS 3
5 #define EXAMS 4
6
7 /* function prototypes */
8 int minimum(const int grades[][EXAMS], int pupils, int tests);
9 int maximum(const int grades[][EXAMS], int pupils, int tests);
10 double average(const int setOfGrades[], int tests);
11 void printArray(const int grades[][EXAMS], int pupils, int tests);

```

---

**Fig. 6.22** | Double-subscripted arrays example. (Part I of 4.)

```

12
13 /* function main begins program execution */
14 int main(void)
15 {
16 int student; /* student counter */
17
18 /* initialize student grades for three students (rows) */
19 const int studentGrades[STUDENTS][EXAMS] =
20 { { 77, 68, 86, 73 },
21 { 96, 87, 89, 78 },
22 { 70, 90, 86, 81 } };
23
24 /* output array studentGrades */
25 printf("The array is:\n");
26 printArray(studentGrades, STUDENTS, EXAMS);
27
28 /* determine smallest and largest grade values */
29 printf("\n\nLowest grade: %d\nHighest grade: %d\n",
30 minimum(studentGrades, STUDENTS, EXAMS),
31 maximum(studentGrades, STUDENTS, EXAMS));
32
33 /* calculate average grade for each student */
34 for (student = 0; student < STUDENTS; student++) {
35 printf("The average grade for student %d is %.2f\n",
36 student, average(studentGrades[student], EXAMS));
37 } /* end for */
38
39 return 0; /* indicates successful termination */
40 } /* end main */
41
42 /* Find the minimum grade */
43 int minimum(const int grades[][EXAMS], int pupils, int tests)
44 {
45 int i; /* student counter */
46 int j; /* exam counter */
47 int lowGrade = 100; /* initialize to highest possible grade */
48
49 /* loop through rows of grades */
50 for (i = 0; i < pupils; i++) {
51
52 /* loop through columns of grades */
53 for (j = 0; j < tests; j++) {
54
55 if (grades[i][j] < lowGrade) {
56 lowGrade = grades[i][j];
57 } /* end if */
58 } /* end inner for */
59 } /* end outer for */
60
61 return lowGrade; /* return minimum grade */
62 } /* end function minimum */
63

```

**Fig. 6.22** | Double-subscripted arrays example. (Part 2 of 4.)

```

64 /* Find the maximum grade */
65 int maximum(const int grades[][EXAMS], int pupils, int tests)
66 {
67 int i; /* student counter */
68 int j; /* exam counter */
69 int highGrade = 0; /* initialize to lowest possible grade */
70
71 /* loop through rows of grades */
72 for (i = 0; i < pupils; i++) {
73
74 /* loop through columns of grades */
75 for (j = 0; j < tests; j++) {
76
77 if (grades[i][j] > highGrade) {
78 highGrade = grades[i][j];
79 } /* end if */
80 } /* end inner for */
81 } /* end outer for */
82
83 return highGrade; /* return maximum grade */
84 } /* end function maximum */
85
86 /* Determine the average grade for a particular student */
87 double average(const int setOfGrades[], int tests)
88 {
89 int i; /* exam counter */
90 int total = 0; /* sum of test grades */
91
92 /* total all grades for one student */
93 for (i = 0; i < tests; i++) {
94 total += setOfGrades[i];
95 } /* end for */
96
97 return (double) total / tests; /* average */
98 } /* end function average */
99
100 /* Print the array */
101 void printArray(const int grades[][EXAMS], int pupils, int tests)
102 {
103 int i; /* student counter */
104 int j; /* exam counter */
105
106 /* output column heads */
107 printf(" [0] [1] [2] [3]");
108
109 /* output grades in tabular format */
110 for (i = 0; i < pupils; i++) {
111
112 /* output label for row */
113 printf("\nstudentGrades[%d] ", i);
114

```

**Fig. 6.22** | Double-subscripted arrays example. (Part 3 of 4.)

```

115 /* output grades for one student */
116 for (j = 0; j < tests; j++) {
117 printf("%-5d", grades[i][j]);
118 } /* end inner for */
119 } /* end outer for */
120 } /* end function printArray */

```

The array is:

|                  | [0] | [1] | [2] | [3] |
|------------------|-----|-----|-----|-----|
| studentGrades[0] | 77  | 68  | 86  | 73  |
| studentGrades[1] | 96  | 87  | 89  | 78  |
| studentGrades[2] | 70  | 90  | 86  | 81  |

Lowest grade: 68

Highest grade: 96

The average grade for student 0 is 76.00

The average grade for student 1 is 87.50

The average grade for student 2 is 81.75

**Fig. 6.22** | Double-subscripted arrays example. (Part 4 of 4.)

Functions `minimum`, `maximum` and `printArray` each receive three arguments—the `studentGrades` array (called `grades` in each function), the number of students (rows of the array) and the number of exams (columns of the array). Each function loops through array `grades` using nested `for` statements. The following nested `for` statement is from the function `minimum` definition:

```

/* loop through rows of grades */
for (i = 0; i < pupils; i++) {
 /* loop through columns of grades */
 for (j = 0; j < tests; j++) {
 if (grades[i][j] < lowGrade) {
 lowGrade = grades[i][j];
 } /* end if */
 } /* end inner for */
} /* end outer for */

```

The outer `for` statement begins by setting `i` (i.e., the row subscript) to 0 so that the elements of the first row (i.e., the grades of the first student) can be compared to variable `lowGrade` in the body of the inner `for` statement. The inner `for` statement loops through the four grades of a particular row and compares each grade to `lowGrade`. If a grade is less than `lowGrade`, `lowGrade` is set to that grade. The outer `for` statement then increments the row subscript to 1. The elements of the second row are compared to variable `lowGrade`. The outer `for` statement then increments the row subscript to 2. The elements of the third row are compared to variable `lowGrade`. When execution of the nested structure is complete, `lowGrade` contains the smallest grade in the double-subscripted array. Function `maximum` works similarly to function `minimum`.

Function `average` (line 87) takes two arguments—a single-subscripted array of test results for a particular student called `setOfGrades` and the number of test results in the array. When `average` is called, the first argument `studentGrades[student]` is passed. This causes the address of one row of the double-subscripted array to be passed to `average`.

The argument `studentGrades[1]` is the starting address of the second row of the array. Remember that a double-subscripted array is basically an array of single-subscripted arrays and that the name of a single-subscripted array is the address of the array in memory. Function `average` calculates the sum of the array elements, divides the total by the number of test results and returns the floating-point result.

## Summary

### Section 6.1 Introduction

- Arrays are data structures consisting of related data items of the same type.
- Arrays are “static” entities in that they remain the same size throughout program execution.

### Section 6.2 Arrays

- An array is a group of memory locations related by the fact that they all have the same name and the same type.
- To refer to a particular location or element in the array, specify the name of the array and the position number of the particular element in the array.
- The first element in every array is the zeroth element. Thus, the first element of array `c` is referred to as `c[0]`, the second element of array `c` is referred to as `c[1]`, the seventh element of array `c` is referred to as `c[6]`, and, in general, the *i*th element of array `c` is referred to as `c[i - 1]`.
- Array names, like other variable names, can contain only letters, digits and underscores. Array names cannot begin with a digit.
- The position number contained within square brackets is more formally called a subscript. A subscript must be an integer or an integer expression.
- The brackets used to enclose the subscript of an array are actually considered to be an operator in C. They have the same level of precedence as the function call operator.

### Section 6.3 Defining Arrays

- Arrays occupy space in memory. You specify the type of each element and the number of elements in the array so that the computer may reserve the appropriate amount of memory.
- An array of type `char` can be used to store a character string.

### Section 6.4 Array Examples

- The elements of an array can be initialized when the array is defined by following the definition with an equals sign and braces, `{}`, containing a comma-separated list of initializers. If there are fewer initializers than elements in the array, the remaining elements are initialized to zero.
- The statement `int n[10] = {0};` explicitly initializes the first element to zero and initializes the remaining nine elements to zero because there are fewer initializers than there are elements in the array. It's important to remember that automatic arrays are not automatically initialized to zero. You must at least initialize the first element to zero for the remaining elements to be automatically zeroed. This method of initializing the array elements to 0 is performed at compile time for static arrays and at runtime for automatic arrays.
- If the array size is omitted from a definition with an initializer list, the number of elements in the array will be the number of elements in the initializer list.
- The `#define` preprocessor directive can be used to define a symbolic constant—an identifier that is replaced with replacement text by the C preprocessor before the program is compiled. When the program is preprocessed, all occurrences of the symbolic constant are replaced with the replacement text. Using symbolic constants to specify array sizes makes programs more scalable.

- C has no array bounds checking to prevent a program from referring to an element that does not exist. Thus, an executing program can “walk off” the end of an array without warning. You should ensure that all array references remain within the bounds of the array.
- A string such as “hello” is really a static array of individual characters in C.
- A character array can be initialized using a string literal. In this case, the size of the array is determined by the compiler based on the length of the string.
- Every string contains a special string-termination character called the null character. The character constant representing the null character is ‘\0’.
- A character array representing a string should always be defined large enough to hold the number of characters in the string and the terminating null character.
- Character arrays also can be initialized with individual character constants in an initializer list.
- Because a string is really an array of characters, we can access individual characters in a string directly using array subscript notation.
- You can input a string directly into a character array from the keyboard using `scanf` and the conversion specifier `%s`. The name of the character array is passed to `scanf` without the preceding `&` and used with nonstring variables. The `&` is normally used to provide `scanf` with a variable’s location in memory so that a value can be stored there. An array name is the address of the start of the array; therefore, the `&` is not necessary.
- Function `scanf` reads characters from the keyboard until the first white-space character is encountered—it does not check the array size. Thus, `scanf` can write beyond the end of the array.
- A character array representing a string can be output with `printf` and the `%s` conversion specifier. The characters of the string are printed until a terminating null character is encountered.
- A static local variable exists for the duration of the program but is only visible in the function body. We can apply `static` to a local array definition so that the array is not created and initialized each time the function is called and the array is not destroyed each time the function is exited in the program. This reduces program execution time, particularly for programs with frequently called functions that contain large arrays.
- Arrays that are static are automatically initialized once at compile time. If you do not explicitly initialize a static array, that array’s elements are initialized to zero by the compiler.

### *Section 6.5 Passing Arrays to Functions*

- To pass an array argument to a function, specify the name of the array without any brackets.
- Unlike char arrays that contain strings, other array types do not have a special terminator. For this reason, the size of an array is passed to a function, so that the function can process the proper number of elements.
- C automatically passes arrays to functions by reference—the called functions can modify the element values in the callers’ original arrays. The name of the array evaluates to the address of the first element of the array. Because the starting address of the array is passed, the called function knows precisely where the array is stored. Therefore, when the called function modifies array elements in its function body, it’s modifying the actual elements of the array in their original memory locations.
- Although entire arrays are passed by reference, individual array elements are passed by value exactly as simple variables are.
- Such simple single pieces of data (such as individual `ints`, `floats` and `chars`) are called scalars.
- To pass an element of an array to a function, use the subscripted name of the array element as an argument in the function call.



- For a function to receive an array through a function call, the function's parameter list must specify that an array will be received. The size of the array is not required between the array brackets. If it's included, the compiler checks that it's greater than zero, then ignores it.
- When an array parameter is preceded by the `const` qualifier, the elements of the array become constant in the function body, and any attempt to modify an element of the array in the function body results in a compile-time error.

### *Section 6.6 Sorting Arrays*

- Sorting data (i.e., placing the data into a particular order such as ascending or descending) is one of the most important computing applications.
- One sorting technique is called the bubble sort or the sinking sort, because the smaller values gradually "bubble" their way upward to the top of the array like air bubbles rising in water, while the larger values sink to the bottom of the array. The technique is to make several passes through the array. On each pass, successive pairs of elements are compared. If a pair is in increasing order (or if the values are identical), we leave the values as they are. If a pair is in decreasing order, their values are swapped in the array.
- Because of the way the successive comparisons are made, a large value may move down the array many positions on a single pass, but a small value may move up only one position.
- The chief virtue of the bubble sort is that it's easy to program. However, the bubble sort runs slowly. This becomes apparent when sorting large arrays.

### *Section 6.7 Case Study: Computing Mean, Median and Mode Using Arrays*

- The mean is the arithmetic average of a set of values.
- The median is the "middle value" in a sorted set of values.
- The mode is the value that occurs most frequently in a set of values.

### *Section 6.8 Searching Arrays*

- The process of finding a particular element of an array is called searching.
- The linear search compares each element of the array with the search key. Since the array is not in any particular order, it's just as likely that the value will be found in the first element as in the last. On average, therefore, the search key will be compared with half the elements of the array.
- The linear searching method works well for small or unsorted arrays. For sorted arrays, the high-speed binary search technique can be used.
- The binary search algorithm eliminates from consideration one-half of the elements in a sorted array after each comparison. The algorithm locates the middle element of the array and compares it to the search key. If they are equal, the search key is found and the array subscript of that element is returned. If they are not equal, the problem is reduced to searching one-half of the array. If the search key is less than the middle element of the array, the first half of the array is searched, otherwise the second half of the array is searched. If the search key is not found in the specified subarray (piece of the original array), the algorithm is repeated on one-quarter of the original array. The search continues until the search key is equal to the middle element of a subarray, or until the subarray consists of one element that is not equal to the search key (i.e., the search key is not found).
- When using a binary search, the maximum number of comparisons required for any array can be determined by finding the first power of 2 greater than the number of array elements.

### *Section 6.9 Multiple-Subscripted Arrays*

- A common use of multiple-subscripted arrays (also called multidimensional arrays) is to represent tables of values consisting of information arranged in rows and columns. To identify a par-

ticular table element, we must specify two subscripts: The first (by convention) identifies the element's row and the second (by convention) identifies the element's column.

- Tables or arrays that require two subscripts to identify a particular element are called double-subscripted arrays.
- Multiple-subscripted arrays can have more than two subscripts.
- A multiple-subscripted array can be initialized when it's defined, much like a single-subscripted array. The values are grouped by row in braces. If there are not enough initializers for a given row, the remaining elements of that row are initialized to 0.
- The first subscript of a multiple-subscripted array parameter declaration is not required, but all subsequent subscripts are required. The compiler uses these subscripts to determine the locations in memory of elements in multiple-subscripted arrays. All array elements are stored consecutively in memory regardless of the number of subscripts. In a double-subscripted array, the first row is stored in memory followed by the second row.
- Providing the subscript values in a parameter declaration enables the compiler to tell the function how to locate an element in the array. In a double-subscripted array, each row is basically a single-subscripted array. To locate an element in a particular row, the compiler must know how many elements are in each row so that it can skip the proper number of memory locations when accessing the array.

## Terminology

|                                  |                          |
|----------------------------------|--------------------------|
| array 196                        | null character 207       |
| binary search 223                | position number 196      |
| bubble sort 216                  | replacement text 201     |
| const keyword 215                | scalable 202             |
| double-subscripted array 229     | scalar 212               |
| element 196                      | search key 223           |
| index (or subscript) 196         | searching 223            |
| initializer 199                  | sinking sort 216         |
| key value 223                    | subscript 196            |
| linear search 223                | survey data analysis 218 |
| <i>m</i> -by- <i>n</i> array 229 | symbolic constant 201    |
| multidimensional array 229       | table 229                |
| multiple-subscripted array 229   | value 196                |
| name 196                         | zeroth element 196       |

## Self-Review Exercises

- 6.1** Answer each of the following:
- Lists and tables of values are stored in \_\_\_\_\_.
  - An array's elements are related by the fact that they have the same \_\_\_\_\_ and \_\_\_\_\_.
  - The number used to refer to a particular element of an array is called its \_\_\_\_\_.
  - A(n) \_\_\_\_\_ should be used to specify the size of an array because it makes the program more scalable.
  - The process of placing the elements of an array in order is called \_\_\_\_\_ the array.
  - Determining whether an array contains a certain key value is called \_\_\_\_\_ the array.
  - An array that uses two subscripts is referred to as a(n) \_\_\_\_\_ array.
- 6.2** State whether the following are *true* or *false*. If the answer is *false*, explain why.
- An array can store many different types of values.
  - An array subscript can be of data type `double`.

- c) If there are fewer initializers in an initializer list than the number of elements in the array, C automatically initializes the remaining elements to the last value in the list of initializers.
- d) It's an error if an initializer list contains more initializers than there are elements in the array.
- e) An individual array element that is passed to a function as an argument of the form `a[i]` and modified in the called function will contain the modified value in the calling function.

**6.3** Answer the following questions regarding an array called `fractions`.

- a) Define a symbolic constant `SIZE` to be replaced with the replacement text 10.
- b) Define an array with `SIZE` elements of type `double` and initialize the elements to 0.
- c) Name the fourth element from the beginning of the array.
- d) Refer to array element 4.
- e) Assign the value 1.667 to array element nine.
- f) Assign the value 3.333 to the seventh element of the array.
- g) Print array elements 6 and 9 with two digits of precision to the right of the decimal point, and show the output that is displayed on the screen.
- h) Print all the elements of the array, using a `for` repetition statement. Assume the integer variable `x` has been defined as a control variable for the loop. Show the output.

**6.4** Write statements to accomplish the following:

- a) Define `table` to be an integer array and to have 3 rows and 3 columns. Assume the symbolic constant `SIZE` has been defined to be 3.
- b) How many elements does the array `table` contain? Print the total number of elements.
- c) Use a `for` repetition statement to initialize each element of `table` to the sum of its subscripts. Assume the integer variables `x` and `y` are defined as control variables.
- d) Print the values of each element of array `table`. Assume the array was initialized with the definition:

```
int table[SIZE][SIZE] =
{ { 1, 8 }, { 2, 4, 6 }, { 5 } };
```

**6.5** Find the error in each of the following program segments and correct the error.

- a) `#define SIZE 100;`
- b) `SIZE = 10;`
- c) Assume `int b[ 10 ] = { 0 }, i;`  

```
for (i = 0; i <= 10; i++) {
 b[i] = 1;
}
```
- d) `#include <stdio.h>;`
- e) Assume `int a[ 2 ][ 2 ] = { { 1, 2 }, { 3, 4 } };`  

```
a[1, 1] = 5;
```
- f) `#define VALUE = 120`

## Answers to Self-Review Exercises

**6.1** a) Arrays. b) Name, type. c) Subscript. d) Symbolic constant. e) Sorting. f) Searching. g) Double-subscripted.

- 6.2**
- a) False. An array can store only values of the same type.
  - b) False. An array subscript must be an integer or an integer expression.
  - c) False. C automatically initializes the remaining elements to zero.
  - d) True.
  - e) False. Individual elements of an array are passed by value. If the entire array is passed to a function, then any modifications will be reflected in the original.

- 6.3**
- a) `#define SIZE 10`
  - b) `double fractions[ SIZE ] = { 0.0 };`
  - c) `fractions[ 3 ]`
  - d) `fractions[ 4 ]`
  - e) `fractions[ 9 ] = 1.667;`
  - f) `fractions[ 6 ] = 3.333;`
  - g) `printf( "%.2f %.2f\n", fractions[ 6 ], fractions[ 9 ] );`  
*Output:* 3.33 1.67.
  - h) `for ( x = 0; x < SIZE; x++ ) {`  
`printf( "fractions[%d] = %f\n", x, fractions[ x ] );`  
`}`

*Output:*

```
fractions[0] = 0.000000
fractions[1] = 0.000000
fractions[2] = 0.000000
fractions[3] = 0.000000
fractions[4] = 0.000000
fractions[5] = 0.000000
fractions[6] = 3.333000
fractions[7] = 0.000000
fractions[8] = 0.000000
fractions[9] = 1.667000
```

- 6.4**
- a) `int table[ SIZE ][ SIZE ];`
  - b) Nine elements. `printf( "%d\n", SIZE * SIZE );`
  - c) `for ( x = 0; x < SIZE; x++ ) {`  
`for ( y = 0; y < SIZE; y++ ) {`  
`table[ x ][ y ] = x + y;`  
`}`  
`}`
  - d) `for ( x = 0; x < SIZE; x++ ) {`  
`for ( y = 0; y < SIZE; y++ ) {`  
`printf( "table[%d][%d] = %d\n", x, y, table[ x ][ y ] );`  
`}`  
`}`

*Output:*

```
table[0][0] = 1
table[0][1] = 8
table[0][2] = 0
table[1][0] = 2
table[1][1] = 4
table[1][2] = 6
table[2][0] = 5
table[2][1] = 0
table[2][2] = 0
```

- 6.5**
- a) Error: Semicolon at end of `#define` preprocessor directive.  
Correction: Eliminate semicolon.
  - b) Error: Assigning a value to a symbolic constant using an assignment statement.  
Correction: Assign a value to the symbolic constant in a `#define` preprocessor directive without using the assignment operator as in `#define SIZE 10`.
  - c) Error: Referencing an array element outside the bounds of the array (`b[ 10 ]`).  
Correction: Change the final value of the control variable to 9.

- d) Error: Semicolon at end of `#include` preprocessor directive.  
Correction: Eliminate semicolon.
- e) Error: Array subscripting done incorrectly.  
Correction: Change the statement to `a[ 1 ][ 1 ] = 5;`
- f) Error: Assigning a value to a symbolic constant using an assignment statement.  
Correction: Assign a value to the symbolic constant in a `#define` preprocessor directive without using the assignment operator as in `#define VALUE 120.`

## Exercises

**6.6** Fill in the blanks in each of the following:

- a) C stores lists of values in \_\_\_\_\_.
- b) The elements of an array are related by the fact that they \_\_\_\_\_.
- c) When referring to an array element, the position number contained within parentheses is called a(n) \_\_\_\_\_.
- d) The names of the five elements of array `p` are \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_, and \_\_\_\_\_.
- e) The contents of a particular element of an array is called the \_\_\_\_\_ of that element.
- f) Naming an array, stating its type and specifying the number of elements in the array is called \_\_\_\_\_ the array.
- g) The process of placing the elements of an array into either ascending or descending order is called \_\_\_\_\_.
- h) In a double-subscripted array, the first subscript (by convention) identifies the \_\_\_\_\_ of an element and the second subscript (by convention) identifies the \_\_\_\_\_ of an element.
- i) An  $m$ -by- $n$  array contains \_\_\_\_\_ rows, \_\_\_\_\_ columns and \_\_\_\_\_ elements.
- j) The name of the element in row 3 and column 5 of array `d` is \_\_\_\_\_.

**6.7** State which of the following are *true* and which are *false*. If *false*, explain why.

- a) To refer to a particular location or element within an array, we specify the name of the array and the value of the particular element.
- b) An array definition reserves space for the array.
- c) To indicate that 100 locations should be reserved for integer array `p`, write  
`p[ 100 ];`
- d) A C program that initializes the elements of a 15-element array to zero must contain one `for` statement.
- e) A C program that totals the elements of a double-subscripted array must contain nested `for` statements.
- f) The mean, median and mode of the following set of values are 5, 6 and 7, respectively: 1, 2, 5, 6, 7, 7, 7.

**6.8** Write statements to accomplish each of the following:

- a) Display the value of the seventh element of character array `f`.
- b) Input a value into element 4 of single-subscripted floating-point array `b`.
- c) Initialize each of the five elements of single-subscripted integer array `g` to 8.
- d) Total the elements of floating-point array `c` of 100 elements.
- e) Copy array `a` into the first portion of array `b`. Assume `double a[11], b[34];`
- f) Determine and print the smallest and largest values contained in 99-element floating-point array `w`.

**6.9** Consider a 2-by-5 integer array `t`.

- a) Write a definition for `t`.

- b) How many rows does `t` have?
- c) How many columns does `t` have?
- d) How many elements does `t` have?
- e) Write the names of all the elements in the second row of `t`.
- f) Write the names of all the elements in the third column of `t`.
- g) Write a single statement that sets the element of `t` in row 1 and column 2 to zero.
- h) Write a series of statements that initialize each element of `t` to zero. Do not use a repetition structure.
- i) Write a nested `for` statement that initializes each element of `t` to zero.
- j) Write a statement that inputs the values for the elements of `t` from the terminal.
- k) Write a series of statements that determine and print the smallest value in array `t`.
- l) Write a statement that displays the elements of the first row of `t`.
- m) Write a statement that totals the elements of the fourth column of `t`.
- n) Write a series of statements that print the array `t` in tabular format. List the column subscripts as headings across the top and list the row subscripts at the left of each row.

**6.10** (*Sales Commissions*) Use a single-subscripted array to solve the following problem. A company pays its salespeople on a commission basis. The salespeople receive \$200 per week plus 9% of their gross sales for that week. For example, a salesperson who grosses \$3000 in sales in a week receives \$200 plus 9% of \$3000, or a total of \$470. Write a C program (using an array of counters) that determines how many of the salespeople earned salaries in each of the following ranges (assume that each salesperson's salary is truncated to an integer amount):

- a) \$200–299
- b) \$300–399
- c) \$400–499
- d) \$500–599
- e) \$600–699
- f) \$700–799
- g) \$800–899
- h) \$900–999
- i) \$1000 and over

**6.11** (*Bubble Sort*) The bubble sort presented in Fig. 6.15 is inefficient for large arrays. Make the following simple modifications to improve the performance of the bubble sort.

- a) After the first pass, the largest number is guaranteed to be in the highest-numbered element of the array; after the second pass, the two highest numbers are “in place,” and so on. Instead of making nine comparisons on every pass, modify the bubble sort to make eight comparisons on the second pass, seven on the third pass and so on.
- b) The data in the array may already be in the proper order or near-proper order, so why make nine passes if fewer will suffice? Modify the sort to check at the end of each pass whether any swaps have been made. If none has been made, then the data must already be in the proper order, so the program should terminate. If swaps have been made, then at least one more pass is needed.

**6.12** Write single statements that perform each of the following single-subscripted array operations:

- a) Initialize the 10 elements of integer array `counts` to zeros.
- b) Add 1 to each of the 15 elements of integer array `bonus`.
- c) Read the 12 values of floating-point array `monthlyTemperatures` from the keyboard.
- d) Print the five values of integer array `bestScores` in column format.

**6.13** Find the error(s) in each of the following statements:

- a) Assume: `char str[ 5 ];`  
`scanf( "%s", str ); /* User types hello */`

- b) Assume: `int a[ 3 ]`;  
`printf( "$d %d %d\n", a[ 1 ], a[ 2 ], a[ 3 ] );`  
 c) `double f[ 3 ] = { 1.1, 10.01, 100.001, 1000.0001 };`  
 d) Assume: `double d[ 2 ][ 10 ]`;  
`d[ 1, 9 ] = 2.345;`

**6.14 (Mean, Median and Mode Program Modifications)** Modify the program of Fig. 6.16 so function `mode` is capable of handling a tie for the mode value. Also modify function `median` so the two middle elements are averaged in an array with an even number of elements.

**6.15 (Duplicate Elimination)** Use a single-subscripted array to solve the following problem. Read in 20 numbers, each of which is between 10 and 100, inclusive. As each number is read, print it only if it's not a duplicate of a number already read. Provide for the "worst case" in which all 20 numbers are different. Use the smallest possible array to solve this problem.

**6.16** Label the elements of 3-by-5 double-subscripted array `sales` to indicate the order in which they are set to zero by the following program segment:

```
for (row = 0; row <= 2; row++) {
 for (column = 0; column <= 4; column++) {
 sales[row][column] = 0;
 }
}
```

**6.17** What does the following program do?

```
1 /* ex06_17.c */
2 /* What does this program do? */
3 #include <stdio.h>
4 #define SIZE 10
5
6 int whatIsThis(const int b[], int p); /* function prototype */
7
8 /* function main begins program execution */
9 int main(void)
10 {
11 int x; /* holds return value of function whatIsThis */
12
13 /* initialize array a */
14 int a[SIZE] = { 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 };
15
16 x = whatIsThis(a, SIZE);
17
18 printf("Result is %d\n", x);
19 return 0; /* indicates successful termination */
20 } /* end main */
21
22 /* what does this function do? */
23 int whatIsThis(const int b[], int p)
24 {
25 /* base case */
26 if (p == 1) {
27 return b[0];
28 } /* end if */
29 else { /* recursion step */
30
31 return b[p - 1] + whatIsThis(b, p - 1);
32 } /* end else */
33 } /* end function whatIsThis */
```

**6.18** What does the following program do?

```

1 /* ex06_18.c */
2 /* What does this program do? */
3 #include <stdio.h>
4 #define SIZE 10
5
6 /* function prototype */
7 void someFunction(const int b[], int startIndex, int size);
8
9 /* function main begins program execution */
10 int main(void)
11 {
12 int a[SIZE] = { 8, 3, 1, 2, 6, 0, 9, 7, 4, 5 }; /* initialize a */
13
14 printf("Answer is:\n");
15 someFunction(a, 0, SIZE);
16 printf("\n");
17 return 0; /* indicates successful termination */
18 } /* end main */
19
20 /* What does this function do? */
21 void someFunction(const int b[], int startIndex, int size)
22 {
23 if (startIndex < size) {
24 someFunction(b, startIndex + 1, size);
25 printf("%d ", b[startIndex]);
26 } /* end if */
27 } /* end function someFunction */

```

**6.19 (Dice Rolling)** Write a program that simulates the rolling of two dice. The program should use `rand` to roll the first die, and should use `rand` again to roll the second die. The sum of the two values should then be calculated. [Note: Since each die can show an integer value from 1 to 6, then the sum of the two values will vary from 2 to 12, with 7 being the most frequent sum and 2 and 12 the least frequent sums.] Figure 6.23 shows the 36 possible combinations of the two dice. Your program should roll the two dice 36,000 times. Use a single-subscripted array to tally the numbers of times each possible sum appears. Print the results in a tabular format. Also, determine if the totals are reasonable; i.e., there are six ways to roll a 7, so approximately one-sixth of all the rolls should be 7.

|   | 1 | 2 | 3 | 4  | 5  | 6  |
|---|---|---|---|----|----|----|
| 1 | 2 | 3 | 4 | 5  | 6  | 7  |
| 2 | 3 | 4 | 5 | 6  | 7  | 8  |
| 3 | 4 | 5 | 6 | 7  | 8  | 9  |
| 4 | 5 | 6 | 7 | 8  | 9  | 10 |
| 5 | 6 | 7 | 8 | 9  | 10 | 11 |
| 6 | 7 | 8 | 9 | 10 | 11 | 12 |

**Fig. 6.23** | Dice rolling outcomes.



**6.20** (*Game of Craps*) Write a program that runs 1000 games of craps (without human intervention) and answers each of the following questions:

- How many games are won on the first roll, second roll, ..., twentieth roll and after the twentieth roll?
- How many games are lost on the first roll, second roll, ..., twentieth roll and after the twentieth roll?
- What are the chances of winning at craps? [*Note:* You should discover that craps is one of the fairest casino games. What do you suppose this means?]
- What is the average length of a game of craps?
- Do the chances of winning improve with the length of the game?

**6.21** (*Airline Reservations System*) A small airline has just purchased a computer for its new automated reservations system. The president has asked you to program the new system. You'll write a program to assign seats on each flight of the airline's only plane (capacity: 10 seats).

Your program should display the following menu of alternatives:

```
Please type 1 for "first class"
Please type 2 for "economy"
```

If the person types 1, then your program should assign a seat in the first class section (seats 1–5). If the person types 2, then your program should assign a seat in the economy section (seats 6–10). Your program should then print a boarding pass indicating the person's seat number and whether it's in the first class or economy section of the plane.

Use a single-subscripted array to represent the seating chart of the plane. Initialize all the elements of the array to 0 to indicate that all seats are empty. As each seat is assigned, set the corresponding element of the array to 1 to indicate that the seat is no longer available.

Your program should, of course, never assign a seat that has already been assigned. When the first class section is full, your program should ask the person if it's acceptable to be placed in the economy section (and vice versa). If yes, then make the appropriate seat assignment. If no, then print the message "Next flight leaves in 3 hours."

**6.22** (*Total Sales*) Use a double-subscripted array to solve the following problem. A company has four salespeople (1 to 4) who sell five different products (1 to 5). Once a day, each salesperson passes in a slip for each different type of product sold. Each slip contains:

- The salesperson number
- The product number
- The total dollar value of that product sold that day

Thus, each salesperson passes in between 0 and 5 sales slips per day. Assume that the information from all of the slips for last month is available. Write a program that will read all this information for last month's sales and summarize the total sales by salesperson by product. All totals should be stored in the double-subscripted array `sales`. After processing all the information for last month, print the results in tabular format with each of the columns representing a particular salesperson and each of the rows representing a particular product. Cross total each row to get the total sales of each product for last month; cross total each column to get the total sales by salesperson for last month. Your tabular printout should include these cross totals to the right of the totaled rows and to the bottom of the totaled columns.

**6.23** (*Turtle Graphics*) The Logo language, which is particularly popular among personal computer users, made the concept of *turtle graphics* famous. Imagine a mechanical turtle that walks around the room under the control of a C program. The turtle holds a pen in one of two positions, up or down. While the pen is down, the turtle traces out shapes as it moves; while the pen is up, the turtle moves about freely without writing anything. In this problem you'll simulate the operation of the turtle and create a computerized sketchpad as well.

Use a 50-by-50 array `floor` which is initialized to zeros. Read commands from an array that contains them. Keep track of the current position of the turtle at all times and whether the pen is currently up or down. Assume that the turtle always starts at position 0, 0 of the floor with its pen up. The set of turtle commands your program must process are shown in Fig. 6.24. Suppose that the turtle is somewhere near the center of the floor. The following “program” would draw and print a 12-by-12 square:

```
2
5,12
3
5,12
3
5,12
3
5,12
1
6
9
```

As the turtle moves with the pen down, set the appropriate elements of array `floor` to 1s. When the 6 command (print) is given, wherever there is a 1 in the array, display an asterisk, or some other character you choose. Wherever there is a zero, display a blank. Write a program to implement the turtle graphics capabilities discussed here. Write several turtle graphics programs to draw interesting shapes. Add other commands to increase the power of your turtle graphics language.

| Command | Meaning                                            |
|---------|----------------------------------------------------|
| 1       | Pen up                                             |
| 2       | Pen down                                           |
| 3       | Turn right                                         |
| 4       | Turn left                                          |
| 5, 10   | Move forward 10 spaces (or a number other than 10) |
| 6       | Print the 50-by-50 array                           |
| 9       | End of data (sentinel)                             |

**Fig. 6.24** | Turtle commands.

**6.24 (Knight’s Tour)** One of the more interesting puzzlers for chess buffs is the Knight’s Tour problem, originally proposed by the mathematician Euler. The question is this: Can the chess piece called the knight move around an empty chessboard and touch each of the 64 squares once and only once? We study this intriguing problem in depth here.

The knight makes L-shaped moves (over two in one direction and then over one in a perpendicular direction). Thus, from a square in the middle of an empty chessboard, the knight can make eight different moves (numbered 0 through 7) as shown in Fig. 6.25.

- Draw an 8-by-8 chessboard on a sheet of paper and attempt a Knight’s Tour by hand. Put a 1 in the first square you move to, a 2 in the second square, a 3 in the third, and so on. Before starting the tour, estimate how far you think you’ll get, remembering that a full tour consists of 64 moves. How far did you get? Were you close to the estimate?
- Now let’s develop a program that will move the knight around a chessboard. The board itself is represented by an 8-by-8 double-subscripted array `board`. Each of the squares is initialized to zero. We describe each of the eight possible moves in terms of both their

horizontal and vertical components. For example, a move of type 0 as shown in Fig. 6.25 consists of moving two squares horizontally to the right and one square vertically upward. Move 2 consists of moving one square horizontally to the left and two squares vertically upward. Horizontal moves to the left and vertical moves upward are indicated with negative numbers. The eight moves may be described by two single-subscripted arrays, `horizontal` and `vertical`, as follows:


```
horizontal[0] = 2
horizontal[1] = 1
horizontal[2] = -1
horizontal[3] = -2
horizontal[4] = -2
horizontal[5] = -1
horizontal[6] = 1
horizontal[7] = 2

vertical[0] = -1
vertical[1] = -2
vertical[2] = -2
vertical[3] = -1
vertical[4] = 1
vertical[5] = 2
vertical[6] = 2
vertical[7] = 1
```

Let the variables `currentRow` and `currentColumn` indicate the row and column of the knight's current position on the board. To make a move of type `moveNumber`, where `moveNumber` is between 0 and 7, your program uses the statements

```
currentRow += vertical[moveNumber];
currentColumn += horizontal[moveNumber];
```

Keep a counter that varies from 1 to 64. Record the latest count in each square the knight moves to. Remember to test each potential move to see if the knight has already visited that square. And, of course, test every potential move to make sure that the knight does not land off the chessboard. Now write a program to move the knight around the chessboard. Run the program. How many moves did the knight make?



**Fig. 6.25** | The eight possible moves of the knight.

- c) After attempting to write and run a Knight's Tour program, you have probably developed some valuable insights. We'll use these to develop a *heuristic* (or strategy) for mov-

ing the knight. Heuristics do not guarantee success, but a carefully developed heuristic greatly improves the chance of success. You may have observed that the outer squares are in some sense more troublesome than the squares nearer the center of the board. In fact, the most troublesome, or inaccessible, squares are the four corners.

Intuition may suggest that you should attempt to move the knight to the most troublesome squares first and leave open those that are easiest to get to, so that when the board gets congested near the end of the tour, there will be a greater chance of success.

We may develop an “accessibility heuristic” by classifying each of the squares according to how accessible it is and always moving the knight to the square (within the knight’s L-shaped moves, of course) that is most inaccessible. We label a double-subscripted array *accessibility* with numbers indicating from how many squares each particular square is accessible. On a blank chessboard, the center squares are therefore rated as 8s, the corner squares are rated as 2s, and the other squares have accessibility numbers of 3, 4, or 6 as follows:

|   |   |   |   |   |   |   |   |
|---|---|---|---|---|---|---|---|
| 2 | 3 | 4 | 4 | 4 | 4 | 3 | 2 |
| 3 | 4 | 6 | 6 | 6 | 6 | 4 | 3 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 4 | 6 | 8 | 8 | 8 | 8 | 6 | 4 |
| 3 | 4 | 6 | 6 | 6 | 6 | 4 | 3 |
| 2 | 3 | 4 | 4 | 4 | 4 | 3 | 2 |

Now write a version of the Knight’s Tour program using the accessibility heuristic. At any time, the knight should move to the square with the lowest accessibility number. In case of a tie, the knight may move to any of the tied squares. Therefore, the tour may begin in any of the four corners. [Note: As the knight moves around the chessboard, your program should reduce the accessibility numbers as more and more squares become occupied. In this way, at any given time during the tour, each available square’s accessibility number will remain equal to precisely the number of squares from which that square may be reached.] Run this version of your program. Did you get a full tour? Now modify the program to run 64 tours, one from each square of the chessboard. How many full tours did you get?

- d) Write a version of the Knight’s Tour program which, when encountering a tie between two or more squares, decides what square to choose by looking ahead to those squares reachable from the “tied” squares. Your program should move to the square for which the next move would arrive at a square with the lowest accessibility number.

**6.25 (Knight’s Tour: Brute-Force Approaches)** In Exercise 6.24 we developed a solution to the Knight’s Tour problem. The approach used, called the “accessibility heuristic,” generates many solutions and executes efficiently.

As computers continue increasing in power, we’ll be able to solve many problems with sheer computer power and relatively unsophisticated algorithms. Let’s call this approach “brute-force” problem solving.

- a) Use random number generation to enable the knight to walk around the chess board (in its legitimate L-shaped moves, of course) at random. Your program should run one tour and print the final chessboard. How far did the knight get?
- b) Most likely, the preceding program produced a relatively short tour. Now modify your program to attempt 1000 tours. Use a single-subscripted array to keep track of the number of tours of each length. When your program finishes attempting the 1000 tours, it should print this information in neat tabular format. What was the best result?
- c) Most likely, the preceding program gave you some “respectable” tours but no full tours. Now “pull all the stops out” and simply let your program run until it produces a full

tour. [Caution: This version of the program could run for hours on a powerful computer.] Once again, keep a table of the number of tours of each length and print this table when the first full tour is found. How many tours did your program attempt before producing a full tour? How much time did it take?


- d) Compare the brute-force version of the Knight's Tour with the accessibility heuristic version. Which required a more careful study of the problem? Which algorithm was more difficult to develop? Which required more computer power? Could we be certain (in advance) of obtaining a full tour with the accessibility heuristic approach? Could we be certain (in advance) of obtaining a full tour with the brute-force approach? Argue the pros and cons of brute-force problem solving in general.

**6.26 (Eight Queens)** Another puzzler for chess buffs is the Eight Queens problem. Simply stated: Is it possible to place eight queens on an empty chessboard so that no queen is “attacking” any other—that is, so that no two queens are in the same row, the same column, or along the same diagonal? Use the kind of thinking developed in Exercise 6.24 to formulate a heuristic for solving the Eight Queens problem. Run your program. [Hint: It's possible to assign a numeric value to each square of the chessboard indicating how many squares of an empty chessboard are “eliminated” once a queen is placed in that square. For example, each of the four corners would be assigned the value 22, as in Fig. 6.26.]

Once these “elimination numbers” are placed in all 64 squares, an appropriate heuristic might be: Place the next queen in the square with the smallest elimination number. Why is this strategy intuitively appealing?

**6.27 (Eight Queens: Brute-Force Approaches)** In this problem you'll develop several brute-force approaches to solving the Eight Queens problem introduced in Exercise 6.26.

- Solve the Eight Queens problem, using the random brute-force technique developed in Exercise 6.25.
- Use an exhaustive technique (i.e., try all possible combinations of eight queens on the chessboard).
- Why do you suppose the exhaustive brute-force approach may not be appropriate for solving the Eight Queens problem?
- Compare and contrast the random brute-force and exhaustive brute-force approaches in general.



**Fig. 6.26** | The 22 squares eliminated by placing a queen in the upper-left corner.

**6.28 (Duplicate Elimination)** In Chapter 12, we explore the high-speed binary search tree data structure. One feature of a binary search tree is that duplicate values are discarded when insertions are made into the tree. This is referred to as duplicate elimination. Write a program that produces

20 random numbers between 1 and 20. The program should store all nonduplicate values in an array. Use the smallest possible array to accomplish this task.

**6.29** (*Knight's Tour: Closed Tour Test*) In the Knight's Tour, a full tour is when the knight makes 64 moves touching each square of the chessboard once and only once. A closed tour occurs when the 64th move is one move away from the location in which the knight started the tour. Modify the Knight's Tour program you wrote in Exercise 6.24 to test for a closed tour if a full tour has occurred.

**6.30** (*The Sieve of Eratosthenes*) A prime integer is any integer greater than 1 that can be divided evenly only by itself and 1. The Sieve of Eratosthenes is a method of finding prime numbers. It works as follows:

- Create an array with all elements initialized to 1 (true). Array elements with prime subscripts will remain 1. All other array elements will eventually be set to zero.
- Starting with array subscript 2 (subscript 1 is not prime), every time an array element is found whose value is 1, loop through the remainder of the array and set to zero every element whose subscript is a multiple of the subscript for the element with value 1. For array subscript 2, all elements beyond 2 in the array that are multiples of 2 will be set to zero (subscripts 4, 6, 8, 10, and so on.). For array subscript 3, all elements beyond 3 in the array that are multiples of 3 will be set to zero (subscripts 6, 9, 12, 15, and so on.).

When this process is complete, the array elements that are still set to 1 indicate that the subscript is a prime number. Write a program that uses an array of 1000 elements to determine and print the prime numbers between 1 and 999. Ignore element 0 of the array.

## Recursion Exercises

**6.31** (*Palindromes*) A palindrome is a string that is spelled the same way forward and backward. Some examples of palindromes are: "radar," "able was i ere i saw elba," and, if you ignore blanks, "a man a plan a canal panama." Write a recursive function `testPalindrome` that returns 1 if the string stored in the array is a palindrome and 0 otherwise. The function should ignore spaces and punctuation in the string.

**6.32** (*Linear Search*) Modify the program of Fig. 6.18 to use a recursive `linearSearch` function to perform the linear search of the array. The function should receive an integer array and the size of the array as arguments. If the search key is found, return the array subscript; otherwise, return -1.

**6.33** (*Binary Search*) Modify the program of Fig. 6.19 to use a recursive `binarySearch` function to perform the binary search of the array. The function should receive an integer array and the starting subscript and ending subscript as arguments. If the search key is found, return the array subscript; otherwise, return -1.

**6.34** (*Eight Queens*) Modify the Eight Queens program you created in Exercise 6.26 to solve the problem recursively.

**6.35** (*Print an array*) Write a recursive function `printArray` that takes an array and the size of the array as arguments, prints the array, and returns nothing. The function should stop processing and return when it receives an array of size zero.

**6.36** (*Print a string backward*) Write a recursive function `stringReverse` that takes a character array as an argument, prints it back to front and returns nothing. The function should stop processing and return when the terminating null character of the string is encountered.

**6.37** (*Find the minimum value in an array*) Write a recursive function `recursiveMinimum` that takes an integer array and the array size as arguments and returns the smallest element of the array. The function should stop processing and return when it receives an array of one element.

## Special Section: Sudoku

The game of Sudoku exploded in popularity worldwide in 2005. Almost every major newspaper now publishes a Sudoku puzzle daily. Handheld game players let you play anytime, anywhere and create puzzles on demand at various levels of difficulty. Be sure to check out our Sudoku Resource Center at [www.deitel.com/sudoku](http://www.deitel.com/sudoku) for downloads, tutorials, books, e-books and more that will help you master the game. And not for the faint of heart—try fiendishly difficult Sudokus with tricky twists, a circular Sudoku and a variant of the puzzle with five interlocking grids. Subscribe to our free newsletter, the *Deitel® Buzz Online*, for notifications of updates to our Sudoku Resource Center and to other Deitel Resource Centers at [www.deitel.com](http://www.deitel.com) that provide games, puzzles and other interesting programming projects.

A completed Sudoku puzzle is a  $9 \times 9$  grid (i.e., a two-dimensional array) in which the digits 1 through 9 appear once and only once in each row, each column and each of nine  $3 \times 3$  grids. In the partially completed  $9 \times 9$  grid of Fig. 6.27, row 1, column 1, and the  $3 \times 3$  grid in the upper-left corner of the board each contain the digits 1 through 9 once and only once. We use C's two-dimensional array row and column-numbering conventions, but we're ignoring row 0 and column 0 in conformance with Sudoku community conventions.

The typical Sudoku puzzle provides many filled-in cells and many blanks, often arranged in a symmetrical pattern as is typical with crossword puzzles. The player's task is to fill in the blanks to complete the puzzle. Some puzzles are easy to solve; some are quite difficult, requiring sophisticated solution strategies.

In Appendix D, Game Programming: Solving Sudoku, we'll discuss various simple solution strategies, and suggest what to do when these fail. We'll also present various approaches for programming Sudoku puzzle creators and solvers in C. Unfortunately, Standard C does not include graphics and GUI (graphical user interface) capabilities, so our representation of the board won't be as elegant as we could make it in Java and other programming languages that support these capabilities. You may want to revisit your Sudoku programs after you read Appendix E, Game Programming with the Allegro C Library. Allegro, which is not part of Standard C, offers capabilities that will help you add graphics and even sounds to your Sudoku programs.

|   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
|---|---|---|---|---|---|---|---|---|---|
| 1 | 5 | 1 | 3 | 4 | 9 | 7 | 6 | 2 | 8 |
| 2 | 4 | 6 | 8 |   |   |   |   |   |   |
| 3 | 7 | 9 | 2 |   |   |   |   |   |   |
| 4 | 2 |   |   |   |   |   |   |   |   |
| 5 | 9 |   |   |   |   |   |   |   |   |
| 6 | 3 |   |   |   |   |   |   |   |   |
| 7 | 8 |   |   |   |   |   |   |   |   |
| 8 | 1 |   |   |   |   |   |   |   |   |
| 9 | 6 |   |   |   |   |   |   |   |   |

**Fig. 6.27** | Partially completed  $9 \times 9$  Sudoku grid. Note the nine  $3 \times 3$  grids.



*Addresses are given to us to  
conceal our whereabouts.*

—Saki (H. H. Munro)

*By indirection find direction  
out.*

—William Shakespeare

*Many things,  
having full reference  
To one consent,  
may work contrariously.*

—William Shakespeare

*You will find it a very good  
practice always to verify your  
references, sir!*

—Dr. Routh

## Objectives

In this chapter, you'll learn:

- Pointers and pointer operators.
- To use pointers to pass arguments to functions by reference.
- The close relationships among pointers, arrays and strings.
- To use pointers to functions.
- To define and use arrays of strings.



- |                                                                 |                                                               |
|-----------------------------------------------------------------|---------------------------------------------------------------|
| <b>7.1</b> Introduction                                         | <b>7.7</b> sizeof Operator                                    |
| <b>7.2</b> Pointer Variable Definitions and Initialization      | <b>7.8</b> Pointer Expressions and Pointer Arithmetic         |
| <b>7.3</b> Pointer Operators                                    | <b>7.9</b> Relationship between Pointers and Arrays           |
| <b>7.4</b> Passing Arguments to Functions by Reference          | <b>7.10</b> Arrays of Pointers                                |
| <b>7.5</b> Using the <code>const</code> Qualifier with Pointers | <b>7.11</b> Case Study: Card Shuffling and Dealing Simulation |
| <b>7.6</b> Bubble Sort Using Call-by-Reference                  | <b>7.12</b> Pointers to Functions                             |


Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises  
 Special Section: Building Your Own Computer | Array of Function Pointer Exercises | Making a Difference

## 7.1 Introduction

In this chapter, we discuss one of the most powerful features of the C programming language, the **pointer**.<sup>1</sup> Pointers are among C's most difficult capabilities to master. Pointers enable programs to simulate call-by-reference and to create and manipulate dynamic data structures, i.e., data structures that can grow and shrink at execution time, such as linked lists, queues, stacks and trees. This chapter explains basic pointer concepts. Chapter 10 examines the use of pointers with structures. Chapter 12 introduces dynamic memory management techniques and presents examples of creating and using dynamic data structures.

## 7.2 Pointer Variable Definitions and Initialization

Pointers are variables whose values are memory addresses. Normally, a variable directly contains a specific value. A pointer, on the other hand, contains an address of a variable that contains a specific value. In this sense, a variable name *directly* references a value, and a pointer *indirectly* references a value (Fig. 7.1). Referencing a value through a pointer is called **indirection**.



**Fig. 7.1** | Directly and indirectly referencing a variable.

1. Pointers and pointer-based entities such as arrays and strings, when misused intentionally or accidentally, can lead to errors and security breaches. See our Secure C Programming Resource Center ([www.deitel.com/SecureC/](http://www.deitel.com/SecureC/)) for articles, books, white papers and forums on this important topic.

Pointers, like all variables, must be defined before they can be used. The definition

```
int *countPtr, count;
```

specifies that variable `countPtr` is of type `int *` (i.e., a pointer to an integer) and is read, “`countPtr` is a pointer to `int`” or “`countPtr` points to an object of type `int`.” Also, the variable `count` is defined to be an `int`, not a pointer to an `int`. The `*` only applies to `countPtr` in the definition. When `*` is used in this manner in a definition, it indicates that the variable being defined is a pointer. Pointers can be defined to point to objects of any type.



#### Common Programming Error 7.1

The asterisk (`*`) notation used to declare pointer variables does not distribute to all variable names in a declaration. Each pointer must be declared with the `*` prefixed to the name; e.g., if you wish to declare `xPtr` and `yPtr` as `int` pointers, use `int *xPtr, *yPtr;`.



#### Common Programming Error 7.2

Include the letters `ptr` in pointer variable names to make it clear that these variables are pointers and thus need to be handled appropriately.

Pointers should be initialized either when they’re defined or in an assignment statement. A pointer may be initialized to `NULL`, `0` or an address. A pointer with the value `NULL` points to nothing. `NULL` is a symbolic constant defined in the `<stddef.h>` header (and several other headers, such as `<stdio.h>`). Initializing a pointer to `0` is equivalent to initializing a pointer to `NULL`, but `NULL` is preferred. When `0` is assigned, it’s first converted to a pointer of the appropriate type. The value `0` is the only integer value that can be assigned directly to a pointer variable. Assigning a variable’s address to a pointer is discussed in Section 7.3.



#### Error-Prevention Tip 7.1

Initialize pointers to prevent unexpected results.

## 7.3 Pointer Operators


The `&`, or **address operator**, is a unary operator that returns the address of its operand. For example, assuming the definitions

```
int y = 5;
int *yPtr;
```

the statement

```
yPtr = &y;
```

assigns the address of the variable `y` to pointer variable `yPtr`. Variable `yPtr` is then said to “point to” `y`. Figure 7.2 shows a schematic representation of memory after the preceding assignment is executed.



**Fig. 7.2** | Graphical representation of a pointer pointing to an integer variable in memory.

Figure 7.3 shows the representation of the pointer in memory, assuming that integer variable `y` is stored at location 600000, and pointer variable `yPtr` is stored at location 500000. The operand of the address operator must be a variable; the address operator cannot be applied to constants, to expressions or to variables declared with the storage-class register.



**Fig. 7.3** | Representation of `y` and `yPtr` in memory.

The unary `*` operator, commonly referred to as the **indirection operator** or **dereferencing operator**, returns the value of the object to which its operand (i.e., a pointer) points. For example, the statement

```
printf("%d", *yPtr);
```

prints the value of variable `y`, namely 5. Using `*` in this manner is called **dereferencing a pointer**.



### Common Programming Error 7.3

*Dereferencing a pointer that has not been properly initialized or that has not been assigned to point to a specific location in memory is an error. This could cause a fatal execution-time error, or it could accidentally modify important data and allow the program to run to completion with incorrect results.*

Figure 7.4 demonstrates the pointer operators `&` and `*`. The `printf` conversion specifier `%p` outputs the memory location as a hexadecimal integer on most platforms. (See Appendix C, Number Systems, for more information on hexadecimal integers.) Notice that the address of `a` and the value of `aPtr` are identical in the output, thus confirming that the address of `a` is indeed assigned to the pointer variable `aPtr` (line 11). The `&` and `*` operators are complements of one another—when they're both applied consecutively to `aPtr` in either order (line 21), the same result is printed. Figure 7.5 lists the precedence and associativity of the operators introduced to this point.

```
1 /* Fig. 7.4: fig07_04.c
2 Using the & and * operators */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int a; /* a is an integer */
8 int *aPtr; /* aPtr is a pointer to an integer */
9
10 a = 7;
11 aPtr = &a; /* aPtr set to address of a */
```

**Fig. 7.4** | Using the `&` and `*` pointer operators. (Part I of 2.)

```

12
13 printf("The address of a is %p"
14 "\nThe value of aPtr is %p", &a, aPtr);
15
16 printf("\n\nThe value of a is %d"
17 "\nThe value of *aPtr is %d", a, *aPtr);
18
19 printf("\n\nShowing that * and & are complements of "
20 "each other\n&*aPtr = %p"
21 "\n*&aPtr = %p\n", &*aPtr, *&aPtr);
22 return 0; /* indicates successful termination */
23 } /* end main */

```

The address of a is 0012FF7C  
The value of aPtr is 0012FF7C

The value of a is 7  
The value of \*aPtr is 7

Showing that \* and & are complements of each other.  
&\*aPtr = 0012FF7C  
\*&aPtr = 0012FF7C

**Fig. 7.4** | Using the & and \* pointer operators. (Part 2 of 2.)

| Operators              | Associativity | Type           |
|------------------------|---------------|----------------|
| () []                  | left to right | highest        |
| + - ++ -- ! * & (type) | right to left | unary          |
| * / %                  | left to right | multiplicative |
| + -                    | left to right | additive       |
| < <= > >=              | left to right | relational     |
| == !=                  | left to right | equality       |
| &&                     | left to right | logical AND    |
|                        | left to right | logical OR     |
| ?:                     | right to left | conditional    |
| = += -= *= /= %=       | right to left | assignment     |
| ,                      | left to right | comma          |

**Fig. 7.5** | Operator precedence and associativity.

## 7.4 Passing Arguments to Functions by Reference

There are two ways to pass arguments to a function—**call-by-value** and **call-by-reference**. All arguments in C are passed by value. As we saw in Chapter 5, `return` may be used to return one value from a called function to a caller (or to return control from a called function without passing back a value). Many functions require the capability to modify one or more variables in the caller or to pass a pointer to a large data object to avoid the over-

head of passing the object by value (which incurs the overhead of making a copy of the object). For these purposes, C provides the capabilities for **simulating call-by-reference**.

In C, you use pointers and the indirection operator to simulate call-by-reference. When calling a function with arguments that should be modified, the addresses of the arguments are passed. This is normally accomplished by applying the address operator (&) to the variable (in the caller) whose value will be modified. As we saw in Chapter 6, arrays are not passed using operator & because C automatically passes the starting location in memory of the array (the name of an array is equivalent to &arrayName[0]). When the address of a variable is passed to a function, the indirection operator (\*) may be used in the function to modify the value at that location in the caller's memory.

The programs in Fig. 7.6 and Fig. 7.7 present two versions of a function that cubes an integer—cubeByValue and cubeByReference. Figure 7.6 passes the variable number to function cubeByValue using call-by-value (line 14). The cubeByValue function cubes its argument and passes the new value back to main using a return statement. The new value is assigned to number in main (line 14).

---

```

1 /* Fig. 7.6: fig07_06.c
2 Cube a variable using call-by-value */
3 #include <stdio.h>
4
5 int cubeByValue(int n); /* prototype */
6
7 int main(void)
8 {
9 int number = 5; /* initialize number */
10
11 printf("The original value of number is %d", number);
12
13 /* pass number by value to cubeByValue */
14 number = cubeByValue(number);
15
16 printf("\nThe new value of number is %d\n", number);
17 return 0; /* indicates successful termination */
18 } /* end main */
19
20 /* calculate and return cube of integer argument */
21 int cubeByValue(int n)
22 {
23 return n * n * n; /* cube local variable n and return result */
24 } /* end function cubeByValue */

```

The original value of number is 5  
The new value of number is 125

**Fig. 7.6** | Cube a variable using call-by-value.

Figure 7.7 passes the variable number using call-by-reference (line 15)—the address of number is passed—to function cubeByReference. Function cubeByReference takes as a parameter a pointer to an int called nPtr (line 22). The function dereferences the pointer and cubes the value to which nPtr points (line 24), then assigns the result to \*nPtr (which

is really number in main), thus changing the value of number in main. Figure 7.8 and Fig. 7.9 analyze graphically the programs in Fig. 7.6 and Fig. 7.7, respectively.

```

1 /* Fig. 7.7: fig07_07.c
2 Cube a variable using call-by-reference with a pointer argument */
3
4 #include <stdio.h>
5
6 void cubeByReference(int *nPtr); /* prototype */
7
8 int main(void)
9 {
10 int number = 5; /* initialize number */
11
12 printf("The original value of number is %d", number);
13
14 /* pass address of number to cubeByReference */
15 cubeByReference(&number);
16
17 printf("\nThe new value of number is %d\n", number);
18 return 0; /* indicates successful termination */
19 } /* end main */
20
21 /* calculate cube of *nPtr; modifies variable number in main */
22 void cubeByReference(int *nPtr)
23 {
24 *nPtr = *nPtr * *nPtr * *nPtr; /* cube *nPtr */
25 } /* end function cubeByReference */

```

```

The original value of number is 5
The new value of number is 125

```

**Fig. 7.7** | Cube a variable using call-by-reference with a pointer argument.

A function receiving an address as an argument must define a pointer parameter to receive the address. For example, in Fig. 7.7 the header for function `cubeByReference` (line 22) is:


```
void cubeByReference(int *nPtr)
```

The header specifies that `cubeByReference` receives the address of an integer variable as an argument, stores the address locally in `nPtr` and does not return a value.


The function prototype for `cubeByReference` contains `int *` in parentheses. As with other variable types, it's not necessary to include names of pointers in function prototypes. Names included for documentation purposes are ignored by the C compiler.

In the function header and in the prototype for a function that expects a single-subscripted array as an argument, the pointer notation in the parameter list of function `cubeByReference` may be used. The compiler does not differentiate between a function that receives a pointer and a function that receives a single-subscripted array. This, of course, means that the function must “know” when it's receiving an array or simply a single variable for which it is to perform call by reference. When the compiler encounters


Step 1: Before `main` calls `cubeByValue`:




Step 2: After `cubeByValue` receives the call:




Step 3: After `cubeByValue` cubes parameter `n` and before `cubeByValue` returns to `main`:



Step 4: After `cubeByValue` returns to `main` and before assigning the result to `number`:




Step 5: After `main` completes the assignment to `number`:




**Fig. 7.8** | Analysis of a typical call-by-value.

a function parameter for a single-subscripted array of the form `int b[]`, the compiler converts the parameter to the pointer notation `int *b`. The two forms are interchangeable.


Step 1: Before main calls cubeByReference:



Step 2: After cubeByReference receives the call and before \*nPtr is cubed:



Step 3: After \*nPtr is cubed and before program control returns to main:



**Fig. 7.9** | Analysis of a typical call-by-reference with a pointer argument.



### Error-Prevention Tip 7.2

Use call-by-value to pass arguments to a function unless the caller explicitly requires the called function to modify the value of the argument variable in the caller's environment. This prevents accidental modification of the caller's arguments and is another example of the principle of least privilege.

## 7.5 Using the const Qualifier with Pointers

The **const** qualifier enables you to inform the compiler that the value of a particular variable should not be modified. The const qualifier did not exist in early versions of C; it was added to the language by the ANSI C committee.



### Software Engineering Observation 7.1

The const qualifier can be used to enforce the principle of least privilege. Using the principle of least privilege to properly design software reduces debugging time and improper side effects, making a program easier to modify and maintain.



### Portability Tip 7.1

Although const is well defined in Standard C, some compilers do not enforce it.



Over the years, a large base of legacy code was written in early versions of C that did not use `const` because it was not available. For this reason, there are significant opportunities for improvement in the reengineering of old C code.

Six possibilities exist for using (or not using) `const` with function parameters—two with call-by-value parameter passing and four with call-by-reference parameter passing. How do you choose one of the six possibilities? Let the **principle of least privilege** be your guide. Always award a function enough access to the data in its parameters to accomplish its specified task, but no more.

In Chapter 5, we explained that all calls in C are call-by-value—a copy of the argument in the function call is made and passed to the function. If the copy is modified in the function, the original value in the caller does not change. In many cases, a value passed to a function is modified so the function can accomplish its task. However, in some instances, the value should not be altered in the called function, even though it manipulates only a copy of the original value.

Consider a function that takes a single-subscripted array and its size as arguments and prints the array. Such a function should loop through the array and output each array element individually. The size of the array is used in the function body to determine the high subscript of the array, so the loop can terminate when the printing is completed. Neither the size of the array nor its contents should change in the function body.



#### Error-Prevention Tip 7.3

*If a variable does not (or should not) change in the body of a function to which it's passed, the variable should be declared `const` to ensure that it's not accidentally modified.*

If an attempt is made to modify a value that is declared `const`, the compiler catches it and issues either a warning or an error, depending on the particular compiler.



#### Software Engineering Observation 7.2

*Only one value in a calling function can be altered when using call-by-value. That value must be assigned from the return value of the function to a variable in the caller. To modify multiple variables from a calling function in a called function, use call-by-reference.*



#### Error-Prevention Tip 7.4

*Before using a function, check its function prototype to determine if the function is able to modify the values passed to it.*



#### Common Programming Error 7.4

*Being unaware that a function is expecting pointers as arguments for call-by-reference and passing arguments call-by-value. Some compilers take the values assuming they're pointers and dereference the values as pointers. At runtime, memory-access violations or segmentation faults are often generated. Other compilers catch the mismatch in types between arguments and parameters and generate error messages.*

There are four ways to pass a pointer to a function: a **non-constant pointer to non-constant data**, a **constant pointer to nonconstant data**, a **non-constant pointer to constant data**, and a **constant pointer to constant data**. Each of the four combinations provides different access privileges. These are discussed in the next several examples.

*Converting a String to Uppercase Using a Non-Constant Pointer to Non-Constant Data*

The highest level of data access is granted by a non-constant pointer to non-constant data. In this case, the data can be modified through the dereferenced pointer, and the pointer can be modified to point to other data items. A declaration for a non-constant pointer to non-constant data does not include `const`. Such a pointer might be used to receive a string as an argument to a function that uses [pointer arithmetic](#) to process (and possibly modify) each character in the string. Function `convertToUpper` of Fig. 7.10 declares its parameter, a non-constant pointer to non-constant data called `sPtr` (`char *sPtr`), in line 21. The function processes the array `string` (pointed to by `sPtr`) one character at a time using pointer arithmetic. C standard library function `islower` (called in line 25) tests the character contents of the address pointed to by `sPtr`. If a character is in the range `a` to `z`, `islower` returns true and C standard library function `toupper` (line 26) is called to convert the character to its corresponding uppercase letter; otherwise, `islower` returns false and the next character in the string is processed. Line 29 moves the pointer to the next character in the string. Pointer arithmetic will be discussed in more detail in Section 7.8.

---

```

1 /* Fig. 7.10: fig07_10.c
2 Converting a string to uppercase using a
3 non-constant pointer to non-constant data */
4
5 #include <stdio.h>
6 #include <ctype.h>
7
8 void convertToUpper(char *sPtr); /* prototype */
9
10 int main(void)
11 {
12 char string[] = "characters and $32.98"; /* initialize char array */
13
14 printf("The string before conversion is: %s", string);
15 convertToUpper(string);
16 printf("\nThe string after conversion is: %s\n", string);
17 return 0; /* indicates successful termination */
18 } /* end main */
19
20 /* convert string to uppercase letters */
21 void convertToUpper(char *sPtr)
22 {
23 while (*sPtr != '\0') { /* current character is not '\0' */
24
25 if (islower(*sPtr)) { /* if character is lowercase, */
26 *sPtr = toupper(*sPtr); /* convert to uppercase */
27 } /* end if */
28
29 ++sPtr; /* move sPtr to the next character */
30 } /* end while */
31 } /* end function convertToUpper */

```

---

**Fig. 7.10** | Converting a string to uppercase using a non-constant pointer to non-constant data.  
(Part I of 2.)

The string before conversion is: characters and \$32.98  
 The string after conversion is: CHARACTERS AND \$32.98

**Fig. 7.10** | Converting a string to uppercase using a non-constant pointer to non-constant data.  
 (Part 2 of 2.)

*Printing a String One Character at a Time Using a Non-Constant Pointer to Constant Data*

A non-constant pointer to constant data can be modified to point to any data item of the appropriate type, but the data to which it points cannot be modified. Such a pointer might be used to receive an array argument to a function that will process each element without modifying the data. For example, function `printCharacters` (Fig. 7.11) declares parameter `sPtr` to be of type `const char *` (line 22). The declaration is read from right to left as “`sPtr` is a pointer to a character constant.” The function uses a `for` statement to output each character in the string until the null character is encountered. After each character is printed, pointer `sPtr` is incremented to point to the next character in the string.

```

1 /* Fig. 7.11: fig07_11.c
2 Printing a string one character at a time using
3 a non-constant pointer to constant data */
4
5 #include <stdio.h>
6
7 void printCharacters(const char *sPtr);
8
9 int main(void)
10 {
11 /* initialize char array */
12 char string[] = "print characters of a string";
13
14 printf("The string is:\n");
15 printCharacters(string);
16 printf("\n");
17 return 0; /* indicates successful termination */
18 } /* end main */
19
20 /* sPtr cannot modify the character to which it points,
21 i.e., sPtr is a "read-only" pointer */
22 void printCharacters(const char *sPtr)
23 {
24 /* loop through entire string */
25 for (; *sPtr != '\0'; sPtr++) { /* no initialization */
26 printf("%c", *sPtr);
27 } /* end for */
28 } /* end function printCharacters */

```

The string is:  
 print characters of a string

**Fig. 7.11** | Printing a string one character at a time using a non-constant pointer to constant data.

Figure 7.12 illustrates the attempt to compile a function that receives a non-constant pointer (xPtr) to constant data. This function attempts to modify the data pointed to by xPtr in line 20—which results in a compilation error. [Note: The actual error message you see will be compiler specific.]

```

1 /* Fig. 7.12: fig07_12.c
2 Attempting to modify data through a
3 non-constant pointer to constant data. */
4 #include <stdio.h>
5 void f(const int *xPtr); /* prototype */
6
7
8 int main(void)
9 {
10 int y; /* define y */
11
12 f(&y); /* f attempts illegal modification */
13 return 0; /* indicates successful termination */
14 } /* end main */
15
16 /* xPtr cannot be used to modify the
17 value of the variable to which it points */
18 void f(const int *xPtr)
19 {
20 *xPtr = 100; /* error: cannot modify a const object */
21 } /* end function f */

```

```

Compiling...
FIG07_12.c
c:\examples\ch07\fig07_12.c(22) : error C2166: l-value specifies const object
Error executing cl.exe.

FIG07_12.exe - 1 error(s), 0 warning(s)

```

**Fig. 7.12** | Attempting to modify data through a non-constant pointer to constant data.

As we know, arrays are aggregate data types that store related data items of the same type under one name. In Chapter 10, we'll discuss another form of aggregate data type called a **structure** (sometimes called a **record** in other languages). A structure is capable of storing related data items of different data types under one name (e.g., storing information about each employee of a company). When a function is called with an array as an argument, the array is automatically passed to the function by reference. However, structures are always passed by value—a copy of the entire structure is passed. This requires the execution-time overhead of making a copy of each data item in the structure and storing it on the computer's function call stack. When structure data must be passed to a function, we can use pointers to constant data to get the performance of call-by-reference and the protection of call-by-value. When a pointer to a structure is passed, only a copy of the address at which the structure is stored must be made. On a machine with 4-byte addresses, a copy of 4 bytes of memory is made rather than a copy of possibly hundreds or thousands of bytes of the structure.

**Performance Tip 7.1**

*Pass large objects such as structures using pointers to constant data to obtain the performance benefits of call-by-reference and the security of call-by-value.*

Using pointers to constant data in this manner is an example of a **time/space trade-off**. If memory is low and execution efficiency is a concern, use pointers. If memory is in abundance and efficiency is not a major concern, pass data by value to enforce the principle of least privilege. Remember that some systems do not enforce `const` well, so call-by-value is still the best way to prevent data from being modified.

***Attempting to Modify a Constant Pointer to Non-Constant Data***

A constant pointer to non-constant data always points to the same memory location, and the data at that location can be modified through the pointer. This is the default for an array name. An array name is a constant pointer to the beginning of the array. All data in the array can be accessed and changed by using the array name and array subscripting. A constant pointer to non-constant data can be used to receive an array as an argument to a function that accesses array elements using only array subscript notation. Pointers that are declared `const` must be initialized when they're defined (if the pointer is a function parameter, it's initialized with a pointer that is passed to the function). Figure 7.13 attempts to modify a constant pointer. Pointer `ptr` is defined in line 12 to be of type `int * const`. The definition is read from right to left as “`ptr` is a constant pointer to an integer.” The pointer is initialized (line 12) with the address of integer variable `x`. The program attempts to assign the address of `y` to `ptr` (line 15), but the compiler generates an error message.

```

1 /* Fig. 7.13: fig07_13.c
2 Attempting to modify a constant pointer to non-constant data */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int x; /* define x */
8 int y; /* define y */
9
10 /* ptr is a constant pointer to an integer that can be modified
11 through ptr, but ptr always points to the same memory location */
12 int * const ptr = &x;
13
14 *ptr = 7; /* allowed: *ptr is not const */
15 ptr = &y; /* error: ptr is const; cannot assign new address */
16 return 0; /* indicates successful termination */
17 } /* end main */

```

Compiling...

FIG07\_13.c

c:\examples\ch07\FIG07\_13.c(15) : error C2166: l-value specifies const object  
Error executing cl.exe.

FIG07\_13.exe - 1 error(s), 0 warning(s)

**Fig. 7.13** | Attempting to modify a constant pointer to non-constant data.

*Attempting to Modify a Constant Pointer to Constant Data*

The least access privilege is granted by a constant pointer to constant data. Such a pointer always points to the same memory location, and the data at that memory location cannot be modified. This is how an array should be passed to a function that only looks at the array using array subscript notation and does not modify the array. Figure 7.14 defines pointer variable `ptr` (line 13) to be of type `const int *const`, which is read from right to left as “`ptr` is a constant pointer to an integer constant.” The figure shows the error messages generated when an attempt is made to modify the data to which `ptr` points (line 16) and when an attempt is made to modify the address stored in the pointer variable (line 17).

---

```

1 /* Fig. 7.14: fig07_14.c
2 Attempting to modify a constant pointer to constant data. */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int x = 5; /* initialize x */
8 int y; /* define y */
9
10 /* ptr is a constant pointer to a constant integer. ptr always
11 points to the same location; the integer at that location
12 cannot be modified */
13 const int *const ptr = &x;
14
15 printf("%d\n", *ptr);
16 *ptr = 7; /* error: *ptr is const; cannot assign new value */
17 ptr = &y; /* error: ptr is const; cannot assign new address */
18 return 0; /* indicates successful termination */
19 } /* end main */

```

Compiling...

FIG07\_14.c

c:\examples\ch07\FIG07\_14.c(17) : error C2166: l-value specifies const object

c:\examples\ch07\FIG07\_14.c(18) : error C2166: l-value specifies const object

Error executing cl.exe.

FIG07\_12.exe - 2 error(s), 0 warning(s)

**Fig. 7.14** | Attempting to modify a constant pointer to constant data.

## 7.6 Bubble Sort Using Call-by-Reference

Let's improve the bubble sort program of Fig. 6.15 to use two functions—`bubbleSort` and `swap`. Function `bubbleSort` sorts the array. It calls function `swap` (line 51) to exchange the array elements `array[j]` and `array[j + 1]` (see Fig. ). Remember that C enforces information hiding between functions, so `swap` does not have access to individual array elements in `bubbleSort`. Because `bubbleSort` *wants* `swap` to have access to the array elements to be swapped, `bubbleSort` passes each of these elements call-by-reference to `swap`—the address of each array element is passed explicitly. Although entire arrays are automatically passed by reference, individual array elements are scalars and are ordinarily passed by val-

ue. Therefore, bubbleSort uses the address operator (&) on each of the array elements in the swap call (line 51) to effect call-by-reference as follows

```
swap(&array[j], &array[j + 1]);
```

Function swap receives &array[j] in pointer variable element1Ptr (line 59). Even though swap—because of information hiding—is not allowed to know the name array[j], swap may use \*element1Ptr as a synonym for array[j]—when swap references \*element1Ptr, it's actually referencing array[j] in bubbleSort. Similarly, when swap references \*element2Ptr, it's actually referencing array[j + 1] in bubbleSort. Even though swap is not allowed to say

```
hold = array[j];
array[j] = array[j + 1];
array[j + 1] = hold;
```

precisely the same effect is achieved by lines 61 through 63

```
int hold = *element1Ptr;
*element1Ptr = *element2Ptr;
*element2Ptr = hold;
```

---

```
1 /* Fig. 7.15: fig07_15.c
2 This program puts values into an array, sorts the values into
3 ascending order, and prints the resulting array. */
4 #include <stdio.h>
5 #define SIZE 10
6
7 void bubbleSort(int * const array, const int size); /* prototype */
8
9 int main(void)
10 {
11 /* initialize array a */
12 int a[SIZE] = { 2, 6, 4, 8, 10, 12, 89, 68, 45, 37 };
13
14 int i; /* counter */
15
16 printf("Data items in original order\n");
17
18 /* loop through array a */
19 for (i = 0; i < SIZE; i++) {
20 printf("%4d", a[i]);
21 } /* end for */
22
23 bubbleSort(a, SIZE); /* sort the array */
24
25 printf("\nData items in ascending order\n");
26
27 /* loop through array a */
28 for (i = 0; i < SIZE; i++) {
29 printf("%4d", a[i]);
30 } /* end for */
31
```

---

**Fig. 7.15** | Bubble sort with call-by-reference. (Part I of 2.)

```

32 printf("\n");
33 return 0; /* indicates successful termination */
34 } /* end main */
35
36 /* sort an array of integers using bubble sort algorithm */
37 void bubbleSort(int * const array, const int size)
38 {
39 void swap(int *element1Ptr, int *element2Ptr); /* prototype */
40 int pass; /* pass counter */
41 int j; /* comparison counter */
42
43 /* loop to control passes */
44 for (pass = 0; pass < size - 1; pass++) {
45
46 /* loop to control comparisons during each pass */
47 for (j = 0; j < size - 1; j++) {
48
49 /* swap adjacent elements if they are out of order */
50 if (array[j] > array[j + 1]) {
51 swap(&array[j], &array[j + 1]);
52 } /* end if */
53 } /* end inner for */
54 } /* end outer for */
55 } /* end function bubbleSort */
56
57 /* swap values at memory locations to which element1Ptr and
58 element2Ptr point */
59 void swap(int *element1Ptr, int *element2Ptr)
60 {
61 int hold = *element1Ptr;
62 *element1Ptr = *element2Ptr;
63 *element2Ptr = hold;
64 } /* end function swap */

```

|                               |   |   |   |   |    |    |    |    |    |    |
|-------------------------------|---|---|---|---|----|----|----|----|----|----|
| Data items in original order  | 2 | 6 | 4 | 8 | 10 | 12 | 89 | 68 | 45 | 37 |
| Data items in ascending order | 2 | 4 | 6 | 8 | 10 | 12 | 37 | 45 | 68 | 89 |

**Fig. 7.15** | Bubble sort with call-by-reference. (Part 2 of 2.)

Several features of function `bubbleSort` should be noted. The function header (line 37) declares `array` as `int * const array` rather than `int array[]` to indicate that `bubbleSort` receives a single-subscripted array as an argument (again, these notations are interchangeable). Parameter `size` is declared `const` to enforce the principle of least privilege. Although parameter `size` receives a copy of a value in `main`, and modifying the copy cannot change the value in `main`, `bubbleSort` does not need to alter `size` to accomplish its task. The size of the array remains fixed during the execution of function `bubbleSort`. Therefore, `size` is declared `const` to ensure that it's not modified. If the size of the array is modified during the sorting process, the sorting algorithm might not run correctly.

The prototype for function `swap` (line 39) is included in the body of function `bubbleSort` because `bubbleSort` is the only function that calls `swap`. Placing the prototype in



`bubbleSort` restricts proper calls of `swap` to those made from `bubbleSort`. Other functions that attempt to call `swap` do not have access to a proper function prototype, so the compiler generates one automatically. This normally results in a prototype that does not match the function header (and generates a compilation warning or error) because the compiler assumes `int` for the return type and the parameter types.



### Software Engineering Observation 7.3

*Placing function prototypes in the definitions of other functions enforces the principle of least privilege by restricting proper function calls to the functions in which the prototypes appear.*

Function `bubbleSort` receives the size of the array as a parameter (line 37). The function must know the size of the array to sort the array. When an array is passed to a function, the memory address of the first element of the array is received by the function. The address, of course, does not convey the number of elements in the array. Therefore, you must pass to the function the array size. [Note: Another common practice is to pass a pointer to the beginning of the array and a pointer to the location just beyond the end of the array. The difference of the two pointers is the length of the array and the resulting code is simpler.]

In the program, the size of the array is explicitly passed to function `bubbleSort`. There are two main benefits to this approach—software reusability and proper software engineering. By defining the function to receive the array size as an argument, we enable the function to be used by any program that sorts single-subscripted integer arrays of any size.



### Software Engineering Observation 7.4

*When passing an array to a function, also pass the size of the array. This helps make the function reusable in many programs.*

We could have stored the array's size in a global variable that is accessible to the entire program. This would be more efficient, because a copy of the size is not made to pass to the function. However, other programs that require an integer array-sorting capability may not have the same global variable, so the function cannot be used in those programs.



### Software Engineering Observation 7.5

*Global variables usually violate the principle of least privilege and can lead to poor software engineering. Global variables should be used only to represent truly shared resources, such as the time of day.*

The size of the array could have been programmed directly into the function. This restricts the use of the function to an array of a specific size and significantly reduces its reusability. Only programs processing single-subscripted integer arrays of the specific size coded into the function can use the function.

## 7.7 sizeof Operator

C provides the special unary operator `sizeof` to determine the size in bytes of an array (or any other data type) during program compilation. When applied to the name of an array as in Fig. 7.16 (line 14), the `sizeof` operator returns the total number of bytes in the array

as an integer. Variables of type `float` are normally stored in 4 bytes of memory, and array is defined to have 20 elements. Therefore, there are a total of 80 bytes in array.



### Performance Tip 7.2

*sizeof is a compile-time operator, so it does not incur any execution-time overhead.*

```

1 /* Fig. 7.16: fig07_16.c
2 Applying sizeof to an array name returns
3 the number of bytes in the array. */
4 #include <stdio.h>
5
6 size_t getSize(float *ptr); /* prototype */
7
8 int main(void)
9 {
10 float array[20]; /* create array */
11
12 printf("The number of bytes in the array is %d"
13 "\nThe number of bytes returned by getSize is %d\n",
14 sizeof(array), getSize(array));
15 return 0; /* indicates successful termination */
16 } /* end main */
17
18 /* return size of ptr */
19 size_t getSize(float *ptr)
20 {
21 return sizeof(ptr);
22 } /* end function getSize */

```

```

The number of bytes in the array is 80
The number of bytes returned by getSize is 4

```

**Fig. 7.16** | Applying `sizeof` to an array name returns the number of bytes in the array.

The number of elements in an array also can be determined with `sizeof`. For example, consider the following array definition:

```
double real[22];
```

Variables of type `double` normally are stored in 8 bytes of memory. Thus, array `real` contains a total of 176 bytes. To determine the number of elements in the array, the following expression can be used:

```
sizeof(real) / sizeof(real[0])
```

The expression determines the number of bytes in array `real` and divides that value by the number of bytes used in memory to store the first element of array `real` (a `double` value).

Function `getSize` returns type `size_t`. Type `size_t` is a type defined by the C standard as the integral type (unsigned or unsigned long) of the value returned by operator `sizeof`. Type `size_t` is defined in header `<stddef.h>` (which is included by several headers, such as `<stdio.h>`). [Note: If you attempt to compile Fig. 7.16 and receive errors,

simply include `<stddef.h>` in your program.] Figure 7.17 calculates the number of bytes used to store each of the standard data types. The results could be different between computers.



### Portability Tip 7.2

*The number of bytes used to store a particular data type may vary between systems. When writing programs that depend on data type sizes and that will run on several computer systems, use `sizeof` to determine the number of bytes used to store the data types.*

```

1 /* Fig. 7.17: fig07_17.c
2 Demonstrating the sizeof operator */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 char c;
8 short s;
9 int i;
10 long l;
11 float f;
12 double d;
13 long double ld;
14 int array[20]; /* create array of 20 int elements */
15 int *ptr = array; /* create pointer to array */
16
17 printf(" sizeof c = %d\\tsizeof(char) = %d"
18 "\\n sizeof s = %d\\tsizeof(short) = %d"
19 "\\n sizeof i = %d\\tsizeof(int) = %d"
20 "\\n sizeof l = %d\\tsizeof(long) = %d"
21 "\\n sizeof f = %d\\tsizeof(float) = %d"
22 "\\n sizeof d = %d\\tsizeof(double) = %d"
23 "\\n sizeof ld = %d\\tsizeof(long double) = %d"
24 "\\n sizeof array = %d"
25 "\\n sizeof ptr = %d\\n",
26 sizeof c, sizeof(char), sizeof s, sizeof(short), sizeof i,
27 sizeof(int), sizeof l, sizeof(long), sizeof f,
28 sizeof(float), sizeof d, sizeof(double), sizeof ld,
29 sizeof(long double), sizeof array, sizeof ptr);
30 return 0; /* indicates successful termination */
31 } /* end main */

```

|                   |                         |
|-------------------|-------------------------|
| sizeof c = 1      | sizeof(char) = 1        |
| sizeof s = 2      | sizeof(short) = 2       |
| sizeof i = 4      | sizeof(int) = 4         |
| sizeof l = 4      | sizeof(long) = 4        |
| sizeof f = 4      | sizeof(float) = 4       |
| sizeof d = 8      | sizeof(double) = 8      |
| sizeof ld = 8     | sizeof(long double) = 8 |
| sizeof array = 80 |                         |
| sizeof ptr = 4    |                         |

**Fig. 7.17** | Using operator `sizeof` to determine standard data type sizes.

Operator `sizeof` can be applied to any variable name, type or value (including the value of an expression). When applied to a variable name (that is not an array name) or a constant, the number of bytes used to store the specific type of variable or constant is returned. The parentheses used with `sizeof` are required if a type name with two words is supplied as its operand (such as `long double` or `unsigned short`). Omitting the parentheses in this case results in a syntax error. The parentheses are not required if a variable name or a one-word type name is supplied as its operand, but they can still be included without causing an error.

## 7.8 Pointer Expressions and Pointer Arithmetic

Pointers are valid operands in arithmetic expressions, assignment expressions and comparison expressions. However, not all the operators normally used in these expressions are valid in conjunction with pointer variables. This section describes the operators that can have pointers as operands, and how these operators are used.

A limited set of arithmetic operations may be performed on pointers. A pointer may be incremented (`++`) or decremented (`--`), an integer may be added to a pointer (`+` or `+=`), an integer may be subtracted from a pointer (`-` or `-=`) and one pointer may be subtracted from another.


Assume that array `int v[5]` has been defined and its first element is at location 3000 in memory. Assume pointer `vPtr` has been initialized to point to `v[0]`—i.e., the value of `vPtr` is 3000. Figure 7.18 illustrates this situation for a machine with 4-byte integers. Variable `vPtr` can be initialized to point to array `v` with either of the statements

```
vPtr = v;
vPtr = &v[0];
```



### Portability Tip 7.3

*Most computers today have 2-byte or 4-byte integers. Some of the newer machines use 8-byte integers. Because the results of pointer arithmetic depend on the size of the objects a pointer points to, pointer arithmetic is machine dependent.*




**Fig. 7.18** | Array `v` and a pointer variable `vPtr` that points to `v`.

In conventional arithmetic,  $3000 + 2$  yields the value 3002. This is normally not the case with pointer arithmetic. When an integer is added to or subtracted from a pointer, the pointer is not incremented or decremented simply by that integer, but by that integer

times the size of the object to which the pointer refers. The number of bytes depends on the object's data type. For example, the statement

```
vPtr += 2;
```

would produce 3008 ( $3000 + 2 * 4$ ), assuming an integer is stored in 4 bytes of memory. In the array `v`, `vPtr` would now point to `v[2]` (Fig. 7.19). If an integer is stored in 2 bytes of memory, then the preceding calculation would result in memory location 3004 ( $3000 + 2 * 2$ ). If the array were of a different data type, the preceding statement would increment the pointer by twice the number of bytes that it takes to store an object of that data type. When performing pointer arithmetic on a character array, the results will be consistent with regular arithmetic, because each character is 1 byte long.



**Fig. 7.19** | The pointer `vPtr` after pointer arithmetic.

If `vPtr` had been incremented to 3016, which points to `v[4]`, the statement

```
vPtr -= 4;
```

would set `vPtr` back to 3000—the beginning of the array. If a pointer is being incremented or decremented by one, the increment (`++`) and decrement (`--`) operators can be used. Either of the statements

```
++vPtr;
vPtr++;
```

increments the pointer to point to the next location in the array. Either of the statements

```
--vPtr;
vPtr--;
```

decrements the pointer to point to the previous element of the array.

Pointer variables may be subtracted from one another. For example, if `vPtr` contains the location 3000, and `v2Ptr` contains the address 3008, the statement

```
x = v2Ptr - vPtr;
```

would assign to `x` the number of array elements from `vPtr` to `v2Ptr`, in this case 2 (not 8). Pointer arithmetic is meaningless unless performed on an array. We cannot assume that two variables of the same type are stored contiguously in memory unless they're adjacent elements of an array.



### Common Programming Error 7.5

*Using pointer arithmetic on a pointer that does not refer to an element in an array.*



### Common Programming Error 7.6

*Subtracting or comparing two pointers that do not refer to elements in the same array.*



### Common Programming Error 7.7

*Running off either end of an array when using pointer arithmetic.*

A pointer can be assigned to another pointer if both have the same type. The exception to this rule is the **pointer to void** (i.e., **void \***), which is a generic pointer that can represent any pointer type. All pointer types can be assigned a pointer to **void**, and a pointer to **void** can be assigned a pointer of any type. In both cases, a cast operation is not required.

A pointer to **void** cannot be dereferenced. Consider this: The compiler knows that a pointer to **int** refers to 4 bytes of memory on a machine with 4-byte integers, but a pointer to **void** simply contains a memory location for an unknown data type—the precise number of bytes to which the pointer refers is not known by the compiler. The compiler must know the data type to determine the number of bytes to be dereferenced for a particular pointer.



### Common Programming Error 7.8

*Assigning a pointer of one type to a pointer of another type if neither is of type **void \*** is a syntax error.*



### Common Programming Error 7.9

*Dereferencing a **void \*** pointer is a syntax error.*

Pointers can be compared using equality and relational operators, but such comparisons are meaningless unless the pointers point to elements of the same array. Pointer comparisons compare the addresses stored in the pointers. A comparison of two pointers pointing to elements in the same array could show, for example, that one pointer points to a higher-numbered element of the array than the other pointer does. A common use of pointer comparison is determining whether a pointer is **NULL**.

## 7.9 Relationship between Pointers and Arrays

Arrays and pointers are intimately related in C and often may be used interchangeably. An array name can be thought of as a constant pointer. Pointers can be used to do any operation involving array subscripting.

Assume that integer array **b[5]** and integer pointer variable **bPtr** have been defined. Since the array name (without a subscript) is a pointer to the first element of the array, we can set **bPtr** equal to the address of the first element in array **b** with the statement

```
bPtr = b;
```

This statement is equivalent to taking the address of the array's first element as follows:

```
bPtr = &b[0];
```

Array element `b[3]` can alternatively be referenced with the pointer expression

```
*(bPtr + 3)
```

The 3 in the above expression is the **offset** to the pointer. When the pointer points to the beginning of an array, the offset indicates which element of the array should be referenced, and the offset value is identical to the array subscript. The preceding notation is referred to as **pointer/offset notation**. The parentheses are necessary because the precedence of `*` is higher than the precedence of `+`. Without the parentheses, the above expression would add 3 to the value of the expression `*bPtr` (i.e., 3 would be added to `b[0]`, assuming `bPtr` points to the beginning of the array). Just as the array element can be referenced with a pointer expression, the address

```
&b[3]
```

can be written with the pointer expression

```
bPtr + 3
```

The array itself can be treated as a pointer and used in pointer arithmetic. For example, the expression

```
*(b + 3)
```

also refers to the array element `b[3]`. In general, all subscripted array expressions can be written with a pointer and an offset. In this case, pointer/offset notation was used with the name of the array as a pointer. The preceding statement does not modify the array name in any way; `b` still points to the first element in the array.

Pointers can be subscripted exactly as arrays can. For example, if `bPtr` has the value `b`, the expression

```
bPtr[1]
```

refers to the array element `b[1]`. This is referred to as **pointer/subscript notation**.

Remember that an array name is essentially a constant pointer; it always points to the beginning of the array. Thus, the expression

```
b += 3
```

is invalid because it attempts to modify the value of the array name with pointer arithmetic.



### Common Programming Error 7.10

*Attempting to modify an array name with pointer arithmetic is a syntax error.*

Figure 7.20 uses the four methods we have discussed for referring to array elements—array subscripting, pointer/offset with the array name as a pointer, **pointer subscripting**, and pointer/offset with a pointer—to print the four elements of the integer array `b`.

```

1 /* Fig. 7.20: fig07_20.cpp
2 Using subscripting and pointer notations with arrays */
3
4 #include <stdio.h>
5
6 int main(void)
7 {
8 int b[] = { 10, 20, 30, 40 }; /* initialize array b */
9 int *bPtr = b; /* set bPtr to point to array b */
10 int i; /* counter */
11 int offset; /* counter */
12
13 /* output array b using array subscript notation */
14 printf("Array b printed with:\nArray subscript notation\n");
15
16 /* loop through array b */
17 for (i = 0; i < 4; i++) {
18 printf("b[%d] = %d\n", i, b[i]);
19 } /* end for */
20
21 /* output array b using array name and pointer/offset notation */
22 printf("\nPointer/offset notation where\n"
23 "the pointer is the array name\n");
24
25 /* loop through array b */
26 for (offset = 0; offset < 4; offset++) {
27 printf("*(b + %d) = %d\n", offset, *(b + offset));
28 } /* end for */
29
30 /* output array b using bPtr and array subscript notation */
31 printf("\nPointer subscript notation\n");
32
33 /* loop through array b */
34 for (i = 0; i < 4; i++) {
35 printf("bPtr[%d] = %d\n", i, bPtr[i]);
36 } /* end for */
37
38 /* output array b using bPtr and pointer/offset notation */
39 printf("\nPointer/offset notation\n");
40
41 /* loop through array b */
42 for (offset = 0; offset < 4; offset++) {
43 printf("*(bPtr + %d) = %d\n", offset, *(bPtr + offset));
44 } /* end for */
45
46 return 0; /* indicates successful termination */
47 } /* end main */

```

Array b printed with:  
 Array subscript notation  
 b[ 0 ] = 10  
 b[ 1 ] = 20

**Fig. 7.20** | Using four methods of referencing array elements. (Part I of 2.)



```

b[2] = 30
b[3] = 40

Pointer/offset notation where
the pointer is the array name
*(b + 0) = 10
*(b + 1) = 20
*(b + 2) = 30
*(b + 3) = 40

Pointer subscript notation
bPtr[0] = 10
bPtr[1] = 20
bPtr[2] = 30
bPtr[3] = 40

Pointer/offset notation
*(bPtr + 0) = 10
*(bPtr + 1) = 20
*(bPtr + 2) = 30
*(bPtr + 3) = 40

```

**Fig. 7.20** | Using four methods of referencing array elements. (Part 2 of 2.)

To further illustrate the interchangeability of arrays and pointers, let's look at the two string-copying functions—`copy1` and `copy2`—in the program of Fig. 7.21. Both functions copy a string (possibly a character array) into a character array. After a comparison of the function prototypes for `copy1` and `copy2`, the functions appear identical. They accomplish the same task; however, they're implemented differently.

```

1 /* Fig. 7.21: fig07_21.c
2 Copying a string using array notation and pointer notation. */
3 #include <stdio.h>
4
5 void copy1(char * const s1, const char * const s2); /* prototype */
6 void copy2(char *s1, const char *s2); /* prototype */
7
8 int main(void)
9 {
10 char string1[10]; /* create array string1 */
11 char *string2 = "Hello"; /* create a pointer to a string */
12 char string3[10]; /* create array string3 */
13 char string4[] = "Good Bye"; /* create a pointer to a string */
14
15 copy1(string1, string2);
16 printf("string1 = %s\n", string1);
17
18 copy2(string3, string4);
19 printf("string3 = %s\n", string3);
20 return 0; /* indicates successful termination */
21 } /* end main */

```

**Fig. 7.21** | Copying a string using array notation and pointer notation. (Part 1 of 2.)

```

22
23 /* copy s2 to s1 using array notation */
24 void copy1(char * const s1, const char * const s2)
25 {
26 int i; /* counter */
27
28 /* loop through strings */
29 for (i = 0; (s1[i] = s2[i]) != '\0'; i++) {
30 ; /* do nothing in body */
31 } /* end for */
32 } /* end function copy1 */
33
34 /* copy s2 to s1 using pointer notation */
35 void copy2(char *s1, const char *s2)
36 {
37 /* loop through strings */
38 for (; (*s1 = *s2) != '\0'; s1++, s2++) {
39 ; /* do nothing in body */
40 } /* end for */
41 } /* end function copy2 */

```

```

string1 = Hello
string3 = Good Bye

```

**Fig. 7.21** | Copying a string using array notation and pointer notation. (Part 2 of 2.)

Function `copy1` uses array subscript notation to copy the string in `s2` to the character array `s1`. The function defines counter variable `i` as the array subscript. The `for` statement header (line 29) performs the entire copy operation—its body is the empty statement. The header specifies that `i` is initialized to zero and incremented by one on each iteration of the loop. The expression `s1[i] = s2[i]` copies one character from `s2` to `s1`. When the null character is encountered in `s2`, it's assigned to `s1`, and the value of the assignment becomes the value assigned to the left operand (`s1`). The loop terminates because the integer value of the null character is zero (false).

Function `copy2` uses pointers and pointer arithmetic to copy the string in `s2` to the character array `s1`. Again, the `for` statement header (line 38) performs the entire copy operation. The header does not include any variable initialization. As in function `copy1`, the expression `(*s1 = *s2)` performs the copy operation. Pointer `s2` is dereferenced, and the resulting character is assigned to the dereferenced pointer `*s1`. After the assignment in the condition, the pointers are incremented to point to the next element of array `s1` and the next character of string `s2`, respectively. When the null character is encountered in `s2`, it's assigned to the dereferenced pointer `s1` and the loop terminates.

The first argument to both `copy1` and `copy2` must be an array large enough to hold the string in the second argument. Otherwise, an error may occur when an attempt is made to write into a memory location that is not part of the array. Also, the second parameter of each function is declared as `const char *` (a constant string). In both functions, the second argument is copied into the first argument—characters are read from it one at a time, but the characters are never modified. Therefore, the second parameter is declared to point to a constant value so that the principle of least privilege is enforced—neither


function requires the capability of modifying the second argument, so neither function is provided with that capability.

## 7.10 Arrays of Pointers

Arrays may contain pointers. A common use of an **array of pointers** is to form an **array of strings**, referred to simply as a **string array**. Each entry in the array is a string, but in C a string is essentially a pointer to its first character. So each entry in an array of strings is actually a pointer to the first character of a string. Consider the definition of string array `suit`, which might be useful in representing a deck of cards.

```
const char *suit[4] = { "Hearts", "Diamonds", "Clubs", "Spades" };
```

The `suit[4]` portion of the definition indicates an array of 4 elements. The `char *` portion of the declaration indicates that each element of array `suit` is of type “pointer to char.” Qualifier `const` indicates that the strings pointed to by each element pointer will not be modified. The four values to be placed in the array are “Hearts”, “Diamonds”, “Clubs” and “Spades”. Each is stored in memory as a null-terminated character string that is one character longer than the number of characters between quotes. The four strings are 7, 9, 6 and 7 characters long, respectively. Although it appears as though these strings are being placed in the `suit` array, only pointers are actually stored in the array (Fig. 7.22). Each pointer points to the first character of its corresponding string. Thus, even though the `suit` array is fixed in size, it provides access to character strings of any length. This flexibility is one example of C’s powerful data-structuring capabilities.



**Fig. 7.22** | Graphical representation of the `suit` array.

The suits could have been placed in a two-dimensional array, in which each row would represent a suit and each column would represent a letter from a suit name. Such a data structure would have to have a fixed number of columns per row, and that number would have to be as large as the largest string. Therefore, considerable memory could be wasted when a large number of strings were being stored with most strings shorter than the longest string. We use string arrays to represent a deck of cards in the next section.

## 7.11 Case Study: Card Shuffling and Dealing Simulation

In this section, we use random number generation to develop a card shuffling and dealing simulation program. This program can then be used to implement programs that play specific card games. To reveal some subtle performance problems, we have intentionally used suboptimal shuffling and dealing algorithms. In this chapter’s exercises and in Chapter 10, we develop more efficient algorithms.

Using the top-down, stepwise refinement approach, we develop a program that will shuffle a deck of 52 playing cards and then deal each of the 52 cards. The top-down approach is particularly useful in attacking larger, more complex problems than we have seen in the early chapters.

We use 4-by-13 double-subscripted array `deck` to represent the deck of playing cards (Fig. 7.23). The rows correspond to the suits—row 0 corresponds to hearts, row 1 to diamonds, row 2 to clubs and row 3 to spades. The columns correspond to the face values of the cards—columns 0 through 9 correspond to ace through ten respectively, and columns 10 through 12 correspond to jack, queen and king. We shall load string array `suit` with character strings representing the four suits, and string array `face` with character strings representing the thirteen face values.

|          |   | Ace | Two | Three | Four | Five | Six | Seven | Eight | Nine | Ten | Jack | Queen | King |
|----------|---|-----|-----|-------|------|------|-----|-------|-------|------|-----|------|-------|------|
|          |   | 0   | 1   | 2     | 3    | 4    | 5   | 6     | 7     | 8    | 9   | 10   | 11    | 12   |
| Hearts   | 0 |     |     |       |      |      |     |       |       |      |     |      |       |      |
| Diamonds | 1 |     |     |       |      |      |     |       |       |      |     |      |       |      |
| Clubs    | 2 |     |     |       |      |      |     |       |       |      |     |      |       |      |
| Spades   | 3 |     |     |       |      |      |     |       |       |      |     |      |       |      |

$\text{deck}[2][12]$  represents the King of Clubs  
 Clubs      King

**Fig. 7.23** | Double-subscripted array representation of a deck of cards.

This simulated deck of cards may be shuffled as follows. First the array `deck` is cleared to zeros. Then, a row (0–3) and a column (0–12) are each chosen at random. The number 1 is inserted in array element `deck[row][column]` to indicate that this card is going to be the first one dealt from the shuffled deck. This process continues with the numbers 2, 3, ..., 52 being randomly inserted in the deck array to indicate which cards are to be placed second, third, ..., and fifty-second in the shuffled deck. As the deck array begins to fill with card numbers, it's possible that a card will be selected twice—i.e., `deck[row][column]` will be nonzero when it's selected. This selection is simply ignored and other rows and columns are repeatedly chosen at random until an unselected card is found. Eventually, the numbers 1 through 52 will occupy the 52 slots of the deck array. At this point, the deck of cards is fully shuffled.

This shuffling algorithm could execute indefinitely if cards that have already been shuffled are repeatedly selected at random. This phenomenon is known as **indefinite postponement**. In the exercises, we discuss a better shuffling algorithm that eliminates the possibility of indefinite postponement.



### Performance Tip 7.3

*Sometimes an algorithm that emerges in a “natural” way can contain subtle performance problems, such as indefinite postponement. Seek algorithms that avoid indefinite postponement.*

To deal the first card, we search the array for `deck[row][column]` equal to 1. This is accomplished with a nested for statement that varies row from 0 to 3 and column from 0 to 12. What card does that element of the array correspond to? The suit array has been preloaded with the four suits, so to get the suit, we print the character string `suit[row]`. Similarly, to get the face value of the card, we print the character string `face[column]`. We also print the character string " of ". Printing this information in the proper order enables us to print each card in the form "King of Clubs", "Ace of Diamonds" and so on.

Let's proceed with the top-down, stepwise refinement process. The top is simply

*Shuffle and deal 52 cards*

Our first refinement yields:

*Initialize the suit array  
Initialize the face array  
Initialize the deck array  
Shuffle the deck  
Deal 52 cards*

"Shuffle the deck" may be expanded as follows:

*For each of the 52 cards  
Place card number in randomly selected unoccupied slot of deck*

"Deal 52 cards" may be expanded as follows:

*For each of the 52 cards  
Find card number in deck array and print face and suit of card*

Incorporating these expansions yields our complete second refinement:

*Initialize the suit array  
Initialize the face array  
Initialize the deck array  
For each of the 52 cards  
Place card number in randomly selected unoccupied slot of deck  
For each of the 52 cards  
Find card number in deck array and print face and suit of card*

"Place card number in randomly selected unoccupied slot of deck" may be expanded as:

*Choose slot of deck randomly  
While chosen slot of deck has been previously chosen  
Choose slot of deck randomly  
Place card number in chosen slot of deck*

"Find card number in deck array and print face and suit of card" may be expanded as:

*For each slot of the deck array  
If slot contains card number  
Print the face and suit of the card*

Incorporating these expansions yields our third refinement:

```

Initialize the suit array
Initialize the face array
Initialize the deck array

For each of the 52 cards
 Choose slot of deck randomly
 While slot of deck has been previously chosen
 Choose slot of deck randomly
 Place card number in chosen slot of deck

For each of the 52 cards
 For each slot of deck array
 If slot contains desired card number
 Print the face and suit of the card

```

This completes the refinement process. This program is more efficient if the shuffle and deal portions of the algorithm are combined so that each card is dealt as it's placed in the deck. We have chosen to program these operations separately because normally cards are dealt after they're shuffled (not while they're shuffled).

The card shuffling and dealing program is shown in Fig. 7.24, and a sample execution is shown in Fig. 7.25. Conversion specifier `%s` is used to print strings of characters in the calls to `printf`. The corresponding argument in the `printf` call must be a pointer to `char` (or a `char` array). The format specification `"%5s of %-8s"` (line 73) prints a character string right justified in a field of five characters followed by " of " and a character string left justified in a field of eight characters. The minus sign in `%-8s` signifies left justification.

---

```

1 /* Fig. 7.24: fig07_24.c
2 Card shuffling dealing program */
3 #include <stdio.h>
4 #include <stdlib.h>
5 #include <time.h>
6
7 /* prototypes */
8 void shuffle(int wDeck[][13]);
9 void deal(const int wDeck[][13], const char *wFace[],
10 const char *wSuit[]);
11
12 int main(void)
13 {
14 /* initialize suit array */
15 const char *suit[4] = { "Hearts", "Diamonds", "Clubs", "Spades" };
16
17 /* initialize face array */
18 const char *face[13] =
19 { "Ace", "Deuce", "Three", "Four",
20 "Five", "Six", "Seven", "Eight",
21 "Nine", "Ten", "Jack", "Queen", "King" };

```

---

**Fig. 7.24** | Card dealing program. (Part I of 3.)

```

22
23 /* initialize deck array */
24 int deck[4][13] = { 0 };
25
26 srand(time(0)); /* seed random-number generator */
27
28 shuffle(deck); /* shuffle the deck */
29 deal(deck, face, suit); /* deal the deck */
30 return 0; /* indicates successful termination */
31 } /* end main */
32
33 /* shuffle cards in deck */
34 void shuffle(int wDeck[][13])
35 {
36 int row; /* row number */
37 int column; /* column number */
38 int card; /* counter */
39
40 /* for each of the 52 cards, choose slot of deck randomly */
41 for (card = 1; card <= 52; card++) {
42
43 /* choose new random location until unoccupied slot found */
44 do {
45 row = rand() % 4;
46 column = rand() % 13;
47 } while(wDeck[row][column] != 0); /* end do...while */
48
49 /* place card number in chosen slot of deck */
50 wDeck[row][column] = card;
51 } /* end for */
52 } /* end function shuffle */
53
54 /* deal cards in deck */
55 void deal(const int wDeck[][13], const char *wFace[],
56 const char *wSuit[])
57 {
58 int card; /* card counter */
59 int row; /* row counter */
60 int column; /* column counter */
61
62 /* deal each of the 52 cards */
63 for (card = 1; card <= 52; card++) {
64 /* loop through rows of wDeck */
65
66 for (row = 0; row <= 3; row++) {
67
68 /* loop through columns of wDeck for current row */
69 for (column = 0; column <= 12; column++) {
70
71 /* if slot contains current card, display card */
72 if (wDeck[row][column] == card) {
73 printf("%5s of %-8s%c", wFace[column], wSuit[row],
74 card % 2 == 0 ? '\n' : '\t');

```

**Fig. 7.24** | Card dealing program. (Part 2 of 3.)

```

75 } /* end if */
76 } /* end for */
77 } /* end for */
78 } /* end for */
79 } /* end function deal */

```

**Fig. 7.24** | Card dealing program. (Part 3 of 3.)

|                   |                   |
|-------------------|-------------------|
| Nine of Hearts    | Five of Clubs     |
| Queen of Spades   | Three of Spades   |
| Queen of Hearts   | Ace of Clubs      |
| King of Hearts    | Six of Spades     |
| Jack of Diamonds  | Five of Spades    |
| Seven of Hearts   | King of Clubs     |
| Three of Clubs    | Eight of Hearts   |
| Three of Diamonds | Four of Diamonds  |
| Queen of Diamonds | Five of Diamonds  |
| Six of Diamonds   | Five of Hearts    |
| Ace of Spades     | Six of Hearts     |
| Nine of Diamonds  | Queen of Clubs    |
| Eight of Spades   | Nine of Clubs     |
| Deuce of Clubs    | Six of Clubs      |
| Deuce of Spades   | Jack of Clubs     |
| Four of Clubs     | Eight of Clubs    |
| Four of Spades    | Seven of Spades   |
| Seven of Diamonds | Seven of Clubs    |
| King of Spades    | Ten of Diamonds   |
| Jack of Hearts    | Ace of Hearts     |
| Jack of Spades    | Ten of Clubs      |
| Eight of Diamonds | Deuce of Diamonds |
| Ace of Diamonds   | Nine of Spades    |
| Four of Hearts    | Deuce of Hearts   |
| King of Diamonds  | Ten of Spades     |
| Three of Hearts   | Ten of Hearts     |

**Fig. 7.25** | Sample run of card dealing program.

There's a weakness in the dealing algorithm. Once a match is found, the two inner for statements continue searching the remaining elements of deck for a match. We correct this deficiency in this chapter's exercises and in a Chapter 10 case study.

## 7.12 Pointers to Functions

A **pointer to a function** contains the address of the function in memory. In Chapter 6, we saw that an array name is really the address in memory of the first element of the array. Similarly, a function name is really the starting address in memory of the code that performs the function's task. Pointers to functions can be passed to functions, returned from functions, stored in arrays and assigned to other function pointers.

To illustrate the use of pointers to functions, Fig. 7.26 presents a modified version of the bubble sort program in Fig. 7.15. The new version consists of `main` and functions `bubble`, `swap`, `ascending` and `descending`. Function `bubbleSort` receives a pointer to a function—either function `ascending` or function `descending`—as an argument, in addi-



tion to an integer array and the size of the array. The program prompts the user to choose whether the array should be sorted in ascending or in descending order. If the user enters 1, a pointer to function `ascending` is passed to function `bubble`, causing the array to be sorted into increasing order. If the user enters 2, a pointer to function `descending` is passed to function `bubble`, causing the array to be sorted into decreasing order. The output of the program is shown in Fig. 7.27.

---

```

1 /* Fig. 7.26: fig07_26.c
2 Multipurpose sorting program using function pointers */
3 #include <stdio.h>
4 #define SIZE 10
5
6 /* prototypes */
7 void bubble(int work[], const int size, int (*compare)(int a, int b));
8 int ascending(int a, int b);
9 int descending(int a, int b);
10
11 int main(void)
12 {
13 int order; /* 1 for ascending order or 2 for descending order */
14 int counter; /* counter */
15
16 /* initialize array a */
17 int a[SIZE] = { 2, 6, 4, 8, 10, 12, 89, 68, 45, 37 };
18
19 printf("Enter 1 to sort in ascending order,\n"
20 "Enter 2 to sort in descending order: ");
21 scanf("%d", &order);
22
23 printf("\nData items in original order\n");
24
25 /* output original array */
26 for (counter = 0; counter < SIZE; counter++) {
27 printf("%5d", a[counter]);
28 } /* end for */
29
30 /* sort array in ascending order; pass function ascending as an
31 argument to specify ascending sorting order */
32 if (order == 1) {
33 bubble(a, SIZE, ascending);
34 printf("\nData items in ascending order\n");
35 } /* end if */
36 else { /* pass function descending */
37 bubble(a, SIZE, descending);
38 printf("\nData items in descending order\n");
39 } /* end else */
40
41 /* output sorted array */
42 for (counter = 0; counter < SIZE; counter++) {
43 printf("%5d", a[counter]);
44 } /* end for */

```

---

**Fig. 7.26** | Multipurpose sorting program using function pointers. (Part I of 2.)

```

45 printf("\n");
46 return 0; /* indicates successful termination */
47 } /* end main */
48
49 /* multipurpose bubble sort; parameter compare is a pointer to
50 the comparison function that determines sorting order */
51 void bubble(int work[], const int size, int (*compare)(int a, int b))
52 {
53 int pass; /* pass counter */
54 int count; /* comparison counter */
55
56 void swap(int *element1Ptr, int *element2Ptr); /* prototype */
57
58 /* loop to control passes */
59 for (pass = 1; pass < size; pass++) {
60
61 /* loop to control number of comparisons per pass */
62 for (count = 0; count < size - 1; count++) {
63
64 /* if adjacent elements are out of order, swap them */
65 if ((*compare)(work[count], work[count + 1])) {
66 swap(&work[count], &work[count + 1]);
67 } /* end if */
68 } /* end for */
69 } /* end for */
70 } /* end function bubble */
71
72 /* swap values at memory locations to which element1Ptr and
73 element2Ptr point */
74 void swap(int *element1Ptr, int *element2Ptr)
75 {
76 int hold; /* temporary holding variable */
77
78 hold = *element1Ptr;
79 *element1Ptr = *element2Ptr;
80 *element2Ptr = hold;
81 } /* end function swap */
82
83 /* determine whether elements are out of order for an ascending
84 order sort */
85 int ascending(int a, int b)
86 {
87 return b < a; /* swap if b is less than a */
88 } /* end function ascending */
89
90 /* determine whether elements are out of order for a descending
91 order sort */
92 int descending(int a, int b)
93 {
94 return b > a; /* swap if b is greater than a */
95 } /* end function descending */
96

```

**Fig. 7.26** | Multipurpose sorting program using function pointers. (Part 2 of 2.)

```

Enter 1 to sort in ascending order,
Enter 2 to sort in descending order: 1

Data items in original order
 2 6 4 8 10 12 89 68 45 37
Data items in ascending order
 2 4 6 8 10 12 37 45 68 89

```

```

Enter 1 to sort in ascending order,
Enter 2 to sort in descending order: 2

Data items in original order
 2 6 4 8 10 12 89 68 45 37
Data items in descending order
89 68 45 37 12 10 8 6 4 2

```

**Fig. 7.27** | The outputs of the bubble sort program in Fig. 7.26.

The following parameter appears in the function header for `bubble` (line 52)

```
int (*compare)(int a, int b)
```

This tells `bubble` to expect a parameter (`compare`) that is a pointer to a function that receives two integer parameters and returns an integer result. Parentheses are needed around `*compare` to group `*` with `compare` to indicate that `compare` is a pointer. If we had not included the parentheses, the declaration would have been

```
int *compare(int a, int b)
```

which declares a function that receives two integers as parameters and returns a pointer to an integer.

The function prototype for `bubble` is shown in line 7. The prototype could have been written as

```
int (*)(int, int);
```

without the function-pointer name and parameter names.

The function passed to `bubble` is called in an `if` statement (line 66) as follows:

```
if ((*compare)(work[count], work[count + 1]))
```

Just as a pointer to a variable is dereferenced to access the value of the variable, a pointer to a function is dereferenced to use the function.

The call to the function could have been made without dereferencing the pointer as in

```
if (compare(work[count], work[count + 1]))
```

which uses the pointer directly as the function name. We prefer the first method of calling a function through a pointer because it explicitly illustrates that `compare` is a pointer to a function that is dereferenced to call the function. The second method of calling a function through a pointer makes it appear as though `compare` is an actual function. This may be confusing to a user of the program who would like to see the definition of function `compare` and finds that it's never defined in the file.

*Using Function Pointers to Create a Menu-Driven System*

A common use of **function pointers** is in text-based menu-driven systems. A user is prompted to select an option from a menu (possibly from 1 to 5) by typing the menu item's number. Each option is serviced by a different function. Pointers to each function are stored in an array of pointers to functions. The user's choice is used as a subscript in the array, and the pointer in the array is used to call the function.

Figure 7.28 provides a generic example of the mechanics of defining and using an array of pointers to functions. We define three functions—`function1`, `function2` and `function3`—that each take an integer argument and return nothing. We store pointers to these three functions in array `f`, which is defined in line 14.

---

```

1 /* Fig. 7.28: fig07_28.c
2 Demonstrating an array of pointers to functions */
3 #include <stdio.h>
4
5 /* prototypes */
6 void function1(int a);
7 void function2(int b);
8 void function3(int c);
9
10 int main(void)
11 {
12 /* initialize array of 3 pointers to functions that each take an
13 int argument and return void */
14 void (*f[3])(int) = { function1, function2, function3 };
15
16 int choice; /* variable to hold user's choice */
17
18 printf("Enter a number between 0 and 2, 3 to end: ");
19 scanf("%d", &choice);
20
21 /* process user's choice */
22 while (choice >= 0 && choice < 3) {
23
24 /* invoke function at location choice in array f and pass
25 choice as an argument */
26 (*f[choice])(choice);
27
28 printf("Enter a number between 0 and 2, 3 to end: ");
29 scanf("%d", &choice);
30 } /* end while */
31
32 printf("Program execution completed.\n");
33 return 0; /* indicates successful termination */
34 } /* end main */
35
36 void function1(int a)
37 {
38 printf("You entered %d so function1 was called\n\n", a);
39 } /* end function1 */
40
```

---

**Fig. 7.28** | Demonstrating an array of pointers to functions. (Part I of 2.)

```

41 void function2(int b)
42 {
43 printf("You entered %d so function2 was called\n\n", b);
44 } /* end function2 */
45
46 void function3(int c)
47 {
48 printf("You entered %d so function3 was called\n\n", c);
49 } /* end function3 */

```

```

Enter a number between 0 and 2, 3 to end: 0
You entered 0 so function1 was called

Enter a number between 0 and 2, 3 to end: 1
You entered 1 so function2 was called

Enter a number between 0 and 2, 3 to end: 2
You entered 2 so function3 was called

Enter a number between 0 and 2, 3 to end: 3
Program execution completed.

```

**Fig. 7.28** | Demonstrating an array of pointers to functions. (Part 2 of 2.)

The definition is read beginning in the leftmost set of parentheses, “f is an array of 3 pointers to functions that each take an int as an argument and return void.” The array is initialized with the names of the three functions. When the user enters a value between 0 and 2, the value is used as the subscript into the array of pointers to functions. In the function call (line 26), f[choice] selects the pointer at location choice in the array. The pointer is dereferenced to call the function, and choice is passed as the argument to the function. Each function prints its argument’s value and its function name to demonstrate that the function is called correctly. In this chapter’s exercises, you’ll develop several text-based, menu-driven systems.

## Summary

### Section 7.2 Pointer Variable Definitions and Initialization

- A pointer contains an address of another variable that contains a value. In this sense, a variable name *directly* references a value, and a pointer *indirectly* references a value.
- Referencing a value through a pointer is called indirection.
- Pointers can be defined to point to objects of any type.
- Pointers should be initialized either when they’re defined or in an assignment statement. A pointer may be initialized to NULL, 0 or an address. A pointer with the value NULL points to nothing. Initializing a pointer to 0 is equivalent to initializing a pointer to NULL, but NULL is preferred. The value 0 is the only integer value that can be assigned directly to a pointer variable.
- NULL is a symbolic constant defined in the <stddef.h> header (and several other headers).

### Section 7.3 Pointer Operators

- The &, or address operator, is a unary operator that returns the address of its operand.

- The operand of the address operator must be a variable.
- The indirection operator `*` returns the value of the object to which its operand points.
- The `printf` conversion specifier `%p` outputs a memory location as a hexadecimal integer on most platforms.

### *Section 7.4 Passing Arguments to Functions by Reference*

- All arguments in C are passed by value.
- C provides the capabilities for simulating call-by-reference using pointers and the indirection operator. To pass a variable by reference, apply the address operator (`&`) to the variable's name.
- When the address of a variable is passed to a function, the indirection operator (`*`) may be used in the function to modify the value at that location in the caller's memory.
- A function receiving an address as an argument must define a pointer parameter to receive the address.
- The compiler does not differentiate between a function that receives a pointer and a function that receives a single-subscripted array. A function must "know" when it's receiving an array vs. a single variable passed by reference.
- When the compiler encounters a function parameter for a single-subscripted array of the form `int b[]`, the compiler converts the parameter to the pointer notation `int *b`.

### *Section 7.5 Using the **const** Qualifier with Pointers*

- The `const` qualifier indicates that the value of a particular variable should not be modified.
- If an attempt is made to modify a value that is declared `const`, the compiler catches it and issues either a warning or an error, depending on the particular compiler.
- There are four ways to pass a pointer to a function: a non-constant pointer to non-constant data, a constant pointer to non-constant data, a non-constant pointer to constant data, and a constant pointer to constant data.
- With a non-constant pointer to non-constant data, the data can be modified through the dereferenced pointer, and the pointer can be modified to point to other data items.
- A non-constant pointer to constant data can be modified to point to any data item of the appropriate type, but the data to which it points cannot be modified.
- A constant pointer to non-constant data always points to the same memory location, and the data at that location can be modified through the pointer. This is the default for an array name.
- A constant pointer to constant data always points to the same memory location, and the data at that memory location cannot be modified.

### *Section 7.7 **sizeof** Operator*

- Unary operator `sizeof` determine the size in bytes of a variable or type at compilation time.
- When applied to the name of an array, `sizeof` returns the total number of bytes in the array.
- Type `size_t` is an integral type (unsigned or unsigned long) returned by operator `sizeof`. Type `size_t` is defined in header `<stddef.h>`.
- Operator `sizeof` can be applied to any variable name, type or value.
- The parentheses used with `sizeof` are required if a type name is supplied as its operand.

### *Section 7.8 Pointer Expressions and Pointer Arithmetic*

- A limited set of arithmetic operations may be performed on pointers. A pointer may be incremented (`++`) or decremented (`--`), an integer may be added to a pointer (`+` or `+=`), an integer may be subtracted from a pointer (`-` or `-=`) and one pointer may be subtracted from another.

- When an integer is added to or subtracted from a pointer, the pointer is incremented or decremented by that integer times the size of the object to which the pointer refers.
- Two pointers to elements of the same array may be subtracted from one another to determine the number of elements between them.
- A pointer can be assigned to another pointer if both have the same type. An exception to this is the pointer of type `void *` which can represent any pointer type. All pointer types can be assigned a `void *` pointer, and a `void *` pointer can be assigned a pointer of any type.
- A `void *` pointer cannot be dereferenced.
- Pointers can be compared using equality and relational operators, but such comparisons are meaningless unless the pointers point to elements of the same array. Pointer comparisons compare the addresses stored in the pointers.
- A common use of pointer comparison is determining whether a pointer is `NULL`.

### *Section 7.9 Relationship between Pointers and Arrays*

- Arrays and pointers are intimately related in C and often may be used interchangeably.
- An array name can be thought of as a constant pointer.
- Pointers can be used to do any operation involving array subscripting.
- When a pointer points to the beginning of an array, adding an offset to the pointer indicates which element of the array should be referenced, and the offset value is identical to the array subscript. This is referred to as pointer/offset notation.
- An array name can be treated as a pointer and used in pointer arithmetic expressions that do not attempt to modify the address of the pointer.
- Pointers can be subscripted exactly as arrays can. This is referred to as pointer/subscript notation.
- A parameter of type `const char *` typically represents a constant string.

### *Section 7.10 Arrays of Pointers*

- Arrays may contain pointers. A common use of an array of pointers is to form an array of strings. Each entry in the array is a string, but in C a string is essentially a pointer to its first character. So each entry in an array of strings is actually a pointer to the first character of a string.

### *Section 7.12 Pointers to Functions*

- A pointer to a function contains the address of the function in memory. A function name is really the starting address in memory of the code that performs the function's task.
- Pointers to functions can be passed to functions, returned from functions, stored in arrays and assigned to other function pointers.
- A pointer to a function is dereferenced to call the function. A function pointer can be used directly as the function name when calling the function.
- A common use of function pointers is in text-based, menu-driven systems.

## Terminology

address operator (&) 255

array of pointers 280

array of strings 280

call-by-reference 257

call-by-value 257

const qualifier 261

constant pointer to constant data 262

constant pointer to non-constant data 262

dereferencing a pointer 256

dereferencing operator (\*) 256

function pointer 289

indefinite postponement 281

indirection 254

indirection operator (\*) 256

non-constant pointer to constant data 262  
 non-constant pointer to non-constant data 262  
 offset to a pointer 276  
 pointer 254  
 pointer arithmetic 263  
 pointer/offset notation 276  
 pointer/subscript notation 276  
 pointer subscripting 276  
 pointer to a function 285  
 pointer to void (void \*) 275  
 principle of least privilege 262  
 record 265  
 simulating call-by-reference 258  
 sizeof operator 270  
 size\_t type 271  
 string array 280  
 structure 265  
 time/space tradeoff 266  
 void \* (pointer to void) 275

## Self-Review Exercises

**7.1** Answer each of the following:

- A pointer variable contains as its value the \_\_\_\_\_ of another variable.
- The three values that can be used to initialize a pointer are \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- The only integer that can be assigned to a pointer is \_\_\_\_\_.

**7.2** State whether the following are *true* or *false*. If the answer is *false*, explain why.

- The address operator (&) can be applied only to constants, to expressions and to variables declared with the storage-class register.
- A pointer that is declared to be void can be dereferenced.
- Pointers of different types may not be assigned to one another without a cast operation.

**7.3** Answer each of the following. Assume that single-precision floating-point numbers are stored in 4 bytes, and that the starting address of the array is at location 1002500 in memory. Each part of the exercise should use the results of previous parts where appropriate.

- Define an array of type float called numbers with 10 elements, and initialize the elements to the values 0.0, 1.1, 2.2, ..., 9.9. Assume the symbolic constant SIZE has been defined as 10.
- Define a pointer, nPtr, that points to an object of type float.
- Print the elements of array numbers using array subscript notation. Use a for statement and assume the integer control variable i has been defined. Print each number with 1 position of precision to the right of the decimal point.
- Give two separate statements that assign the starting address of array numbers to the pointer variable nPtr.
- Print the elements of array numbers using pointer/offset notation with the pointer nPtr.
- Print the elements of array numbers using pointer/offset notation with the array name as the pointer.
- Print the elements of array numbers by subscripting pointer nPtr.
- Refer to element 4 of array numbers using array subscript notation, pointer/offset notation with the array name as the pointer, pointer subscript notation with nPtr and pointer/offset notation with nPtr.
- Assuming that nPtr points to the beginning of array numbers, what address is referenced by nPtr + 8? What value is stored at that location?
- Assuming that nPtr points to numbers[5], what address is referenced by nPtr -= 4. What is the value stored at that location?

**7.4** For each of the following, write a statement that performs the indicated task. Assume that floating-point variables number1 and number2 are defined and that number1 is initialized to 7.3.

- Define the variable fPtr to be a pointer to an object of type float.
- Assign the address of variable number1 to pointer variable fPtr.



- c) Print the value of the object pointed to by fPtr.
- d) Assign the value of the object pointed to by fPtr to variable number2.
- e) Print the value of number2.
- f) Print the address of number1. Use the %p conversion specifier.
- g) Print the address stored in fPtr. Use the %p conversion specifier. Is the value printed the same as the address of number1?

### 7.5 Do each of the following:

- a) Write the function header for a function called exchange that takes two pointers to floating-point numbers x and y as parameters and does not return a value.
- b) Write the function prototype for the function in part (a).
- c) Write the function header for a function called evaluate that returns an integer and that takes as parameters integer x and a pointer to function poly. Function poly takes an integer parameter and returns an integer.
- d) Write the function prototype for the function in part (c).

### 7.6 Find the error in each of the following program segments. Assume

```
int *zPtr; /* zPtr will reference array z */
int *aPtr = NULL;
void *sPtr = NULL;
int number, i;
int z[5] = { 1, 2, 3, 4, 5 };
sPtr = z;
```

- a) ++zPtr;
- b) /\* use pointer to get first value of array; assume zPtr is initialized \*/  
number = zPtr;
- c) /\* assign array element 2 (the value 3) to number;  
assume zPtr is initialized \*/  
number = \*zPtr[ 2 ];
- d) /\* print entire array z; assume zPtr is initialized \*/  
for ( i = 0; i <= 5; i++ ) {  
 printf( "%d ", zPtr[ i ] );  
}
- e) /\* assign the value pointed to by sPtr to number \*/  
number = \*sPtr;
- f) ++z;

## Answers to Self-Review Exercises

- 7.1 a) address. b) 0, NULL, an address. c) 0.
- 7.2 a) False. The address operator can be applied only to variables. The address operator cannot be applied to variables declared with storage class register.  
b) False. A pointer to void cannot be dereferenced, because there is no way to know exactly how many bytes of memory to dereference.  
c) False. Pointers of type void can be assigned pointers of other types, and pointers of type void can be assigned to pointers of other types.
- 7.3 a) float numbers[ SIZE ] =  
 { 0.0, 1.1, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7, 8.8, 9.9 };
- b) float \*nPtr;
- c) for ( i = 0; i < SIZE; i++ ) {  
 printf( "%.1f ", numbers[ i ] );  
}

- d) `nPtr = numbers;`  
`nPtr = &numbers[ 0 ];`
- e) `for ( i = 0; i < SIZE; i++ ) {`  
`printf( "%.1f ", *( nPtr + i ) );`  
`}`
- f) `for ( i = 0; i < SIZE; i++ ) {`  
`printf( "%.1f ", *( numbers + i ) );`  
`}`
- g) `for ( i = 0; i < SIZE; i++ ) {`  
`printf( "%.1f ", nPtr[ i ] );`  
`}`
- h) `numbers[ 4 ]`  
`*( numbers + 4 )`  
`nPtr[ 4 ]`  
`*( nPtr + 4 )`
- i) The address is  $1002500 + 8 * 4 = 1002532$ . The value is 8.8.
- j) The address of `numbers[ 5 ]` is  $1002500 + 5 * 4 = 1002520$ .  
 The address of `nPtr - 4` is  $1002520 - 4 * 4 = 1002504$ .  
 The value at that location is 1.1.

- 7.4**
- a) `float *fPtr;`
  - b) `fPtr = &number1;`
  - c) `printf( "The value of *fPtr is %f\n", *fPtr );`
  - d) `number2 = *fPtr;`
  - e) `printf( "The value of number2 is %f\n", number2 );`
  - f) `printf( "The address of number1 is %p\n", &number1 );`
  - g) `printf( "The address stored in fptr is %p\n", fPtr );`  
 Yes, the value is the same.

- 7.5**
- a) `void exchange( float *x, float *y )`
  - b) `void exchange( float *x, float *y );`
  - c) `int evaluate( int x, int (*poly)( int ) )`
  - d) `int evaluate( int x, int (*poly)( int ) );`

- 7.6**
- a) Error: `zPtr` has not been initialized.  
 Correction: Initialize `zPtr` with `zPtr = z;` before performing the pointer arithmetic.
  - b) Error: The pointer is not dereferenced.  
 Correction: Change the statement to `number = *zPtr;`
  - c) Error: `zPtr[ 2 ]` is not a pointer and should not be dereferenced.  
 Correction: Change `*zPtr[ 2 ]` to `zPtr[ 2 ]`.
  - d) Error: Referring to an array element outside the array bounds with pointer subscripting.  
 Correction: Change the operator `<=` in the for condition to `<`.
  - e) Error: Dereferencing a void pointer.  
 Correction: To dereference the pointer, it must first be cast to an integer pointer.  
 Change the statement to `number = *( ( int * ) sPtr );`
  - f) Error: Trying to modify an array name with pointer arithmetic.  
 Correction: Use a pointer variable instead of the array name to accomplish pointer arithmetic, or subscript the array name to refer to a specific element.

## Exercises

- 7.7** Answer each of the following:

- a) The \_\_\_\_\_ operator returns the location in memory where its operand is stored.

- b) The \_\_\_\_\_ operator returns the value of the object to which its operand points.
- c) To simulate call-by-reference when passing a nonarray variable to a function, it's necessary to pass the \_\_\_\_\_ of the variable to the function.

**7.8** State whether the following are *true* or *false*. If *false*, explain why.

- a) Two pointers that point to different arrays cannot be compared meaningfully.
- b) Because the name of an array is a pointer to the first element of the array, array names may be manipulated in precisely the same manner as pointers.

**7.9** Answer each of the following. Assume that unsigned integers are stored in 2 bytes and that the starting address of the array is at location 1002500 in memory.

- a) Define an array of type `unsigned int` called `values` with five elements, and initialize the elements to the even integers from 2 to 10. Assume the symbolic constant `SIZE` has been defined as 5.
- b) Define a pointer `vPtr` that points to an object of type `unsigned int`.
- c) Print the elements of array `values` using array subscript notation. Use a `for` statement and assume integer control variable `i` has been defined.
- d) Give two separate statements that assign the starting address of array `values` to pointer variable `vPtr`.
- e) Print the elements of array `values` using pointer/offset notation.
- f) Print the elements of array `values` using pointer/offset notation with the array name as the pointer.
- g) Print the elements of array `values` by subscripting the pointer to the array.
- h) Refer to element 5 of array `values` using array subscript notation, pointer/offset notation with the array name as the pointer, pointer subscript notation, and pointer/offset notation.
- i) What address is referenced by `vPtr + 3`? What value is stored at that location?
- j) Assuming `vPtr` points to `values[4]`, what address is referenced by `vPtr -= 4`. What value is stored at that location?

**7.10** For each of the following, write a single statement that performs the indicated task. Assume that long integer variables `value1` and `value2` have been defined and that `value1` has been initialized to 200000.

- a) Define the variable `lPtr` to be a pointer to an object of type `long`.
- b) Assign the address of variable `value1` to pointer variable `lPtr`.
- c) Print the value of the object pointed to by `lPtr`.
- d) Assign the value of the object pointed to by `lPtr` to variable `value2`.
- e) Print the value of `value2`.
- f) Print the address of `value1`.
- g) Print the address stored in `lPtr`. Is the value printed the same as the address of `value1`?

**7.11** Do each of the following:

- a) Write the function header for function `zero`, which takes a long integer array parameter `bigIntegers` and does not return a value.
- b) Write the function prototype for the function in part a.
- c) Write the function header for function `add1AndSum`, which takes an integer array parameter `oneTooSmall` and returns an integer.
- d) Write the function prototype for the function described in part c.

*Note: Exercise 7.12 through Exercise 7.15 are reasonably challenging. Once you have done these problems, you ought to be able to implement most popular card games easily.*

**7.12** (*Card Shuffling and Dealing*) Modify the program in Fig. 7.24 so that the card-dealing function deals a five-card poker hand. Then write the following additional functions:

- Determine if the hand contains a pair.
- Determine if the hand contains two pairs.
- Determine if the hand contains three of a kind (e.g., three jacks).
- Determine if the hand contains four of a kind (e.g., four aces).
- Determine if the hand contains a flush (i.e., all five cards of the same suit).
- Determine if the hand contains a straight (i.e., five cards of consecutive face values).

**7.13** (*Project: Card Shuffling and Dealing*) Use the functions developed in Exercise 7.12 to write a program that deals two five-card poker hands, evaluates each hand, and determines which is the better hand.

**7.14** (*Project: Card Shuffling and Dealing*) Modify the program developed in Exercise 7.13 so that it can simulate the dealer. The dealer's five-card hand is dealt “face down” so the player cannot see it. The program should then evaluate the dealer's hand, and based on the quality of the hand, the dealer should draw one, two or three more cards to replace the corresponding number of unneeded cards in the original hand. The program should then re-evaluate the dealer's hand. [*Caution: This is a difficult problem!*]

**7.15** (*Project: Card Shuffling and Dealing*) Modify the program developed in Exercise 7.14 so that it can handle the dealer's hand automatically, but the player is allowed to decide which cards of the player's hand to replace. The program should then evaluate both hands and determine who wins. Now use this new program to play 20 games against the computer. Who wins more games, you or the computer? Have one of your friends play 20 games against the computer. Who wins more games? Based on the results of these games, make appropriate modifications to refine your poker playing program (this, too, is a difficult problem). Play 20 more games. Does your modified program play a better game?

**7.16** (*Card Shuffling and Dealing Modification*) In the card shuffling and dealing program of Fig. 7.24, we intentionally used an inefficient shuffling algorithm that introduced the possibility of indefinite postponement. In this problem, you'll create a high-performance shuffling algorithm that avoids indefinite postponement.

Modify the program of Fig. 7.24 as follows. Begin by initializing the deck array as shown in Fig. 7.29. Modify the `shuffle` function to loop row-by-row and column-by-column through the array, touching every element once. Each element should be swapped with a randomly selected element of the array. Print the resulting array to determine if the deck is satisfactorily shuffled (as in Fig. 7.30, for example). You may want your program to call the `shuffle` function several times to ensure a satisfactory shuffle.

Although the approach in this problem improves the shuffling algorithm, the dealing algorithm still requires searching the deck array for card 1, then card 2, then card 3, and so on. Worse yet, even after the dealing algorithm locates and deals the card, the algorithm continues searching through the remainder of the deck. Modify the program of Fig. 7.24 so that once a card is dealt, no

| Unshuffled deck array |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-----------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|
|                       | 0  | 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | 9  | 10 | 11 | 12 |
| 0                     | 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | 9  | 10 | 11 | 12 | 13 |
| 1                     | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 |
| 2                     | 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 |
| 3                     | 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 | 51 | 52 |

**Fig. 7.29** | Unshuffled deck array.

| Sample shuffled deck array |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|
|                            | 0  | 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | 9  | 10 | 11 | 12 |
| 0                          | 19 | 40 | 27 | 25 | 36 | 46 | 10 | 34 | 35 | 41 | 18 | 2  | 44 |
| 1                          | 13 | 28 | 14 | 16 | 21 | 30 | 8  | 11 | 31 | 17 | 24 | 7  | 1  |
| 2                          | 12 | 33 | 15 | 42 | 43 | 23 | 45 | 3  | 29 | 32 | 4  | 47 | 26 |
| 3                          | 50 | 38 | 52 | 39 | 48 | 51 | 9  | 5  | 37 | 49 | 22 | 6  | 20 |

**Fig. 7.30** | Sample shuffled deck array.

further attempts are made to match that card number, and the program immediately proceeds with dealing the next card. In Chapter 10, we develop a dealing algorithm that requires only one operation per card.

**7.17 (Simulation: The Tortoise and the Hare)** In this problem, you'll recreate one of the truly great moments in history, namely the classic race of the tortoise and the hare. You'll use random number generation to develop a simulation of this memorable event.

Our contenders begin the race at “square 1” of 70 squares. Each square represents a possible position along the race course. The finish line is at square 70. The first contender to reach or pass square 70 is rewarded with a pail of fresh carrots and lettuce. The course weaves its way up the side of a slippery mountain, so occasionally the contenders lose ground.

There is a clock that ticks once per second. With each tick of the clock, your program should adjust the position of the animals according to the rules of Fig. 7.31.

| Animal   | Move type  | Percentage of the time | Actual move            |
|----------|------------|------------------------|------------------------|
| Tortoise | Fast plod  | 50%                    | 3 squares to the right |
|          | Slip       | 20%                    | 6 squares to the left  |
|          | Slow plod  | 30%                    | 1 square to the right  |
| Hare     | Sleep      | 20%                    | No move at all         |
|          | Big hop    | 20%                    | 9 squares to the right |
|          | Big slip   | 10%                    | 12 squares to the left |
|          | Small hop  | 30%                    | 1 square to the right  |
|          | Small slip | 20%                    | 2 squares to the left  |

**Fig. 7.31** | Tortoise and hare rules for adjusting positions.

Use variables to keep track of the positions of the animals (i.e., position numbers are 1–70). Start each animal at position 1 (i.e., the “starting gate”). If an animal slips left before square 1, move the animal back to square 1.

Generate the percentages in the preceding table by producing a random integer,  $i$ , in the range  $1 \leq i \leq 10$ . For the tortoise, perform a “fast plod” when  $1 \leq i \leq 5$ , a “slip” when  $6 \leq i \leq 7$ , or a “slow plod” when  $8 \leq i \leq 10$ . Use a similar technique to move the hare.

Begin the race by printing

```
BANG !!!!!
AND THEY'RE OFF !!!!!
```

Then, for each tick of the clock (i.e., each repetition of a loop), print a 70-position line showing the letter T in the position of the tortoise and the letter H in the position of the hare. Occasionally,

the contenders will land on the same square. In this case, the tortoise bites the hare and your program should print OUCH!!! beginning at that position. All print positions other than the T, the H, or the OUCH!!! (in case of a tie) should be blank.

After each line is printed, test if either animal has reached or passed square 70. If so, then print the winner and terminate the simulation. If the tortoise wins, print TORTOISE WINS!!! YAY!!! If the hare wins, print Hare wins. Yuch. If both animals win on the same tick of the clock, you may want to favor the turtle (the “underdog”), or you may want to print It's a tie. If neither animal wins, perform the loop again to simulate the next tick of the clock. When you're ready to run your program, assemble a group of fans to watch the race. You'll be amazed at how involved your audience gets!

**7.18** (*Card Shuffling and Dealing Modification*) Modify the card shuffling and dealing program of Fig. 7.24 so the shuffling and dealing operations are performed by the same function (shuffleAndDeal). The function should contain one nested looping structure that is similar to function shuffle in Fig. 7.24.

**7.19** What does this program do?

```

1 /* ex07_19.c */
2 /* What does this program do? */
3 #include <stdio.h>
4
5 void mystery1(char *s1, const char *s2); /* prototype */
6
7 int main(void)
8 {
9 char string1[80]; /* create char array */
10 char string2[80]; /* create char array */
11
12 printf("Enter two strings: ");
13 scanf("%s%s", string1, string2);
14 mystery1(string1, string2);
15 printf("%s", string1);
16 return 0; /* indicates successful termination */
17 } /* end main */
18
19 /* What does this function do? */
20 void mystery1(char *s1, const char *s2)
21 {
22 while (*s1 != '\0') {
23 s1++;
24 } /* end while */
25
26 for (; *s1 = *s2; s1++, s2++) {
27 ; /* empty statement */
28 } /* end for */
29 } /* end function mystery1 */

```

**7.20** What does this program do?

```

1 /* ex07_20.c */
2 /* what does this program do? */
3 #include <stdio.h>
4
5 int mystery2(const char *s); /* prototype */
6
7 int main(void)
8 {
9 char string[80]; /* create char array */

```

```

10
11 printf("Enter a string: ");
12 scanf("%s", string);
13 printf("%d\n", mystery2(string));
14 return 0; /* indicates successful termination */
15 } /* end main */
16
17 /* What does this function do? */
18 int mystery2(const char *s)
19 {
20 int x; /* counter */
21
22 /* loop through string */
23 for (x = 0; *s != '\0'; s++) {
24 x++;
25 } /* end for */
26
27 return x;
28 } /* end function mystery2 */

```

**7.21** Find the error in each of the following program segments. If the error can be corrected, explain how.

- a) `int *number;`  
`printf( "%d\n", *number );`
- b) `float *realPtr;`  
`long *integerPtr;`  
`integerPtr = realPtr;`
- c) `int * x, y;`  
`x = y;`
- d) `char s[] = "this is a character array";`  
`int count;`  
`for ( ; *s != '\0'; s++)`  
`printf( "%c ", *s );`
- e) `short *numPtr, result;`  
`void *genericPtr = numPtr;`  
`result = *genericPtr + 7;`
- f) `float x = 19.34;`  
`float xPtr = &x;`  
`printf( "%f\n", xPtr );`
- g) `char *s;`  
`printf( "%s\n", s );`

**7.22** (*Maze Traversal*) The following grid is a double-subscripted array representation of a maze.

```

#
. . . #
. . # . # . # # . #
. # . . . #
. . . # # # . # .
. . . # .
. . # . # . # .
. # . # . # .
. # .
. # # .
. # . .
#

```

The # symbols represent the walls of the maze, and the periods (.) represent squares in the possible paths through the maze.

There is a simple algorithm for walking through a maze that guarantees finding the exit (assuming there is an exit). If there is not an exit, you'll arrive at the starting location again. Place your right hand on the wall to your right and begin walking forward. Never remove your hand from the wall. If the maze turns to the right, you follow the wall to the right. As long as you do not remove your hand from the wall, eventually you'll arrive at the exit of the maze. There may be a shorter path than the one you have taken, but you're guaranteed to get out of the maze.

Write recursive function `mazeTraverse` to walk through the maze. The function should receive as arguments a 12-by-12 character array representing the maze and the starting location of the maze. As `mazeTraverse` attempts to locate the exit from the maze, it should place the character X in each square in the path. The function should display the maze after each move so the user can watch as the maze is solved.

**7.23** (*Generating Mazes Randomly*) Write a function `mazeGenerator` that takes as an argument a double-subscripted 12-by-12 character array and randomly produces a maze. The function should also provide the starting and ending locations of the maze. Try your function `mazeTraverse` from Exercise 7.22 using several randomly generated mazes.

**7.24** (*Mazes of Any Size*) Generalize functions `mazeTraverse` and `mazeGenerator` of Exercise 7.22 and Exercise 7.23 to process mazes of any width and height.

**7.25** (*Arrays of Pointers to Functions*) Rewrite the program of Fig. 6.22 to use a menu-driven interface. The program should offer the user four options as follows:

```
Enter a choice:
0 Print the array of grades
1 Find the minimum grade
2 Find the maximum grade
3 Print the average on all tests for each student
4 End program
```

One restriction on using arrays of pointers to functions is that all the pointers must have the same type. The pointers must be to functions of the same return type that receive arguments of the same type. For this reason, the functions in Fig. 6.22 must be modified so that they each return the same type and take the same parameters. Modify functions `minimum` and `maximum` to print the minimum or maximum value and return nothing. For option 3, modify function `average` of Fig. 6.22 to output the average for each student (not a specific student). Function `average` should return nothing and take the same parameters as `printArray`, `minimum` and `maximum`. Store the pointers to the four functions in array `processGrades` and use the choice made by the user as the subscript into the array for calling each function.

**7.26** What does this program do?

```
1 /* ex07_26.c */
2 /* What does this program do? */
3 #include <stdio.h>
4
5 int mystery3(const char *s1, const char *s2); /* prototype */
6
7 int main(void)
8 {
9 char string1[80]; /* create char array */
10 char string2[80]; /* create char array */
11
12 printf("Enter two strings: ");
```



```
13 scanf("%s%s", string1 , string2);
14 printf("The result is %d\n", mystery3(string1, string2));
15 return 0; /* indicates successful termination */
16 } /* end main */
17
18 int mystery3(const char *s1, const char *s2)
19 {
20 for (; *s1 != '\0' && *s2 != '\0'; s1++, s2++) {
21
22 if (*s1 != *s2) {
23 return 0;
24 } /* end if */
25 } /* end for */
26
27 return 1;
28 } /* end function mystery3 */
```

Special Section: Building Your Own Computer

In the next several problems, we take a temporary diversion away from the world of high-level language programming. We “peel open” a computer and look at its internal structure. We introduce machine-language programming and write several machine-language programs. To make this an especially valuable experience, we then build a computer (through the technique of software-based *simulation*) on which you can execute your machine-language programs!

**7.27 (Machine-Language Programming)** Let’s create a computer we’ll call the Simpletron. As its name implies, it’s a simple machine, but as we’ll soon see, a powerful one as well. The Simpletron runs programs written in the only language it directly understands—that is, Simpletron Machine Language, or SML for short.

The Simpletron contains an *accumulator*—a “special register” in which information is put before the Simpletron uses that information in calculations or examines it in various ways. All information in the Simpletron is handled in terms of *words*. A word is a signed four-digit decimal number such as +3364, -1293, +0007, -0001 and so on. The Simpletron is equipped with a 100-word memory, and these words are referenced by their location numbers 00, 01, ..., 99.

Before running an SML program, we must *load* or place the program into memory. The first instruction (or statement) of every SML program is always placed in location 00.

Each instruction written in SML occupies one word of the Simpletron’s memory (and hence instructions are signed four-digit decimal numbers). We assume that the sign of an SML instruction is always plus, but the sign of a data word may be either plus or minus. Each location in the Simpletron’s memory may contain either an instruction, a data value used by a program or an unused (and hence undefined) area of memory. The first two digits of each SML instruction are the *operation code*, which specifies the operation to be performed. SML operation codes are summarized in Fig. 7.32.

| Operation code                  | Meaning                                                           |
|---------------------------------|-------------------------------------------------------------------|
| <i>Input/output operations:</i> |                                                                   |
| #define READ 10                 | Read a word from the terminal into a specific location in memory. |
| #define WRITE 11                | Write a word from a specific location in memory to the terminal.  |

Fig. 7.32 | Simpletron Machine Language (SML) operation codes. (Part I of 2.)

| Operation code                         | Meaning                                                                                                            |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------|
| <i>Load/store operations:</i>          |                                                                                                                    |
| <code>#define LOAD 20</code>           | Load a word from a specific location in memory into the accumulator.                                               |
| <code>#define STORE 21</code>          | Store a word from the accumulator into a specific location in memory.                                              |
| <i>Arithmetic operations:</i>          |                                                                                                                    |
| <code>#define ADD 30</code>            | Add a word from a specific location in memory to the word in the accumulator (leave result in accumulator).        |
| <code>#define SUBTRACT 31</code>       | Subtract a word from a specific location in memory from the word in the accumulator (leave result in accumulator). |
| <code>#define DIVIDE 32</code>         | Divide a word from a specific location in memory into the word in the accumulator (leave result in accumulator).   |
| <code>#define MULTIPLY 33</code>       | Multiply a word from a specific location in memory by the word in the accumulator (leave result in accumulator).   |
| <i>Transfer of control operations:</i> |                                                                                                                    |
| <code>#define BRANCH 40</code>         | Branch to a specific location in memory.                                                                           |
| <code>#define BRANCHNEG 41</code>      | Branch to a specific location in memory if the accumulator is negative.                                            |
| <code>#define BRANCHZERO 42</code>     | Branch to a specific location in memory if the accumulator is zero.                                                |
| <code>#define HALT 43</code>           | Halt—i.e., the program has completed its task.                                                                     |

**Fig. 7.32** | Simpletron Machine Language (SML) operation codes. (Part 2 of 2.)

The last two digits of an SML instruction are the *operand*, which is the address of the memory location containing the word to which the operation applies. Now let's consider several simple SML programs. The following SML program reads two numbers from the keyboard, and computes and prints their sum.

| Example 1<br>Location | Number | Instruction  |
|-----------------------|--------|--------------|
| 00                    | +1007  | (Read A)     |
| 01                    | +1008  | (Read B)     |
| 02                    | +2007  | (Load A)     |
| 03                    | +3008  | (Add B)      |
| 04                    | +2109  | (Store C)    |
| 05                    | +1109  | (Write C)    |
| 06                    | +4300  | (Halt)       |
| 07                    | +0000  | (Variable A) |
| 08                    | +0000  | (Variable B) |
| 09                    | +0000  | (Result C)   |

The instruction +1007 reads the first number from the keyboard and places it into location 07 (which has been initialized to zero). Then +1008 reads the next number into location 08. The *load* instruction, +2007, puts the first number into the accumulator, and the *add* instruction, +3008, adds the second number to the number in the accumulator. *All SML arithmetic instructions leave their results in the accumulator.* The *store* instruction, +2109, places the result back into memory location 09, from which the *write* instruction, +1109, takes the number and prints it (as a signed four-digit decimal number). The *halt* instruction, +4300, terminates execution.

The following SML program reads two numbers from the keyboard, and determines and prints the larger value. Note the use of the instruction +4107 as a conditional transfer of control, much the same as C's *if* statement.

| Example 2 |        |                         |
|-----------|--------|-------------------------|
| Location  | Number | Instruction             |
| 00        | +1009  | (Read A)                |
| 01        | +1010  | (Read B)                |
| 02        | +2009  | (Load A)                |
| 03        | +3110  | (Subtract B)            |
| 04        | +4107  | (Branch negative to 07) |
| 05        | +1109  | (Write A)               |
| 06        | +4300  | (Halt)                  |
| 07        | +1110  | (Write B)               |
| 08        | +4300  | (Halt)                  |
| 09        | +0000  | (Variable A)            |
| 10        | +0000  | (Variable B)            |

Now write SML programs to accomplish each of the following tasks.

- Use a sentinel-controlled loop to read 10 positive integers and compute and print their sum.
- Use a counter-controlled loop to read seven numbers, some positive and some negative, and compute and print their average.
- Read a series of numbers and determine and print the largest number. The first number read indicates how many numbers should be processed.

**7.28 (A Computer Simulator)** It may at first seem outrageous, but in this problem you're going to build your own computer. No, you won't be soldering components together. Rather, you'll use the powerful technique of *software-based simulation* to create a *software model* of the Simpletron. You'll not be disappointed. Your Simpletron simulator will turn the computer you're using into a Simpletron, and you'll actually be able to run, test and debug the SML programs you wrote in Exercise 7.27.

When you run your Simpletron simulator, it should begin by printing:

```
*** Welcome to Simpletron! ***
*** Please enter your program one instruction ***
*** (or data word) at a time. I will type the ***
*** location number and a question mark (?). ***
*** You then type the word for that location. ***
*** Type the sentinel -99999 to stop entering ***
*** your program. ***
```

Simulate the memory of the Simpletron with a single-subscripted array memory that has 100 elements. Now assume that the simulator is running, and let's examine the dialog as we enter the program of Example 2 of Exercise 7.27:

```
00 ? +1009
01 ? +1010
02 ? +2009
03 ? +3110
04 ? +4107
05 ? +1109
06 ? +4300
07 ? +1110
08 ? +4300
09 ? +0000
10 ? +0000
11 ? -99999
*** Program loading completed ***
*** Program execution begins ***
```

The SML program has now been placed (or loaded) into the array memory. Now the Simpletron executes the SML program. It begins with the instruction in location 00 and, continues sequentially, unless directed to some other part of the program by a transfer of control.

Use the variable `accumulator` to represent the accumulator register. Use the variable `instructionCounter` to keep track of the location in memory that contains the instruction being performed. Use the variable `operationCode` to indicate the operation currently being performed—i.e., the left two digits of the instruction word. Use the variable `operand` to indicate the memory location on which the current instruction operates. Thus, `operand` is the rightmost two digits of the instruction currently being performed. Do not execute instructions directly from memory. Rather, transfer the next instruction to be performed from memory to a variable called `instructionRegister`. Then “pick off” the left two digits and place them in the variable `operationCode`, and “pick off” the right two digits and place them in `operand`.

When Simpletron begins execution, the special registers are initialized as follows:

```
accumulator +0000
instructionCounter 00
instructionRegister +0000
operationCode 00
operand 00
```

Now let's “walk through” the execution of the first SML instruction, +1009 in memory location 00. This is called an *instruction execution cycle*.

The `instructionCounter` tells us the location of the next instruction to be performed. We *fetch* the contents of that location from memory by using the C statement

```
instructionRegister = memory[instructionCounter];
```

The operation code and the operand are extracted from the instruction register by the statements

```
operationCode = instructionRegister / 100;
operand = instructionRegister % 100;
```

Now the Simpletron must determine that the operation code is actually a *read* (versus a *write*, a *load*, and so on). A switch differentiates among the twelve operations of SML.

In the switch statement, the behavior of various SML instructions is simulated as follows (we leave the others to the reader):

```
read: scanf("%d", &memory[operand]);
load: accumulator = memory[operand];
add: accumulator += memory[operand];
```

*Various branch instructions:* We'll discuss these shortly.  
*halt:* This instruction prints the message

```
*** Simpletron execution terminated ***
```

then prints the name and contents of each register as well as the complete contents of memory. Such a printout is often called a *computer dump*. To help you program your dump function, a sample dump format is shown in Fig. 7.33. A dump after executing a Simpletron program would show the actual values of instructions and data values at the moment execution terminated.

```
REGISTERS:
accumulator +0000
instructionCounter 00
instructionRegister +0000
operationCode 00
operand 00

MEMORY:
 0 1 2 3 4 5 6 7 8 9
0 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
10 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
20 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
30 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
40 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
50 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
60 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
70 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
80 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
90 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
```

**Fig. 7.33** | Sample Simpletron dump format.

Let's proceed with the execution of our program's first instruction, namely the +1009 in location 00. As we have indicated, the `switch` statement simulates this by performing the C statement

```
scanf("%d", &memory[operand]);
```

A question mark (?) should be displayed on the screen before the `scanf` is executed to prompt the user for input. The Simpletron waits for the user to type a value and then press the *Return* key. The value is then read into location 09.

At this point, simulation of the first instruction is completed. All that remains is to prepare the Simpletron to execute the next instruction. Since the instruction just performed was not a transfer of control, we need merely increment the instruction counter register as follows:

```
++instructionCounter;
```

This completes the simulated execution of the first instruction. The entire process (i.e., the instruction execution cycle) begins anew with the fetch of the next instruction to be executed.

Now let's consider how the branching instructions—the transfers of control—are simulated. All we need to do is adjust the value in the instruction counter appropriately. Therefore, the unconditional branch instruction (40) is simulated within the `switch` as

```
instructionCounter = operand;
```

The conditional “branch if accumulator is zero” instruction is simulated as

```
if (accumulator == 0) {
 instructionCounter = operand;
}
```

At this point, you should implement your Simpletron simulator and run the SML programs you wrote in Exercise 7.27. You may embellish SML with additional features and provide for these in your simulator.

Your simulator should check for various types of errors. During the program loading phase, for example, each number the user types into the Simpletron's memory must be in the range -9999 to +9999. Your simulator should use a `while` loop to test that each number entered is in this range, and, if not, keep prompting the user to reenter the number until the user enters a correct number.

During the execution phase, your simulator should check for various serious errors, such as attempts to divide by zero, attempts to execute invalid operation codes and accumulator overflows (i.e., arithmetic operations resulting in values larger than +9999 or smaller than -9999). Such serious errors are called *fatal errors*. When a fatal error is detected, your simulator should print an error message such as:

```
*** Attempt to divide by zero ***
*** Simpletron execution abnormally terminated ***
```

and should print a full computer dump in the format we have discussed previously. This will help the user locate the error in the program.

**7.29 (Modifications to the Simpletron Simulator)** In Exercise 7.28, you wrote a software simulation of a computer that executes programs written in Simpletron Machine Language (SML). In this exercise, we propose several modifications and enhancements to the Simpletron Simulator. In Exercises 12.26 and 12.27, we propose building a compiler that converts programs written in a high-level programming language (a variation of BASIC) to Simpletron Machine Language. Some of the following modifications and enhancements may be required to execute the programs produced by the compiler.

- Extend the Simpletron Simulator's memory to contain 1000 memory locations to enable the Simpletron to handle larger programs.
- Allow the simulator to perform remainder calculations. This requires an additional Simpletron Machine Language instruction.
- Allow the simulator to perform exponentiation calculations. This requires an additional Simpletron Machine Language instruction.
- Modify the simulator to use hexadecimal values rather than integer values to represent Simpletron Machine Language instructions.
- Modify the simulator to allow output of a newline. This requires an additional Simpletron Machine Language instruction.
- Modify the simulator to process floating-point values in addition to integer values.
- Modify the simulator to handle string input. [*Hint:* Each Simpletron word can be divided into two groups, each holding a two-digit integer. Each two-digit integer represents the ASCII decimal equivalent of a character. Add a machine-language instruction that will input a string and store the string beginning at a specific Simpletron memory location. The first half of the word at that location will be a count of the number of characters in the string (i.e., the length of the string). Each succeeding half word contains one ASCII character expressed as two decimal digits. The machine-language instruction converts each character into its ASCII equivalent and assigns it to a half word.]
- Modify the simulator to handle output of strings stored in the format of part (g). [*Hint:* Add a machine-language instruction that prints a string beginning at a specified Simpletron memory location. The first half of the word at that location is the length of the string in characters. Each succeeding half word contains one ASCII character expressed as two decimal digits. The machine-language instruction checks the length and prints the string by translating each two-digit number into its equivalent character.]

## Array of Function Pointer Exercises

**7.30 (Calculating Circle Circumference, Circle Area or Sphere Volume Using Function Pointers)** Using the techniques you learned in Fig. 7.28, create a text-based, menu-driven program that allows

the user to choose whether to calculate the circumference of a circle, the area of a circle or the volume of a sphere. The program should then input a radius from the user, perform the appropriate calculation and display the result. Use an array of function pointers in which each pointer represents a function that returns `void` and receives a `double` parameter. The corresponding functions should each display messages indicating which calculation was performed, the value of the radius and the result of the calculation.

**7.31** (*Calculator Using Function Pointers*) Using the techniques you learned in Fig. 7.28, create a text-based, menu-driven program that allows the user to choose whether to add, subtract, multiply or divide two numbers. The program should then input two `double` values from the user, perform the appropriate calculation and display the result. Use an array of function pointers in which each pointer represents a function that returns `void` and receives two `double` parameters. The corresponding functions should each display messages indicating which calculation was performed, the values of the parameters and the result of the calculation.

## Making a Difference

**7.32** (*Polling*) The Internet and the web are enabling more people to network, join a cause, voice opinions, and so on. The U.S. presidential candidates in 2008 used the Internet intensively to get out their messages and raise money for their campaigns. In this exercise, you'll write a simple polling program that allows users to rate five social-consciousness issues from 1 (least important) to 10 (most important). Pick five causes that are important to you (e.g., political issues, global environmental issues). Use a one-dimensional array `topics` (of type `char *`) to store the five causes. To summarize the survey responses, use a 5-row, 10-column two-dimensional array `responses` (of type `int`), each row corresponding to an element in the `topics` array. When the program runs, it should ask the user to rate each issue. Have your friends and family respond to the survey. Then have the program display a summary of the results, including:

- A tabular report with the five topics down the left side and the 10 ratings across the top, listing in each column the number of ratings received for each topic.
- To the right of each row, show the average of the ratings for that issue.
- Which issue received the highest point total? Display both the issue and the point total.
- Which issue received the lowest point total? Display both the issue and the point total.

**7.33** (*CarbonFootprint Calculator: Arrays of Function Pointers*) Using arrays of function pointers, as you learned in this chapter, you can specify a set of functions that are called with the same types of arguments and return the same type of data. Governments and companies worldwide are becoming increasingly concerned with carbon footprints (annual releases of carbon dioxide into the atmosphere) from buildings burning various types of fuels for heat, vehicles burning fuels for power, and the like. Many scientists blame these greenhouse gases for the phenomenon called global warming. Create three functions that help calculate the carbon footprint of a building, a car and a bicycle, respectively. Each function should input appropriate data from the user then calculate and display the carbon footprint. (Check out a few websites that explain how to calculate carbon footprints.) Each function should receive no parameters and return `void`. Write a program that prompts the user to enter the type of carbon footprint to calculate, then calls the corresponding function in the array of function pointers. For each type of carbon footprint, display some identifying information and the object's carbon footprint.



# C Characters and Strings

## 8

*Vigorous writing is concise. A sentence should contain no unnecessary words, a paragraph no unnecessary sentences.*

—William Strunk, Jr.

*I have made this letter longer than usual, because I lack the time to make it short.*

—Blaise Pascal

*The difference between the almost-right word and the right word is really a large matter—it's the difference between the lightning bug and the lightning.*

—Mark Twains

### Objectives

In this chapter, you'll learn:

- To use the functions of the character-handling library (`<ctype.h>`).
- To use the string-conversion functions of the general utilities library (`<stdlib.h>`).
- To use the string and character input/output functions of the standard input/output library (`<stdio.h>`).
- To use the string-processing functions of the string handling library (`<string.h>`).
- The power of function libraries for achieving software reusability.



- |                                                                         |                                                                |
|-------------------------------------------------------------------------|----------------------------------------------------------------|
| <b>8.1</b> Introduction                                                 | <b>8.7</b> Comparison Functions of the String-Handling Library |
| <b>8.2</b> Fundamentals of Strings and Characters                       | <b>8.8</b> Search Functions of the String-Handling Library     |
| <b>8.3</b> Character-Handling Library                                   | <b>8.9</b> Memory Functions of the String-Handling Library     |
| <b>8.4</b> String-Conversion Functions                                  | <b>8.10</b> Other Functions of the String-Handling Library     |
| <b>8.5</b> Standard Input/Output Library Functions                      |                                                                |
| <b>8.6</b> String-Manipulation Functions of the String-Handling Library |                                                                |

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises |  
 Special Section: Advanced String-Manipulation Exercises |  
 A Challenging String-Manipulation Project | Making a Difference*

## 8.1 Introduction

In this chapter, we introduce the C Standard Library functions that facilitate string and character processing.<sup>1</sup> The functions enable programs to process characters, strings, lines of text and blocks of memory.

The chapter discusses the techniques used to develop editors, word processors, page layout software, computerized typesetting systems and other kinds of text-processing software. The text manipulations performed by formatted input/output functions like `printf` and `scanf` can be implemented using the functions discussed in this chapter.

## 8.2 Fundamentals of Strings and Characters

Characters are the fundamental building blocks of source programs. Every program is composed of a sequence of characters that—when grouped together meaningfully—is interpreted by the computer as a series of instructions used to accomplish a task. A program may contain **character constants**. A character constant is an `int` value represented as a character in single quotes. The value of a character constant is the integer value of the character in the machine's **character set**. For example, `'z'` represents the integer value of `z`, and `'\n'` the integer value of newline (122 and 10 in ASCII, respectively).

A **string** is a series of characters treated as a single unit. A string may include letters, digits and various **special characters** such as `+`, `-`, `*`, `/` and `$`. **String literals**, or **string constants**, in C are written in double quotation marks as follows:

|                                       |                      |
|---------------------------------------|----------------------|
| <code>"John Q. Doe"</code>            | (a name)             |
| <code>"99999 Main Street"</code>      | (a street address)   |
| <code>"Waltham, Massachusetts"</code> | (a city and state)   |
| <code>"(201) 555-1212"</code>         | (a telephone number) |

A string in C is an array of characters ending in the **null character** (`'\0'`). A string is accessed via a pointer to the first character in the string. The value of a string is the address

1. Pointers and pointer-based entities such as arrays and strings, when misused intentionally or accidentally, can lead to errors and security breaches. See our Secure C Programming Resource Center ([www.deitel.com/SecureC/](http://www.deitel.com/SecureC/)) for articles, books, white papers and forums on this important topic.

of its first character. Thus, in C, it is appropriate to say that a **string is a pointer**—in fact, a pointer to the string's first character. In this sense, strings are like arrays, because an array is also a pointer to its first element.

A character array or a variable of type `char *` can be initialized with a string in a definition. The definitions

```
char color[] = "blue";
const char *colorPtr = "blue";
```

each initialize a variable to the string "blue". The first definition creates a 5-element array `color` containing the characters 'b', 'l', 'u', 'e' and '\0'. The second definition creates pointer variable `colorPtr` that points to the string "blue" somewhere in memory.



### Portability Tip 8.1

*When a variable of type `char *` is initialized with a string literal, some compilers may place the string in a location in memory where the string cannot be modified. If you might need to modify a string literal, it should be stored in a character array to ensure modifiability on all systems.*

The preceding array definition could also have been written

```
char color[] = { 'b', 'l', 'u', 'e', '\0' };
```

When defining a character array to contain a string, the array must be large enough to store the string and its terminating null character. The preceding definition automatically determines the size of the array based on the number of initializers in the initializer list.



### Common Programming Error 8.1

*Not allocating sufficient space in a character array to store the null character that terminates a string is an error.*



### Common Programming Error 8.2

*Printing a "string" that does not contain a terminating null character is an error.*



### Error-Prevention Tip 8.1

*When storing a string of characters in a character array, be sure that the array is large enough to hold the largest string that will be stored. C allows strings of any length to be stored. If a string is longer than the character array in which it is to be stored, characters beyond the end of the array will overwrite data in memory following the array.*

A string can be stored in an array using `scanf`. For example, the following statement stores a string in character array `word[20]`:

```
scanf("%s", word);
```

The string entered by the user is stored in `word`. Variable `word` is an array, which is, of course, a pointer, so the `&` is not needed with argument `word`. Recall from Section 6.4 that function `scanf` will read characters until a space, tab, newline or end-of-file indicator is encountered. So, it is possible that the user input could exceed 19 characters and that your program might crash! For this reason, use the conversion specifier `%19s` so that `scanf` reads

up to 19 characters and saves the last character for the terminating null character. This prevents `scanf` from writing characters into memory beyond the end of `s`. (For reading input lines of arbitrary length, there is a nonstandard—yet widely supported—function `getline`, usually included in `stdio.h`.) For a character array to be printed as a string, the array must contain a terminating null character.



**Common Programming Error 8.3**

*Processing a single character as a string. A string is a pointer—probably a respectably large integer. However, a character is a small integer (ASCII values range 0–255). On many systems this causes an error, because low memory addresses are reserved for special purposes such as operating-system interrupt handlers—so “access violations” occur.*



**Common Programming Error 8.4**

*Passing a character as an argument to a function when a string is expected (and vice versa) is a compilation error.*

8.3 Character-Handling Library

The **character-handling library** (`<ctype.h>`) includes several functions that perform useful tests and manipulations of character data. Each function receives a character—represented as an `int`—or EOF as an argument. As we discussed in Chapter 4, characters are often manipulated as integers, because a character in C is usually a 1-byte integer. EOF normally has the value `-1`, and some hardware architectures do not allow negative values to be stored in `char` variables, so the character-handling functions manipulate characters as integers. Figure 8.1 summarizes the functions of the character-handling library.

| Prototype                           | Function description                                                                                                                                                                                                                                                                             |
|-------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>int isdigit( int c );</code>  | Returns a true value if <code>c</code> is a digit and 0 (false) otherwise.                                                                                                                                                                                                                       |
| <code>int isalpha( int c );</code>  | Returns a true value if <code>c</code> is a letter and 0 otherwise.                                                                                                                                                                                                                              |
| <code>int isalnum( int c );</code>  | Returns a true value if <code>c</code> is a digit or a letter and 0 otherwise.                                                                                                                                                                                                                   |
| <code>int isxdigit( int c );</code> | Returns a true value if <code>c</code> is a hexadecimal digit character and 0 otherwise. (See Appendix C, Number Systems, for a detailed explanation of binary numbers, octal numbers, decimal numbers and hexadecimal numbers.)                                                                 |
| <code>int islower( int c );</code>  | Returns a true value if <code>c</code> is a lowercase letter and 0 otherwise.                                                                                                                                                                                                                    |
| <code>int isupper( int c );</code>  | Returns a true value if <code>c</code> is an uppercase letter and 0 otherwise.                                                                                                                                                                                                                   |
| <code>int tolower( int c );</code>  | If <code>c</code> is an uppercase letter, <code>tolower</code> returns <code>c</code> as a lowercase letter. Otherwise, <code>tolower</code> returns the argument unchanged.                                                                                                                     |
| <code>int toupper( int c );</code>  | If <code>c</code> is a lowercase letter, <code>toupper</code> returns <code>c</code> as an uppercase letter. Otherwise, <code>toupper</code> returns the argument unchanged.                                                                                                                     |
| <code>int isspace( int c );</code>  | Returns a true value if <code>c</code> is a white-space character—newline ( <code>'\n'</code> ), space ( <code>' '</code> ), form feed ( <code>'\f'</code> ), carriage return ( <code>'\r'</code> ), horizontal tab ( <code>'\t'</code> ) or vertical tab ( <code>'\v'</code> )—and 0 otherwise. |

Fig. 8.1 | Character-handling library (`<ctype.h>`) functions. (Part 1 of 2.)

| Prototype                          | Function description                                                                                                             |
|------------------------------------|----------------------------------------------------------------------------------------------------------------------------------|
| <code>int iscntrl( int c );</code> | Returns a true value if <code>c</code> is a control character and 0 otherwise.                                                   |
| <code>int ispunct( int c );</code> | Returns a true value if <code>c</code> is a printing character other than a space, a digit, or a letter and returns 0 otherwise. |
| <code>int isprint( int c );</code> | Returns a true value if <code>c</code> is a printing character including a space ( ' ') and returns 0 otherwise.                 |
| <code>int isgraph( int c );</code> | Returns a true value if <code>c</code> is a printing character other than a space ( ' ') and returns 0 otherwise.                |

**Fig. 8.1** | Character-handling library (<ctype.h>) functions. (Part 2 of 2.)

### Functions *isdigit*, *isalpha*, *isalnum* and *isxdigit*

Figure 8.2 demonstrates functions `isdigit`, `isalpha`, `isalnum` and `isxdigit`. Function `isdigit` determines whether its argument is a digit (0–9). Function `isalpha` determines whether its argument is an uppercase (A–Z) or lowercase letter (a–z). Function `isalnum` determines whether its argument is an uppercase letter, a lowercase letter or a digit. Function `isxdigit` determines whether its argument is a **hexadecimal digit** (A–F, a–f, 0–9).

```

1 /* Fig. 8.2: fig08_02.c
2 Using functions isdigit, isalpha, isalnum, and isxdigit */
3 #include <stdio.h>
4 #include <ctype.h>
5
6 int main(void)
7 {
8 printf("%s\n%s\n\n", "According to isdigit: ",
9 isdigit('8') ? "8 is a " : "8 is not a ", "digit",
10 isdigit('#') ? "# is a " : "# is not a ", "digit");
11
12 printf("%s\n%s\n\n", "According to isalpha:",
13 isalpha('A') ? "A is a " : "A is not a ", "letter",
14 isalpha('b') ? "b is a " : "b is not a ", "letter",
15 isalpha('&') ? "& is a " : "& is not a ", "letter",
16 isalpha('4') ? "4 is a " : "4 is not a ", "letter");
17
18 printf("%s\n%s\n\n", "According to isalnum:",
19 isalnum('A') ? "A is a " : "A is not a ",
20 "digit or a letter",
21 isalnum('8') ? "8 is a " : "8 is not a ",
22 "digit or a letter",
23 isalnum('#') ? "# is a " : "# is not a ",
24 "digit or a letter");
25
26 printf("%s\n\n", "According to isxdigit:",
27 isxdigit('A') ? "A is a " : "A is not a ", "hexadecimal digit",
28 isxdigit('a') ? "a is a " : "a is not a ", "hexadecimal digit",
29 isxdigit('0') ? "0 is a " : "0 is not a ", "hexadecimal digit",
30 isxdigit('f') ? "f is a " : "f is not a ", "hexadecimal digit",
31 isxdigit('F') ? "F is a " : "F is not a ", "hexadecimal digit",
32 isxdigit('9') ? "9 is a " : "9 is not a ", "hexadecimal digit");
33 }
```

**Fig. 8.2** | Using `isdigit`, `isalpha`, `isalnum` and `isxdigit`. (Part 1 of 2.)

```

30 isxdigit('F') ? "F is a " : "F is not a ",
31 "hexadecimal digit",
32 isxdigit('J') ? "J is a " : "J is not a ",
33 "hexadecimal digit",
34 isxdigit('7') ? "7 is a " : "7 is not a ",
35 "hexadecimal digit",
36 isxdigit('$') ? "$ is a " : "$ is not a ",
37 "hexadecimal digit",
38 isxdigit('f') ? "f is a " : "f is not a ",
39 "hexadecimal digit");
40 return 0; /* indicates successful termination */
41 } /* end main */

```

According to isdigit:

8 is a digit  
# is not a digit

According to isalpha:

A is a letter  
b is a letter  
& is not a letter  
4 is not a letter

According to isalnum:

A is a digit or a letter  
8 is a digit or a letter  
# is not a digit or a letter

According to isxdigit:

F is a hexadecimal digit  
J is not a hexadecimal digit  
7 is a hexadecimal digit  
\$ is not a hexadecimal digit  
f is a hexadecimal digit

**Fig. 8.2** | Using isdigit, isalpha, isalnum and isxdigit. (Part 2 of 2.)

Figure 8.2 uses the conditional operator (?:) to determine whether the string " is a " or the string " is not a " should be printed in the output for each character tested. For example, the expression

```
isdigit('8') ? "8 is a " : "8 is not a "
```

indicates that if '8' is a digit, the string "8 is a " is printed, and if '8' is not a digit (i.e., isdigit returns 0), the string "8 is not a " is printed.

### ***Functions islower, isupper, tolower and toupper***

Figure 8.3 demonstrates functions **islower**, **isupper**, **tolower** and **toupper**. Function **islower** determines whether its argument is a lowercase letter (a–z). Function **isupper** determines whether its argument is an uppercase letter (A–Z). Function **tolower** converts an uppercase letter to a lowercase letter and returns the lowercase letter. If the argument is not an uppercase letter, **tolower** returns the argument unchanged. Function **toupper** converts a lowercase letter to an uppercase letter and returns the uppercase letter. If the argument is not a lowercase letter, **toupper** returns the argument unchanged.

```

1 /* Fig. 8.3: fig08_03.c
2 Using functions islower, isupper, tolower, toupper */
3 #include <stdio.h>
4 #include <ctype.h>
5
6 int main(void)
7 {
8 printf("%s\n%s\n%s\n%s\n%s\n%s\n",
9 "According to islower:",
10 islower('p') ? "p is a " : "p is not a ",
11 "lowercase letter",
12 islower('P') ? "P is a " : "P is not a ",
13 "lowercase letter",
14 islower('5') ? "5 is a " : "5 is not a ",
15 "lowercase letter",
16 islower('!') ? "! is a " : "! is not a ",
17 "lowercase letter");
18
19 printf("%s\n%s\n%s\n%s\n%s\n%s\n",
20 "According to isupper:",
21 isupper('D') ? "D is an " : "D is not an ",
22 "uppercase letter",
23 isupper('d') ? "d is an " : "d is not an ",
24 "uppercase letter",
25 isupper('8') ? "8 is an " : "8 is not an ",
26 "uppercase letter",
27 isupper('$') ? "$ is an " : "$ is not an ",
28 "uppercase letter");
29
30 printf("%s%c\n%s%c\n%s%c\n%s%c\n",
31 "u converted to uppercase is ", toupper('u'),
32 "7 converted to uppercase is ", toupper('7'),
33 "$ converted to uppercase is ", toupper('$'),
34 "L converted to lowercase is ", tolower('L'));
35 return 0; /* indicates successful termination */
36 } /* end main */

```

According to islower:  
p is a lowercase letter  
P is not a lowercase letter  
5 is not a lowercase letter  
! is not a lowercase letter

According to isupper:  
D is an uppercase letter  
d is not an uppercase letter  
8 is not an uppercase letter  
\$ is not an uppercase letter

u converted to uppercase is U  
7 converted to uppercase is 7  
\$ converted to uppercase is \$  
L converted to lowercase is l

**Fig. 8.3** | Using functions `islower`, `isupper`, `tolower` and `toupper`.

*Functions isspace, iscntrl, ispunct, isprint and isgraph*

Figure 8.4 demonstrates functions `isspace`, `iscntrl`, `ispunct`, `isprint` and `isgraph`. Function `isspace` determines if a character is one of the following white-space characters: space (' '), form feed ('\f'), newline ('\n'), carriage return ('\r'), horizontal tab ('\t') or vertical tab ('\v'). Function `iscntrl` determines if a character is one of the following **control characters**: horizontal tab ('\t'), vertical tab ('\v'), form feed ('\f'), alert ('\a'), backspace ('\b'), carriage return ('\r') or newline ('\n'). Function `ispunct` determines if a character is a **printing character** other than a space, a digit or a letter, such as \$, #, (, ), [, ], {, }, ;, : or %. Function `isprint` determines if a character can be displayed on the screen (including the space character). Function `isgraph` is the same as `isprint`, except that the space character is not included.

---

```

1 /* Fig. 8.4: fig08_04.c
2 Using functions isspace, iscntrl, ispunct, isprint, isgraph */
3 #include <stdio.h>
4 #include <ctype.h>
5
6 int main(void)
7 {
8 printf("%s\n%s\n%s\n%s\n%s\n",
9 "According to isspace:",
10 "Newline", isspace('\n') ? " is a " : " is not a ",
11 "whitespace character", "Horizontal tab",
12 isspace('\t') ? " is a " : " is not a ",
13 "whitespace character",
14 isspace('%') ? "% is a " : "% is not a ",
15 "whitespace character");
16
17 printf("%s\n%s\n%s\n%s\n", "According to iscntrl:",
18 "Newline", iscntrl('\n') ? " is a " : " is not a ",
19 "control character", iscntrl('$') ? "$ is a " :
20 "$ is not a ", "control character");
21
22 printf("%s\n%s\n%s\n%s\n",
23 "According to ispunct:",
24 ispunct(';') ? "; is a " : "; is not a ",
25 "punctuation character",
26 ispunct('Y') ? "Y is a " : "Y is not a ",
27 "punctuation character",
28 ispunct('#') ? "# is a " : "# is not a ",
29 "punctuation character");
30
31 printf("%s\n%s\n%s\n%s\n", "According to isprint:",
32 isprint('$') ? "$ is a " : "$ is not a ",
33 "printing character",
34 isprint('\a') ? " is a " : " is not a ",
35 "printing character");
36
37 printf("%s\n%s\n%s\n", "According to isgraph:",
38 isgraph('Q') ? "Q is a " : "Q is not a ",
39 "printing character other than a space",

```

---

**Fig. 8.4** | Using `isspace`, `iscntrl`, `ispunct`, `isprint` and `isgraph`. (Part I of 2.)

```

40 "Space", isgraph(' ') ? " is a " : " is not a ",
41 "printing character other than a space");
42 return 0; /* indicates successful termination */
43 } /* end main */

```

According to isspace:  
 Newline is a whitespace character  
 Horizontal tab is a whitespace character  
 % is not a whitespace character

According to iscntrl:  
 Newline is a control character  
 \$ is not a control character

According to ispunct:  
 ; is a punctuation character  
 Y is not a punctuation character  
 # is a punctuation character

According to isprint:  
 \$ is a printing character  
 Alert is not a printing character

According to isgraph:  
 Q is a printing character other than a space  
 Space is not a printing character other than a space

**Fig. 8.4** | Using isspace, iscntrl, ispunct, isprint and isgraph. (Part 2 of 2.)

## 8.4 String-Conversion Functions

This section presents the **string-conversion functions** from the **general utilities library** (`<stdlib.h>`). These functions convert strings of digits to integer and floating-point values. Figure 8.5 summarizes the string-conversion functions. Note the use of `const` to declare variable `nPtr` in the function headers (read from right to left as “`nPtr` is a pointer to a character constant”); `const` specifies that the argument value will not be modified.

| Function prototype                                                               | Function description                                    |
|----------------------------------------------------------------------------------|---------------------------------------------------------|
| <code>double atof( const char *nPtr );</code>                                    | Converts the string <code>nPtr</code> to double.        |
| <code>int atoi( const char *nPtr );</code>                                       | Converts the string <code>nPtr</code> to int.           |
| <code>long atol( const char *nPtr );</code>                                      | Converts the string <code>nPtr</code> to long int.      |
| <code>double strtod( const char *nPtr, char **endPtr );</code>                   | Converts the string <code>nPtr</code> to double.        |
| <code>long strtol( const char *nPtr, char **endPtr, int base );</code>           | Converts the string <code>nPtr</code> to long.          |
| <code>unsigned long strtoul( const char *nPtr, char **endPtr, int base );</code> | Converts the string <code>nPtr</code> to unsigned long. |

**Fig. 8.5** | String-conversion functions of the general utilities library.



**Function `atof`**

Function `atof` (Fig. 8.6) converts its argument—a string that represents a floating-point number—to a `double` value. The function returns the `double` value. If the converted value cannot be represented—for example, if the first character of the string is a letter—the behavior of function `atof` is undefined.

---

```

1 /* Fig. 8.6: fig08_06.c
2 Using atof */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 int main(void)
7 {
8 double d; /* variable to hold converted string */
9
10 d = atof("99.0");
11
12 printf("%s%.3f\n%s%.3f\n",
13 "The string \"99.0\" converted to double is ", d,
14 "The converted value divided by 2 is ", d / 2.0);
15 return 0; /* indicates successful termination */
16 } /* end main */

```

---

The string "99.0" converted to double is 99.000  
The converted value divided by 2 is 49.500

**Fig. 8.6** | Using `atof`.

**Function `atoi`**

Function `atoi` (Fig. 8.7) converts its argument—a string of digits that represents an integer—to an `int` value. The function returns the `int` value. If the converted value cannot be represented, the behavior of function `atoi` is undefined.

---

```

1 /* Fig. 8.7: fig08_07.c
2 Using atoi */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 int main(void)
7 {
8 int i; /* variable to hold converted string */
9
10 i = atoi("2593");
11
12 printf("%s%d\n%s%d\n",
13 "The string \"2593\" converted to int is ", i,
14 "The converted value minus 593 is ", i - 593);
15 return 0; /* indicates successful termination */
16 } /* end main */

```

---

**Fig. 8.7** | Using `atoi`. (Part I of 2.)

The string "2593" converted to int is 2593  
 The converted value minus 593 is 2000

**Fig. 8.7** | Using `atoi`. (Part 2 of 2.)

### Function `atoi`

Function `atoi` (Fig. 8.8) converts its argument—a string of digits representing a long integer—to a long value. The function returns the long value. If the converted value cannot be represented, the behavior of function `atoi` is undefined. If `int` and `long` are both stored in 4 bytes, function `atoi` and function `atol` work identically.

```

1 /* Fig. 8.8: fig08_08.c
2 Using atol */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 int main(void)
7 {
8 long l; /* variable to hold converted string */
9
10 l = atol("1000000");
11
12 printf("%s%d\n%s%d\n",
13 "The string \"1000000\" converted to long int is ", l,
14 "The converted value divided by 2 is ", l / 2);
15 return 0; /* indicates successful termination */
16 } /* end main */

```

The string "1000000" converted to long int is 1000000  
 The converted value divided by 2 is 500000

**Fig. 8.8** | Using `atol`.

### Function `strtod`

Function `strtod` (Fig. 8.9) converts a sequence of characters representing a floating-point value to `double`. The function receives two arguments—a string (`char *`) and a pointer to a string (`char **`). The string contains the character sequence to be converted to `double`. The pointer is assigned the location of the first character after the converted portion of the string. Line 14

```
d = strtod(string, &stringPtr);
```

indicates that `d` is assigned the `double` value converted from `string`, and `stringPtr` is assigned the location of the first character after the converted value (51.2) in `string`.

```

1 /* Fig. 8.9: fig08_09.c
2 Using strtod */
3 #include <stdio.h>

```

**Fig. 8.9** | Using `strtod`. (Part 1 of 2.)

```

4 #include <stdlib.h>
5
6 int main(void)
7 {
8 /* initialize string pointer */
9 const char *string = "51.2% are admitted"; /* initialize string */
10
11 double d; /* variable to hold converted sequence */
12 char *stringPtr; /* create char pointer */
13
14 d = strtod(string, &stringPtr);
15
16 printf("The string \"%s\" is converted to the\n", string);
17 printf("double value %.2f and the string \"%s\"\n", d, stringPtr);
18 return 0; /* indicates successful termination */
19 } /* end main */

```

The string "51.2% are admitted" is converted to the double value 51.20 and the string "% are admitted"

**Fig. 8.9** | Using `strtod`. (Part 2 of 2.)

### Function `strtol`

Function `strtol` (Fig. 8.10) converts to long a sequence of characters representing an integer. The function receives three arguments—a string (`char *`), a pointer to a string and an integer. The string contains the character sequence to be converted. The pointer is assigned the location of the first character after the converted portion of the string. The integer specifies the base of the value being converted. Line 13

```
x = strtol(string, &remainderPtr, 0);
```

indicates that `x` is assigned the long value converted from `string`. The second argument, `remainderPtr`, is assigned the remainder of `string` after the conversion. Using `NULL` for the second argument causes the remainder of the string to be ignored. The third argument, `0`, indicates that the value to be converted can be in octal (base 8), decimal (base 10) or hexadecimal (base 16) format. The base can be specified as `0` or any value between 2 and 36. See Appendix C, Number Systems, for a detailed explanation of the octal, decimal and hexadecimal number systems. Numeric representations of integers from base 11 to base 36 use the characters A–Z to represent the values 10 to 35. For example, hexadecimal values can consist of the digits 0–9 and the characters A–F. A base-11 integer can consist of the digits 0–9 and the character A. A base-24 integer can consist of the digits 0–9 and the characters A–N. A base-36 integer can consist of the digits 0–9 and the characters A–Z.

```

1 /* Fig. 8.10: fig08_10.c
2 Using strtol */
3 #include <stdio.h>
4 #include <stdlib.h>
5

```

**Fig. 8.10** | Using `strtol`. (Part 1 of 2.)

```

6 int main(void)
7 {
8 const char *string = "-1234567abc"; /* initialize string pointer */
9
10 char *remainderPtr; /* create char pointer */
11 long x; /* variable to hold converted sequence */
12
13 x = strtol(string, &remainderPtr, 0);
14
15 printf("%s\\\"%s\\\"\\n%s%ld\\n%s\\\"%s\\\"\\n%s%ld\\n",
16 "The original string is ", string,
17 "The converted value is ", x,
18 "The remainder of the original string is ",
19 remainderPtr,
20 "The converted value plus 567 is ", x + 567);
21 return 0; /* indicates successful termination */
22 } /* end main */

```

```

The original string is "-1234567abc"
The converted value is -1234567
The remainder of the original string is "abc"
The converted value plus 567 is -1234000

```

**Fig. 8.10** | Using `strtoul`. (Part 2 of 2.)

### Function `strtoul`

Function `strtoul` (Fig. 8.11) converts to unsigned long a sequence of characters representing an unsigned long integer. The function works identically to function `strtoul`. The statement

```
x = strtoul(string, &remainderPtr, 0);
```

in Fig. 8.11 indicates that `x` is assigned the unsigned long value converted from `string`. The second argument, `&remainderPtr`, is assigned the remainder of `string` after the conversion. The third argument, `0`, indicates that the value to be converted can be in octal, decimal or hexadecimal format.

```

1 /* Fig. 8.11: fig08_11.c
2 Using strtoul */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 int main(void)
7 {
8 const char *string = "1234567abc"; /* initialize string pointer */
9 unsigned long x; /* variable to hold converted sequence */
10 char *remainderPtr; /* create char pointer */
11
12 x = strtoul(string, &remainderPtr, 0);
13

```

**Fig. 8.11** | Using `strtoul`. (Part 1 of 2.)

```
14 printf("%s\\%s\\\"\\n%s%lu\\n%s\\\"%s\\\"\\n%s%lu\\n",
15 "The original string is ", string,
16 "The converted value is ", x,
17 "The remainder of the original string is ",
18 remainderPtr,
19 "The converted value minus 567 is ", x - 567);
20 return 0; /* indicates successful termination */
21 }
```

The original string is "1234567abc"  
The converted value is 1234567  
The remainder of the original string is "abc"  
The converted value minus 567 is 1234000

Fig. 8.11 | Using strtoul. (Part 2 of 2.)

### 8.5 Standard Input/Output Library Functions

This section presents several functions from the standard input/output library (`<stdio.h>`) specifically for manipulating character and string data. Figure 8.12 summarizes the character and string input/output functions of the standard input/output library.

| Function prototype                                            | Function description                                                                                                                                                                                                                                                                                                                                                                                                                                |
|---------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>int getchar( void );</code>                             | Inputs the next character from the standard input and returns it as an integer.                                                                                                                                                                                                                                                                                                                                                                     |
| <code>char *fgets( char *s, int n, FILE *stream);</code>      | Inputs characters from the specified stream into the array <code>s</code> until a newline or end-of-file character is encountered, or until <code>n - 1</code> bytes are read. In this chapter, we specify the stream as <code>stdin</code> —the standard input stream, which is typically used to read characters from the keyboard. A terminating null character is appended to the array. Returns the string that was read into <code>s</code> . |
| <code>int putchar( int c );</code>                            | Prints the character stored in <code>c</code> and returns it as an integer.                                                                                                                                                                                                                                                                                                                                                                         |
| <code>int puts( const char *s );</code>                       | Prints the string <code>s</code> followed by a newline character. Returns a non-zero integer if successful, or EOF if an error occurs.                                                                                                                                                                                                                                                                                                              |
| <code>int sprintf( char *s, const char *format, ... );</code> | Equivalent to <code>printf</code> , except the output is stored in the array <code>s</code> instead of printed on the screen. Returns the number of characters written to <code>s</code> , or EOF if an error occurs.                                                                                                                                                                                                                               |
| <code>int sscanf( char *s, const char *format, ... );</code>  | Equivalent to <code>scanf</code> , except the input is read from the array <code>s</code> rather than from the keyboard. Returns the number of items successfully read by the function, or EOF if an error occurs.                                                                                                                                                                                                                                  |

Fig. 8.12 | Standard input/output library character and string functions.

*Functions fgets and putchar*

Figure 8.13 uses functions `fgets` and `putchar` to read a line of text from the standard input (keyboard) and recursively output the characters of the line in reverse order. Function `fgets` reads characters from the standard input into its first argument—an array of chars—until a newline or the end-of-file indicator is encountered, or until the maximum number of characters is read. The maximum number of characters is one fewer than the value specified in `fgets`'s second argument. The third argument specifies the stream from which to read characters—in this case, we use the standard input stream (`stdin`). A null character (`'\0'`) is appended to the array when reading terminates. Function `putchar` prints its character argument. The program calls recursive function `reverse` to print the line of text backward. If the first character of the array received by `reverse` is the null character `'\0'`, `reverse` returns. Otherwise, `reverse` is called again with the address of the subarray beginning at element `s[1]`, and character `s[0]` is output with `putchar` when the recursive call is completed. The order of the two statements in the `else` portion of the `if` statement causes `reverse` to walk to the terminating null character of the string before a character is printed. As the recursive calls are completed, the characters are output in reverse order.

---

```

1 /* Fig. 8.13: fig08_13.c
2 Using gets and putchar */
3 #include <stdio.h>
4
5 void reverse(const char * const sPtr); /* prototype */
6
7 int main(void)
8 {
9 char sentence[80]; /* create char array */
10
11 printf("Enter a line of text:\n");
12
13 /* use fgets to read line of text */
14 fgets(sentence, 80, stdin);
15
16 printf("\nThe line printed backward is:\n");
17 reverse(sentence);
18 return 0; /* indicates successful termination */
19 } /* end main */
20
21 /* recursively outputs characters in string in reverse order */
22 void reverse(const char * const sPtr)
23 {
24 /* if end of the string */
25 if (sPtr[0] == '\0') { /* base case */
26 return;
27 } /* end if */
28 else { /* if not end of the string */
29 reverse(&sPtr[1]); /* recursion step */
30 putchar(sPtr[0]); /* use putchar to display character */
31 } /* end else */
32 } /* end function reverse */

```

---

**Fig. 8.13** | Using `fgets` and `putchar`. (Part I of 2.)

```
Enter a line of text:
Characters and Strings

The line printed backward is:
sgnirtS dna sretcarahC
```

```
Enter a line of text:
able was I ere I saw elba

The line printed backward is:
able was I ere I saw elba
```

**Fig. 8.13** | Using `fgets` and `putchar`. (Part 2 of 2.)

### *Functions `getchar` and `puts`*

Figure 8.14 uses functions `getchar` and `puts` to read characters from the standard input into character array `sentence` and print the array of characters as a string. Function `getchar` reads a character from the standard input and returns the character as an integer. Function `puts` takes a string (`char *`) as an argument and prints the string followed by a newline character. The program stops inputting characters when `getchar` reads the newline character entered by the user to end the line of text. A null character is appended to array `sentence` (line 19) so that the array may be treated as a string. Then, function `puts` prints the string contained in `sentence`.

```
1 /* Fig. 8.14: fig08_14.c
2 Using getchar and puts */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 char c; /* variable to hold character input by user */
8 char sentence[80]; /* create char array */
9 int i = 0; /* initialize counter i */
10
11 /* prompt user to enter line of text */
12 puts("Enter a line of text:");
13
14 /* use getchar to read each character */
15 while ((c = getchar()) != '\n') {
16 sentence[i++] = c;
17 } /* end while */
18
19 sentence[i] = '\0'; /* terminate string */
20
21 /* use puts to display sentence */
22 puts("\nThe line entered was:");
23 puts(sentence);
24 return 0; /* indicates successful termination */
25 } /* end main */
```

**Fig. 8.14** | Using `getchar` and `puts`. (Part 1 of 2.)

```
Enter a line of text:
This is a test.
```

```
The line entered was:
This is a test.
```

**Fig. 8.14** | Using `getchar` and `puts`. (Part 2 of 2.)

### Function `sprintf`

Figure 8.15 uses function `sprintf` to print formatted data into array `s`—an array of characters. The function uses the same conversion specifiers as `printf` (see Chapter 9 for a detailed discussion of formatting). The program inputs an `int` value and a `double` value to be formatted and printed to array `s`. Array `s` is the first argument of `sprintf`.

```
1 /* Fig. 8.15: fig08_15.c
2 Using sprintf */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 char s[80]; /* create char array */
8 int x; /* x value to be input */
9 double y; /* y value to be input */
10
11 printf("Enter an integer and a double:\n");
12 scanf("%d%lf", &x, &y);
13
14 sprintf(s, "integer:%6d\ndouble:%8.2f", x, y);
15
16 printf("%s\n%s\n",
17 "The formatted output stored in array s is:", s);
18 return 0; /* indicates successful termination */
19 } /* end main */
```

```
Enter an integer and a double:
298 87.375
The formatted output stored in array s is:
integer: 298
double: 87.38
```

**Fig. 8.15** | Using `sprintf`.

### Function `sscanf`

Figure 8.16 uses function `sscanf` to read formatted data from character array `s`. The function uses the same conversion specifiers as `scanf`. The program reads an `int` and a `double` from array `s` and stores the values in `x` and `y`, respectively. The values of `x` and `y` are printed. Array `s` is the first argument of `sscanf`.



```

1 /* Fig. 8.16: fig08_16.c
2 Using sscanf */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 char s[] = "31298 87.375"; /* initialize array s */
8 int x; /* x value to be input */
9 double y; /* y value to be input */
10
11 sscanf(s, "%d%lf", &x, &y);
12 printf("%s\n%s%6d\n%s%8.3f\n",
13 "The values stored in character array s are:",
14 "integer:", x, "double:", y);
15 return 0; /* indicates successful termination */
16 } /* end main */

```

The values stored in character array s are:  
integer: 31298  
double: 87.375

**Fig. 8.16** | Using `sscanf`.

## 8.6 String-Manipulation Functions of the String-Handling Library

The string-handling library (`<string.h>`) provides many useful functions for manipulating string data ([copying strings](#) and [concatenating strings](#)), [comparing strings](#), searching strings for characters and other strings, [tokenizing strings](#) (separating strings into logical pieces) and [determining the length of strings](#). This section presents the string-manipulation functions of the string-handling library. The functions are summarized in Fig. 8.17. Every function—except for `strncpy`—appends the null character to its result.

| Function prototype                                               | Function description                                                                                                                                           |
|------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>char *strcpy( char *s1, const char *s2 )</code>            | Copies string s2 into array s1. The value of s1 is returned.                                                                                                   |
| <code>char *strncpy( char *s1, const char *s2, size_t n )</code> | Copies at most n characters of string s2 into array s1. The value of s1 is returned.                                                                           |
| <code>char *strcat( char *s1, const char *s2 )</code>            | Appends string s2 to array s1. The first character of s2 overwrites the terminating null character of s1. The value of s1 is returned.                         |
| <code>char *strncat( char *s1, const char *s2, size_t n )</code> | Appends at most n characters of string s2 to array s1. The first character of s2 overwrites the terminating null character of s1. The value of s1 is returned. |

**Fig. 8.17** | String-manipulation functions of the string-handling library.

Functions `strncpy` and `strncat` specify a parameter of type `size_t`, which is a type defined by the C standard as the integral type of the value returned by operator `sizeof`.



### Portability Tip 8.2

Type `size_t` is a system-dependent synonym for either type `unsigned long` or type `unsigned int`.



### Error-Prevention Tip 8.2

When using functions from the string-handling library, include the `<string.h>` header.

Function `strncpy` copies its second argument (a string) into its first argument (a character array that must be large enough to store the string and its terminating null character, which is also copied). Function `strncpy` is equivalent to `strcpy`, except that `strncpy` specifies the number of characters to be copied from the string into the array. Function `strncpy` does not necessarily copy the terminating null character of its second argument. A terminating null character is written only if the number of characters to be copied is at least one more than the length of the string. For example, if "test" is the second argument, a terminating null character is written only if the third argument to `strncpy` is at least 5 (four characters in "test" plus a terminating null character). If the third argument is larger than 5, null characters are appended to the array until the total number of characters specified by the third argument are written.



### Common Programming Error 8.5

Not appending a terminating null character to the first argument of a `strncpy` when the third argument is less than or equal to the length of the string in the second argument.

### Functions `strcpy` and `strncpy`

Figure 8.18 uses `strcpy` to copy the entire string in array `x` into array `y` and uses `strncpy` to copy the first 14 characters of array `x` into array `z`. A null character ('\0') is appended to array `z`, because the call to `strncpy` in the program does not write a terminating null character (the third argument is less than the string length of the second argument).

```

1 /* Fig. 8.18: fig08_18.c
2 Using strcpy and strncpy */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 char x[] = "Happy Birthday to You"; /* initialize char array x */
9 char y[25]; /* create char array y */
10 char z[15]; /* create char array z */
11
12 /* copy contents of x into y */
13 printf("%s%s\n%s%s\n",
14 "The string in array x is: ", x,
15 "The string in array y is: ", strcpy(y, x));

```

**Fig. 8.18** | Using `strcpy` and `strncpy`. (Part I of 2.)

```

16
17 /* copy first 14 characters of x into z. Does not copy null
18 character */
19 strncpy(z, x, 14);
20
21 z[14] = '\0'; /* terminate string in z */
22 printf("The string in array z is: %s\n", z);
23 return 0; /* indicates successful termination */
24 } /* end main */

```

The string in array x is: Happy Birthday to You  
The string in array y is: Happy Birthday to You  
The string in array z is: Happy Birthday

**Fig. 8.18** | Using `strcpy` and `strncpy`. (Part 2 of 2.)

### Functions `strcat` and `strncat`

Function `strcat` appends its second argument (a string) to its first argument (a character array containing a string). The first character of the second argument replaces the null (`'\0'`) that terminates the string in the first argument. You must ensure that the array used to store the first string is large enough to store the first string, the second string and the terminating null character copied from the second string. Function `strncat` appends a specified number of characters from the second string to the first string. A terminating null character is automatically appended to the result. Figure 8.19 demonstrates function `strcat` and function `strncat`.

```

1 /* Fig. 8.19: fig08_19.c
2 Using strcat and strncat */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 char s1[20] = "Happy "; /* initialize char array s1 */
9 char s2[] = "New Year "; /* initialize char array s2 */
10 char s3[40] = ""; /* initialize char array s3 to empty */
11
12 printf("s1 = %s\ns2 = %s\n", s1, s2);
13
14 /* concatenate s2 to s1 */
15 printf("strcat(s1, s2) = %s\n", strcat(s1, s2));
16
17 /* concatenate first 6 characters of s1 to s3. Place '\0'
18 after last character */
19 printf("strncat(s3, s1, 6) = %s\n", strncat(s3, s1, 6));
20
21 /* concatenate s1 to s3 */
22 printf("strcat(s3, s1) = %s\n", strcat(s3, s1));
23 return 0; /* indicates successful termination */
24 } /* end main */

```

**Fig. 8.19** | Using `strcat` and `strncat`. (Part 1 of 2.)

```
s1 = Happy
s2 = New Year
strcat(s1, s2) = Happy New Year
strncat(s3, s1, 6) = Happy
strcat(s3, s1) = Happy Happy New Year
```

**Fig. 8.19** | Using `strcat` and `strncat`. (Part 2 of 2.)

## 8.7 Comparison Functions of the String-Handling Library

This section presents the string-handling library's [string-comparison functions](#), `strcmp` and `strncmp`. Fig. 8.20 contains their prototypes and a brief description of each function.

| Function prototype                                                    | Function description                                                                                                                                                                                                                                     |
|-----------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>int strcmp( const char *s1, const char *s2 );</code>            | Compares the string <code>s1</code> with the string <code>s2</code> . The function returns 0, less than 0 or greater than 0 if <code>s1</code> is equal to, less than or greater than <code>s2</code> , respectively.                                    |
| <code>int strncmp( const char *s1, const char *s2, size_t n );</code> | Compares up to <code>n</code> characters of the string <code>s1</code> with the string <code>s2</code> . The function returns 0, less than 0 or greater than 0 if <code>s1</code> is equal to, less than or greater than <code>s2</code> , respectively. |

**Fig. 8.20** | String-comparison functions of the string-handling library.

Figure 8.21 compares three strings using `strcmp` and `strncmp`. Function `strcmp` compares its first string argument with its second string argument, character by character. The function returns 0 if the strings are equal, a negative value if the first string is less than the second string and a positive value if the first string is greater than the second string. Function `strncmp` is equivalent to `strcmp`, except that `strncmp` compares up to a specified number of characters. Function `strncmp` does not compare characters following a null character in a string. The program prints the integer value returned by each function call.

```
1 /* Fig. 8.21: fig08_21.c
2 Using strcmp and strncmp */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 const char *s1 = "Happy New Year"; /* initialize char pointer */
9 const char *s2 = "Happy New Year"; /* initialize char pointer */
10 const char *s3 = "Happy Holidays"; /* initialize char pointer */
11
```

**Fig. 8.21** | Using `strcmp` and `strncmp`. (Part 1 of 2.)

```

12 printf("%s%s\n%s%s\n%s%s\n\n%s%2d\n%s%2d\n%s%2d\n\n",
13 "s1 = ", s1, "s2 = ", s2, "s3 = ", s3,
14 "strcmp(s1, s2) = ", strcmp(s1, s2),
15 "strcmp(s1, s3) = ", strcmp(s1, s3),
16 "strcmp(s3, s1) = ", strcmp(s3, s1));
17
18 printf("%s%2d\n%s%2d\n%s%2d\n",
19 "strncmp(s1, s3, 6) = ", strncmp(s1, s3, 6),
20 "strncmp(s1, s3, 7) = ", strncmp(s1, s3, 7),
21 "strncmp(s3, s1, 7) = ", strncmp(s3, s1, 7));
22 return 0; /* indicates successful termination */
23 } /* end main */

```

```

s1 = Happy New Year
s2 = Happy New Year
s3 = Happy Holidays

```

```

strcmp(s1, s2) = 0
strcmp(s1, s3) = 1
strcmp(s3, s1) = -1

```

```

strncmp(s1, s3, 6) = 0
strncmp(s1, s3, 7) = 6
strncmp(s3, s1, 7) = -6

```

**Fig. 8.21** | Using `strcmp` and `strncmp`. (Part 2 of 2.)



### Common Programming Error 8.6

*Assuming that `strcmp` and `strncmp` return 1 when their arguments are equal is a logic error. Both functions return 0 (strangely, the equivalent of C's false value) for equality. Therefore, when testing two strings for equality, the result of function `strcmp` or `strncmp` should be compared with 0 to determine if the strings are equal.*

To understand just what it means for one string to be “greater than” or “less than” another string, consider the process of alphabetizing a series of last names. The reader would, no doubt, place “Jones” before “Smith,” because the first letter of “Jones” comes before the first letter of “Smith” in the alphabet. But the alphabet is more than just a list of 26 letters—it is an ordered list of characters. Each letter occurs in a specific position within the list. “Z” is more than merely a letter of the alphabet; “Z” is specifically the 26<sup>th</sup> letter of the alphabet.

How does the computer know that one particular letter comes before another? All characters are represented inside the computer as **numeric codes**; when the computer compares two strings, it actually compares the numeric codes of the characters in the strings.



### Portability Tip 8.3

*The internal numeric codes used to represent characters may be different on different computers.*

In an effort to standardize character representations, most computer manufacturers have designed their machines to utilize one of two popular coding schemes—**ASCII** or **EBCDIC**. ASCII stands for “American Standard Code for Information Interchange,” and

EBCDIC stands for “Extended Binary Coded Decimal Interchange Code.” There are other coding schemes, but these two are the most popular. The Unicode® Standard outlines a specification to produce consistent encoding of the vast majority of the world’s characters and symbols. To learn more about Unicode, visit [www.unicode.org](http://www.unicode.org).

ASCII, EBCDIC and Unicode are called **character sets**. String and character manipulations actually involve the manipulation of the appropriate numeric codes and not the characters themselves. This explains the interchangeability of characters and small integers in C. Since it is meaningful to say that one numeric code is greater than, less than or equal to another numeric code, it becomes possible to relate various characters or strings to one another by referring to the character codes. Appendix B lists the ASCII character codes.

## 8.8 Search Functions of the String-Handling Library

This section presents the functions of the string-handling library used to search strings for characters and other strings. The functions are summarized in Fig. 8.22. The functions `strcspn` and `strspn` return `size_t`.

### Function prototype and description

**char** \*strchr( **const char** \*s, **int** c );

Locates the first occurrence of character `c` in string `s`. If `c` is found, a pointer to `c` in `s` is returned. Otherwise, a NULL pointer is returned.

**size\_t** strcspn( **const char** \*s1, **const char** \*s2 );

Determines and returns the length of the initial segment of string `s1` consisting of characters *not* contained in string `s2`.

**size\_t** strspn( **const char** \*s1, **const char** \*s2 );

Determines and returns the length of the initial segment of string `s1` consisting only of characters contained in string `s2`.

**char** \*strpbrk( **const char** \*s1, **const char** \*s2 );

Locates the first occurrence in string `s1` of any character in string `s2`. If a character from string `s2` is found, a pointer to the character in string `s1` is returned. Otherwise, a NULL pointer is returned.

**char** \*strrchr( **const char** \*s, **int** c );

Locates the last occurrence of `c` in string `s`. If `c` is found, a pointer to `c` in string `s` is returned. Otherwise, a NULL pointer is returned.

**char** \*strstr( **const char** \*s1, **const char** \*s2 );

Locates the first occurrence in string `s1` of string `s2`. If the string is found, a pointer to the string in `s1` is returned. Otherwise, a NULL pointer is returned.

**char** \*strtok( **char** \*s1, **const char** \*s2 );

A sequence of calls to `strtok` breaks string `s1` into “tokens”—logical pieces such as words in a line of text—separated by characters contained in string `s2`. The first call contains `s1` as the first argument, and subsequent calls to continue tokenizing the same string contain NULL as the first argument. A pointer to the current token is returned by each call. If there are no more tokens when the function is called, NULL is returned.

**Fig. 8.22** | String-manipulation functions of the string-handling library.

**Function strchr**

Function **strchr** searches for the first occurrence of a character in a string. If the character is found, **strchr** returns a pointer to the character in the string; otherwise, **strchr** returns NULL. Figure 8.23 uses **strchr** to search for the first occurrences of 'a' and 'z' in the string "This is a test".

---

```

1 /* Fig. 8.23: fig08_23.c
2 Using strchr */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 const char *string = "This is a test"; /* initialize char pointer */
9 char character1 = 'a'; /* initialize character1 */
10 char character2 = 'z'; /* initialize character2 */
11
12 /* if character1 was found in string */
13 if (strchr(string, character1) != NULL) {
14 printf("'%c' was found in \"%s\".\n",
15 character1, string);
16 } /* end if */
17 else { /* if character1 was not found */
18 printf("'%c' was not found in \"%s\".\n",
19 character1, string);
20 } /* end else */
21
22 /* if character2 was found in string */
23 if (strchr(string, character2) != NULL) {
24 printf("'%c' was found in \"%s\".\n",
25 character2, string);
26 } /* end if */
27 else { /* if character2 was not found */
28 printf("'%c' was not found in \"%s\".\n",
29 character2, string);
30 } /* end else */
31
32 return 0; /* indicates successful termination */
33 } /* end main */

```

```

'a' was found in "This is a test".
'z' was not found in "This is a test".

```

**Fig. 8.23** | Using **strchr**.

**Function strcspn**

Function **strcspn** (Fig. 8.24) determines the length of the initial part of the string in its first argument that does not contain any characters from the string in its second argument. The function returns the length of the segment.

```

1 /* Fig. 8.24: fig08_24.c
2 Using strcspn */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 /* initialize two char pointers */
9 const char *string1 = "The value is 3.14159";
10 const char *string2 = "1234567890";
11
12 printf("%s\n%s\n\n%s\n%s\n",
13 "string1 = ", string1, "string2 = ", string2,
14 "The length of the initial segment of string1",
15 "containing no characters from string2 = ",
16 strcspn(string1, string2));
17 return 0; /* indicates successful termination */
18 } /* end main */

```

```

string1 = The value is 3.14159
string2 = 1234567890

```

```

The length of the initial segment of string1
containing no characters from string2 = 13

```

**Fig. 8.24** | Using `strcspn`.

### Function `strpbrk`

Function `strpbrk` searches its first string argument for the first occurrence of any character in its second string argument. If a character from the second argument is found, `strpbrk` returns a pointer to the character in the first argument; otherwise, `strpbrk` returns `NULL`. Figure 8.25 shows a program that locates the first occurrence in `string1` of any character from `string2`.

```

1 /* Fig. 8.25: fig08_25.c
2 Using strpbrk */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 const char *string1 = "This is a test"; /* initialize char pointer */
9 const char *string2 = "beware"; /* initialize char pointer */
10
11 printf("%s\n%s\n\n%c'%s\n\n%s\n\n",
12 "Of the characters in ", string2,
13 *strpbrk(string1, string2),
14 " appears earliest in ", string1);
15 return 0; /* indicates successful termination */
16 } /* end main */

```

**Fig. 8.25** | Using `strpbrk`. (Part I of 2.)



Of the characters in "beware"  
'a' appears earliest in  
"This is a test"

**Fig. 8.25** | Using `strpbrk`. (Part 2 of 2.)

### Function `strrchr`

Function `strrchr` searches for the last occurrence of the specified character in a string. If the character is found, `strrchr` returns a pointer to the character in the string; otherwise, `strrchr` returns `NULL`. Figure 8.26 shows a program that searches for the last occurrence of the character 'z' in the string "A zoo has many animals including zebras."

```

1 /* Fig. 8.26: fig08_26.c
2 Using strrchr */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 /* initialize char pointer */
9 const char *string1 = "A zoo has many animals including zebras";
10
11 int c = 'z'; /* character to search for */
12
13 printf("%s\n%s'%c'%s\n%s\n",
14 "The remainder of string1 beginning with the",
15 "last occurrence of character ", c,
16 " is: ", strrchr(string1, c));
17 return 0; /* indicates successful termination */
18 } /* end main */

```

The remainder of string1 beginning with the  
last occurrence of character 'z' is: "zebras"

**Fig. 8.26** | Using `strrchr`.

### Function `strspn`

Function `strspn` (Fig. 8.27) determines the length of the initial part of the string in its first argument that contains only characters from the string in its second argument. The function returns the length of the segment.

```

1 /* Fig. 8.27: fig08_27.c
2 Using strspn */
3 #include <stdio.h>
4 #include <string.h>
5

```

**Fig. 8.27** | Using `strspn`. (Part 1 of 2.)

```

6 int main(void)
7 {
8 /* initialize two char pointers */
9 const char *string1 = "The value is 3.14159";
10 const char *string2 = "aehi lsTuv";
11
12 printf("%s%s\n%s%s\n\n%s\n\n%su\n",
13 "string1 = ", string1, "string2 = ", string2,
14 "The length of the initial segment of string1",
15 "containing only characters from string2 = ",
16 strspn(string1, string2));
17 return 0; /* indicates successful termination */
18 } /* end main */

```

```

string1 = The value is 3.14159
string2 = aehi lsTuv

The length of the initial segment of string1
containing only characters from string2 = 13

```

**Fig. 8.27** | Using `strspn`. (Part 2 of 2.)

### Function `strstr`

Function `strstr` searches for the first occurrence of its second string argument in its first string argument. If the second string is found in the first string, a pointer to the location of the string in the first argument is returned. Figure 8.28 uses `strstr` to find the string "def" in the string "abcdefabcdef".

```

1 /* Fig. 8.28: fig08_28.c
2 Using strstr */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 const char *string1 = "abcdefabcdef"; /* string to search */
9 const char *string2 = "def"; /* string to search for */
10
11 printf("%s%s\n%s%s\n\n%s\n\n%s%s\n",
12 "string1 = ", string1, "string2 = ", string2,
13 "The remainder of string1 beginning with the",
14 "first occurrence of string2 is: ",
15 strstr(string1, string2));
16 return 0; /* indicates successful termination */
17 } /* end main */

```

```

string1 = abcdefabcdef
string2 = def

The remainder of string1 beginning with the
first occurrence of string2 is: defabcdef

```

**Fig. 8.28** | Using `strstr`.

**Function strtok**

Function `strtok` (Fig. 8.29) is used to break a string into a series of **tokens**. A token is a sequence of characters separated by **delimiters** (usually spaces or punctuation marks, but a delimiter can be any character). For example, in a line of text, each word can be considered a token, and the spaces and punctuation separating the words can be considered delimiters.

---

```

1 /* Fig. 8.29: fig08_29.c
2 Using strtok */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 /* initialize array string */
9 char string[] = "This is a sentence with 7 tokens";
10 char *tokenPtr; /* create char pointer */
11
12 printf("%s\n%s\n\n%s\n",
13 "The string to be tokenized is:", string,
14 "The tokens are:");
15
16 tokenPtr = strtok(string, " "); /* begin tokenizing sentence */
17
18 /* continue tokenizing sentence until tokenPtr becomes NULL */
19 while (tokenPtr != NULL) {
20 printf("%s\n", tokenPtr);
21 tokenPtr = strtok(NULL, " "); /* get next token */
22 } /* end while */
23
24 return 0; /* indicates successful termination */
25 } /* end main */

```

```

The string to be tokenized is:
This is a sentence with 7 tokens

```

```

The tokens are:
This
is
a
sentence
with
7
tokens

```

**Fig. 8.29** | Using `strtok`.

Multiple calls to `strtok` are required to tokenize a string—i.e., break it into tokens (assuming that the string contains more than one token). The first call to `strtok` contains two arguments: a string to be tokenized, and a string containing characters that separate the tokens. In Fig. 8.29, the statement

```
tokenPtr = strtok(string, " "); /* begin tokenizing sentence */
```

assigns `tokenPtr` a pointer to the first token in `string`. The second argument, " ", indicates that tokens are separated by spaces. Function `strtok` searches for the first character in `string` that is not a delimiting character (space). This begins the first token. The function then finds the next delimiting character in the string and replaces it with a null (`'\0'`) character to terminate the current token. Function `strtok` saves a pointer to the next character following the token in `string` and returns a pointer to the current token.

Subsequent `strtok` calls in line 21 continue tokenizing `string`. These calls contain `NULL` as their first argument. The `NULL` argument indicates that the call to `strtok` should continue tokenizing from the location in `string` saved by the last call to `strtok`. If no tokens remain when `strtok` is called, `strtok` returns `NULL`. You can change the delimiter string in each new call to `strtok`. Figure 8.29 uses `strtok` to tokenize the string "This is a sentence with 7 tokens". Each token is printed separately. Function `strtok` modifies the input string by placing `\0` at the end of each token; therefore, a copy of the string should be made if the string will be used again in the program after the calls to `strtok`.

## 8.9 Memory Functions of the String-Handling Library

The string-handling library functions presented in this section manipulate, compare and search blocks of memory. The functions treat blocks of memory as character arrays and can manipulate any block of data. Figure 8.30 summarizes the memory functions of the string-handling library. In the function discussions, "object" refers to a block of data.

| Function prototype                                                   | Function description                                                                                                                                                                                                                                                                                                                                                                              |
|----------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>void *memcpy( void *s1, const void *s2, size_t n );</code>     | Copies <code>n</code> characters from the object pointed to by <code>s2</code> into the object pointed to by <code>s1</code> . A pointer to the resulting object is returned.                                                                                                                                                                                                                     |
| <code>void *memmove( void *s1, const void *s2, size_t n );</code>    | Copies <code>n</code> characters from the object pointed to by <code>s2</code> into the object pointed to by <code>s1</code> . The copy is performed as if the characters were first copied from the object pointed to by <code>s2</code> into a temporary array and then from the temporary array into the object pointed to by <code>s1</code> . A pointer to the resulting object is returned. |
| <code>int memcmp( const void *s1, const void *s2, size_t n );</code> | Compares the first <code>n</code> characters of the objects pointed to by <code>s1</code> and <code>s2</code> . The function returns 0, less than 0 or greater than 0 if <code>s1</code> is equal to, less than or greater than <code>s2</code> .                                                                                                                                                 |
| <code>void *memchr( const void *s, int c, size_t n );</code>         | Locates the first occurrence of <code>c</code> (converted to unsigned char) in the first <code>n</code> characters of the object pointed to by <code>s</code> . If <code>c</code> is found, a pointer to <code>c</code> in the object is returned. Otherwise, <code>NULL</code> is returned.                                                                                                      |
| <code>void *memset( void *s, int c, size_t n );</code>               | Copies <code>c</code> (converted to unsigned char) into the first <code>n</code> characters of the object pointed to by <code>s</code> . A pointer to the result is returned.                                                                                                                                                                                                                     |

**Fig. 8.30** | Memory functions of the string-handling library.

The pointer parameters to these functions are declared `void *` so they can be used to manipulate memory for any data type. In Chapter 7, we saw that a pointer to any data type can be assigned directly to a pointer of type `void *`, and a pointer of type `void *` can be assigned directly to a pointer to any data type. For this reason, these functions can receive pointers to any data type. Because a `void *` pointer cannot be dereferenced, each function receives a size argument that specifies the number of characters (bytes) the function will process. For simplicity, the examples in this section manipulate character arrays (blocks of characters).

### Function `memcpy`

Function `memcpy` copies a specified number of characters from the object pointed to by its second argument into the object pointed to by its first argument. The function can receive a pointer to any type of object. The result of this function is undefined if the two objects overlap in memory (i.e., if they are parts of the same object)—in such cases, use `memmove`. Figure 8.31 uses `memcpy` to copy the string in array `s2` to array `s1`.

```

1 /* Fig. 8.31: fig08_31.c
2 Using memcpy */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 char s1[17]; /* create char array s1 */
9 char s2[] = "Copy this string"; /* initialize char array s2 */
10
11 memcpy(s1, s2, 17);
12 printf("%s\n%s\n%s\n",
13 "After s2 is copied into s1 with memcpy,",
14 "s1 contains ", s1);
15 return 0; /* indicates successful termination */
16 } /* end main */

```

After `s2` is copied into `s1` with `memcpy`,  
`s1` contains "Copy this string"

**Fig. 8.31** | Using `memcpy`.

### Function `memmove`

Function `memmove`, like `memcpy`, copies a specified number of bytes from the object pointed to by its second argument into the object pointed to by its first argument. Copying is performed as if the bytes were copied from the second argument into a temporary character array, then copied from the temporary array into the first argument. This allows characters from one part of a string to be copied into another part of the same string. Figure 8.32 uses `memmove` to copy the last 10 bytes of array `x` into the first 10 bytes of array `x`.



### Common Programming Error 8.7

*String-manipulation functions other than `memmove` that copy characters have undefined results when copying takes place between parts of the same string.*

```

1 /* Fig. 8.32: fig08_32.c
2 Using memmove */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 char x[] = "Home Sweet Home"; /* initialize char array x */
9
10 printf("%s\n", "The string in array x before memmove is: ", x);
11 printf("%s\n", "The string in array x after memmove is: ",
12 memmove(x, &x[5], 10));
13 return 0; /* indicates successful termination */
14 } /* end main */

```

The string in array x before memmove is: Home Sweet Home  
The string in array x after memmove is: Sweet Home Home

**Fig. 8.32** | Using `memmove`.

#### Function `memcmp`

Function `memcmp` (Fig. 8.33) compares the specified number of characters of its first argument with the corresponding characters of its second argument. The function returns a value greater than 0 if the first argument is greater than the second, returns 0 if the arguments are equal and returns a value less than 0 if the first argument is less than the second.

```

1 /* Fig. 8.33: fig08_33.c
2 Using memcmp */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 char s1[] = "ABCDEFGFG"; /* initialize char array s1 */
9 char s2[] = "ABCDXYZ"; /* initialize char array s2 */
10
11 printf("%s\n%s\n\n%s2d\n%s2d\n%s2d\n",
12 "s1 = ", s1, "s2 = ", s2,
13 "memcmp(s1, s2, 4) = ", memcmp(s1, s2, 4),
14 "memcmp(s1, s2, 7) = ", memcmp(s1, s2, 7),
15 "memcmp(s2, s1, 7) = ", memcmp(s2, s1, 7));
16 return 0; /* indicate successful termination */
17 } /* end main */

```

s1 = ABCDEFG  
s2 = ABCDXYZ

memcmp( s1, s2, 4 ) = 0  
memcmp( s1, s2, 7 ) = -1  
memcmp( s2, s1, 7 ) = 1

**Fig. 8.33** | Using `memcmp`.

*Function memchr*

Function **memchr** searches for the first occurrence of a byte, represented as unsigned char, in the specified number of bytes of an object. If the byte is found, a pointer to the byte in the object is returned; otherwise, a NULL pointer is returned. Figure 8.34 searches for the character (byte) 'r' in the string "This is a string".

---

```

1 /* Fig. 8.34: fig08_34.c
2 Using memchr */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 const char *s = "This is a string"; /* initialize char pointer */
9
10 printf("%s\\'%c\\'%s\\'%s\\'\\n",
11 "The remainder of s after character ", 'r',
12 " is found is ", memchr(s, 'r', 16));
13 return 0; /* indicates successful termination */
14 } /* end main */

```

---

The remainder of s after character 'r' is found is "ring"

**Fig. 8.34** | Using **memchr**.

*Function memset*

Function **memset** copies the value of the byte in its second argument into the first *n* bytes of the object pointed to by its first argument, where *n* is specified by the third argument. Figure 8.35 uses **memset** to copy 'b' into the first 7 bytes of **string1**.

---

```

1 /* Fig. 8.35: fig08_35.c
2 Using memset */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 char string1[15] = "BBBBBBBBBBBBBB"; /* initialize string1 */
9
10 printf("string1 = %s\\n", string1);
11 printf("string1 after memset = %s\\n", memset(string1, 'b', 7));
12 return 0; /* indicates successful termination */
13 } /* end main */

```

---

string1 = BBBBBBBBBBBBBB  
string1 after memset = bbbbbbbBBBBBBB

**Fig. 8.35** | Using **memset**.

## 8.10 Other Functions of the String-Handling Library

The two remaining functions of the string-handling library are `strerror` and `strlen`. Figure 8.36 summarizes the `strerror` and `strlen` functions.

| Function prototype                           | Function description                                                                                                                                                                                          |
|----------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>char *strerror( int errornum );</code> | Maps <code>errornum</code> into a full text string in a compiler- and locale-specific manner (e.g. the message may appear in different languages based on its location). A pointer to the string is returned. |
| <code>size_t strlen( const char *s );</code> | Determines the length of string <code>s</code> . The number of characters preceding the terminating null character is returned.                                                                               |

**Fig. 8.36** | Other functions of the string-handling library.

### Function `strerror`

Function `strerror` takes an error number and creates an error message string. A pointer to the string is returned. Figure 8.37 demonstrates `strerror`.

```

1 /* Fig. 8.37: fig08_37.c
2 Using strerror */
3 #include <stdio.h>
4 #include <string.h>
5
6 int main(void)
7 {
8 printf("%s\n", strerror(2));
9 return 0; /* indicates successful termination */
10 } /* end main */

```

No such file or directory

**Fig. 8.37** | Using `strerror`.

### Function `strlen`

Function `strlen` takes a string as an argument and returns the number of characters in the string—the terminating null character is not included in the length. Figure 8.38 demonstrates function `strlen`.

```

1 /* Fig. 8.38: fig08_38.c
2 Using strlen */
3 #include <stdio.h>
4 #include <string.h>

```

**Fig. 8.38** | Using `strlen`. (Part I of 2.)



```

5
6 int main(void)
7 {
8 /* initialize 3 char pointers */
9 const char *string1 = "abcdefghijklmnopqrstuvwxy";
10 const char *string2 = "four";
11 const char *string3 = "Boston";
12
13 printf("%s\\\"%s\\\"%s%lu\\n%s\\\"%s\\\"%s%lu\\n%s\\\"%s\\\"%s%lu\\n",
14 "The length of ", string1, " is ",
15 (unsigned long) strlen(string1),
16 "The length of ", string2, " is ",
17 (unsigned long) strlen(string2),
18 "The length of ", string3, " is ",
19 (unsigned long) strlen(string3));
20 return 0; /* indicates successful termination */
21 } /* end main */

```

```

The length of "abcdefghijklmnopqrstuvwxy" is 26
The length of "four" is 4
The length of "Boston" is 6

```

**Fig. 8.38** | Using `strlen`. (Part 2 of 2.)

## Summary

### Section 8.2 Fundamentals of Strings and Characters

- Characters are the fundamental building blocks of source programs. Every program is composed of a sequence of characters that—when grouped together meaningfully—is interpreted by the computer as a series of instructions used to accomplish a task.
- A character constant is an `int` value represented as a character in single quotes. The value of a character constant is the character's integer value in the machine's character set.
- A string is a series of characters treated as a single unit. A string may include letters, digits and various special characters such as `+`, `-`, `*`, `/` and `$`. String literals, or string constants, in C are written in double quotation marks.
- A string in C is an array of characters ending in the null character (`'\0'`).
- A string is accessed via a pointer to its first character. The value of a string is the address of its first character.
- A character array or a variable of type `char *` can be initialized with a string in a definition.
- When defining a character array to contain a string, the array must be large enough to store the string and its terminating null character.
- A string can be stored in an array using `scanf`. Function `scanf` will read characters until a space, tab, newline or end-of-file indicator is encountered.
- For a character array to be printed as a string, the array must contain a terminating null character.

### Section 8.3 Character-Handling Library

- Function `islower` determines whether its argument is a lowercase letter (a–z).
- Function `isupper` determines whether its argument is an uppercase letter (A–Z).

- Function `isdigit` determines whether its argument is a digit (0–9).
- Function `isalpha` determines whether its argument is an uppercase letter (A–Z) or a lowercase letter (a–z).
- Function `isalnum` determines whether its argument is an uppercase letter (A–Z), a lowercase letter (a–z) or a digit (0–9).
- Function `isxdigit` determines whether its argument is a hexadecimal digit (A–F, a–f, 0–9).
- Function `toupper` converts a lowercase letter to uppercase and returns the uppercase letter.
- Function `tolower` converts an uppercase letter to lowercase and returns the lowercase letter.
- Function `isspace` determines whether its argument is one of the following white-space characters: ' ' (space), '\f', '\n', '\r', '\t' or '\v'.
- Function `iscntrl` determines whether its argument is one of the following control characters: '\t', '\v', '\f', '\a', '\b', '\r' or '\n'.
- Function `ispunct` determines whether its argument is a printing character other than a space, a digit or a letter.
- Function `isprint` determines whether its argument is any printing character including the space character.
- Function `isgraph` determines whether its argument is a printing character other than the space character.

#### *Section 8.4 String-Conversion Functions*

- Function `atof` converts its argument—a string beginning with a series of digits that represents a floating-point number—to a `double` value.
- Function `atoi` converts its argument—a string beginning with a series of digits that represents an integer—to an `int` value.
- Function `atol` converts its argument—a string beginning with a series of digits that represents a long integer—to a `long` value.
- Function `strtod` converts a sequence of characters representing a floating-point value to `double`. The function receives two arguments—a string (`char *`) and a pointer to `char *`. The string contains the character sequence to be converted, and the location specified by the pointer to `char *` is assigned the address of the remainder of the string after the conversion.
- Function `strtol` converts a sequence of characters representing an integer to `long`. The function receives three arguments—a string (`char *`), a pointer to `char *` and an integer. The string contains the character sequence to be converted, the location specified by the pointer to `char *` is assigned the address of the remainder of the string after the conversion and the integer specifies the base of the value being converted.
- Function `strtoul` converts a sequence of characters representing an integer to unsigned `long`. The function receives three arguments—a string (`char *`), a pointer to `char *` and an integer. The string contains the character sequence to be converted, the location specified by the pointer to `char *` is assigned the address of the remainder of the string after the conversion and the integer specifies the base of the value being converted.

#### *Section 8.5 Standard Input/Output Library Functions*

- Function `fgets` reads characters until a newline character or the end-of-file indicator is encountered. The arguments to `fgets` are an array of type `char`, the maximum number of characters that can be read and the stream from which to read. A null character ('\0') is appended to the array after reading terminates.
- Function `putchar` prints its character argument.

- Function `getchar` reads a single character from the standard input and returns the character as an integer. If the end-of-file indicator is encountered, `getchar` returns `EOF`.
- Function `puts` takes a string (`char *`) as an argument and prints the string followed by a newline character.
- Function `sprintf` uses the same conversion specifications as function `printf` to print formatted data into an array of type `char`.
- Function `sscanf` uses the same conversion specifications as function `scanf` to read formatted data from a string.

### *Section 8.6 String-Manipulation Functions of the String-Handling Library*

- Function `strcpy` copies its second argument (a string) into its first argument (a character array). You must ensure that the array is large enough to store the string and its terminating null character.
- Function `strncpy` is equivalent to `strcpy`, except that a call to `strncpy` specifies the number of characters to be copied from the string into the array. The terminating null character will be copied only if the number of characters to be copied is one more than the length of the string.
- Function `strcat` appends its second string argument—including the terminating null character—to its first string argument. The first character of the second string replaces the null (`'\0'`) character of the first string. You must ensure that the array used to store the first string is large enough to store both the first string and the second string.
- Function `strncat` appends a specified number of characters from the second string to the first string. A terminating null character is appended to the result.

### *Section 8.7 Comparison Functions of the String-Handling Library*

- Function `strcmp` compares its first string argument to its second string argument, character by character. It returns 0 if the strings are equal, returns a negative value if the first string is less than the second and returns a positive value if the first string is greater than the second.
- Function `strncmp` is equivalent to `strcmp`, except that `strncmp` compares a specified number of characters. If one of the strings is shorter than the number of characters specified, `strncmp` compares characters until the null character in the shorter string is encountered.

### *Section 8.8 Search Functions of the String-Handling Library*

- Function `strchr` searches for the first occurrence of a character in a string. If the character is found, `strchr` returns a pointer to the character in the string; otherwise, `strchr` returns `NULL`.
- Function `strcspn` determines the length of the initial part of the string in its first argument that does not contain any characters from the string in its second argument. The function returns the length of the segment.
- Function `strpbrk` searches for the first occurrence in its first argument of any character in its second argument. If a character from the second argument is found, `strpbrk` returns a pointer to the character; otherwise, `strpbrk` returns `NULL`.
- Function `strrchr` searches for the last occurrence of a character in a string. If the character is found, `strrchr` returns a pointer to the character in the string; otherwise, `strrchr` returns `NULL`.
- Function `strspn` determines the length of the initial part of the string in its first argument that contains only characters from the string in its second argument. The function returns the length of the segment.
- Function `strstr` searches for the first occurrence of its second string argument in its first string argument. If the second string is found in the first string, a pointer to the location of the string in the first argument is returned.

- A sequence of calls to `strtok` breaks the first string `s1` into tokens that are separated by characters contained in the second string `s2`. The first call contains `s1` as the first argument, and subsequent calls to continue tokenizing the same string contain `NULL` as the first argument. A pointer to the current token is returned by each call. If there are no more tokens when the function is called, a `NULL` pointer is returned.

### *Section 8.9 Memory Functions of the String-Handling Library*

- Function `memcpy` copies a specified number of characters from the object to which its second argument points into the object to which its first argument points. The function can receive a pointer to any type of object. Function `memcpy` manipulates the bytes of the object as characters.
- Function `memmove` copies a specified number of bytes from the object pointed to by its second argument to the object pointed to by its first argument. Copying is accomplished as if the bytes were copied from the second argument to a temporary character array and then copied from the temporary array to the first argument.
- Function `memcmp` compares the specified number of characters of its first and second arguments.
- Function `memchr` searches for the first occurrence of a byte, represented as unsigned char, in the specified number of bytes of an object. If the byte is found, a pointer to the byte is returned; otherwise, a `NULL` pointer is returned.
- Function `memset` copies its second argument, treated as an unsigned char, to a specified number of bytes of the object pointed to by the first argument.

### *Section 8.10 Other Functions of the String-Handling Library*

- Function `strerror` maps an integer error number into a full text string in a locale specific manner. A pointer to the string is returned.
- Function `strlen` takes a string as an argument and returns the number of characters in the string—the terminating null character is not included in the length of the string.

## Terminology

ASCII (American Standard Code for Information Interchange) 330  
`atof` function 318  
`atoi` function 318  
`atol` function 319  
character constant 310  
character-handling library 312  
character set 310  
comparing string 326  
concatenating strings 326  
control characters 316  
copying string 326  
delimiter 336  
determining the length of string 326  
EBCDIC (Extended Binary Coded Decimal Interchange Code) 330  
`fgets` function 323  
general utilities library (`<stdlib.h>`) 317  
`getchar` function 324  
hexadecimal 313  
`isalnum` function 313

`isalpha` function 313  
`isctr1` function 316  
`isdigit` function 313  
`isgraph` function 316  
`islower` function 314  
`isprint` function 316  
`ispunct` function 316  
`isspace` function 316  
`isupper` function 314  
`isxdigit` function 313  
`memchr` function 340  
`memcmp` function 339  
`memcpy` function 338  
`memmove` function 338  
`memset` function 340  
null character (`'\0'`) 310  
numeric code 330  
printing character 316  
`putchar` function 323  
`puts` function 324  
special character 310

|                                |                        |
|--------------------------------|------------------------|
| sprintf function 325           | strlen function 341    |
| sscanf function 325            | strncat function 327   |
| <stdio.h> header 322           | strncmp function 329   |
| <stdlib.h> header 317          | strncpy function 327   |
| strcat function 328            | strpbrk function 333   |
| strchr function 332            | strrchr function 334   |
| strcmp function 329            | strstr function 335    |
| strcspn function 332           | strtod function 319    |
| strerror function 341          | strtok function 336    |
| string 310                     | strtol function 320    |
| string comparison function 329 | strtoul function 321   |
| string constant 310            | token 336              |
| string-conversion function 317 | tokenizing strings 326 |
| string is a pointer 311        | tolower function 314   |
| string literal 310             | toupper function 314   |

## Self-Review Exercises

**8.1** Write a single statement to accomplish each of the following. Assume that variables *c* (which stores a character), *x*, *y* and *z* are of type *int*, variables *d*, *e* and *f* are of type *double*, variable *ptr* is of type *char \** and arrays *s1*[100] and *s2*[100] are of type *char*.

- Convert the character stored in variable *c* to an uppercase letter. Assign the result to variable *c*.
- Determine if the value of variable *c* is a digit. Use the conditional operator as shown in Figs. 8.2–8.4 to print " is a " or " is not a " when the result is displayed.
- Convert the string "1234567" to *long* and print the value.
- Determine if the value of variable *c* is a control character. Use the conditional operator to print " is a " or " is not a " when the result is displayed.
- Read a line of text into array *s1* from the keyboard. Do not use *scanf*.
- Print the line of text stored in array *s1*. Do not use *printf*.
- Assign *ptr* the location of the last occurrence of *c* in *s1*.
- Print the value of variable *c*. Do not use *printf*.
- Convert the string "8.63582" to *double* and print the value.
- Determine if the value of *c* is a letter. Use the conditional operator to print " is a " or " is not a " when the result is displayed.
- Read a character from the keyboard and store the character in variable *c*.
- Assign *ptr* the location of the first occurrence of *s2* in *s1*.
- Determine if the value of variable *c* is a printing character. Use the conditional operator to print " is a " or " is not a " when the result is displayed.
- Read three *double* values into variables *d*, *e* and *f* from the string "1.27 10.3 9.432".
- Copy the string stored in array *s2* into array *s1*.
- Assign *ptr* the location of the first occurrence in *s1* of any character from *s2*.
- Compare the string in *s1* with the string in *s2*. Print the result.
- Assign *ptr* the location of the first occurrence of *c* in *s1*.
- Use *sprintf* to print the values of integer variables *x*, *y* and *z* into array *s1*. Each value should be printed with a field width of 7.
- Append 10 characters from the string in *s2* to the string in *s1*.
- Determine the length of the string in *s1*. Print the result.
- Convert the string "-21" to *int* and print the value.
- Assign *ptr* to the location of the first token in *s2*. Tokens in the string *s2* are separated by commas (,).

**8.2** Show two different methods of initializing character array `vowel` with the string of vowels "AEIOU".

**8.3** What, if anything, prints when each of the following C statements is performed? If the statement contains an error, describe the error and indicate how to correct it. Assume the following variable definitions:

```
char s1[50] = "jack", s2[50] = " jill", s3[50], *sptr;

a) printf("%c%s", toupper(s1[0]), &s1[1]);
b) printf("%s", strcpy(s3, s2));
c) printf("%s", strcat(strcat(strcpy(s3, s1), " and "), s2));
d) printf("%u", strlen(s1) + strlen(s2));
e) printf("%u", strlen(s3));
```

**8.4** Find the error in each of the following program segments and explain how to correct it:

```
a) char s[10];
 strncpy(s, "hello", 5);
 printf("%s\n", s);
b) printf("%s", 'a');
c) char s[12];
 strcpy(s, "Welcome Home");
d) if (strcmp(string1, string2)) {
 printf("The strings are equal\n");
}
```

## Answers to Self-Review Exercises

- 8.1**
- a) `c = toupper( c );`
  - b) `printf( "%c'%sdigit'\n", c, isdigit( c ) ? " is a " : " is not a " );`
  - c) `printf( "%ld\n", atol( "1234567" ) );`
  - d) `printf( "%c'%scontrol character'\n",`  
`c, iscntrl( c ) ? " is a " : " is not a " );`
  - e) `fgets( s1, 100, stdin );`
  - f) `puts( s1 );`
  - g) `ptr = strchr( s1, c );`
  - h) `putchar( c );`
  - i) `printf( "%f\n", atof( "8.63582" ) );`
  - j) `printf( "%c'%sletter'\n", c, isalpha( c ) ? " is a " : " is not a " );`
  - k) `c = getchar();`
  - l) `ptr = strstr( s1, s2 );`
  - m) `printf( "%c'%sprinting character'\n",`  
`c, isprint( c ) ? " is a " : " is not a " );`
  - n) `sscanf( "1.27 10.3 9.432", "%f%f%f", &d, &e, &f );`
  - o) `strcpy( s1, s2 );`
  - p) `ptr = strpbrk( s1, s2 );`
  - q) `printf( "strcmp( s1, s2 ) = %d\n", strcmp( s1, s2 ) );`
  - r) `ptr = strchr( s1, c );`
  - s) `sprintf( s1, "%7d%7d%7d", x, y, z );`
  - t) `strncat( s1, s2, 10 );`
  - u) `printf( "strlen(s1) = %u\n", strlen( s1 ) );`
  - v) `printf( "%d\n", atoi( "-21" ) ); *`
  - w) `ptr = strtok( s2, ", " );`

**8.2** `char vowel[] = "AEIOU";`  
`char vowel[] = { 'A', 'E', 'I', 'O', 'U', '\0' };`

- 8.3**
- a) Jack
  - b) jill
  - c) jack and jill
  - d) 8
  - e) 13

- 8.4**
- a) Error: Function `strncpy` does not write a terminating null character to array `s`, because its third argument is equal to the length of the string "hello".  
Correction: Make the third argument of `strncpy` 6, or assign `'\0'` to `s[5]`.
  - b) Error: Attempting to print a character constant as a string.  
Correction: Use `%c` to output the character, or replace `'a'` with `"a"`.
  - c) Error: Character array `s` is not large enough to store the terminating null character.  
Correction: Declare the array with more elements.
  - d) Error: Function `strcmp` returns 0 if the strings are equal; therefore, the condition in the `if` statement is false, and the `printf` will not be executed.  
Correction: Compare the result of `strcmp` with 0 in the condition.

## Exercises

**8.5** (*Character Testing*) Write a program that inputs a character from the keyboard and tests the character with each of the functions in the character-handling library. The program should print the value returned by each function.

**8.6** (*Displaying Strings in Uppercase and Lowercase*) Write a program that inputs a line of text into char array `s[100]`. Output the line in uppercase letters and in lowercase letters.

**8.7** (*Converting Strings to Integers for Calculations*) Write a program that inputs four strings that represent integers, converts the strings to integers, sums the values and prints the total of the four values.

**8.8** (*Converting Strings to Floating Point for Calculations*) Write a program that inputs four strings that represent floating-point values, converts the strings to double values, sums the values and prints the total of the four values.

**8.9** (*Comparing Strings*) Write a program that uses function `strcmp` to compare two strings input by the user. The program should state whether the first string is less than, equal to or greater than the second string.

**8.10** (*Comparing Portions of Strings*) Write a program that uses function `strncmp` to compare two strings input by the user. The program should input the number of characters to be compared, then display whether the first string is less than, equal to or greater than the second string.

**8.11** (*Random Sentences*) Write a program that uses random number generation to create sentences. The program should use four arrays of pointers to char called `article`, `noun`, `verb` and `preposition`. The program should create a sentence by selecting a word at random from each array in the following order: `article`, `noun`, `verb`, `preposition`, `article` and `noun`. As each word is picked, it should be concatenated to the previous words in an array large enough to hold the entire sentence. The words should be separated by spaces. When the final sentence is output, it should start with a capital letter and end with a period. The program should generate 20 such sentences. The arrays should be filled as follows: The `article` array should contain the articles "the", "a", "one", "some" and "any"; the `noun` array should contain the nouns "boy", "girl", "dog", "town" and "car"; the `verb` array should contain the verbs "drove", "jumped", "ran", "walked" and "skipped"; the `preposition` array should contain the prepositions "to", "from", "over", "under" and "on".

After the preceding program is written and working, modify it to produce a short story consisting of several of these sentences. (How about the possibility of a random term paper writer?)

**8.12 (Limericks)** A limerick is a humorous five-line verse in which the first and second lines rhyme with the fifth, and the third line rhymes with the fourth. Using techniques similar to those developed in Exercise 8.11, write a program that produces random limericks. Polishing this program to produce good limericks is a challenging problem, but the result will be worth the effort!

**8.13 (Pig Latin)** Write a program that encodes English-language phrases into pig Latin. Pig Latin is a form of coded language often used for amusement. Many variations exist in the methods used to form pig-Latin phrases. For simplicity, use the following algorithm:

To form a pig-Latin phrase from an English-language phrase, tokenize the phrase into words with function `strtok`. To translate each English word into a pig-Latin word, place the first letter of the English word at the end of the English word and add the letters “ay.” Thus the word “jump” becomes “umpjay,” the word “the” becomes “hetay” and the word “computer” becomes “omputer-cay.” Blanks between words remain as blanks. Assume the following: The English phrase consists of words separated by blanks, there are no punctuation marks, and all words have two or more letters. Function `printLatinWord` should display each word. [Hint: Each time a token is found in a call to `strtok`, pass the token pointer to function `printLatinWord`, and print the pig-Latin word. Note: We’ve provided simplified rules for converting words to Pig Latin here. For more detailed rules and variations, visit [en.wikipedia.org/wiki/Pig\\_Latin](http://en.wikipedia.org/wiki/Pig_Latin).]

**8.14 (Tokenizing Telephone Numbers)** Write a program that inputs a telephone number as a string in the form (555) 555-5555. The program should use function `strtok` to extract the area code as a token, the first three digits of the phone number as a token and the last four digits of the phone number as a token. The seven digits of the phone number should be concatenated into one string. The program should convert the area-code string to `int` and convert the phone-number string to `long`. Both the area code and the phone number should be printed.

**8.15 (Displaying a Sentence with Its Words Reversed)** Write a program that inputs a line of text, tokenizes the line with function `strtok` and outputs the tokens in reverse order.

**8.16 (Searching for Substrings)** Write a program that inputs a line of text and a search string from the keyboard. Using function `strstr`, locate the first occurrence of the search string in the line of text, and assign the location to variable `searchPtr` of type `char *`. If the search string is found, print the remainder of the line of text beginning with the search string. Then, use `strstr` again to locate the next occurrence of the search string in the line of text. If a second occurrence is found, print the remainder of the line of text beginning with the second occurrence. [Hint: The second call to `strstr` should contain `searchPtr + 1` as its first argument.]

**8.17 (Counting the Occurrences of a Substring)** Write a program based on the program of Exercise 8.16 that inputs several lines of text and a search string and uses function `strstr` to determine the total occurrences of the string in the lines of text. Print the result.

**8.18 (Counting the Occurrences of a Character)** Write a program that inputs several lines of text and a search character and uses function `strchr` to determine the total occurrences of the character in the lines of text.

**8.19 (Counting the Letters of the Alphabet in a String)** Write a program based on the program of Exercise 8.18 that inputs several lines of text and uses function `strchr` to determine the total occurrences of each letter of the alphabet in the lines of text. Uppercase and lowercase letters should be counted together. Store the totals for each letter in an array and print the values in tabular format after the totals have been determined.

**8.20 (Counting the Number of Words in a String)** Write a program that inputs several lines of text and uses `strtok` to count the total number of words. Assume that the words are separated by either spaces or newline characters.



**8.21** (*Alphabetizing a List of Strings*) Use the string-comparison functions discussed in Section 8.6 and the techniques for sorting arrays developed in Chapter 6 to write a program that alphabetizes a list of strings. Use the names of 10 or 15 towns in your area as data for your program.

**8.22** The chart in Appendix B shows the numeric code representations for the characters in the ASCII character set. Study this chart and then state whether each of the following is *true* or *false*.

- The letter “A” comes before the letter “B.”
- The digit “9” comes before the digit “0.”
- The commonly used symbols for addition, subtraction, multiplication and division all come before any of the digits.
- The digits come before the letters.
- If a sort program sorts strings into ascending sequence, then the program will place the symbol for a right parenthesis before the symbol for a left parenthesis.

**8.23** (*Strings Starting with “b”*) Write a program that reads a series of strings and prints only those strings beginning with the letter “b.”

**8.24** (*Strings Ending with “ed”*) Write a program that reads a series of strings and prints only those strings that end with the letters “ed.”

**8.25** (*Printing Letters for Various ASCII Codes*) Write a program that inputs an ASCII code and prints the corresponding character. Modify this program so that it generates all possible three-digit codes in the range 000 to 255 and attempts to print the corresponding characters. What happens when this program is run?

**8.26** (*Write Your Own Character-Handling Functions*) Using the ASCII character chart in Appendix B as a guide, write your own versions of the character-handling functions in Fig. 8.1.

**8.27** (*Write Your String Conversion Functions*) Write your own versions of the functions in Fig. 8.5 for converting strings to numbers.

**8.28** (*Write Your Own String Copy and Concatenation Functions*) Write two versions of each of the string-copy and string-concatenation functions in Fig. 8.17. The first version should use array subscripting, and the second version should use pointers and pointer arithmetic.

**8.29** (*Write Your Own Character and String I/O Functions*) Write your own versions of the functions `getchar`, `putchar` and `puts` described in Fig. 8.12.

**8.30** (*Write Your Own String Comparison Functions*) Write two versions of each string-comparison function in Fig. 8.20. The first version should use array subscripting, and the second version should use pointers and pointer arithmetic.

**8.31** (*Write Your Own String Searching Functions*) Write your own versions of the functions in Fig. 8.22 for searching strings.

**8.32** (*Write Your Own Memory-Handling Functions*) Write your own versions of the functions in Fig. 8.30 for manipulating blocks of memory.

**8.33** (*Write Your Own String Length Function*) Write two versions of function `strlen` in Fig. 8.36. The first version should use array subscripting, and the second version should use pointers and pointer arithmetic.

## Special Section: Advanced String-Manipulation Exercises

The preceding exercises are keyed to the text and designed to test the reader’s understanding of fundamental string-manipulation concepts. This section includes a collection of intermediate and advanced problems. The reader should find these problems challenging yet enjoyable. The problems vary considerably in difficulty. Some require an hour or two of program writing and

implementation. Others are useful for lab assignments that might require two or three weeks of study and implementation. Some are challenging term projects.

**8.34 (Text Analysis)** The availability of computers with string-manipulation capabilities has resulted in some rather interesting approaches to analyzing the writings of great authors. Much attention has been focused on whether William Shakespeare ever lived. Some scholars find substantial evidence that Christopher Marlowe actually penned the masterpieces attributed to Shakespeare. Researchers have used computers to find similarities in the writings of these two authors. This exercise examines three methods for analyzing texts with a computer.

- a) Write a program that reads several lines of text and prints a table indicating the number of occurrences of each letter of the alphabet in the text. For example, the phrase

To be, or not to be: that is the question:

contains one “a,” two “b’s,” no “c’s,” and so on.

- b) Write a program that reads several lines of text and prints a table indicating the number of one-letter words, two-letter words, three-letter words, and so on, appearing in the text. For example, the phrase

Whether 'tis nobler in the mind to suffer

contains

| Word length | Occurrences        |
|-------------|--------------------|
| 1           | 0                  |
| 2           | 2                  |
| 3           | 1                  |
| 4           | 2 (including 'tis) |
| 5           | 0                  |
| 6           | 2                  |
| 7           | 1                  |

- c) Write a program that reads several lines of text and prints a table indicating the number of occurrences of each different word in the text. The first version of your program should include the words in the table in the same order in which they appear in the text. A more interesting (and useful) printout should then be attempted in which the words are sorted alphabetically. For example, the lines

To be, or not to be: that is the question:

Whether 'tis nobler in the mind to suffer

contain the words “to” three times, the word “be” two times, the word “or” once, and so on.

**8.35 (Word Processing)** The detailed treatment of string manipulation in this text is largely attributable to the exciting growth in word processing in recent years. One important function in word-processing systems is *type justification*—the alignment of words to both the left and right margins of a page. This generates a professional-looking document that gives the appearance of being set in type, rather than prepared on a typewriter. Type justification can be accomplished on computer systems by inserting one or more blank characters between each of the words in a line so that the rightmost word aligns with the right margin.

Write a program that reads several lines of text and prints this text in type-justified format. Assume that the text is to be printed on 8 1/2-inch-wide paper and that one-inch margins are to be

allowed on both the left and right sides of the printed page. Assume that the computer prints 10 characters to the horizontal inch. Therefore, your program should print 6 1/2 inches of text or 65 characters per line.

**8.36** (*Printing Dates in Various Formats*) Dates are commonly printed in several different formats in business correspondence. Two of the more common formats are

07/21/2003 and July 21, 2003

Write a program that reads a date in the first format and prints it in the second format.

**8.37** (*Check Protection*) Computers are frequently used in check-writing systems, such as payroll and accounts payable applications. Many stories circulate regarding weekly paychecks being printed (by mistake) for amounts in excess of \$1 million. Weird amounts are printed by computerized check-writing systems because of human error and/or machine failure. Systems designers, of course, make every effort to build controls into their systems to prevent erroneous checks from being issued.

Another serious problem is the intentional alteration of a check amount by someone who intends to cash it fraudulently. To prevent a dollar amount from being altered, most computerized check-writing systems employ a technique called *check protection*.

Checks designed for imprinting by computer contain a fixed number of spaces in which the computer may print an amount. Suppose a paycheck contains nine blank spaces in which the computer is supposed to print the amount of a weekly paycheck. If the amount is large, then all nine of those spaces will be filled—for example:

```
11,230.60 (check amount)

123456789 (position numbers)
```

On the other hand, if the amount is less than \$1000, then several of the spaces will ordinarily be left blank—for example,

```
99.87

123456789
```

contains four blank spaces. If a check is printed with blank spaces, it is easier for someone to alter the amount of the check. To prevent a check from being altered, many check-writing systems insert *leading asterisks* to protect the amount as follows:

```
****99.87

123456789
```

Write a program that inputs a dollar amount to be printed on a check and then prints the amount in check-protected format with leading asterisks if necessary. Assume that nine spaces are available for printing an amount.

**8.38** (*Writing the Word Equivalent of a Check Amount*) Continuing the discussion of the previous example, we reiterate the importance of designing check-writing systems to prevent alteration of check amounts. One common security method requires that the check amount be both written in numbers and “spelled out” in words. Even if someone is able to alter the numerical amount of the check, it is extremely difficult to change the amount in words.

Many computerized check-writing systems do not print the amount of the check in words. Perhaps the main reason for this omission is the fact that most high-level languages used in commercial applications do not contain adequate string-manipulation features. Another reason is that the logic for writing word equivalents of check amounts is somewhat involved.

Write a program that inputs a numeric check amount and writes the word equivalent of the amount. For example, the amount 112.43 should be written as

ONE HUNDRED TWELVE and 43/100

**8.39 (Morse Code)** Perhaps the most famous of all coding schemes is Morse code, developed by Samuel Morse in 1832 for use with the telegraph system. Morse code assigns a series of dots and dashes to each letter of the alphabet, each digit, and a few special characters (such as period, comma, colon and semicolon). In sound-oriented systems, the dot represents a short sound and the dash represents a long sound. Other representations of dots and dashes are used with light-oriented systems and signal-flag systems.

Separation between words is indicated by a space—quite simply, the absence of a dot or dash. In a sound-oriented system, a space is indicated by a short period of time during which no sound is transmitted. The international version of Morse code appears in Fig. 8.39.

| Character | Code | Character | Code  | Character     | Code   |
|-----------|------|-----------|-------|---------------|--------|
| A         | .-   | N         | -.    | <i>Digits</i> |        |
| B         | -... | O         | ---   | 1             | .....  |
| C         | -.-. | P         | .-.-  | 2             | ..---- |
| D         | -..  | Q         | --.-  | 3             | ...--  |
| E         | .    | R         | .-.   | 4             | ....-  |
| F         | ..-. | S         | ...   | 5             | .....  |
| G         | --.  | T         | -     | 6             | -....  |
| H         | .... | U         | ..-   | 7             | --...  |
| I         | ..   | V         | ...-  | 8             | ----.  |
| J         | .... | W         | .-.-  | 9             | ----.  |
| K         | -.-  | X         | -.-.- | 0             | -----  |
| L         | .-.. | Y         | -.--  |               |        |
| M         | --   | Z         | --..  |               |        |

**Fig. 8.39** | The letters of the alphabet as expressed in international Morse code.

Write a program that reads an English-language phrase and encodes the phrase into Morse code. Also write a program that reads a phrase in Morse code and converts the phrase into the English-language equivalent. Use one blank between each Morse-coded letter and three blanks between each Morse-coded word.

**8.40 (A Metric Conversion Program)** Write a program that will assist the user with metric conversions. Your program should allow the user to specify the names of the units as strings (i.e., centimeters, liters, grams, and so on for the metric system and inches, quarts, pounds, and so on for the English system) and should respond to simple questions such as

"How many inches are in 2 meters?"  
 "How many liters are in 10 quarts?"

Your program should recognize invalid conversions. For example, the question

"How many feet in 5 kilograms?"

is not meaningful, because "feet" are units of length while "kilograms" are units of mass.

**8.41 (Dunning Letters)** Many businesses spend a great deal of time and money collecting overdue debts. *Dunning* is the process of making repeated and insistent demands upon a debtor in an attempt to collect a debt.

Computers are often used to generate dunning letters automatically and in increasing degrees of severity as a debt ages. The theory is that as a debt becomes older, it becomes more difficult to collect, and therefore the dunning letters must become more threatening.

Write a program that contains the texts of five dunning letters of increasing severity. Your program should accept as input the following:

- a) Debtor's name
- b) Debtor's address
- c) Debtor's account
- d) Amount owed
- e) Age of the amount owed (i.e., one month overdue, two months overdue, and so on).

Use the age of the amount owed to select one of the five message texts, and then print the dunning letter, inserting the other user-supplied information where appropriate.

## A Challenging String-Manipulation Project

**8.42** (*A Crossword-Puzzle Generator*) Most people have worked a crossword puzzle at one time or another, but few have ever attempted to generate one. Generating a crossword puzzle is a difficult problem. It is suggested here as a string-manipulation project requiring substantial sophistication and effort. There are many issues you must resolve to get even the simplest crossword-puzzle generator program working. For example, how does one represent the grid of a crossword puzzle inside the computer? Should one use a series of strings, or should double-subscripted arrays be used? You need a source of words (i.e., a computerized dictionary) that can be directly referenced by the program. In what form should these words be stored to facilitate the complex manipulations required by the program? The really ambitious reader will want to generate the “clues” portion of the puzzle in which the brief hints for each “across” word and each “down” word are printed for the puzzle worker. Merely printing a version of the blank puzzle itself is not a simple problem.

## Making a Difference

**8.43** (*Cooking with Healthier Ingredients*) Obesity in America is increasing at an alarming rate. Check the map from the Centers for Disease Control and Prevention (CDC) at [www.cdc.gov/nccdphp/dnpa/Obesity/trend/maps/index.htm](http://www.cdc.gov/nccdphp/dnpa/Obesity/trend/maps/index.htm), which shows obesity trends in the United States over the last 20 years. As obesity increases, so do occurrences of related problems (e.g., heart disease, high blood pressure, high cholesterol, type 2 diabetes). Write a program that helps users choose healthier ingredients when cooking, and helps those allergic to certain foods (e.g., nuts, gluten) find substitutes. The program should read a recipe from the user and suggest healthier replacements for some of the ingredients. For simplicity, your program should assume the recipe has no abbreviations for measures such as teaspoons, cups, and tablespoons, and uses numerical digits for quantities (e.g., 1 egg, 2 cups) rather than spelling them out (one egg, two cups). Some common substitutions are shown in Fig. 8.40. Your program should display a warning such as, “Always consult your physician before making significant changes to your diet.”

Your program should take into consideration that replacements are not always one-for-one. For example, if a cake recipe calls for three eggs, it might reasonably use six egg whites instead. Conversion data for measurements and substitutes can be obtained at websites such as:

[chinesefood.about.com/od/recipeconversionfaqs/f/usmetricrecipes.htm](http://chinesefood.about.com/od/recipeconversionfaqs/f/usmetricrecipes.htm)  
[www.pioneerthinking.com/eggsub.html](http://www.pioneerthinking.com/eggsub.html)  
[www.gourmetsleuth.com/conversions.htm](http://www.gourmetsleuth.com/conversions.htm)

Your program should consider the user's health concerns, such as high cholesterol, high blood pressure, weight loss, gluten allergy, and so on. For high cholesterol, the program should suggest substitutes for eggs and dairy products; if the user wishes to lose weight, low-calorie substitutes for ingredients such as sugar should be suggested.

| Ingredient             | Substitution                                                                                                       |
|------------------------|--------------------------------------------------------------------------------------------------------------------|
| 1 cup sour cream       | 1 cup yogurt                                                                                                       |
| 1 cup milk             | 1/2 cup evaporated milk and 1/2 cup water                                                                          |
| 1 teaspoon lemon juice | 1/2 teaspoon vinegar                                                                                               |
| 1 cup sugar            | 1/2 cup honey, 1 cup molasses<br>or 1/4 cup agave nectar                                                           |
| 1 cup butter           | 1 cup margarine or yogurt                                                                                          |
| 1 cup flour            | 1 cup rye or rice flour                                                                                            |
| 1 cup mayonnaise       | 1 cup cottage cheese<br>or 1/8 cup mayonnaise and 7/8 cup yogurt                                                   |
| 1 egg                  | 2 tablespoons cornstarch, arrowroot flour<br>or potato starch or 2 egg whites<br>or 1/2 of a large banana (mashed) |
| 1 cup milk             | 1 cup soy milk                                                                                                     |
| 1/4 cup oil            | 1/4 cup applesauce                                                                                                 |
| white bread            | whole-grain bread                                                                                                  |

**Fig. 8.40** | Typical ingredient substitutes.

**8.44** (*Spam Scanner*) Spam (or junk e-mail) costs U.S. organizations billions of dollars a year in spam-prevention software, equipment, network resources, bandwidth, and lost productivity. Research online some of the most common spam e-mail messages and words, and check your own junk e-mail folder. Create a list of 30 words and phrases commonly found in spam messages. Write a program in which the user enters an e-mail message. Read the message into a large character array and ensure that the program does not attempt to insert characters past the end of the array. Then, scan the message for each of the 30 keywords or phrases. For each occurrence of one of these within the message, add a point to the message's "spam score." Next, rate the likelihood that the message is spam, based on the number of points it received.

**8.45** (*SMS Language*) Short Message Service (SMS) is a communications service that allows sending text messages of 160 or fewer characters between mobile phones. With the proliferation of mobile phone use worldwide, SMS is being used in many developing nations for political purposes (e.g., voicing opinions and opposition), reporting news about natural disasters, and so on. For example, check out [comunica.org/radio2.0/archives/87](http://comunica.org/radio2.0/archives/87). Since the length of SMS messages is limited, SMS Language—abbreviations of common words and phrases in mobile text messages, e-mails, instant messages, etc.—is often used. For example, "in my opinion" is "IMO" in SMS Language. Research SMS Language online. Write a program in which the user can enter a message using SMS Language, then the program translates it into English (or your own language). Also provide a mechanism to translate text written in English (or your own language) into SMS Language. One potential problem is that one SMS abbreviation could expand into a variety of phrases. For example, IMO (as used above) could also stand for "International Maritime Organization," "in memory of," etc.

**8.46** (*Gender-Neutrality*) In Exercise 1.12, you researched eliminating sexism in all forms of communication. You then described the algorithm you'd use to read through a paragraph of text and replace gender-specific words with gender-neutral equivalents. Create a program that reads a paragraph of text, then replaces gender-specific words with gender-neutral ones. Display the resulting gender-neutral text.



# 9

## C Formatted Input/Output

*All the news that's fit to print.*

—Adolph S. Ochs

*What mad pursuit? What struggle to escape?*

—John Keats

*Remove not the landmark on the boundary of the fields.*

—Amenemope

### Objectives

In this chapter, you'll learn:

- To use input and output streams.
- To use all print formatting capabilities.
- To use all input formatting capabilities.
- To print with field widths and precisions.
- To use formatting flags in the `printf` format control string.
- To output literals and escape sequences.
- To format input using `scanf`.



- |                                                       |                                                                         |
|-------------------------------------------------------|-------------------------------------------------------------------------|
| <b>9.1</b> Introduction                               | <b>9.8</b> Printing with Field Widths and Precision                     |
| <b>9.2</b> Streams                                    | <b>9.9</b> Using Flags in the <code>printf</code> Format Control String |
| <b>9.3</b> Formatting Output with <code>printf</code> | <b>9.10</b> Printing Literals and Escape Sequences                      |
| <b>9.4</b> Printing Integers                          | <b>9.11</b> Reading Formatted Input with <code>scanf</code>             |
| <b>9.5</b> Printing Floating-Point Numbers            |                                                                         |
| <b>9.6</b> Printing Strings and Characters            |                                                                         |
| <b>9.7</b> Other Conversion Specifiers                |                                                                         |

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises*

## 9.1 Introduction

An important part of the solution to any problem is the presentation of the results. In this chapter, we discuss in depth the formatting features of `scanf` and `printf`. These functions input data from the **standard input stream** and output data to the standard output stream. Four other functions that use the standard input and standard output—`gets`, `puts`, `getchar` and `putchar`—were discussed in Chapter 8. Include the header `<stdio.h>` in programs that call these functions.

Many features of `printf` and `scanf` were discussed earlier in the text. This chapter summarizes those features and introduces others. Chapter 11 discusses several additional functions included in the standard input/output (`<stdio.h>`) library.

## 9.2 Streams

All input and output is performed with **streams**, which are sequences of bytes. In input operations, the bytes flow from a device (e.g., a keyboard, a disk drive, a network connection) to main memory. In output operations, bytes flow from main memory to a device (e.g., a display screen, a printer, a disk drive, a network connection, and so on).

When program execution begins, three streams are connected to the program automatically. Normally, the standard input stream is connected to the keyboard and the standard output stream is connected to the screen. Operating systems often allow these streams to be redirected to other devices. A third stream, the **standard error stream**, is connected to the screen. Error messages are output to the standard error stream. Streams are discussed in detail in Chapter 11, C File Processing.

## 9.3 Formatting Output with `printf`

Precise output formatting is accomplished with `printf`. Every `printf` call contains a **format control string** that describes the output format. The format control string consists of **conversion specifiers**, **flags**, **field widths**, **precisions** and **literal characters**. Together with the percent sign (%), these form **conversion specifications**. Function `printf` can perform the following formatting capabilities, each of which is discussed in this chapter:

1. **Rounding** floating-point values to an indicated number of decimal places.
2. Aligning a column of numbers with decimal points appearing one above the other.
3. **Right justification** and **left justification** of outputs.



- 4. Inserting literal characters at precise locations in a line of output.
- 5. Representing floating-point numbers in exponential format.
- 6. Representing unsigned integers in octal and hexadecimal format. See Appendix C for more information on octal and hexadecimal values.
- 7. Displaying all types of data with fixed-size field widths and precisions.

The `printf` function has the form

```
printf(format-control-string, other-arguments);
```

*format-control-string* describes the output format, and *other-arguments* (which are optional) correspond to each conversion specification in *format-control-string*. Each conversion specification begins with a percent sign and ends with a conversion specifier. There can be many conversion specifications in one format control string.



**Common Programming Error 9.1**

*Forgetting to enclose a format-control-string in quotation marks is a syntax error.*



**Good Programming Practice 9.1**

*Format outputs neatly for presentation to make program outputs more readable and reduce user errors.*

## 9.4 Printing Integers

An integer is a whole number, such as 776, 0 or -52, that contains no decimal point. Integer values are displayed in one of several formats. Figure 9.1 describes the **integer conversion specifiers**.

| Conversion specifier | Description                                                                                                                                                                            |
|----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| d                    | Display as a signed decimal integer.                                                                                                                                                   |
| i                    | Display as a signed decimal integer. [Note: The i and d specifiers are different when used with scanf.]                                                                                |
| o                    | Display as an unsigned octal integer.                                                                                                                                                  |
| u                    | Display as an unsigned decimal integer.                                                                                                                                                |
| x or X               | Display as an unsigned hexadecimal integer. X causes the digits 0-9 and the letters A-F to be displayed and x causes the digits 0-9 and a-f to be displayed.                           |
| h or l (letter l)    | Place before any integer conversion specifier to indicate that a short or long integer is displayed, respectively. Letters h and l are more precisely called <b>length modifiers</b> . |

**Fig. 9.1** | Integer conversion specifiers.

Figure 9.2 prints an integer using each of the integer conversion specifiers. Only the minus sign prints; plus signs are suppressed. Later in this chapter we'll see how to force

plus signs to print. Also, the value -455, when read by `%u` (line 15), is converted to the unsigned value 4294966841.

```

1 /* Fig 9.2: fig09_02.c */
2 /* Using the integer conversion specifiers */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 printf("%d\n", 455);
8 printf("%i\n", 455); /* i same as d in printf */
9 printf("%d\n", +455);
10 printf("%d\n", -455);
11 printf("%hd\n", 32000);
12 printf("%ld\n", 2000000000L); /* L suffix makes literal a long */
13 printf("%o\n", 455);
14 printf("%u\n", 455);
15 printf("%u\n", -455);
16 printf("%x\n", 455);
17 printf("%X\n", 455);
18 return 0; /* indicates successful termination */
19 } /* end main */

```

```

455
455
455
-455
32000
2000000000
707
455
4294966841
1c7
1C7

```

**Fig. 9.2** | Using integer conversion specifiers.



### Common Programming Error 9.2

*Printing a negative value with a conversion specifier that expects an unsigned value.*

## 9.5 Printing Floating-Point Numbers

A floating-point value contains a decimal point as in 33.5, 0.0 or -657.983. Floating-point values are displayed in one of several formats. Figure 9.3 describes the floating-point conversion specifiers. The **conversion specifiers e and E** display floating-point values in **exponential notation**—the computer equivalent of **scientific notation** used in mathematics. For example, the value 150.4582 is represented in scientific notation as

$$1.504582 \times 10^2$$

and is represented in exponential notation as

1.504582E+02

by the computer. This notation indicates that 1.504582 is multiplied by 10 raised to the second power (E+02). The E stands for “exponent.”

Values displayed with the conversion specifiers e, E and f show six digits of precision to the right of the decimal point by default (e.g., 1.04592); other precisions can be specified explicitly. **Conversion specifier f** always prints at least one digit to the left of the decimal point. Conversion specifiers e and E print lowercase e and uppercase E, respectively, preceding the exponent, and print exactly one digit to the left of the decimal point.

**Conversion specifier g (or G)** prints in either e (E) or f format with no trailing zeros (1.234000 is printed as 1.234). Values are printed with e (E) if, after conversion to exponential notation, the value’s exponent is less than -4, or the exponent is greater than or equal to the specified precision (six significant digits by default for g and G). Otherwise, conversion specifier f is used to print the value. Trailing zeros are not printed in the fractional part of a value output with g or G. At least one decimal digit is required for the decimal point to be output. The values 0.0000875, 8750000.0, 8.75, 87.50 and 875 are printed as 8.75e-05, 8.75e+06, 8.75, 87.5 and 875 with the conversion specifier g. The value 0.0000875 uses e notation because, when it’s converted to exponential notation, its exponent (-5) is less than -4. The value 8750000.0 uses e notation because its exponent (6) is equal to the default precision.

| Conversion specifier | Description                                                                                                                               |
|----------------------|-------------------------------------------------------------------------------------------------------------------------------------------|
| e or E               | Display a floating-point value in exponential notation.                                                                                   |
| f                    | Display floating-point values in fixed-point notation. [Note: In C99, you can also use F.]                                                |
| g or G               | Display a floating-point value in either the floating-point form f or the exponential form e (or E), based on the magnitude of the value. |
| L                    | Place before any floating-point conversion specifier to indicate that a long double floating-point value is displayed.                    |

Fig. 9.3 | Floating-point conversion specifiers.

The precision for conversion specifiers g and G indicates the maximum number of significant digits printed, including the digit to the left of the decimal point. The value 1234567.0 is printed as 1.23457e+06, using conversion specifier %g (remember that all floating-point conversion specifiers have a default precision of 6). There are 6 significant digits in the result. The difference between g and G is identical to the difference between e and E when the value is printed in exponential notation—lowercase g causes a lowercase e to be output, and uppercase G causes an uppercase E to be output.



**Error-Prevention Tip 9.1**  
*When outputting data, be sure that the user is aware of situations in which data may be imprecise due to formatting (e.g., rounding errors from specifying precisions).*

Figure 9.4 demonstrates each of the floating-point conversion specifiers. The %E, %e and %g conversion specifiers cause the value to be rounded in the output and the conversion specifier %f does not. [Note: With some compilers, the exponent in the outputs will be shown with two digits to the right of the + sign.]

```

1 /* Fig 9.4: fig09_04.c */
2 /* Printing floating-point numbers with
3 floating-point conversion specifiers */
4
5 #include <stdio.h>
6
7 int main(void)
8 {
9 printf("%e\n", 1234567.89);
10 printf("%e\n", +1234567.89);
11 printf("%e\n", -1234567.89);
12 printf("%E\n", 1234567.89);
13 printf("%f\n", 1234567.89);
14 printf("%g\n", 1234567.89);
15 printf("%G\n", 1234567.89);
16 return 0; /* indicates successful termination */
17 } /* end main */

```

```

1.234568e+006
1.234568e+006
-1.234568e+006
1.234568E+006
1234567.890000
1.23457e+006
1.23457E+006

```

**Fig. 9.4** | Using floating-point conversion specifiers.

## 9.6 Printing Strings and Characters

The `c` and `s` conversion specifiers are used to print individual characters and strings, respectively. **Conversion specifier `c`** requires a `char` argument. **Conversion specifier `s`** requires a pointer to `char` as an argument. Conversion specifier `s` causes characters to be printed until a terminating null (`'\0'`) character is encountered. The program shown in Fig. 9.5 displays characters and strings with conversion specifiers `c` and `s`.



### Common Programming Error 9.3

*Using `%c` to print a string is an error. The conversion specifier `%c` expects a `char` argument. A string is a pointer to `char` (i.e., a `char *`).*



### Common Programming Error 9.4

*Using `%s` to print a `char` argument often causes a fatal execution-time error called an access violation. The conversion specifier `%s` expects an argument of type pointer to `char`.*



### Common Programming Error 9.5

*Using single quotes around character strings is a syntax error. Character strings must be enclosed in double quotes.*



### Common Programming Error 9.6

*Using double quotes around a character constant creates a pointer to a string consisting of two characters, the second of which is the terminating null.*

```
1 /* Fig 9.5: fig09_05c */
2 /* Printing strings and characters */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 char character = 'A'; /* initialize char */
8 char string[] = "This is a string"; /* initialize char array */
9 const char *stringPtr = "This is also a string"; /* char pointer */
10
11 printf("%c\n", character);
12 printf("%s\n", "This is a string");
13 printf("%s\n", string);
14 printf("%s\n", stringPtr);
15 return 0; /* indicates successful termination */
16 }
```

```
A
This is a string
This is a string
This is also a string
```

Fig. 9.5 | Using the character and string conversion specifiers.

### 9.7 Other Conversion Specifiers

The three remaining conversion specifiers are p, n and % (Fig. 9.6). The **conversion specifier %n** stores the number of characters output so far in the current printf—the corresponding argument is a pointer to an integer variable in which the value is stored—nothing is printed by a %n. The conversion specifier % causes a percent sign to be output.

| Conversion specifier | Description                                                                                                                                                             |
|----------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| p                    | Display a pointer value in an implementation-defined manner.                                                                                                            |
| n                    | Store the number of characters already output in the current printf statement. A pointer to an integer is supplied as the corresponding argument. Nothing is displayed. |
| %                    | Display the percent character.                                                                                                                                          |

Fig. 9.6 | Other conversion specifiers.

Figure 9.7’s %p prints the value of ptr and the address of x; these values are identical because ptr is assigned the address of x. Next, %n stores the number of characters output by the third printf statement (line 15) in integer variable y, and the value of y is printed. The last printf statement (line 21) uses %% to print the % character in a character string. Every printf call returns a value—either the number of characters output, or a negative value if an output error occurs. [Note: This example will not execute in Microsoft Visual C++ because %n has been disabled by Microsoft “for security reasons.” To execute the rest of the program, remove lines 15–16.]

**Portability Tip 9.1**

The conversion specifier `p` displays an address in an implementation-defined manner (on many systems, hexadecimal notation is used rather than decimal notation).

**Common Programming Error 9.7**

Trying to print a literal percent character using `%` rather than `%%` in the format control string. When `%` appears in a format control string, it must be followed by a conversion specifier.

```

1 /* Fig 9.7: fig09_07.c */
2 /* Using the p, n, and % conversion specifiers */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int *ptr; /* define pointer to int */
8 int x = 12345; /* initialize int x */
9 int y; /* define int y */
10
11 ptr = &x; /* assign address of x to ptr */
12 printf("The value of ptr is %p\n", ptr);
13 printf("The address of x is %p\n\n", &x);
14
15 printf("Total characters printed on this line:%n", &y);
16 printf(" %d\n\n", y);
17
18 y = printf("This line has 28 characters\n");
19 printf("%d characters were printed\n\n", y);
20
21 printf("Printing a %% in a format control string\n");
22 return 0; /* indicates successful termination */
23 } /* end main */

```

The value of ptr is 0012FF78  
The address of x is 0012FF78

Total characters printed on this line: 38

This line has 28 characters  
28 characters were printed

Printing a % in a format control string

**Fig. 9.7** | Using the `p`, `n` and `%` conversion specifiers.

## 9.8 Printing with Field Widths and Precision

The exact size of a field in which data is printed is specified by a **field width**. If the field width is larger than the data being printed, the data will normally be right justified within that field. An integer representing the field width is inserted between the percent sign (`%`) and the conversion specifier (e.g., `%4d`). Figure 9.8 prints two groups of five numbers each, right justifying those numbers that contain fewer digits than the field width. The field

width is increased to print values wider than the field and that the minus sign for a negative value uses one character position in the field width. Field widths can be used with all conversion specifiers.



### Common Programming Error 9.8

*Not providing a sufficiently large field width to handle a value to be printed can offset other data being printed and can produce confusing outputs. Know your data!*

```

1 /* Fig 9.8: fig09_08.c */
2 /* Printing integers right-justified */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 printf("%4d\n", 1);
8 printf("%4d\n", 12);
9 printf("%4d\n", 123);
10 printf("%4d\n", 1234);
11 printf("%4d\n\n", 12345);
12
13 printf("%4d\n", -1);
14 printf("%4d\n", -12);
15 printf("%4d\n", -123);
16 printf("%4d\n", -1234);
17 printf("%4d\n", -12345);
18 return 0; /* indicates successful termination */
19 } /* end main */

```

```

1
12
123
1234
12345

-1
-12
-123
-1234
-12345

```

**Fig. 9.8** | Right justifying integers in a field.

Function `printf` also enables you to specify the precision with which data is printed. Precision has different meanings for different data types. When used with integer conversion specifiers, precision indicates the minimum number of digits to be printed. If the printed value contains fewer digits than the specified precision and the precision value has a leading zero or decimal point, zeros are prefixed to the printed value until the total number of digits is equivalent to the precision. If neither a zero nor a decimal point is present in the precision value, spaces are inserted instead. The default precision for integers is 1. When used with floating-point conversion specifiers `e`, `E` and `f`, the precision is the number of digits to appear after the decimal point. When used with conversion specifiers `g` and `G`, the precision is the maximum number of significant digits to be printed. When

used with conversion specifier `s`, the precision is the maximum number of characters to be written from the string. To use precision, place a decimal point (`.`), followed by an integer representing the precision between the percent sign and the conversion specifier. Figure 9.9 demonstrates the use of precision in format control strings. When a floating-point value is printed with a precision smaller than the original number of decimal places in the value, the value is rounded.

```

1 /* Fig 9.9: fig09_09.c */
2 /* Using precision while printing integers,
3 floating-point numbers, and strings */
4 #include <stdio.h>
5
6 int main(void)
7 {
8 int i = 873; /* initialize int i */
9 double f = 123.94536; /* initialize double f */
10 char s[] = "Happy Birthday"; /* initialize char array s */
11
12 printf("Using precision for integers\n");
13 printf("\t%.4d\n\t%.9d\n\n", i, i);
14
15 printf("Using precision for floating-point numbers\n");
16 printf("\t%.3f\n\t%.3e\n\t%.3g\n\n", f, f, f);
17
18 printf("Using precision for strings\n");
19 printf("\t%.11s\n", s);
20 return 0; /* indicates successful termination */
21 } /* end main */

```

```

Using precision for integers
 0873
 000000873

Using precision for floating-point numbers
 123.945
 1.239e+002
 124

Using precision for strings
 Happy Birth

```

**Fig. 9.9** | Using precisions to display information of several types.

The field width and the precision can be combined by placing the field width, followed by a decimal point, followed by a precision between the percent sign and the conversion specifier, as in the statement

```
printf("%9.3f", 123.456789);
```

which displays 123.457 with three digits to the right of the decimal point right justified in a nine-digit field.

It's possible to specify the field width and the precision using integer expressions in the argument list following the format control string. To use this feature, insert an asterisk



(\*) in place of the field width or precision (or both). The matching `int` argument in the argument list is evaluated and used in place of the asterisk. A field width's value may be either positive or negative (which causes the output to be left justified in the field as described in the next section). The statement

```
printf("%*.*f", 7, 2, 98.736);
```

uses 7 for the field width, 2 for the precision and outputs the value 98.74 right justified.

### 9.9 Using Flags in the printf Format Control String

Function `printf` also provides flags to supplement its output formatting capabilities. Five flags are available for use in format control strings (Fig. 9.10). To use a flag in a format control string, place the flag immediately to the right of the percent sign. Several flags may be combined in one conversion specifier.

| Flag           | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|----------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| - (minus sign) | Left justify the output within the specified field.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| + (plus sign)  | Display a plus sign preceding positive values and a minus sign preceding negative values.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| <i>space</i>   | Print a space before a positive value not printed with the + flag.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| #              | Prefix 0 to the output value when used with the octal conversion specifier <code>o</code> .<br>Prefix 0x or 0X to the output value when used with the hexadecimal conversion specifiers <code>x</code> or <code>X</code> .<br>Force a decimal point for a floating-point number printed with <code>e</code> , <code>E</code> , <code>f</code> , <code>g</code> or <code>G</code> that does not contain a fractional part. (Normally the decimal point is printed only if a digit follows it.) For <code>g</code> and <code>G</code> specifiers, trailing zeros are not eliminated. |
| 0 (zero)       | Pad a field with leading zeros.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |

Fig. 9.10 | Format control string flags.

Figure 9.11 demonstrates right justification and left justification of a string, an integer, a character and a floating-point number.

```
1 /* Fig 9.11: fig09_11.c */
2 /* Right justifying and left justifying values */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 printf("%10s%10d%10c%10f\n\n", "hello", 7, 'a', 1.23);
8 printf("%-10s%-10d%-10c%-10f\n", "hello", 7, 'a', 1.23);
9 return 0; /* indicates successful termination */
10 }
```

Fig. 9.11 | Left justifying strings in a field. (Part I of 2.)

|       |   |   |          |
|-------|---|---|----------|
| hello | 7 | a | 1.230000 |
| hello | 7 | a | 1.230000 |

**Fig. 9.11** | Left justifying strings in a field. (Part 2 of 2.)

Figure 9.12 prints a positive number and a negative number, each with and without the **+ flag**. The minus sign is displayed in both cases, but the plus sign is displayed only when the + flag is used.

```

1 /* Fig 9.12: fig09_12.c */
2 /* Printing numbers with and without the + flag */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 printf("%d\n%d\n", 786, -786);
8 printf("%+d\n%+d\n", 786, -786);
9 return 0; /* indicates successful termination */
10 } /* end main */

```

```

786
-786
+786
-786

```

**Fig. 9.12** | Printing positive and negative numbers with and without the + flag.

Figure 9.13 prefixes a space to the positive number with the **space flag**. This is useful for aligning positive and negative numbers with the same number of digits. The value -547 is not preceded by a space in the output because of its minus sign.

```

1 /* Fig 9.13: fig09_13.c */
2 /* Printing a space before signed values
3 not preceded by + or - */
4 #include <stdio.h>
5
6 int main(void)
7 {
8 printf("% d\n% d\n", 547, -547);
9 return 0; /* indicates successful termination */
10 } /* end main */

```

```

547
-547

```

**Fig. 9.13** | Using the space flag.

Figure 9.14 uses the **# flag** to prefix 0 to the octal value and 0x and 0X to the hexadecimal values, and to force the decimal point on a value printed with g.

```

1 /* Fig 9.14: fig09_14.c */
2 /* Using the # flag with conversion specifiers
3 o, x, X and any floating-point specifier */
4 #include <stdio.h>
5
6 int main(void)
7 {
8 int c = 1427; /* initialize c */
9 double p = 1427.0; /* initialize p */
10
11 printf("%#o\n", c);
12 printf("%#x\n", c);
13 printf("%#X\n", c);
14 printf("\n%g\n", p);
15 printf("%#g\n", p);
16 return 0; /* indicates successful termination */
17 } /* end main */

```

```

02623
0x593
0X593

1427
1427.00

```

**Fig. 9.14** | Using the # flag.

Figure 9.15 combines the + flag and the **0 (zero) flag** to print 452 in a 9-space field with a + sign and leading zeros, then prints 452 again using only the 0 flag and a 9-space field.

```

1 /* Fig 9.15: fig09_15.c */
2 /* Printing with the 0(zero) flag fills in leading zeros */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 printf("%+09d\n", 452);
8 printf("%09d\n", 452);
9 return 0; /* indicates successful termination */
10 } /* end main */

```

```

+00000452
000000452

```

**Fig. 9.15** | Using the 0 (zero) flag.

## 9.10 Printing Literals and Escape Sequences

Most literal characters to be printed in a `printf` statement can simply be included in the format control string. However, there are several “problem” characters, such as the quotation mark (") that delimits the format control string itself. Various control characters, such

as newline and tab, must be represented by escape sequences. An escape sequence is represented by a backslash (\), followed by a particular escape character. Figure 9.16 lists the escape sequences and the actions they cause.



### Common Programming Error 9.9

*Attempting to print as literal data in a printf statement a single quote, double quote or backslash character without preceding that character with a backslash to form a proper escape sequence is an error.*

| Escape sequence            | Description                                            |
|----------------------------|--------------------------------------------------------|
| \' (single quote)          | Output the single quote (') character.                 |
| \" (double quote)          | Output the double quote (") character.                 |
| \? (question mark)         | Output the question mark (?) character.                |
| \\ (backslash)             | Output the backslash (\) character.                    |
| \a (alert or bell)         | Cause an audible (bell) or visual alert.               |
| \b (backspace)             | Move the cursor back one position on the current line. |
| \f (new page or form feed) | Move the cursor to the start of the next logical page. |
| \n (newline)               | Move the cursor to the beginning of the next line.     |
| \r (carriage return)       | Move the cursor to the beginning of the current line.  |
| \t (horizontal tab)        | Move the cursor to the next horizontal tab position.   |
| \v (vertical tab)          | Move the cursor to the next vertical tab position.     |

**Fig. 9.16** | Escape sequences.

## 9.1.1 Reading Formatted Input with scanf

Precise input formatting can be accomplished with scanf. Every scanf statement contains a format control string that describes the format of the data to be input. The format control string consists of conversion specifiers and literal characters. Function scanf has the following input formatting capabilities:

1. Inputting all types of data.
2. Inputting specific characters from an input stream.
3. Skipping specific characters in the input stream.

Function scanf is written in the following form:

```
scanf(format-control-string, other-arguments);
```

*format-control-string* describes the formats of the input, and *other-arguments* are pointers to variables in which the input will be stored.



### Good Programming Practice 9.2

*When inputting data, prompt the user for one data item or a few data items at a time. Avoid asking the user to enter many data items in response to a single prompt.*

**Good Programming Practice 9.3**

*Always consider what the user and your program will do when (not if) incorrect data is entered—for example, a value for an integer that is nonsensical in a program's context, or a string with missing punctuation or spaces.*

Figure 9.17 summarizes the conversion specifiers used to input all types of data. The remainder of this section provides programs that demonstrate reading data with the various `scanf` conversion specifiers.

| Conversion specifier                                                                | Description                                                                                                                                                                                                                                                  |
|-------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>Integers</i>                                                                     |                                                                                                                                                                                                                                                              |
| <code>d</code>                                                                      | Read an optionally signed decimal integer. The corresponding argument is a pointer to an <code>int</code> .                                                                                                                                                  |
| <code>i</code>                                                                      | Read an optionally signed decimal, octal or hexadecimal integer. The corresponding argument is a pointer to an <code>int</code> .                                                                                                                            |
| <code>o</code>                                                                      | Read an octal integer. The corresponding argument is a pointer to an unsigned <code>int</code> .                                                                                                                                                             |
| <code>u</code>                                                                      | Read an unsigned decimal integer. The corresponding argument is a pointer to an unsigned <code>int</code> .                                                                                                                                                  |
| <code>x</code> or <code>X</code>                                                    | Read a hexadecimal integer. The corresponding argument is a pointer to an unsigned <code>int</code> .                                                                                                                                                        |
| <code>h</code> or <code>l</code>                                                    | Place before any of the integer conversion specifiers to indicate that a short or long integer is to be input.                                                                                                                                               |
| <i>Floating-point numbers</i>                                                       |                                                                                                                                                                                                                                                              |
| <code>e</code> , <code>E</code> , <code>f</code> , <code>g</code> or <code>G</code> | Read a floating-point value. The corresponding argument is a pointer to a floating-point variable.                                                                                                                                                           |
| <code>l</code> or <code>L</code>                                                    | Place before any of the floating-point conversion specifiers to indicate that a <code>double</code> or long <code>double</code> value is to be input. The corresponding argument is a pointer to a <code>double</code> or long <code>double</code> variable. |
| <i>Characters and strings</i>                                                       |                                                                                                                                                                                                                                                              |
| <code>c</code>                                                                      | Read a character. The corresponding argument is a pointer to a <code>char</code> ; no null ( <code>'\0'</code> ) is added.                                                                                                                                   |
| <code>s</code>                                                                      | Read a string. The corresponding argument is a pointer to an array of type <code>char</code> that is large enough to hold the string and a terminating null ( <code>'\0'</code> ) character—which is automatically added.                                    |
| <i>Scan set</i>                                                                     |                                                                                                                                                                                                                                                              |
| <code>[scan characters]</code>                                                      | Scan a string for a set of characters that are stored in an array.                                                                                                                                                                                           |
| <i>Miscellaneous</i>                                                                |                                                                                                                                                                                                                                                              |
| <code>p</code>                                                                      | Read an address of the same form produced when an address is output with <code>%p</code> in a <code>printf</code> statement.                                                                                                                                 |
| <code>n</code>                                                                      | Store the number of characters input so far in this call to <code>scanf</code> . The corresponding argument is a pointer to an <code>int</code> .                                                                                                            |
| <code>%</code>                                                                      | Skip a percent sign ( <code>%</code> ) in the input.                                                                                                                                                                                                         |

**Fig. 9.17** | Conversion specifiers for `scanf`.

Figure 9.18 reads integers with the various integer conversion specifiers and displays the integers as decimal numbers. Conversion specifier **%i** is capable of inputting decimal, octal and hexadecimal integers.

---

```

1 /* Fig 9.18: fig09_18.c */
2 /* Reading integers */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int a;
8 int b;
9 int c;
10 int d;
11 int e;
12 int f;
13 int g;
14
15 printf("Enter seven integers: ");
16 scanf("%d%i%i%i%o%u%x", &a, &b, &c, &d, &e, &f, &g);
17
18 printf("The input displayed as decimal integers is:\n");
19 printf("%d %d %d %d %d %d %d\n", a, b, c, d, e, f, g);
20 return 0; /* indicates successful termination */
21 } /* end main */

```

---

```

Enter seven integers: -70 -70 070 0x70 70 70 70
The input displayed as decimal integers is:
-70 -70 56 112 56 70 112

```

**Fig. 9.18** | Reading input with integer conversion specifiers.

When inputting floating-point numbers, any of the floating-point conversion specifiers **e**, **E**, **f**, **g** or **G** can be used. Figure 9.19 reads three floating-point numbers, one with each of the three types of floating conversion specifiers, and displays all three numbers with conversion specifier **f**. The program output confirms the fact that floating-point values are imprecise—this is highlighted by the third value printed.

---

```

1 /* Fig 9.19: fig09_19.c */
2 /* Reading floating-point numbers */
3 #include <stdio.h>
4
5 /* function main begins program execution */
6 int main(void)
7 {
8 double a;
9 double b;
10 double c;
11

```

---

**Fig. 9.19** | Reading input with floating-point conversion specifiers. (Part I of 2.)

```

12 printf("Enter three floating-point numbers: \n");
13 scanf("%le%lf%lg", &a, &b, &c);
14
15 printf("Here are the numbers entered in plain\n");
16 printf("floating-point notation:\n");
17 printf("%f\n%f\n%f\n", a, b, c);
18 return 0; /* indicates successful termination */
19 } /* end main */

```

```

Enter three floating-point numbers:
1.27987 1.27987e+03 3.38476e-06
Here are the numbers entered in plain
floating-point notation:
1.279870
1279.870000
0.000003

```

**Fig. 9.19** | Reading input with floating-point conversion specifiers. (Part 2 of 2.)

Characters and strings are input using the conversion specifiers `c` and `s`, respectively. Figure 9.20 prompts the user to enter a string. The program inputs the first character of the string with `%c` and stores it in the character variable `x`, then inputs the remainder of the string with `%s` and stores it in character array `y`.

```

1 /* Fig 9.20: fig09_20.c */
2 /* Reading characters and strings */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 char x;
8 char y[9];
9
10 printf("Enter a string: ");
11 scanf("%c%s", &x, y);
12
13 printf("The input was:\n");
14 printf("the character \"%c\" ", x);
15 printf("and the string \"%s\"\n", y);
16 return 0; /* indicates successful termination */
17 } /* end main */

```

```

Enter a string: Sunday
The input was:
the character "S" and the string "unday"

```

**Fig. 9.20** | Inputting characters and strings.

A sequence of characters can be input using a **scan set**. A scan set is a set of characters encloseded in square brackets, `[]`, and preceded by a percent sign in the format control string. A scan set scans the characters in the input stream, looking only for those characters that match characters contained in the scan set. Each time a character is matched, it's

stored in the scan set's corresponding argument—a pointer to a character array. The scan set stops inputting characters when a character that is not contained in the scan set is encountered. If the first character in the input stream does not match a character in the scan set, only the null character is stored in the array. Figure 9.21 uses the scan set [aeiou] to scan the input stream for vowels. Notice that the first seven letters of the input are read. The eighth letter (h) is not in the scan set and therefore the scanning is terminated.

---

```

1 /* Fig 9.21: fig09_21.c */
2 /* Using a scan set */
3 #include <stdio.h>
4
5 /* function main begins program execution */
6 int main(void)
7 {
8 char z[9]; /* define array z */
9
10 printf("Enter string: ");
11 scanf("[%aeiou]", z); /* search for set of characters */
12
13 printf("The input was \"%s\\n\"", z);
14 return 0; /* indicates successful termination */
15 } /* end main */

```

```

Enter string: ooeoooahah
The input was "ooeooa"

```

**Fig. 9.21** | Using a scan set.

The scan set can also be used to scan for characters not contained in the scan set by using an **inverted scan set**. To create an inverted scan set, place a **caret (^)** in the square brackets before the scan characters. This causes characters not appearing in the scan set to be stored. When a character contained in the inverted scan set is encountered, input terminates. Figure 9.22 uses the inverted scan set [^aeiou] to search for consonants—more properly to search for “nonvowels.”

---

```

1 /* Fig 9.22: fig09_22.c */
2 /* Using an inverted scan set */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 char z[9];
8
9 printf("Enter a string: ");
10 scanf("[^aeiou]", z); /* inverted scan set */
11
12 printf("The input was \"%s\\n\"", z);
13 return 0; /* indicates successful termination */
14 } /* end main */

```

**Fig. 9.22** | Using an inverted scan set. (Part I of 2.)



```
Enter a string: String
The input was "Str"
```

**Fig. 9.22** | Using an inverted scan set. (Part 2 of 2.)

A field width can be used in a `scanf` conversion specifier to read a specific number of characters from the input stream. Figure 9.23 inputs a series of consecutive digits as a two-digit integer and an integer consisting of the remaining digits in the input stream.

```
1 /* Fig 9.23: fig09_23.c */
2 /* inputting data with a field width */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int x;
8 int y;
9
10 printf("Enter a six digit integer: ");
11 scanf("%2d%d", &x, &y);
12
13 printf("The integers input were %d and %d\n", x, y);
14 return 0; /* indicates successful termination */
15 } /* end main */
```

```
Enter a six digit integer: 123456
The integers input were 12 and 3456
```

**Fig. 9.23** | Inputting data with a field width.

Often it's necessary to skip certain characters in the input stream. For example, a date could be entered as

```
11-10-1999
```

Each number in the date needs to be stored, but the dashes that separate the numbers can be discarded. To eliminate unnecessary characters, include them in the format control string of `scanf` (**white-space** characters—such as space, newline and tab—skip all leading white-space). For example, to skip the dashes in the input, use the statement

```
scanf("%d-%d-%d", &month, &day, &year);
```

Although, this `scanf` does eliminate the dashes in the preceding input, it's possible that the date could be entered as

```
10/11/1999
```

In this case, the preceding `scanf` would not eliminate the unnecessary characters. For this reason, `scanf` provides the **assignment suppression character** `*`. The assignment suppression character enables `scanf` to read any type of data from the input and discard it without assigning it to a variable. Figure 9.24 uses the assignment suppression character in the `%c` conversion specifier to indicate that a character appearing in the input stream should be

read and discarded. Only the month, day and year are stored. The values of the variables are printed to demonstrate that they are in fact input correctly. The argument lists for each `scanf` call do not contain variables for the conversion specifiers that use the assignment suppression character. The corresponding characters are simply discarded.

```

1 /* Fig 9.24: fig09_24.c */
2 /* Reading and discarding characters from the input stream */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int month1;
8 int day1;
9 int year1;
10 int month2;
11 int day2;
12 int year2;
13
14 printf("Enter a date in the form mm-dd-yyyy: ");
15 scanf("%d%c%d%c%d", &month1, &day1, &year1);
16
17 printf("month = %d day = %d year = %d\n\n", month1, day1, year1);
18
19 printf("Enter a date in the form mm/dd/yyyy: ");
20 scanf("%d%c%d%c%d", &month2, &day2, &year2);
21
22 printf("month = %d day = %d year = %d\n", month2, day2, year2);
23 return 0; /* indicates successful termination */
24 } /* end main */

```

```

Enter a date in the form mm-dd-yyyy: 11-18-2003
month = 11 day = 18 year = 2003

Enter a date in the form mm/dd/yyyy: 11/18/2003
month = 11 day = 18 year = 2003

```

**Fig. 9.24** | Reading and discarding characters from the input stream.

## Summary

### Section 9.2 Streams

- All input and output is dealt with in streams—sequences of characters organized into lines. Each line consists of zero or more characters and ends with a newline character.
- Normally, the standard input stream is connected to the keyboard, and the standard output stream is connected to the computer screen.
- Operating systems often allow the standard input and standard output streams to be redirected to other devices.

### Section 9.3 Formatting Output with *printf*

- A format control string describes the formats in which the output values appear. The format control string consists of conversion specifiers, flags, field widths, precisions and literal characters.

### Section 9.4 Printing Integers

- Integers are printed with the following conversion specifiers: `d` or `i` for optionally signed integers, `o` for unsigned integers in octal form, `u` for unsigned integers in decimal form and `x` or `X` for unsigned integers in hexadecimal form. The modifier `h` or `l` is prefixed to the preceding conversion specifiers to indicate a short or long integer, respectively.

### Section 9.5 Printing Floating-Point Numbers

- Floating-point values are printed with the following conversion specifiers: `e` or `E` for exponential notation, `f` for regular floating-point notation, and `g` or `G` for either `e` (or `E`) notation or `f` notation. When the `g` (or `G`) conversion specifier is indicated, the `e` (or `E`) conversion specifier is used if the value's exponent is less than  $-4$  or greater than or equal to the precision with which the value is printed.
- The precision for the `g` and `G` conversion specifiers indicates the maximum number of significant digits printed.

### Section 9.6 Printing Strings and Characters

- The conversion specifier `c` prints a character.
- The conversion specifier `s` prints a string of characters ending in the null character.

### Section 9.7 Other Conversion Specifiers

- The conversion specifier `p` displays an address in an implementation-defined manner (on many systems, hexadecimal notation is used).
- The conversion specifier `n` stores the number of characters already output in the current `printf` statement. The corresponding argument is a pointer to an `int`.
- The conversion specifier `%%` causes a literal `%` to be output.

### Section 9.8 Printing with Field Widths and Precision

- If the field width is larger than the object being printed, the object is right justified by default.
- Field widths can be used with all conversion specifiers.
- Precision used with integer conversion specifiers indicates the minimum number of digits printed. Zeros are prefixed to the printed value until the number of digits is equivalent to the precision.
- Precision used with floating-point conversion specifiers `e`, `E` and `f` indicates the number of digits that appear after the decimal point. Precision used with floating-point conversion specifiers `g` and `G` indicates the number of significant digits to appear.
- Precision used with conversion specifier `s` indicates the number of characters to be printed.
- The field width and the precision can be combined by placing the field width, followed by a decimal point, followed by the precision between the percent sign and the conversion specifier.
- It's possible to specify the field width and the precision through integer expressions in the argument list following the format control string. To do so, use an asterisk (`*`) for the field width or precision. The matching argument in the argument list is used in place of the asterisk. The value of the argument can be negative for the field width but must be positive for the precision.

### Section 9.9 Using Flags in the `printf` Format Control String

- The `-` flag left justifies its argument in a field.
- The `+` flag prints a plus sign for positive values and a minus sign for negative values. The space flag prints a space preceding a positive value not displayed with the `+` flag.
- The `#` flag prefixes `0` to octal values and `0x` or `0X` to hexadecimal values, and forces the decimal point to be printed for floating-point values printed with `e`, `E`, `f`, `g` or `G`.
- The `0` flag prints leading zeros for a value that does not occupy its entire field width.

### Section 9.10 Printing Literals and Escape Sequences

- Most literal characters to be printed in a `printf` statement can simply be included in the format control string. However, there are several “problem” characters, such as the quotation mark (") that delimits the format control string itself. Various control characters, such as newline and tab, must be represented by escape sequences. An escape sequence is represented by a backslash (\), followed by a particular escape character.

### Section 9.11 Formatting Input with `scanf`

- Precise input formatting is accomplished with the `scanf` library function.
- Integers are input with `scanf` with the conversion specifiers `d` and `i` for optionally signed integers and `o`, `u`, `x` or `X` for unsigned integers. The modifiers `h` and `l` are placed before an integer conversion specifier to input a short or long integer, respectively.
- Floating-point values are input with `scanf` with the conversion specifiers `e`, `E`, `f`, `g` or `G`. The modifiers `l` and `L` are placed before any of the floating-point conversion specifiers to indicate that the input value is a double or long double value, respectively.
- Characters are input with `scanf` with the conversion specifier `c`.
- Strings are input with `scanf` with the conversion specifier `s`.
- A scan set scans the characters in the input, looking only for those characters that match characters contained in the scan set. When a character is matched, it's stored in a character array. The scan set stops inputting characters when a character not contained in the scan set is encountered.
- To create an inverted scan set, place a caret (^) in the square brackets before the scan characters. This causes characters input with `scanf` and not appearing in the scan set to be stored until a character contained in the inverted scan set is encountered.
- Address values are input with `scanf` with the conversion specifier `p`.
- Conversion specifier `n` stores the number of characters input previously in the current `scanf`. The corresponding argument is a pointer to `int`.
- The conversion specifier `%%` with `scanf` matches a single `%` character in the input.
- The assignment suppression character reads data from the input stream and discards the data.
- A field width is used in `scanf` to read a specific number of characters from the input stream.

## Terminology

" (quotation mark) 368  
 \* assignment suppression character 374  
 # flag 367  
 % character in a conversion specifier 357  
 %% conversion specifier 362  
 %c conversion specifier 361  
 %E conversion specifier 359  
 %e conversion specifier 359  
 %f conversion specifier 360  
 %g (or %G) conversion specifier 360  
 %i conversion specifier 371  
 %p conversion specifier 362  
 %s conversion specifier 361, 372  
 %u conversion specifier 359  
 + flag 367  
 0 (zero) flag 368  
 caret (^) 373

conversion specification 357  
 conversion specifier 357  
 exponential notation 359  
 field width 357  
 flag 357  
 format control string 357  
 integer conversion specifier 358  
 inverted scan set 373  
 left justification 357  
 length modifier 358  
 literal character 357  
 precision 357  
 printf function 357  
 right justification 357  
 rounding 357  
 scan set 372  
 scanf function 357

|                                  |                           |
|----------------------------------|---------------------------|
| scientific notation 359          | <stdio.h> header file 357 |
| space flag 367                   | stream 357                |
| standard error stream (cerr) 357 | white space 374           |
| standard input stream (cin) 357  |                           |

## Self-Review Exercises

**9.1** Fill in the blanks in each of the following:

- All input and output is dealt with in the form of \_\_\_\_\_.
- The \_\_\_\_\_ stream is normally connected to the keyboard.
- The \_\_\_\_\_ stream is normally connected to the computer screen.
- Precise output formatting is accomplished with the \_\_\_\_\_ function.
- The format control string may contain \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- The conversion specifier \_\_\_\_\_ or \_\_\_\_\_ may be used to output a signed decimal integer.
- The conversion specifiers \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_ are used to display unsigned integers in octal, decimal and hexadecimal form, respectively.
- The modifiers \_\_\_\_\_ and \_\_\_\_\_ are placed before the integer conversion specifiers to indicate that short or long integer values are to be displayed.
- The conversion specifier \_\_\_\_\_ is used to display a floating-point value in exponential notation.
- The modifier \_\_\_\_\_ is placed before any floating-point conversion specifier to indicate that a long double value is to be displayed.
- The conversion specifiers e, E and f are displayed with \_\_\_\_\_ digits of precision to the right of the decimal point if no precision is specified.
- The conversion specifiers \_\_\_\_\_ and \_\_\_\_\_ are used to print strings and characters, respectively.
- All strings end in the \_\_\_\_\_ character.
- The field width and precision in a printf conversion specifier can be controlled with integer expressions by substituting a(n) \_\_\_\_\_ for the field width or for the precision and placing an integer expression in the corresponding argument of the argument list.
- The \_\_\_\_\_ flag causes output to be left justified in a field.
- The \_\_\_\_\_ flag causes values to be displayed with either a plus sign or a minus sign.
- Precise input formatting is accomplished with the \_\_\_\_\_ function.
- A(n) \_\_\_\_\_ is used to scan a string for specific characters and store the characters in an array.
- The conversion specifier \_\_\_\_\_ can be used to input optionally signed octal, decimal and hexadecimal integers.
- The conversion specifiers \_\_\_\_\_ can be used to input a double value.
- The \_\_\_\_\_ is used to read data from the input stream and discard it without assigning it to a variable.
- A(n) \_\_\_\_\_ can be used in a scanf conversion specifier to indicate that a specific number of characters or digits should be read from the input stream.

**9.2** Find the error in each of the following and explain how the error can be corrected.

- The following statement should print the character 'c'.  

```
printf("%s\n", 'c');
```
- The following statement should print 9.375%.  

```
printf("%.3f%", 9.375);
```
- The following statement should print the first character of the string "Monday".  

```
printf("%c\n", "Monday");
```

- d) `printf( "A string in quotes" );`
- e) `printf( %d%d, 12, 20 );`
- f) `printf( "%c", "x" );`
- g) `printf( "%s\n", 'Richard' );`

**9.3** Write a statement for each of the following:

- a) Print 1234 right justified in a 10-digit field.
- b) Print 123.456789 in exponential notation with a sign (+ or -) and 3 digits of precision.
- c) Read a `double` value into variable `number`.
- d) Print 100 in octal form preceded by 0.
- e) Read a string into character array `string`.
- f) Read characters into array `n` until a nondigit character is encountered.
- g) Use integer variables `x` and `y` to specify the field width and precision used to display the `double` value 87.4573.
- h) Read a value of the form 3.5%. Store the percentage in `float` variable `percent` and eliminate the % from the input stream. Do not use the assignment suppression character.
- i) Print 3.333333 as a long `double` value with a sign (+ or -) in a field of 20 characters with a precision of 3.

## Answers to Self-Review Exercises

**9.1** a) Streams. b) Standard input. c) Standard output. d) `printf`. e) Conversion specifiers, flags, field widths, precisions, literal characters. f) d, i. g) o, u, x (or X). h) h, l. i) e (or E). j) L. k) G. l) s, c. m) NULL ('0'). n) asterisk (\*). o) - (minus). p) + (plus). q) `scanf`. r) Scan set. s) i. t) l, L, E, l, f, l, g or L, G. u) Assignment suppression character (\*). v) Field width.

- 9.2**
- a) Error: Conversion specifier `s` expects an argument of type pointer to char.  
Correction: To print the character 'c', use the conversion specifier `%c` or change 'c' to "c".
  - b) Error: Trying to print the literal character % without using the conversion specifier `%%`.  
Correction: Use `%%` to print a literal % character.
  - c) Error: Conversion specifier `c` expects an argument of type char.  
Correction: To print the first character of "Monday" use the conversion specifier `%1s`.
  - d) Error: Trying to print the literal character " without using the \ escape sequence.  
Correction: Replace each quote in the inner set of quotes with \".
  - e) Error: The format control string is not enclosed in double quotes.  
Correction: Enclose `%d%d` in double quotes.
  - f) Error: The character `x` is enclosed in double quotes.  
Correction: Character constants to be printed with `%c` must be enclosed in single quotes.
  - g) Error: The string to be printed is enclosed in single quotes.  
Correction: Use double quotes instead of single quotes to represent a string.

- 9.3**
- a) `printf( "%10d\n", 1234 );`
  - b) `printf( "%+.3e\n", 123.456789 );`
  - c) `scanf( "%lf", &number );`
  - d) `printf( "%#o\n", 100 );`
  - e) `scanf( "%s", string );`
  - f) `scanf( "%[0123456789]", n );`
  - g) `printf( "%*.2f\n", x, y, 87.4573 );`
  - h) `scanf( "%f%%", &percent );`
  - i) `printf( "%+20.3Lf\n", 3.333333 );`

## Exercises

- 9.4** Write a `printf` or `scanf` statement for each of the following:
- Print unsigned integer 40000 left justified in a 15-digit field with 8 digits.
  - Read a hexadecimal value into variable `hex`.
  - Print 200 with and without a sign.
  - Print 100 in hexadecimal form preceded by `0x`.
  - Read characters into array `s` until the letter `p` is encountered.
  - Print 1.234 in a 9-digit field with preceding zeros.
  - Read a time of the form `hh:mm:ss`, storing the parts of the time in the integer variables `hour`, `minute` and `second`. Skip the colons (`:`) in the input stream. Use the assignment suppression character.
  - Read a string of the form `"characters"` from the standard input. Store the string in character array `s`. Eliminate the quotation marks from the input stream.
  - Read a time of the form `hh:mm:ss`, storing the parts of the time in the integer variables `hour`, `minute` and `second`. Skip the colons (`:`) in the input stream. Do not use the assignment suppression character.

- 9.5** Show what each of the following statements prints. If a statement is incorrect, indicate why.
- `printf( "%-10d\n", 10000 );`
  - `printf( "%c\n", "This is a string" );`
  - `printf( "%*.1f\n", 8, 3, 1024.987654 );`
  - `printf( "%#o\n%X\n#e\n", 17, 17, 1008.83689 );`
  - `printf( "% ld\n%+ld\n", 1000000, 1000000 );`
  - `printf( "%10.2E\n", 444.93738 );`
  - `printf( "%10.2g\n", 444.93738 );`
  - `printf( "%d\n", 10.987 );`

- 9.6** Find the error(s) in each of the following program segments. Explain how each error can be corrected.

- `printf( "%s\n", 'Happy Birthday' );`
- `printf( "%c\n", 'Hello' );`
- `printf( "%c\n", "This is a string" );`
- The following statement should print `"Bon Voyage"`:  
`printf( ""%s"" , "Bon Voyage" );`
- `char day[] = "Sunday";`  
`printf( "%s\n", day[ 3 ] );`
- `printf( 'Enter your name: ' );`
- `printf( %f, 123.456 );`
- The following statement should print the characters `'o'` and `'k'`:  
`printf( "%s%s\n", 'O', 'K' );`
- `char s[ 10 ];`  
`scanf( "%c", s[ 7 ] );`

- 9.7** (*Differences Between `%d` and `%i`*) Write a program to test the difference between the `%d` and `%i` conversion specifiers when used in `scanf` statements. Use the statements

```
scanf("%i%d", &x, &y);
printf("%d %d\n", x, y);
```

to input and print the values. Test the program with the following sets of input data:

```
10 10
-10 -10
010 010
0x10 0x10
```

**9.8** (*Displaying Values and Their Number of Characters*) Write a program that loads 10-element array number with random integers from 1 to 1000. For each value, print the value and a running total of the number of characters printed. Use the %n conversion specifier to determine the number of characters output for each value. Print the total number of characters output for all values up to and including the current value each time the current value is printed.

**9.9** (*Printing Pointer Values as Integers*) Write a program that prints pointer values using all the integer conversion specifiers and the %p conversion specifier. Which ones print strange values? Which ones cause errors? In which format does the %p conversion specifier display the address on your system?

**9.10** (*Printing Numbers in Various Field Widths*) Write a program to test the results of printing the integer value 12345 and the floating-point value 1.2345 in various size fields. What happens when the values are printed in fields containing fewer digits than the values?

**9.11** (*Rounding Floating-Point Numbers*) Write a program that prints the value 100.453627 rounded to the nearest digit, tenth, hundredth, thousandth and ten-thousandth.

**9.12** (*Displaying a String in a Field*) Write a program that inputs a string from the keyboard and determines the length of the string. Print the string using twice the length as the field width.

**9.13** (*Temperature Conversions*) Write a program that converts integer Fahrenheit temperatures from 0 to 212 degrees to floating-point Celsius temperatures with 3 digits of precision. Perform the calculation using the formula

```
celsius = 5.0 / 9.0 * (fahrenheit - 32);
```

The output should be printed in two right-justified columns of 10 characters each, and the Celsius temperatures should be preceded by a sign for both positive and negative values.

**9.14** (*Escape Sequences*) Write a program to test all the escape sequences in Figure 9.16. For the escape sequences that move the cursor, print a character before and after printing the escape sequence so it's clear where the cursor has moved.

**9.15** (*Printing a Question Mark*) Write a program that determines whether ? can be printed as part of a printf format control string as a literal character rather than using the \? escape sequence.

**9.16** (*Reading an Integer with Each scanf Conversion Specifier*) Write a program that inputs the value 437 using each of the scanf integer conversion specifiers. Print each input value using all the integer conversion specifiers.

**9.17** (*Outputting a Number with the Floating-Point Conversion Specifiers*) Write a program that uses each of the conversion specifiers e, f and g to input the value 1.2345. Print the values of each variable to prove that each conversion specifier can be used to input this same value.

**9.18** (*Reading Strings in Quotes*) In some programming languages, strings are entered surrounded by either single or double quotation marks. Write a program that reads the three strings suzy, "suzy" and 'suzy'. Are the single and double quotes ignored by C or read as part of the string?

**9.19** (*Printing a Question Mark as a Character Constant*) Write a program that determines whether ? can be printed as the character constant '?' rather than the character constant escape sequence '\?' using conversion specifier %c in the format control string of a printf statement.

**9.20** (*Using %g with Various Precisions*) Write a program that uses the conversion specifier g to output the value 9876.12345. Print the value with precisions ranging from 1 to 9.



# 10

## C Structures, Unions, Bit Manipulations and Enumerations

*But yet an union in partition.*

—William Shakespeare

*The same old charitable lie  
Repeated as the years scoot by  
Perpetually makes a bit—  
“You really haven’t changed a  
bit!”*

—Margaret Fishback

*I could never make out what  
those damned dots meant.*

—Winston Churchill

### Objectives

In this chapter, you’ll learn:

- To create and use structures, unions and enumerations.
- To pass structures to functions by value and by reference.
- To manipulate data with the bitwise operators.
- To create bit fields for storing data compactly.



|                                             |                                                                             |
|---------------------------------------------|-----------------------------------------------------------------------------|
| <b>10.1</b> Introduction                    | <b>10.7</b> Example: High-Performance Card Shuffling and Dealing Simulation |
| <b>10.2</b> Structure Definitions           | <b>10.8</b> Unions                                                          |
| <b>10.3</b> Initializing Structures         | <b>10.9</b> Bitwise Operators                                               |
| <b>10.4</b> Accessing Structure Members     | <b>10.10</b> Bit Fields                                                     |
| <b>10.5</b> Using Structures with Functions | <b>10.11</b> Enumeration Constants                                          |
| <b>10.6</b> typedef                         |                                                                             |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 10.1 Introduction

**Structures**—sometimes referred to as **aggregates**—are collections of related variables under one name. Structures may contain variables of many different data types—in contrast to arrays that contain only elements of the same data type. Structures are commonly used to define records to be stored in files (see Chapter 11, C File Processing). Pointers and structures facilitate the formation of more complex data structures such as linked lists, queues, stacks and trees (see Chapter 12, C Data Structures).

## 10.2 Structure Definitions

Structures are **derived data types**—they are constructed using objects of other types. Consider the following structure definition:

```
struct card {
 char *face;
 char *suit;
};
```

Keyword **struct** introduces the structure definition. The identifier **card** is the **structure tag**, which names the structure definition and is used with the keyword **struct** to declare variables of the **structure type**. In this example, the structure type is **struct card**. Variables declared within the braces of the structure definition are the structure's **members**. Members of the same structure type must have unique names, but two different structure types may contain members of the same name without conflict (we'll soon see why). Each structure definition must end with a semicolon.



### Common Programming Error 10.1

*Forgetting the semicolon that terminates a structure definition is a syntax error.*

The definition of **struct card** contains members **face** and **suit** of type **char \***. Structure members can be variables of the primitive data types (e.g., **int**, **float**, etc.), or aggregates, such as arrays and other structures. As we saw in Chapter 6, each element of an array must be of the same type. Structure members, however, can be of many types. For example, the following **struct** contains character array members for an employee's first and last names, an **int** member for the employee's age, a **char** member that would contain 'M' or 'F' for the employee's gender and a **double** member for the employee's hourly salary;

```

struct employee {
 char firstName[20];
 char lastName[20];
 int age;
 char gender;
 double hourlySalary;
};

```

### *Self-Referential Structures*

A structure cannot contain an instance of itself. For example, a variable of type `struct employee` cannot be declared in the definition for `struct employee`. A pointer to `struct employee`, however, may be included. For example,

```

struct employee2 {
 char firstName[20];
 char lastName[20];
 int age;
 char gender;
 double hourlySalary;
 struct employee2 person; /* ERROR */
 struct employee2 *ePtr; /* pointer */
};

```

`struct employee2` contains an instance of itself (`person`), which is an error. Because `ePtr` is a pointer (to type `struct employee2`), it is permitted in the definition. A structure containing a member that is a pointer to the same structure type is referred to as a **self-referential structure**. Self-referential structures are used in Chapter 12 to build linked data structures.

### *Defining Variables of Structure Types*

Structure definitions do not reserve any space in memory; rather, each definition creates a new data type that is used to define variables. Structure variables are defined like variables of other types. The definition

```

struct card aCard, deck[52], *cardPtr;

```

declares `aCard` to be a variable of type `struct card`, declares `deck` to be an array with 52 elements of type `struct card` and declares `cardPtr` to be a pointer to `struct card`. Variables of a given structure type may also be declared by placing a comma-separated list of the variable names between the closing brace of the structure definition and the semicolon that ends the structure definition. For example, the preceding definition could have been incorporated into the `struct card` structure definition as follows:

```

struct card {
 char *face;
 char *suit;
} aCard, deck[52], *cardPtr;

```

### *Structure Tag Names*

The structure tag name is optional. If a structure definition does not contain a structure tag name, variables of the structure type may be declared only in the structure definition—not in a separate declaration.

**Good Programming Practice 10.1**

*Always provide a structure tag name when creating a structure type. The structure tag name is convenient for declaring new variables of the structure type later in the program.*

**Good Programming Practice 10.2**

*Choosing a meaningful structure tag name helps make a program self-documenting.*

**Operations That Can Be Performed on Structures**

The only valid operations that may be performed on structures are the following: assigning structure variables to structure variables of the same type, taking the address (&) of a structure variable, accessing the members of a structure variable (see Section 10.4) and using the `sizeof` operator to determine the size of a structure variable.


**Common Programming Error 10.2**

*Assigning a structure of one type to a structure of a different type is a compilation error.*

Structures may not be compared using operators `==` and `!=`, because structure members are not necessarily stored in consecutive bytes of memory. Sometimes there are “holes” in a structure, because computers may store specific data types only on certain memory boundaries such as half word, word or double word boundaries. A word is a standard memory unit used to store data in a computer—usually 2 bytes or 4 bytes. Consider the following structure definition, in which `sample1` and `sample2` of type `struct example` are declared:

```
struct example {
 char c;
 int i;
} sample1, sample2;
```

A computer with 2-byte words may require that each member of `struct example` be aligned on a word boundary, i.e., at the beginning of a word (this is machine dependent). Figure 10.1 shows a sample storage alignment for a variable of type `struct example` that has been assigned the character 'a' and the integer 97 (the bit representations of the values are shown). If the members are stored beginning at word boundaries, there is a 1-byte hole (byte 1 in the figure) in the storage for variables of type `struct example`. The value in the 1-byte hole is undefined. Even if the member values of `sample1` and `sample2` are in fact equal, the structures are not necessarily equal, because the undefined 1-byte holes are not likely to contain identical values.



**Fig. 10.1** | Possible storage alignment for a variable of type `struct example` showing an undefined area in memory.

**Portability Tip 10.1**

*Because the size of data items of a particular type is machine dependent and because storage alignment considerations are machine dependent, so too is the representation of a structure.*

## 10.3 Initializing Structures

Structures can be initialized using initializer lists as with arrays. To initialize a structure, follow the variable name in the definition with an equals sign and a brace-enclosed, comma-separated list of initializers. For example, the declaration

```
struct card aCard = { "Three", "Hearts" };
```

creates variable `aCard` to be of type `struct card` (as defined in Section 10.2) and initializes member `face` to "Three" and member `suit` to "Hearts". If there are fewer initializers in the list than members in the structure, the remaining members are automatically initialized to 0 (or NULL if the member is a pointer). Structure variables defined outside a function definition (i.e., externally) are initialized to 0 or NULL if they are not explicitly initialized in the external definition. Structure variables may also be initialized in assignment statements by assigning a structure variable of the same type, or by assigning values to the individual members of the structure.

## 10.4 Accessing Structure Members

Two operators are used to access members of structures: the **structure member operator** (`.`)—also called the dot operator—and the **structure pointer operator** (`->`)—also called the **arrow operator**. The structure member operator accesses a structure member via the structure variable name. For example, to print member `suit` of structure variable `aCard` defined in Section 10.3, use the statement

```
printf("%s", aCard.suit); /* displays Hearts */
```

The structure pointer operator—consisting of a minus (`-`) sign and a greater than (`>`) sign with no intervening spaces—accesses a structure member via a **pointer to the structure**. Assume that the pointer `cardPtr` has been declared to point to `struct card` and that the address of structure `aCard` has been assigned to `cardPtr`. To print member `suit` of structure `aCard` with pointer `cardPtr`, use the statement

```
printf("%s", cardPtr->suit); /* displays Hearts */
```

The expression `cardPtr->suit` is equivalent to `(*cardPtr).suit`, which dereferences the pointer and accesses the member `suit` using the structure member operator. The parentheses are needed here because the structure member operator (`.`) has a higher precedence than the pointer dereferencing operator (`*`). The structure pointer operator and structure member operator, along with parentheses (for calling functions) and brackets (`[]`) used for array subscripting, have the highest operator precedence and associate from left to right.

**Good Programming Practice 10.3**

*Do not put spaces around the `->` and `.` operators. Omitting spaces helps emphasize that the expressions the operators are contained in are essentially single variable names.*



### Common Programming Error 10.3

*Inserting space between the - and > components of the structure pointer operator (or between the components of any other multiple keystroke operator except ?:) is a syntax error.*



### Common Programming Error 10.4

*Attempting to refer to a member of a structure by using only the member's name is a syntax error.*



### Common Programming Error 10.5

*Not using parentheses when referring to a structure member that uses a pointer and the structure member operator (e.g., \*cardPtr.suit) is a syntax error.*

The program of Fig. 10.2 demonstrates the use of the structure member and structure pointer operators. Using the structure member operator, the members of structure aCard are assigned the values "Ace" and "Spades", respectively (lines 18 and 19). Pointer cardPtr is assigned the address of structure aCard (line 21). Function printf prints the members of structure variable aCard using the structure member operator with variable name aCard, the structure pointer operator with pointer cardPtr and the structure member operator with dereferenced pointer cardPtr (lines 23 through 25).

```

1 /* Fig. 10.2: fig10_02.c
2 Using the structure member and
3 structure pointer operators */
4 #include <stdio.h>
5
6 /* card structure definition */
7 struct card {
8 char *face; /* define pointer face */
9 char *suit; /* define pointer suit */
10 }; /* end structure card */
11
12 int main(void)
13 {
14 struct card aCard; /* define one struct card variable */
15 struct card *cardPtr; /* define a pointer to a struct card */
16
17 /* place strings into aCard */
18 aCard.face = "Ace";
19 aCard.suit = "Spades";
20
21 cardPtr = &aCard; /* assign address of aCard to cardPtr */
22
23 printf("%s%s\n%s%s\n%s%s\n", aCard.face, " of ", aCard.suit,
24 cardPtr->face, " of ", cardPtr->suit,
25 (*cardPtr).face, " of ", (*cardPtr).suit);
26 return 0; /* indicates successful termination */
27 } /* end main */

```

**Fig. 10.2** | Structure member operator and structure pointer operator. (Part I of 2.)



```
Ace of Spades
Ace of Spades
Ace of Spades
```

**Fig. 10.2** | Structure member operator and structure pointer operator. (Part 2 of 2.)

## 10.5 Using Structures with Functions

Structures may be passed to functions by passing individual structure members, by passing an entire structure or by passing a pointer to a structure. When structures or individual structure members are passed to a function, they are passed by value. Therefore, the members of a caller's structure cannot be modified by the called function. To pass a structure by reference, pass the address of the structure variable. Arrays of structures—like all other arrays—are automatically passed by reference.

In Chapter 6, we stated that an array could be passed by value by using a structure. To pass an array by value, create a structure with the array as a member. Structures are passed by value, so the array is passed by value.



### Common Programming Error 10.6

*Assuming that structures, like arrays, are automatically passed by reference and trying to modify the caller's structure values in the called function is a logic error.*



### Performance Tip 10.1

*Passing structures by reference is more efficient than passing structures by value (which requires the entire structure to be copied).*

## 10.6 typedef

The keyword **typedef** provides a mechanism for creating synonyms (or aliases) for previously defined data types. Names for structure types are often defined with **typedef** to create shorter type names. For example, the statement

```
typedef struct card Card;
```

defines the new type name **Card** as a synonym for type **struct card**. C programmers often use **typedef** to define a structure type, so a structure tag is not required. For example, the following definition

```
typedef struct {
 char *face;
 char *suit;
} Card;
```

creates the structure type **Card** without the need for a separate **typedef** statement.



### Good Programming Practice 10.4

*Capitalize the first letter of **typedef** names to emphasize that they are synonyms for other type names.*

Card can now be used to declare variables of type struct card. The declaration

```
Card deck[52];
```

declares an array of 52 Card structures (i.e., variables of type struct card). Creating a new name with typedef does not create a new type; typedef simply creates a new type name, which may be used as an alias for an existing type name. A meaningful name helps make the program self-documenting. For example, when we read the previous declaration, we know “deck is an array of 52 Cards.”

Often, typedef is used to create synonyms for the basic data types. For example, a program requiring 4-byte integers may use type int on one system and type long on another. Programs designed for portability often use typedef to create an alias for 4-byte integers, such as Integer. The alias Integer can be changed once in the program to make the program work on both systems.



### Portability Tip 10.2

*Use typedef to help make a program more portable.*

## 10.7 Example: High-Performance Card Shuffling and Dealing Simulation

The program in Fig. 10.3 is based on the card shuffling and dealing simulation discussed in Chapter 7. The program represents the deck of cards as an array of structures. The program uses high-performance shuffling and dealing algorithms. The output for the high-performance card shuffling and dealing program is shown in Fig. 10.4.

```
1 /* Fig. 10.3: fig10_03.c
2 The card shuffling and dealing program using structures */
3 #include <stdio.h>
4 #include <stdlib.h>
5 #include <time.h>
6
7 /* card structure definition */
8 struct card {
9 const char *face; /* define pointer face */
10 const char *suit; /* define pointer suit */
11 }; /* end structure card */
12
13 typedef struct card Card; /* new type name for struct card */
14
15 /* prototypes */
16 void fillDeck(Card * const wDeck, const char * wFace[],
17 const char * wSuit[]);
18 void shuffle(Card * const wDeck);
19 void deal(const Card * const wDeck);
20
21 int main(void)
22 {
```

**Fig. 10.3** | High-performance card shuffling and dealing simulation. (Part I of 3.)



```

23 Card deck[52]; /* define array of Cards */
24
25 /* initialize array of pointers */
26 const char *face[] = { "Ace", "Deuce", "Three", "Four", "Five",
27 "Six", "Seven", "Eight", "Nine", "Ten",
28 "Jack", "Queen", "King"};
29
30 /* initialize array of pointers */
31 const char *suit[] = { "Hearts", "Diamonds", "Clubs", "Spades"};
32
33 srand(time(NULL)); /* randomize */
34
35 fillDeck(deck, face, suit); /* load the deck with Cards */
36 shuffle(deck); /* put Cards in random order */
37 deal(deck); /* deal all 52 Cards */
38 return 0; /* indicates successful termination */
39 } /* end main */
40
41 /* place strings into Card structures */
42 void fillDeck(Card * const wDeck, const char * wFace[],
43 const char * wSuit[])
44 {
45 int i; /* counter */
46
47 /* loop through wDeck */
48 for (i = 0; i <= 51; i++) {
49 wDeck[i].face = wFace[i % 13];
50 wDeck[i].suit = wSuit[i / 13];
51 } /* end for */
52 } /* end function fillDeck */
53
54 /* shuffle cards */
55 void shuffle(Card * const wDeck)
56 {
57 int i; /* counter */
58 int j; /* variable to hold random value between 0 - 51 */
59 Card temp; /* define temporary structure for swapping Cards */
60
61 /* loop through wDeck randomly swapping Cards */
62 for (i = 0; i <= 51; i++) {
63 j = rand() % 52;
64 temp = wDeck[i];
65 wDeck[i] = wDeck[j];
66 wDeck[j] = temp;
67 } /* end for */
68 } /* end function shuffle */
69
70 /* deal cards */
71 void deal(const Card * const wDeck)
72 {
73 int i; /* counter */
74

```

**Fig. 10.3** | High-performance card shuffling and dealing simulation. (Part 2 of 3.)

```

75 /* loop through wDeck */
76 for (i = 0; i <= 51; i++) {
77 printf("%5s of %-8s%s", wDeck[i].face, wDeck[i].suit,
78 (i + 1) % 4 ? " " : "\n");
79 } /* end for */
80 } /* end function deal */

```

**Fig. 10.3** | High-performance card shuffling and dealing simulation. (Part 3 of 3.)

|                   |                   |                   |                   |
|-------------------|-------------------|-------------------|-------------------|
| Three of Hearts   | Jack of Clubs     | Three of Spades   | Six of Diamonds   |
| Five of Hearts    | Eight of Spades   | Three of Clubs    | Deuce of Spades   |
| Jack of Spades    | Four of Hearts    | Deuce of Hearts   | Six of Clubs      |
| Queen of Clubs    | Three of Diamonds | Eight of Diamonds | King of Clubs     |
| King of Hearts    | Eight of Hearts   | Queen of Hearts   | Seven of Clubs    |
| Seven of Diamonds | Nine of Spades    | Five of Clubs     | Eight of Clubs    |
| Six of Hearts     | Deuce of Diamonds | Five of Spades    | Four of Clubs     |
| Deuce of Clubs    | Nine of Hearts    | Seven of Hearts   | Four of Spades    |
| Ten of Spades     | King of Diamonds  | Ten of Hearts     | Jack of Diamonds  |
| Four of Diamonds  | Six of Spades     | Five of Diamonds  | Ace of Diamonds   |
| Ace of Clubs      | Jack of Hearts    | Ten of Clubs      | Queen of Diamonds |
| Ace of Hearts     | Ten of Diamonds   | Nine of Clubs     | King of Spades    |
| Ace of Spades     | Nine of Diamonds  | Seven of Spades   | Queen of Spades   |

**Fig. 10.4** | Output for the high-performance card shuffling and dealing simulation.

In the program, function `fillDeck` (lines 42–52) initializes the `Card` array in order with Ace through King of each suit. The `Card` array is passed (in line 36) to function `shuffle` (lines 55–68), where the high-performance shuffling algorithm is implemented. Function `shuffle` takes an array of 52 `Card` structures as an argument. The function loops through the 52 cards (array subscripts 0 to 51) using a `for` statement in lines 62–67. For each card, a number between 0 and 51 is picked randomly. Next, the current `Card` structure and the randomly selected `Card` structure are swapped in the array (lines 64 through 66). A total of 52 swaps are made in a single pass of the entire array, and the array of `Card` structures is shuffled! This algorithm cannot suffer from indefinite postponement like the shuffling algorithm presented in Chapter 7. Since the `Card` structures were swapped in place in the array, the high-performance dealing algorithm implemented in function `deal` (lines 71–80) requires only one pass of the array to deal the shuffled cards.



### Common Programming Error 10.7

*Forgetting to include the array subscript when referring to individual structures in an array of structures is a syntax error.*

## 10.8 Unions

A **union** is a derived data type—like a structure—with members that share the same storage space. For different situations in a program, some variables may not be relevant, but other variables are—so a union shares the space instead of wasting storage on variables that are not being used. The members of a union can be of any data type. The number of bytes used to store a union must be at least enough to hold the largest member. In most cases,

unions contain two or more data types. Only one member, and thus one data type, can be referenced at a time. It is your responsibility to ensure that the data in a union is referenced with the proper data type.



### Common Programming Error 10.8

*Referencing data in a union with a variable of the wrong type is a logic error.*



### Portability Tip 10.3

*If data is stored in a union as one type and referenced as another type, the results are implementation dependent.*

### Union Declarations

A union is declared with keyword `union` in the same format as a structure. The union definition

```
union number {
 int x;
 double y;
};
```

indicates that `number` is a union type with members `int x` and `double y`. The union definition is normally placed in a header and included in all source files that use the union type.



### Software Engineering Observation 10.1

*As with a struct definition, a union definition simply creates a new type. Placing a union or struct definition outside any function does not create a global variable.*

### Operations That Can Be Performed on Unions

The operations that can be performed on a union are the following: assigning a union to another union of the same type, taking the address (`&`) of a union variable, and accessing union members using the structure member operator and the structure pointer operator. Unions may not be compared using operators `==` and `!=` for the same reasons that structures cannot be compared.

### Initializing Unions in Declarations

In a declaration, a union may be initialized with a value of the same type as the first union member. For example, with the preceding union, the declaration

```
union number value = { 10 };
```

is a valid initialization of union variable `value` because the union is initialized with an `int`, but the following declaration would truncate the floating-point part of the initializer value and normally would produce a warning from the compiler:

```
union number value = { 1.43 };
```



### Common Programming Error 10.9

*Comparing unions is a syntax error.*

**Portability Tip 10.4**

*The amount of storage required to store a union is implementation dependent but will always be at least as large as the largest member of the union.*

**Portability Tip 10.5**

*Some unions may not port easily to other computer systems. Whether a union is portable or not often depends on the storage alignment requirements for the union member data types on a given system.*

**Performance Tip 10.2**

*Unions conserve storage.*

**Demonstrating Unions**

The program in Fig. 10.5 uses the variable `value` (line 13) of type union `number` to display the value stored in the union as both an `int` and a `double`. The program output is implementation dependent. The program output shows that the internal representation of a `double` value can be quite different from the representation of `int`.

```

1 /* Fig. 10.5: fig10_05.c
2 An example of a union */
3 #include <stdio.h>
4
5 /* number union definition */
6 union number {
7 int x;
8 double y;
9 }; /* end union number */
10
11 int main(void)
12 {
13 union number value; /* define union variable */
14
15 value.x = 100; /* put an integer into the union */
16 printf("%s\n%s\n%s\n %d\n\n%s\n %f\n\n",
17 "Put a value in the integer member",
18 "and print both members.",
19 "int:", value.x,
20 "double:", value.y);
21
22 value.y = 100.0; /* put a double into the same union */
23 printf("%s\n%s\n%s\n %d\n\n%s\n %f\n",
24 "Put a value in the floating member",
25 "and print both members.",
26 "int:", value.x,
27 "double:", value.y);
28 return 0; /* indicates successful termination */
29 } /* end main */

```

**Fig. 10.5** | Displaying the value of a union in both member data types. (Part I of 2.)

```
Put a value in the integer member
and print both members.
```

```
int:
 100
```

```
double:
```

```
-92559592117433136000.000000
```

```
Put a value in the floating member
and print both members.
```

```
int:
 0
```

```
double:
```

```
100.000000
```

**Fig. 10.5** | Displaying the value of a union in both member data types. (Part 2 of 2.)

## 10.9 Bitwise Operators

Computers represent all data internally as sequences of bits. Each bit can assume the value 0 or the value 1. On most systems, a sequence of 8 bits forms a byte—the standard storage unit for a variable of type `char`. Other data types are stored in larger numbers of bytes. The bitwise operators are used to manipulate the bits of integral operands (`char`, `short`, `int` and `long`; both signed and unsigned). Unsigned integers are normally used with the bitwise operators.



### Portability Tip 10.6

*Bitwise data manipulations are machine dependent.*

The bitwise operator discussions in this section show the binary representations of the integer operands. For a detailed explanation of the binary (also called base-2) number system see Appendix C. Also, the programs in Sections 10.9–10.10 were tested using Microsoft Visual C++. Because of the machine-dependent nature of bitwise manipulations, these programs may not work on your system.

The bitwise operators are **bitwise AND (&)**, **bitwise inclusive OR (|)**, **bitwise exclusive OR (^)**, **left shift (<<)**, **right shift (>>)** and **complement (~)**. The bitwise AND, bitwise inclusive OR and bitwise exclusive OR operators compare their two operands bit by bit. The bitwise AND operator sets each bit in the result to 1 if the corresponding bit in both operands is 1. The bitwise inclusive OR operator sets each bit in the result to 1 if the corresponding bit in either (or both) operand(s) is 1. The bitwise exclusive OR operator sets each bit in the result to 1 if the corresponding bit in exactly one operand is 1. The left-shift operator shifts the bits of its left operand to the left by the number of bits specified in its right operand. The right-shift operator shifts the bits in its left operand to the right by the number of bits specified in its right operand. The bitwise complement operator sets all 0 bits in its operand to 1 in the result and sets all 1 bits to 0 in the result. Detailed discussions of each bitwise operator appear in the following examples. The bitwise operators are summarized in Fig. 10.6.

| Operator                  | Description                                                                                                                                                 |
|---------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|
| &    bitwise AND          | The bits in the result are set to 1 if the corresponding bits in the two operands are both 1.                                                               |
| bitwise inclusive OR      | The bits in the result are set to 1 if at least one of the corresponding bits in the two operands is 1.                                                     |
| ^    bitwise exclusive OR | The bits in the result are set to 1 if exactly one of the corresponding bits in the two operands is 1.                                                      |
| <<   left shift           | Shifts the bits of the first operand left by the number of bits specified by the second operand; fill from the right with 0 bits.                           |
| >>   right shift          | Shifts the bits of the first operand right by the number of bits specified by the second operand; the method of filling from the left is machine dependent. |
| ~    one's complement     | All 0 bits are set to 1 and all 1 bits are set to 0.                                                                                                        |

**Fig. 10.6** | Bitwise operators.

### *Displaying an Unsigned Integer in Bits*

When using the bitwise operators, it is useful to print values in their binary representation to illustrate the precise effects of these operators. The program of Fig. 10.7 prints an unsigned integer in its binary representation in groups of eight bits each. For the examples in this section, we assume that unsigned integers are stored in 4 bytes (32 bits) of memory.

```

1 /* Fig. 10.7: fig10_07.c
2 Printing an unsigned integer in bits */
3 #include <stdio.h>
4
5 void displayBits(unsigned value); /* prototype */
6
7 int main(void)
8 {
9 unsigned x; /* variable to hold user input */
10
11 printf("Enter an unsigned integer: ");
12 scanf("%u", &x);
13
14 displayBits(x);
15 return 0; /* indicates successful termination */
16 } /* end main */
17
18 /* display bits of an unsigned integer value */
19 void displayBits(unsigned value)
20 {
21 unsigned c; /* counter */
22
23 /* define displayMask and left shift 31 bits */
24 unsigned displayMask = 1 << 31;
25
```

**Fig. 10.7** | Displaying an unsigned integer in bits. (Part I of 2.)

```
26 printf("%10u = ", value);
27
28 /* loop through bits */
29 for (c = 1; c <= 32; c++) {
30 putchar(value & displayMask ? '1' : '0');
31 value <= 1; /* shift value left by 1 */
32
33 if (c % 8 == 0) { /* output space after 8 bits */
34 putchar(' ');
35 } /* end if */
36 } /* end for */
37
38 putchar('\n');
39 } /* end function displayBits */
```

Enter an unsigned integer: **65000**  
65000 = 00000000 00000000 11111101 11101000

**Fig. 10.7** | Displaying an unsigned integer in bits. (Part 2 of 2.)

Function `displayBits` (lines 19–39) uses the bitwise AND operator to combine variable `value` with variable `displayMask` (line 32). Often, the bitwise AND operator is used with an operand called a **mask**—an integer value with specific bits set to 1. Masks are used to hide some bits in a value while selecting other bits. In function `displayBits`, mask variable `displayMask` is assigned the value

```
1 << 31 (10000000 00000000 00000000 00000000)
```

The left-shift operator shifts the value 1 from the low order (rightmost) bit to the high order (leftmost) bit in `displayMask` and fills in 0 bits from the right. Line 32

```
putchar(value & displayMask ? '1' : '0');
```

determines whether a 1 or a 0 should be printed for the current leftmost bit of variable `value`. When `value` and `displayMask` are combined using `&`, all the bits except the high-order bit in variable `value` are “masked off” (hidden), because any bit “ANDed” with 0 yields 0. If the leftmost bit is 1, `value & displayMask` evaluates to a nonzero (true) value and 1 is printed—otherwise, 0 is printed. Variable `value` is then left shifted one bit by the expression `value <= 1` (this is equivalent to `value = value << 1`). These steps are repeated for each bit in unsigned variable `value`. Figure 10.8 summarizes the results of combining two bits with the bitwise AND operator.

| Bit 1 | Bit 2 | Bit 1 & Bit 2 |
|-------|-------|---------------|
| 0     | 0     | 0             |
| 1     | 0     | 0             |
| 0     | 1     | 0             |
| 1     | 1     | 1             |

**Fig. 10.8** | Results of combining two bits with the bitwise AND operator `&`.



### Common Programming Error 10.10

Using the logical AND operator (&&) for the bitwise AND operator (&) and vice versa is an error.

#### *Making Function `displayBits` More Scalable and Portable*

In line 24 of Fig. 10.7, we hard coded the integer 31 to indicate that the value 1 should be shifted to the leftmost bit in the variable `displayMask`. Similarly, in line 29, we hard coded the integer 32 to indicate that the loop should iterate 32 times—once for each bit in variable `value`. We assumed that unsigned integers are always stored in 32 bits (4 bytes) of memory. Many of today's popular computers use 32-bit word hardware architectures. C programmers tend to work across many hardware architectures, and sometimes unsigned integers will be stored in smaller or larger numbers of bits.

The program in Fig. 10.7 can be made more scalable and more portable by replacing the integer 31 in line 24 with the expression

```
CHAR_BIT * sizeof(unsigned) - 1
```

and by replacing the integer 32 in line 29 with the the expression

```
CHAR_BIT * sizeof(unsigned)
```

The symbolic constant `CHAR_BIT` (defined in `<limits.h>`) represents the number of bits in a byte (normally 8). As you learned in Section 7.7, operator `sizeof` determines the number of bytes used to store an object or type. On a computer that uses 32-bit words, the expression `sizeof( unsigned )` evaluates to 4, so the two preceding expressions evaluate to 31 and 32, respectively. On a computer that uses 16-bit words, the `sizeof` expression evaluates to 2 and the two preceding expressions evaluate to 15 and 16, respectively.

#### *Using the Bitwise AND, Inclusive OR, Exclusive OR and Complement Operators*

Figure 10.9 demonstrates the use of the bitwise AND operator, the bitwise inclusive OR operator, the bitwise exclusive OR operator and the bitwise complement operator. The program uses function `displayBits` (lines 53–74) to print the unsigned integer values. The output is shown in Fig. 10.10.

```
1 /* Fig. 10.9: fig10_09.c
2 Using the bitwise AND, bitwise inclusive OR, bitwise
3 exclusive OR and bitwise complement operators */
4 #include <stdio.h>
5
6 void displayBits(unsigned value); /* prototype */
7
8 int main(void)
9 {
10 unsigned number1;
11 unsigned number2;
12 unsigned mask;
13 unsigned setBits;
```

**Fig. 10.9** | Bitwise AND, bitwise inclusive OR, bitwise exclusive OR and bitwise complement operators. (Part I of 3.)



```

14
15 /* demonstrate bitwise AND (&) */
16 number1 = 65535;
17 mask = 1;
18 printf("The result of combining the following\n");
19 displayBits(number1);
20 displayBits(mask);
21 printf("using the bitwise AND operator & is\n");
22 displayBits(number1 & mask);
23
24 /* demonstrate bitwise inclusive OR (|) */
25 number1 = 15;
26 setBits = 241;
27 printf("\nThe result of combining the following\n");
28 displayBits(number1);
29 displayBits(setBits);
30 printf("using the bitwise inclusive OR operator | is\n");
31 displayBits(number1 | setBits);
32
33 /* demonstrate bitwise exclusive OR (^) */
34 number1 = 139;
35 number2 = 199;
36 printf("\nThe result of combining the following\n");
37 displayBits(number1);
38 displayBits(number2);
39 printf("using the bitwise exclusive OR operator ^ is\n");
40 displayBits(number1 ^ number2);
41
42 /* demonstrate bitwise complement (~)*/
43 number1 = 21845;
44 printf("\nThe one's complement of\n");
45 displayBits(number1);
46 printf("is\n");
47 displayBits(~number1);
48 return 0; /* indicates successful termination */
49 } /* end main */
50
51 /* display bits of an unsigned integer value */
52 void displayBits(unsigned value)
53 {
54 unsigned c; /* counter */
55
56 /* declare displayMask and left shift 31 bits */
57 unsigned displayMask = 1 << 31;
58
59 printf("%10u = ", value);
60
61 /* loop through bits */
62 for (c = 1; c <= 32; c++) {
63 putchar(value & displayMask ? '1' : '0');
64 value <<= 1; /* shift value left by 1 */

```

**Fig. 10.9** | Bitwise AND, bitwise inclusive OR, bitwise exclusive OR and bitwise complement operators. (Part 2 of 3.)

```

65
66 if (c % 8 == 0) { /* output a space after 8 bits */
67 putchar(' ');
68 } /* end if */
69 } /* end for */
70
71 putchar('\n');
72 } /* end function displayBits */

```

**Fig. 10.9** | Bitwise AND, bitwise inclusive OR, bitwise exclusive OR and bitwise complement operators. (Part 3 of 3.)

```

The result of combining the following
65535 = 00000000 00000000 11111111 11111111
1 = 00000000 00000000 00000000 00000001
using the bitwise AND operator & is
1 = 00000000 00000000 00000000 00000001

The result of combining the following
15 = 00000000 00000000 00000000 00001111
241 = 00000000 00000000 00000000 11110001
using the bitwise inclusive OR operator | is
255 = 00000000 00000000 00000000 11111111

The result of combining the following
139 = 00000000 00000000 00000000 10001011
199 = 00000000 00000000 00000000 11000111
using the bitwise exclusive OR operator ^ is
76 = 00000000 00000000 00000000 01001100

The one's complement of
21845 = 00000000 00000000 01010101 01010101
is
4294945450 = 11111111 11111111 10101010 10101010

```

**Fig. 10.10** | Output for the program of Fig. 10.9.

In Fig. 10.9, integer variable `number1` is assigned value 65535 (00000000 00000000 11111111 11111111) in line 16 and variable `mask` is assigned the value 1 (00000000 00000000 00000000 00000001) in line 17. When `number1` and `mask` are combined using the bitwise AND operator (`&`) in the expression `number1 & mask` (line 22), the result is 00000000 00000000 00000000 00000001. All the bits except the low-order bit in variable `number1` are “masked off” (hidden) by “ANDing” with variable `mask`.

The bitwise inclusive OR operator is used to set specific bits to 1 in an operand. In Fig. 10.9, variable `number1` is assigned 15 (00000000 00000000 00000000 00001111) in line 25, and variable `setBits` is assigned 241 (00000000 00000000 00000000 11110001) in line 26. When `number1` and `setBits` are combined using the bitwise OR operator in the expression `number1 | setBits` (line 31), the result is 255 (00000000 00000000 00000000 11111111). Figure 10.11 summarizes the results of combining two bits with the bitwise inclusive OR operator.



### Common Programming Error 10.11

Using the logical OR operator (`||`) for the bitwise OR operator (`|`) and vice versa is an error.

| Bit 1 | Bit 2 | Bit 1   Bit 2 |
|-------|-------|---------------|
| 0     | 0     | 0             |
| 1     | 0     | 1             |
| 0     | 1     | 1             |
| 1     | 1     | 1             |

**Fig. 10.11** | Results of combining two bits with the bitwise inclusive OR operator |.

The bitwise exclusive OR operator ( $\wedge$ ) sets each bit in the result to 1 if *exactly* one of the corresponding bits in its two operands is 1. In Fig. 10.9, variables `number1` and `number2` are assigned the values 139 (00000000 00000000 00000000 10001011) and 199 (00000000 00000000 00000000 11000111) in lines 34–35. When these variables are combined with the exclusive OR operator in the expression `number1 ^ number2` (line 40), the result is 00000000 00000000 00000000 01001100. Figure 10.12 summarizes the results of combining two bits with the bitwise exclusive OR operator.

| Bit 1 | Bit 2 | Bit 1 ^ Bit 2 |
|-------|-------|---------------|
| 0     | 0     | 0             |
| 1     | 0     | 1             |
| 0     | 1     | 1             |
| 1     | 1     | 0             |

**Fig. 10.12** | Results of combining two bits with the bitwise exclusive OR operator  $\wedge$ .

The **bitwise complement operator** ( $\sim$ ) sets all 1 bits in its operand to 0 in the result and sets all 0 bits to 1 in the result—otherwise referred to as “taking the **one’s complement** of the value.” In Fig. 10.9, variable `number1` is assigned the value 21845 (00000000 00000000 01010101 01010101) in line 43. When the expression `~number1` (line 47) is evaluated, the result is 00000000 00000000 10101010 10101010.

### Using the Bitwise Left- and Right-Shift Operators

The program of Fig. 10.13 demonstrates the left-shift operator ( $\ll$ ) and the right-shift operator ( $\gg$ ). Function `displayBits` is used to print the unsigned integer values.

---

```

1 /* Fig. 10.13: fig10_13.c
2 Using the bitwise shift operators */
3 #include <stdio.h>
4
5 void displayBits(unsigned value); /* prototype */
6
```

---

**Fig. 10.13** | Bitwise shift operators. (Part I of 2.)

```

7 int main(void)
8 {
9 unsigned number1 = 960; /* initialize number1 */
10
11 /* demonstrate bitwise left shift */
12 printf("\nThe result of left shifting\n");
13 displayBits(number1);
14 printf("8 bit positions using the ");
15 printf("left shift operator << is\n");
16 displayBits(number1 << 8);
17
18 /* demonstrate bitwise right shift */
19 printf("\nThe result of right shifting\n");
20 displayBits(number1);
21 printf("8 bit positions using the ");
22 printf("right shift operator >> is\n");
23 displayBits(number1 >> 8);
24 return 0; /* indicates successful termination */
25 } /* end main */
26
27 /* display bits of an unsigned integer value */
28 void displayBits(unsigned value)
29 {
30 unsigned c; /* counter */
31
32 /* declare displayMask and left shift 31 bits */
33 unsigned displayMask = 1 << 31;
34
35 printf("%7u = ", value);
36
37 /* loop through bits */
38 for (c = 1; c <= 32; c++) {
39 putchar(value & displayMask ? '1' : '0');
40 value <= 1; /* shift value left by 1 */
41
42 if (c % 8 == 0) { /* output a space after 8 bits */
43 putchar(' ');
44 } /* end if */
45 } /* end for */
46
47 putchar('\n');
48 } /* end function displayBits */

```

The result of left shifting  
 960 = 00000000 00000000 00000011 11000000  
 8 bit positions using the left shift operator << is  
 245760 = 00000000 00000011 11000000 00000000

The result of right shifting  
 960 = 00000000 00000000 00000011 11000000  
 8 bit positions using the right shift operator >> is  
 3 = 00000000 00000000 00000000 00000011

**Fig. 10.13** | Bitwise shift operators. (Part 2 of 2.)

The left-shift operator (`<<`) shifts the bits of its left operand to the left by the number of bits specified in its right operand. Bits vacated to the right are replaced with 0s; 1s shifted off the left are lost. In Fig. 10.13, variable `number1` is assigned the value 960 (00000000 00000000 00000011 11000000) in line 9. The result of left shifting variable `number1` 8 bits in the expression `number1 << 8` (line 16) is 49152 (00000000 00000000 11000000 00000000).

The right-shift operator (`>>`) shifts the bits of its left operand to the right by the number of bits specified in its right operand. Performing a right shift on an unsigned integer causes the vacated bits at the left to be replaced by 0s; 1s shifted off the right are lost. In Fig. 10.13, the result of right shifting `number1` in the expression `number1 >> 8` (line 23) is 3 (00000000 00000000 00000000 00000011).



**Common Programming Error 10.12**  
*The result of shifting a value is undefined if the right operand is negative or if the right operand is larger than the number of bits in which the left operand is stored.*



**Portability Tip 10.7**  
*Right shifting is machine dependent. Right shifting a signed integer fills the vacated bits with 0s on some machines and with 1s on others.*

**Bitwise Assignment Operators**

Each binary bitwise operator has a corresponding assignment operator. These **bitwise assignment operators** are shown in Fig. 10.14 and are used in a manner similar to the arithmetic assignment operators introduced in Chapter 3.

| Bitwise assignment operators |                                           |
|------------------------------|-------------------------------------------|
| <code>&amp;=</code>          | Bitwise AND assignment operator.          |
| <code> =</code>              | Bitwise inclusive OR assignment operator. |
| <code>^=</code>              | Bitwise exclusive OR assignment operator. |
| <code>&lt;&lt;=</code>       | Left-shift assignment operator.           |
| <code>&gt;&gt;=</code>       | Right-shift assignment operator.          |

**Fig. 10.14** | The bitwise assignment operators.

Figure 10.15 shows the precedence and associativity of the various operators introduced to this point in the text. They are shown top to bottom in decreasing order of precedence.

| Operator                                         | Associativity | Type    |
|--------------------------------------------------|---------------|---------|
| <code>() [] . -&gt;</code>                       | left to right | highest |
| <code>+ - ++ -- ! &amp; * ~ sizeof (type)</code> | right to left | unary   |

**Fig. 10.15** | Operator precedence and associativity. (Part 1 of 2.)

| Operator                          | Associativity | Type           |
|-----------------------------------|---------------|----------------|
| * / %                             | left to right | multiplicative |
| + -                               | left to right | additive       |
| << >>                             | left to right | shifting       |
| < <= > >=                         | left to right | relational     |
| == !=                             | left to right | equality       |
| &                                 | left to right | bitwise AND    |
| ^                                 | left to right | bitwise OR     |
|                                   | left to right | bitwise OR     |
| &&                                | left to right | logical AND    |
|                                   | left to right | logical OR     |
| ?:                                | right to left | conditional    |
| = += -= *= /= &=  = ^= <<= >>= %= | right to left | assignment     |
| ,                                 | left to right | comma          |

**Fig. 10.15** | Operator precedence and associativity. (Part 2 of 2.)

## 10.10 Bit Fields

C enables you to specify the number of bits in which an unsigned or int member of a structure or union is stored. This is referred to as a **bit field**. Bit fields enable better memory utilization by storing data in the minimum number of bits required. Bit field members *must* be declared as int or unsigned



### Performance Tip 10.3

*Bit fields help conserve storage.*

Consider the following structure definition:

```
struct bitCard {
 unsigned face : 4;
 unsigned suit : 2;
 unsigned color : 1;
};
```

which contains three unsigned bit fields—face, suit and color—used to represent a card from a deck of 52 cards. A bit field is declared by following an unsigned or int **member name** with a colon (:) and an integer constant representing the **width** of the field (i.e., the number of bits in which the member is stored). The constant representing the width must be an integer between 0 and the total number of bits used to store an int on your system, inclusive. Our examples were tested on a computer with 4-byte (32-bit) integers.

The preceding structure definition indicates that member face is stored in 4 bits, member suit is stored in 2 bits and member color is stored in 1 bit. The number of bits is based on the desired range of values for each structure member. Member face stores values from 0 (Ace) through 12 (King)—4 bits can store values in the range 0–15. Member

suit stores values from 0 through 3 (0 = Diamonds, 1 = Hearts, 2 = Clubs, 3 = Spades)—2 bits can store values in the range 0–3. Finally, member color stores either 0 (Red) or 1 (Black)—1 bit can store either 0 or 1.

Figure 10.16 (output shown in Fig. 10.17) creates array deck containing 52 struct bitCard structures in line 20. Function fillDeck (lines 28–38) inserts the 52 cards in the deck array and function deal (lines 42–54) prints the 52 cards. Notice that bit field members of structures are accessed exactly as any other structure member. Member color is included as a means of indicating the card color on a system that allows color displays. It is possible to specify an **unnamed bit field** to be used as **padding** in the structure. For example, the structure definition

```
struct example {
 unsigned a : 13;
 unsigned : 19;
 unsigned b : 4;
};
```

uses an unnamed 19-bit field as padding—nothing can be stored in those 19 bits. Member b (on our 4-byte-word computer) is stored in another storage unit.

---

```
1 /* Fig. 10.16: fig10_16.c
2 Representing cards with bit fields in a struct */
3
4 #include <stdio.h>
5
6 /* bitCard structure definition with bit fields */
7 struct bitCard {
8 unsigned face : 4; /* 4 bits; 0-15 */
9 unsigned suit : 2; /* 2 bits; 0-3 */
10 unsigned color : 1; /* 1 bit; 0-1 */
11 }; /* end struct bitCard */
12
13 typedef struct bitCard Card; /* new type name for struct bitCard */
14
15 void fillDeck(Card * const wDeck); /* prototype */
16 void deal(const Card * const wDeck); /* prototype */
17
18 int main(void)
19 {
20 Card deck[52]; /* create array of Cards */
21
22 fillDeck(deck);
23 deal(deck);
24 return 0; /* indicates successful termination */
25 } /* end main */
26
27 /* initialize Cards */
28 void fillDeck(Card * const wDeck)
29 {
30 int i; /* counter */
31
```

---

**Fig. 10.16** | Bit fields to store a deck of cards. (Part 1 of 2.)

```

32 /* loop through wDeck */
33 for (i = 0; i <= 51; i++) {
34 wDeck[i].face = i % 13;
35 wDeck[i].suit = i / 13;
36 wDeck[i].color = i / 26;
37 } /* end for */
38 } /* end function fillDeck */
39
40 /* output cards in two column format; cards 0-25 subscripted with
41 k1 (column 1); cards 26-51 subscripted k2 (column 2) */
42 void deal(const Card * const wDeck)
43 {
44 int k1; /* subscripts 0-25 */
45 int k2; /* subscripts 26-51 */
46
47 /* loop through wDeck */
48 for (k1 = 0, k2 = k1 + 26; k1 <= 25; k1++, k2++) {
49 printf("Card:%3d Suit:%2d Color:%2d ",
50 wDeck[k1].face, wDeck[k1].suit, wDeck[k1].color);
51 printf("Card:%3d Suit:%2d Color:%2d\n",
52 wDeck[k2].face, wDeck[k2].suit, wDeck[k2].color);
53 } /* end for */
54 } /* end function deal */

```

**Fig. 10.16** | Bit fields to store a deck of cards. (Part 2 of 2.)

|          |         |          |          |         |          |
|----------|---------|----------|----------|---------|----------|
| Card: 0  | Suit: 0 | Color: 0 | Card: 0  | Suit: 2 | Color: 1 |
| Card: 1  | Suit: 0 | Color: 0 | Card: 1  | Suit: 2 | Color: 1 |
| Card: 2  | Suit: 0 | Color: 0 | Card: 2  | Suit: 2 | Color: 1 |
| Card: 3  | Suit: 0 | Color: 0 | Card: 3  | Suit: 2 | Color: 1 |
| Card: 4  | Suit: 0 | Color: 0 | Card: 4  | Suit: 2 | Color: 1 |
| Card: 5  | Suit: 0 | Color: 0 | Card: 5  | Suit: 2 | Color: 1 |
| Card: 6  | Suit: 0 | Color: 0 | Card: 6  | Suit: 2 | Color: 1 |
| Card: 7  | Suit: 0 | Color: 0 | Card: 7  | Suit: 2 | Color: 1 |
| Card: 8  | Suit: 0 | Color: 0 | Card: 8  | Suit: 2 | Color: 1 |
| Card: 9  | Suit: 0 | Color: 0 | Card: 9  | Suit: 2 | Color: 1 |
| Card: 10 | Suit: 0 | Color: 0 | Card: 10 | Suit: 2 | Color: 1 |
| Card: 11 | Suit: 0 | Color: 0 | Card: 11 | Suit: 2 | Color: 1 |
| Card: 12 | Suit: 0 | Color: 0 | Card: 12 | Suit: 2 | Color: 1 |
| Card: 0  | Suit: 1 | Color: 0 | Card: 0  | Suit: 3 | Color: 1 |
| Card: 1  | Suit: 1 | Color: 0 | Card: 1  | Suit: 3 | Color: 1 |
| Card: 2  | Suit: 1 | Color: 0 | Card: 2  | Suit: 3 | Color: 1 |
| Card: 3  | Suit: 1 | Color: 0 | Card: 3  | Suit: 3 | Color: 1 |
| Card: 4  | Suit: 1 | Color: 0 | Card: 4  | Suit: 3 | Color: 1 |
| Card: 5  | Suit: 1 | Color: 0 | Card: 5  | Suit: 3 | Color: 1 |
| Card: 6  | Suit: 1 | Color: 0 | Card: 6  | Suit: 3 | Color: 1 |
| Card: 7  | Suit: 1 | Color: 0 | Card: 7  | Suit: 3 | Color: 1 |
| Card: 8  | Suit: 1 | Color: 0 | Card: 8  | Suit: 3 | Color: 1 |
| Card: 9  | Suit: 1 | Color: 0 | Card: 9  | Suit: 3 | Color: 1 |
| Card: 10 | Suit: 1 | Color: 0 | Card: 10 | Suit: 3 | Color: 1 |
| Card: 11 | Suit: 1 | Color: 0 | Card: 11 | Suit: 3 | Color: 1 |
| Card: 12 | Suit: 1 | Color: 0 | Card: 12 | Suit: 3 | Color: 1 |

**Fig. 10.17** | Output of the program in Fig. 10.16.



An **unnamed bit field with a zero width** is used to align the next bit field on a new storage-unit boundary. For example, the structure definition

```
struct example {
 unsigned a : 13;
 unsigned : 0;
 unsigned b : 4;
};
```

uses an unnamed 0-bit field to skip the remaining bits (as many as there are) of the storage unit in which a is stored and to align b on the next storage-unit boundary.



### Portability Tip 10.8

*Bit-field manipulations are machine dependent. For example, some computers allow bit fields to cross word boundaries, whereas others do not.*



### Common Programming Error 10.13

*Attempting to access individual bits of a bit field as if they were elements of an array is a syntax error. Bit fields are not “arrays of bits.”*



### Common Programming Error 10.14

*Attempting to take the address of a bit field (the & operator may not be used with bit fields because they do not have addresses).*



### Performance Tip 10.4

*Although bit fields save space, using them can cause the compiler to generate slower-executing machine-language code. This occurs because it takes extra machine language operations to access only portions of an addressable storage unit. This is one of many examples of the kinds of space–time trade-offs that occur in computer science.*

## 10.11 Enumeration Constants

C provides one final user-defined type called an **enumeration**. An enumeration, introduced by the keyword `enum`, is a set of integer **enumeration constants** represented by identifiers. Values in an `enum` start with 0, unless specified otherwise, and are incremented by 1. For example, the enumeration

```
enum months {
 JAN, FEB, MAR, APR, MAY, JUN, JUL, AUG, SEP, OCT, NOV, DEC };
```

creates a new type, `enum months`, in which the identifiers are set to the integers 0 to 11, respectively. To number the months 1 to 12, use the following enumeration:

```
enum months {
 JAN = 1, FEB, MAR, APR, MAY, JUN, JUL, AUG, SEP, OCT, NOV, DEC
};
```

Since the first value in the preceding enumeration is explicitly set to 1, the remaining values are incremented from 1, resulting in the values 1 through 12. The identifiers in an enumeration must be unique. The value of each enumeration constant of an enumeration can be set explicitly in the definition by assigning a value to the identifier. Multiple members of an enumeration can have the same constant value. In the program of Fig. 10.18,

the enumeration variable `month` is used in a `for` statement to print the months of the year from the array `monthName`. We've made `monthName[ 0 ]` the empty string `""`. Some programmers might prefer to set `monthName[ 0 ]` to a value such as `***ERROR***` to indicate that a logic error occurred.



### Common Programming Error 10.15

*Assigning a value to an enumeration constant after it has been defined is a syntax error.*



### Good Programming Practice 10.5

*Use only uppercase letters enumeration constant names. This makes these constants stand out in a program and reminds you that enumeration constants are not variables.*

```

1 /* Fig. 10.18: fig10_18.c
2 Using an enumeration type */
3 #include <stdio.h>
4
5 /* enumeration constants represent months of the year */
6 enum months {
7 JAN = 1, FEB, MAR, APR, MAY, JUN, JUL, AUG, SEP, OCT, NOV, DEC };
8
9 int main(void)
10 {
11 enum months month; /* can contain any of the 12 months */
12
13 /* initialize array of pointers */
14 const char *monthName[] = { "", "January", "February", "March",
15 "April", "May", "June", "July", "August", "September", "October",
16 "November", "December" };
17
18 /* loop through months */
19 for (month = JAN; month <= DEC; month++) {
20 printf("%2d%11s\n", month, monthName[month]);
21 } /* end for */
22
23 return 0; /* indicates successful termination */
24 } /* end main */

```

```

1 January
2 February
3 March
4 April
5 May
6 June
7 July
8 August
9 September
10 October
11 November
12 December

```

**Fig. 10.18** | Using an enumeration.

## Summary

### Section 10.1 Introduction

- Structures are collections of related variables under one name. They may contain variables of many different data types.
- Structures are commonly used to define records to be stored in files.
- Pointers and structures facilitate the formation of more complex data structures such as linked lists, queues, stacks and trees.

### Section 10.2 Structure Definitions

- Keyword `struct` introduces a structure definition.
- The identifier following keyword `struct` is the structure tag, which names the structure definition. The structure tag is used with the keyword `struct` to declare variables of the structure type.
- Variables declared within the braces of the structure definition are the structure's members.
- Members of the same structure type must have unique names.
- Each structure definition must end with a semicolon.
- Structure members can be variables of the primitive data types or aggregates, such as arrays and other structures.
- A structure cannot contain an instance of itself but may include a pointer to another object of the same type.
- A structure containing a member that is a pointer to the same structure type is referred to as a self-referential structure. Self-referential structures are used to build linked data structures.
- Structure definitions do not reserve any space in memory; they create new data types that are used to define variables.
- Variables of a given structure type can be declared by placing a comma-separated list of variable names between the closing brace of the structure definition and its ending semicolon.
- The structure tag name is optional. If a structure definition does not contain a structure tag name, variables of the structure type may be declared only in the structure definition.
- The only valid operations that may be performed on structures are assigning structure variables to variables of the same type, taking the address (`&`) of a structure variable, accessing the members of a structure variable and using the `sizeof` operator to determine the size of a structure variable.

### Section 10.3 Initializing Structures

- Structures can be initialized using initializer lists.
- If there are fewer initializers in the list than members in the structure, the remaining members are automatically initialized to 0 (or `NULL` if the member is a pointer).
- Members of structure variables defined outside a function definition are initialized to 0 or `NULL` if they are not explicitly initialized in the external definition.
- Structure variables may be initialized in assignment statements by assigning a structure variable of the same type, or by assigning values to the individual members of the structure.

### Section 10.4 Accessing Structure Members

- The structure member operator (`.`) and the structure pointer operator (`->`) are used to access structure members.
- The structure member operator accesses a structure member via the structure variable name.
- The structure pointer operator accesses a structure member via a pointer to the structure.

### Section 10.5 Using Structures with Functions

- Structures may be passed to functions by passing individual structure members, by passing an entire structure or by passing a pointer to a structure.
- Structure variables are passed by value by default.
- To pass a structure by reference, pass its address. Arrays of structures—like all other arrays—are automatically passed by reference.
- To pass an array by value, create a structure with the array as a member. Structures are passed by value, so the array is passed by value.

### Section 10.6 typedef

- The keyword `typedef` provides a mechanism for creating synonyms for previously defined types.
- Names for structure types are often defined with `typedef` to create shorter type names.
- Often, `typedef` is used to create synonyms for the basic data types. For example, a program requiring 4-byte integers may use type `int` on one system and type `long` on another. Programs designed for portability often use `typedef` to create an alias for 4-byte integers such as `Integer`. The alias `Integer` can be changed once in the program to make the program work on both systems.

### Section 10.8 Unions

- A union is declared with keyword `union` in the same format as a structure. Its members share the same storage space.
- The members of a union can be of any data type. The number of bytes used to store a union must be at least enough to hold the largest member.
- Only one member of a union can be referenced at a time. It is your responsibility to ensure that the data in a union is referenced with the proper data type.
- The operations that can be performed on a union are assigning a union to another of the same type, taking the address (`&`) of a union variable, and accessing union members using the structure member operator and the structure pointer operator.
- A union may be initialized in a declaration with a value of the same type as the first union member.

### Section 10.9 Bitwise Operators

- Computers represent all data internally as sequences of bits with the values 0 or 1.
- On most systems, a sequence of 8 bits form a byte—the standard storage unit for a variable of type `char`. Other data types are stored in larger numbers of bytes.
- The bitwise operators are used to manipulate the bits of integral operands (`char`, `short`, `int` and `long`; both signed and unsigned). Unsigned integers are normally used.
- The bitwise operators are bitwise AND (`&`), bitwise inclusive OR (`|`), bitwise exclusive OR (`^`), left shift (`<<`), right shift (`>>`) and complement (`~`).
- The bitwise AND, bitwise inclusive OR and bitwise exclusive OR operators compare their two operands bit by bit. The bitwise AND operator sets each bit in the result to 1 if the corresponding bit in both operands is 1. The bitwise inclusive OR operator sets each bit in the result to 1 if the corresponding bit in either (or both) operand(s) is 1. The bitwise exclusive OR operator sets each bit in the result to 1 if the corresponding bit in exactly one operand is 1.
- The left-shift operator shifts the bits of its left operand to the left by the number of bits specified in its right operand. Bits vacated to the right are replaced with 0s; 1s shifted off the left are lost.
- The right-shift operator shifts the bits in its left operand to the right by the number of bits specified in its right operand. Performing a right shift on an unsigned integer causes the vacated bits at the left to be replaced by 0s; bits shifted off the right are lost.

- The bitwise complement operator sets all 0 bits in its operand to 1 in the result and sets all 1 bits to 0 in the result.
- Often, the bitwise AND operator is used with an operand called a mask—an integer value with specific bits set to 1. Masks are used to hide some bits in a value while selecting other bits.
- The symbolic constant `CHAR_BIT` (defined in `<limits.h>`) represents the number of bits in a byte (normally 8). It can be used to make a bit-manipulation program more scalable and portable.
- Each binary bitwise operator has a corresponding assignment operator.

### Section 10.10 Bit Fields

- C enables you to specify the number of bits in which an `unsigned` or `int` member of a structure or union is stored. This is referred to as a bit field. Bit fields enable better memory utilization by storing data in the minimum number of bits required.
- A bit field is declared by following an `unsigned` or `int` member name with a colon (`:`) and an integer constant representing the width of the field. The constant must be an integer between 0 and the total number of bits used to store an `int` on your system, inclusive.
- Bit-field members of structures are accessed exactly as any other structure member.
- It is possible to specify an unnamed bit field to be used as padding in the structure.
- An unnamed bit field with a zero width aligns the next bit field on a new storage unit boundary.

### Section 10.11 Enumeration Constants

- An `enum` defines a set of integer constants represented by identifiers. Values in an `enum` start with 0, unless specified otherwise, and are incremented by 1.
- The identifiers in an `enum` must be unique.
- The value of an `enum` constant can be set explicitly via assignment in the `enum` definition.
- Multiple members of an enumeration can have the same constant value.

## Terminology

|                                                      |                                                       |
|------------------------------------------------------|-------------------------------------------------------|
| . structure member operator 386                      | member 383                                            |
| ~ bitwise complement operator 400                    | member name (bit field) 403                           |
| aggregate 383                                        | one's complement 400                                  |
| arrow operator ( <code>-&gt;</code> ) 386            | padding 404                                           |
| bit field 403                                        | pointer to the structure 386                          |
| bit field member name 403                            | right-shift operator ( <code>&gt;&gt;</code> ) 394    |
| bitwise AND ( <code>&amp;</code> ) operator 394      | self-referential structure 384                        |
| bitwise assignment operator 402                      | struct 383                                            |
| bitwise complement operator ( <code>~</code> ) 400   | structure 383                                         |
| bitwise exclusive OR ( <code>^</code> ) operator 394 | structure member ( <code>.</code> ) operator 386      |
| bitwise inclusive OR ( <code> </code> ) operator 394 | structure pointer ( <code>-&gt;</code> ) operator 386 |
| <code>CHAR_BIT</code> symbolic constant 397          | structure tag 383                                     |
| complement operator ( <code>~</code> ) 394           | structure type 383                                    |
| derived data type 383                                | typedef 388                                           |
| enumeration 406                                      | union 391                                             |
| enumeration constants 406                            | unnamed bit field 404                                 |
| left-shift operator ( <code>&lt;&lt;</code> ) 394    | unnamed bit field with a zero width 406               |
| mask 396                                             | width of a bit field 403                              |

## Self-Review Exercises

**10.1** Fill in the blanks in each of the following:

- A(n) \_\_\_\_\_ is a collection of related variables under one name.
- A(n) \_\_\_\_\_ is a collection of variables under one name in which the variables share the same storage.
- The bits in the result of an expression using the \_\_\_\_\_ operator are set to 1 if the corresponding bits in each operand are set to 1. Otherwise, the bits are set to zero.
- The variables declared in a structure definition are called its \_\_\_\_\_.
- In an expression using the \_\_\_\_\_ operator, bits are set to 1 if at least one of the corresponding bits in either operand is set to 1. Otherwise, the bits are set to zero.
- Keyword \_\_\_\_\_ introduces a structure declaration.
- Keyword \_\_\_\_\_ is used to create a synonym for a previously defined data type.
- In an expression using the \_\_\_\_\_ operator, bits are set to 1 if exactly one of the corresponding bits in either operand is set to 1. Otherwise, the bits are set to zero.
- The bitwise AND operator (&) is often used to \_\_\_\_\_ bits, that is to select certain bits while zeroing others.
- Keyword \_\_\_\_\_ is used to introduce a union definition.
- The name of the structure is referred to as the structure \_\_\_\_\_.
- A structure member is accessed with either the \_\_\_\_\_ or the \_\_\_\_\_ operator.
- The \_\_\_\_\_ and \_\_\_\_\_ operators are used to shift the bits of a value to the left or to the right, respectively.
- A(n) \_\_\_\_\_ is a set of integers represented by identifiers.

**10.2** State whether each of the following is *true* or *false*. If *false*, explain why.

- Structures may contain variables of only one data type.
- Two unions can be compared (using ==) to determine if they are equal.
- The tag name of a structure is optional.
- Members of different structures must have unique names.
- Keyword typedef is used to define new data types.
- Structures are always passed to functions by reference.
- Structures may not be compared by using operators == and !=.

**10.3** Write code to accomplish each of the following:

- Define a structure called part containing int variable partNumber and char array partName with values that may be as long as 25 characters (including the terminating null character).
- Define Part to be a synonym for the type struct part.
- Use Part to declare variable a to be of type struct part, array b[ 10 ] to be of type struct part and variable ptr to be of type pointer to struct part.
- Read a part number and a part name from the keyboard into the individual members of variable a.
- Assign the member values of variable a to element 3 of array b.
- Assign the address of array b to the pointer variable ptr.
- Print the member values of element 3 of array b using the variable ptr and the structure pointer operator to refer to the members.

**10.4** Find the error in each of the following:

- Assume that struct card has been defined containing two pointers to type char, namely face and suit. Also, the variable c has been defined to be of type struct card and the variable cPtr has been defined to be of type pointer to struct card. Variable cPtr has been assigned the address of c.

```
printf("%s\n", *cPtr->face);
```

- b) Assume that struct card has been defined containing two pointers to type char, namely face and suit. Also, the array hearts[ 13 ] has been defined to be of type struct card. The following statement should print the member face of array element 10.

```
printf("%s\n", hearts.face);
```

- c) **union** values {  
     **char** w;  
     **float** x;  
     **double** y;  
 };

```
union values v = { 1.27 };
```

- d) **struct** person {  
     **char** lastName[ 15 ];  
     **char** firstName[ 15 ];  
     **int** age;  
 }

- e) Assume struct person has been defined as in part (d) but with the appropriate correction.

```
person d;
```

- f) Assume variable p has been declared as type struct person and variable c has been declared as type struct card.

```
p = c;
```

## Answers to Self-Review Exercises

**10.1** a) structure. b) union. c) bitwise AND (&). d) members. e) bitwise inclusive OR (|). f) struct. g) typedef. h) bitwise exclusive OR (^). i) mask. j) union. k) tag name. l) structure member, structure pointer. m) left-shift operator (<<), right-shift operator (>>). n) enumeration.

- 10.2** a) False. A structure can contain variables of many data types.  
 b) False. Unions cannot be compared because there might be bytes of undefined data with different values in union variables that are otherwise identical.  
 c) True.  
 d) False. The members of separate structures can have the same names, but the members of the same structure must have unique names.  
 e) False. Keyword typedef is used to define new names (synonyms) for previously defined data types.  
 f) False. Structures are always passed to functions call-by-value.  
 g) True, because of alignment problems.

- 10.3** a) **struct** part {  
     **int** partNumber;  
     **char** partName[26];  
 };  
 b) **typedef struct** part Part;  
 c) Part a, b[ 10 ], \*ptr;  
 d) scanf( "%d%25s", &a.partNumber, &a.partName );  
 e) b[ 3 ] = a;  
 f) ptr = b;  
 g) printf( "%d %s\n", ( ptr + 3 )->partNumber, ( ptr + 3 )->partName );

- 10.4**
- The parentheses that should enclose `*cPtr` have been omitted, causing the order of evaluation of the expression to be incorrect. The expression should be `( *cPtr )->face`
  - The array subscript has been omitted. The expression should be `hearts[ 10 ].face`.
  - A union can be initialized only with a value that has the same type as the union's first member.
  - A semicolon is required to end a structure definition.
  - Keyword `struct` was omitted from the variable declaration. The declaration should be `struct person d;`
  - Variables of different structure types cannot be assigned to one another.

## Exercises

- 10.5** Provide the definition for each of the following structures and unions:
- Structure `inventory` containing character array `partName[ 30 ]`, integer `partNumber`, floating point `price`, integer `stock` and integer `reorder`.
  - Union `data` containing `char c`, `short s`, `long b`, `float f` and `double d`.
  - A structure called `address` that contains character arrays `streetAddress[ 25 ]`, `city[ 20 ]`, `state[ 3 ]` and `zipCode[ 6 ]`.
  - Structure `student` that contains arrays `firstName[ 15 ]` and `lastName[ 15 ]` and variable `homeAddress` of type `struct address` from part (c).
  - Structure `test` containing 16 bit fields with widths of 1 bit. The names of the bit fields are the letters `a` to `p`.
- 10.6** Given the following structure and variable definitions,

```

struct customer {
 char lastName[15];
 char firstName[15];
 int customerNumber;

 struct {
 char phoneNumber[11];
 char address[50];
 char city[15];
 char state[3];
 char zipCode[6];
 } personal;
} customerRecord, *customerPtr;

customerPtr = &customerRecord;

```

write an expression that can be used to access the structure members in each of the following parts:

- Member `lastName` of structure `customerRecord`.
- Member `lastName` of the structure pointed to by `customerPtr`.
- Member `firstName` of structure `customerRecord`.
- Member `firstName` of the structure pointed to by `customerPtr`.
- Member `customerNumber` of structure `customerRecord`.
- Member `customerNumber` of the structure pointed to by `customerPtr`.
- Member `phoneNumber` of member `personal` of structure `customerRecord`.
- Member `phoneNumber` of member `personal` of the structure pointed to by `customerPtr`.
- Member `address` of member `personal` of structure `customerRecord`.
- Member `address` of member `personal` of the structure pointed to by `customerPtr`.
- Member `city` of member `personal` of structure `customerRecord`.
- Member `city` of member `personal` of the structure pointed to by `customerPtr`.



- m) Member state of member `personal` of structure `customerRecord`.
- n) Member state of member `personal` of the structure pointed to by `customerPtr`.
- o) Member `zipCode` of member `personal` of structure `customerRecord`.
- p) Member `zipCode` of member `personal` of the structure pointed to by `customerPtr`.

**10.7 (Card Shuffling and Dealing Modification)** Modify the program of Fig. 10.16 to shuffle the cards using a high-performance shuffle (as shown in Fig. 10.3). Print the resulting deck in two-column format as in Fig. 10.4. Precede each card with its color.

**10.8 (Using Unions)** Create union `integer` with members `char c`, `short s`, `int i` and `long b`. Write a program that inputs value of type `char`, `short`, `int` and `long` and stores the values in union variables of type `union integer`. Each union variable should be printed as a `char`, a `short`, an `int` and a `long`. Do the values always print correctly?

**10.9 (Using Unions)** Create union `floatingPoint` with members `float f`, `double d` and `long double x`. Write a program that inputs value of type `float`, `double` and `long double` and stores the values in union variables of type `union floatingPoint`. Each union variable should be printed as a `float`, a `double` and a `long double`. Do the values always print correctly?

**10.10 (Right-Shifting Integers)** Write a program that right shifts an integer variable 4 bits. The program should print the integer in bits before and after the shift operation. Does your system place 0s or 1s in the vacated bits?

**10.11 (Right-Shifting Integers)** If your computer uses 2-byte integers, modify the program of Fig. 10.7 so that it works with 2-byte integers.

**10.12 (Left-Shifting Integers)** Left shifting an unsigned integer by 1 bit is equivalent to multiplying the value by 2. Write function `power2` that takes two integer arguments `number` and `pow` and calculates

$$\text{number} * 2^{\text{pow}}$$

Use the shift operator to calculate the result. Print the values as integers and as bits.

**10.13 (Packing Characters into an Integer)** The left-shift operator can be used to pack two character values into an unsigned integer variable. Write a program that inputs two characters from the keyboard and passes them to function `packCharacters`. To pack two characters into an unsigned integer variable, assign the first character to the unsigned variable, shift the unsigned variable left by 8 bit positions and combine the unsigned variable with the second character using the bitwise inclusive OR operator. The program should output the characters in their bit format before and after they are packed into the unsigned integer to prove that the characters are in fact packed correctly in the unsigned variable.

**10.14 (Unpacking Characters from an Integer)** Using the right-shift operator, the bitwise AND operator and a mask, write function `unpackCharacters` that takes the unsigned integer from Exercise 10.13 and unpacks it into two characters. To unpack two characters from an unsigned integer, combine the unsigned integer with the mask 65280 (00000000 00000000 11111111 00000000) and right shift the result 8 bits. Assign the resulting value to a `char` variable. Then combine the unsigned integer with the mask 255 (00000000 00000000 00000000 11111111). Assign the result to another `char` variable. The program should print the unsigned integer in bits before it is unpacked, then print the characters in bits to confirm that they were unpacked correctly.

**10.15 (Packing Characters into an Integer)** If your system uses 4-byte integers, rewrite the program of Exercise 10.13 to pack 4 characters.

**10.16 (Unpacking Characters from an Integer)** If your system uses 4-byte integers, rewrite the function `unpackCharacters` of Exercise 10.14 to unpack 4 characters. Create the masks you need to

unpack the 4 characters by left shifting the value 255 in the mask variable by 8 bits 0, 1, 2 or 3 times (depending on the byte you're unpacking).

**10.17 (Reversing the Order of an Integer's Bits)** Write a program that reverses the order of the bits in an unsigned integer value. The program should input the value from the user and call function `reverseBits` to print the bits in reverse order. Print the value in bits both before and after the bits are reversed to confirm that the bits are reversed properly.

**10.18 (Portable `displayBits` Function)** Modify function `displayBits` of Fig. 10.7 so it is portable between systems using 2-byte integers and systems using 4-byte integers. [Hint: Use the `sizeof` operator to determine the size of an integer on a particular machine.]

**10.19 (What is the Value of X?)** The following program uses function `multiple` to determine if the integer entered from the keyboard is a multiple of some integer X. Examine the function `multiple`, then determine X's value.

```

1 /* ex10_19.c */
2 /* This program determines if a value is a multiple of X. */
3 #include <stdio.h>
4
5 int multiple(int num); /* prototype */
6
7 int main(void)
8 {
9 int y; /* y will hold an integer entered by the user */
10
11 printf("Enter an integer between 1 and 32000: ");
12 scanf("%d", &y);
13
14 /* if y is a multiple of X */
15 if (multiple(y)) {
16 printf("%d is a multiple of X\n", y);
17 } /* end if */
18 else {
19 printf("%d is not a multiple of X\n", y);
20 } /* end else */
21
22 return 0; /* indicates successful termination */
23 } /* end main */
24
25 /* determine if num is a multiple of X */
26 int multiple(int num)
27 {
28 int i; /* counter */
29 int mask = 1; /* initialize mask */
30 int mult = 1; /* initialize mult */
31
32 for (i = 1; i <= 10; i++, mask <= 1) {
33
34 if ((num & mask) != 0) {
35 mult = 0;
36 break;
37 } /* end if */
38 } /* end for */
39
40 return mult;
41 } /* end function multiple */

```

**10.20** What does the following program do?

```

1 /* ex10_20.c */
2 #include <stdio.h>
3
4 int mystery(unsigned bits); /* prototype */
5
6 int main(void)
7 {
8 unsigned x; /* x will hold an integer entered by the user */
9
10 printf("Enter an integer: ");
11 scanf("%u", &x);
12
13 printf("The result is %d\n", mystery(x));
14 return 0; /* indicates successful termination */
15 } /* end main */
16
17 /* What does this function do? */
18 int mystery(unsigned bits)
19 {
20 unsigned i; /* counter */
21 unsigned mask = 1 << 31; /* initialize mask */
22 unsigned total = 0; /* initialize total */
23
24 for (i = 1; i <= 32; i++, bits <= 1) {
25
26 if ((bits & mask) == mask) {
27 total++;
28 } /* end if */
29 } /* end for */
30
31 return !(total % 2) ? 1 : 0;
32 } /* end function mystery */

```

**Making a Difference**

**10.21** (*Computerization of Health Records*) A health care issue that has been in the news lately is the computerization of health records. This possibility is being approached cautiously because of sensitive privacy and security concerns, among others. Computerizing health records could make it easier for patients to share their health profiles and histories among their various health care professionals. This could improve the quality of health care, help avoid drug conflicts and erroneous drug prescriptions, reduce costs and in emergencies could save lives. In this exercise, you'll design a "starter" `HealthProfile` structure for a person. The structure's members should include the person's first name, last name, gender, date of birth (consisting of separate attributes for the month, day and year of birth), height (in inches) and weight (in pounds). Your program should have a function that receives this data and uses it to set the members of a `HealthProfile` variable. The program also should include functions that calculate and return the user's age in years, maximum heart rate and target-heart-rate range (see Exercise 3.48), and body mass index (BMI; see Exercise 2.32). The program should prompt for the person's information, create a `HealthProfile` variable for that person and display the information from that variable—including the person's first name, last name, gender, date of birth, height and weight—then it should calculate and display the person's age in years, BMI, maximum heart rate and target-heart-rate range. It should also display the "BMI values" chart from Exercise 2.32.

# C File Processing

# 11

*I read part of it all the way through.*

—Samuel Goldwyn

*Hats off!  
The flag is passing by.*

—Henry Holcomb Bennett

*Consciousness ... does not appear to itself chopped up in bits. ... A “river” or a “stream” are the metaphors by which it is most naturally described.*

—William James

*I can only assume that a “Do Not File” document is filed in a “Do Not File” file.*

—Senator Frank Church

## Objectives

In this chapter, you’ll learn:

- To create, read, write and update files.
- Sequential access file processing.
- Random-access file processing.

- |                                                        |                                                           |
|--------------------------------------------------------|-----------------------------------------------------------|
| <b>11.1</b> Introduction                               | <b>11.7</b> Creating a Random-Access File                 |
| <b>11.2</b> Data Hierarchy                             | <b>11.8</b> Writing Data Randomly to a Random-Access File |
| <b>11.3</b> Files and Streams                          | <b>11.9</b> Reading Data from a Random-Access File        |
| <b>11.4</b> Creating a Sequential-Access File          | <b>11.10</b> Case Study: Transaction-Processing Program   |
| <b>11.5</b> Reading Data from a Sequential-Access File |                                                           |
| <b>11.6</b> Random-Access Files                        |                                                           |

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference*

## 11.1 Introduction

Storage of data in variables and arrays is temporary—such data is lost when a program terminates. **Files** are used for permanent retention of data. Computers store files on secondary storage devices, especially disk storage devices. In this chapter, we explain how data files are created, updated and processed by C programs. We consider sequential-access files and random-access files.

## 11.2 Data Hierarchy

Ultimately, all data items processed by a computer are reduced to combinations of **zeros and ones**. This occurs because it's simple and economical to build electronic devices that can assume two stable states—one of the states represents 0 and the other represents 1. It's remarkable that the impressive functions performed by computers involve only the most fundamental manipulations of 0s and 1s.

The smallest data item in a computer can assume the value 0 or the value 1. Such a data item is called a **bit** (short for “**binary digit**”—a digit that can assume one of two values). Computer circuitry performs various simple bit manipulations such as determining a bit's value, setting a bit's value and reversing a bit (from 1 to 0 or from 0 to 1).

It's cumbersome to work with data in the low-level form of bits. Instead, programmers prefer to work with data in the form of **decimal digits** (i.e., 0, 1, 2, 3, 4, 5, 6, 7, 8, and 9), **letters** (i.e., A–Z, and a–z), and **special symbols** (i.e., \$, @, %, &, \*, (, ), -, +, ", :, ?, /, and others). Digits, letters, and special symbols are referred to as **characters**. The set of all characters that may be used to write programs and represent data items on a particular computer is called that computer's **character set**. Since computers can process only 1s and 0s, every character in a computer's character set is represented as a pattern of 1s and 0s (called a **byte**). Today, bytes are most commonly composed of eight bits. You create programs and data items as characters; computers then manipulate and process these characters as patterns of bits.


Just as characters are composed of bits, **fields** are composed of characters. A field is a group of characters that conveys meaning. For example, a field consisting solely of uppercase and lowercase letters can be used to represent a person's name.

Data items processed by computers form a **data hierarchy** in which data items become larger and more complex in structure as we progress from bits, to characters (bytes), to fields, and so on.

A **record** (i.e., a **struct** in C) is composed of several fields. In a payroll system, for example, a record for a particular employee might consist of the following fields:

1. Social Security number (alphanumeric field)
2. Name (alphabetic field)
3. Address (alphanumeric field)
4. Hourly salary rate (numeric field)
5. Number of exemptions claimed (numeric field)
6. Year-to-date earnings (numeric field)
7. Amount of federal taxes withheld (numeric field)

Thus, a record is a group of related fields. In the preceding example, each of the fields belongs to the same employee. Of course, a particular company may have many employees and will have a payroll record for each employee. A **file** is a group of related records. A company's payroll file normally contains one record for each employee. Thus, a payroll file for a small company might contain only 22 records, whereas a payroll file for a large company might contain 100,000 records. It's not unusual for an organization to have hundreds or even thousands of files, with some containing billions or even trillions of characters of information. Figure 11.1 illustrates the data hierarchy.



**Fig. 11.1** | Data hierarchy.

To facilitate the retrieval of specific records from a file, at least one field in each record is chosen as a **record key**. A record key identifies a record as belonging to a particular person or entity. For example, in the payroll record described in this section, the Social Security number would normally be chosen as the record key.



There are many ways of organizing records in a file. The most popular type of organization is called a **sequential file**, in which records are typically stored in order by the record key field. In a payroll file, records are usually placed in order by Social Security Number. The first employee record in the file contains the lowest Social Security number, and subsequent records contain increasingly higher Social Security numbers.

Most businesses store data in many different files. For example, companies may have payroll files, accounts receivable files (listing money due from clients), accounts payable files (listing money due to suppliers), inventory files (listing facts about all the items handled by the business) and many other types of files. A group of related files is sometimes called a **database**. A collection of programs designed to create and manage databases is called a **database management system (DBMS)**.

### 11.3 Files and Streams

C views each file simply as a sequential stream of bytes (Fig. 11.2). Each file ends either with an **end-of-file marker** or at a specific byte number recorded in a system-maintained, administrative data structure. When a file is opened, a **stream** is associated with the file. Three files and their associated streams are automatically opened when program execution begins—the **standard input**, the **standard output** and the **standard error**. Streams provide communication channels between files and programs. For example, the standard input stream enables a program to read data from the keyboard, and the standard output stream enables a program to print data on the screen. Opening a file returns a pointer to a `FILE` structure (defined in `<stdio.h>`) that contains information used to process the file. This structure includes a **file descriptor**, i.e., an index into an operating system array called the **open file table**. Each array element contains a **file control block (FCB)** that the operating system uses to administer a particular file. The standard input, standard output and standard error are manipulated using file pointers **`stdin`**, **`stdout`** and **`stderr`**.



**Fig. 11.2** | C's view of a file of  $n$  bytes.

The standard library provides many functions for reading data from files and for writing data to files. Function **`fgetc`**, like **`getchar`**, reads one character from a file. Function `fgetc` receives as an argument a **`FILE`** pointer for the file from which a character will be read. The call `fgetc( stdin )` reads one character from `stdin`—the standard input. This call is equivalent to the call **`getchar()`**. Function **`fputc`**, like **`putchar`**, writes one character to a file. Function `fputc` receives as arguments a character to be written and a pointer for the file to which the character will be written. The function call `fputc( 'a', stdout )` writes the character 'a' to `stdout`—the standard output. This call is equivalent to `putchar( 'a' )`.

Several other functions used to read data from standard input and write data to standard output have similarly named file processing functions. The **`fgets`** and **`fputs`** functions, for example, can be used to read a line from a file and write a line to a file, respectively. In the next several sections, we introduce the file processing equivalents of

functions `scanf` and `printf`—`fscanf` and `fprintf`. Later in the chapter we discuss functions `fread` and `fwrite`.

## 11.4 Creating a Sequential-Access File

C imposes no structure on a file. Thus, notions such as a record of a file do not exist as part of the C language. Therefore, you must provide a file structure to meet the requirements of a particular application. The following example shows how to impose a record structure on a file.

Figure 11.3 creates a simple sequential-access file that might be used in an accounts receivable system to help keep track of the amounts owed by a company's credit clients. For each client, the program obtains an account number, the client's name and the client's balance (i.e., the amount the client owes the company for goods and services received in the past). The data obtained for each client constitutes a "record" for that client. The account number is used as the record key in this application—the file will be created and maintained in account number order. This program assumes the user enters the records in account number order. In a comprehensive accounts receivable system, a sorting capability would be provided so the user could enter the records in any order. The records would then be sorted and written to the file. [Note: Figures 11.7–11.8 use the data file created in Fig. 11.3, so you must run Fig. 11.3 before Figs. 11.7–11.8.]

---

```

1 /* Fig. 11.3: fig11_03.c
2 Create a sequential file */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int account; /* account number */
8 char name[30]; /* account name */
9 double balance; /* account balance */
10
11 FILE *cfPtr; /* cfPtr = clients.dat file pointer */
12
13 /* fopen opens file. Exit program if unable to create file */
14 if ((cfPtr = fopen("clients.dat", "w")) == NULL) {
15 printf("File could not be opened\n");
16 } /* end if */
17 else {
18 printf("Enter the account, name, and balance.\n");
19 printf("Enter EOF to end input.\n");
20 printf("? ");
21 scanf("%d%s%lf", &account, name, &balance);
22
23 /* write account, name and balance into file with fprintf */
24 while (!feof(stdin)) {
25 fprintf(cfPtr, "%d %s %.2f\n", account, name, balance);
26 printf("? ");
27 scanf("%d%s%lf", &account, name, &balance);
28 } /* end while */

```

---

**Fig. 11.3** | Creating a sequential file. (Part I of 2.)



```

29
30 fclose(cfPtr); /* fclose closes file */
31 } /* end else */
32
33 return 0; /* indicates successful termination */
34 } /* end main */

```

```

Enter the account, name, and balance.
Enter EOF to end input.
? 100 Jones 24.98
? 200 Doe 345.67
? 300 White 0.00
? 400 Stone -42.16
? 500 Rich 224.62
? ^Z

```

**Fig. 11.3** | Creating a sequential file. (Part 2 of 2.)

Now let's examine this program. Line 11 states that `cfPtr` is a pointer to a `FILE` structure. A C program administers each file with a separate `FILE` structure. You need not know the specifics of the `FILE` structure to use files, though the interested reader can study the declaration in `stdio.h`. We'll soon see precisely how the `FILE` structure leads indirectly to the operating system's file control block (FCB) for a file.

Each open file must have a separately declared pointer of type `FILE` that is used to refer to the file. Line 14 names the file—"clients.dat"—to be used by the program and establishes a "line of communication" with the file. The file pointer `cfPtr` is assigned a pointer to the `FILE` structure for the file opened with `fopen`. Function `fopen` takes two arguments: a file name and a **file open mode**. The file open mode "w" indicates that the file is to be opened for writing. If a file does not exist and it's opened for writing, `fopen` creates the file. If an existing file is opened for writing, the contents of the file are discarded without warning. In the program, the `if` statement is used to determine whether the file pointer `cfPtr` is `NULL` (i.e., the file is not opened). If it's `NULL`, the program prints an error message and terminates. Otherwise, the program processes the input and writes it to the file.



#### Common Programming Error 11.1

*Opening an existing file for writing ("w") when, in fact, the user wants to preserve the file, discards the contents of the file without warning.*



#### Common Programming Error 11.2

*Forgetting to open a file before attempting to reference it in a program is a logic error.*

The program prompts the user to enter the various fields for each record or to enter end-of-file when data entry is complete. Figure 11.4 lists the key combinations for entering end-of-file for various computer systems.

Line 24 uses function `fEOF` to determine whether the end-of-file indicator is set for the file to which `stdin` refers. The end-of-file indicator informs the program that there is no more data to be processed. In Fig. 11.3, the end-of-file indicator is set for the standard input when the user enters the end-of-file key combination. The argument to function

| Operating system    | Key combination |
|---------------------|-----------------|
| Linux/Mac OS X/UNIX | <Ctrl> d        |
| Windows             | <Ctrl> z        |

**Fig. 11.4** | End-of-file key combinations for various popular operating systems.

`fEOF` is a pointer to the file being tested for the end-of-file indicator (`stdin` in this case). The function returns a nonzero (true) value when the end-of-file indicator has been set; otherwise, the function returns zero. The `while` statement that includes the `fEOF` call in this program continues executing while the end-of-file indicator is not set.

Line 25 writes data to the file `clients.dat`. The data may be retrieved later by a program designed to read the file (see Section 11.5). Function `fprintf` is equivalent to `printf` except that `fprintf` also receives as an argument a file pointer for the file to which the data will be written. Function `fprintf` can output data to the standard output by using `stdout` as the file pointer, as in:

```
fprintf(stdout, "%d %s %.2f\n", account, name, balance);
```



### Common Programming Error 11.3

*Using the wrong file pointer to refer to a file is a logic error.*



### Error-Prevention Tip 11.1

*Be sure that calls to file processing functions in a program contain the correct file pointers.*

After the user enters end-of-file, the program closes the `clients.dat` file with `fclose` and terminates. Function `fclose` also receives the file pointer (rather than the file name) as an argument. If function `fclose` is not called explicitly, the operating system normally will close the file when program execution terminates. This is an example of operating system “housekeeping.”



### Good Programming Practice 11.1

*Explicitly close each file as soon as it's no longer needed.*




### Performance Tip 11.1

*Closing a file can free resources for which other users or programs may be waiting.*

In the sample execution for the program of Fig. 11.3, the user enters information for five accounts, then enters end-of-file to signal that data entry is complete. The sample execution does not show how the data records actually appear in the file. To verify that the file has been created successfully, in the next section we present a program that reads the file and prints its contents.

Figure 11.5 illustrates the relationship between `FILE` pointers, `FILE` structures and FCBs in memory. When the file “`clients.dat`” is opened, an FCB for the file is copied



**Fig. 11.5** | Relationship between FILE pointers, FILE structures and FCBs.

into memory. The figure shows the connection between the file pointer returned by `fopen` and the FCB used by the operating system to administer the file.

Programs may process no files, one file or several files. Each file used in a program must have a unique name and will have a different file pointer returned by `fopen`. All subsequent file processing functions after the file is opened must refer to the file with the

appropriate file pointer. Files may be opened in one of several modes (Fig. 11.6). To create a file, or to discard the contents of a file before writing data, open the file for writing ("w"). To read an existing file, open it for reading ("r"). To add records to the end of an existing file, open the file for appending ("a"). To open a file so that it may be written to and read from, open the file for updating in one of the three update modes—"r+", "w+" or "a+". Mode "r+" opens a file for reading and writing. Mode "w+" creates a file for reading and writing. If the file already exists, the file is opened and the current contents of the file are discarded. Mode "a+" opens a file for reading and writing—all writing is done at the end of the file. If the file does not exist, it's created. Each file open mode has a corresponding binary mode (containing the letter b) for manipulating binary files. The binary modes are used in Sections 11.6–11.10 when we introduce random-access files. If an error occurs while opening a file in any mode, **fopen** returns NULL.

| Mode | Description                                                                                         |
|------|-----------------------------------------------------------------------------------------------------|
| r    | Open an existing file for reading.                                                                  |
| w    | Create a file for writing. If the file already exists, discard the current contents.                |
| a    | Append; open or create a file for writing at the end of the file.                                   |
| r+   | Open an existing file for update (reading and writing).                                             |
| w+   | Create a file for update. If the file already exists, discard the current contents.                 |
| a+   | Append: open or create a file for update; writing is done at the end of the file.                   |
| rb   | Open an existing file for reading in binary mode.                                                   |
| wb   | Create a file for writing in binary mode. If the file already exists, discard the current contents. |
| ab   | Append; open or create a file for writing at the end of the file in binary mode.                    |
| rb+  | Open an existing file for update (reading and writing) in binary mode.                              |
| wb+  | Create a file for update in binary mode. If the file already exists, discard the current contents.  |
| ab+  | Append: open or create a file for update in binary mode; writing is done at the end of the file.    |

**Fig. 11.6** | File opening modes.



#### Common Programming Error 11.4

*Opening a nonexistent file for reading is an error.*



#### Common Programming Error 11.5

*Opening a file for reading or writing without having been granted the appropriate access rights to the file (this is operating-system dependent) is an error.*



#### Common Programming Error 11.6

*Opening a file for writing when no disk space is available is an error.*



### Common Programming Error 11.7

*Opening a file with the incorrect file mode is a logic error. For example, opening a file in write mode ("w") when it should be opened in update mode ("r+") causes the contents of the file to be discarded.*



### Error-Prevention Tip 11.2

*Open a file only for reading (and not update) if the contents of the file should not be modified. This prevents unintentional modification of the file's contents. This is another example of the principle of least privilege.*

## 11.5 Reading Data from a Sequential-Access File

Data is stored in files so that the data can be retrieved for processing when needed. The previous section demonstrated how to create a file for sequential access. This section shows how to read data sequentially from a file.

Figure 11.7 reads records from the file "clients.dat" created by the program of Fig. 11.3 and prints the contents of the records. Line 11 indicates that `cfPtr` is a pointer to a `FILE`. Line 14 attempts to open the file "clients.dat" for reading ("r") and determines whether the file is opened successfully (i.e., `fopen` does not return `NULL`). Line 19 reads a "record" from the file. Function `fscanf` is equivalent to function `scanf`, except `fscanf` receives as an argument a file pointer for the file from which the data is read. After this statement executes the first time, `account` will have the value 100, `name` will have the value "Jones" and `balance` will have the value 24.98. Each time the second `fscanf` statement (line 24) executes, the program reads another record from the file and `account`, `name` and `balance` take on new values. When the program reaches the end of the file, the file is closed (line 27) and the program terminates. Function `fEOF` returns true only *after* the program attempts to read the nonexistent data following the last line.

```

1 /* Fig. 11.7: fig11_07.c
2 Reading and printing a sequential file */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int account; /* account number */
8 char name[30]; /* account name */
9 double balance; /* account balance */
10
11 FILE *cfPtr; /* cfPtr = clients.dat file pointer */
12
13 /* fopen opens file; exits program if file cannot be opened */
14 if ((cfPtr = fopen("clients.dat", "r")) == NULL) {
15 printf("File could not be opened\n");
16 } /* end if */
17 else { /* read account, name and balance from file */
18 printf("%-10s%-13s\n", "Account", "Name", "Balance");
19 fscanf(cfPtr, "%d%s%lf", &account, name, &balance);

```

**Fig. 11.7** | Reading and printing a sequential file. (Part 1 of 2.)

```

20
21 /* while not end of file */
22 while (!feof(cfPtr)) {
23 printf("%-10d%-13s%7.2f\n", account, name, balance);
24 fscanf(cfPtr, "%d%s%lf", &account, name, &balance);
25 } /* end while */
26
27 fclose(cfPtr); /* fclose closes the file */
28 } /* end else */
29
30 return 0; /* indicates successful termination */
31 } /* end main */

```

| Account | Name  | Balance |
|---------|-------|---------|
| 100     | Jones | 24.98   |
| 200     | Doe   | 345.67  |
| 300     | White | 0.00    |
| 400     | Stone | -42.16  |
| 500     | Rich  | 224.62  |

**Fig. 11.7** | Reading and printing a sequential file. (Part 2 of 2.)

### *Resetting the File Position Pointer*

To retrieve data sequentially from a file, a program normally starts reading from the beginning of the file and reads all data consecutively until the desired data is found. It may be desirable to process the data sequentially in a file several times (from the beginning of the file) during the execution of a program. A statement such as

```
rewind(cfPtr);
```

causes a program's **file position pointer**—which indicates the number of the next byte in the file to be read or written—to be repositioned to the beginning of the file (i.e., byte 0) pointed to by `cfPtr`. The file position pointer is not really a pointer. Rather it's an integer value that specifies the byte location in the file at which the next read or write is to occur. This is sometimes referred to as the **file offset**. The file position pointer is a member of the `FILE` structure associated with each file.

### *Credit Inquiry Program*

The program of Fig. 11.8 allows a credit manager to obtain lists of customers with zero balances (i.e., customers who do not owe any money), customers with credit balances (i.e., customers to whom the company owes money) and customers with debit balances (i.e., customers who owe the company money for goods and services received). A credit balance is a negative amount; a debit balance is a positive amount.

The program displays a menu and allows the credit manager to enter one of three options to obtain credit information. Option 1 produces a list of accounts with zero balances. Option 2 produces a list of accounts with credit balances. Option 3 produces a list of accounts with debit balances. Option 4 terminates program execution. A sample output is shown in Fig. 11.9.

---

```

1 /* Fig. 11.8: fig11_08.c
2 Credit inquiry program */
3 #include <stdio.h>
4
5 /* function main begins program execution */
6 int main(void)
7 {
8 int request; /* request number */
9 int account; /* account number */
10 double balance; /* account balance */
11 char name[30]; /* account name */
12 FILE *cfPtr; /* clients.dat file pointer */
13
14 /* fopen opens the file; exits program if file cannot be opened */
15 if ((cfPtr = fopen("clients.dat", "r")) == NULL) {
16 printf("File could not be opened\n");
17 } /* end if */
18 else {
19
20 /* display request options */
21 printf("Enter request\n"
22 " 1 - List accounts with zero balances\n"
23 " 2 - List accounts with credit balances\n"
24 " 3 - List accounts with debit balances\n"
25 " 4 - End of run\n? ");
26 scanf("%d", &request);
27
28 /* process user's request */
29 while (request != 4) {
30
31 /* read account, name and balance from file */
32 fscanf(cfPtr, "%d%s%lf", &account, name, &balance);
33
34 switch (request) {
35 case 1:
36 printf("\nAccounts with zero balances:\n");
37
38 /* read file contents (until eof) */
39 while (!feof(cfPtr)) {
40
41 if (balance == 0) {
42 printf("%-10d%-13s%7.2f\n",
43 account, name, balance);
44 } /* end if */
45
46 /* read account, name and balance from file */
47 fscanf(cfPtr, "%d%s%lf",
48 &account, name, &balance);
49 } /* end while */
50
51 break;
52 case 2:
53 printf("\nAccounts with credit balances:\n");

```

---

**Fig. 11.8** | Credit inquiry program. (Part 1 of 2.)

```

54
55 /* read file contents (until eof) */
56 while (!feof(cfPtr)) {
57
58 if (balance < 0) {
59 printf("%-10d%-13s%7.2f\n",
60 account, name, balance);
61 } /* end if */
62
63 /* read account, name and balance from file */
64 fscanf(cfPtr, "%d%s%f",
65 &account, name, &balance);
66 } /* end while */
67
68 break;
69 case 3:
70 printf("\nAccounts with debit balances:\n");
71
72 /* read file contents (until eof) */
73 while (!feof(cfPtr)) {
74
75 if (balance > 0) {
76 printf("%-10d%-13s%7.2f\n",
77 account, name, balance);
78 } /* end if */
79
80 /* read account, name and balance from file */
81 fscanf(cfPtr, "%d%s%f",
82 &account, name, &balance);
83 } /* end while */
84
85 break;
86 } /* end switch */
87
88 rewind(cfPtr); /* return cfPtr to beginning of file */
89
90 printf("\n? ");
91 scanf("%d", &request);
92 } /* end while */
93
94 printf("End of run.\n");
95 fclose(cfPtr); /* fclose closes the file */
96 } /* end else */
97
98 return 0; /* indicates successful termination */
99 } /* end main */

```

**Fig. 11.8** | Credit inquiry program. (Part 2 of 2.)

Data in this type of sequential file cannot be modified without the risk of destroying other data. For example, if the name “White” needed to be changed to “Worthington,” the old name cannot simply be overwritten. The record for White was written to the file as

```
300 White 0.00
```



```

Enter request
1 - List accounts with zero balances
2 - List accounts with credit balances
3 - List accounts with debit balances
4 - End of run
? 1

Accounts with zero balances:
300 White 0.00

? 2

Accounts with credit balances:
400 Stone -42.16

? 3

Accounts with debit balances:
100 Jones 24.98
200 Doe 345.67
500 Rich 224.62

? 4
End of run.

```

**Fig. 11.9** | Sample output of the credit inquiry program of Fig. 11.8.

If the record is rewritten beginning at the same location in the file using the new name, the record would be

```
300 Worthington 0.00
```

The new record is larger (has more characters) than the original record. The characters beyond the second “o” in “Worthington” would overwrite the beginning of the next sequential record in the file. The problem here is that in the **formatted input/output model** using `fprintf` and `fscanf`, fields—and hence records—can vary in size. For example, the values 7, 14, -117, 2074 and 27383 are all ints stored in the same number of bytes internally, but they are different-sized fields when displayed on the screen or written to a file as text.

Therefore, sequential access with `fprintf` and `fscanf` is not usually used to update records in place. Instead, the entire file is usually rewritten. To make the preceding name change, the records before 300 White 0.00 in such a sequential-access file would be copied to a new file, the new record would be written and the records after 300 White 0.00 would be copied to the new file. This requires processing every record in the file to update one record.


## 11.6 Random-Access Files

As we stated previously, records in a file created with the formatted output function `fprintf` are not necessarily the same length. However, individual records of a **random-access file** are normally fixed in length and may be accessed directly (and thus quickly) without searching through other records. This makes random-access files appropriate for airline reservation systems, banking systems, point-of-sale systems, and other kinds of

**transaction processing systems** that require rapid access to specific data. There are other ways of implementing random-access files, but we'll limit our discussion to this straightforward approach using fixed-length records.

Because every record in a random-access file normally has the same length, the exact location of a record relative to the beginning of the file can be calculated as a function of the record key. We'll soon see how this facilitates immediate access to specific records, even in large files.

Figure 11.10 illustrates one way to implement a random-access file. Such a file is like a freight train with many cars—some empty and some with cargo. Each car in the train is the same length.



**Fig. 11.10** | C's view of a random-access file.

Fixed-length records enable data to be inserted in a random-access file without destroying other data in the file. Data stored previously can also be updated or deleted without rewriting the entire file. In the following sections we explain how to create a random-access file, enter data, read the data both sequentially and randomly, update the data, and delete data no longer needed.

## 11.7 Creating a Random-Access File

Function `fwrite` transfers a specified number of bytes beginning at a specified location in memory to a file. The data is written beginning at the location in the file indicated by the file position pointer. Function `fread` transfers a specified number of bytes from the location in the file specified by the file position pointer to an area in memory beginning with a specified address. Now, when writing an integer, instead of using

```
fprintf(fPtr, "%d", number);
```

which could print a single digit or as many as 11 digits (10 digits plus a sign, each of which requires 1 byte of storage) for a 4-byte integer, we can use

```
fwrite(&number, sizeof(int), 1, fPtr);
```

which always writes 4 bytes (or 2 bytes on a system with 2-byte integers) from a variable `number` to the file represented by `fPtr` (we'll explain the 1 argument shortly). Later, `fread` can be used to read 4 of those bytes into an integer variable `number`. Although `fread` and `fwrite` read and write data, such as integers, in fixed-size rather than variable-size format,

the data they handle are processed in computer “raw data” format (i.e., bytes of data) rather than in `printf`’s and `scanf`’s human-readable text format. Since the “raw” representation of data is system-dependent, “raw data” may not be readable on other systems, or by programs produced by other compilers or with other compiler options.

Functions `fwrite` and `fread` are capable of reading and writing arrays of data to and from disk. The third argument of both `fread` and `fwrite` is the number of elements in the array that should be read from disk or written to disk. The preceding `fwrite` function call writes a single integer to disk, so the third argument is 1 (as if one element of an array is being written).

File processing programs rarely write a single field to a file. Normally, they write one struct at a time, as we show in the following examples.

Consider the following problem statement:

*Create a credit processing system capable of storing up to 100 fixed-length records. Each record should consist of an account number that will be used as the record key, a last name, a first name and a balance. The resulting program should be able to update an account, insert a new account record, delete an account and list all the account records in a formatted text file for printing. Use a random-access file.*

The next several sections introduce the techniques necessary to create the credit processing program. Figure 11.11 shows how to open a random-access file, define a record format using a struct, write data to the disk and close the file. This program initializes all 100 records of the file “credit.dat” with empty structs using the function `fwrite`. Each empty struct contains 0 for the account number, “” (the empty string) for the last name, “” for the first name and 0.0 for the balance. The file is initialized in this manner to create space on the disk in which the file will be stored and to make it possible to determine if a record contains data.

---

```

1 /* Fig. 11.11: fig11_11.c
2 Creating a random-access file sequentially */
3 #include <stdio.h>
4
5 /* clientData structure definition */
6 struct clientData {
7 int acctNum; /* account number */
8 char lastName[15]; /* account last name */
9 char firstName[10]; /* account first name */
10 double balance; /* account balance */
11 }; /* end structure clientData */
12
13 int main(void)
14 {
15 int i; /* counter used to count from 1-100 */
16
17 /* create clientData with default information */
18 struct clientData blankClient = { 0, "", "", 0.0 };
19
20 FILE *cfPtr; /* credit.dat file pointer */
21
```

---

**Fig. 11.11** | Creating a random access file sequentially. (Part 1 of 2.)

---

```

22 /* fopen opens the file; exits if file cannot be opened */
23 if ((cfPtr = fopen("credit.dat", "wb")) == NULL) {
24 printf("File could not be opened.\n");
25 } /* end if */
26 else {
27 /* output 100 blank records to file */
28 for (i = 1; i <= 100; i++) {
29 fwrite(&blankClient, sizeof(struct clientData), 1, cfPtr);
30 } /* end for */
31
32 fclose (cfPtr); /* fclose closes the file */
33 } /* end else */
34
35 return 0; /* indicates successful termination */
36 } /* end main */

```

---

**Fig. 11.11** | Creating a random access file sequentially. (Part 2 of 2.)

Function `fwrite` writes a block (specific number of bytes) of data to a file. In our program, line 29 causes the structure `blankClient` of size `sizeof( struct clientData )` to be written to the file pointed to by `cfPtr`. The operator `sizeof` returns the size in bytes of its operand in parentheses (in this case `struct clientData`). The `sizeof` operator returns an unsigned integer and can be used to determine the size in bytes of any data type or expression. For example, `sizeof(int)` can be used to determine whether an integer is stored in 2 or 4 bytes on a particular computer.

Function `fwrite` can actually be used to write several elements of an array of objects. To write several array elements, supply in the call to `fwrite` a pointer to an array as the first argument and the number of elements to be written as the third argument. In the preceding statement, `fwrite` was used to write a single object that was not an array element. Writing a single object is equivalent to writing one element of an array, hence the 1 in the `fwrite` call. [Note: Figures 11.12, 11.15 and 11.16 use the data file created in Fig. 11.11, so you must run Fig. 11.11 before Figs. 11.12, 11.15 and 11.16]

## 11.8 Writing Data Randomly to a Random-Access File

Figure 11.12 writes data to the file "credit.dat". It uses the combination of `fseek` and `fwrite` to store data at specific locations in the file. Function `fseek` sets the file position pointer to a specific position in the file, then `fwrite` writes the data. A sample execution is shown in Fig. 11.13.

---

```

1 /* Fig. 11.12: fig11_12.c
2 Writing to a random access file */
3 #include <stdio.h>
4
5 /* clientData structure definition */
6 struct clientData {
7 int acctNum; /* account number */
8 char lastName[15]; /* account last name */

```

---

**Fig. 11.12** | Writing data randomly to a random-access file. (Part 1 of 2.)

```

9 char firstName[10]; /* account first name */
10 double balance; /* account balance */
11 }; /* end structure clientData */
12
13 int main(void)
14 {
15 FILE *cFPtr; /* credit.dat file pointer */
16
17 /* create clientData with default information */
18 struct clientData client = { 0, "", "", 0.0 };
19
20 /* fopen opens the file; exits if file cannot be opened */
21 if ((cFPtr = fopen("credit.dat", "rb+")) == NULL) {
22 printf("File could not be opened.\n");
23 } /* end if */
24 else {
25 /* require user to specify account number */
26 printf("Enter account number"
27 " (1 to 100, 0 to end input)\n? ");
28 scanf("%d", &client.acctNum);
29
30 /* user enters information, which is copied into file */
31 while (client.acctNum != 0) {
32 /* user enters last name, first name and balance */
33 printf("Enter lastname, firstname, balance\n? ");
34
35 /* set record lastName, firstName and balance value */
36 fscanf(stdin, "%s%s%lf", client.lastName,
37 client.firstName, &client.balance);
38
39 /* seek position in file to user-specified record */
40 fseek(cFPtr, (client.acctNum - 1) *
41 sizeof(struct clientData), SEEK_SET);
42
43 /* write user-specified information in file */
44 fwrite(&client, sizeof(struct clientData), 1, cFPtr);
45
46 /* enable user to input another account number */
47 printf("Enter account number\n? ");
48 scanf("%d", &client.acctNum);
49 } /* end while */
50
51 fclose(cFPtr); /* fclose closes the file */
52 } /* end else */
53
54 return 0; /* indicates successful termination */
55 } /* end main */

```

**Fig. 11.12** | Writing data randomly to a random-access file. (Part 2 of 2.)

Lines 40–41 position the file position pointer for the file referenced by `cFPtr` to the byte location calculated by `( client.accountNum - 1 ) * sizeof( struct clientData )`. The value of this expression is called the **offset** or the **displacement**. Because the account number is between 1 and 100 but the byte positions in the file start with 0, 1 is subtracted


```

Enter account number (1 to 100, 0 to end input)
? 37
Enter lastname, firstname, balance
? Barker Doug 0.00
Enter account number
? 29
Enter lastname, firstname, balance
? Brown Nancy -24.54
Enter account number
? 96
Enter lastname, firstname, balance
? Stone Sam 34.98
Enter account number
? 88
Enter lastname, firstname, balance
? Smith Dave 258.34
Enter account number
? 33
Enter lastname, firstname, balance
? Dunn Stacey 314.33
Enter account number
? 0

```

**Fig. 11.13** | Sample execution of the program in Fig. 11.12.

from the account number when calculating the byte location of the record. Thus, for record 1, the file position pointer is set to byte 0 of the file. The symbolic constant **SEEK\_SET** indicates that the file position pointer is positioned relative to the beginning of the file by the amount of the offset. As the above statement indicates, a seek for account number 1 in the file sets the file position pointer to the beginning of the file because the byte location calculated is 0. Figure 11.14 illustrates the file pointer referring to a FILE structure in memory. The file position pointer in this diagram indicates that the next byte to be read or written is 5 bytes from the beginning of the file.



**Fig. 11.14** | File position pointer indicating an offset of 5 bytes from the beginning of the file.

The function prototype for `fseek` is

```
int fseek(FILE *stream, long int offset, int whence);
```

where `offset` is the number of bytes to seek from location `whence` in the file pointed to by `stream`. The argument `whence` can have one of three values—`SEEK_SET`, `SEEK_CUR` or `SEEK_END` (all defined in `<stdio.h>`)—indicating the location in the file from which the seek begins. `SEEK_SET` indicates that the seek starts at the beginning of the file; `SEEK_CUR` indicates that the seek starts at the current location in the file; and `SEEK_END` indicates that the seek starts at the end of the file.

For simplicity, the programs in this chapter do not perform error checking. If you wish to determine whether functions like `fscanf` (lines 36–37), `fseek` (lines 40–41) and `fwrite` (line 44) operate correctly, you can check their return values. Function `fscanf` returns the number of data items successfully read or the value `EOF` if a problem occurs while reading data. Function `fseek` returns a nonzero value if the seek operation cannot be performed. Function `fwrite` returns the number of items it successfully output. If this number is less than the third argument in the function call, then a write error occurred.

## 11.9 Reading Data from a Random-Access File

Function `fread` reads a specified number of bytes from a file into memory. For example,

```
fread(&client, sizeof(struct clientData), 1, cFPtr);
```

reads the number of bytes determined by `sizeof( struct clientData )` from the file referenced by `cFPtr` and stores the data in the structure `client`. The bytes are read from the location in the file specified by the file position pointer. Function `fread` can be used to read several fixed-size array elements by providing a pointer to the array in which the elements will be stored and by indicating the number of elements to be read. The preceding statement specifies that one element should be read. To read more than one element, specify the number of elements in the third argument of the `fread` statement. Function `fread` returns the number of items it successfully input. If this number is less than the third argument in the function call, then a read error occurred.

Figure 11.15 reads sequentially every record in the "credit.dat" file, determines whether each record contains data and displays the formatted data for records containing data. Function `fEOF` determines when the end of the file is reached, and the `fread` function transfers data from the disk to the `clientData` structure `client`.

```
1 /* Fig. 11.15: fig11_15.c
2 Reading a random access file sequentially */
3 #include <stdio.h>
4
5 /* clientData structure definition */
6 struct clientData {
7 int acctNum; /* account number */
8 char lastName[15]; /* account last name */
9 char firstName[10]; /* account first name */
10 double balance; /* account balance */
11 }; /* end structure clientData */
```

**Fig. 11.15** | Reading a random-access file sequentially. (Part 1 of 2.)

```

12
13 int main(void)
14 {
15 FILE *cfPtr; /* credit.dat file pointer */
16
17 /* create clientData with default information */
18 struct clientData client = { 0, "", "", 0.0 };
19
20 /* fopen opens the file; exits if file cannot be opened */
21 if ((cfPtr = fopen("credit.dat", "rb")) == NULL) {
22 printf("File could not be opened.\n");
23 } /* end if */
24 else {
25 printf("%-6s%-16s%-11s%10s\n", "Acct", "Last Name",
26 "First Name", "Balance");
27
28 /* read all records from file (until eof) */
29 while (!feof(cfPtr)) {
30 fread(&client, sizeof(struct clientData), 1, cfPtr);
31
32 /* display record */
33 if (client.acctNum != 0) {
34 printf("%-6d%-16s%-11s%10.2f\n",
35 client.acctNum, client.lastName,
36 client.firstName, client.balance);
37 } /* end if */
38 } /* end while */
39
40 fclose(cfPtr); /* fclose closes the file */
41 } /* end else */
42
43 return 0; /* indicates successful termination */
44 } /* end main */

```

| Acct | Last Name | First Name | Balance |
|------|-----------|------------|---------|
| 29   | Brown     | Nancy      | -24.54  |
| 33   | Dunn      | Stacey     | 314.33  |
| 37   | Barker    | Doug       | 0.00    |
| 88   | Smith     | Dave       | 258.34  |
| 96   | Stone     | Sam        | 34.98   |

**Fig. 11.15** | Reading a random-access file sequentially. (Part 2 of 2.)

## 11.10 Case Study: Transaction-Processing Program

We now present a substantial transaction-processing program using random-access files. The program maintains a bank's account information. The program updates existing accounts, adds new accounts, deletes accounts and stores a listing of all the current accounts in a text file for printing. We assume that the program of Fig. 11.11 has been executed to create the file `credit.dat`.

The program has five options. Option 1 calls function `textFile` (lines 65–95) to store a formatted list of all the accounts in a text file called `accounts.txt` that may be printed



later. The function uses `fread` and the sequential file access techniques used in the program of Fig. 11.15. After choosing option 1 the file `accounts.txt` contains:

| Acct | Last Name | First Name | Balance |
|------|-----------|------------|---------|
| 29   | Brown     | Nancy      | -24.54  |
| 33   | Dunn      | Stacey     | 314.33  |
| 37   | Barker    | Doug       | 0.00    |
| 88   | Smith     | Dave       | 258.34  |
| 96   | Stone     | Sam        | 34.98   |

Option 2 calls the function `updateRecord` (lines 98–142) to update an account. The function will only update a record that already exists, so the function first checks to see if the record specified by the user is empty. The record is read into structure `client` with `fread`, then member `acctNum` is compared to 0. If it's 0, the record contains no information, and a message is printed stating that the record is empty. Then, the menu choices are displayed. If the record contains information, function `updateRecord` inputs the transaction amount, calculates the new balance and rewrites the record to the file. A typical output for option 2 is

```
Enter account to update (1 - 100): 37
37 Barker Doug 0.00

Enter charge (+) or payment (-): +87.99
37 Barker Doug 87.99
```

Option 3 calls the function `newRecord` (lines 179–218) to add a new account to the file. If the user enters an account number for an existing account, `newRecord` displays an error message that the record already contains information, and the menu choices are printed again. This function uses the same process to add a new account as does the program in Fig. 11.12. A typical output for option 3 is

```
Enter new account number (1 - 100): 22
Enter lastname, firstname, balance
? Johnston Sarah 247.45
```

Option 4 calls function `deleteRecord` (lines 145–176) to delete a record from the file. Deletion is accomplished by asking the user for the account number and reinitializing the record. If the account contains no information, `deleteRecord` displays an error message that the account does not exist. Option 5 terminates program execution. The program is shown in Fig. 11.16. The file "`credit.dat`" is opened for update (reading and writing) using "`rb+`" mode.

```
1 /* Fig. 11.16: fig11_16.c
2 This program reads a random access file sequentially, updates data
3 already written to the file, creates new data to be placed in the
4 file, and deletes data previously in the file. */
```

```

5 #include <stdio.h>
6
7 /* clientData structure definition */
8 struct clientData {
9 int acctNum; /* account number */
10 char lastName[15]; /* account last name */
11 char firstName[10]; /* account first name */
12 double balance; /* account balance */
13 }; /* end structure clientData */
14
15 /* prototypes */
16 int enterChoice(void);
17 void textFile(FILE *readPtr);
18 void updateRecord(FILE *fPtr);
19 void newRecord(FILE *fPtr);
20 void deleteRecord(FILE *fPtr);
21
22 int main(void)
23 {
24 FILE *cfPtr; /* credit.dat file pointer */
25 int choice; /* user's choice */
26
27 /* fopen opens the file; exits if file cannot be opened */
28 if ((cfPtr = fopen("credit.dat", "rb+")) == NULL) {
29 printf("File could not be opened.\n");
30 } /* end if */
31 else {
32 /* enable user to specify action */
33 while ((choice = enterChoice()) != 5) {
34 switch (choice) {
35 /* create text file from record file */
36 case 1:
37 textFile(cfPtr);
38 break;
39 /* update record */
40 case 2:
41 updateRecord(cfPtr);
42 break;
43 /* create record */
44 case 3:
45 newRecord(cfPtr);
46 break;
47 /* delete existing record */
48 case 4:
49 deleteRecord(cfPtr);
50 break;
51 /* display message if user does not select valid choice */
52 default:
53 printf("Incorrect choice\n");
54 break;
55 } /* end switch */
56 } /* end while */
57 }

```

**Fig. 11.16** | Bank account program. (Part 2 of 6.)

```

58 fclose(cFPtr); /* fclose closes the file */
59 } /* end else */
60
61 return 0; /* indicates successful termination */
62 } /* end main */
63
64 /* create formatted text file for printing */
65 void textFile(FILE *readPtr)
66 {
67 FILE *writePtr; /* accounts.txt file pointer */
68
69 /* create clientData with default information */
70 struct clientData client = { 0, "", "", 0.0 };
71
72 /* fopen opens the file; exits if file cannot be opened */
73 if ((writePtr = fopen("accounts.txt", "w")) == NULL) {
74 printf("File could not be opened.\n");
75 } /* end if */
76 else {
77 rewind(readPtr); /* sets pointer to beginning of file */
78 fprintf(writePtr, "%-6s%-16s%-11s%10s\n",
79 "Acct", "Last Name", "First Name", "Balance");
80
81 /* copy all records from random-access file into text file */
82 while (!feof(readPtr)) {
83 fread(&client, sizeof(struct clientData), 1, readPtr);
84
85 /* write single record to text file */
86 if (client.acctNum != 0) {
87 fprintf(writePtr, "%-6d%-16s%-11s%10.2f\n",
88 client.acctNum, client.lastName,
89 client.firstName, client.balance);
90 } /* end if */
91 } /* end while */
92
93 fclose(writePtr); /* fclose closes the file */
94 } /* end else */
95 } /* end function textFile */
96
97 /* update balance in record */
98 void updateRecord(FILE *fPtr)
99 {
100 int account; /* account number */
101 double transaction; /* transaction amount */
102
103 /* create clientData with no information */
104 struct clientData client = { 0, "", "", 0.0 };
105
106 /* obtain number of account to update */
107 printf("Enter account to update (1 - 100): ");
108 scanf("%d", &account);
109

```

Fig. 11.16 | Bank account program. (Part 3 of 6.)

```

110 /* move file pointer to correct record in file */
111 fseek(fPtr, (account - 1) * sizeof(struct clientData),
112 SEEK_SET);
113
114 /* read record from file */
115 fread(&client, sizeof(struct clientData), 1, fPtr);
116
117 /* display error if account does not exist */
118 if (client.acctNum == 0) {
119 printf("Account #%d has no information.\n", account);
120 } /* end if */
121 else { /* update record */
122 printf("%-6d%-16s%-11s%10.2f\n\n",
123 client.acctNum, client.lastName,
124 client.firstName, client.balance);
125
126 /* request transaction amount from user */
127 printf("Enter charge (+) or payment (-): ");
128 scanf("%lf", &transaction);
129 client.balance += transaction; /* update record balance */
130
131 printf("%-6d%-16s%-11s%10.2f\n",
132 client.acctNum, client.lastName,
133 client.firstName, client.balance);
134
135 /* move file pointer to correct record in file */
136 fseek(fPtr, (account - 1) * sizeof(struct clientData),
137 SEEK_SET);
138
139 /* write updated record over old record in file */
140 fwrite(&client, sizeof(struct clientData), 1, fPtr);
141 } /* end else */
142 } /* end function updateRecord */
143
144 /* delete an existing record */
145 void deleteRecord(FILE *fPtr)
146 {
147 struct clientData client; /* stores record read from file */
148 struct clientData blankClient = { 0, "", "", 0 }; /* blank client */
149
150 int accountNum; /* account number */
151
152 /* obtain number of account to delete */
153 printf("Enter account number to delete (1 - 100): ");
154 scanf("%d", &accountNum);
155
156 /* move file pointer to correct record in file */
157 fseek(fPtr, (accountNum - 1) * sizeof(struct clientData),
158 SEEK_SET);
159
160 /* read record from file */
161 fread(&client, sizeof(struct clientData), 1, fPtr);

```

**Fig. 11.16** | Bank account program. (Part 4 of 6.)

```

162
163 /* display error if record does not exist */
164 if (client.acctNum == 0) {
165 printf("Account %d does not exist.\n", accountNum);
166 } /* end if */
167 else { /* delete record */
168 /* move file pointer to correct record in file */
169 fseek(fPtr, (accountNum - 1) * sizeof(struct clientData),
170 SEEK_SET);
171
172 /* replace existing record with blank record */
173 fwrite(&blankClient,
174 sizeof(struct clientData), 1, fPtr);
175 } /* end else */
176 } /* end function deleteRecord */
177
178 /* create and insert record */
179 void newRecord(FILE *fPtr)
180 {
181 /* create clientData with default information */
182 struct clientData client = { 0, "", "", 0.0 };
183
184 int accountNum; /* account number */
185
186 /* obtain number of account to create */
187 printf("Enter new account number (1 - 100): ");
188 scanf("%d", &accountNum);
189
190 /* move file pointer to correct record in file */
191 fseek(fPtr, (accountNum - 1) * sizeof(struct clientData),
192 SEEK_SET);
193
194 /* read record from file */
195 fread(&client, sizeof(struct clientData), 1, fPtr);
196
197 /* display error if account already exists */
198 if (client.acctNum != 0) {
199 printf("Account #%d already contains information.\n",
200 client.acctNum);
201 } /* end if */
202 else { /* create record */
203 /* user enters last name, first name and balance */
204 printf("Enter lastname, firstname, balance\n? ");
205 scanf("%s%s%lf", &client.lastName, &client.firstName,
206 &client.balance);
207
208 client.acctNum = accountNum;
209
210 /* move file pointer to correct record in file */
211 fseek(fPtr, (client.acctNum - 1) *
212 sizeof(struct clientData), SEEK_SET);
213

```

**Fig. 11.16** | Bank account program. (Part 5 of 6.)

```

214 /* insert record in file */
215 fwrite(&client,
216 sizeof(struct clientData), 1, fPtr);
217 } /* end else */
218 } /* end function newRecord */
219
220 /* enable user to input menu choice */
221 int enterChoice(void)
222 {
223 int menuChoice; /* variable to store user's choice */
224
225 /* display available options */
226 printf("\nEnter your choice\n"
227 "1 - store a formatted text file of accounts called\n"
228 " \"accounts.txt\" for printing\n"
229 "2 - update an account\n"
230 "3 - add a new account\n"
231 "4 - delete an account\n"
232 "5 - end program\n? ");
233
234 scanf("%d", &menuChoice); /* receive choice from user */
235 return menuChoice;
236 } /* end function enterChoice */

```

**Fig. 11.16** | Bank account program. (Part 6 of 6.)

## Summary

### Section 11.1 Introduction

- Files are used for permanent retention of large amounts of data.
- Computers store files on secondary storage devices, especially disk storage devices.

### Section 11.2 Data Hierarchy

- The smallest data item in a computer can assume the value 0 or the value 1. Such a data item is called a bit (short for “binary digit”—a digit that can assume one of two values).
- Computer circuitry performs various simple bit manipulations such as determining a bit’s value, setting a bit’s value and reversing a bit (from 1 to 0 or from 0 to 1).
- Programmers prefer to work with data in the form of decimal digits, letters and special symbols., which are referred to as characters.
- The set of all characters that may be used to write programs and represent data items on a particular computer is called that computer’s character set.
- Every character in a computer’s character set is represented as a pattern of 1s and 0s (called a byte).
- Bytes are most commonly composed of eight bits.
- Fields are composed of characters. A field is a group of characters that conveys meaning.
- A record (i.e., a struct) is a group of related fields.
- A file is a group of related records.
- To facilitate the retrieval of specific records from a file, at least one field in each record is chosen as a record key. A record key identifies a record as belonging to a particular person or entity.

- The most popular type of file organization is called a sequential file, in which records are typically stored in order by the record key field.

### *Section 11.3 Files and Streams*

- C views each file as a sequential stream of bytes. When a file is opened, a stream is associated with the file.
- Three files and their associated streams are automatically opened when program execution begins—the standard input, the standard output and the standard error.
- Streams provide communication channels between files and programs.
- The standard input stream enables a program to read data from the keyboard, and the standard output stream enables a program to print data on the screen.
- Opening a file returns a pointer to a FILE structure (defined in `<stdio.h>`) that contains information used to process the file. This structure includes a file descriptor, i.e., an index into an operating system array called the open file table. Each array element contains a file control block (FCB) that the operating system uses to administer a particular file.
- The standard input, standard output and standard error are manipulated using file pointers `stdin`, `stdout` and `stderr`.
- Function `fgetc` reads one character from a file. It receives as an argument a FILE pointer for the file from which a character will be read.
- Function `fputc` writes one character to a file. It receives as arguments a character to be written and a pointer for the file to which the character will be written.
- The `fgets` and `fputs` functions read a line from a file or write a line to a file, respectively.

### *Section 11.4 Creating a Sequential-Access File*

- C imposes no structure on a file. You must provide a file structure to meet the requirements of a particular application.
- A C program administers each file with a separate FILE structure.
- Each open file must have a separately declared pointer of type FILE that is used to refer to the file.
- Function `fopen` takes as arguments a file name and a file open mode and returns a pointer to the FILE structure for the file opened.
- The file open mode "w" indicates that the file is to be opened for writing. If the file does not exist, `fopen` creates the file. If it exists, the contents are discarded without warning.
- Function `fopen` returns NULL if it's unable to open a file.
- Function `feof` receives a pointer to a FILE and returns a nonzero (true) value when the end-of-file indicator has been set; otherwise, the function returns zero.
- Function `fprintf` is equivalent to `printf` except that `fprintf` also receives as an argument a file pointer for the file to which the data will be written.
- Function `fclose` receives a file pointer as an argument and closes the specified file.
- When a file is opened, the file control block (FCB) for the file is copied into memory. The FCB is used by the operating system to administer the file.
- To create a file, or to discard the file's contents before writing data, open the file for writing ("w").
- To read an existing file, open it for reading ("r").
- To add records to the end of an existing file, open the file for appending ("a").
- To open a file so that it may be written to and read from, open the file for updating in one of the three update modes—"r+", "w+" or "a+". Mode "r+" opens a file for reading and writing. Mode

"w+" creates a file for reading and writing. If the file already exists, it's opened and its contents are discarded. Mode "a+" opens a file for reading and writing—all writing is done at the end of the file. If the file does not exist, it's created.

- Each file open mode has a corresponding binary mode (containing the letter b) for manipulating binary files.

### *Section 11.5 Reading Data from a Sequential-Access File*

- Function `fscanf` is equivalent to function `scanf` except `fscanf` receives as an argument a file pointer for the file from which the data is read.
- To retrieve data sequentially from a file, a program normally starts reading from the beginning of the file and reads all data consecutively until the desired data is found.
- Function `rewind` causes a program's file position pointer to be repositioned to the beginning of the file (i.e., byte 0) pointed to its argument.
- The file position pointer is an integer value that specifies the byte location in the file at which the next read or write is to occur. This is sometimes referred to as the file offset. The file position pointer is a member of the `FILE` structure associated with each file.
- The data in a sequential file typically cannot be modified without the risk of destroying other data in the file.

### *Section 11.6 Random-Access Files*

- Individual records of a random-access file are normally fixed in length and may be accessed directly (and thus quickly) without searching through other records.
- Because every record in a random-access file normally has the same length, the exact location of a record relative to the beginning of the file can be calculated as a function of the record key.
- Fixed-length records enable data to be inserted in a random-access file without destroying other data. Data stored previously can also be updated or deleted without rewriting the entire file.

### *Section 11.7 Creating a Random-Access File*

- Function `fwrite` transfers a specified number of bytes beginning at a specified location in memory to a file. The data is written beginning at the file position pointer's location.
- Function `fread` transfers a specified number of bytes from the location in the file specified by the file position pointer to an area in memory beginning with a specified address.
- Functions `fwrite` and `fread` are capable of reading and writing arrays of data from and to disk. The third argument of both `fread` and `fwrite` is the number of elements to process in the array.
- File processing programs normally write one struct at a time.
- Function `fwrite` writes a block (specific number of bytes) of data to a file.
- To write several array elements, supply in the call to `fwrite` a pointer to an array as the first argument and the number of elements to be written as the third argument.

### *Section 11.8 Writing Data Randomly to a Random-Access File*

- Function `fseek` sets the file position pointer for a given file to a specific position in the file. Its second argument indicates the number of bytes to seek and its third argument indicates the location from which to seek. The third argument can have one of three values—`SEEK_SET`, `SEEK_CUR` or `SEEK_END` (all defined in `<stdio.h>`). `SEEK_SET` indicates that the seek starts at the beginning of the file; `SEEK_CUR` indicates that the seek starts at the current location in the file; and `SEEK_END` indicates that the seek starts at the end of the file.
- If you wish to determine whether functions like `fscanf`, `fseek` and `fwrite` operate correctly, you can check their return values.



- Function `fscanf` returns the number of fields successfully read or the value EOF if a problem occurs while reading data.
- Function `fseek` returns a nonzero value if the seek operation cannot be performed.
- Function `fwrite` returns the number of items it successfully output. If this number is less than the third argument in the function call, then a write error occurred.

### Section 11.9 Reading Data from a Random-Access File

- Function `fread` reads a specified number of bytes from a file into memory.
- Function `fread` can be used to read several fixed-size array elements by providing a pointer to the array in which the elements will be stored and by indicating the number of elements to be read.
- Function `fread` returns the number of items it successfully input. If this number is less than the third argument in the function call, then a read error occurred.

## Terminology

|                                       |                                                      |
|---------------------------------------|------------------------------------------------------|
| binary digit 418                      | <code>fscanf</code> function 421                     |
| bit 418                               | <code>fseek</code> function 433                      |
| byte 418                              | <code>fwrite</code> function 421                     |
| character 418                         | <code>getchar</code> function 420                    |
| character set 418                     | letter 418                                           |
| data hierarchy 418                    | NULL 422                                             |
| database 420                          | offset 434                                           |
| database management system (DBMS) 420 | open file table 420                                  |
| displacement 434                      | <code>printf</code> function 421                     |
| end-of-file marker 420                | <code>putchar</code> function 420                    |
| <code>fclose</code> function 423      | random-access file 430                               |
| <code>feof</code> function 422        | record 419                                           |
| <code>fgetc</code> function 420       | record key 419                                       |
| <code>fgets</code> function 420       | SEEK_CUR 436                                         |
| field 418                             | SEEK_END 436                                         |
| FILE type 420                         | SEEK_SET 435                                         |
| file 419                              | sequential file 420                                  |
| file control block (FCB) 420          | special symbol 418                                   |
| file descriptor 420                   | standard error 420                                   |
| file offset 427                       | standard input file 420                              |
| file open mode 422                    | standard output file 420                             |
| file position pointer 427             | <code>stderr</code> (the standard error device) 420  |
| <code>fopen</code> function 425       | <code>stdin</code> (the standard input device) 420   |
| formatted input/output model 430      | <code>stdout</code> (the standard output device) 420 |
| <code>fprintf</code> function 421     | stream 420                                           |
| <code>fputs</code> function 420       | transaction-processing system 431                    |
| <code>fread</code> function 421       | zeros and ones 418                                   |

## Self-Review Exercises

11.1 Fill in the blanks in each of the following:

- Ultimately, all data items processed by a computer are reduced to combinations of \_\_\_\_\_ and \_\_\_\_\_.
- The smallest data item a computer can process is called a(n) \_\_\_\_\_.
- A(n) \_\_\_\_\_ is a group of related records.
- Digits, letters and special symbols are referred to as \_\_\_\_\_.

- e) A group of related files is called a \_\_\_\_\_.
- f) Function \_\_\_\_\_ closes a file.
- g) The \_\_\_\_\_ function reads data from a file in a manner similar to how `scanf` reads from `stdin`.
- h) Function \_\_\_\_\_ reads a character from a specified file.
- i) Function \_\_\_\_\_ reads a line from a specified file.
- j) Function \_\_\_\_\_ opens a file.
- k) Function \_\_\_\_\_ is normally used when reading data from a file in random-access applications.
- l) Function \_\_\_\_\_ repositions the file position pointer to a specific location in the file.

**11.2** State which of the following are *true* and which are *false*. If *false*, explain why.

- a) Function `fscanf` cannot be used to read data from the standard input.
- b) You must explicitly use `fopen` to open the standard input, standard output and standard error streams.
- c) A program must explicitly call function `fclose` to close a file.
- d) If the file position pointer points to a location in a sequential file other than the beginning of the file, the file must be closed and reopened to read from the beginning of the file.
- e) Function `fprintf` can write to the standard output.
- f) Data in sequential-access files are always updated without overwriting other data.
- g) It's not necessary to search through all the records in a random-access file to find a specific record.
- h) Records in random-access files are not of uniform length.
- i) Function `fseek` may only seek relative to the beginning of a file.

**11.3** Write a single statement to accomplish each of the following. Assume that each of these statements applies to the same program.

- a) Write a statement that opens the file "oldmast.dat" for reading and assigns the returned file pointer to `ofPtr`.
- b) Write a statement that opens the file "trans.dat" for reading and assigns the returned file pointer to `tfPtr`.
- c) Write a statement that opens the file "newmast.dat" for writing (and creation) and assigns the returned file pointer to `nfPtr`.
- d) Write a statement that reads a record from the file "oldmast.dat". The record consists of integer `accountNum`, string `name` and floating-point `currentBalance`.
- e) Write a statement that reads a record from the file "trans.dat". The record consists of the integer `accountNum` and floating-point `dollarAmount`.
- f) Write a statement that writes a record to the file "newmast.dat". The record consists of the integer `accountNum`, string `name` and floating-point `currentBalance`.

**11.4** Find the error in each of the following program segments and explain how to correct it.

- a) The file referred to by `fPtr` ("payables.dat") has not been opened.  

```
printf(fPtr, "%d%s%d\n", account, company, amount);
```
- b) `open( "receive.dat", "r+" );`
- c) The following statement should read a record from the file "payables.dat". File pointer `payPtr` refers to this file, and file pointer `recPtr` refers to the file "receive.dat":  

```
scanf(recPtr, "%d%s%d\n", &account, company, &amount);
```
- d) The file "tools.dat" should be opened to add data to the file without discarding the current data.  

```
if ((fPtr = fopen("tools.dat", "w")) != NULL)
```
- e) The file "courses.dat" should be opened for appending without modifying the current contents of the file.  

```
if ((cPtr = fopen("courses.dat", "w+")) != NULL)
```

## Answers to Self-Review Exercises

**11.1** a) 1s, 0s. b) Bit. c) File. d) Characters. e) Database. f) `fclose`. g) `fscanf`. h) `fgetc`. i) `fgets`. j) `fopen`. k) `fread`. l) `fseek`.

**11.2** a) False. Function `fscanf` can be used to read from the standard input by including the pointer to the standard input stream, `stdin`, in the call to `fscanf`.  
 b) False. These three streams are opened automatically by C when program execution begins.  
 c) False. The files will be closed when program execution terminates, but all files should be explicitly closed with `fclose`.  
 d) False. Function `rewind` can be used to reposition the file position pointer to the beginning of the file.  
 e) True.  
 f) False. In most cases, sequential file records are not of uniform length. Therefore, it's possible that updating a record will cause other data to be overwritten.  
 g) True.  
 h) False. Records in a random-access file are normally of uniform length.  
 i) False. It's possible to seek from the beginning of the file, from the end of the file and from the current location in the file.

**11.3** a) `ofPtr = fopen( "oldmast.dat", "r" );`  
 b) `tfPtr = fopen( "trans.dat", "r" );`  
 c) `nfPtr = fopen( "newmast.dat", "w" );`  
 d) `fscanf( ofPtr, "%d%s%f", &accountNum, name, &currentBalance );`  
 e) `fscanf( tfPtr, "%d%f", &accountNum, &dollarAmount );`  
 f) `fprintf( nfPtr, "%d %s %.2f", accountNum, name, currentBalance );`

**11.4** a) Error: The file "payables.dat" has not been opened before the reference to its file pointer.  
 Correction: Use `fopen` to open "payables.dat" for writing, appending or updating.  
 b) Error: Function `open` is not a Standard C function.  
 Correction: Use function `fopen`.  
 c) Error: Function `fscanf` uses the incorrect file pointer to refer to file "payables.dat".  
 Correction: Use file pointer `payPtr` to refer to "payables.dat".  
 d) Error: The contents of the file are discarded because the file is opened for writing ("w").  
 Correction: To add data to the file, either open the file for updating ("r+") or open the file for appending ("a").  
 e) Error: File "courses.dat" is opened for updating in "w+" mode which discards the current contents of the file.  
 Correction: Open the file "a" mode.

## Exercises

**11.5** Fill in the blanks in each of the following:  
 a) Computers store large amounts of data on secondary storage devices as \_\_\_\_\_.  
 b) A(n) \_\_\_\_\_ is composed of several fields.  
 c) A field that may contain digits, letters and blanks is called a(n) \_\_\_\_\_ field.  
 d) To facilitate the retrieval of specific records from a file, one field in each record is chosen as a(n) \_\_\_\_\_.  
 e) Most information stored in computer systems is stored in \_\_\_\_\_ files.  
 f) A group of related characters that conveys meaning is called a(n) \_\_\_\_\_.

- g) The file pointers for the three files that are opened automatically when program execution begins are named \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- h) Function \_\_\_\_\_ writes a character to a specified file.
- i) Function \_\_\_\_\_ writes a line to a specified file.
- j) Function \_\_\_\_\_ is generally used to write data to a random-access file.
- k) Function \_\_\_\_\_ repositions the file position pointer to the beginning of the file.

**11.6** State which of the following are *true* and which are *false*. If *false*, explain why.

- a) The impressive functions performed by computers essentially involve the manipulation of zeros and ones.
- b) People prefer to manipulate bits instead of characters and fields because bits are more compact.
- c) People specify programs and data items as characters; computers then manipulate and process these characters as groups of zeros and ones.
- d) A person's zip code is an example of a numeric field.
- e) A person's street address is generally considered to be an alphabetic field in computer applications.
- f) Data items processed by a computer form a data hierarchy in which data items become larger and more complex as we progress from fields to characters to bits etc.
- g) A record key identifies a record as belonging to a particular field.
- h) Most companies store their information in a single file to facilitate computer processing.
- i) Files are always referred to by name in C programs.
- j) When a program creates a file, the file is automatically retained by the computer for future reference.

**11.7 (File Matching)** Exercise 11.3 asked the reader to write a series of single statements. Actually, these statements form the core of an important type of file-processing program, namely, a file-matching program. In commercial data processing, it's common to have several files in each system. In an accounts receivable system, for example, there is generally a master file containing detailed information about each customer such as the customer's name, address, telephone number, outstanding balance, credit limit, discount terms, contract arrangements and possibly a condensed history of recent purchases and cash payments.

As transactions occur (i.e., sales are made and cash payments arrive in the mail), they are entered into a file. At the end of each business period (i.e., a month for some companies, a week for others and a day in some cases) the file of transactions (called "trans.dat" in Exercise 11.3) is applied to the master file (called "oldmast.dat" in Exercise 11.3), thus updating each account's record of purchases and payments. After each of these updatings run, the master file is rewritten as a new file ("newmast.dat"), which is then used at the end of the next business period to begin the updating process again.

File-matching programs must deal with certain problems that do not exist in single-file programs. For example, a match does not always occur. A customer on the master file might not have made any purchases or cash payments in the current business period, and therefore no record for this customer will appear on the transaction file. Similarly, a customer who did make some purchases or cash payments might have just moved to this community, and the company may not have had a chance to create a master record for this customer.

Use the statements written in Exercise 11.3 as the basis for a complete file-matching accounts receivable program. Use the account number on each file as the record key for matching purposes. Assume that each file is a sequential file with records stored in increasing account number order.

When a match occurs (i.e., records with the same account number appear on both the master file and the transaction file), add the dollar amount on the transaction file to the current balance on the master file and write the "newmast.dat" record. (Assume that purchases are indicated by positive amounts on the transaction file, and that payments are indicated by negative amounts.)

When there is a master record for a particular account but no corresponding transaction record, merely write the master record to "newmast.dat". When there is a transaction record but no corresponding master record, print the message "Unmatched transaction record for account number ..." (fill in the account number from the transaction record).

**11.8** (*Creating Data for the File Matching Program*) After writing the program of Exercise 11.7, write a simple program to create some test data for checking out the program of Exercise 11.7. Use the following sample account data:

| Master File:   |            |         |
|----------------|------------|---------|
| Account number | Name       | Balance |
| 100            | Alan Jones | 348.17  |
| 300            | Mary Smith | 27.19   |
| 500            | Sam Sharp  | 0.00    |
| 700            | Suzy Green | -14.22  |

| Transaction File: |               |
|-------------------|---------------|
| Account number    | Dollar amount |
| 100               | 27.14         |
| 300               | 62.11         |
| 400               | 100.56        |
| 900               | 82.17         |

**11.9** Run the program of Exercise 11.7 using the files of test data created in Exercise 11.8. Use the listing program of Exercise 11.7 to print the new master file. Check the results carefully.

**11.10** (*File Matching with Multiple Transactions*) It's possible (actually common) to have several transaction records with the same record key. This occurs because a particular customer might make several purchases and cash payments during a business period. Rewrite your accounts receivable file-matching program of Exercise 11.7 to provide for the possibility of handling several transaction records with the same record key. Modify the test data of Exercise 11.8 to include the following additional transaction records:

| Account number | Dollar amount |
|----------------|---------------|
| 300            | 83.89         |
| 700            | 80.78         |
| 700            | 1.53          |

**11.11** Write statements that accomplish each of the following. Assume that the structure

```
struct person {
 char lastName[15];
 char firstName[15];
 char age[4];
};
```

has been defined and that the file is already open for writing.

- Initialize the file "nameage.dat" so that there are 100 records with `lastName = "unsigned"`, `firstName = ""` and `age = "0"`.
- Input 10 last names, first names and ages, and write them to the file.
- Update a record; if there is no information in the record, tell the user "No info".
- Delete a record that has information by reinitializing that particular record.

**11.12 (Hardware Inventory)** You're the owner of a hardware store and need to keep an inventory that can tell you what tools you have, how many you have and the cost of each one. Write a program that initializes the file "hardware.dat" to 100 empty records, lets you input the data concerning each tool, enables you to list all your tools, lets you delete a record for a tool that you no longer have and lets you update *any* information in the file. The tool identification number should be the record number. Use the following information to start your file:

| Record # | Tool name       | Quantity | Cost  |
|----------|-----------------|----------|-------|
| 3        | Electric sander | 7        | 57.98 |
| 17       | Hammer          | 76       | 11.99 |
| 24       | Jig saw         | 21       | 11.00 |
| 39       | Lawn mower      | 3        | 79.50 |
| 56       | Power saw       | 18       | 99.99 |
| 68       | Screwdriver     | 106      | 6.99  |
| 77       | Sledge hammer   | 11       | 21.50 |
| 83       | Wrench          | 34       | 7.50  |

**11.13 (Telephone Number Word Generator)** Standard telephone keypads contain the digits 0 through 9. The numbers 2 through 9 each have three letters associated with them, as is indicated by the following table:

| Digit | Letter | Digit | Letter |
|-------|--------|-------|--------|
| 2     | A B C  | 6     | M N O  |
| 3     | D E F  | 7     | P R S  |
| 4     | G H I  | 8     | T U V  |
| 5     | J K L  | 9     | W X Y  |

Many people find it difficult to memorize phone numbers, so they use the correspondence between digits and letters to develop seven-letter words that correspond to their phone numbers. For example, a person whose telephone number is 686-2377 might use the correspondence indicated in the above table to develop the seven-letter word "NUMBERS."

Businesses frequently attempt to get telephone numbers that are easy for their clients to remember. If a business can advertise a simple word for its customers to dial, then, no doubt, the business will receive a few more calls.

Each seven-letter word corresponds to exactly one seven-digit telephone number. The restaurant wishing to increase its take-home business could surely do so with the number 825-3688 (i.e., "TAKEOUT").

Each seven-digit phone number corresponds to many separate seven-letter words. Unfortunately, most of these represent unrecognizable juxtapositions of letters. It's possible, however, that the owner of a barber shop would be pleased to know that the shop's telephone number, 424-7288, corresponds to "HAIRCUT." The owner of a liquor store would, no doubt, be delighted to find

that the store's telephone number, 233-7226, corresponds to "BEERCAN." A veterinarian with the phone number 738-2273 would be pleased to know that the number corresponds to the letters "PETCARE."

Write a C program that, given a seven-digit number, writes to a file every possible seven-letter word corresponding to that number. There are 2187 ( $3$  to the seventh power) such words. Avoid phone numbers with the digits 0 and 1.

**11.14 (Telephone Number Word Generator Modification)** If you have a computerized dictionary available, modify the program you wrote in Exercise 11.13 to look up the words in the dictionary. Some seven-letter combinations created by this program consist of two or more words (the phone number 843-2677 produces "THEBOSS").

**11.15** Modify the example of Fig. 8.14 to use functions `fgetc` and `fputs` rather than `getchar` and `puts`. The program should give the user the option to read from the standard input and write to the standard output or to read from a specified file and write to a specified file. If the user chooses the second option, have the user enter the file names for the input and output files.

**11.16 (Outputting Type Sizes to a File)** Write a program that uses the `sizeof` operator to determine the sizes in bytes of the various data types on your computer system. Write the results to the file "datasize.dat" so you may print the results later. The format for the results in the file should be as follows:

| Data type          | Size |
|--------------------|------|
| char               | 1    |
| unsigned char      | 1    |
| short int          | 2    |
| unsigned short int | 2    |
| int                | 4    |
| unsigned int       | 4    |
| long int           | 4    |
| unsigned long int  | 4    |
| float              | 4    |
| double             | 8    |
| long double        | 16   |

[Note: The type sizes on your computer might be different from those listed above.]

**11.17 (Simpletron with File Processing)** In Exercise 7.19, you wrote a software simulation of a computer that used a special machine language called Simpletron Machine Language (SML). In the simulation, each time you wanted to run an SML program, you entered the program into the simulator from the keyboard. If you made a mistake while typing the SML program, the simulator was restarted and the SML code was reentered. It would be nice to be able to read the SML program from a file rather than type it each time. This would reduce time and mistakes in preparing to run SML programs.

- Modify the simulator you wrote in Exercise 7.19 to read SML programs from a file specified by the user at the keyboard.
- After the Simpletron executes, it outputs the contents of its registers and memory on the screen. It would be nice to capture the output in a file, so modify the simulator to write its output to a file in addition to displaying the output on the screen.

## Making a Difference

**11.1 (Phishing Scanner)** Phishing is a form of identity theft in which, in an e-mail, a sender posing as a trustworthy source attempts to acquire private information, such as your user names, passwords, credit-card numbers and social security number. Phishing e-mails claiming to be from

popular banks, credit-card companies, auction sites, social networks and online payment services may look quite legitimate. These fraudulent messages often provide links to spoofed (fake) websites where you're asked to enter sensitive information.

Visit McAfee® ([www.mcafee.com/us/threat\\_center/anti\\_phishing/phishing\\_top10.html](http://www.mcafee.com/us/threat_center/anti_phishing/phishing_top10.html)), Security Extra ([www.securityextra.com/](http://www.securityextra.com/)), [www.snopes.com](http://www.snopes.com) and other websites to find lists of the top phishing scams. Also check out the Anti-Phishing Working Group ([www.antiphishing.org/](http://www.antiphishing.org/)), and the FBI's Cyber Investigations website ([www.fbi.gov/cyberinvest/cyberhome.htm](http://www.fbi.gov/cyberinvest/cyberhome.htm)), where you'll find information about the latest scams and how to protect yourself.

Create a list of 30 words, phrases and company names commonly found in phishing messages. Assign a point value to each based on your estimate of its likeliness to be in a phishing message (e.g., one point if it's somewhat likely, two points if moderately likely, or three points if highly likely). Write a program that scans a file of text for these terms and phrases. For each occurrence of a keyword or phrase within the text file, add the assigned point value to the total points for that word or phrase. For each keyword or phrase found, output one line with the word or phrase, the number of occurrences and the point total. Then show the point total for the entire message. Does your program assign a high point total to some actual phishing e-mails you've received? Does it assign a high point total to some legitimate e-mails you've received?



# 12

## C Data Structures

*Much that I bound,  
I could not free;  
Much that I freed  
returned to me.*

—Lee Wilson Dodd

*‘Will you walk a little faster?’  
said a whiting to a snail, ‘There’s  
a porpoise close behind us, and  
he’s treading on my tail.’*

—Lewis Carroll

*There is always room at the top.*

—Daniel Webster

*Push on — keep moving.*

—Thomas Morton

*I think that I shall never see  
A poem lovely as a tree.*

—Joyce Kilmer

### Objectives

In this chapter, you’ll learn:

- To allocate and free memory dynamically for data objects.
- To form linked data structures using pointers, self-referential structures and recursion.
- To create and manipulate linked lists, queues, stacks and binary trees.
- Various important applications of linked data structures.



- |                                         |                    |
|-----------------------------------------|--------------------|
| <b>12.1</b> Introduction                | <b>12.5</b> Stacks |
| <b>12.2</b> Self-Referential Structures | <b>12.6</b> Queues |
| <b>12.3</b> Dynamic Memory Allocation   | <b>12.7</b> Trees  |
| <b>12.4</b> Linked Lists                |                    |

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises  
Special Section: Building Your Own Compiler*

## 12.1 Introduction

We’ve studied fixed-size data structures such as single-subscripted arrays, double-subscripted arrays and `structs`. This chapter introduces **dynamic data structures** with sizes that grow and shrink at execution time. **Linked lists** are collections of data items “lined up in a row”—insertions and deletions are made anywhere in a linked list. **Stacks** are important in compilers and operating systems—insertions and deletions are made only at one end of a stack—its **top**. **Queues** represent waiting lines; insertions are made at the back (also referred to as the **tail**) of a queue and deletions are made from the front (also referred to as the **head**) of a queue. **Binary trees** facilitate high-speed searching and sorting of data, efficient elimination of duplicate data items, representing file system directories and compiling expressions into machine language. Each of these data structures has many other interesting applications.

We’ll discuss each of the major types of data structures and implement programs that create and manipulate these data structures. In the next part of the book—the introduction to C++ and object-oriented programming—we’ll study data abstraction. This technique will enable us to build these data structures in a dramatically different manner designed for producing software that is much easier to maintain and reuse.

This is a challenging chapter. The programs are substantial and they incorporate most of what you have learned in the earlier chapters. The programs are especially heavy on pointer manipulation, a subject many people consider to be among the most difficult topics in C. The chapter is loaded with highly practical programs that you’ll be able to use in more advanced courses; the chapter includes a rich collection of exercises that emphasize practical applications of the data structures.

We sincerely hope that you’ll attempt the major project described in the special section entitled Building Your Own Compiler. You have been using a compiler to translate your C programs to machine language so that you could execute your programs on your computer. In this project, you’ll actually build your own compiler. It will read a file of statements written in a simple, yet powerful, high-level language similar to early versions of the popular language BASIC. Your compiler will translate these statements into a file of Simpletron Machine Language (SML) instructions. SML is the language you learned in the Chapter 7 special section, Building Your Own Computer. Your Simpletron Simulator program will then execute the SML program produced by your compiler! This project will give you a wonderful opportunity to exercise most of what you have learned in this course. The special section carefully walks you through the specifications of the high-level language, and describes the algorithms you’ll need to convert each type of high-level language statement into machine language instructions. If you enjoy being challenged, you might

attempt the many enhancements to both the compiler and the Simpletron Simulator suggested in the exercises.

## 12.2 Self-Referential Structures

A **self-referential structure** contains a pointer member that points to a structure of the same structure type. For example, the definition

```
struct node {
 int data;
 struct node *nextPtr;
};
```

defines a type, `struct node`. A structure of type `struct node` has two members—integer member `data` and pointer member `nextPtr`. Member `nextPtr` points to a structure of type `struct node`—a structure of the same type as the one being declared here, hence the term “self-referential structure.” Member `nextPtr` is referred to as a **link**—i.e., `nextPtr` can be used to “tie” a structure of type `struct node` to another structure of the same type. Self-referential structures can be linked together to form useful data structures such as lists, queues, stacks and trees. Figure 12.1 illustrates two self-referential structure objects linked together to form a list. A slash—representing a **NULL** pointer—is placed in the link member of the second self-referential structure to indicate that the link does not point to another structure. [Note: The slash is only for illustration purposes; it does not correspond to the backslash character in C.] A NULL pointer normally indicates the end of a data structure just as the null character indicates the end of a string.



### Common Programming Error 12.1

*Not setting the link in the last node of a list to NULL can lead to runtime errors.*



**Fig. 12.1** | Self-referential structures linked together.

## 12.3 Dynamic Memory Allocation

Creating and maintaining dynamic data structures requires **dynamic memory allocation**—the ability for a program to obtain more memory space at execution time to hold new nodes, and to release space no longer needed. The limit for dynamic memory allocation can be as large as the amount of available physical memory in the computer or the amount of available virtual memory in a virtual memory system. Often, the limits are much smaller because available memory must be shared among many applications.

Functions `malloc` and `free`, and operator `sizeof`, are essential to dynamic memory allocation. Function `malloc` takes as an argument the number of bytes to be allocated and returns a pointer of type `void *` (**pointer to void**) to the allocated memory. A `void *` pointer may be assigned to a variable of any pointer type. Function `malloc` is normally used with the `sizeof` operator. For example, the statement

```
newPtr = malloc(sizeof(struct node));
```

evaluates `sizeof( struct node )` to determine the size in bytes of a structure of type `struct node`, allocates a new area in memory of that number of bytes and stores a pointer to the allocated memory in variable `newPtr`. The allocated memory is not initialized. If no memory is available, `malloc` returns `NULL`.

Function `free` deallocates memory—i.e., the memory is returned to the system so that the memory can be reallocated in the future. To free memory dynamically allocated by the preceding `malloc` call, use the statement

```
free(newPtr);
```

C also provides functions `calloc` and `realloc` for creating and modifying dynamic arrays. These functions are discussed in Section 14.11. The following sections discuss lists, stacks, queues and trees, each of which is created and maintained with dynamic memory allocation and self-referential structures.



### Portability Tip 12.1

*A structure's size is not necessarily the sum of the sizes of its members. This is so because of various machine-dependent boundary alignment requirements (see Chapter 10).*



### Common Programming Error 12.2

*Assuming that the size of a structure is simply the sum of the sizes of its members is a logic error.*



### Good Programming Practice 12.1

*Use the `sizeof` operator to determine the size of a structure.*



### Error-Prevention Tip 12.1

*When using `malloc`, test for a `NULL` pointer return value, which indicates that the memory was not allocated.*



### Common Programming Error 12.3

*Not returning dynamically allocated memory when it's no longer needed can cause the system to run out of memory prematurely. This is sometimes called a “memory leak.”*



### Good Programming Practice 12.2

*When memory that was dynamically allocated is no longer needed, use `free` to return the memory to the system immediately.*



### Common Programming Error 12.4

*Freeing memory not allocated dynamically with `malloc` is an error.*



### Common Programming Error 12.5

*Referring to memory that has been freed is an error that typically results in the program crashing.*

## 12.4 Linked Lists

A **linked list** is a linear collection of self-referential structures, called **nodes**, connected by pointer **links**—hence, the term “linked” list. A linked list is accessed via a pointer to the first node of the list. Subsequent nodes are accessed via the link pointer member stored in each node. By convention, the link pointer in the last node of a list is set to NULL to mark the end of the list. Data is stored in a linked list dynamically—each node is created as necessary. A node can contain data of any type including other struct objects. Stacks and queues are also linear data structures, and, as we’ll see, are constrained versions of linked lists. Trees are nonlinear data structures.

Lists of data can be stored in arrays, but linked lists provide several advantages. A linked list is appropriate when the number of data elements to be represented in the data structure is unpredictable. Linked lists are dynamic, so the length of a list can increase or decrease as necessary. The size of an array, however cannot be altered once memory is allocated. Arrays can become full. Linked lists become full only when the system has insufficient memory to satisfy dynamic storage allocation requests.



### Performance Tip 12.1

*An array can be declared to contain more elements than the number of data items expected, but this can waste memory. Linked lists can provide better memory utilization in these situations.*

Linked lists can be maintained in sorted order by inserting each new element at the proper point in the list.



### Performance Tip 12.2


*Insertion and deletion in a sorted array can be time consuming—all the elements following the inserted or deleted element must be shifted appropriately.*



### Performance Tip 12.3

*The elements of an array are stored contiguously in memory. This allows immediate access to any array element because the address of any element can be calculated directly based on its position relative to the beginning of the array. Linked lists do not afford such immediate access to their elements.*

Linked list nodes are normally not stored contiguously in memory. Logically, however, the nodes of a linked list appear to be contiguous. Figure 12.2 illustrates a linked list with several nodes.



**Fig. 12.2** | Linked list graphical representation.



### Performance Tip 12.4

*Using dynamic memory allocation (instead of arrays) for data structures that grow and shrink at execution time can save memory. Keep in mind, however, that the pointers take up space, and that dynamic memory allocation incurs the overhead of function calls.*

Figure 12.3 (output shown in Fig. 12.4) manipulates a list of characters. The program enables you to insert a character in the list in alphabetical order (function `insert`) or to delete a character from the list (function `delete`). This is a large and complex program. A detailed discussion of the program follows. Exercise 12.20 asks the reader to implement a recursive function that prints a list backwards. Exercise 12.21 asks the reader to implement a recursive function that searches a linked list for a particular data item.

```

1 /* Fig. 12.3: fig12_03.c
2 Operating and maintaining a list */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 /* self-referential structure */
7 struct listNode {
8 char data; /* each listNode contains a character */
9 struct listNode *nextPtr; /* pointer to next node */
10 }; /* end structure listNode */
11
12 typedef struct listNode ListNode; /* synonym for struct listNode */
13 typedef ListNode *ListNodePtr; /* synonym for ListNode* */
14
15 /* prototypes */
16 void insert(ListNodePtr *sPtr, char value);
17 char delete(ListNodePtr *sPtr, char value);
18 int isEmpty(ListNodePtr sPtr);
19 void printList(ListNodePtr currentPtr);
20 void instructions(void);
21
22 int main(void)
23 {
24 ListNodePtr startPtr = NULL; /* initially there are no nodes */
25 int choice; /* user's choice */
26 char item; /* char entered by user */
27
28 instructions(); /* display the menu */
29 printf("? ");
30 scanf("%d", &choice);
31
32 /* loop while user does not choose 3 */
33 while (choice != 3) {
34
35 switch (choice) {
36 case 1:
37 printf("Enter a character: ");
38 scanf("\n%c", &item);

```

**Fig. 12.3** | Inserting and deleting nodes in a list. (Part I of 4.)



```

39 insert(&startPtr, item); /* insert item in list */
40 printList(startPtr);
41 break;
42 case 2: /* delete an element */
43 /* if list is not empty */
44 if (!isEmpty(startPtr)) {
45 printf("Enter character to be deleted: ");
46 scanf("\n%c", &item);
47
48 /* if character is found, remove it */
49 if (delete(&startPtr, item)) { /* remove item */
50 printf("%c deleted.\n", item);
51 printList(startPtr);
52 } /* end if */
53 else {
54 printf("%c not found.\n\n", item);
55 } /* end else */
56 } /* end if */
57 else {
58 printf("List is empty.\n\n");
59 } /* end else */
60
61 break;
62 default:
63 printf("Invalid choice.\n\n");
64 instructions();
65 break;
66 } /* end switch */
67
68 printf("? ");
69 scanf("%d", &choice);
70 } /* end while */
71
72 printf("End of run.\n");
73 return 0; /* indicates successful termination */
74 } /* end main */
75
76 /* display program instructions to user */
77 void instructions(void)
78 {
79 printf("Enter your choice:\n"
80 " 1 to insert an element into the list.\n"
81 " 2 to delete an element from the list.\n"
82 " 3 to end.\n");
83 } /* end function instructions */
84
85 /* Insert a new value into the list in sorted order */
86 void insert(ListNodePtr *sPtr, char value)
87 {
88 ListNodePtr newPtr; /* pointer to new node */
89 ListNodePtr previousPtr; /* pointer to previous node in list */
90 ListNodePtr currentPtr; /* pointer to current node in list */
91

```

**Fig. 12.3** | Inserting and deleting nodes in a list. (Part 2 of 4.)

```

92 newPtr = malloc(sizeof(ListNode)); /* create node */
93
94 if (newPtr != NULL) { /* is space available */
95 newPtr->data = value; /* place value in node */
96 newPtr->nextPtr = NULL; /* node does not link to another node */
97
98 previousPtr = NULL;
99 currentPtr = *sPtr;
100
101 /* loop to find the correct location in the list */
102 while (currentPtr != NULL && value > currentPtr->data) {
103 previousPtr = currentPtr; /* walk to ... */
104 currentPtr = currentPtr->nextPtr; /* ... next node */
105 } /* end while */
106
107 /* insert new node at beginning of list */
108 if (previousPtr == NULL) {
109 newPtr->nextPtr = *sPtr;
110 *sPtr = newPtr;
111 } /* end if */
112 else { /* insert new node between previousPtr and currentPtr */
113 previousPtr->nextPtr = newPtr;
114 newPtr->nextPtr = currentPtr;
115 } /* end else */
116 } /* end if */
117 else {
118 printf("%c not inserted. No memory available.\n", value);
119 } /* end else */
120 } /* end function insert */
121
122 /* Delete a list element */
123 char delete(ListNodePtr *sPtr, char value)
124 {
125 ListNodePtr previousPtr; /* pointer to previous node in list */
126 ListNodePtr currentPtr; /* pointer to current node in list */
127 ListNodePtr tempPtr; /* temporary node pointer */
128
129 /* delete first node */
130 if (value == (*sPtr)->data) {
131 tempPtr = *sPtr; /* hold onto node being removed */
132 *sPtr = (*sPtr)->nextPtr; /* de-thread the node */
133 free(tempPtr); /* free the de-threaded node */
134 return value;
135 } /* end if */
136 else {
137 previousPtr = *sPtr;
138 currentPtr = (*sPtr)->nextPtr;
139
140 /* loop to find the correct location in the list */
141 while (currentPtr != NULL && currentPtr->data != value) {
142 previousPtr = currentPtr; /* walk to ... */
143 currentPtr = currentPtr->nextPtr; /* ... next node */
144 } /* end while */

```

**Fig. 12.3** | Inserting and deleting nodes in a list. (Part 3 of 4.)



```

145
146 /* delete node at currentPtr */
147 if (currentPtr != NULL) {
148 tempPtr = currentPtr;
149 previousPtr->nextPtr = currentPtr->nextPtr;
150 free(tempPtr);
151 return value;
152 } /* end if */
153 } /* end else */
154
155 return '\0';
156 } /* end function delete */
157
158 /* Return 1 if the list is empty, 0 otherwise */
159 int isEmpty(ListNodePtr sPtr)
160 {
161 return sPtr == NULL;
162 } /* end function isEmpty */
163
164 /* Print the list */
165 void printList(ListNodePtr currentPtr)
166 {
167 /* if list is empty */
168 if (currentPtr == NULL) {
169 printf("List is empty.\n\n");
170 } /* end if */
171 else {
172 printf("The list is:\n");
173
174 /* while not the end of the list */
175 while (currentPtr != NULL) {
176 printf("%c --> ", currentPtr->data);
177 currentPtr = currentPtr->nextPtr;
178 } /* end while */
179
180 printf("NULL\n\n");
181 } /* end else */
182 } /* end function printList */

```

**Fig. 12.3** | Inserting and deleting nodes in a list. (Part 4 of 4.)

```

Enter your choice:
 1 to insert an element into the list.
 2 to delete an element from the list.
 3 to end.
? 1
Enter a character: B
The list is:
B --> NULL

? 1
Enter a character: A

```

**Fig. 12.4** | Sample output for the program of Fig. 12.3. (Part 1 of 2.)

```

The list is:
A --> B --> NULL

? 1
Enter a character: C
The list is:
A --> B --> C --> NULL

? 2
Enter character to be deleted: D
D not found.

? 2
Enter character to be deleted: B
B deleted.
The list is:
A --> C --> NULL

? 2
Enter character to be deleted: C
C deleted.
The list is:
A --> NULL

? 2
Enter character to be deleted: A
A deleted.
List is empty.

? 4
Invalid choice.

Enter your choice:
 1 to insert an element into the list.
 2 to delete an element from the list.
 3 to end.
? 3
End of run.

```

**Fig. 12.4** | Sample output for the program of Fig. 12.3. (Part 2 of 2.)


The primary functions of linked lists are `insert` (lines 86–120) and `delete` (lines 123–156). Function `isEmpty` (lines 159–162) is called a **predicate function**—it does not alter the list in any way; rather it determines if the list is empty (i.e., the pointer to the first node of the list is `NULL`). If the list is empty, 1 is returned; otherwise, 0 is returned. Function `printList` (lines 165–182) prints the list.

### ***Function insert***

Characters are inserted in the list in alphabetical order. Function `insert` (lines 86–120) receives the address of the list and a character to be inserted. The address of the list is necessary when a value is to be inserted at the start of the list. Providing the address of the list enables the list (i.e., the pointer to the first node of the list) to be modified via a call by reference. Since the list itself is a pointer (to its first element), passing the address of the list creates a **pointer to a pointer** (i.e., **double indirection**). This is a complex notion and

requires careful programming. The steps for inserting a character in the list are as follows (see Fig. 12.5):

1. Create a node by calling `malloc`, assigning to `newPtr` the address of the allocated memory (line 92), assigning the character to be inserted to `newPtr->data` (line 95), and assigning `NULL` to `newPtr->nextPtr` (line 96).
2. Initialize `previousPtr` to `NULL` (line 198) and `currentPtr` to `*sPtr` (line 99)—the pointer to the start of the list. Pointers `previousPtr` and `currentPtr` store the locations of the node preceding the insertion point and the node after the insertion point.
3. While `currentPtr` is not `NULL` and the value to be inserted is greater than `currentPtr->data` (line 102), assign `currentPtr` to `previousPtr` (line 103) and advance `currentPtr` to the next node in the list (line 104). This locates the insertion point for the value.
4. If `previousPtr` is `NULL` (line 108), insert the new node as the first node in the list (lines 109–110). Assign `*sPtr` to `newPtr->nextPtr` (the new node link points to the former first node) and assign `newPtr` to `*sPtr` (`*sPtr` points to the new node). Otherwise, if `previousPtr` is not `NULL`, the new node is inserted in place (lines 113–114). Assign `newPtr` to `previousPtr->nextPtr` (the previous node points to the new node) and assign `currentPtr` to `newPtr->nextPtr` (the new node link points to the current node).



**Fig. 12.5** | Inserting a node in order in a list.



### Error-Prevention Tip 12.2

*Assign NULL to the link member of a new node. Pointers should be initialized before they are used.*

Figure 12.5 illustrates the insertion of a node containing the character 'C' into an ordered list. Part a) of the figure shows the list and the new node before the insertion. Part b) of the figure shows the result of inserting the new node. The reassigned pointers are dotted arrows. For simplicity, we implemented function `insert` (and other similar functions in this chapter) with a `void` return type. It's possible that function `malloc` will fail to allocate the requested memory. In this case, it would be better for our `insert` function to return a status that indicates whether the operation was successful.

### Function `delete`


Function `delete` (lines 123–156) receives the address of the pointer to the start of the list and a character to be deleted. The steps for deleting a character from the list are as follows:

1. If the character to be deleted matches the character in the first node of the list (line 130), assign `*sPtr` to `tempPtr` (`tempPtr` will be used to free the unneeded memory), assign `(*sPtr)->nextPtr` to `*sPtr` (`*sPtr` now points to the second node in the list), free the memory pointed to by `tempPtr`, and return the character that was deleted.
2. Otherwise, initialize `previousPtr` with `*sPtr` and initialize `currentPtr` with `(*sPtr)->nextPtr` (lines 137–138).
3. While `currentPtr` is not `NULL` and the value to be deleted is not equal to `currentPtr->data` (Line 141), assign `currentPtr` to `previousPtr` (line 142), and assign `currentPtr->nextPtr` to `currentPtr` (line 143). This locates the character to be deleted if it's contained in the list.
4. If `currentPtr` is not `NULL` (line 147), assign `currentPtr` to `tempPtr` (line 148), assign `currentPtr->nextPtr` to `previousPtr->nextPtr` (line 149), free the node pointed to by `tempPtr` (line 150), and return the character that was deleted from the list (line 151). If `currentPtr` is `NULL`, return the null character (`'\0'`) to signify that the character to be deleted was not found in the list (line 155).

Figure 12.6 illustrates the deletion of a node from a linked list. Part a) of the figure shows the linked list after the preceding insert operation. Part b) shows the reassignment of the link element of `previousPtr` and the assignment of `currentPtr` to `tempPtr`. Pointer `tempPtr` is used to free the memory allocated to store 'C'.

### Function `printList`

Function `printList` (lines 165–182) receives a pointer to the start of the list as an argument and refers to the pointer as `currentPtr`. The function first determines if the list is empty (lines 168–170) and, if so, prints "The list is empty." and terminates. Otherwise, it prints the data in the list (lines 171–181). While `currentPtr` is not `NULL`, the value of `currentPtr->data` is printed by the function, and `currentPtr->nextPtr` is assigned to `currentPtr`. If the link in the last node of the list is not `NULL`, the printing algorithm will try to print past the end of the list, and an error will occur. The printing algorithm is identical for linked lists, stacks and queues.



**Fig. 12.6** | Deleting a node from a list.

## 12.5 Stacks


A **stack** is a constrained version of a linked list. New nodes can be added to a stack and removed from a stack only at the top. For this reason, a stack is referred to as a **last-in, first-out (LIFO)** data structure. A stack is referenced via a pointer to the top element of the stack. The link member in the last node of the stack is set to NULL to indicate the bottom of the stack.

Figure 12.7 illustrates a stack with several nodes. Stacks and linked lists are represented identically. The difference between stacks and linked lists is that insertions and deletions may occur anywhere in a linked list, but only at the top of a stack.



### Common Programming Error 12.6

*Not setting the link in the bottom node of a stack to NULL can lead to runtime errors.*



**Fig. 12.7** | Stack graphical representation.

The primary functions used to manipulate a stack are **push** and **pop**. Function **push** creates a new node and places it on top of the stack. Function **pop** removes a node from the top of the stack, frees the memory that was allocated to the popped node and returns the popped value.

Figure 12.8 (output shown in Fig. 12.9) implements a simple stack of integers. The program provides three options: 1) push a value onto the stack (function push), 2) pop a value off the stack (function pop) and 3) terminate the program.

---

```

1 /* Fig. 12.8: fig12_08.c
2 dynamic stack program */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 /* self-referential structure */
7 struct stackNode {
8 int data; /* define data as an int */
9 struct stackNode *nextPtr; /* stackNode pointer */
10 }; /* end structure stackNode */
11
12 typedef struct stackNode StackNode; /* synonym for struct stackNode */
13 typedef StackNode *StackNodePtr; /* synonym for StackNode* */
14
15 /* prototypes */
16 void push(StackNodePtr *topPtr, int info);
17 int pop(StackNodePtr *topPtr);
18 int isEmpty(StackNodePtr topPtr);
19 void printStack(StackNodePtr currentPtr);
20 void instructions(void);
21
22 /* function main begins program execution */
23 int main(void)
24 {
25 StackNodePtr stackPtr = NULL; /* points to stack top */
26 int choice; /* user's menu choice */
27 int value; /* int input by user */
28
29 instructions(); /* display the menu */
30 printf("? ");
31 scanf("%d", &choice);
32
33 /* while user does not enter 3 */
34 while (choice != 3) {
35
36 switch (choice) {
37 /* push value onto stack */
38 case 1:
39 printf("Enter an integer: ");
40 scanf("%d", &value);
41 push(&stackPtr, value);
42 printStack(stackPtr);
43 break;
44 /* pop value off stack */
45 case 2:
46 /* if stack is not empty */
47 if (!isEmpty(stackPtr)) {

```

---

**Fig. 12.8** | A simple stack program. (Part I of 3.)

---

```

48 printf("The popped value is %d.\n", pop(&stackPtr));
49 } /* end if */
50
51 printStack(stackPtr);
52 break;
53 default:
54 printf("Invalid choice.\n\n");
55 instructions();
56 break;
57 } /* end switch */
58
59 printf("? ");
60 scanf("%d", &choice);
61 } /* end while */
62
63 printf("End of run.\n");
64 return 0; /* indicates successful termination */
65 } /* end main */
66
67 /* display program instructions to user */
68 void instructions(void)
69 {
70 printf("Enter choice:\n"
71 "1 to push a value on the stack\n"
72 "2 to pop a value off the stack\n"
73 "3 to end program\n");
74 } /* end function instructions */
75
76 /* Insert a node at the stack top */
77 void push(StackNodePtr *topPtr, int info)
78 {
79 StackNodePtr newPtr; /* pointer to new node */
80
81 newPtr = malloc(sizeof(StackNode));
82
83 /* insert the node at stack top */
84 if (newPtr != NULL) {
85 newPtr->data = info;
86 newPtr->nextPtr = *topPtr;
87 *topPtr = newPtr;
88 } /* end if */
89 else { /* no space available */
90 printf("%d not inserted. No memory available.\n", info);
91 } /* end else */
92 } /* end function push */
93
94 /* Remove a node from the stack top */
95 int pop(StackNodePtr *topPtr)
96 {
97 StackNodePtr tempPtr; /* temporary node pointer */
98 int popValue; /* node value */
99

```

---

**Fig. 12.8** | A simple stack program. (Part 2 of 3.)

```

100 tempPtr = *topPtr;
101 popValue = (*topPtr)->data;
102 *topPtr = (*topPtr)->nextPtr;
103 free(tempPtr);
104 return popValue;
105 } /* end function pop */
106
107 /* Print the stack */
108 void printStack(StackNodePtr currentPtr)
109 {
110 /* if stack is empty */
111 if (currentPtr == NULL) {
112 printf("The stack is empty.\n\n");
113 } /* end if */
114 else {
115 printf("The stack is:\n");
116
117 /* while not the end of the stack */
118 while (currentPtr != NULL) {
119 printf("%d --> ", currentPtr->data);
120 currentPtr = currentPtr->nextPtr;
121 } /* end while */
122
123 printf("NULL\n\n");
124 } /* end else */
125 } /* end function printList */
126
127 /* Return 1 if the stack is empty, 0 otherwise */
128 int isEmpty(StackNodePtr topPtr)
129 {
130 return topPtr == NULL;
131 } /* end function isEmpty */

```

**Fig. 12.8** | A simple stack program. (Part 3 of 3.)

```

Enter choice:
1 to push a value on the stack
2 to pop a value off the stack
3 to end program
? 1
Enter an integer: 5
The stack is:
5 --> NULL

? 1
Enter an integer: 6
The stack is:
6 --> 5 --> NULL

? 1
Enter an integer: 4
The stack is:
4 --> 6 --> 5 --> NULL

```

**Fig. 12.9** | Sample output from the program of Fig. 12.8. (Part 1 of 2.)



```

? 2
The popped value is 4.
The stack is:
6 --> 5 --> NULL

? 2
The popped value is 6.
The stack is:
5 --> NULL

? 2
The popped value is 5.
The stack is empty.

? 2
The stack is empty.

? 4
Invalid choice.

Enter choice:
1 to push a value on the stack
2 to pop a value off the stack
3 to end program
? 3
End of run.

```

**Fig. 12.9** | Sample output from the program of Fig. 12.8. (Part 2 of 2.)

### **Function *push***

Function `push` (lines 77–92) places a new node at the top of the stack. The function consists of three steps:


1. Create a new node by calling `malloc` and assign the location of the allocated memory to `newPtr` (line 81).
2. Assign to `newPtr->data` the value to be placed on the stack (line 85) and assign `*topPtr` (the stack top pointer) to `newPtr->nextPtr` (line 86)—the link member of `newPtr` now points to the previous top node.
3. Assign `newPtr` to `*topPtr` (line 87)—`*topPtr` now points to the new stack top.

Manipulations involving `*topPtr` change the value of `stackPtr` in `main`. Figure 12.10 illustrates function `push`. Part a) of the figure shows the stack and the new node before the push operation. The dotted arrows in part b) illustrate Steps 2 and 3 of the push operation that enable the node containing 12 to become the new stack top.

### **Function *pop***

Function `pop` (lines 95–105) removes a node from the top of the stack. Function `main` determines if the stack is empty before calling `pop`. The `pop` operation consists of five steps:


1. Assign `*topPtr` to `tempPtr` (line 100); `tempPtr` will be used to free the unneeded memory.
2. Assign `(*topPtr)->data` to `popValue` (line 101) to save the value in the top node.



**Fig. 12.10** | push operation.

3. Assign `(*topPtr)->nextPtr` to `*topPtr` (line 102) so `*topPtr` contains address of the new top node.
4. Free the memory pointed to by `tempPtr` (line 103).
5. Return `popValue` to the caller (line 104).

Figure 12.11 illustrates function `pop`. Part (a) shows the stack after the previous push operation. Part (b) shows `tempPtr` pointing to the first node of the stack and `topPtr` pointing to the second node of the stack. Function `free` is used to free the memory pointed to by `tempPtr`.



**Fig. 12.11** | pop operation.

### Applications of Stacks

Stacks have many interesting applications. For example, whenever a function call is made, the called function must know how to return to its caller, so the return address is pushed

onto a stack. If a series of function calls occurs, the successive return values are pushed onto the stack in last-in, first-out order so that each function can return to its caller. Stacks support recursive function calls in the same manner as conventional nonrecursive calls.

Stacks contain the space created for automatic variables on each invocation of a function. When the function returns to its caller, the space for that function's automatic variables is popped off the stack, and these variables no longer are known to the program. Stacks are used by compilers in the process of evaluating expressions and generating machine language code. The exercises explore several applications of stacks.

## 12.6 Queues

Another common data structure is the **queue**. A queue is similar to a checkout line in a grocery store—the first person in line is serviced first, and other customers enter the line only at the end and wait to be serviced. Queue nodes are removed only from the **head of the queue** and are inserted only at the **tail of the queue**. For this reason, a queue is referred to as a **first-in, first-out (FIFO)** data structure. The insert and remove operations are known as enqueue and dequeue.

Queues have many applications in computer systems. Many computers have only a single processor, so only one user at a time may be serviced. Entries for the other users are placed in a queue. Each entry gradually advances to the front of the queue as users receive service. The entry at the front of the queue is the next to receive service.


Queues are also used to support print spooling. A multiuser environment may have only a single printer. Many users may be generating outputs to be printed. If the printer is busy, other outputs may still be generated. These are spooled to disk where they wait in a queue until the printer becomes available.

Information packets also wait in queues in computer networks. Each time a packet arrives at a network node, it must be routed to the next node on the network along the path to the packet's final destination. The routing node routes one packet at a time, so additional packets are enqueued until the router can route them. Figure 12.12 illustrates a queue with several nodes. Note the pointers to the head of the queue and the tail of the queue.



### Common Programming Error 12.7

*Not setting the link in the last node of a queue to NULL can lead to runtime errors.*



**Fig. 12.12** | Queue graphical representation.

Figure 12.13 (output in Fig. 12.14) performs queue manipulations. The program provides several options: insert a node in the queue (function `enqueue`), remove a node from the queue (function `dequeue`) and terminate the program.

---

```

1 /* Fig. 12.13: fig12_13.c
2 Operating and maintaining a queue */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 /* self-referential structure */
7 struct queueNode {
8 char data; /* define data as a char */
9 struct queueNode *nextPtr; /* queueNode pointer */
10 }; /* end structure queueNode */
11
12 typedef struct queueNode QueueNode;
13 typedef QueueNode *QueueNodePtr;
14
15 /* function prototypes */
16 void printQueue(QueueNodePtr currentPtr);
17 int isEmpty(QueueNodePtr headPtr);
18 char dequeue(QueueNodePtr *headPtr, QueueNodePtr *tailPtr);
19 void enqueue(QueueNodePtr *headPtr, QueueNodePtr *tailPtr,
20 char value);
21 void instructions(void);
22
23 /* function main begins program execution */
24 int main(void)
25 {
26 QueueNodePtr headPtr = NULL; /* initialize headPtr */
27 QueueNodePtr tailPtr = NULL; /* initialize tailPtr */
28 int choice; /* user's menu choice */
29 char item; /* char input by user */
30
31 instructions(); /* display the menu */
32 printf("? ");
33 scanf("%d", &choice);
34
35 /* while user does not enter 3 */
36 while (choice != 3) {
37
38 switch(choice) {
39 /* enqueue value */
40 case 1:
41 printf("Enter a character: ");
42 scanf("\n%c", &item);
43 enqueue(&headPtr, &tailPtr, item);
44 printQueue(headPtr);
45 break;
46 /* dequeue value */

```

---

**Fig. 12.13** | Processing a queue. (Part I of 3.)

```

47 case 2:
48 /* if queue is not empty */
49 if (!isEmpty(headPtr)) {
50 item = dequeue(&headPtr, &tailPtr);
51 printf("%c has been dequeued.\n", item);
52 } /* end if */
53
54 printQueue(headPtr);
55 break;
56 default:
57 printf("Invalid choice.\n\n");
58 instructions();
59 break;
60 } /* end switch */
61
62 printf("? ");
63 scanf("%d", &choice);
64 } /* end while */
65
66 printf("End of run.\n");
67 return 0; /* indicates successful termination */
68 } /* end main */
69
70 /* display program instructions to user */
71 void instructions(void)
72 {
73 printf ("Enter your choice:\n"
74 " 1 to add an item to the queue\n"
75 " 2 to remove an item from the queue\n"
76 " 3 to end\n");
77 } /* end function instructions */
78
79 /* insert a node a queue tail */
80 void enqueue(QueueNodePtr *headPtr, QueueNodePtr *tailPtr,
81 char value)
82 {
83 QueueNodePtr newPtr; /* pointer to new node */
84
85 newPtr = malloc(sizeof(QueueNode));
86
87 if (newPtr != NULL) { /* is space available */
88 newPtr->data = value;
89 newPtr->nextPtr = NULL;
90
91 /* if empty, insert node at head */
92 if (isEmpty(*headPtr)) {
93 *headPtr = newPtr;
94 } /* end if */
95 else {
96 (*tailPtr)->nextPtr = newPtr;
97 } /* end else */
98 }

```

**Fig. 12.13** | Processing a queue. (Part 2 of 3.)

```

99 *tailPtr = newPtr;
100 } /* end if */
101 else {
102 printf("%c not inserted. No memory available.\n", value);
103 } /* end else */
104 } /* end function enqueue */
105
106 /* remove node from queue head */
107 char dequeue(QueueNodePtr *headPtr, QueueNodePtr *tailPtr)
108 {
109 char value; /* node value */
110 QueueNodePtr tempPtr; /* temporary node pointer */
111
112 value = (*headPtr)->data;
113 tempPtr = *headPtr;
114 *headPtr = (*headPtr)->nextPtr;
115
116 /* if queue is empty */
117 if (*headPtr == NULL) {
118 *tailPtr = NULL;
119 } /* end if */
120
121 free(tempPtr);
122 return value;
123 } /* end function dequeue */
124
125 /* Return 1 if the list is empty, 0 otherwise */
126 int isEmpty(QueueNodePtr headPtr)
127 {
128 return headPtr == NULL;
129 } /* end function isEmpty */
130
131 /* Print the queue */
132 void printQueue(QueueNodePtr currentPtr)
133 {
134 /* if queue is empty */
135 if (currentPtr == NULL) {
136 printf("Queue is empty.\n\n");
137 } /* end if */
138 else {
139 printf("The queue is:\n");
140
141 /* while not end of queue */
142 while (currentPtr != NULL) {
143 printf("%c --> ", currentPtr->data);
144 currentPtr = currentPtr->nextPtr;
145 } /* end while */
146
147 printf("NULL\n\n");
148 } /* end else */
149 } /* end function printQueue */

```

**Fig. 12.13** | Processing a queue. (Part 3 of 3.)

```

Enter your choice:
 1 to add an item to the queue
 2 to remove an item from the queue
 3 to end
? 1
Enter a character: A
The queue is:
A --> NULL

? 1
Enter a character: B
The queue is:
A --> B --> NULL

? 1
Enter a character: C
The queue is:
A --> B --> C --> NULL

? 2
A has been dequeued.
The queue is:
B --> C --> NULL

? 2
B has been dequeued.
The queue is:
C --> NULL

? 2
C has been dequeued.
Queue is empty.

? 2
Queue is empty.

? 4
Invalid choice.

Enter your choice:
 1 to add an item to the queue
 2 to remove an item from the queue
 3 to end
? 3
End of run.

```

**Fig. 12.14** | Sample output from the program in Fig. 12.13.


### *Function enqueue*

Function `enqueue` (lines 80–104) receives three arguments from `main`: the address of the pointer to the head of the queue, the address of the pointer to the tail of the queue and the value to be inserted in the queue. The function consists of three steps:

1. To create a new node: Call `malloc`, assign the allocated memory location to `newPtr` (line 85), assign the value to be inserted in the queue to `newPtr->data` (line 88) and assign `NULL` to `newPtr->nextPtr` (line 89).

2. If the queue is empty (line 92), assign newPtr to \*headPtr (line 93); otherwise, assign pointer newPtr to (\*tailPtr)->nextPtr (line 96).
3. Assign newPtr to \*tailPtr (line 99).

Figure 12.15 illustrates an enqueue operation. Part a) shows the queue and the new node before the operation. The dotted arrows in part b) illustrate Steps 2 and 3 of function enqueue that enable a new node to be added to the end of a queue that is not empty.



**Fig. 12.15** | enqueue operation.

### Function dequeue

Function dequeue (lines 107–123) receives the address of the pointer to the head of the queue and the address of the pointer to the tail of the queue as arguments and removes the first node from the queue. The dequeue operation consists of six steps:

1. Assign (\*headPtr)->data to value to save the data (line 112).
2. Assign \*headPtr to tempPtr (line 113), which will be used to free the unneeded memory.
3. Assign (\*headPtr)->nextPtr to \*headPtr (line 114) so that \*headPtr now points to the new first node in the queue.
4. If \*headPtr is NULL (line 117), assign NULL to \*tailPtr (line 118).
5. Free the memory pointed to by tempPtr (line 121).
6. Return value to the caller (line 122).

Figure 12.16 illustrates function dequeue. Part a) shows the queue after the preceding enqueue operation. Part b) shows tempPtr pointing to the dequeued node, and headPtr pointing to the new first node of the queue. Function free is used to reclaim the memory pointed to by tempPtr.






Fig. 12.16 | dequeue operation.

## 12.7 Trees

Linked lists, stacks and queues are **linear data structures**. A **tree** is a nonlinear, two-dimensional data structure with special properties. Tree nodes contain two or more links. This section discusses **binary trees** (Fig. 12.17)—trees whose nodes all contain two links (none, one, or both of which may be NULL). The **root node** is the first node in a tree. Each link in the root node refers to a **child**. The **left child** is the first node in the **left subtree**, and the **right child** is the first node in the **right subtree**. The children of a node are called **siblings**. A node with no children is called a **leaf node**. Computer scientists normally draw trees from the root node down—exactly the opposite of trees in nature.





Fig. 12.17 | Binary tree graphical representation.

In this section, a special binary tree called a **binary search tree** is created. A binary search tree (with no duplicate node values) has the characteristic that the values in any left subtree are less than the value in its parent node, and the values in any right subtree are greater than the value in its **parent node**. Figure 12.18 illustrates a binary search tree with 12 values. The shape of the binary search tree that corresponds to a set of data can vary, depending on the order in which the values are inserted into the tree.



### Common Programming Error 12.8

*Not setting to NULL the links in leaf nodes of a tree can lead to runtime errors.*



**Fig. 12.18** | Binary search tree.

Figure 12.19 (output shown in Fig. 12.20) creates a binary search tree and traverses it three ways—**inorder**, **preorder** and **postorder**. The program generates 10 random numbers and inserts each in the tree, except that duplicate values are discarded.

```

1 /* Fig. 12.19: fig12_19.c
2 Create a binary tree and traverse it
3 preorder, inorder, and postorder */
4 #include <stdio.h>
5 #include <stdlib.h>
6 #include <time.h>
7
8 /* self-referential structure */
9 struct treeNode {
10 struct treeNode *leftPtr; /* pointer to left subtree */
11 int data; /* node value */
12 struct treeNode *rightPtr; /* pointer to right subtree */
13 }; /* end structure treeNode */
14
15 typedef struct treeNode TreeNode; /* synonym for struct treeNode */
16 typedef TreeNode *TreeNodePtr; /* synonym for TreeNode* */
17
18 /* prototypes */
19 void insertNode(TreeNodePtr *treePtr, int value);
20 void inOrder(TreeNodePtr treePtr);
21 void preOrder(TreeNodePtr treePtr);
22 void postOrder(TreeNodePtr treePtr);
23

```

**Fig. 12.19** | Creating and traversing a binary tree. (Part I of 3.)

---

```

24 /* function main begins program execution */
25 int main(void)
26 {
27 int i; /* counter to loop from 1-10 */
28 int item; /* variable to hold random values */
29 TreeNodePtr rootPtr = NULL; /* tree initially empty */
30
31 srand(time(NULL));
32 printf("The numbers being placed in the tree are:\n");
33
34 /* insert random values between 0 and 14 in the tree */
35 for (i = 1; i <= 10; i++) {
36 item = rand() % 15;
37 printf("%3d", item);
38 insertNode(&rootPtr, item);
39 } /* end for */
40
41 /* traverse the tree preOrder */
42 printf("\n\nThe preOrder traversal is:\n");
43 preOrder(rootPtr);
44
45 /* traverse the tree inOrder */
46 printf("\n\nThe inOrder traversal is:\n");
47 inOrder(rootPtr);
48
49 /* traverse the tree postOrder */
50 printf("\n\nThe postOrder traversal is:\n");
51 postOrder(rootPtr);
52 return 0; /* indicates successful termination */
53 } /* end main */
54
55 /* insert node into tree */
56 void insertNode(TreeNodePtr *treePtr, int value)
57 {
58 /* if tree is empty */
59 if (*treePtr == NULL) {
60 *treePtr = malloc(sizeof(TreeNode));
61
62 /* if memory was allocated then assign data */
63 if (*treePtr != NULL) {
64 (*treePtr)->data = value;
65 (*treePtr)->leftPtr = NULL;
66 (*treePtr)->rightPtr = NULL;
67 } /* end if */
68 else {
69 printf("%d not inserted. No memory available.\n", value);
70 } /* end else */
71 } /* end if */
72 else { /* tree is not empty */
73 /* data to insert is less than data in current node */
74 if (value < (*treePtr)->data) {
75 insertNode(&((*treePtr)->leftPtr), value);
76 } /* end if */

```

---

**Fig. 12.19** | Creating and traversing a binary tree. (Part 2 of 3.)

```

77
78 /* data to insert is greater than data in current node */
79 else if (value > (*treePtr)->data) {
80 insertNode(&((*treePtr)->rightPtr), value);
81 } /* end else if */
82 else { /* duplicate data value ignored */
83 printf("dup");
84 } /* end else */
85 } /* end else */
86 } /* end function insertNode */
87
88 /* begin inorder traversal of tree */
89 void inOrder(TreeNodePtr treePtr)
90 {
91 /* if tree is not empty then traverse */
92 if (treePtr != NULL) {
93 inOrder(treePtr->leftPtr);
94 printf("%3d", treePtr->data);
95 inOrder(treePtr->rightPtr);
96 } /* end if */
97 } /* end function inOrder */
98
99 /* begin preorder traversal of tree */
100 void preOrder(TreeNodePtr treePtr)
101 {
102 /* if tree is not empty then traverse */
103 if (treePtr != NULL) {
104 printf("%3d", treePtr->data);
105 preOrder(treePtr->leftPtr);
106 preOrder(treePtr->rightPtr);
107 } /* end if */
108 } /* end function preOrder */
109
110 /* begin postorder traversal of tree */
111 void postOrder(TreeNodePtr treePtr)
112 {
113 /* if tree is not empty then traverse */
114 if (treePtr != NULL) {
115 postOrder(treePtr->leftPtr);
116 postOrder(treePtr->rightPtr);
117 printf("%3d", treePtr->data);
118 } /* end if */
119 } /* end function postOrder */

```

**Fig. 12.19** | Creating and traversing a binary tree. (Part 3 of 3.)

The numbers being placed in the tree are:

6 7 4 12 7dup 2 2dup 5 7dup 11

The preOrder traversal is:

6 4 2 5 7 12 11

**Fig. 12.20** | Sample output from the program of Fig. 12.19. (Part 1 of 2.)

```

The inOrder traversal is:
 2 4 5 6 7 11 12

The postOrder traversal is:
 2 5 4 11 12 7 6

```

**Fig. 12.20** | Sample output from the program of Fig. 12.19. (Part 2 of 2.)

The functions used in Fig. 12.19 to create a binary search tree and traverse the tree are recursive. Function `insertNode` (lines 56–86) receives the address of the tree and an integer to be stored in the tree as arguments. *A node can only be inserted as a leaf node in a binary search tree.* The steps for inserting a node in a binary search tree are as follows:

1. If `*treePtr` is `NULL` (line 59), create a new node (line 60). Call `malloc`, assign the allocated memory to `*treePtr`, assign to `(*treePtr)->data` the integer to be stored (line 64), assign to `(*treePtr)->leftPtr` and `(*treePtr)->rightPtr` the value `NULL` (lines 65–66, and return control to the caller (either `main` or a previous call to `insertNode`).
2. If the value of `*treePtr` is not `NULL` and the value to be inserted is less than `(*treePtr)->data`, function `insertNode` is called with the address of `(*treePtr)->leftPtr` (line 75). If the value to be inserted is greater than `(*treePtr)->data`, function `insertNode` is called with the address of `(*treePtr)->rightPtr` (line 80). Otherwise, the recursive steps continue until a `NULL` pointer is found, then Step 1) is executed to insert the new node.


Functions `inOrder` (lines 89–97), `preOrder` (lines 100–108) and `postOrder` (lines 111–119) each receive a tree (i.e., the pointer to the root node of the tree) and traverse the tree.

The steps for an `inOrder` traversal are:

1. Traverse the left subtree `inOrder`.
2. Process the value in the node.
3. Traverse the right subtree `inOrder`.

The value in a node is not processed until the values in its left subtree are processed. The `inOrder` traversal of the tree in Fig. 12.21 is:

```
6 13 17 27 33 42 48
```



**Fig. 12.21** | Binary search tree with seven nodes.

The `inOrder` traversal of a binary search tree prints the node values in ascending order. The process of creating a binary search tree actually sorts the data—and thus this process is called the **binary tree sort**.

The steps for a `preOrder` traversal are:

1. Process the value in the node.
2. Traverse the left subtree `preOrder`.
3. Traverse the right subtree `preOrder`.

The value in each node is processed as the node is visited. After the value in a given node is processed, the values in the left subtree are processed, then the values in the right subtree are processed. The `preOrder` traversal of the tree in Fig. 12.21 is:

```
27 13 6 17 42 33 48
```

The steps for a `postOrder` traversal are:

1. Traverse the left subtree `postOrder`.
2. Traverse the right subtree `postOrder`.
3. Process the value in the node.

The value in each node is not printed until the values of its children are printed. The `postOrder` traversal of the tree in Fig. 12.21 is:

```
6 17 13 33 48 42 27
```

The binary search tree facilitates **duplicate elimination**. As the tree is being created, an attempt to insert a duplicate value will be recognized because a duplicate will follow the same “go left” or “go right” decisions on each comparison as the original value did. Thus, the duplicate will eventually be compared with a node in the tree containing the same value. The duplicate value may simply be discarded at this point.

Searching a binary tree for a value that matches a key value is also fast. If the tree is tightly packed, each level contains about twice as many elements as the previous level. So a binary search tree with  $n$  elements would have a maximum of  $\log_2 n$  levels, and thus a maximum of  $\log_2 n$  comparisons would have to be made either to find a match or to determine that no match exists. This means, for example, that when searching a (tightly packed) 1000-element binary search tree, no more than 10 comparisons need to be made because  $2^{10} > 1000$ . When searching a (tightly packed) 1,000,000 element binary search tree, no more than 20 comparisons need to be made because  $2^{20} > 1,000,000$ .

In the exercises, algorithms are presented for several other binary tree operations such as deleting an item from a binary tree, printing a binary tree in a two-dimensional tree format and performing a level order traversal of a binary tree. The level order traversal of a binary tree visits the nodes of the tree row-by-row starting at the root node level. On each level of the tree, the nodes are visited from left to right. Other binary tree exercises include allowing a binary search tree to contain duplicate values, inserting string values in a binary tree and determining how many levels are contained in a binary tree.

## Summary

### Section 12.1 Introduction

- Dynamic data structures grow and shrink at execution time.
- Linked lists are collections of data items “lined up in a row”—insertions and deletions are made anywhere in a linked list.

- With stacks, insertions and deletions are made only at the top.
- Queues represent waiting lines; insertions are made at the back (also referred to as the tail) of a queue and deletions are made from the front (also referred to as the head) of a queue.
- Binary trees facilitate high-speed searching and sorting of data, efficient elimination of duplicate data items, representing file system directories and compiling expressions into machine language.

### *Section 12.2 Self-Referential Structures*

- A self-referential structure contains a pointer member that points to a structure of the same type.
- Self-referential structures can be linked together to form lists, queues, stacks and trees.
- A NULL pointer normally indicates the end of a data structure.

### *Section 12.3 Dynamic Memory Allocation*

- Creating and maintaining dynamic data structures require dynamic memory allocation.
- Functions `malloc` and `free`, and operator `sizeof`, are essential to dynamic memory allocation.
- Function `malloc` receives the number of bytes to be allocated and returns a `void *` pointer to the allocated memory. A `void *` pointer may be assigned to a variable of any pointer type.
- Function `malloc` is normally used with the `sizeof` operator.
- The memory allocated by `malloc` is not initialized.
- If no memory is available, `malloc` returns NULL.
- Function `free` deallocates memory so that the memory can be reallocated in the future.
- C also provides functions `calloc` and `realloc` for creating and modifying dynamic arrays.

### *Section 12.4 Linked Lists*

- A linked list is a linear collection of self-referential structures, called nodes, connected by pointer links.
- A linked list is accessed via a pointer to the first node. Subsequent nodes are accessed via the link pointer member stored in each node.
- By convention, the link pointer in the last node of a list is set to NULL to mark the end of the list.
- Data is stored in a linked list dynamically—each node is created as necessary.
- A node can contain data of any type including other struct objects.
- Linked lists are dynamic, so the length of a list can increase or decrease as necessary.
- Linked list nodes are normally not stored contiguously in memory. Logically, however, the nodes of a linked list appear to be contiguous.

### *Section 12.5 Stacks*

- A stack is a constrained version of a linked list. New nodes can be added to a stack and removed from a stack only at the top—referred to as a last-in, first-out (LIFO) data structure.
- The primary functions used to manipulate a stack are `push` and `pop`. Function `push` creates a new node and places it on top of the stack. Function `pop` removes a node from the top of the stack, frees the memory that was allocated to the popped node and returns the popped value.
- Whenever a function call is made, the called function must know how to return to its caller, so the return address is pushed onto a stack. If a series of function calls occurs, the successive return values are pushed onto the stack in last-in, first-out order so that each function can return to its caller. Stacks support recursive function calls in the same manner as conventional nonrecursive calls.
- Stacks are used by compilers in the process of evaluating expressions and generating machine language code.

### Section 12.6 Queues

- Queue nodes are removed only from the head of the queue and are inserted only at the tail of the queue—referred to as a first-in, first-out (FIFO) data structure.
- The insert and remove operations for a queue are known as enqueue and dequeue.

### Section 12.7 Trees

- A tree is a nonlinear, two-dimensional data structure. Tree nodes contain two or more links.
- Binary trees are trees whose nodes all contain two links.
- The root node is the first node in a tree. Each link in the root node of a binary tree refers to a child. The left child is the first node in the left subtree, and the right child is the first node in the right subtree. The children of a node are called siblings.
- A node with no children is called a leaf node.
- A binary search tree (with no duplicate node values) has the characteristic that the values in any left subtree are less than the value in its parent node, and the values in any right subtree are greater than the value in its parent node.
- A node can only be inserted as a leaf node in a binary search tree.
- The steps for an in-order traversal are: Traverse the left subtree in-order, process the value in the node, then traverse the right subtree in-order. The value in a node is not processed until the values in its left subtree are processed.
- The in-order traversal of a binary search tree processes the node values in ascending order. The process of creating a binary search tree actually sorts the data—and thus this process is called the binary tree sort.
- The steps for a pre-order traversal are: Process the value in the node, traverse the left subtree pre-order, then traverse the right subtree pre-order. The value in each node is processed as the node is visited. After the value in a given node is processed, the values in the left subtree are processed, then the values in the right subtree are processed.
- The steps for a post-order traversal are: Traverse the left subtree post-order, traverse the right subtree post-order, then process the value in the node. The value in each node is not processed until the values of its children are processed.
- A binary search tree facilitates duplicate elimination. As the tree is being created, an attempt to insert a duplicate value will be recognized because a duplicate will follow the same “go left” or “go right” decisions on each comparison as the original value did. Thus, the duplicate will eventually be compared with a node in the tree containing the same value. The duplicate value may simply be discarded at this point.
- Searching a binary tree for a value that matches a key value is fast. If the tree is tightly packed, each level contains about twice as many elements as the previous level. So a binary search tree with  $n$  elements would have a maximum of  $\log_2 n$  levels, and thus a maximum of  $\log_2 n$  comparisons would have to be made either to find a match or to determine that no match exists. This means that when searching a (tightly packed) 1000-element binary search tree, no more than 10 comparisons need to be made because  $2^{10} > 1000$ . When searching a (tightly packed) 1,000,000-element binary search tree, no more than 20 comparisons need to be made because  $2^{20} > 1,000,000$ .

## Terminology

binary search tree 479  
 binary tree 455, 478  
 binary tree sort 482  
 child 478

dequeue function of a queue 473  
 double indirection (pointer to a pointer) 463  
 duplicate elimination 483  
 dynamic data structure 455



dynamic memory allocation 456  
 enqueue function of a queue 473  
 first-in first-out (FIFO) 472  
 free function 456  
 head of a queue 455  
 infix notation 489  
 inorder 479  
 last-in-first-out (LIFO) 466  
 leaf node 478  
 left child 478  
 left subtree 478  
 level order binary tree traversal 493  
 linear data structures 478  
 link 458  
 link (pointer in a self-referential structure) 456  
 linked list 455, 458  
 malloc function 456  
 node 458  
 NULL pointer 456  
 parent node 479  
 pointer to pointer (double indirection) 463  
 pointer to void (void \*) 456  
 postfix notation 489  
 postorder 479  
 predicate function 463  
 preorder 479  
 queue 455, 472  
 replacement node 493  
 right child 478  
 right subtree 478  
 root node of a binary tree 478  
 self-referential structure 456  
 sibling 478  
 sizeof operator 456  
 stack 455, 466  
 tail of a queue 455  
 top of a stack 455  
 tree 478

## Self-Review Exercises

**12.1** Fill in the blanks in each of the following:

- A self-\_\_\_\_\_ structure is used to form dynamic data structures.
- Function \_\_\_\_\_ is used to dynamically allocate memory.
- A(n) \_\_\_\_\_ is a specialized version of a linked list in which nodes can be inserted and deleted only from the start of the list.
- Functions that look at a linked list but do not modify it are referred to as \_\_\_\_\_.
- A queue is referred to as a(n) \_\_\_\_\_ data structure.
- The pointer to the next node in a linked list is referred to as a(n) \_\_\_\_\_.
- Function \_\_\_\_\_ is used to reclaim dynamically allocated memory.
- A(n) \_\_\_\_\_ is a specialized version of a linked list in which nodes can be inserted only at the start of the list and deleted only from the end of the list.
- A(n) \_\_\_\_\_ is a nonlinear, two-dimensional data structure that contains nodes with two or more links.
- A stack is referred to as a(n) \_\_\_\_\_ data structure because the last node inserted is the first node removed.
- The nodes of a(n) \_\_\_\_\_ tree contain two link members.
- The first node of a tree is the \_\_\_\_\_ node.
- Each link in a tree node points to a(n) \_\_\_\_\_ or \_\_\_\_\_ of that node.
- A tree node that has no children is called a(n) \_\_\_\_\_ node.
- The three traversal algorithms (covered in this chapter) for a binary tree are \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.

**12.2** What are the differences between a linked list and a stack?

**12.3** What are the differences between a stack and a queue?

**12.4** Write a statement or set of statements to accomplish each of the following. Assume that all the manipulations occur in main (therefore, no addresses of pointer variables are needed), and assume the following definitions:

```

struct gradeNode {
 char lastName[20];

```

```
double grade;
struct gradeNode *nextPtr;
};

typedef struct gradeNode GradeNode;
typedef GradeNode *GradeNodePtr;
```


- Create a pointer to the start of the list called `startPtr`. The list is empty.
- Create a new node of type `GradeNode` that is pointed to by pointer `newPtr` of type `GradeNodePtr`. Assign the string "Jones" to member `lastName` and the value 91.5 to member `grade` (use `strcpy`). Provide any necessary declarations and statements.
- Assume that the list pointed to by `startPtr` currently consists of 2 nodes—one containing "Jones" and one containing "Smith". The nodes are in alphabetical order. Provide the statements necessary to insert in order nodes containing the following data for `lastName` and `grade`:

|             |      |
|-------------|------|
| "Adams"     | 85.0 |
| "Thompson"  | 73.5 |
| "Pritchard" | 66.5 |

Use pointers `previousPtr`, `currentPtr` and `newPtr` to perform the insertions. State what `previousPtr` and `currentPtr` point to before each insertion. Assume that `newPtr` always points to the new node, and that the new node has already been assigned the data.

- Write a `while` loop that prints the data in each node of the list. Use pointer `currentPtr` to move along the list.
- Write a `while` loop that deletes all the nodes in the list and frees the memory associated with each node. Use pointer `currentPtr` and pointer `tempPtr` to walk along the list and free memory, respectively.

**12.5** Provide the inorder, preorder and postorder traversals of the binary search tree of Fig. 12.22.



**Fig. 12.22** | A 15-node binary search tree.

## Answers to Self-Review Exercises

**12.1** a) referential. b) `malloc`. c) stack. d) predicates. e) FIFO. f) link. g) free. h) queue. i) tree. j) LIFO. k) binary. l) root. m) child, subtree. n) leaf. o) inorder, preorder postorder.

**12.2** It's possible to insert a node anywhere in a linked list, and remove a node from anywhere in a linked list. However, nodes in a stack may only be inserted at the top of the stack and removed from the top of a stack.

**12.3** A queue has pointers to both its head and its tail so that nodes may be inserted at the tail and deleted from the head. A stack has a single pointer to the top of the stack where both insertion and deletion of nodes is performed.

**12.4** a) `GradeNodePtr startPtr = NULL;`  
 b) `GradeNodePtr newPtr;`  
`newPtr = malloc( sizeof( GradeNode ) );`

```

strcpy(newPtr->lastName, "Jones");
newPtr->grade = 91.5;
newPtr->nextPtr = NULL;
c) To insert "Adams":
previousPtr is NULL, currentPtr points to the first element in the list.
newPtr->nextPtr = currentPtr;
startPtr = newPtr;
To insert "Thompson":
previousPtr points to the last element in the list (containing "Smith")
currentPtr is NULL.
newPtr->nextPtr = currentPtr;
previousPtr->nextPtr = newPtr;
To insert "Pritchard":
previousPtr points to the node containing "Jones"
currentPtr points to the node containing "Smith"
newPtr->nextPtr = currentPtr;
previousPtr->nextPtr = newPtr;
d) currentPtr = startPtr;
while (currentPtr != NULL) {
 printf("Lastname = %s\nGrade = %6.2f\n",
 currentPtr->lastName, currentPtr->grade);
 currentPtr = currentPtr->nextPtr;
}
e) currentPtr = startPtr;
while (currentPtr != NULL) {
 tempPtr = currentPtr;
 currentPtr = currentPtr->nextPtr;
 free(tempPtr);
}
startPtr = NULL;

```

**12.5** The inorder traversal is:

11 18 19 28 32 40 44 49 69 71 72 83 92 97 99

The preorder traversal is:

49 28 18 11 19 40 32 44 83 71 69 72 97 92 99

The postorder traversal is:

11 19 18 32 44 40 28 69 72 71 92 99 97 83 49

## Exercises

**12.6** (*Concatenating Lists*) Write a program that concatenates two linked lists of characters. The program should include function `concatenate` that takes pointers to both lists as arguments and concatenates the second list to the first list.

**12.7** (*Merging Ordered Lists*) Write a program that merges two ordered lists of integers into a single ordered list of integers. Function `merge` should receive pointers to the first node of each of the lists to be merged and should return a pointer to the first node of the merged list.

**12.8** (*Inserting into an Ordered List*) Write a program that inserts 25 random integers from 0 to 100 in order in a linked list. The program should calculate the sum of the elements and the floating-point average of the elements.

**12.9** (*Creating a Linked List, then Reversing Its Elements*) Write a program that creates a linked list of 10 characters, then creates a copy of the list in reverse order.

**12.10** (*Reversing the Words of a Sentence*) Write a program that inputs a line of text and uses a stack to print the line reversed.

**12.11** (*Palindrome Tester*) Write a program that uses a stack to determine if a string is a palindrome (i.e., the string is spelled identically backward and forward). The program should ignore spaces and punctuation.

**12.12** (*Infix-to-Postfix Converter*) Stacks are used by compilers to help in the process of evaluating expressions and generating machine language code. In this and the next exercise, we investigate how compilers evaluate arithmetic expressions consisting only of constants, operators and parentheses.

Humans generally write expressions like  $3 + 4$  and  $7 / 9$  in which the operator (+ or / here) is written between its operands—this is called **infix notation**. Computers “prefer” **postfix notation** in which the operator is written to the right of its two operands. The preceding infix expressions would appear in postfix notation as  $3\ 4\ +$  and  $7\ 9\ /$ , respectively.

To evaluate a complex infix expression, a compiler would first convert the expression to postfix notation, and then evaluate the postfix version of the expression. Each of these algorithms requires only a single left-to-right pass of the expression. Each algorithm uses a stack in support of its operation, and in each the stack is used for a different purpose.

In this exercise, you’ll write a version of the infix-to-postfix conversion algorithm. In the next exercise, you’ll write a version of the postfix expression evaluation algorithm.

Write a program that converts an ordinary infix arithmetic expression (assume a valid expression is entered) with single digit integers such as

$$(6 + 2) * 5 - 8 / 4$$

to a postfix expression. The postfix version of the preceding infix expression is

$$6\ 2\ +\ 5\ *\ 8\ 4\ /\ -$$

The program should read the expression into character array `infix`, and use modified versions of the stack functions implemented in this chapter to help create the postfix expression in character array `postfix`. The algorithm for creating a postfix expression is as follows:

- 1) Push a left parenthesis '(' onto the stack.
- 2) Append a right parenthesis ')' to the end of `infix`.
- 3) While the stack is not empty, read `infix` from left to right and do the following:
  - If the current character in `infix` is a digit, copy it to the next element of `postfix`.
  - If the current character in `infix` is a left parenthesis, push it onto the stack.
  - If the current character in `infix` is an operator,
    - Pop operators (if there are any) at the top of the stack while they have equal or higher precedence than the current operator, and insert the popped operators in `postfix`.
    - Push the current character in `infix` onto the stack.
  - If the current character in `infix` is a right parenthesis
    - Pop operators from the top of the stack and insert them in `postfix` until a left parenthesis is at the top of the stack.
    - Pop (and discard) the left parenthesis from the stack.

The following arithmetic operations are allowed in an expression:

- + addition
- subtraction
- \* multiplication
- / division

^ exponentiation  
% remainder

The stack should be maintained with the following declarations:

```
struct stackNode {
 char data;
 struct stackNode *nextPtr;
};

typedef struct stackNode StackNode;
typedef StackNode *StackNodePtr;
```

The program should consist of main and eight other functions with the following function headers:

```
void convertToPostfix(char infix[], char postfix[])
```

Convert the infix expression to postfix notation.

```
int isOperator(char c)
```

Determine if c is an operator.

```
int precedence(char operator1, char operator2)
```

Determine if the precedence of operator1 is less than, equal to, or greater than the precedence of operator2. The function returns -1, 0 and 1, respectively.

```
void push(StackNodePtr *topPtr, char value)
```

Push a value on the stack.

```
char pop(StackNodePtr *topPtr)
```

Pop a value off the stack.

```
char stackTop(StackNodePtr topPtr)
```

Return the top value of the stack without popping the stack.

```
int isEmpty(StackNodePtr topPtr)
```

Determine if the stack is empty.

```
void printStack(StackNodePtr topPtr)
```

Print the stack.

**12.13 (Postfix Evaluator)** Write a program that evaluates a postfix expression (assume it's valid) such as

6 2 + 5 \* 8 4 / -

The program should read a postfix expression consisting of single digits and operators into a character array. Using modified versions of the stack functions implemented earlier in this chapter, the program should scan the expression and evaluate it. The algorithm is as follows:

- 1) Append the null character ('\0') to the end of the postfix expression. When the null character is encountered, no further processing is necessary.
- 2) While '\0' has not been encountered, read the expression from left to right.

If the current character is a digit,

Push its integer value onto the stack (the integer value of a digit character is its value in the computer's character set minus the value of '0' in the computer's character set).

Otherwise, if the current character is an *operator*,

Pop the two top elements of the stack into variables x and y.

Calculate y *operator* x.

Push the result of the calculation onto the stack.

- 3) When the null character is encountered in the expression, pop the top value of the stack. This is the result of the postfix expression.

[*Note:* In 2) above, if the operator is '/', the top of the stack is 2, and the next element in the stack is 8, then pop 2 into x, pop 8 into y, evaluate  $8 / 2$ , and push the result, 4, back on the stack. This note also applies to operator '-'.]

The arithmetic operations allowed in an expression are:

- + addition
- subtraction
- \* multiplication
- / division
- ^ exponentiation
- % remainder

The stack should be maintained with the following declarations:

```
struct stackNode {
 int data;
 struct stackNode *nextPtr;
};

typedef struct stackNode StackNode;
typedef StackNode *StackNodePtr;
```

The program should consist of main and six other functions with the following function headers:

```
int evaluatePostfixExpression(char *expr)
 Evaluate the postfix expression.

int calculate(int op1, int op2, char operator)
 Evaluate the expression op1 operator op2.

void push(StackNodePtr *topPtr, int value)
 Push a value on the stack.

int pop(StackNodePtr *topPtr)
 Pop a value off the stack.

int isEmpty(StackNodePtr topPtr)
 Determine if the stack is empty.

void printStack(StackNodePtr topPtr)
 Print the stack.
```

**12.14 (Postfix Evaluator Modification)** Modify the postfix evaluator program of Exercise 12.13 so that it can process integer operands larger than 9.

**12.15 (Supermarket Simulation)** Write a program that simulates a check-out line at a supermarket. The line is a queue. Customers arrive in random integer intervals of 1 to 4 minutes. Also, each customer is serviced in random integer intervals of 1 to 4 minutes. Obviously, the rates need to be balanced. If the average arrival rate is larger than the average service rate, the queue will grow infinitely. Even with balanced rates, randomness can still cause long lines. Run the supermarket simulation for a 12-hour day (720 minutes) using the following algorithm:

- 1) Choose a random integer between 1 and 4 to determine the minute at which the first customer arrives.
- 2) At the first customer's arrival time:
  - Determine customer's service time (random integer from 1 to 4);
  - Begin servicing the customer;
  - Schedule arrival time of next customer (random integer 1 to 4 added to the current time).

- 3) For each minute of the day:
  - If the next customer arrives,
    - Say so;
    - Enqueue the customer;
    - Schedule the arrival time of the next customer;
  - If service was completed for the last customer;
    - Say so;
    - Dequeue next customer to be serviced;
    - Determine customer's service completion time  
(random integer from 1 to 4 added to the current time).

Now run your simulation for 720 minutes and answer each of the following:

- a) What is the maximum number of customers in the queue at any time?
- b) What is the longest wait any one customer experienced?
- c) What happens if the arrival interval is changed from 1 to 4 minutes to 1 to 3 minutes?

**12.16** (*Allowing Duplicates in a Binary Tree*) Modify the program of Fig. 12.19 to allow the binary tree to contain duplicate values.

**12.17** (*Binary Search Tree of Strings*) Write a program based on the program of Fig. 12.19 that inputs a line of text, tokenizes the sentence into separate words, inserts the words in a binary search tree, and prints the inorder, preorder, and postorder traversals of the tree.

[Hint: Read the line of text into an array. Use `strtok` to tokenize the text. When a token is found, create a new node for the tree, assign the pointer returned by `strtok` to member `string` of the new node, and insert the node in the tree.]

**12.18** (*Duplicate Elimination*) In this chapter, we saw that duplicate elimination is straightforward when creating a binary search tree. Describe how you would perform duplicate elimination using only a single subscripted array. Compare the performance of array-based duplicate elimination with the performance of binary-search-tree-based duplicate elimination.

**12.19** (*Depth of a Binary Tree*) Write a function `depth` that receives a binary tree and determines how many levels it has.

**12.20** (*Recursively Print a List Backwards*) Write a function `printListBackwards` that recursively outputs the items in a list in reverse order. Use your function in a test program that creates a sorted list of integers and prints the list in reverse order.

**12.21** (*Recursively Search a List*) Write a function `searchList` that recursively searches a linked list for a specified value. The function should return a pointer to the value if it's found; otherwise, `NULL` should be returned. Use your function in a test program that creates a list of integers. The program should prompt the user for a value to locate in the list.

**12.22** (*Binary Tree Delete*) In this exercise, we discuss deleting items from binary search trees. The deletion algorithm is not as straightforward as the insertion algorithm. There are three cases that are encountered when deleting an item—the item is contained in a leaf node (i.e., it has no children), the item is contained in a node that has one child, or the item is contained in a node that has two children.

If the item to be deleted is contained in a leaf node, the node is deleted and the pointer in the parent node is set to `NULL`.

If the item to be deleted is contained in a node with one child, the pointer in the parent node is set to point to the child node and the node containing the data item is deleted. This causes the child node to take the place of the deleted node in the tree.

The last case is the most difficult. When a node with two children is deleted, another node must take its place. However, the pointer in the parent node cannot simply be assigned to point to one of the children of the node to be deleted. In most cases, the resulting binary search tree would

not adhere to the following characteristic of binary search trees: *The values in any left subtree are less than the value in the parent node, and the values in any right subtree are greater than the value in the parent node.*

Which node is used as a **replacement node** to maintain this characteristic? Either the node containing the largest value in the tree less than the value in the node being deleted, or the node containing the smallest value in the tree greater than the value in the node being deleted. Let's consider the node with the smaller value. In a binary search tree, the largest value less than a parent's value is located in the left subtree of the parent node and is guaranteed to be contained in the rightmost node of the subtree. This node is located by walking down the left subtree to the right until the pointer to the right child of the current node is NULL. We're now pointing to the replacement node which is either a leaf node or a node with one child to its left. If the replacement node is a leaf node, the steps to perform the deletion are as follows:

- 1) Store the pointer to the node to be deleted in a temporary pointer variable (this pointer is used to delete the dynamically allocated memory).
- 2) Set the pointer in the parent of the node being deleted to point to the replacement node.
- 3) Set the pointer in the parent of the replacement node to null.
- 4) Set the pointer to the right subtree in the replacement node to point to the right subtree of the node to be deleted.
- 5) Delete the node to which the temporary pointer variable points.

The deletion steps for a replacement node with a left child are similar to those for a replacement node with no children, but the algorithm also must move the child to the replacement node's position. If the replacement node is a node with a left child, the steps to perform the deletion are as follows:

- 1) Store the pointer to the node to be deleted in a temporary pointer variable.
- 2) Set the pointer in the parent of the node being deleted to point to the replacement node.
- 3) Set the pointer in the parent of the replacement node to point to the left child of the replacement node.
- 4) Set the pointer to the right subtree in the replacement node to point to the right subtree of the node to be deleted.
- 5) Delete the node to which the temporary pointer variable points.

Write function `deleteNode` which takes as its arguments a pointer to the root node of the tree and the value to be deleted. The function should locate in the tree the node containing the value to be deleted and use the algorithms discussed here to delete the node. If the value is not found in the tree, the function should print a message that indicates whether or not the value is deleted. Modify the program of Fig. 12.19 to use this function. After deleting an item, call the `inOrder`, `preOrder` and `postOrder` traversal functions to confirm that the delete operation was performed correctly.

**12.23 (Binary Tree Search)** Write function `binaryTreeSearch` that attempts to locate a specified value in a binary search tree. The function should take as arguments a pointer to the root node of the binary tree and a search key to be located. If the node containing the search key is found, the function should return a pointer to that node; otherwise, the function should return a NULL pointer.

**12.24 (Level Order Binary Tree Traversal)** The program of Fig. 12.19 illustrated three recursive methods of traversing a binary tree—inorder traversal, preorder traversal, and postorder traversal. This exercise presents the **level order traversal** of a binary tree in which the node values are printed level-by-level starting at the root node level. The nodes on each level are printed from left to right. The level order traversal is not a recursive algorithm. It uses the queue data structure to control the output of the nodes. The algorithm is as follows:

- 1) Insert the root node in the queue
- 2) While there are nodes left in the queue,
  - Get the next node in the queue
  - Print the node's value



If the pointer to the left child of the node is not null  
 Insert the left child node in the queue  
 If the pointer to the right child of the node is not null  
 Insert the right child node in the queue.

Write function `levelOrder` to perform a level order traversal of a binary tree. The function should take as an argument a pointer to the root node of the binary tree. Modify the program of Fig. 12.19 to use this function. Compare the output from this function to the outputs of the other traversal algorithms to see that it worked correctly. [Note: You'll also need to modify and incorporate the queue processing functions of Fig. 12.13 in this program.]

**12.25 (Printing Trees)** Write a recursive function `outputTree` to display a binary tree on the screen. The function should output the tree row-by-row with the top of the tree at the left of the screen and the bottom of the tree toward the right of the screen. Each row is output vertically. For example, the binary tree illustrated in Fig. 12.22 is output as follows:

```

 99
 97 92
 83 72
 71 69
 49 44
 40 32
 28 19
 18 11

```

Note the rightmost leaf node appears at the top of the output in the rightmost column, and the root node appears at the left of the output. Each column of output starts five spaces to the right of the previous column. Function `outputTree` should receive as arguments a pointer to the root node of the tree and an integer `totalSpaces` representing the number of spaces preceding the value to be output (this variable should start at zero so the root node is output at the left of the screen). The function uses a modified inorder traversal to output the tree—it starts at the rightmost node in the tree and works back to the left. The algorithm is as follows:

- While the pointer to the current node is not null
  - Recursively call `outputTree` with the current node's right subtree and `totalSpaces + 5`
  - Use a for statement to count from 1 to `totalSpaces` and output spaces
  - Output the value in the current node
  - Set the pointer to the current node to point to the left subtree of the current node
  - Increment `totalSpaces` by 5.

## Special Section: Building Your Own Compiler

In Exercises 7.27–7.29, we introduced Simpletron Machine Language (SML), and you implemented a Simpletron computer simulator to execute SML programs. In Exercises 12.26–12.30, we build a compiler that converts programs written in a high-level programming language to SML. This section “ties” together the entire programming process. You'll write programs in this new high-level language, compile them on the compiler you build and run them on the simulator you built in Exercise 7.28. You should make every effort to implement your compiler in an object-oriented manner. [Note: Due to the size of the descriptions for Exercises 12.26–12.30, we've posted them in a PDF document located at [www.deitel.com/books/cht6/](http://www.deitel.com/books/cht6/).]

*Hold thou the good; define it well.*

—Alfred, Lord Tennyson

*I have found you an argument; but I am not obliged to find you an understanding.*

—Samuel Johnson

*A good symbol is the best argument, and is a missionary to persuade thousands.*

—Ralph Waldo Emerson

*The partisan, when he is engaged in a dispute, cares nothing about the rights of the question, but is anxious only to convince his hearers of his own assertions.*

—Plato

## Objectives

In this chapter, you'll learn:

- To use `#include` to develop large programs.
- To use `#define` to create macros and macros with arguments.
- To use conditional compilation to specify portions of a program that should not always be compiled (such as code that assists you in debugging).
- To display error messages during conditional compilation.
- To use assertions to test if the values of expressions are correct.

|                                                                             |                                                                                  |
|-----------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| <b>13.1</b> Introduction                                                    | <b>13.6</b> <code>#error</code> and <code>#pragma</code> Preprocessor Directives |
| <b>13.2</b> <code>#include</code> Preprocessor Directive                    | <b>13.7</b> <code>#</code> and <code>##</code> Operators                         |
| <b>13.3</b> <code>#define</code> Preprocessor Directive: Symbolic Constants | <b>13.8</b> Line Numbers                                                         |
| <b>13.4</b> <code>#define</code> Preprocessor Directive: Macros             | <b>13.9</b> Predefined Symbolic Constants                                        |
| <b>13.5</b> Conditional Compilation                                         | <b>13.10</b> Assertions                                                          |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 13.1 Introduction

The **C preprocessor** executes before a program is compiled. Some actions it performs are the inclusion of other files in the file being compiled, definition of **symbolic constants** and **macros**, **conditional compilation** of program code and **conditional execution of preprocessor directives**. Preprocessor directives begin with `#` and only white-space characters and comments may appear before a preprocessor directive on a line.

## 13.2 `#include` Preprocessor Directive

The **`#include` preprocessor directive** has been used throughout this text. The `#include` directive causes a copy of a specified file to be included in place of the directive. The two forms of the `#include` directive are:

```
#include <filename>
#include "filename"
```

The difference between these is the location the preprocessor begins searches for the file to be included. If the file name is enclosed in quotes, the preprocessor starts searches in the same directory as the file being compiled for the file to be included (and may search other locations as well). This method is normally used to include programmer-defined headers. If the file name is enclosed in angle brackets (`<` and `>`)—used for **standard library headers**—the search is performed in an implementation-dependent manner, normally through predesignated compiler and system directories.

The `#include` directive is used to include standard library headers such as `stdio.h` and `stdlib.h` (see Fig. 5.6) and with programs consisting of several source files that are to be compiled together. A header containing declarations common to the separate program files is often created and included in the file. Examples of such declarations are structure and union declarations, enumerations and function prototypes.

## 13.3 `#define` Preprocessor Directive: Symbolic Constants

The **`#define` directive** creates symbolic constants—constants represented as symbols—and **macros**—operations defined as symbols. The `#define` directive format is

```
#define identifier replacement-text
```

When this line appears in a file, all subsequent occurrences of identifier that do not appear in string literals will be replaced by **replacement-text** automatically before the program is compiled. For example,

```
#define PI 3.14159
```

replaces all subsequent occurrences of the symbolic constant PI with the numeric constant 3.14159. Symbolic constants enable you to create a name for a constant and use the name throughout the program. If the constant needs to be modified throughout the program, it can be modified once in the #define directive. When the program is recompiled, all occurrences of the constant in the program will be modified accordingly. [Note: Everything to the right of the symbolic constant name replaces the symbolic constant.] For example, #define PI = 3.14159 causes the preprocessor to replace every occurrence of the identifier PI with = 3.14159. This is the cause of many subtle logic and syntax errors. Redefining a symbolic constant with a new value is also an error.



### Good Programming Practice 13.1

*Using meaningful names for symbolic constants helps make programs more self-documenting.*



### Good Programming Practice 13.2

*By convention, symbolic constants are defined using only uppercase letters and underscores.*

## 13.4 #define Preprocessor Directive: Macros

A **macro** is an identifier defined in a #define preprocessor directive. As with symbolic constants, the **macro-identifier** is replaced in the program with the **replacement-text** before the program is compiled. Macros may be defined with or without **arguments**. A macro without arguments is processed like a symbolic constant. In a **macro with arguments**, the arguments are substituted in the replacement text, then the macro is **expanded**—i.e., the replacement-text replaces the identifier and argument list in the program. [Note: A symbolic constant is a type of macro.]

Consider the following macro definition with one argument for the area of a circle:

```
#define CIRCLE_AREA(x) ((PI) * (x) * (x))
```

Wherever CIRCLE\_AREA(y) appears in the file, the value of y is substituted for x in the replacement-text, the symbolic constant PI is replaced by its value (defined previously) and the macro is expanded in the program. For example, the statement

```
area = CIRCLE_AREA(4);
```

is expanded to

```
area = ((3.14159) * (4) * (4));
```

and the value of the expression is evaluated and assigned to variable area. The parentheses around each x in the replacement text force the proper order of evaluation when the macro argument is an expression. For example, the statement

```
area = CIRCLE_AREA(c + 2);
```

is expanded to

```
area = ((3.14159) * (c + 2) * (c + 2));
```

which evaluates correctly because the parentheses force the proper order of evaluation. If the parentheses are omitted, the macro expansion is

```
area = 3.14159 * c + 2 * c + 2;
```

which evaluates incorrectly as

```
area = (3.14159 * c) + (2 * c) + 2;
```

because of the rules of operator precedence.



### Common Programming Error 13.1

*Forgetting to enclose macro arguments in parentheses in the replacement text can lead to logic errors.*

Macro CIRCLE\_AREA could be defined as a function. Function circleArea

```
double circleArea(double x)
{
 return 3.14159 * x * x;
}
```

performs the same calculation as macro CIRCLE\_AREA, but the overhead of a function call is associated with function circleArea. The advantages of macro CIRCLE\_AREA are that macros insert code directly in the program—avoiding function call overhead—and the program remains readable because the CIRCLE\_AREA calculation is defined separately and named meaningfully. A disadvantage is that its argument is evaluated twice.



### Performance Tip 13.1

*Macros can sometimes be used to replace a function call with inline code to eliminate the overhead of a function call. Today's optimizing compilers often inline functions for you, so many programmers no longer use macros for this purpose. C99 also provides the inline keyword (see Appendix G).*

The following is a macro definition with two arguments for the area of a rectangle:

```
#define RECTANGLE_AREA(x, y) ((x) * (y))
```

Wherever RECTANGLE\_AREA(x, y) appears in the program, the values of x and y are substituted in the macro replacement text and the macro is expanded in place of the macro name. For example, the statement

```
rectArea = RECTANGLE_AREA(a + 4, b + 7);
```

is expanded to

```
rectArea = ((a + 4) * (b + 7));
```

The value of the expression is evaluated and assigned to variable rectArea.

The replacement text for a macro or symbolic constant is normally any text on the line after the identifier in the #define directive. If the replacement text for a macro or symbolic constant is longer than the remainder of the line, a **backslash** (\) must be placed at the end of the line, indicating that the replacement text continues on the next line.

Symbolic constants and macros can be discarded by using the **#undef** **preprocessor directive**. Directive **#undef** “undefines” a symbolic constant or macro name. The **scope** of a symbolic constant or macro is from its definition until it is undefined with **#undef**, or until the end of the file. Once undefined, a name can be redefined with **#define**.

Functions in the standard library sometimes are defined as macros based on other library functions. A macro commonly defined in the `stdio.h` header is

```
#define getchar() getc(stdin)
```

The macro definition of `getchar` uses function `getc` to get one character from the standard input stream. Function `putchar` of the `stdio.h` header and the character handling functions of the `ctype.h` header often are implemented as macros as well. Expressions with side effects (i.e., variable values are modified) should not be passed to a macro because macro arguments may be evaluated more than once.

## 13.5 Conditional Compilation

**Conditional compilation** enables you to control the execution of preprocessor directives and the compilation of program code. Each of the conditional preprocessor directives evaluates a constant integer expression. Cast expressions, `sizeof` expressions and enumeration constants cannot be evaluated in preprocessor directives.

The conditional preprocessor construct is much like the `if` selection statement. Consider the following preprocessor code:

```
#if !defined(MY_CONSTANT)
#define MY_CONSTANT 0
#endif
```

These directives determine if `MY_CONSTANT` is defined. The expression `defined(MY_CONSTANT)` evaluates to 1 if `MY_CONSTANT` is defined; 0 otherwise. If the result is 0, `!defined(MY_CONSTANT)` evaluates to 1 and `MY_CONSTANT` is defined. Otherwise, the `#define` directive is skipped. Every `#if` construct ends with `#endif`. Directives `#ifdef` and `#ifndef` are shorthand for `#if defined(name)` and `#if !defined(name)`. A multiple-part conditional preprocessor construct may be tested by using the `#elif` (the equivalent of `else if` in an `if` statement) and the `#else` (the equivalent of `else` in an `if` statement) directives. These directives are frequently used to prevent header files from being included multiple times in the same source file. We use this technique extensively in the C++ part of this book.

During program development, it is often helpful to “comment out” portions of code to prevent it from being compiled. If the code contains comments, `/*` and `*/` cannot be used to accomplish this task. Instead, you can use the following preprocessor construct:

```
#if 0
 code prevented from compiling
#endif
```

To enable the code to be compiled, replace the 0 in the preceding construct with 1.

Conditional compilation is commonly used as a debugging aid. Many C implementations provide **debuggers**, which provide much more powerful features than conditional compilation. If a debugger is not available, `printf` statements are often used to print variable values and to confirm the flow of control. These `printf` statements can be enclosed



in conditional preprocessor directives so the statements are only compiled while the debugging process is not completed. For example,

```
#ifdef DEBUG
 printf("Variable x = %d\n", x);
#endif
```

causes a `printf` statement to be compiled in the program if the symbolic constant `DEBUG` has been defined (`#define DEBUG`) before directive `#ifdef DEBUG`. When debugging is completed, the `#define` directive is removed from the source file (or commented out) and the `printf` statements inserted for debugging purposes are ignored during compilation. In larger programs, it may be desirable to define several different symbolic constants that control the conditional compilation in separate sections of the source file.



### Common Programming Error 13.2

*Inserting conditionally compiled `printf` statements for debugging purposes in locations where C currently expects a single statement. In this case, the conditionally compiled statement should be enclosed in a compound statement. Thus, when the program is compiled with debugging statements, the flow of control of the program is not altered.*

## 13.6 `#error` and `#pragma` Preprocessor Directives

The `#error` directive

```
#error tokens
```

prints an implementation-dependent message including the *tokens* specified in the directive. The tokens are sequences of characters separated by spaces. For example,

```
#error 1 - Out of range error
```

contains 6 tokens. When a `#error` directive is processed on some systems, the tokens in the directive are displayed as an error message, preprocessing stops and the program does not compile.

The `#pragma` directive

```
#pragma tokens
```

causes an implementation-defined action. A pragma not recognized by the implementation is ignored. For more information on `#error` and `#pragma`, see the documentation for your C implementation.

## 13.7 `#` and `##` Operators

The `#` and `##` preprocessor operators are available in Standard C. The `#` operator causes a replacement text token to be converted to a string surrounded by quotes. Consider the following macro definition:

```
#define HELLO(x) printf("Hello, " #x "\n");
```

When `HELLO(John)` appears in a program file, it is expanded to

```
printf("Hello, " "John" "\n");
```

The string "John" replaces #x in the replacement text. Strings separated by white space are concatenated during preprocessing, so the preceding statement is equivalent to

```
printf("Hello, John\n");
```

The # operator must be used in a macro with arguments because the operand of # refers to an argument of the macro.

The ## operator concatenates two tokens. Consider the following macro definition:

```
#define TOKENCONCAT(x, y) x ## y
```

When TOKENCONCAT appears in the program, its arguments are concatenated and used to replace the macro. For example, TOKENCONCAT(0, K) is replaced by 0K in the program. The ## operator must have two operands.

## 13.8 Line Numbers

The **#line preprocessor directive** causes the subsequent source code lines to be renumbered starting with the specified constant integer value. The directive

```
#line 100
```

starts line numbering from 100 beginning with the next source code line. A file name can be included in the #line directive. The directive

```
#line 100 "file1.c"
```

indicates that lines are numbered from 100 beginning with the next source code line and that the name of the file for the purpose of any compiler messages is "file1.c". The directive normally is used to help make the messages produced by syntax errors and compiler warnings more meaningful. The line numbers do not appear in the source file.

## 13.9 Predefined Symbolic Constants

Standard C provides **predefined symbolic constants**, several of which are shown in Fig. 13.1. The identifiers for each of the predefined symbolic constants begin and end with *two* underscores. These identifiers and the defined identifier (used in Section 13.5) cannot be used in #define or #undef directives.

| Symbolic constant | Explanation                                                                                       |
|-------------------|---------------------------------------------------------------------------------------------------|
| __LINE__          | The line number of the current source code line (an integer constant).                            |
| __FILE__          | The presumed name of the source file (a string).                                                  |
| __DATE__          | The date the source file was compiled (a string of the form "Mmm dd yyyy" such as "Jan 19 2002"). |
| __TIME__          | The time the source file was compiled (a string literal of the form "hh:mm:ss").                  |
| __STDC__          | The value 1 if the compiler supports Standard C.                                                  |

**Fig. 13.1** | Some predefined symbolic constants.



## 13.10 Assertions

The **assert** macro—defined in the `<assert.h>` header—tests the value of an expression. If the value of the expression is false (0), **assert** prints an error message and calls function **abort** (of the general utilities library—`<stdlib.h>`) to terminate program execution. This is a useful debugging tool for testing if a variable has a correct value. For example, suppose variable `x` should never be larger than 10 in a program. An assertion may be used to test the value of `x` and print an error message if the value of `x` is incorrect. The statement would be

```
assert(x <= 10);
```

If `x` is greater than 10 when the preceding statement is encountered in a program, an error message containing the line number and file name is printed and the program terminates. You may then concentrate on this area of the code to find the error. If the symbolic constant `NDEBUG` is defined, subsequent assertions will be ignored. Thus, when assertions are no longer needed, the line

```
#define NDEBUG
```

is inserted in the program file rather than deleting each assertion manually.



### Software Engineering Observation 13.1

*Assertions are not meant as a substitute for error handling during normal runtime conditions. Their use should be limited to finding logic errors.*

## Summary

### Section 13.1 Introduction

- The preprocessor executes before a program is compiled.
- All preprocessor directives begin with #.

### Section 13.2 #include Preprocessor Directive

- Only white-space characters and comments may appear before a preprocessor directive on a line.
- The `#include` directive includes a copy of the specified file. If the file name is enclosed in quotes, the preprocessor begins searching in the same directory as the file being compiled for the file to be included. If the file name is enclosed in angle brackets (< and >), the search is performed in an implementation-defined manner.

### Section 13.3 #define Preprocessor Directive: Symbolic Constants

- The `#define` preprocessor directive is used to create symbolic constants and macros.
- A symbolic constant is a name for a constant.
- A macro is an operation defined in a `#define` preprocessor directive. Macros may be defined with or without arguments.

### Section 13.4 #define Preprocessor Directive: Macros

- The replacement text for a macro or symbolic constant is any text remaining on the line after the identifier in the `#define` directive. If the replacement text for a macro or symbolic constant is longer than the remainder of the line, a backslash (\) is placed at the end of the line indicating that the replacement text continues on the next line.

- Symbolic constants and macros can be discarded by using the `#undef` preprocessor directive. Directive `#undef` “undefines” the symbolic constant or macro name.
- The scope of a symbolic constant or macro is from its definition until it is undefined with `#undef` or until the end of the file.

### Section 13.5 Conditional Compilation

- Conditional compilation enables you to control the execution of preprocessor directives and the compilation of program code.
- The conditional preprocessor directives evaluate constant integer expressions. Cast expressions, `sizeof` expressions and enumeration constants cannot be evaluated in preprocessor directives.
- Every `#if` construct ends with `#endif`.
- Directives `#ifdef` and `#ifndef` are provided as shorthand for `#if defined(name)` and `#if !defined(name)`.
- Multiple-part conditional preprocessor constructs may be tested with directives `#elif` and `#else`.

### Section 13.6 `#error` and `#pragma` Preprocessor Directives

- The `#error` directive prints an implementation-dependent message that includes the tokens specified in the directive.
- The `#pragma` directive causes an implementation-defined action. If the pragma is not recognized by the implementation, the pragma is ignored.

### Section 13.7 `#` and `##` Operators

- The `#` operator causes a replacement text token to be converted to a string surrounded by quotes. The `#` operator must be used in a macro with arguments, because the operand of `#` must be an argument of the macro.
- The `##` operator concatenates two tokens. The `##` operator must have two operands.

### Section 13.8 Line Numbers

- The `#line` preprocessor directive causes the subsequent source code lines to be renumbered starting with the specified constant integer value.

### Section 13.9 Predefined Symbolic Constants

- Constant `__LINE__` is the line number (an integer) of the current source code line. Constant `__FILE__` is the presumed name of the file (a string). Constant `__DATE__` is the date the source file is compiled (a string). Constant `__TIME__` is the time the source file is compiled (a string). Constant `__STDC__` indicates whether the compiler supports Standard C. Each of the predefined symbolic constants begins and ends with two underscores.

### Section 13.10 Assertions

- Macro `assert`—defined in the `<assert.h>` header—tests the value of an expression. If the value of the expression is 0 (false), `assert` prints an error message and calls function `abort` to terminate program execution.

## Terminology

abort function 502  
 arguments 497  
 assert macro 502  
 <assert.h> 502  
 backslash (\) 498  
 C preprocessor 496

conditional compilation 496  
 conditional execution of preprocessor directive 496  
 debugger 499  
 #define preprocessor directive 496  
 #elif preprocessor directive 499

|                                                  |                                                 |
|--------------------------------------------------|-------------------------------------------------|
| <code>#endif</code> preprocessor directive 499   | macro identifier 497                            |
| <code>#error</code> preprocessor directive 500   | macro with an argument 497                      |
| expand a macro 497                               | <code>#pragma</code> preprocessor directive 500 |
| <code>#if</code> preprocessor directive 499      | predefined symbolic constant 501                |
| <code>#ifdef</code> preprocessor directive 499   | preprocessor directive 496                      |
| <code>#ifndef</code> preprocessor directive 499  | replacement text 497                            |
| <code>#include</code> preprocessor directive 496 | scope 499                                       |
| <code>#line</code> preprocessor directive 501    | symbolic constant 496                           |
| macro 496                                        | <code>#undef</code> preprocessor directive 499  |

## Self-Review Exercises

- 13.1** Fill in the blanks in each of the following:
- Every preprocessor directive must begin with \_\_\_\_\_.
  - The conditional compilation construct may be extended to test for multiple cases by using the \_\_\_\_\_ and the \_\_\_\_\_ directives.
  - The \_\_\_\_\_ directive creates macros and symbolic constants.
  - Only \_\_\_\_\_ characters may appear before a preprocessor directive on a line.
  - The \_\_\_\_\_ directive discards symbolic constant and macro names.
  - The \_\_\_\_\_ and \_\_\_\_\_ directives are provided as shorthand notation for `#if defined(name)` and `#if !defined(name)`.
  - \_\_\_\_\_ enables you to control the execution of preprocessor directives and the compilation of program code.
  - The \_\_\_\_\_ macro prints a message and terminates program execution if the value of the expression the macro evaluates is 0.
  - The \_\_\_\_\_ directive inserts a file in another file.
  - The \_\_\_\_\_ operator concatenates its two arguments.
  - The \_\_\_\_\_ operator converts its operand to a string.
  - The character \_\_\_\_\_ indicates that the replacement text for a symbolic constant or macro continues on the next line.
  - The \_\_\_\_\_ directive causes the source code lines to be numbered from the indicated value beginning with the next source code line.

**13.2** Write a program to print the values of the predefined symbolic constants listed in Fig. 13.1.

- 13.3** Write a preprocessor directive to accomplish each of the following:
- Define symbolic constant YES to have the value 1.
  - Define symbolic constant NO to have the value 0.
  - Include the header `common.h`. The header is found in the same directory as the file being compiled.
  - Renumber the remaining lines in the file beginning with line number 3000.
  - If symbolic constant TRUE is defined, undefine it and redefine it as 1. Do not use `#ifdef`.
  - If symbolic constant TRUE is defined, undefine it and redefine it as 1. Use the `#ifdef` preprocessor directive.
  - If symbolic constant TRUE is not equal to 0, define symbolic constant FALSE as 0. Otherwise define FALSE as 1.
  - Define macro CUBE\_VOLUME that computes the volume of a cube. The macro takes one argument.

## Answers to Self-Review Exercises

- 13.1** a) `#`. b) `#elif`, `#else`. c) `#define`. d) white-space. e) `#undef`. f) `#ifdef`, `#ifndef`. g) Conditional compilation. h) `assert`. i) `#include`. j) `##`. k) `#`. l) `\`. m) `#line`.

## 13.2 See below.

```

1 /* Print the values of the predefined macros */
2 #include <stdio.h>
3 int main(void)
4 {
5 printf("__LINE__ = %d\n", __LINE__);
6 printf("__FILE__ = %s\n", __FILE__);
7 printf("__DATE__ = %s\n", __DATE__);
8 printf("__TIME__ = %s\n", __TIME__);
9 printf("__STDC__ = %s\n", __STDC__);
10 return 0;
11 }

```

```

__LINE__ = 5
__FILE__ = macros.c
__DATE__ = Jun 5 2003
__TIME__ = 09:38:58
__STDC__ = 1

```

- 13.3
- a) `#define YES 1`
  - b) `#define NO 0`
  - c) `#include "common.h"`
  - d) `#line 3000`
  - e) `#if defined( TRUE )`  
`#undef TRUE`  
`#define TRUE 1`  
`#endif`
  - f) `#ifdef TRUE`  
`#undef TRUE`  
`#define TRUE 1`  
`#endif`
  - g) `#if TRUE`  
`#define FALSE 0`  
`#else`  
`#define FALSE 1`  
`#endif`
  - h) `#define CUBE_VOLUME( x ) ( ( x ) * ( x ) * ( x ) )`

## Exercises

13.4 (*Volume of a Sphere*) Write a program that defines a macro with one argument to compute the volume of a sphere. The program should compute the volume for spheres of radius 1 to 10 and print the results in tabular format. The formula for the volume of a sphere is

$$\left( 4.0 / 3 \right) * \pi * r^3$$

where  $\pi$  is 3.14159.

13.5 (*Adding Two Numbers*) Write a program that produces the following output:

```
The sum of x and y is 13
```

The program should define macro SUM with two arguments, x and y, and use SUM to produce the output.

**13.6** (*Smallest of Two Numbers*) Write a program that defines and uses macro `MINIMUM2` to determine the smallest of two numeric values. Input the values from the keyboard.

**13.7** (*Smallest of Three Numbers*) Write a program that defines and uses macro `MINIMUM3` to determine the smallest of three numeric values. Macro `MINIMUM3` should use macro `MINIMUM2` defined in Exercise 13.6 to determine the smallest number. Input the values from the keyboard.

**13.8** (*Printing a String*) Write a program that defines and uses macro `PRINT` to print a string value.

**13.9** (*Printing an Array*) Write a program that defines and uses macro `PRINTARRAY` to print an array of integers. The macro should receive the array and the number of elements in the array as arguments.

**13.10** (*Totaling an Array's Contents*) Write a program that defines and uses macro `SUMARRAY` to sum the values in a numeric array. The macro should receive the array and the number of elements in the array as arguments.



*We'll use a signal I have tried  
and found far-reaching and  
easy to yell. Waa-hoo!*

—Zane Grey

*It is quite a three-pipe problem.*

—Sir Arthur Conan Doyle

### Objectives

In this chapter, you'll learn:

- To redirect keyboard input to come from a file.
- To redirect screen output to be placed in a file.
- To write functions that use variable-length argument lists.
- To process command-line arguments.
- To assign specific types to numeric constants.
- To use temporary files.
- To process external asynchronous events in a program.
- To allocate memory dynamically for arrays.
- To change the size of memory that was dynamically allocated previously.

|                                                                                |                                                                                                |
|--------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------|
| <b>14.1</b> Introduction                                                       | <b>14.7</b> <code>volatile</code> Type Qualifier                                               |
| <b>14.2</b> Redirecting I/O                                                    | <b>14.8</b> Suffixes for Integer and Floating-Point Constants                                  |
| <b>14.3</b> Variable-Length Argument Lists                                     | <b>14.9</b> More on Files                                                                      |
| <b>14.4</b> Using Command-Line Arguments                                       | <b>14.10</b> Signal Handling                                                                   |
| <b>14.5</b> Notes on Compiling Multiple-Source-File Programs                   | <b>14.11</b> Dynamic Memory Allocation: Functions <code>calloc</code> and <code>realloc</code> |
| <b>14.6</b> Program Termination with <code>exit</code> and <code>atexit</code> | <b>14.12</b> Unconditional Branching with <code>goto</code>                                    |

Summary | Terminology | Self-Review Exercise | Answers to Self-Review Exercise | Exercises

## 14.1 Introduction

This chapter presents several additional topics not ordinarily covered in introductory courses. Many of the capabilities discussed here are specific to particular operating systems, especially Linux/UNIX and Windows.

## 14.2 Redirecting I/O

Normally the input to a program is from the keyboard (standard input), and the output from a program is displayed on the screen (standard output). On most computer systems—Linux/UNIX and Windows systems in particular—it’s possible to **redirect** inputs to come from a file rather than the keyboard and redirect outputs to be placed in a file rather than on the screen. Both forms of redirection can be accomplished without using the file-processing capabilities of the standard library.

There are several ways to redirect input and output from the command line. Consider the executable file `sum` (on Linux/UNIX systems) that inputs integers one at a time and keeps a running total of the values until the end-of-file indicator is set, then prints the result. Normally the user inputs integers from the keyboard and enters the end-of-file key combination to indicate that no further values will be input. With input redirection, the input can be stored in a file. For example, if the data is stored in file `input`, the command line

```
$ sum < input
```

executes the program `sum`; the **redirect input symbol** (`<`) indicates that the data in file `input` is to be used as input by the program. Redirecting input on a Windows system is performed identically.

The character `$` is a typical Linux/UNIX command line prompt (some systems use a `%` prompt or other symbol). Students often find it difficult to understand that redirection is an operating system function, not another C feature.

The second method of redirecting input is **piping**. A **pipe** (`|`) causes the output of one program to be redirected as the input to another program. Suppose program `random` outputs a series of random integers; the output of `random` can be “piped” directly to program `sum` using the command line

```
$ random | sum
```



This causes the sum of the integers produced by `random` to be calculated. Piping is performed identically in Linux/UNIX and Windows.

Program output can be redirected to a file by using the **redirect output symbol** (`>`). For example, to redirect the output of program `random` to file `out`, use

```
$ random > out
```

Finally, program output can be appended to the end of an existing file by using the **append output symbol** (`>>`). For example, to append the output from program `random` to file `out` created in the preceding command line, use the command line

```
$ random >> out
```

## 14.3 Variable-Length Argument Lists

It's possible to create functions that receive an unspecified number of arguments. Most programs in the text have used the standard library function `printf` which, as you know, takes a variable number of arguments. As a minimum, `printf` must receive a string as its first argument, but `printf` can receive any number of additional arguments. The function prototype for `printf` is

```
int printf(const char *format, ...);
```

The **ellipsis** (`...`) in the function prototype indicates that the function receives a variable number of arguments of any type. The ellipsis must always be placed at the end of the parameter list.

The macros and definitions of the **variable arguments headers** `<stdarg.h>` (Fig. 14.1) provide the capabilities necessary to build functions with **variable-length argument lists**. Figure 14.2 demonstrates function `average` (lines 26–41) that receives a variable number of arguments. The first argument of `average` is always the number of values to be averaged.

| Identifier            | Explanation                                                                                                                                                                                                                                                                      |
|-----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>va_list</code>  | A type suitable for holding information needed by macros <code>va_start</code> , <code>va_arg</code> and <code>va_end</code> . To access the arguments in a variable-length argument list, an object of type <code>va_list</code> must be defined.                               |
| <code>va_start</code> | A macro that is invoked before the arguments of a variable-length argument list can be accessed. The macro initializes the object declared with <code>va_list</code> for use by the <code>va_arg</code> and <code>va_end</code> macros.                                          |
| <code>va_arg</code>   | A macro that expands to an expression of the value and type of the next argument in the variable-length argument list. Each invocation of <code>va_arg</code> modifies the object declared with <code>va_list</code> so that the object points to the next argument in the list. |
| <code>va_end</code>   | A macro that facilitates a normal return from a function whose variable-length argument list was referred to by the <code>va_start</code> macro.                                                                                                                                 |

**Fig. 14.1** | `stdarg.h` variable-length argument list type and macros.



```

1 /* Fig. 14.2: fig14_02.c
2 Using variable-length argument lists */
3 #include <stdio.h>
4 #include <stdarg.h>
5
6 double average(int i, ...); /* prototype */
7
8 int main(void)
9 {
10 double w = 37.5;
11 double x = 22.5;
12 double y = 1.7;
13 double z = 10.2;
14
15 printf("%s%.1f\n%s%.1f\n%s%.1f\n%s%.1f\n\n",
16 "w = ", w, "x = ", x, "y = ", y, "z = ", z);
17 printf("%s%.3f\n%s%.3f\n%s%.3f\n",
18 "The average of w and x is ", average(2, w, x),
19 "The average of w, x, and y is ", average(3, w, x, y),
20 "The average of w, x, y, and z is ",
21 average(4, w, x, y, z));
22 return 0; /* indicates successful termination */
23 } /* end main */
24
25 /* calculate average */
26 double average(int i, ...)
27 {
28 double total = 0; /* initialize total */
29 int j; /* counter for selecting arguments */
30 va_list ap; /* stores information needed by va_start and va_end */
31
32 va_start(ap, i); /* initializes the va_list object */
33
34 /* process variable length argument list */
35 for (j = 1; j <= i; j++) {
36 total += va_arg(ap, double);
37 } /* end for */
38
39 va_end(ap); /* clean up variable-length argument list */
40 return total / i; /* calculate average */
41 } /* end function average */

```

```

w = 37.5
x = 22.5
y = 1.7
z = 10.2

```

```

The average of w and x is 30.000
The average of w, x, and y is 20.567
The average of w, x, y, and z is 17.975

```

**Fig. 14.2** | Using variable-length argument lists.

Function `average` (lines 26–41) uses all the definitions and macros of header `<stdarg.h>`. Object `ap`, of type `va_list` (line 30), is used by macros `va_start`, `va_arg` and `va_end` to process the variable-length argument list of function `average`. The function begins by invoking macro `va_start` (line 32) to initialize object `ap` for use in `va_arg` and `va_end`. The macro receives two arguments—object `ap` and the identifier of the rightmost argument in the argument list before the ellipsis—`i` in this case (`va_start` uses `i` here to determine where the variable-length argument list begins). Next function `average` repeatedly adds the arguments in the variable-length argument list to variable `total` (lines 37–39). The value to be added to `total` is retrieved from the argument list by invoking macro `va_arg`. Macro `va_arg` receives two arguments—object `ap` and the type of the value expected in the argument list—`double` in this case. The macro returns the value of the argument. Function `average` invokes macro `va_end` (line 39) with object `ap` as an argument to facilitate a normal return to `main` from `average`. Finally, the average is calculated and returned to `main`.



#### Common Programming Error 14.1

*Placing an ellipsis in the middle of a function parameter list is a syntax error. An ellipsis may only be placed at the end of the parameter list.*

The reader may question how function `printf` and function `scanf` know what type to use in each `va_arg` macro. The answer is that `printf` and `scanf` scan the format conversion specifiers in the format control string to determine the type of the next argument to be processed.

## 14.4 Using Command-Line Arguments

On many systems, it's possible to pass arguments to `main` from a command line by including parameters `int argc` and `char *argv[]` in the parameter list of `main`. Parameter `argc` receives the number of command-line arguments. Parameter `argv` is an array of strings in which the actual command-line arguments are stored. Common uses of command-line arguments include passing options to a program and passing filenames to a program.

Figure 14.3 copies a file into another file one character at a time. We assume that the executable file for the program is called `mycopy`. A typical command line for the `mycopy` program on a Linux/UNIX system is

```
$ mycopy input output
```

This command line indicates that file `input` is to be copied to file `output`. When the program is executed, if `argc` is not 3 (`mycopy` counts as one of the arguments), the program prints an error message and terminates. Otherwise, array `argv` contains the strings `"mycopy"`, `"input"` and `"output"`. The second and third arguments on the command line are used as file names by the program. The files are opened using function `fopen`. If both files are opened successfully, characters are read from file `input` and written to file `output` until the end-of-file indicator for file `input` is set. Then the program terminates. The result is an exact copy of file `input`. See the manuals for your system for more information on command-line arguments. [Note: In Visual C++, you can specify the command-line arguments by going to **Project Properties > Configuration Properties > Debugging** and entering the arguments in the textbox to the right of **Command Arguments**.]

---

```

1 /* Fig. 14.3: fig14_03.c
2 Using command-line arguments */
3 #include <stdio.h>
4
5 int main(int argc, char *argv[])
6 {
7 FILE *inFilePtr; /* input file pointer */
8 FILE *outFilePtr; /* output file pointer */
9 int c; /* define c to hold characters input by user */
10
11 /* check number of command-line arguments */
12 if (argc != 3) {
13 printf("Usage: mycopy infile outfile\n");
14 } /* end if */
15 else {
16 /* if input file can be opened */
17 if ((inFilePtr = fopen(argv[1], "r")) != NULL) {
18 /* if output file can be opened */
19 if ((outFilePtr = fopen(argv[2], "w")) != NULL) {
20 /* read and output characters */
21 while ((c = fgetc(inFilePtr)) != EOF) {
22 fputc(c, outFilePtr);
23 } /* end while */
24 } /* end if */
25 else { /* output file could not be opened */
26 printf("File \"%s\" could not be opened\n", argv[2]);
27 } /* end else */
28 } /* end if */
29 else { /* input file could not be opened */
30 printf("File \"%s\" could not be opened\n", argv[1]);
31 } /* end else */
32 } /* end else */
33
34 return 0; /* indicates successful termination */
35 } /* end main */

```

---

**Fig. 14.3** | Using command-line arguments.

## 14.5 Notes on Compiling Multiple-Source-File Programs

It's possible to build programs that consist of multiple source files. There are several considerations when creating programs in multiple files. For example, the definition of a function must be entirely contained in one file—it cannot span two or more files.

In Chapter 5, we introduced the concepts of storage class and scope. We learned that variables declared outside any function definition are of storage class **static** by default and are referred to as global variables. Global variables are accessible to any function defined in the same file after the variable is declared. Global variables also are accessible to functions in other files. However, the global variables must be declared in each file in which they are used. For example, if we define global integer variable `flag` in one file and refer to it in a second file, the second file must contain the declaration

```
extern int flag;
```

prior to the variable's use in that file. This declaration uses the storage class specifier **extern** to indicate that variable `flag` is defined either later in the same file or in a different file. The compiler informs the linker that unresolved references to variable `flag` appear in the file (the compiler does not know where `flag` is defined, so it lets the linker attempt to find `flag`). If the linker cannot locate a definition of `flag`, the linker issues an error message and does not produce an executable file. If the linker finds a proper global definition, the linker resolves the references by indicating where `flag` is located.



#### Software Engineering Observation 14.1

*Global variables should be avoided unless application performance is critical because they violate the principle of least privilege.*

Just as **extern** declarations can be used to declare global variables to other program files, function prototypes can extend the scope of a function beyond the file in which it's defined (the **extern** specifier is not required in a function prototype). Simply include the function prototype in each file in which the function is invoked and compile the files together (see Section 13.2). Function prototypes indicate to the compiler that the specified function is defined either later in the same file or in a different file. Again, the compiler does not attempt to resolve references to such a function—that task is left to the linker. If the linker cannot locate a proper function definition, the linker issues an error message.

As an example of using function prototypes to extend the scope of a function, consider any program containing the preprocessor directive `#include <stdio.h>`, which includes in a file the function prototypes for functions such as `printf` and `scanf`. Other functions in the file can use `printf` and `scanf` to accomplish their tasks. The `printf` and `scanf` functions are defined in other files. We do not need to know where they are defined. We're simply reusing the code in our programs. The linker resolves our references to these functions automatically. This process enables us to use the functions in the standard library.



#### Software Engineering Observation 14.2

*Creating programs in multiple source files facilitates software reusability and good software engineering. Functions may be common to many applications. In such instances, those functions should be stored in their own source files, and each source file should have a corresponding header file containing function prototypes. This enables programmers of different applications to reuse the same code by including the proper header file and compiling their applications with the corresponding source file.*

It's possible to restrict the scope of a global variable or function to the file in which it's defined. The storage class specifier **static**, when applied to a global variable or a function, prevents it from being used by any function that is not defined in the same file. This is referred to as **internal linkage**. Global variables and functions that are not preceded by **static** in their definitions have **external linkage**—they can be accessed in other files if those files contain proper declarations and/or function prototypes.

The global variable declaration

```
static const double PI = 3.14159;
```

creates constant variable `PI` of type `double`, initializes it to 3.14159 and indicates that `PI` is known only to functions in the file in which it's defined.

The `static` specifier is commonly used with utility functions that are called only by functions in a particular file. If a function is not required outside a particular file, the principle of least privilege should be enforced by using `static`. If a function is defined before it's used in a file, `static` should be applied to the function definition. Otherwise, `static` should be applied to the function prototype.

When building large programs in multiple source files, compiling the program becomes tedious if small changes are made to one file and the entire program must be recompiled. Many systems provide special utilities that recompile only the modified program file. On Linux/UNIX systems the utility is called `make`. Utility `make` reads a file called `makefile` that contains instructions for compiling and linking the program. Products such as Eclipse™ and Microsoft® Visual C++® provide similar utilities as well. For more information on `make` utilities, see the manual for your development tool.

## 14.6 Program Termination with `exit` and `atexit`

The general utilities library (`<stdlib.h>`) provides methods of terminating program execution by means other than a conventional return from function `main`. Function `exit` forces a program to terminate as if it executed normally. The function often is used to terminate a program when an input error is detected, or if a file to be processed by the program cannot be opened. Function `atexit` registers a function that should be called upon successful termination of the program—i.e., either when the program terminates by reaching the end of `main`, or when `exit` is invoked.

Function `atexit` takes as an argument a pointer to a function (i.e., the function name). Functions called at program termination cannot have arguments and cannot return a value. Up to 32 functions may be registered for execution at program termination.

Function `exit` takes one argument. The argument is normally the symbolic constant `EXIT_SUCCESS` or the symbolic constant `EXIT_FAILURE`. If `exit` is called with `EXIT_SUCCESS`, the implementation-defined value for successful termination is returned to the calling environment. If `exit` is called with `EXIT_FAILURE`, the implementation-defined value for unsuccessful termination is returned. When function `exit` is invoked, any functions previously registered with `atexit` are invoked in the reverse order of their registration, all streams associated with the program are flushed and closed, and control returns to the host environment.

Figure 14.4 tests functions `exit` and `atexit`. The program prompts the user to determine whether the program should be terminated with `exit` or by reaching the end of `main`. Function `print` is executed at program termination in each case.

---

```

1 /* Fig. 14.4: fig14_04.c
2 Using the exit and atexit functions */
3 #include <stdio.h>
4 #include <stdlib.h>
5
6 void print(void); /* prototype */
7
```

---

**Fig. 14.4** | `exit` and `atexit` functions. (Part I of 2.)

```

8 int main(void)
9 {
10 int answer; /* user's menu choice */
11
12 atexit(print); /* register function print */
13 printf("Enter 1 to terminate program with function exit"
14 "\nEnter 2 to terminate program normally\n");
15 scanf("%d", &answer);
16
17 /* call exit if answer is 1 */
18 if (answer == 1) {
19 printf("\nTerminating program with function exit\n");
20 exit(EXIT_SUCCESS);
21 } /* end if */
22
23 printf("\nTerminating program by reaching the end of main\n");
24 return 0; /* indicates successful termination */
25 } /* end main */
26
27 /* display message before termination */
28 void print(void)
29 {
30 printf("Executing function print at program "
31 "termination\nProgram terminated\n");
32 } /* end function print */

```

```

Enter 1 to terminate program with function exit
Enter 2 to terminate program normally
1

```

```

Terminating program with function exit
Executing function print at program termination
Program terminated

```

```

Enter 1 to terminate program with function exit
Enter 2 to terminate program normally
2

```

```

Terminating program by reaching the end of main
Executing function print at program termination
Program terminated

```

**Fig. 14.4** | `exit` and `atexit` functions. (Part 2 of 2.)

## 14.7 volatile Type Qualifier

In Chapters 6–7, we introduced the `const` type qualifier. C also provides the `volatile` type qualifier to suppress various kinds of optimizations. The C standard indicates that when `volatile` is used to qualify a type, the nature of the access to an object of that type is implementation dependent. This usually implies that the variable may be changed by another program or by the computer's hardware.

## 14.8 Suffixes for Integer and Floating-Point Constants

C provides integer and floating-point suffixes for specifying the types of integer and floating-point constants. The integer suffixes are: `u` or `U` for an **unsigned integer**, `l` or `L` for a **long integer**, and `ul`, `lu`, `UL` or `LU` for an unsigned long integer. The following constants are of type `unsigned`, `long` and `unsigned long`, respectively:

```
174u
8358L
28373ul
```

If an integer constant is not suffixed, its type is determined by the first type capable of storing a value of that size (first `int`, then **long int**, then **unsigned long int**).

The floating-point suffixes are: `f` or `F` for a **float**, and `l` or `L` for a **long double**. The following constants are of type **float** and **long double**, respectively:

```
1.28f
3.14159L
```

A floating-point constant that is not suffixed is automatically of type `double`.

## 14.9 More on Files

Chapter 11 introduced capabilities for processing text files with sequential access and random access. C also provides capabilities for processing binary files, but some computer systems do not support binary files. If binary files are not supported and a file is opened in a binary file mode (Fig. 14.5), the file will be processed as a text file. Binary files should be used instead of text files only in situations where rigid speed, storage and/or compatibility conditions demand binary files. Otherwise, text files are always preferred for their inherent portability and for the ability to use other standard tools to examine and manipulate the file data.

| Mode             | Description                                                                                  |
|------------------|----------------------------------------------------------------------------------------------|
| <code>rb</code>  | Open an existing binary file for reading.                                                    |
| <code>wb</code>  | Create a binary file for writing. If the file already exists, discard the current contents.  |
| <code>ab</code>  | Append; open or create a binary file for writing at end-of-file.                             |
| <code>rb+</code> | Open an existing binary file for update (reading and writing).                               |
| <code>wb+</code> | Create a binary file for update. If the file already exists, discard the current contents.   |
| <code>ab+</code> | Append; open or create a binary file for update; all writing is done at the end of the file. |

**Fig. 14.5** | Binary file open modes.



### Performance Tip 14.1

*Use binary files instead of text files in applications that demand high performance.*



### Portability Tip 14.1

*Use text files when writing portable programs.*

The standard library also provides function `tmpfile` that opens a **temporary file** in mode "wb+". Although this is a binary file mode, some systems process temporary files as text files. A temporary file exists until it's closed with `fclose`, or until the program terminates. Microsoft has deprecated this function "for security reasons."

Figure 14.6 changes the tabs in a file to spaces. The program prompts the user to enter the name of a file to be modified. If the file entered by the user and the temporary file are opened successfully, the program reads characters from the file to be modified and writes them to the temporary file. If the character read is a tab ('\t'), it's replaced by a space and written to the temporary file. When the end of the file being modified is reached, the file pointers for each file are repositioned to the start of each file with `rewind`. Next, the temporary file is copied into the original file one character at a time. The program prints the original file as it copies characters into the temporary file and prints the new file as it copies characters from the temporary file to the original file to confirm the characters being written.

---

```

1 /* Fig. 14.6: fig14_06.c
2 Using temporary files */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 FILE *filePtr; /* pointer to file being modified */
8 FILE *tempFilePtr; /* temporary file pointer */
9 int c; /* define c to hold characters read from a file */
10 char fileName[30]; /* create char array */
11
12 printf("This program changes tabs to spaces.\n"
13 "Enter a file to be modified: ");
14 scanf("%29s", fileName);
15
16 /* fopen opens the file */
17 if ((filePtr = fopen(fileName, "r+")) != NULL) {
18 /* create temporary file */
19 if ((tempFilePtr = tmpfile()) != NULL) {
20 printf("\nThe file before modification is:\n");
21
22 /* read characters from file and place in temporary file */
23 while ((c = getc(filePtr)) != EOF) {
24 putchar(c);
25 putc(c == '\t' ? ' ': c, tempFilePtr);
26 } /* end while */
27
28 rewind(tempFilePtr);
29 rewind(filePtr);
30 printf("\n\nThe file after modification is:\n");
31
32 /* read from temporary file and write into original file */
33 while ((c = getc(tempFilePtr)) != EOF) {
34 putchar(c);
35 putc(c, filePtr);
36 } /* end while */
37 } /* end if */

```

---

**Fig. 14.6** | Temporary files. (Part I of 2.)



```
38 else { /* if temporary file could not be opened */
39 printf("Unable to open temporary file\n");
40 } /* end else */
41 } /* end if */
42 else { /* if file could not be opened */
43 printf("Unable to open %s\n", fileName);
44 } /* end else */
45
46 return 0; /* indicates successful termination */
47 } /* end main */
```

This program changes tabs to spaces.  
Enter a file to be modified: data.txt

The file before modification is:

|   |   |   |   |   |   |
|---|---|---|---|---|---|
| 0 | 1 | 2 | 3 | 4 |   |
|   | 5 | 6 | 7 | 8 | 9 |

The file after modification is:

|   |   |   |   |   |   |
|---|---|---|---|---|---|
| 0 | 1 | 2 | 3 | 4 |   |
|   | 5 | 6 | 7 | 8 | 9 |

Fig. 14.6 | Temporary files. (Part 2 of 2.)

### 14.10 Signal Handling

An external asynchronous **event**, or **signal**, can cause a program to terminate prematurely. Some events include **interrupts** (typing `<Ctrl> c` on a Linux/UNIX or Windows system), **illegal instructions**, **segmentation violations**, termination orders from the operating system and **floating-point exceptions** (division by zero or multiplying large floating-point values). The **signal handling library** (`<signal.h>`) provides the capability to **trap** unexpected events with function **signal**. Function `signal` receives two arguments—an integer signal number and a pointer to the signal handling function. Signals can be generated by function **raise** which takes an integer signal number as an argument. Figure 14.7 summarizes the standard signals defined in header file `<signal.h>`.

| Signal  | Explanation                                                                                        |
|---------|----------------------------------------------------------------------------------------------------|
| SIGABRT | Abnormal termination of the program (such as a call to function <code>abort</code> ).              |
| SIGFPE  | An erroneous arithmetic operation, such as a divide by zero or an operation resulting in overflow. |
| SIGILL  | Detection of an illegal instruction.                                                               |
| SIGINT  | Receipt of an interactive attention signal.                                                        |
| SIGSEGV | An invalid access to storage.                                                                      |
| SIGTERM | A termination request set to the program.                                                          |

Fig. 14.7 | `signal.h` standard signals.

Figure 14.8 uses function `signal` to trap an interactive signal (`SIGINT`). Line 15 calls `signal` with `SIGINT` and a pointer to function `signalHandler` (remember that the name of a function is a pointer to the beginning of the function). When a signal of type `SIGINT` occurs, control passes to function `signalHandler`, which prints a message and gives the user the option to continue normal execution of the program. If the user wishes to continue execution, the signal handler is reinitialized by calling `signal` again and control returns to the point in the program at which the signal was detected. In this program, function `raise` (line 24) is used to simulate an interactive signal. A random number between 1 and 50 is chosen. If the number is 25, `raise` is called to generate the signal. Normally, interactive signals are initiated outside the program. For example, typing `<Ctrl> c` during program execution on a Linux/UNIX or Windows system generates an interactive signal that terminates program execution. Signal handling can be used to trap the interactive signal and prevent the program from being terminated.

---

```

1 /* Fig. 14.8: fig14_08.c
2 Using signal handling */
3 #include <stdio.h>
4 #include <signal.h>
5 #include <stdlib.h>
6 #include <time.h>
7
8 void signalHandler(int signalValue); /* prototype */
9
10 int main(void)
11 {
12 int i; /* counter used to loop 100 times */
13 int x; /* variable to hold random values between 1-50 */
14
15 signal(SIGINT, signalHandler); /* register signal handler */
16 srand(time(NULL));
17
18 /* output numbers 1 to 100 */
19 for (i = 1; i <= 100; i++) {
20 x = 1 + rand() % 50; /* generate random number to raise SIGINT */
21
22 /* raise SIGINT when x is 25 */
23 if (x == 25) {
24 raise(SIGINT);
25 } /* end if */
26
27 printf("%4d", i);
28
29 /* output \n when i is a multiple of 10 */
30 if (i % 10 == 0) {
31 printf("\n");
32 } /* end if */
33 } /* end for */
34
35 return 0; /* indicates successful termination */
36 } /* end main */

```

---

**Fig. 14.8** | Signal handling. (Part I of 2.)

```

37
38 /* handles signal */
39 void signalHandler(int signalValue)
40 {
41 int response; /* user's response to signal (1 or 2) */
42
43 printf("%s%d%s\n%s",
44 "\nInterrupt signal (", signalValue, ") received.",
45 "Do you wish to continue (1 = yes or 2 = no)? ");
46
47 scanf("%d", &response);
48
49 /* check for invalid responses */
50 while (response != 1 && response != 2) {
51 printf("(1 = yes or 2 = no)? ");
52 scanf("%d", &response);
53 } /* end while */
54
55 /* determine if it is time to exit */
56 if (response == 1) {
57 /* reregister signal handler for next SIGINT */
58 signal(SIGINT, signalHandler);
59 } /* end if */
60 else {
61 exit(EXIT_SUCCESS);
62 } /* end else */
63 } /* end function signalHandler */

```

```

1 2 3 4 5 6 7 8 9 10
11 12 13 14 15 16 17 18 19 20
21 22 23 24 25 26 27 28 29 30
31 32 33 34 35 36 37 38 39 40
41 42 43 44 45 46 47 48 49 50
51 52 53 54 55 56 57 58 59 60
61 62 63 64 65 66 67 68 69 70
71 72 73 74 75 76 77 78 79 80
81 82 83 84 85 86 87 88 89 90
91 92 93
Interrupt signal (2) received.
Do you wish to continue (1 = yes or 2 = no)? 1
94 95 96
Interrupt signal (2) received.
Do you wish to continue (1 = yes or 2 = no)? 2

```

**Fig. 14.8** | Signal handling. (Part 2 of 2.)

## 14.11 Dynamic Memory Allocation: Functions `calloc` and `realloc`

Chapter 12 introduced the notion of dynamically allocating memory using function `malloc`. As we stated in Chapter 12, arrays are better than linked lists for rapid sorting, searching and data access. However, arrays are normally **static data structures**. The general

utilities library (`stdlib.h`) provides two other functions for dynamic memory allocation—`calloc` and `realloc`. These functions can be used to create and modify **dynamic arrays**. As shown in Chapter 7, a pointer to an array can be subscripted like an array. Thus, a pointer to a contiguous portion of memory created by `calloc` can be manipulated as an array. Function `calloc` dynamically allocates memory for an array. The prototype for `calloc` is

```
void *calloc(size_t nmemb, size_t size);
```

Its two arguments represent the number of elements (`nmemb`) and the size of each element (`size`). Function `calloc` also initializes the elements of the array to zero. The function returns a pointer to the allocated memory, or a `NULL` pointer if the memory is not allocated. The primary difference between `malloc` and `calloc` is that `calloc` clears the memory it allocates and `malloc` does not.

Function `realloc` changes the size of an object allocated by a previous call to `malloc`, `calloc` or `realloc`. The original object's contents are not modified provided that the amount of memory allocated is larger than the amount allocated previously. Otherwise, the contents are unchanged up to the size of the new object. The prototype for `realloc` is

```
void *realloc(void *ptr, size_t size);
```

The two arguments are a pointer to the original object (`ptr`) and the new size of the object (`size`). If `ptr` is `NULL`, `realloc` works identically to `malloc`. If `size` is 0 and `ptr` is not `NULL`, the memory for the object is freed. Otherwise, if `ptr` is not `NULL` and `size` is greater than zero, `realloc` tries to allocate a new block of memory for the object. If the new space cannot be allocated, the object pointed to by `ptr` is unchanged. Function `realloc` returns either a pointer to the reallocated memory, or a `NULL` pointer to indicate that the memory was not reallocated.

## 14.12 Unconditional Branching with goto

Throughout the text we have stressed the importance of using structured programming techniques to build reliable software that is easy to debug, maintain and modify. In some cases, performance is more important than strict adherence to structured programming techniques. In these cases, some unstructured programming techniques may be used. For example, we can use `break` to terminate execution of a repetition structure before the loop continuation condition becomes false. This saves unnecessary repetitions of the loop if the task is completed before loop termination.

Another instance of unstructured programming is the **goto statement**—an unconditional branch. The result of the `goto` statement is a change in the flow of control of the program to the first statement after the **label** specified in the `goto` statement. A label is an identifier followed by a colon. A label must appear in the same function as the `goto` statement that refers to it. Figure 14.9 uses `goto` statements to loop ten times and print the counter value each time. After initializing `count` to 1, line 11 tests `count` to determine whether it's greater than 10 (the label `start` is skipped because labels do not perform any action). If so, control is transferred from the `goto` to the first statement after the label `end` (which appears at line 20). Otherwise, lines 15–16 print and increment `count`, and control transfers from the `goto` (line 18) to the first statement after the label `start` (which appears at line 9).

```

1 /* Fig. 14.9: fig14_09.c
2 Using goto */
3 #include <stdio.h>
4
5 int main(void)
6 {
7 int count = 1; /* initialize count */
8
9 start: /* label */
10
11 if (count > 10) {
12 goto end;
13 } /* end if */
14
15 printf("%d ", count);
16 count++;
17
18 goto start; /* goto start on line 9 */
19
20 end: /* label */
21 putchar('\n');
22
23 return 0; /* indicates successful termination */
24 } /* end main */

```

```
1 2 3 4 5 6 7 8 9 10
```

**Fig. 14.9** | goto statement.

In Chapter 3, we stated that only three control structures are required to write any program—sequence, selection and repetition. When the rules of structured programming are followed, it's possible to create deeply nested control structures from which it's difficult to efficiently escape. Some programmers use goto statements in such situations as a quick exit from a deeply nested structure. This eliminates the need to test multiple conditions to escape from a control structure.



#### Performance Tip 14.2

*The goto statement can be used to exit deeply nested control structures efficiently.*



#### Software Engineering Observation 14.3

*The goto statement should be used only in performance-oriented applications. The goto statement is unstructured and can lead to programs that are more difficult to debug, maintain and modify.*

## Summary

### Section 14.2 Redirecting I/O

- On many computer systems it's possible to redirect input to a program and output from a program.
- Input is redirected from the command line using the redirect input symbol (<) or using a pipe (|).

- Output is redirected from the command line using the redirect output symbol (>) or the append output symbol (>>). The redirect output symbol simply stores the program output in a file, and the append output symbol appends the output to the end of a file.

### *Section 14.3 Variable-Length Argument Lists*

- The macros and definitions of the variable arguments header `<stdarg.h>` provide the capabilities necessary to build functions with variable-length argument lists.
- An ellipsis (...) in a function prototype indicates a variable number of arguments.
- Type `va_list` is suitable for holding information needed by macros `va_start`, `va_arg` and `va_end`. To access the arguments in a variable-length argument list, an object of type `va_list` must be declared.
- Invoke macro `va_start` before accessing the arguments of a variable-length argument list. The macro initializes the object declared with `va_list` for use by the `va_arg` and `va_end` macros.
- Macro `va_arg` expands to an expression of the value and type of the next argument in the variable length argument list. Each invocation of `va_arg` modifies the object declared with `va_list` so that the object points to the next argument in the list.
- Macro `va_end` facilitates a normal return from a function whose variable argument list was referred to by the `va_start` macro.

### *Section 14.4 Using Command-Line Arguments*

- On many systems it's possible to pass arguments to `main` from the command line by including the parameters `int argc` and `char *argv[]` in the parameter list of `main`. Parameter `argc` receives the number of command-line arguments. Parameter `argv` is an array of strings in which the actual command-line arguments are stored.

### *Section 14.5 Notes on Compiling Multiple-Source-File Programs*

- A function definition must be entirely contained in one file—it cannot span two or more files.
- Global variables must be declared in each file in which they are used.
- Function prototypes can extend the scope of a function beyond the file in which it's defined. This is accomplished by including the function prototype in each file in which the function is invoked and compiling the files together.
- The storage class specifier `static`, when applied to a global variable or a function, prevents it from being used by any function that is not defined in the same file. This is referred to as internal linkage. Global variables and functions that are not preceded by `static` in their definitions have external linkage—they can be accessed in other files if those files contain proper declarations or function prototypes.
- The `static` specifier is commonly used with utility functions that are called only by functions in a particular file. If a function is not required outside a particular file, the principle of least privilege should be enforced by using `static`.
- When building large programs in multiple source files, compiling the program becomes tedious if small changes are made to one file and the entire program must be recompiled. Many systems provide special utilities that recompile only the modified program file. On Linux/UNIX systems the utility is called `make`. Utility `make` reads a file called `makefile` that contains instructions for compiling and linking the program.

### *Section 14.6 Program Termination with `exit` and `atexit`*

- Function `exit` forces a program to terminate as if it executed normally.
- Function `atexit` registers a function to be called upon normal termination of the program—i.e., either when the program terminates by reaching the end of `main` or when `exit` is invoked.

- Function `atexit` takes a pointer to a function as an argument. Functions called at program termination cannot have arguments and cannot return a value. Up to 32 functions may be registered for execution at program termination.
- Function `exit` takes one argument. The argument is normally the symbolic constant `EXIT_SUCCESS` or the symbolic constant `EXIT_FAILURE`. If `exit` is called with `EXIT_SUCCESS`, the implementation-defined value for successful termination is returned to the calling environment. If `exit` is called with `EXIT_FAILURE`, the implementation-defined value for unsuccessful termination is returned.
- When function `exit` is invoked, any functions registered with `atexit` are invoked in the reverse order of their registration, all streams associated with the program are flushed and closed, and control returns to the host environment.

### Section 14.7 *volatile* Type Qualifier

- The C standard indicates that when `volatile` is used to qualify a type, the nature of the access to an object of that type is implementation dependent.

### Section 14.8 Suffixes for Integer and Floating-Point Constants

- C provides integer and floating-point suffixes for specifying the types of integer and floating-point constants. The integer suffixes are: `u` or `U` for an unsigned integer, `l` or `L` for a long integer, and `ul` or `UL` for an unsigned long integer. If an integer constant is not suffixed, its type is determined by the first type capable of storing a value of that size (first `int`, then `long int`, then unsigned long `int`). The floating-point suffixes are: `f` or `F` for a `float`, and `l` or `L` for a long double. A floating-point constant that is not suffixed is of type `double`.

### Section 14.9 More on Files

- C provides capabilities for processing binary files, but some computer systems do not support binary files. If binary files are not supported and a file is opened in a binary file mode, the file will be processed as a text file.
- Function `tmpfile` opens a temporary file in mode "`wb+`". Although this is a binary file mode, some systems process temporary files as text files. A temporary file exists until it's closed with `fclose` or until the program terminates.

### Section 14.10 Signal Handling

- The signal handling library enables trapping of unexpected events with function `signal`. Function `signal` receives two arguments—an integer signal number and a pointer to the signal-handling function.
- Signals can also be generated with function `raise` and an integer argument.

### Section 14.11 Dynamic Memory Allocation: Functions `calloc` and `realloc`

- The general utilities library (`<stdlib.h>`) provides two functions for dynamic memory allocation—`calloc` and `realloc`. These functions can be used to create dynamic arrays.
- Function `calloc` receives two arguments—the number of elements (`nmemb`) and the size of each element (`size`)—and initializes the elements of the array to zero. The function returns either a pointer to the allocated memory, or a `NULL` pointer if the memory is not allocated.
- Function `realloc` changes the size of an object allocated by a previous call to `malloc`, `calloc` or `realloc`. The original object's contents are not modified provided that the amount of memory allocated is larger than the amount allocated previously.
- Function `realloc` takes two arguments—a pointer to the original object (`ptr`) and the new size of the object (`size`). If `ptr` is `NULL`, `realloc` works identically to `malloc`. If `size` is 0 and the pointer received is not `NULL`, the memory for the object is freed. Otherwise, if `ptr` is not `NULL` and `size`

is greater than zero, `realloc` tries to allocate a new block of memory for the object. If the new space cannot be allocated, the object pointed to by `ptr` is unchanged. Function `realloc` returns either a pointer to the reallocated memory, or a `NULL` pointer.

### Section 14.12 Unconditional Branching with *goto*

- The result of the `goto` statement is a change in the flow of control of the program. Program execution continues at the first statement after the label specified in the `goto` statement.
- A label is an identifier followed by a colon. A label must appear in the same function as the `goto` statement that refers to it.

## Terminology

|                                                        |                                                     |
|--------------------------------------------------------|-----------------------------------------------------|
| append output symbol <code>&gt;&gt;</code> 509         | <code>makefile</code> 514                           |
| <code>argc</code> 511                                  | pipe symbol <code>()</code> 508                     |
| <code>argv</code> 511                                  | pipng 508                                           |
| <code>atexit</code> 514                                | <code>raise</code> 518                              |
| <code>calloc</code> 521                                | redirect input from a file 508                      |
| <code>const</code> type qualifier 515                  | redirect input symbol <code>&lt;</code> 508         |
| dynamic array 521                                      | redirect output symbol <code>&gt;</code> 509        |
| ellipsis (...) in a function prototype 509             | segmentation violation 518                          |
| <code>event</code> 518                                 | <code>signal</code> 518                             |
| <code>exit</code> function 514                         | signal handling library 518                         |
| <code>EXIT_FAILURE</code> 514                          | <code>&lt;signal.h&gt;</code> 518                   |
| <code>EXIT_SUCCESS</code> 514                          | <code>static</code> keyword 512                     |
| <code>extern</code> 513                                | static data structure 520                           |
| external linkage 513                                   | <code>&lt;stdlib.h&gt;</code> header file 521       |
| <code>f</code> or <code>F</code> for a float 516       | temporary file 517                                  |
| float 516                                              | <code>tmpfile</code> 517                            |
| floating-point exception 518                           | <code>trap</code> 518                               |
| <code>goto</code> statement 521                        | unsigned integer 516                                |
| illegal instruction 518                                | unsigned long int 516                               |
| internal linkage 513                                   | <code>va_arg</code> 511                             |
| interrupt 518                                          | <code>va_end</code> 511                             |
| <code>l</code> or <code>L</code> for a long double 516 | <code>va_list</code> 511                            |
| label 521                                              | <code>va_start</code> 511                           |
| long double 516                                        | variable arguments header <code>stdarg.h</code> 509 |
| long int 516                                           | variable-length argument list 509                   |
| long integer 516                                       | volatile type qualifier 515                         |
| <code>make</code> 514                                  |                                                     |

## Self-Review Exercise

14.1 Fill in the blanks in each of the following:

- The \_\_\_\_\_ symbol redirects input data from a file rather than the keyboard.
- The \_\_\_\_\_ symbol is used to redirect the screen output so that it's placed in a file.
- The \_\_\_\_\_ symbol is used to append the output of a program to the end of a file.
- A(n) \_\_\_\_\_ directs the output of one program to be the input of another program.
- A(n) \_\_\_\_\_ in the parameter list of a function indicates that the function can receive a variable number of arguments.
- Macro \_\_\_\_\_ must be invoked before the arguments in a variable-length argument list can be accessed.
- Macro \_\_\_\_\_ accesses the individual arguments of a variable-length argument list.



- h) Macro \_\_\_\_\_ facilitates a normal return from a function whose variable argument list was referred to by macro `va_start`.
- i) Argument \_\_\_\_\_ of `main` receives the number of arguments in a command line.
- j) Argument \_\_\_\_\_ of `main` stores command-line arguments as character strings.
- k) Linux/UNIX utility \_\_\_\_\_ reads a file called \_\_\_\_\_ that contains instructions for compiling and linking a program consisting of multiple source files.
- l) Function \_\_\_\_\_ forces a program to terminate execution.
- m) Function \_\_\_\_\_ registers a function to be called upon normal program termination.
- n) An integer or floating-point \_\_\_\_\_ can be appended to an integer or floating-point constant to specify the exact type of the constant.
- o) Function \_\_\_\_\_ opens a temporary file that exists until it's closed or program execution terminates.
- p) Function \_\_\_\_\_ can be used to trap unexpected events.
- q) Function \_\_\_\_\_ generates a signal from within a program.
- r) Function \_\_\_\_\_ dynamically allocates memory for an array and initializes the elements to zero.
- s) Function \_\_\_\_\_ changes the size of a block of previously allocated dynamic memory.

## Answers to Self-Review Exercise

**14.1** a) redirect input (<). b) redirect output (>). c) append output (>>). d) pipe (|). e) ellipsis (...). f) `va_start`. g) `va_arg`. h) `va_end`. i) `argc`. j) `argv`. k) `make`, `makefile`. l) `exit`. m) `atexit`. n) suffix. o) `tmpfile`. p) `signal`. q) `raise`. r) `calloc`. s) `realloc`.

## Exercises

**14.2** (*Variable-Length Argument List: Calculating Products*) Write a program that calculates the product of a series of integers that are passed to function `product` using a variable-length argument list. Test your function with several calls, each with a different number of arguments.

**14.3** (*Printing Command-Line Arguments*) Write a program that prints the command-line arguments of the program.

**14.4** (*Sorting Integers*) Write a program that sorts an array of integers into ascending order or descending order. Use command-line arguments to pass either argument `-a` for ascending order or `-d` for descending order. [Note: This is the standard format for passing options to a program in UNIX.]

**14.5** (*Temporary Files*) Write a program that places a space between each character in a file. The program should first write the contents of the file being modified into a temporary file with spaces between each character, then copy the file back to the original file. This operation should overwrite the original contents of the file.

**14.6** (*Signal Handling*) Read the manuals for your compiler to determine what signals are supported by the signal handling library (`<signal.h>`). Write a program that contains signal handlers for the standard signals `SIGABRT` and `SIGINT`. The program should test the trapping of these signals by calling function `abort` to generate a signal of type `SIGABRT` and by typing `<Ctrl> c` to generate a signal of type `SIGINT`.

**14.7** (*Dynamic Array Allocation*) Write a program that dynamically allocates an array of integers. The size of the array should be input from the keyboard. The elements of the array should be assigned values input from the keyboard. Print the values of the array. Next, reallocate the memory for the array to 1/2 of the current number of elements. Print the values remaining in the array to confirm that they match the first half of the values in the original array.

**14.8** (*Command-Line Arguments*) Write a program that takes two command-line arguments that are file names, reads the characters from the first file one at a time and writes the characters in reverse order to the second file.

**14.9** (*goto Statement*) Write a program that uses `goto` statements to simulate a nested looping structure that prints a square of asterisks as follows:

```

* *
* *
* *
* *

```

The program should use only the following three `printf` statements:

```
printf("%s");
printf(" ");
printf("\n");
```

# 15

## C++ as a Better C; Introducing Object Technology

*A wise skepticism is the first  
attribute of a good critic.*

—James Russell Lowell

*... no science of behavior can  
change the essential nature of  
man ...*

—Burrhus Frederic Skinner

*Nothing can have value without  
being an object of utility.*

—Karl Marx

*Knowledge is the conformity of  
the object and the intellect.*

—Averroës

*Many things,  
having full reference  
To one consent,  
may work contrariously ...*

—William Shakespeare

### Objectives

In this chapter you'll learn:

- C++ enhancements to C.
- The header files of the C++ Standard Library.
- To use `inline` functions.
- To use references.
- To use default arguments.
- To use the unary scope resolution operator to access a global variable.
- To overload functions.
- To create and use function templates that perform identical operations different types.



|                                                   |                                                            |
|---------------------------------------------------|------------------------------------------------------------|
| <b>15.1</b> Introduction                          | <b>15.8</b> Empty Parameter Lists                          |
| <b>15.2</b> C++                                   | <b>15.9</b> Default Arguments                              |
| <b>15.3</b> A Simple Program: Adding Two Integers | <b>15.10</b> Unary Scope Resolution Operator               |
| <b>15.4</b> C++ Standard Library                  | <b>15.11</b> Function Overloading                          |
| <b>15.5</b> Header Files                          | <b>15.12</b> Function Templates                            |
| <b>15.6</b> Inline Functions                      | <b>15.13</b> Introduction to Object Technology and the UML |
| <b>15.7</b> References and Reference Parameters   | <b>15.14</b> Wrap-Up                                       |

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises*

## 15.1 Introduction

We now begin the second section of this unique text. The first 14 chapters presented a thorough treatment of procedural programming and top-down program design with C. The C++ section (Chapters 15–24) introduces two additional programming paradigms—**object-oriented programming** (with classes, encapsulation, objects, operator overloading, inheritance and polymorphism) and **generic programming** (with function templates and class templates). These chapters emphasize “crafting valuable classes” to create reusable software componentry.

## 15.2 C++

C++ improves on many of C’s features and provides object-oriented-programming (OOP) capabilities that increase software productivity, quality and reusability. This chapter discusses many of C++’s enhancements to C.

C’s designers and early implementers never anticipated that the language would become such a phenomenon. When a programming language becomes as entrenched as C, new requirements demand that the language evolve rather than simply be displaced by a new language. C++ was developed by Bjarne Stroustrup at Bell Laboratories and was originally called “C with classes.” The name C++ includes C’s increment operator (++) to indicate that C++ is an enhanced version of C.

Chapters 15–24 provide an introduction to the version of C++ standardized in the United States through the American National Standards Institute (ANSI) and worldwide through the International Standards Organization (ISO). We have done a careful walk-through of the ANSI/ISO C++ standard document and audited our presentation against it for completeness and accuracy. However, C++ is a rich language, and there are some subtleties in the language and some advanced subjects that we have not covered. If you need additional technical details on C++, we suggest that you read the C++ standard document, which you can purchase from the ANSI website

[webstore ansi.org/ansidocstore/product.asp?  
sku=INCITS%2FISO%2FIEC+14882%2D2003](http://webstore ansi.org/ansidocstore/product.asp?sku=INCITS%2FISO%2FIEC+14882%2D2003)

The title of the document is “Programming languages—C++” and its document number is INCITS/ISO/IEC 14882-2003.

## 15.3 A Simple Program: Adding Two Integers

This section revisits the addition program of Fig. 2.8 and illustrates several important features of the C++ language as well as some differences between C and C++. C file names have the .c (lowercase) extension. C++ file names can have one of several extensions, such as .cpp, .cxx or .C (uppercase). We use the extension .cpp.

Figure 15.1 uses C++-style input and output to obtain two integers typed by a user at the keyboard, computes the sum of these values and outputs the result. Lines 1 and 2 each begin with //, indicating that the remainder of each line is a comment. C++ allows you to begin a comment with // and use the remainder of the line as comment text. A // comment is a maximum of one line long. C++ programmers may also use /\*...\*/ C-style comments, which can be more than one line long.

---

```

1 // Fig. 15.1: fig15_01.cpp
2 // Addition program that displays the sum of two numbers.
3 #include <iostream> // allows program to perform input and output
4
5 int main()
6 {
7 int number1; // first integer to add
8
9 std::cout << "Enter first integer: "; // prompt user for data
10 std::cin >> number1; // read first integer from user into number1
11
12 int number2; // second integer to add
13 int sum; // sum of number1 and number2
14
15 std::cout << "Enter second integer: "; // prompt user for data
16 std::cin >> number2; // read second integer from user into number2
17 sum = number1 + number2; // add the numbers; store result in sum
18 std::cout << "Sum is " << sum << std::endl; // display sum; end line
19 } // end function main

```

```

Enter first integer: 45
Enter second integer: 72
Sum is 117

```

**Fig. 15.1** | Addition program that displays the sum of two numbers.

The C++ preprocessor directive in line 3 exhibits the standard C++ style for including header files from the standard library. This line tells the C++ preprocessor to include the contents of the **input/output stream header** file `<iostream>`. This file must be included for any program that outputs data to the screen or inputs data from the keyboard using C++-style stream input/output. We discuss `iostream`'s many features in detail in Chapter 23, Stream Input/Output.

As in C, every C++ program begins execution with function `main` (line 5). Keyword `int` to the left of `main` indicates that `main` returns an integer value. C++ requires you to specify the return type, possibly `void`, for all functions. In C++, specifying a parameter list with empty parentheses is equivalent to specifying a `void` parameter list in C. In C, using empty parentheses in a function definition or prototype is dangerous. It disables compile-

time argument checking in function calls, which allows the caller to pass any arguments to the function. This could lead to runtime errors.



### Common Programming Error 15.1

*Omitting the return type in a C++ function definition is a syntax error.*

Line 7 is a familiar variable declaration. Declarations can be placed almost anywhere in a C++ program, but they must appear before their corresponding variables are used in the program. For example, in Fig. 15.1, the declaration in line 7 could have been placed immediately before line 10, the declaration in line 12 could have been placed immediately before line 16 and the declaration in line 13 could have been placed immediately before line 17.



### Good Programming Practice 15.1

*Always place a blank line between a declaration and adjacent executable statements. This makes the declarations stand out in the program, enhancing program clarity.*

Line 9 uses the **standard output stream object**—`std::cout`—and the **stream insertion operator**, `<<`, to display the string "Enter first integer: ". Output and input in C++ are accomplished with streams of characters. Thus, when line 9 executes, it sends the stream of characters "Enter first integer: " to `std::cout`, which is normally "connected" to the screen. We like to pronounce the preceding statement as "`std::cout` gets the character string "Enter first integer: "."

Line 10 uses the **standard input stream object**—`std::cin`—and the **stream extraction operator**, `>>`, to obtain a value from the keyboard. Using the stream extraction operator with `std::cin` takes character input from the standard input stream, which is usually the keyboard. We like to pronounce the preceding statement as, "`std::cin` gives a value to `number1`" or simply "`std::cin` gives `number1`."

When the computer executes the statement in line 10, it waits for the user to enter a value for variable `number1`. The user responds by typing an integer (as characters), then pressing the *Enter* key. The computer converts the character representation of the number to an integer and assigns this value to the variable `number1`.

Line 15 displays "Enter second integer: " on the screen, prompting the user to take action. Line 16 obtains a value for variable `number2` from the user.

The assignment statement in line 17 calculates the sum of the variables `number1` and `number2` and assigns the result to variable `sum`. Line 18 displays the character string `Sum is` followed by the numerical value of variable `sum` followed by `std::endl`—a so-called **stream manipulator**. The name `endl` is an abbreviation for "end line." The `std::endl` stream manipulator outputs a newline, then "flushes the output buffer." This simply means that, on some systems where outputs accumulate in the machine until there are enough to "make it worthwhile" to display on the screen, `std::endl` forces any accumulated outputs to be displayed at that moment. This can be important when the outputs are prompting the user for an action, such as entering data.

We place `std::` before `cout`, `cin` and `endl`. This is required when we use standard C++ header files. The notation `std::cout` specifies that we're using a name, in this case `cout`, that belongs to "namespace" `std`. Namespaces are an advanced C++ feature that we do not discuss in these introductory C++ chapters. For now, you should simply remember to include `std::` before each mention of `cout`, `cin` and `endl` in a program. This can be



cumbersome—in Fig. 15.3, we introduce the `using` statement, which will enable us to avoid placing `std::` before each use of a namespace `std` name.

The statement in line 18 outputs values of different types. The stream insertion operator “knows” how to output each type of data. Using multiple stream insertion operators (`<<`) in a single statement is referred to as **concatenating**, **chaining** or **cascading stream insertion operations**.

Calculations can also be performed in output statements. We could have combined the statements in lines 17 and 18 into the statement

```
std::cout << "Sum is " << number1 + number2 << std::endl;
```

thus eliminating the need for the variable `sum`.

You’ll notice that we did not have a `return 0;` statement at the end of `main` in this example. According to the C++ standard, if program execution reaches the end of `main` without encountering a `return` statement, it’s assumed that the program terminated successfully—exactly as when the last statement in `main` is a `return` statement with the value 0. For that reason, we omit the `return` statement at the end of `main` in our C++ programs.

A powerful C++ feature is that users can create their own types called **classes** (we introduce this capability in Chapter 16 and explore it in depth in Chapters 17–18). Users can then “teach” C++ how to input and output values of these new data types using the `>>` and `<<` operators (this is called **operator overloading**—a topic we explore in Chapter 19).

## 15.4 C++ Standard Library

C++ programs consist of pieces called **classes** and functions. You can program each piece that you may need to form a C++ program. Instead, most C++ programmers take advantage of the rich collections of existing classes and functions in the **C++ Standard Library**. Thus, there are really two parts to learning the C++ “world.” The first is learning the C++ language itself; the second is learning how to use the classes and functions in the C++ Standard Library. Throughout the book, we discuss many of these classes and functions. P. J. Plauger’s book, *The Standard C Library* (Englewood Cliffs, NJ: Prentice Hall PTR, 1992), is a must read for programmers who need a deep understanding of the Standard C library functions that are included in C++, how to implement them and how to use them to write portable code. The standard class libraries generally are provided by compiler vendors. Many special-purpose class libraries are supplied by independent software vendors.



### Software Engineering Observation 15.1

Use a “building-block” approach to create programs. Avoid reinventing the wheel. Use existing pieces wherever possible. Called **software reuse**, this practice is central to object-oriented programming.



### Software Engineering Observation 15.2

When programming in C++, you typically will use the following building blocks: classes and functions from the C++ Standard Library, classes and functions you and your colleagues create and classes and functions from various popular third-party libraries.

The advantage of creating your own functions and classes is that you’ll know exactly how they work. You’ll be able to examine the C++ code. The disadvantage is the time-con-

suming and complex effort that goes into designing, developing and maintaining new functions and classes that are correct and that operate efficiently.



### Performance Tip 15.1

*Using C++ Standard Library functions and classes instead of writing your own versions can improve program performance, because they are written to perform efficiently. This technique also shortens program development time.*



### Portability Tip 15.1

*Using C++ Standard Library functions and classes instead of writing your own improves program portability, because they are included in every C++ implementation.*

## 15.5 Header Files

The C++ Standard Library is divided into many portions, each with its own header file. The header files contain the function prototypes for the related functions that form each portion of the library. The header files also contain definitions of various class types and functions, as well as constants needed by those functions. A header file “instructs” the compiler on how to interface with library and user-written components.

Figure 15.2 lists some common C++ Standard Library header files. Header file names ending in `.h` are “old-style” header files that have been superseded by the C++ Standard Library header files.

| C++ Standard Library header file                                                                                                                                                                                                            | Explanation                                                                                                                                                                                                                           |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>&lt;iostream&gt;</code>                                                                                                                                                                                                               | Contains function prototypes for the C++ standard input and standard output functions. This header file replaces header file <code>&lt;iostream.h&gt;</code> . This header is discussed in detail in Chapter 23, Stream Input/Output. |
| <code>&lt;iomanip&gt;</code>                                                                                                                                                                                                                | Contains function prototypes for stream manipulators that format streams of data. This header file replaces header file <code>&lt;iomanip.h&gt;</code> . This header is used in Chapter 23, Stream Input/Output.                      |
| <code>&lt;cmath&gt;</code>                                                                                                                                                                                                                  | Contains function prototypes for math library functions. This header file replaces header file <code>&lt;math.h&gt;</code> .                                                                                                          |
| <code>&lt;cstdlib&gt;</code>                                                                                                                                                                                                                | Contains function prototypes for conversions of numbers to text, text to numbers, memory allocation, random numbers and various other utility functions. This header file replaces header file <code>&lt;stdlib.h&gt;</code> .        |
| <code>&lt;ctime&gt;</code>                                                                                                                                                                                                                  | Contains function prototypes and types for manipulating the time and date. This header file replaces header file <code>&lt;time.h&gt;</code> .                                                                                        |
| <code>&lt;vector&gt;</code> , <code>&lt;list&gt;</code> ,<br><code>&lt;deque&gt;</code> , <code>&lt;queue&gt;</code> ,<br><code>&lt;stack&gt;</code> , <code>&lt;map&gt;</code> ,<br><code>&lt;set&gt;</code> , <code>&lt;bitset&gt;</code> | These header files contain classes that implement the C++ Standard Library containers. Containers store data during a program’s execution.                                                                                            |

**Fig. 15.2** | C++ Standard Library header files. (Part I of 2.)



| C++ Standard Library header file | Explanation                                                                                                                                                                                                                                                                                                                   |
|----------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <cctype>                         | Contains function prototypes for functions that test characters for certain properties (such as whether the character is a digit or a punctuation), and function prototypes for functions that can be used to convert lowercase letters to uppercase letters and vice versa. This header file replaces header file <ctype.h>. |
| <cstring>                        | Contains function prototypes for C-style string-processing functions. This header file replaces header file <string.h>.                                                                                                                                                                                                       |
| <typeinfo>                       | Contains classes for runtime type identification (determining data types at execution time).                                                                                                                                                                                                                                  |
| <exception>, <stdexcept>         | These header files contain classes that are used for exception handling (discussed in Chapter 24, Exception Handling).                                                                                                                                                                                                        |
| <memory>                         | Contains classes and functions used by the C++ Standard Library to allocate memory to the C++ Standard Library containers. This header is used in Chapter 24, Exception Handling.                                                                                                                                             |
| <fstream>                        | Contains function prototypes for functions that perform input from files on disk and output to files on disk. This header file replaces header file <fstream.h>.                                                                                                                                                              |
| <string>                         | Contains the definition of class string from the C++ Standard Library.                                                                                                                                                                                                                                                        |
| <sstream>                        | Contains function prototypes for functions that perform input from strings in memory and output to strings in memory.                                                                                                                                                                                                         |
| <functional>                     | Contains classes and functions used by C++ Standard Library algorithms.                                                                                                                                                                                                                                                       |
| <iterator>                       | Contains classes for accessing C++ Standard Library container data.                                                                                                                                                                                                                                                           |
| <algorithm>                      | Contains functions for manipulating container data.                                                                                                                                                                                                                                                                           |
| <cassert>                        | Contains macros for adding diagnostics that aid program debugging. This replaces header file <assert.h> from pre-standard C++.                                                                                                                                                                                                |
| <cfloat>                         | Contains the floating-point size limits of the system. This header file replaces header file <float.h>.                                                                                                                                                                                                                       |
| <climits>                        | Contains the integral size limits of the system. This header file replaces header file <limits.h>.                                                                                                                                                                                                                            |
| <cstdio>                         | Contains function prototypes for the C-style standard input/output library functions and information used by them. This header file replaces header file <stdio.h>.                                                                                                                                                           |
| <locale>                         | Contains classes and functions normally used by stream processing to process data in the natural form for different languages (e.g., monetary formats, sorting strings, character presentation, and so on).                                                                                                                   |
| <limits>                         | Contains classes for defining the numerical data type limits on each computer platform.                                                                                                                                                                                                                                       |
| <utility>                        | Contains classes and functions that are used by many C++ Standard Library header files.                                                                                                                                                                                                                                       |

**Fig. 15.2** | C++ Standard Library header files. (Part 2 of 2.)

You can create custom header files. Programmer-defined header files should end in `.h`. A programmer-defined header file can be included by using the `#include` preprocessor directive. For example, the header file `square.h` can be included in a program by placing the directive `#include "square.h"` at the beginning of the program.

## 15.6 Inline Functions

Implementing a program as a set of functions is good from a software engineering standpoint, but function calls involve execution-time overhead. C++ provides **inline functions** to help reduce function call overhead—especially for small functions. Placing the qualifier **inline** before a function’s return type in the function definition “advises” the compiler to generate a copy of the function’s code in place (when appropriate) to avoid a function call. The trade-off is that multiple copies of the function code are inserted in the program (often making the program larger) rather than there being a single copy of the function to which control is passed each time the function is called. The compiler can ignore the **inline** qualifier and typically does so for all but the smallest functions.



### Software Engineering Observation 15.3

*Changea to an inline function could require clients of the function to be recompiled. This can be significant in program development and maintenance situations.*



### Performance Tip 15.2

*Using inline functions can reduce execution time but may increase program size.*



### Software Engineering Observation 15.4

*The inline qualifier should be used only with small, frequently used functions.*

Figure 15.3 uses **inline** function `cube` (lines 11–14) to calculate the volume of a cube of side length `side`. Keyword `const` in the parameter list of function `cube` tells the compiler that the function does not modify variable `side`. This ensures that the value of `side` is not changed by the function when the calculation is performed. Notice that the complete definition of function `cube` appears before it’s used in the program. This is required so that the compiler knows how to expand a `cube` function call into its inlined code. For this reason, reusable inline functions are typically placed in header files, so that their definitions can be included in each source file that uses them.



### Software Engineering Observation 15.5

*The `const` qualifier should be used to enforce the principle of least privilege. Using the principle of least privilege to properly design software can greatly reduce debugging time and improper side effects, and can make a program easier to modify and maintain.*

```
1 // Fig. 15.3: fig15_03.cpp
2 // Using an inline function to calculate the volume of a cube.
3 #include <iostream>
```

**Fig. 15.3** | **inline** function that calculates the volume of a cube. (Part I of 2.)

```

4 using std::cout;
5 using std::cin;
6 using std::endl;
7
8 // Definition of inline function cube. Definition of function appears
9 // before function is called, so a function prototype is not required.
10 // First line of function definition acts as the prototype.
11 inline double cube(const double side)
12 {
13 return side * side * side; // calculate the cube of side
14 } // end function cube
15
16 int main()
17 {
18 double sideValue; // stores value entered by user
19
20 for (int i = 1; i <= 3; i++)
21 {
22 cout << "\nEnter the side length of your cube: ";
23 cin >> sideValue; // read value from user
24
25 // calculate cube of sideValue and display result
26 cout << "Volume of cube with side "
27 << sideValue << " is " << cube(sideValue) << endl;
28 }
29 } // end main

```

```

Enter the side length of your cube: 1.0
Volume of cube with side 1 is 1

```

```

Enter the side length of your cube: 2.3
Volume of cube with side 2.3 is 12.167

```

```

Enter the side length of your cube: 5.4
Volume of cube with side 5.4 is 157.464

```

**Fig. 15.3** | inline function that calculates the volume of a cube. (Part 2 of 2.)

Lines 4–6 are using statements that help us eliminate the need to repeat the `std::` prefix. Once we include these using statements, we can write `cout` instead of `std::cout`, `cin` instead of `std::cin` and `endl` instead of `std::endl`, in the remainder of the program. From this point forward, each C++ example contains one or more using statements.

In place of lines 4–6, many programmers prefer to use the declaration

```
using namespace std;
```

which enables a program to use all the names in any standard C++ header file (such as `<iostream>`) that a program might include. From this point forward in our C++ programs, we'll use the preceding declaration in our programs.

The `for` statement's condition (line 20) evaluates to either 0 (false) or nonzero (true). This is consistent with C. C++ also provides type `bool` for representing boolean (true/false) values. The two possible values of a `bool` are the keywords `true` and `false`. When `true`

and `false` are converted to integers, they become the values 1 and 0, respectively. When non-boolean values are converted to type `bool`, non-zero values become `true`, and zero or null pointer values become `false`. Figure 15.4 lists the keywords common to C and C++ and the keywords unique to C++.

| C++ keywords                                                  |                           |                       |                               |                          |
|---------------------------------------------------------------|---------------------------|-----------------------|-------------------------------|--------------------------|
| <i>Keywords common to the C and C++ programming languages</i> |                           |                       |                               |                          |
| <code>auto</code>                                             | <code>break</code>        | <code>case</code>     | <code>char</code>             | <code>const</code>       |
| <code>continue</code>                                         | <code>default</code>      | <code>do</code>       | <code>double</code>           | <code>else</code>        |
| <code>enum</code>                                             | <code>extern</code>       | <code>float</code>    | <code>for</code>              | <code>goto</code>        |
| <code>if</code>                                               | <code>int</code>          | <code>long</code>     | <code>register</code>         | <code>return</code>      |
| <code>short</code>                                            | <code>signed</code>       | <code>sizeof</code>   | <code>static</code>           | <code>struct</code>      |
| <code>switch</code>                                           | <code>typedef</code>      | <code>union</code>    | <code>unsigned</code>         | <code>void</code>        |
| <code>volatile</code>                                         | <code>while</code>        |                       |                               |                          |
| <i>C++-only keywords</i>                                      |                           |                       |                               |                          |
| <code>and</code>                                              | <code>and_eq</code>       | <code>asm</code>      | <code>bitand</code>           | <code>bitor</code>       |
| <code>bool</code>                                             | <code>catch</code>        | <code>class</code>    | <code>compl</code>            | <code>const_cast</code>  |
| <code>delete</code>                                           | <code>dynamic_cast</code> | <code>explicit</code> | <code>export</code>           | <code>false</code>       |
| <code>friend</code>                                           | <code>inline</code>       | <code>mutable</code>  | <code>namespace</code>        | <code>new</code>         |
| <code>not</code>                                              | <code>not_eq</code>       | <code>operator</code> | <code>or</code>               | <code>or_eq</code>       |
| <code>private</code>                                          | <code>protected</code>    | <code>public</code>   | <code>reinterpret_cast</code> | <code>static_cast</code> |
| <code>template</code>                                         | <code>this</code>         | <code>throw</code>    | <code>true</code>             | <code>try</code>         |
| <code>typeid</code>                                           | <code>typename</code>     | <code>using</code>    | <code>virtual</code>          | <code>wchar_t</code>     |
| <code>xor</code>                                              | <code>xor_eq</code>       |                       |                               |                          |

**Fig. 15.4** | C++ keywords.

## 15.7 References and Reference Parameters

Two ways to pass arguments to functions in many programming languages are pass-by-value and pass-by-reference. When an argument is passed by value, a *copy* of the argument's value is made and passed (on the function call stack) to the called function. Changes to the copy do not affect the original variable's value in the caller. This prevents the accidental side effects that so greatly hinder the development of correct and reliable software systems. Each argument that has been passed in the programs in this chapter so far has been passed by value.



### Performance Tip 15.3

*One disadvantage of pass-by-value is that, if a large data item is being passed, copying that data can take a considerable amount of execution time and memory space.*

### Reference Parameters

This section introduces **reference parameters**—the first of two means that C++ provides for performing pass-by-reference. With pass-by-reference, the caller gives the called function the ability to access the caller's data directly, and to modify that data if the called function chooses to do so.

**Performance Tip 15.4**

*Pass-by-reference is good for performance reasons, because it can eliminate the pass-by-value overhead of copying large amounts of data.*

**Software Engineering Observation 15.6**

*Pass-by-reference can weaken security; the called function can corrupt the caller's data.*

Later, we'll show how to achieve the performance advantage of pass-by-reference while simultaneously achieving the software engineering advantage of protecting the caller's data from corruption.

A reference parameter is an alias for its corresponding argument in a function call. To indicate that a function parameter is passed by reference, simply follow the parameter's type in the function prototype by an ampersand (&); use the same notation when listing the parameter's type in the function header. For example, the following declaration in a function header

```
int &count
```

when read from right to left is pronounced “count is a reference to an int.” In the function call, simply mention the variable by name to pass it by reference. Then, mentioning the variable by its parameter name in the body of the called function actually refers to the original variable in the calling function, and the original variable can be modified directly by the called function. As always, the function prototype and header must agree.

***Passing Arguments by Value and by Reference***

Figure 15.5 compares pass-by-value and pass-by-reference with reference parameters. The “styles” of the arguments in the calls to function `squareByValue` (line 17) and function `squareByReference` (line 22) are identical—both variables are simply mentioned by name in the function calls. Without checking the function prototypes or function definitions, it's not possible to tell from the calls alone whether either function can modify its arguments. Because function prototypes are mandatory, however, the compiler has no trouble resolving the ambiguity. Recall that a function prototype tells the compiler the type of data returned by the function, the number of parameters the function expects to receive, the types of the parameters, and the order in which they are expected. The compiler uses this information to validate function calls. In C, function prototypes are not required. Making them mandatory in C++ enables **type-safe linkage**, which ensures that the types of the arguments conform to the types of the parameters. Otherwise, the compiler reports an error. Locating such type errors at compile time helps prevent the runtime errors that can occur in C when arguments of incorrect data types are passed to functions.

```
1 // Fig. 15.5: fig15_05.cpp
2 // Comparing pass-by-value and pass-by-reference with references.
3 #include <iostream>
4 using namespace std;
5
6 int squareByValue(int); // function prototype (value pass)
```

**Fig. 15.5** | Passing arguments by value and by reference. (Part I of 2.)

```

7 void squareByReference(int &); // function prototype (reference pass)
8
9 int main()
10 {
11 int x = 2; // value to square using squareByValue
12 int z = 4; // value to square using squareByReference
13
14 // demonstrate squareByValue
15 cout << "x = " << x << " before squareByValue\n";
16 cout << "Value returned by squareByValue: "
17 << squareByValue(x) << endl;
18 cout << "x = " << x << " after squareByValue\n" << endl;
19
20 // demonstrate squareByReference
21 cout << "z = " << z << " before squareByReference" << endl;
22 squareByReference(z);
23 cout << "z = " << z << " after squareByReference" << endl;
24 } // end main
25
26 // squareByValue multiplies number by itself, stores the
27 // result in number and returns the new value of number
28 int squareByValue(int number)
29 {
30 return number *= number; // caller's argument not modified
31 } // end function squareByValue
32
33 // squareByReference multiplies numberRef by itself and stores the result
34 // in the variable to which numberRef refers in the caller
35 void squareByReference(int &numberRef)
36 {
37 numberRef *= numberRef; // caller's argument modified
38 } // end function squareByReference

```

```

x = 2 before squareByValue
Value returned by squareByValue: 4
x = 2 after squareByValue

z = 4 before squareByReference
z = 16 after squareByReference

```

**Fig. 15.5** | Passing arguments by value and by reference. (Part 2 of 2.)



### Common Programming Error 15.2

Because reference parameters are mentioned only by name in the body of the called function, you might inadvertently treat reference parameters as pass-by-value parameters. This can cause unexpected side effects if the original copies of the variables are changed by the function.



### Performance Tip 15.5

For passing large objects efficiently, use a constant reference parameter to simulate the appearance and security of pass-by-value and avoid the overhead of passing a copy of the large object. The called function will not be able to modify the object in the caller.



### Software Engineering Observation 15.7

*Many programmers do not declare parameters passed by value as `const`, even when the called function should not modify the passed argument. Keyword `const` in this context would protect only a copy of the original argument, not the original argument itself, which when passed by value is safe from modification by the called function.*

To specify a reference to a constant, place the `const` qualifier before the type specifier in the parameter declaration. Note in line 35 of Fig. 15.5 the placement of `&` in the parameter list of function `squareByReference`. Some C++ programmers prefer to write `int& numberRef` with the ampersand abutting `int`—both forms are equivalent to the compiler.



### Software Engineering Observation 15.8

*For the combined reasons of clarity and performance, many C++ programmers prefer that modifiable arguments be passed to functions by using pointers, small nonmodifiable arguments be passed by value and large nonmodifiable arguments be passed by using references to constants.*

### References as Aliases within a Function

References can also be used as aliases for other variables within a function (although they typically are used with functions as shown in Fig. 15.5). For example, the code

```
int count = 1; // declare integer variable count
int &cRef = count; // create cRef as an alias for count
cRef++; // increment count (using its alias cRef)
```

increments variable `count` by using its alias `cRef`. Reference variables must be initialized in their declarations, as we show in line 9 of both Fig. 15.6 and Fig. 15.7, and cannot be reassigned as aliases to other variables. Once a reference is declared as an alias for a variable, all operations “performed” on the alias (i.e., the reference) are actually performed on the original variable. The alias is simply another name for the original variable. Taking the address of a reference and comparing references do not cause syntax errors; rather, each operation occurs on the variable for which the reference is an alias. Unless it’s a reference to a constant, a reference argument must be an *lvalue* (e.g., a variable name), not a constant or expression that returns an *rvalue* (e.g., the result of a calculation).

```
1 // Fig. 15.6: fig15_06.cpp
2 // References must be initialized.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 int x = 3;
9 int &y = x; // y refers to (is an alias for) x
10
11 cout << "x = " << x << endl << "y = " << y << endl;
12 y = 7; // actually modifies x
13 cout << "x = " << x << endl << "y = " << y << endl;
14 }
```

**Fig. 15.6** | Initializing and using a reference. (Part 1 of 2.)

```
x = 3
y = 3
x = 7
y = 7
```

**Fig. 15.6** | Initializing and using a reference. (Part 2 of 2.)

```
1 // Fig. 15.7: fig15_07.cpp
2 // References must be initialized.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 int x = 3;
9 int &y; // Error: y must be initialized
10
11 cout << "x = " << x << endl << "y = " << y << endl;
12 y = 7;
13 cout << "x = " << x << endl << "y = " << y << endl;
14 } // end main
```

*Microsoft Visual C++ compiler error message:*

```
C:\examples\ch15\fig15_07\fig15_07.cpp(10) : error C2530: 'y' :
 references must be initialized
```

*GNU C++ compiler error message:*

```
fig15_07.cpp:10: error: 'y' declared as a reference but not initialized
```

**Fig. 15.7** | Uninitialized reference causes a syntax error.

### *Returning a Reference from a Function*

Returning references from functions can be dangerous. When returning a reference to a variable declared in the called function, the variable should be declared *static* within that function. Otherwise, the reference refers to an automatic variable that is discarded when the function terminates; such a variable is “undefined,” and the program’s behavior is unpredictable. References to undefined variables are called **dangling references**.



#### **Common Programming Error 15.3**

*Not initializing a reference variable when it’s declared is a compilation error, unless the declaration is part of a function’s parameter list. Reference parameters are initialized when the function in which they’re declared is called.*



#### **Common Programming Error 15.4**

*Attempting to reassign a previously declared reference to be an alias to another variable is a logic error. The value of the other variable is simply assigned to the variable for which the reference is already an alias.*





### Common Programming Error 15.5

*Returning a reference to an automatic variable in a called function is a logic error. Some compilers issue a warning when this occurs.*

### Error Messages for Uninitialized References

The C++ standard does not specify the error messages that compilers use to indicate particular errors. For this reason, we show in Fig. 15.7 the error messages produced by several compilers when a reference is not initialized.

## 15.8 Empty Parameter Lists

C++, like C, allows you to define functions with no parameters. In C++, an empty parameter list is specified by writing either `void` or nothing at all in parentheses. The prototypes

```
void print();
void print(void);
```

each specify that function `print` does not take arguments and does not return a value. These prototypes are equivalent.



### Portability Tip 15.2

*The meaning of an empty function parameter list in C++ is dramatically different than in C. In C, it means all argument checking is disabled (i.e., the function call can pass any arguments it wants). In C++, it means that the function takes no arguments. Thus, C programs using this feature might cause compilation errors when compiled in C++.*

## 15.9 Default Arguments

It's not uncommon for a program to invoke a function repeatedly with the same argument value for a particular parameter. In such cases, the programmer can specify that such a parameter has a **default argument**, i.e., a default value to be passed to that parameter. When a program omits an argument for a parameter with a default argument in a function call, the compiler rewrites the function call and inserts the default value of that argument to be passed as an argument in the function call.

Default arguments must be the rightmost (trailing) arguments in a function's parameter list. When calling a function with two or more default arguments, if an omitted argument is not the rightmost argument in the argument list, then all arguments to the right of that argument also must be omitted. Default arguments should be specified with the first occurrence of the function name—typically, in the function prototype. If the function prototype is omitted because the function definition also serves as the prototype, then the default arguments should be specified in the function header. Default values can be any expression, including constants, global variables or function calls. Default arguments also can be used with `inline` functions.

Figure 15.8 demonstrates using default arguments in calculating the volume of a box. The function prototype for `boxVolume` (line 7) specifies that all three parameters have been given default values of 1. We provided variable names in the function prototype for readability, but these are not required.

```

1 // Fig. 15.8: fig15_08.cpp
2 // Using default arguments.
3 #include <iostream>
4 using namespace std;
5
6 // function prototype that specifies default arguments
7 int boxVolume(int length = 1, int width = 1, int height = 1);
8
9 int main()
10 {
11 // no arguments--use default values for all dimensions
12 cout << "The default box volume is: " << boxVolume();
13
14 // specify length; default width and height
15 cout << "\n\nThe volume of a box with length 10,\n"
16 << "width 1 and height 1 is: " << boxVolume(10);
17
18 // specify length and width; default height
19 cout << "\n\nThe volume of a box with length 10,\n"
20 << "width 5 and height 1 is: " << boxVolume(10, 5);
21
22 // specify all arguments
23 cout << "\n\nThe volume of a box with length 10,\n"
24 << "width 5 and height 2 is: " << boxVolume(10, 5, 2)
25 << endl;
26 } // end main
27
28 // function boxVolume calculates the volume of a box
29 int boxVolume(int length, int width, int height)
30 {
31 return length * width * height;
32 } // end function boxVolume

```

```

The default box volume is: 1

The volume of a box with length 10,
width 1 and height 1 is: 10

The volume of a box with length 10,
width 5 and height 1 is: 50

The volume of a box with length 10,
width 5 and height 2 is: 100

```

**Fig. 15.8** | Default arguments to a function.



### Common Programming Error 15.6

*It's a compilation error to specify default arguments in both a function's prototype and header.*

The first call to `boxVolume` (line 12) specifies no arguments, thus using all three default values of 1. The second call (line 16) passes a `length` argument, thus using default values of 1 for the `width` and `height` arguments. The third call (line 20) passes arguments

for length and width, thus using a default value of 1 for the height argument. The last call (line 24) passes arguments for length, width and height, thus using no default values. Any arguments passed to the function explicitly are assigned to the function's parameters from left to right. Therefore, when `boxVolume` receives one argument, the function assigns the value of that argument to its length parameter (i.e., the leftmost parameter in the parameter list). When `boxVolume` receives two arguments, the function assigns the values of those arguments to its length and width parameters in that order. Finally, when `boxVolume` receives all three arguments, the function assigns the values of those arguments to its length, width and height parameters, respectively.



### Good Programming Practice 15.2

*Using default arguments can simplify writing function calls. However, some programmers feel that explicitly specifying all arguments is clearer.*



### Software Engineering Observation 15.9

*If the default values for a function change, all client code must be recompiled.*



### Common Programming Error 15.7

*In a function definition, specifying and attempting to use a default argument that is not a rightmost (trailing) argument (while not simultaneously defaulting all the rightmost arguments) is a syntax error.*

## 15.10 Unary Scope Resolution Operator

It's possible to declare local and global variables of the same name. This causes the global variable to be "hidden" by the local variable in the local scope. C++ provides the **unary scope resolution operator** (`::`) to access a global variable when a local variable of the same name is in scope. The unary scope resolution operator cannot be used to access a local variable of the same name in an outer block. A global variable can be accessed directly without the unary scope resolution operator if the name of the global variable is not the same as that of a local variable in scope.

Figure 15.9 demonstrates the unary scope resolution operator with global and local variables of the same name (lines 6 and 10, respectively). To emphasize that the local and global versions of variable `number` are distinct, the program declares one variable of type `int` and the other `double`.

```
1 // Fig. 15.9: fig15_09.cpp
2 // Using the unary scope resolution operator.
3 #include <iostream>
4 using namespace std;
5
6 int number = 7; // global variable named number
7
8 int main()
9 {
10 double number = 10.5; // local variable named number
```

**Fig. 15.9** | Using the unary scope resolution operator. (Part 1 of 2.)

```

11
12 // display values of local and global variables
13 cout << "Local double value of number = " << number
14 << "\nGlobal int value of number = " << ::number << endl;
15 } // end main

```

```

Local double value of number = 10.5
Global int value of number = 7

```

**Fig. 15.9** | Using the unary scope resolution operator. (Part 2 of 2.)

Using the unary scope resolution operator (`::`) with a given variable name is optional when the only variable with that name is a global variable.



### Common Programming Error 15.8

*It's an error to attempt to use the unary scope resolution operator (`::`) to access a nonglobal variable in an outer block. If no global variable with that name exists, a compilation error occurs. If a global variable with that name exists, this is a logic error, because the program will refer to the global variable when you intended to access the nonglobal variable in the outer block.*



### Good Programming Practice 15.3

*Always using the unary scope resolution operator (`::`) to refer to global variables makes programs easier to read and understand, because it makes it clear that you intend to access a global variable rather than a nonglobal variable.*



### Software Engineering Observation 15.10

*Always using the unary scope resolution operator (`::`) to refer to global variables makes programs easier to modify by reducing the risk of name collisions with nonglobal variables.*



### Error-Prevention Tip 15.1

*Always using the unary scope resolution operator (`::`) to refer to a global variable eliminates logic errors that might occur if a nonglobal variable hides the global variable.*



### Error-Prevention Tip 15.2

*Avoid using variables of the same name for different purposes in a program. Although this is allowed in various circumstances, it can lead to errors.*

## 15.11 Function Overloading

C++ enables several functions of the same name to be defined, as long as these functions have different sets of parameters (at least as far as the parameter types or the number of parameters or the order of the parameter types are concerned). This capability is called **function overloading**.<sup>1</sup> When an overloaded function is called, the C++ compiler selects the proper function by examining the number, types and order of the arguments in the

1. The C++ standard requires `float`, `double` and `long double` overloaded versions of the math library functions discussed in Section 5.3.

call. Function overloading is commonly used to create several functions of the same name that perform similar tasks, but on data of different types. For example, many functions in the math library are overloaded for different numeric data types.



#### Good Programming Practice 15.4

*Overloading functions that perform closely related tasks can make programs more readable and understandable.*

#### Overloaded **square** Functions

Figure 15.10 uses overloaded square functions to calculate the square of an `int` (lines 7–11) and the square of a `double` (lines 14–18). Line 22 invokes the `int` version of function square by passing the literal value 7. C++ treats whole-number literal values as type `int` by default. Similarly, line 24 invokes the `double` version of function square by passing the literal value 7.5, which C++ treats as a `double` value by default. In each case the compiler chooses the proper function to call, based on the type of the argument. The outputs confirm that the proper function was called in each case.

```

1 // Fig. 15.10: fig15_10.cpp
2 // Overloaded functions.
3 #include <iostream>
4 using namespace std;
5
6 // function square for int values
7 int square(int x)
8 {
9 cout << "square of integer " << x << " is ";
10 return x * x;
11 } // end function square with int argument
12
13 // function square for double values
14 double square(double y)
15 {
16 cout << "square of double " << y << " is ";
17 return y * y;
18 } // end function square with double argument
19
20 int main()
21 {
22 cout << square(7); // calls int version
23 cout << endl;
24 cout << square(7.5); // calls double version
25 cout << endl;
26 } // end main

```

```

square of integer 7 is 49
square of double 7.5 is 56.25

```

**Fig. 15.10** | Overloaded square functions.

#### *How the Compiler Differentiates Overloaded Functions*

Overloaded functions are distinguished by their **signatures**—a combination of a function's name and its parameter types (in order). The compiler encodes each function iden-

tifier with the number and types of its parameters (sometimes referred to as **name mangling** or **name decoration**) to enable type-safe linkage. This ensures that the proper overloaded function is called and that the argument types conform to the parameter types.

Figure 15.11 was compiled with GNU C++. Rather than showing the execution output of the program (as we normally would), we show the mangled function names produced in assembly language by GNU C++. Each mangled name (other than `main`) begins with two underscores (`__`) followed by the letter `Z`, a number and the function name. The number that follows `Z` specifies how many characters are in the function's name. For example, function `square` has 6 characters in its name, so its mangled name is prefixed with `__Z6`. The function name is then followed by an encoding of its parameter list. In the parameter list for function `nothing2` (line 25; see the fourth output line), `c` represents a `char`, `i` represents an `int`, `Rf` represents a `float &` (i.e., a reference to a `float`) and `Rd` represents a `double &` (i.e., a reference to a `double`). In the parameter list for function `nothing1`, `i` represents an `int`, `f` represents a `float`, `c` represents a `char` and `Ri` represents an `int &`. The two `square` functions are distinguished by their parameter lists; one specifies `d` for `double` and the other specifies `i` for `int`. The return types of the functions are not specified in the mangled names. Overloaded functions can have different return types, but if they do, they must also have different parameter lists. Again, you cannot have two functions with the same signature and different return types. Function-name mangling is compiler specific. Also, function `main` is not mangled, because it cannot be overloaded.

---

```

1 // Fig. 15.11: fig15_11.cpp
2 // Name mangling.
3
4 // function square for int values
5 int square(int x)
6 {
7 return x * x;
8 } // end function square
9
10 // function square for double values
11 double square(double y)
12 {
13 return y * y;
14 } // end function square
15
16 // function that receives arguments of types
17 // int, float, char and int &
18 void nothing1(int a, float b, char c, int &d)
19 {
20 // empty function body
21 } // end function nothing1
22
23 // function that receives arguments of types
24 // char, int, float & and double &
25 int nothing2(char a, int b, float &c, double &d)
26 {
27 return 0;
28 } // end function nothing2

```

---

**Fig. 15.11** | Name mangling to enable type-safe linkage. (Part 1 of 2.)

```

29
30 int main()
31 {
32 return 0; // indicates successful termination
33 } // end main

```

```

__Z6squarei
__Z6squared
__Z8nothing1ifcRi
__Z8nothing2cifRfRd
__main

```

**Fig. 15.11** | Name mangling to enable type-safe linkage. (Part 2 of 2.)



### Common Programming Error 15.9

*Creating overloaded functions with identical parameter lists and different return types is a compilation error.*

The compiler uses only the parameter lists to distinguish between functions of the same name. Overloaded functions need not have the same number of parameters. Programmers should use caution when overloading functions with default parameters, because this may cause ambiguity.



### Common Programming Error 15.10

*A function with default arguments omitted might be called identically to another overloaded function; this is a compilation error. For example, having in a program both a function that explicitly takes no arguments and a function of the same name that contains all default arguments results in a compilation error when an attempt is made to use that function name in a call passing no arguments. The compiler does not know which version of the function to choose.*

## Overloaded Operators

In Chapter 19, we discuss how to overload operators to define how they should operate on objects of user-defined data types. (In fact, we've been using overloaded operators, including the stream insertion operator << and the stream extraction operator >>, each of which is overloaded to be able to display data of all the fundamental types. We say more about overloading << and >> to be able to handle objects of user-defined types in Chapter 19.) Section 15.12 introduces function templates for automatically generating overloaded functions that perform identical tasks on data of different types.

## 15.12 Function Templates

Overloaded functions are used to perform similar operations that may involve different program logic on different data types. If the program logic and operations are identical for each data type, overloading may be performed more compactly and conveniently by using **function templates**. The programmer writes a single function template definition. Given the argument types provided in calls to this function, C++ automatically generates separate **function template specializations** to handle each type of call appropriately. Thus, defining a single function template essentially defines a whole family of overloaded functions.

Figure 15.12 contains the definition of a function template (lines 4–18) for a maximum function that determines the largest of three values. All function template definitions begin with the `template` keyword (line 4) followed by a **template parameter list** to the function template enclosed in angle brackets (< and >). Every parameter in the template parameter list (each is referred to as a **formal type parameter**) is preceded by keyword `typename` or keyword `class` (which are synonyms). The formal type parameters are placeholders for fundamental types or user-defined types. These placeholders are used to specify the types of the function's parameters (line 5), to specify the function's return type (line 5) and to declare variables within the body of the function definition (line 7). A function template is defined like any other function, but uses the formal type parameters as placeholders for actual data types.

The function template in Fig. 15.12 declares a single formal type parameter `T` (line 4) as a placeholder for the type of the data to be tested by function `maximum`. The name of a type parameter must be unique in the template parameter list for a particular template definition. When the compiler detects a maximum invocation in the program source code, the type of the data passed to `maximum` is substituted for `T` throughout the template definition, and C++ creates a complete source-code function for determining the maximum of three values of the specified data type. Then the newly created function is compiled. Thus, templates are a means of code generation.

---

```

1 // Fig. 15.12: maximum.h
2 // Definition of function template maximum.
3
4 template < class T > // or template< typename T >
5 T maximum(T value1, T value2, T value3)
6 {
7 T maximumValue = value1; // assume value1 is maximum
8
9 // determine whether value2 is greater than maximumValue
10 if (value2 > maximumValue)
11 maximumValue = value2;
12
13 // determine whether value3 is greater than maximumValue
14 if (value3 > maximumValue)
15 maximumValue = value3;
16
17 return maximumValue;
18 } // end function template maximum

```

---

**Fig. 15.12** | Function template `maximum` header file.



### Common Programming Error 15.11

*Not placing keyword `class` or keyword `typename` before every formal type parameter of a function template (e.g., writing < class S, T > instead of < class S, class T >) is a syntax error.*

Figure 15.13 uses the `maximum` function template (lines 18, 28 and 38) to determine the largest of three `int` values, three `double` values and three `char` values.



```

1 // Fig. 15.13: fig15_13.cpp
2 // Function template maximum test program.
3 #include <iostream>
4 using namespace std;
5
6 #include "maximum.h" // include definition of function template maximum
7
8 int main()
9 {
10 // demonstrate maximum with int values
11 int int1, int2, int3;
12
13 cout << "Input three integer values: ";
14 cin >> int1 >> int2 >> int3;
15
16 // invoke int version of maximum
17 cout << "The maximum integer value is: "
18 << maximum(int1, int2, int3);
19
20 // demonstrate maximum with double values
21 double double1, double2, double3;
22
23 cout << "\n\nInput three double values: ";
24 cin >> double1 >> double2 >> double3;
25
26 // invoke double version of maximum
27 cout << "The maximum double value is: "
28 << maximum(double1, double2, double3);
29
30 // demonstrate maximum with char values
31 char char1, char2, char3;
32
33 cout << "\n\nInput three characters: ";
34 cin >> char1 >> char2 >> char3;
35
36 // invoke char version of maximum
37 cout << "The maximum character value is: "
38 << maximum(char1, char2, char3) << endl;
39 } // end main

```

```

Input three integer values: 1 2 3
The maximum integer value is: 3

Input three double values: 3.3 2.2 1.1
The maximum double value is: 3.3

Input three characters: A C B
The maximum character value is: C

```

**Fig. 15.13** | Demonstrating function template `maximum`.

In Fig. 15.13, three functions are created as a result of the calls in lines 18, 28 and 38—expecting three `int` values, three `double` values and three `char` values, respectively. For example, the function template specialization created for type `int` replaces each occurrence of `T` with `int` as follows:

```

int maximum(int value1, int value2, int value3)
{
 int maximumValue = value1; // assume value1 is maximum
 // determine whether value2 is greater than maximumValue
 if (value2 > maximumValue)
 maximumValue = value2;
 // determine whether value3 is greater than maximumValue
 if (value3 > maximumValue)
 maximumValue = value3;
 return maximumValue;
} // end function template maximum

```

## 15.13 Introduction to Object Technology and the UML

Now we introduce object orientation, a natural way of thinking about the world and writing computer programs. Our goal here is to help you develop an object-oriented way of thinking and to introduce you to the **Unified Modeling Language™ (UML™)**—a graphical language that allows people who design object-oriented software systems to use an industry-standard notation to represent them. In this section, we introduce basic object-oriented concepts and terminology.

### *Basic Object Technology Concepts*

We begin our introduction to object orientation with some key terminology. Everywhere you look in the real world you see **objects**—people, animals, plants, cars, planes, buildings, computers and so on. Humans think in terms of objects. Telephones, houses, traffic lights, microwave ovens and water coolers are just a few more objects we see around us every day.

Objects have some things in common. They all have **attributes** (e.g., size, shape, color and weight), and they all exhibit **behaviors** (e.g., a ball rolls, bounces, inflates and deflates; a baby cries, sleeps, crawls, walks and blinks; a car accelerates, brakes and turns; a towel absorbs water). We'll study the kinds of attributes and behaviors that software objects have.

Humans learn about existing objects by studying their attributes and observing their behaviors. Different objects can have similar attributes and can exhibit similar behaviors. Comparisons can be made, for example, between babies and adults and between humans and chimpanzees.

**Object-oriented design (OOD)** models software in terms similar to those that people use to describe real-world objects. It takes advantage of class relationships, where objects of a certain class, such as a class of vehicles, have the same characteristics—cars, trucks, little red wagons and roller skates have much in common. OOD takes advantage of **inheritance** relationships, where new classes of objects are derived by absorbing characteristics of existing classes and adding unique characteristics of their own. An object of class “convertible” certainly has the characteristics of the more general class “automobile,” but more specifically, the roof goes up and down.

Object-oriented design provides a natural and intuitive way to view the software design process—namely, modeling objects by their attributes, behaviors and interrelationships just as we describe real-world objects. OOD also models communication between objects. Just as people send messages to one another (e.g., a sergeant commands a soldier to stand at attention), objects also communicate via messages. A bank account object may

receive a message to decrease its balance by a certain amount because the customer has withdrawn that amount of money.

OOD **encapsulates** (i.e., wraps) attributes and **operations** (behaviors) into objects—an object’s attributes and operations are intimately tied together. Objects have the property of **information hiding**. This means that objects may know how to communicate with one another across well-defined **interfaces**, but normally they’re not allowed to know how other objects are implemented—implementation details are hidden within the objects themselves. We can drive a car effectively, for instance, without knowing the details of how engines, transmissions, brakes and exhaust systems work internally—as long as we know how to use the accelerator pedal, the brake pedal, the steering wheel and so on. Information hiding, as we’ll see, is crucial to good software engineering.

Languages like C++ are **object oriented**. Programming in such a language is called **object-oriented programming (OOP)**, and it allows you to implement an object-oriented design as a working software system. Languages like C, on the other hand, are **procedural**, so programming tends to be **action oriented**. In C, the unit of programming is the function. In C++, the unit of programming is the “class” from which objects are eventually **instantiated** (an OOP term for “created”). C++ classes contain functions that implement operations and data that implements attributes.

C programmers concentrate on writing functions. Programmers group actions that perform some common task into functions, and group functions to form programs. Data is certainly important in C, but the view is that data exists primarily in support of the actions that functions perform. The verbs in a system specification help the C programmer determine the set of functions that will work together to implement the system.

### *Classes, Data Members and Member Functions*

C++ programmers concentrate on creating their own user-defined types called classes. Each class contains data as well as the set of functions that manipulate that data and provide services to **clients** (i.e., other classes or functions that use the class). The data components of a class are called **data members**. For example, a bank account class might include an account number and a balance. The function components of a class are called **member functions** (typically called **methods** in other object-oriented programming languages such as Java). For example, a bank account class might include member functions to make a deposit (increasing the balance), make a withdrawal (decreasing the balance) and inquire what the current balance is. The programmer uses built-in types (and other user-defined types) as the “building blocks” for constructing new user-defined types (classes). The nouns in a system specification help the C++ programmer determine the set of classes from which objects are created that work together to implement the system.

Classes are to objects as blueprints are to houses—a class is a “plan” for building an object of the class. Just as we can build many houses from one blueprint, we can instantiate (create) many objects from one class. You cannot cook meals in the kitchen of a blueprint; you can cook meals in the kitchen of a house. You cannot sleep in the bedroom of a blueprint; you can sleep in the bedroom of a house.

Classes can have relationships with other classes. In an object-oriented design of a bank, the “bank teller” class relates to other classes, such as the “customer” class, the “cash drawer” class, the “safe” class, and so on. These relationships are called **associations**. Packaging software as classes makes it possible for future software systems to **reuse** the classes.



### Software Engineering Observation 15.11

*Reuse of existing classes when building new classes and programs saves time, money and effort. Reuse also helps you build more reliable and effective systems, because existing classes often have gone through extensive testing, debugging and performance tuning.*

Indeed, with object technology, you can build much of the new software you'll need by combining existing classes, just as automobile manufacturers combine interchangeable parts. Each new class you create can become a valuable software asset that you and others can reuse to speed and enhance the quality of future software development efforts.

### *Introduction to Object-Oriented Analysis and Design (OOAD)*

Soon you'll be writing programs in C++. How will you create the code for your programs? Perhaps, like many beginning programmers, you'll simply turn on your computer and start typing. This approach may work for small programs, but what if you were asked to create a software system to control thousands of automated teller machines for a major bank? Or what if you were asked to work on a team of 1000 software developers building the next generation of the U.S. air traffic control system? For projects so large and complex, you could not simply sit down and start writing programs.

To create the best solutions, you should follow a detailed process for **analyzing** your project's **requirements** (i.e., determining *what* the system is supposed to do) and developing a **design** that satisfies them (i.e., deciding *how* the system should do it). Ideally, you would go through this process and carefully review the design (or have your design reviewed by other software professionals) before writing any code. If this process involves analyzing and designing your system from an object-oriented point of view, it's called **object-oriented analysis and design (OOAD)**. Experienced programmers know that analysis and design can save many hours by helping avoid an ill-planned system development approach that has to be abandoned partway through its implementation, possibly wasting considerable time, money and effort.

OOAD is the generic term for the process of analyzing a problem and developing an approach for solving it. Small problems like the ones discussed in these first few chapters do not require an exhaustive OOAD process.

As problems and the groups of people solving them increase in size, the methods of OOAD quickly become more appropriate than pseudocode. Ideally, a group should agree on a strictly defined process for solving its problem and a uniform way of communicating the results of that process to one another. Although many different OOAD processes exist, a single graphical language for communicating the results of *any* OOAD process has come into wide use. This language, known as the Unified Modeling Language (UML), was developed in the mid-1990s under the initial direction of three software methodologists: Grady Booch, James Rumbaugh and Ivar Jacobson.

### *History of the UML*

In the 1980s, increasing numbers of organizations began using OOP to build their applications, and a need developed for a standard OOAD process. Many methodologists—including Booch, Rumbaugh and Jacobson—individually produced and promoted separate processes to satisfy this need. Each process had its own notation, or “language” (in the form of graphical diagrams), to convey the results of analysis and design.

In 1994, James Rumbaugh joined Grady Booch at Rational Software Corporation (now a division of IBM), and the two began working to unify their popular processes. They soon were joined by Ivar Jacobson. In 1996, the group released early versions of the UML to the software engineering community and requested feedback. Around the same time, an organization known as the **Object Management Group™ (OMG™)** invited submissions for a common modeling language. The OMG ([www.omg.org](http://www.omg.org)) is a nonprofit organization that promotes the standardization of object-oriented technologies by issuing guidelines and specifications, such as the UML. Several corporations—among them HP, IBM, Microsoft, Oracle and Rational Software—had already recognized the need for a common modeling language. In response to the OMG’s request for proposals, these companies formed **UML Partners**—the consortium that developed the UML version 1.1 and submitted it to the OMG. The OMG accepted the proposal and, in 1997, assumed responsibility for the continuing maintenance and revision of the UML. We present the terminology and notation of the current version of the UML—UML version 2—throughout the C++ section of this book.

### *What Is the UML?*

The Unified Modeling Language is now the most widely used graphical representation scheme for modeling object-oriented systems. Those who design systems use the language (in the form of diagrams) to model their systems, as we do throughout the C++ section of this book. An attractive feature of the UML is its flexibility. The UML is **extensible** (i.e., capable of being enhanced with new features) and is independent of any particular OOAD process. UML modelers are free to use various processes in designing systems, but all developers can now express their designs with one standard set of graphical notations. For more information, visit our UML Resource Center at [www.deitel.com/UML/](http://www.deitel.com/UML/).

## 15.14 Wrap-Up

In this chapter, you learned several of C++’s enhancements to C. We presented basic C++-style input and output with `cin` and `cout` and overviewed the C++ Standard Library header files. We discussed `inline` functions for improving performance by eliminating the overhead of function calls. You learned how to use pass-by-reference with C++’s reference parameters, which enable you to create aliases for existing variables. You learned that multiple functions can be overloaded by providing functions with the same name and different signatures; such functions can be used to perform the same or similar tasks, using different types or different numbers of parameters. We then demonstrated a simpler way of overloading functions using function templates, where a function is defined once but can be used for several different types. You learned the basic terminology of object technology and were introduced to the UML—the most widely used graphical representation scheme for modeling OO systems. In Chapter 16, you’ll learn how to implement your own classes and use objects of those classes in applications.

## Summary

### *Section 15.2 C++*

- C++ improves on many of C’s features and provides object-oriented-programming (OOP) capabilities that increase software productivity, quality and reusability.

- C++ was developed by Bjarne Stroustrup at Bell Labs and was originally called “C with classes.”

### *Section 15.3 A Simple Program: Adding Two Integers*

- C++ filenames can have one of several extensions, such as `.cpp`, `.cxx` or `.C` (uppercase).
- C++ allows you to begin a comment with `//` and use the remainder of the line as comment text. C++ programmers may also use C-style comments.
- The input/output stream header file `<iostream>` must be included for any program that outputs data to the screen or inputs data from the keyboard using C++-style stream input/output.
- As in C, every C++ program begins execution with function `main`. Keyword `int` to the left of `main` indicates that `main` “returns” an integer value.
- In C, you need not specify a return type for functions. However, C++ requires you to specify the return type, possibly `void`, for all functions; otherwise, a syntax error occurs.
- Declarations can be placed almost anywhere in a C++ program, but they must appear before their corresponding variables are used in the program.
- The standard output stream object (`std::cout`) and the stream insertion operator (`<<`) are used to display text on the screen.
- The standard input stream object (`std::cin`) and the stream extraction operator (`>>`) are used to obtain values from the keyboard.
- The stream manipulator `std::endl` outputs a newline, then “flushes the output buffer.”
- The notation `std::cout` specifies that we’re using a name, in this case `cout`, that belongs to “namespace” `std`.
- Using multiple stream insertion operators (`<<`) in a single statement is referred to as concatenating, chaining or cascading stream insertion operations.

### *Section 15.4 C++ Standard Library*

- C++ programs consist of pieces called classes and functions. You can program each piece you may need to form a C++ program. However, most C++ programmers take advantage of the rich collections of existing classes and functions in the C++ Standard Library.

### *Section 15.5 Header Files*

- The C++ Standard Library is divided into many portions, each with its own header file. The header files contain the function prototypes for the related functions that form each portion of the library. The header files also contain definitions of various class types and functions, as well as constants needed by those functions.
- Header file names ending in `.h` are “old-style” header files that have been superseded by the C++ Standard Library header files.

### *Section 15.6 Inline Functions*

- C++ provides inline functions to help reduce function call overhead—especially for small functions. Placing the qualifier `inline` before a function’s return type in the function definition “advises” the compiler to generate a copy of the function’s code in place to avoid a function call.

### *Section 15.7 References and Reference Parameters*

- Two ways to pass arguments to functions in many programming languages are pass-by-value and pass-by-reference.
- When an argument is passed by value, a *copy* of its value is made and passed (on the function call stack) to the called function. Changes to the copy do not affect the original in the caller.
- With pass-by-reference, the caller gives the called function the ability to access the caller’s data directly and to modify it if the called function chooses to do so.

- A reference parameter is an alias for its corresponding argument in a function call.
- To indicate that a function parameter is passed by reference, simply follow the parameter's type in the function prototype by an ampersand (&); use the same notation when listing the parameter's type in the function header.
- Once a reference is declared as an alias for another variable, all operations supposedly performed on the alias (i.e., the reference) are actually performed on the original variable. The alias is simply another name for the original variable.

### *Section 15.8 Empty Parameter Lists*

- In C++, an empty parameter list is specified by writing either `void` or nothing in parentheses.

### *Section 15.9 Default Arguments*

- It's not uncommon for a program to invoke a function repeatedly with the same argument value for a particular parameter. In such cases, the programmer can specify that such a parameter has a default argument, i.e., a default value to be passed to that parameter.
- When a program omits an argument for a parameter with a default argument, the compiler inserts the default value of that argument to be passed as an argument in the function call.
- Default arguments must be the rightmost (trailing) arguments in a function's parameter list.
- Default arguments should be specified with the first occurrence of the function name—typically, in the function prototype.

### *Section 15.10 Unary Scope Resolution Operator*

- C++ provides the unary scope resolution operator (`::`) to access a global variable when a local variable of the same name is in scope.

### *Section 15.11 Function Overloading*

- C++ enables several functions of the same name to be defined, as long as they have different sets of parameters (by number, type and/or order). This capability is called function overloading.
- When an overloaded function is called, the C++ compiler selects the proper function by examining the number, types and order of the arguments in the call.
- Overloaded functions are distinguished by their signatures.
- The compiler encodes each function identifier with the number and types of its parameters to enable type-safe linkage. Type-safe linkage ensures that the proper overloaded function is called and that the types of the arguments conform to the types of the parameters.

### *Section 15.12 Function Templates*

- Overloaded functions are used to perform similar operations that may involve different program logic on data of different types. If the program logic and operations are identical for each data type, overloading may be performed more compactly and conveniently using function templates.
- The programmer writes a single function template definition. Given the argument types provided in calls to this function, C++ automatically generates separate function template specializations to handle each type of call appropriately. Thus, defining a single function template essentially defines a family of overloaded functions.
- All function template definitions begin with the `template` keyword followed by a template parameter list to the function template enclosed in angle brackets (`<` and `>`).
- The formal type parameters are placeholders for fundamental types or user-defined types. These placeholders are used to specify the types of the function's parameters, to specify the function's return type and to declare variables within the body of the function definition.



### Section 15.13 Introduction to Object Technology and the UML

- The Unified Modeling Language (UML) is a graphical language that allows people who build systems to represent their object-oriented designs in a common notation.
- Object-oriented design (OOD) models software components in terms of real-world objects. It takes advantage of class relationships, where objects of a certain class have the same characteristics. It also takes advantage of inheritance relationships, where newly created classes of objects are derived by absorbing characteristics of existing classes and adding unique characteristics of their own. OOD encapsulates data (attributes) and functions (behavior) into objects—the data and functions of an object are intimately tied together.
- Objects have the property of information hiding—objects normally are not allowed to know how other objects are implemented.
- Object-oriented programming (OOP) allows programmers to implement object-oriented designs as working systems.
- C++ programmers create their own user-defined types called classes. Each class contains data (known as data members) and the set of functions (known as member functions) that manipulate that data and provide services to clients.
- Classes can have relationships with other classes. These relationships are called associations.
- Packaging software as classes makes it possible for future software systems to reuse the classes. Groups of related classes are often packaged as reusable components.
- An instance of a class is called an object.
- With object technology, programmers can build much of the software they will need by combining standardized, interchangeable parts called classes.
- The process of analyzing and designing a system from an object-oriented point of view is called object-oriented analysis and design (OOAD).

## Terminology

::, unary scope resolution operator 544

action oriented 552

analyze a requirements document 553

association (in the UML) 552

attribute of an object 551

behavior of an object 551

bool keyword 536

C++ Standard Library 532

cascading stream insertion operations 532

chaining stream insertion operations 532

class 532

client of a class 552

concatenating stream insertion operations 532

dangling reference 541

data member of a class 552

default argument 542

design a system 553

encapsulation 552

endl stream manipulator 531

extensible language 554

false keyword 536

formal type parameter 549

function overloading 545

function template 548

function template specialization 548

generic programming 529

information hiding 552

inheritance 551

inline function 535

inline keyword 535

input/output stream header (<iostream>) 530

instantiate an object of a class 554

interface 552

mangled function name 547

member function 552

method of a class 552

name decoration 547

name mangling 547

object 551

Object Management Group (OMG) 554

object-oriented analysis and design  
(OOAD) 553

object-oriented design (OOD) 551

object-oriented language 552



object-oriented programming (OOP) 529  
 operation of a class 552  
 operator overloading 532  
 procedural programming language 552  
 reference parameter 537  
 requirement of a project 553  
 reuse classes 552  
 signature of a function 546  
 standard input stream object (cin) 531  
 standard output stream object (cout) 531  
 stream extraction operator (>>) 531  
 stream insertion operator (<<) 531  
 stream manipulator 531  
 template parameter list 549  
 true keyword 536  
 type-safe linkage 538  
 UML Partners 554  
 Unified Modeling Language (UML) 551

## Self-Review Exercises

**15.1** Answer each of the following:

- In C++, it's possible to have various functions with the same name that operate on different types or numbers of arguments. This is called function \_\_\_\_\_.
- The \_\_\_\_\_ enables access to a global variable with the same name as a variable in the current scope.
- A function \_\_\_\_\_ enables a single function to be defined to perform the same task on data of many different types.
- \_\_\_\_\_ is the most widely used graphical representation scheme for OO modeling.
- \_\_\_\_\_ models software components in terms of real-world objects.
- C++ programmers create their own user-defined types called \_\_\_\_\_.

**15.2** Why would a function prototype contain a parameter type declaration such as `double &`?

**15.3** (True/False) All arguments to function calls in C++ are passed by value.

**15.4** Write a complete program that prompts the user for the radius of a sphere, and calculates and prints the volume of that sphere. Use an `inline` function `sphereVolume` that returns the result of the following expression: `( 4.0 / 3.0 ) * 3.14159 * pow( radius, 3 )`.

## Answers to Self-Review Exercises

**15.1** a) overloading. b) unary scope resolution operator (`::`). c) template. d) The UML. e) Object-oriented design (OOD). f) classes.

**15.2** This creates a reference parameter of type “reference to `double`” that enables the function to modify the original variable in the calling function.

**15.3** False. C++ enables pass-by-reference using reference parameters.

**15.4** See the following program:

```

1 // Exercise 15.4 Solution: Ex15_04.cpp
2 // Inline function that calculates the volume of a sphere.
3 #include <iostream>
4 #include <cmath>
5
6 const double PI = 3.14159; // define global constant PI
7
8 // calculates volume of a sphere
9 inline double sphereVolume(const double radius)
10 {
11 return 4.0 / 3.0 * PI * pow(radius, 3);
12 } // end inline function sphereVolume
13
14 int main()
15 {

```

```

16 double radiusValue;
17
18 // prompt user for radius
19 cout << "Enter the length of the radius of your sphere: ";
20 cin >> radiusValue; // input radius
21
22 // use radiusValue to calculate volume of sphere and display result
23 cout << "Volume of sphere with radius " << radiusValue
24 << " is " << sphereVolume(radiusValue) << endl;
25 } // end main

```

```

Enter the length of the radius of your sphere: 2
Volume of sphere with radius 2 is 33.5103

```

## Exercises

**15.5** Write a C++ program that prompts the user for the radius of a circle, then calls inline function `circleArea` to calculate the area of that circle.

**15.6** Write a complete C++ program with the two alternate functions specified below, each of which simply triples the variable `count` defined in `main`. Then compare and contrast the two approaches. These two functions are

- a) function `tripleByValue` that passes a copy of `count` by value, triples the copy and returns the new value and
- a) function `tripleByReference` that passes `count` by reference via a reference parameter and triples the original value of `count` through its alias (i.e., the reference parameter).

**15.7** What is the purpose of the unary scope resolution operator?

**15.8** Write a program that uses a function template called `min` to determine the smaller of two arguments. Test the program using integer, character and floating-point number arguments.

**15.9** Write a program that uses a function template called `max` to determine the larger of two arguments. Test the program using integer, character and floating-point number arguments.

**15.10** Determine whether the following program segments contain errors. For each error, explain how it can be corrected. [Note: For a particular program segment, it's possible that no errors are present in the segment.]

- a) 

```
template < class A >
int sum(int num1, int num2, int num3)
{
 return num1 + num2 + num3;
}
```
- b) 

```
void printResults(int x, int y)
{
 cout << "The sum is " << x + y << '\n';
 return x + y;
}
```
- c) 

```
template < A >
A product(A num1, A num2, A num3)
{
 return num1 * num2 * num3;
}
```
- d) 

```
double cube(int);
int cube(int);
```

# 16

## Introduction to Classes and Objects

*Nothing can have value without being an object of utility.*

—Karl Marx

*Your public servants serve you right.*

—Adlai E. Stevenson

*Knowing how to answer one who speaks,  
To reply to one who sends a message.*

—Amenemopel

### Objectives

In this chapter you'll learn:

- How to define a class and use it to create an object.
- How to define member functions in a class to implement the class's behaviors.
- How to declare data members in a class to implement the class's attributes.
- How to call a member function of an object to perform a task.
- The differences between data members of a class and local variables of a function.
- How to use a constructor to initialize an object's data when the object is created.
- How to engineer a class to separate its interface from its implementation and encourage reuse.



- |                                                                         |                                                                |
|-------------------------------------------------------------------------|----------------------------------------------------------------|
| <b>16.1</b> Introduction                                                | <b>16.6</b> Initializing Objects with Constructors             |
| <b>16.2</b> Classes, Objects, Member Functions and Data Members         | <b>16.7</b> Placing a Class in a Separate File for Reusability |
| <b>16.3</b> Defining a Class with a Member Function                     | <b>16.8</b> Separating Interface from Implementation           |
| <b>16.4</b> Defining a Member Function with a Parameter                 | <b>16.9</b> Validating Data with <i>set</i> Functions          |
| <b>16.5</b> Data Members, <i>set</i> Functions and <i>get</i> Functions | <b>16.10</b> Wrap-Up                                           |

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference*

## 16.1 Introduction

In this chapter, you'll begin writing programs that employ the basic concepts of object-oriented programming that we introduced in Section 15.13. Typically, the programs you develop in C++ will consist of function `main` and one or more classes, each containing data members and member functions. If you become part of a development team in industry, you might work on software systems that contain hundreds, or even thousands, of classes. In this chapter, we develop a simple, well-engineered framework for organizing object-oriented programs in C++.

First, we motivate the notion of classes with a real-world example. Then we present a carefully paced sequence of seven complete working programs to demonstrate creating and using your own classes.

## 16.2 Classes, Objects, Member Functions and Data Members

Let's begin with a simple analogy to help you reinforce your understanding from Section 15.13 of classes and their contents. Suppose you want to drive a car and make it go faster by pressing down on its accelerator pedal. What must happen before you can do this? Well, before you can drive a car, someone has to *design* it and *build* it. A car typically begins as engineering drawings, similar to the blueprints used to design a house. These drawings include the design for an accelerator pedal that the driver will use to make the car go faster. In a sense, the pedal “hides” the complex mechanisms that actually make the car go faster, just as the brake pedal “hides” the mechanisms that slow the car, the steering wheel “hides” the mechanisms that turn the car and so on. This enables people with little or no knowledge of how cars are engineered to drive a car easily, simply by using the accelerator pedal, the brake pedal, the steering wheel, the transmission shifting mechanism and other such simple and user-friendly “interfaces” to the car's complex internal mechanisms.

Unfortunately, you cannot drive the engineering drawings of a car—before you can drive a car, it must be built from the engineering drawings that describe it. A completed car will have an actual accelerator pedal to make the car go faster. But even that's not enough—the car will not accelerate on its own, so the driver must press the accelerator pedal to tell the car to go faster.

Now let's use our car example to introduce the key object-oriented programming concepts of this section. Performing a task in a program requires a function (such as `main`). The function describes the mechanisms that actually perform its tasks. The function hides from its user the complex tasks that it performs, just as the accelerator pedal of a car hides from the driver the complex mechanisms of making the car go faster. In C++, we begin by creating a program unit called a class to house a function, just as a car's engineering drawings house the design of an accelerator pedal. Recall from Section 15.13 that a function belonging to a class is called a member function. In a class, you provide one or more member functions that are designed to perform the class's tasks. For example, a class that represents a bank account might contain one member function to deposit money into the account, another to withdraw money from the account and a third to inquire what the current account balance is.

Just as you cannot drive an engineering drawing of a car, you cannot “drive” a class. Just as someone has to build a car from its engineering drawings before you can actually drive the car, *you must create an object of a class before you can get a program to perform the tasks the class describes*. That is one reason C++ is known as an object-oriented programming language. Note also that just as *many* cars can be built from the same engineering drawing, *many* objects can be built from the same class.

When you drive a car, pressing its gas pedal sends a message to the car to perform a task—that is, make the car go faster. Similarly, you send **messages** to an object—each message is known as a **member-function call** and tells a member function of the object to perform its task. This is often called **requesting a service from an object**.

Thus far, we've used the car analogy to introduce classes, objects and member functions. In addition to the capabilities a car provides, it also has many attributes, such as its color, the number of doors, the amount of gas in its tank, its current speed and its total miles driven (i.e., its odometer reading). Like the car's capabilities, these attributes are represented as part of a car's design in its engineering diagrams. As you drive a car, these attributes are always associated with the car. Every car maintains its own attributes. For example, each car knows how much gas is in its own gas tank, but not how much is in the tanks of other cars. Similarly, an object has attributes that are carried with the object as it's used in a program. These attributes are specified as part of the object's class. For example, a bank account object has a balance attribute that represents the amount of money in the account. Each bank account object knows the balance in the account it represents, but not the balances of the other accounts in the bank. Attributes are specified by the class's data members.

The remainder of this chapter presents seven simple examples that demonstrate the concepts we introduced in the context of the car analogy.

## 16.3 Defining a Class with a Member Function

We begin with an example (Fig. 16.1) that consists of class `GradeBook` (lines 8–16), which will represent a grade book that an instructor can use to maintain student test scores, and a `main` function (lines 19–23) that creates a `GradeBook` object. Function `main` uses this object and its member function to display a message on the screen welcoming the instructor to the grade-book program.

First we describe how to define a class and a member function, then how an object is created and how to call an object's member function. The first few examples contain in

```

1 // Fig. 16.1: fig16_01.cpp
2 // Define class GradeBook with a member function displayMessage,
3 // create a GradeBook object, and call its displayMessage function.
4 #include <iostream>
5 using namespace std;
6
7 // GradeBook class definition
8 class GradeBook
9 {
10 public:
11 // function that displays a welcome message to the GradeBook user
12 void displayMessage()
13 {
14 cout << "Welcome to the Grade Book!" << endl;
15 } // end function displayMessage
16 }; // end class GradeBook
17
18 // function main begins program execution
19 int main()
20 {
21 GradeBook myGradeBook; // create a GradeBook object named myGradeBook
22 myGradeBook.displayMessage(); // call object's displayMessage function
23 } // end main

```

Welcome to the Grade Book!

**Fig. 16.1** | Define class `GradeBook` with a member function `displayMessage`, create a `GradeBook` object and call its `displayMessage` function.

the same file function `main` and the `GradeBook` class it uses. Later in the chapter, we introduce more sophisticated ways to structure programs for better software engineering.

### ***Class `GradeBook`***

Before function `main` (lines 19–23) can create a `GradeBook` object, we must tell the compiler what member functions and data members belong to the class—known as **defining a class**. The `GradeBook` **class definition** (lines 8–16) begins with keyword `class` and contains a member function called `displayMessage` (lines 12–15) that displays a message on the screen (line 14). Recall that a class is like a blueprint—so we need to make an object of class `GradeBook` (line 21) and call its `displayMessage` member function (line 22) to get line 14 to execute and display the welcome message. We’ll soon explain lines 21–22 in detail.

The class definition begins in line 8 with the keyword `class` followed by the class name `GradeBook`. By convention, the name of a user-defined class begins with a capital letter, and for readability, each subsequent word in the class name begins with a capital letter. This capitalization style is often referred to as **camel case**, because the pattern of uppercase and lowercase letters resembles the silhouette of a camel.

Every class’s **body** is enclosed in a pair of left and right braces (`{` and `}`), as in lines 9 and 16. The class definition terminates with a semicolon (line 16).



### **Common Programming Error 16.1**

*Forgetting the semicolon at the end of a class definition is a syntax error.*



Recall that the function `main` is always called automatically when you execute a program. Most functions do not get called automatically. As you'll soon see, you must call member function `displayMessage` explicitly to tell it to perform its task.

Line 10 contains the **access-specifier label** `public:`. The keyword `public` is an **access specifier**. Lines 12–15 define member function `displayMessage`. This member function appears after access specifier `public:` to indicate that the function is “available to the public”—that is, it can be called by other functions in the program (such as `main`), and by member functions of other classes (if there are any). Access specifiers are always followed by a colon (:). For the remainder of the text, when we refer to the access specifier `public`, we'll omit the colon as we did in this sentence. Section 16.5 introduces a second access specifier, `private`. Later in the book we'll study the access specifier `protected`.

Each function in a program performs a task and may return a value when it completes its task—for example, a function might perform a calculation, then return the result of that calculation. When you define a function, you must specify a **return type** to indicate the type of the value returned by the function when it completes its task. In line 12, keyword `void` to the left of the function name `displayMessage` is the function's return type. Return type `void` indicates that `displayMessage` will *not* return (i.e., give back) any data to its **calling function** (in this example, `main`, as we'll see in a moment) when it completes its task. In Fig. 16.5, you'll see an example of a function that returns a value.

The name of the member function, `displayMessage`, follows the return type. By convention, function names begin with a lowercase first letter and all subsequent words in the name begin with a capital letter. The parentheses after the member function name indicate that this is a function. An empty set of parentheses, as shown in line 12, indicates that this member function does not require additional data to perform its task. You'll see an example of a member function that does require additional data in Section 16.4. Line 12 is commonly referred to as the **function header**. Every function's body is delimited by left and right braces (`{` and `}`), as in lines 13 and 15.

The body of a function contains statements that perform the function's task. In this case, member function `displayMessage` contains one statement (line 14) that displays the message “Welcome to the Grade Book!”. After this statement executes, the function has completed its task.



### Common Programming Error 16.2

*Returning a value from a function whose return type has been declared `void` is a compilation error.*



### Common Programming Error 16.3

*Defining a function inside another function (i.e., “nesting” functions) is a syntax error.*

## Testing Class `GradeBook`

Next, we'd like to use class `GradeBook` in a program. As you know, function `main` (lines 19–23) begins the execution of every program.


In this program, we'd like to call class `GradeBook`'s `displayMessage` member function to display the welcome message. Typically, you cannot call a member function of a class until you create an object of that class. (As you'll learn in Section 18.6, **static member**

functions are an exception.) Line 21 creates an object of class `GradeBook` called `myGradeBook`. The variable's type is `GradeBook`—the class we defined in lines 8–16. When we declare variables of type `int`, the compiler knows what `int` is—it's a fundamental type. In line 21, however, the compiler does not automatically know what type `GradeBook` is—it's a **user-defined type**. We tell the compiler what `GradeBook` is by including the class definition (lines 8–16). If we omitted these lines, the compiler would issue an error message (such as “`'GradeBook': undeclared identifier`” in Microsoft Visual C++ or “`'GradeBook': undeclared`” in GNU C++). Each class you create becomes a new type that can be used to create objects. You can define new class types as needed; this is one reason why C++ is known as an **extensible language**.

Line 22 calls the member function `displayMessage` (defined in lines 12–15) using variable `myGradeBook` followed by the **dot operator** (`.`), the function name `displayMessage` and an empty set of parentheses. This call causes the `displayMessage` function to perform its task. At the beginning of line 22, “`myGradeBook.`” indicates that `main` should use the `GradeBook` object that was created in line 21. The empty parentheses in line 12 indicate that member function `displayMessage` does not require additional data to perform its task, which is why we called this function with empty parentheses in line 22. (In Section 16.4, you'll see how to pass data to a function.) When `displayMessage` completes its task, the program reaches the end of `main` and terminates.

### *UML Class Diagram for Class `GradeBook`*

Recall from Section 15.13 that the UML is a standardized graphical language used by software developers to represent their object-oriented systems. In the UML, each class is modeled in a **UML class diagram** as a rectangle with three compartments. Figure 16.2 presents a class diagram for class `GradeBook` (Fig. 16.1). The top compartment contains the class's name centered horizontally and in boldface type. The middle compartment contains the class's attributes, which correspond to data members in C++. This compartment is currently empty, because class `GradeBook` does not have any attributes. (Section 16.5 presents a version of class `GradeBook` with an attribute.) The bottom compartment contains the class's operations, which correspond to member functions in C++. The UML models operations by listing the operation name followed by a set of parentheses. Class `GradeBook` has only one member function, `displayMessage`, so the bottom compartment of Fig. 16.2 lists one operation with this name. Member function `displayMessage` does not require additional information to perform its tasks, so the parentheses following `displayMessage` in the class diagram are empty, just as they are in the member function's header in line 12 of Fig. 16.1. The plus sign (+) in front of the operation name indicates that `displayMessage` is a public operation in the UML (i.e., a `public` member function in C++).



**Fig. 16.2** | UML class diagram indicating that class `GradeBook` has a public `displayMessage` operation.



## 16.4 Defining a Member Function with a Parameter

In our car analogy from Section 16.2, we mentioned that pressing a car's gas pedal sends a message to the car to perform a task—make the car go faster. But how fast should the car accelerate? As you know, the farther down you press the pedal, the faster the car accelerates. So the message to the car includes both the task to perform and additional information that helps the car perform the task. This additional information is known as a **parameter**—the value of the parameter helps the car determine how fast to accelerate. Similarly, a member function can require one or more parameters that represent additional data it needs to perform its task. A function call supplies values—called **arguments**—for each of the function's parameters. For example, to make a deposit into a bank account, suppose a `deposit` member function of an `Account` class specifies a parameter that represents the deposit amount. When the `deposit` member function is called, an argument value representing the deposit amount is copied to the member function's parameter. The member function then adds that amount to the account balance.

### *Defining and Testing Class `GradeBook`*

Our next example (Fig. 16.3) redefines class `GradeBook` (lines 9–18) with a `displayMessage` member function (lines 13–17) that displays the course name as part of the welcome message. The new version of `displayMessage` requires a parameter (`courseName` in line 13) that represents the course name to output.

---

```

1 // Fig. 16.3: fig16_03.cpp
2 // Define class GradeBook with a member function that takes a parameter;
3 // Create a GradeBook object and call its displayMessage function.
4 #include <iostream>
5 #include <string> // program uses C++ standard string class
6 using namespace std;
7
8 // GradeBook class definition
9 class GradeBook
10 {
11 public:
12 // function that displays a welcome message to the GradeBook user
13 void displayMessage(string courseName)
14 {
15 cout << "Welcome to the grade book for\n" << courseName << "!"
16 << endl;
17 } // end function displayMessage
18 }; // end class GradeBook
19
20 // function main begins program execution
21 int main()
22 {
23 string nameOfCourse; // string of characters to store the course name
24 GradeBook myGradeBook; // create a GradeBook object named myGradeBook
25

```

---

**Fig. 16.3** | Define class `GradeBook` with a member function that takes a parameter, create a `GradeBook` object and call its `displayMessage` function. (Part I of 2.)

```
26 // prompt for and input course name
27 cout << "Please enter the course name:" << endl;
28 getline(cin, nameOfCourse); // read a course name with blanks
29 cout << endl; // output a blank line
30
31 // call myGradeBook's displayMessage function
32 // and pass nameOfCourse as an argument
33 myGradeBook.displayMessage(nameOfCourse);
34 } // end main
```

```
Please enter the course name:
CS101 Introduction to C++ Programming

Welcome to the grade book for
CS101 Introduction to C++ Programming!
```

**Fig. 16.3** | Define class `GradeBook` with a member function that takes a parameter, create a `GradeBook` object and call its `displayMessage` function. (Part 2 of 2.)

Before discussing the new features of class `GradeBook`, let's see how the new class is used in `main` (lines 21–34). Line 23 creates a variable of type `string` called `nameOfCourse` that will be used to store the course name entered by the user. A variable of type `string` represents a string of characters such as "CS101 Introduction to C++ Programming". A `string` is actually an object of the C++ Standard Library class `string`. This class is defined in [header file `<string>`](#), and the name `string`, like `cout`, belongs to namespace `std`. To enable line 23 to compile, line 5 includes the `<string>` header file. The using declaration in line 6 allows us to simply write `string` in line 23 rather than `std::string`. For now, you can think of `string` variables like variables of other types such as `int`. You'll learn additional `string` capabilities in Section 16.9.

Line 24 creates an object of class `GradeBook` named `myGradeBook`. Line 27 prompts the user to enter a course name. Line 28 reads the name from the user and assigns it to the `nameOfCourse` variable, using the library function `getline` to perform the input. Before we explain this line of code, let's explain why we cannot simply write

```
cin >> nameOfCourse;
```

to obtain the course name. In our sample program execution, we use the course name "CS101 Introduction to C++ Programming," which contains multiple words. (Recall that we highlight user-supplied input in bold.) When `cin` is used with the stream extraction operator, it reads characters until the first white-space character is reached. Thus, only "CS101" would be read by the preceding statement. The rest of the course name would have to be read by subsequent input operations.

In this example, we'd like the user to type the complete course name and press *Enter* to submit it to the program, and we'd like to store the entire course name in the `string` variable `nameOfCourse`. The function call `getline( cin, nameOfCourse )` in line 28 reads characters (including the space characters that separate the words in the input) from the standard input stream object `cin` (i.e., the keyboard) until the newline character is encountered, places the characters in the `string` variable `nameOfCourse` and discards the newline character. When you press *Enter* while typing program input, a newline is inserted in the

input stream. Also, the `<string>` header file must be included in the program to use function `getline` and that the name `getline` belongs to namespace `std`.

Line 33 calls `myGradeBook`'s `displayMessage` member function. The `nameOfCourse` variable in parentheses is the argument that is passed to member function `displayMessage` so that it can perform its task. The value of variable `nameOfCourse` in `main` becomes the value of member function `displayMessage`'s parameter `courseName` in line 13. When you execute this program, member function `displayMessage` outputs as part of the welcome message the course name you type (in our sample execution, `CS101 Introduction to C++ Programming`).

### *More on Arguments and Parameters*

To specify that a function requires data to perform its task, you place additional information in the function's **parameter list**, which is located in the parentheses following the function name. The parameter list may contain any number of parameters, including none at all (represented by empty parentheses as in Fig. 16.1, line 12) to indicate that a function does not require any parameters. Member function `displayMessage`'s parameter list (Fig. 16.3, line 13) declares that the function requires one parameter. Each parameter must specify a type and an identifier. In this case, the type `string` and the identifier `courseName` indicate that member function `displayMessage` requires a `string` to perform its task. The member function body uses the parameter `courseName` to access the value that is passed to the function in the function call (line 33 in `main`). Lines 15–16 display parameter `courseName`'s value as part of the welcome message. The parameter variable's name (line 13) can be the same as or different from the argument variable's name (line 33).

A function can specify multiple parameters by separating each parameter from the next with a comma. The number and order of arguments in a function call must match the number and order of parameters in the parameter list of the called member function's header. Also, the argument types in the function call must be consistent with the types of the corresponding parameters in the function header. (As you'll learn in subsequent chapters, an argument's type and its corresponding parameter's type need not always be identical, but they must be "consistent.") In our example, the one `string` argument in the function call (i.e., `nameOfCourse`) exactly matches the one `string` parameter in the member-function definition (i.e., `courseName`).



#### **Common Programming Error 16.4**

*Placing a semicolon after the right parenthesis enclosing the parameter list of a function definition is a syntax error.*



#### **Common Programming Error 16.5**

*Defining a function parameter again as a variable in the function's body is a compilation error.*



#### **Good Programming Practice 16.1**

*To avoid ambiguity, do not use the same names for the arguments passed to a function and the corresponding parameters in the function definition.*




### Good Programming Practice 16.2

*Choosing meaningful function names and meaningful parameter names makes programs more readable and helps avoid excessive use of comments.*

#### Updated UML Class Diagram for Class **GradeBook**

The UML class diagram of Fig. 16.4 models class **GradeBook** of Fig. 16.3. Like the class **GradeBook** defined in Fig. 16.1, this **GradeBook** class contains public member function `displayMessage`. However, this version of `displayMessage` has a parameter. The UML models a parameter by listing the parameter name, followed by a colon and the parameter type in the parentheses following the operation name. The UML has its own data types similar to those of C++. The UML is language independent—it's used with many different programming languages—so its terminology does not exactly match that of C++. For example, the UML type `String` corresponds to the C++ type `string`. Member function `displayMessage` of class **GradeBook** (Fig. 16.3, lines 13–17) has a `string` parameter named `courseName`, so Fig. 16.4 lists `courseName : String` between the parentheses following the operation name `displayMessage`. This version of the **GradeBook** class still does not have any data members.



**Fig. 16.4** | UML class diagram indicating that class **GradeBook** has a public `displayMessage` operation with a `courseName` parameter of UML type `String`.

## 16.5 Data Members, set Functions and get Functions

Variables declared in a function definition's body are known as **local variables** and can be used only from the line of their declaration in the function to closing right brace (`}`) of the block in which they're declared. A local variable must be declared before it can be used in a function. A local variable cannot be accessed outside the function in which it's declared. When a function terminates, the values of its local variables are lost. Recall from Section 16.2 that an object has attributes that are carried with it as it's used in a program. Such attributes exist throughout the life of the object.

A class normally consists of one or more member functions that manipulate the attributes that belong to a particular object of the class. Attributes are represented as variables in a class definition. Such variables are called **data members** and are declared inside a class definition but outside the bodies of the class's member-function definitions. Each object of a class maintains its own copy of its attributes in memory. The example in this section demonstrates a **GradeBook** class that contains a `courseName` data member to represent a particular **GradeBook** object's course name.

**GradeBook Class with a Data Member, a set Function and a get Function**

In our next example, class `GradeBook` (Fig. 16.5) maintains the course name as a data member so that it can be used or modified at any time during a program's execution. The class contains member functions `setCourseName`, `getCourseName` and `displayMessage`. Member function `setCourseName` stores a course name in a `GradeBook` data member. Member function `getCourseName` obtains the course name from that data member. Member function `displayMessage`—which now specifies no parameters—still displays a welcome message that includes the course name. However, as you'll see, the function now obtains the course name by calling another function in the same class—`getCourseName`.

**Good Programming Practice 16.3**

*Place a blank line between member-function definitions to enhance program readability.*

A typical instructor teaches multiple courses, each with its own course name. Line 34 declares that `courseName` is a variable of type `string`. Because the variable is declared in the class definition (lines 10–35) but outside the bodies of the class's member-function definitions (lines 14–17, 20–23 and 26–32), the variable is a data member. Every instance (i.e., object) of class `GradeBook` contains one copy of each of the class's data members—if there are two `GradeBook` objects, each has its own copy of `courseName` (one per object), as you'll see in the example of Fig. 16.7. A benefit of making `courseName` a data member is that all the member functions of the class (in this case, class `GradeBook`) can manipulate any data members that appear in the class definition (in this case, `courseName`).

---

```

1 // Fig. 16.5: fig16_05.cpp
2 // Define class GradeBook that contains a courseName data member
3 // and member functions to set and get its value;
4 // Create and manipulate a GradeBook object with these functions.
5 #include <iostream>
6 #include <string> // program uses C++ standard string class
7 using namespace std;
8
9 // GradeBook class definition
10 class GradeBook
11 {
12 public:
13 // function that sets the course name
14 void setCourseName(string name)
15 {
16 courseName = name; // store the course name in the object
17 } // end function setCourseName
18
19 // function that gets the course name
20 string getCourseName()
21 {
22 return courseName; // return the object's courseName
23 } // end function getCourseName

```

---

**Fig. 16.5** | Defining and testing class `GradeBook` with a data member and *set* and *get* functions. (Part I of 2.)

```

24
25 // function that displays a welcome message
26 void displayMessage()
27 {
28 // this statement calls getCourseName to get the
29 // name of the course this GradeBook represents
30 cout << "Welcome to the grade book for\n" << getCourseName() << "!"
31 << endl;
32 } // end function displayMessage
33 private:
34 string courseName; // course name for this GradeBook
35 }; // end class GradeBook
36
37 // function main begins program execution
38 int main()
39 {
40 string nameOfCourse; // string of characters to store the course name
41 GradeBook myGradeBook; // create a GradeBook object named myGradeBook
42
43 // display initial value of courseName
44 cout << "Initial course name is: " << myGradeBook.getCourseName()
45 << endl;
46
47 // prompt for, input and set course name
48 cout << "\nPlease enter the course name:" << endl;
49 getline(cin, nameOfCourse); // read a course name with blanks
50 myGradeBook.setCourseName(nameOfCourse); // set the course name
51
52 cout << endl; // outputs a blank line
53 myGradeBook.displayMessage(); // display message with new course name
54 } // end main

```

Initial course name is:

Please enter the course name:

**CS101 Introduction to C++ Programming**

Welcome to the grade book for  
CS101 Introduction to C++ Programming!

**Fig. 16.5** | Defining and testing class GradeBook with a data member and set and get functions. (Part 2 of 2.)

### *Access Specifiers **public** and **private***

Most data-member declarations appear after the access-specifier label **private**: (line 33). Like **public**, keyword **private** is an access specifier. Variables or functions declared after access specifier **private** (and before the next access specifier) are accessible only to member functions of the class for which they're declared. Thus, data member `courseName` can be used only in member functions `setCourseName`, `getCourseName` and `displayMessage` of (every object of) class `GradeBook`. Data member `courseName`, because it's **private**, cannot be accessed by functions outside the class (such as `main`) or by member functions of other classes in the program. Attempting to access data member `courseName` in one of these pro-

gram locations with an expression such as `myGradeBook.courseName` would result in a compilation error containing a message similar to

```
cannot access private member declared in class 'GradeBook'
```



### Software Engineering Observation 16.1

*Generally, data members should be declared private and member functions should be declared public. (We'll see that it's appropriate to declare certain member functions private, if they're to be accessed only by other member functions of the class.)*



### Common Programming Error 16.6

*An attempt by a function, which is not a member of a particular class (or a friend of that class, as we'll see in Chapter 18, *Classes: A Deeper Look, Part 2*), to access a private member of that class is a compilation error.*

The default access for class members is `private` so all members after the class header and before the first access specifier are `private`. The access specifiers `public` and `private` may be repeated, but this is unnecessary and can be confusing.



### Good Programming Practice 16.4

*Despite the fact that the `public` and `private` access specifiers may be repeated and intermixed, list all the `public` members of a class first in one group then list all the `private` members in another group. This focuses the programmer's attention on the class's `public` interface, rather than on the class's implementation.*



### Good Programming Practice 16.5

*If you choose to list the `private` members first in a class definition, explicitly use the `private` access specifier despite the fact that `private` is assumed by default. This improves program clarity.*

Declaring data members with access specifier `private` is known as **data hiding**. When a program creates (instantiates) a `GradeBook` object, data member `courseName` is encapsulated (hidden) in the object and can be accessed only by member functions of the object's class. In class `GradeBook`, member functions `setCourseName` and `getCourseName` manipulate the data member `courseName` directly (and `displayMessage` could do so if necessary).



### Software Engineering Observation 16.2

*You'll learn in Chapter 18 that functions and classes declared by a class to be "friends" can access the private members of the class.*



### Error-Prevention Tip 16.1

*Making the data members of a class `private` and the member functions of the class `public` facilitates debugging because problems with data manipulations are localized to either the class's member functions or the friends of the class.*

## Member Functions `setCourseName` and `getCourseName`

Member function `setCourseName` (defined in lines 14–17) does not return any data when it completes its task, so its return type is `void`. The member function receives one param-

eter—name—which represents the course name that will be passed to it as an argument (as we'll see in line 50 of main). Line 16 assigns name to data member `courseName`. In this example, `setCourseName` does not attempt to validate the course name—i.e., the function does not check that the course name adheres to any particular format or follows any other rules regarding what a “valid” course name looks like. Suppose, for instance, that a university can print student transcripts containing course names of only 25 characters or fewer. In this case, we might want class `GradeBook` to ensure that its data member `courseName` never contains more than 25 characters. We discuss basic validation techniques in Section 16.9.

Member function `getCourseName` (defined in lines 20–23) returns a particular `GradeBook` object's `courseName`. The member function has an empty parameter list, so it does not require additional data to perform its task. The function specifies that it returns a string. When a function that specifies a return type other than `void` is called and completes its task, the function uses a **return statement** (as in line 22) to return a result to its calling function. For example, when you go to an automated teller machine (ATM) and request your account balance, you expect the ATM to give you back a value that represents your balance. Similarly, when a statement calls member function `getCourseName` on a `GradeBook` object, the statement expects to receive the `GradeBook`'s course name (in this case, a string, as specified by the function's return type). If you have a function `square` that returns the square of its argument, the statement

```
result = square(2);
```

returns 4 from function `square` and assigns to variable `result` the value 4. If you have a function `maximum` that returns the largest of three integer arguments, the statement

```
biggest = maximum(27, 114, 51);
```

returns 114 from function `maximum` and assigns to variable `biggest` the value 114.



### Common Programming Error 16.7

*Forgetting to return a value from a function that is supposed to return a value is a compilation error.*

The statements in lines 16 and 22 each use variable `courseName` (line 34) even though it was not declared in any of the member functions. We can use `courseName` in the member functions of class `GradeBook` because `courseName` is a data member of the class. So member function `getCourseName` could be defined before member function `setCourseName`.

### Member Function `displayMessage`

Member function `displayMessage` (lines 26–32) does not return any data when it completes its task, so its return type is `void`. The function does not receive parameters, so its parameter list is empty. Lines 30–31 output a welcome message that includes the value of data member `courseName`. Line 30 calls member function `getCourseName` to obtain the value of `courseName`. Member function `displayMessage` could also access data member `courseName` directly, just as member functions `setCourseName` and `getCourseName` do. We explain shortly why we choose to call member function `getCourseName` to obtain the value of `courseName`.



*Testing Class GradeBook*

The main function (lines 38–54) creates one object of class `GradeBook` and uses each of its member functions. Line 41 creates a `GradeBook` object named `myGradeBook`. Lines 44–45 display the initial course name by calling the object's `getCourseName` member function. The first line of the output does not show a course name, because the object's `courseName` data member (i.e., a string) is initially empty—by default, the initial value of a string is the so-called **empty string**, i.e., a string that does not contain any characters. Nothing appears on the screen when an empty string is displayed.

Line 48 prompts the user to enter a course name. Local string variable `nameOfCourse` (declared in line 40) is set to the course name entered by the user, which is obtained by the call to the `getline` function (line 49). Line 50 calls object `myGradeBook`'s `setCourseName` member function and supplies `nameOfCourse` as the function's argument. When the function is called, the argument's value is copied to parameter `name` (line 14) of member function `setCourseName`. Then the parameter's value is assigned to data member `courseName` (line 16). Line 52 skips a line; then line 53 calls object `myGradeBook`'s `displayMessage` member function to display the welcome message containing the course name.

*Software Engineering with Set and Get Functions*

A class's private data members can be manipulated only by member functions of that class (and by “friends” of the class, as we'll see in Chapter 18). So a **client of an object**—that is, any class or function that calls the object's member functions from outside the object—calls the class's `public` member functions to request the class's services for particular objects of the class. This is why the statements in function `main` call member functions `setCourseName`, `getCourseName` and `displayMessage` on a `GradeBook` object. Classes often provide `public` member functions to allow clients of the class to **set** (i.e., assign values to) or **get** (i.e., obtain the values of) private data members. These member function names need not begin with `set` or `get`, but this naming convention is common. In this example, the member function that *sets* the `courseName` data member is called `setCourseName`, and the member function that *gets* the value of the `courseName` data member is called `getCourseName`. *Set* functions are also sometimes called **mutators** (because they mutate, or change, values), and *get* functions are also sometimes called **accessors** (because they access values).

Recall that declaring data members with access specifier `private` enforces data hiding. Providing `public` *set* and *get* functions allows clients of a class to access the hidden data, but only *indirectly*. The client knows that it's attempting to modify or obtain an object's data, but the client does not know how the object performs these operations. In some cases, a class may internally represent a piece of data one way, but expose that data to clients in a different way. For example, suppose a `Clock` class represents the time of day as a `private int` data member `time` that stores the number of seconds since midnight. However, when a client calls a `Clock` object's `getTime` member function, the object could return the time with hours, minutes and seconds in a string in the format “HH:MM:SS”. Similarly, suppose the `Clock` class provides a *set* function named `setTime` that takes a string parameter in the “HH:MM:SS” format. Using string class capabilities, the `setTime` function could convert this string to a number of seconds, which the function stores in its private data member. The *set* function could also check that the value it receives represents a valid time (e.g., “12:30:45” is valid but “42:85:70” is not). The *set* and *get* func-

tions allow a client to interact with an object, but the object's private data remains safely encapsulated (i.e., hidden) in the object itself.

The *set* and *get* functions of a class also should be used by other member functions within the class to manipulate the class's private data, although these member functions *can* access the private data directly. In Fig. 16.5, member functions `setCourseName` and `getCourseName` are public member functions, so they're accessible to clients of the class, as well as to the class itself. Member function `displayMessage` calls member function `getCourseName` to obtain the value of data member `courseName` for display purposes, even though `displayMessage` can access `courseName` directly—accessing a data member via its *get* function creates a better, more robust class (i.e., a class that is easier to maintain and less likely to stop working). If we decide to change the data member `courseName` in some way, the `displayMessage` definition will not require modification—only the bodies of the *get* and *set* functions that directly manipulate the data member will need to change. For example, suppose we want to represent the course name as two separate data members—`courseNumber` (e.g., "CS101") and `courseTitle` (e.g., "Introduction to C++ Programming"). Member function `displayMessage` can still issue a single call to member function `getCourseName` to obtain the full course name to display as part of the welcome message. In this case, `getCourseName` would need to build and return a string containing the `courseNumber` followed by the `courseTitle`. Member function `displayMessage` would continue to display the complete course title "CS101 Introduction to C++ Programming," because it's unaffected by the change to the class's data members. The benefits of calling a *set* function from another member function of a class will become clear when we discuss validation in Section 16.9.



#### Good Programming Practice 16.6

*Always try to localize the effects of changes to a class's data members by accessing and manipulating the data members through their *get* and *set* functions. Changes to the name of a data member or the data type used to store a data member then affect only the corresponding *get* and *set* functions, but not the callers of those functions.*



#### Software Engineering Observation 16.3

*Write programs that are understandable and easy to maintain. Change is the rule rather than the exception. You should anticipate that your code will be modified.*




#### Software Engineering Observation 16.4

*Provide *set* or *get* functions for each private data item only when appropriate. Services useful to the client should typically be provided in the class's *public* interface.*

#### **GradeBook's UML Class Diagram with a Data Member and *set* and *get* Functions**

Figure 16.6 contains an updated UML class diagram for the version of class `GradeBook` in Fig. 16.5. This diagram models `GradeBook`'s data member `courseName` as an attribute in the middle compartment. The UML represents data members as attributes by listing the attribute name, followed by a colon and the attribute type. The UML type of attribute `courseName` is `String`, which corresponds to `string` in C++. Data member `courseName` is private in C++, so the class diagram lists a minus sign (-) in front of the corresponding

attribute's name. The minus sign in the UML is equivalent to the `private` access specifier in C++. Class `GradeBook` contains three `public` member functions, so the class diagram lists three operations in the third compartment. Operation `setCourseName` has a `String` parameter called `name`. The UML indicates the return type of an operation by placing a colon and the return type after the parentheses following the operation name. Member function `getCourseName` of class `GradeBook` has a `string` return type in C++, so the class diagram shows a `String` return type in the UML. Operations `setCourseName` and `displayMessage` do not return values (i.e., they return `void`), so the UML class diagram does not specify a return type after the parentheses of these operations.



**Fig. 16.6** | UML class diagram for class `GradeBook` with a private `courseName` attribute and public operations `setCourseName`, `getCourseName` and `displayMessage`.

## 16.6 Initializing Objects with Constructors

As mentioned in Section 16.5, when an object of class `GradeBook` (Fig. 16.5) is created, its data member `courseName` is initialized to the empty string by default. What if you want to provide a course name when you create a `GradeBook` object? Each class you declare can provide a **constructor** that can be used to initialize an object of the class when the object is created. A constructor is a special member function that must be defined with the same name as the class, so that the compiler can distinguish it from the class's other member functions. An important difference between constructors and other functions is that constructors cannot return values, so they cannot specify a return type (not even `void`). Normally, constructors are declared `public`.

C++ requires a constructor call for each object that is created, which helps ensure that each object is initialized before it's used in a program. The constructor call occurs implicitly when the object is created. If a class does not explicitly include a constructor, the compiler provides a **default constructor**—that is, a constructor with no parameters. For example, when line 41 of Fig. 16.5 creates a `GradeBook` object, the default constructor is called. The default constructor provided by the compiler creates a `GradeBook` object without giving any initial values to the object's fundamental type data members. [Note: For data members that are objects of other classes, the default constructor implicitly calls each data member's default constructor to ensure that the data member is initialized properly. This is why the `string` data member `courseName` (in Fig. 16.5) was initialized to the empty string—the default constructor for class `string` sets the `string`'s value to the empty string. You'll learn more about initializing data members that are objects of other classes in Section 18.3.]

In the example of Fig. 16.7, we specify a course name for a `GradeBook` object when the object is created (e.g., line 46). In this case, the argument "CS101 Introduction to C++

Programming" is passed to the GradeBook object's constructor (lines 14–17) and used to initialize the `courseName`. Figure 16.7 defines a modified GradeBook class containing a constructor with a `string` parameter that receives the initial course name.

---

```

1 // Fig. 16.7: fig16_07.cpp
2 // Instantiating multiple objects of the GradeBook class and using
3 // the GradeBook constructor to specify the course name
4 // when each GradeBook object is created.
5 #include <iostream>
6 #include <string> // program uses C++ standard string class
7 using namespace std;
8
9 // GradeBook class definition
10 class GradeBook
11 {
12 public:
13 // constructor initializes courseName with string supplied as argument
14 GradeBook(string name)
15 {
16 setCourseName(name); // call set function to initialize courseName
17 } // end GradeBook constructor
18
19 // function to set the course name
20 void setCourseName(string name)
21 {
22 courseName = name; // store the course name in the object
23 } // end function setCourseName
24
25 // function to get the course name
26 string getCourseName()
27 {
28 return courseName; // return object's courseName
29 } // end function getCourseName
30
31 // display a welcome message to the GradeBook user
32 void displayMessage()
33 {
34 // call getCourseName to get the courseName
35 cout << "Welcome to the grade book for\n" << getCourseName()
36 << "!" << endl;
37 } // end function displayMessage
38 private:
39 string courseName; // course name for this GradeBook
40 }; // end class GradeBook
41
42 // function main begins program execution
43 int main()
44 {
45 // create two GradeBook objects
46 GradeBook gradeBook1("CS101 Introduction to C++ Programming");
47 GradeBook gradeBook2("CS102 Data Structures in C++");

```

---

**Fig. 16.7** | Instantiating multiple objects of the GradeBook class and using the GradeBook constructor to specify the course name when each GradeBook object is created. (Part 1 of 2.)

```

48
49 // display initial value of courseName for each GradeBook
50 cout << "gradeBook1 created for course: " << gradeBook1.getCourseName()
51 << "\ngradeBook2 created for course: " << gradeBook2.getCourseName()
52 << endl;
53 } // end main

```

```

gradeBook1 created for course: CS101 Introduction to C++ Programming
gradeBook2 created for course: CS102 Data Structures in C++

```

**Fig. 16.7** | Instantiating multiple objects of the `GradeBook` class and using the `GradeBook` constructor to specify the course name when each `GradeBook` object is created. (Part 2 of 2.)

### *Defining a Constructor*

Lines 14–17 of Fig. 16.7 define a constructor for class `GradeBook`. Notice that the constructor has the same name as its class, `GradeBook`. A constructor specifies in its parameter list the data it requires to perform its task. When you create a new object, you place this data in the parentheses that follow the object name (as we did in lines 46–47). Line 14 indicates that class `GradeBook`'s constructor has a `string` parameter called `name`. Line 14 does not specify a return type, because constructors cannot return values (or even `void`).

Line 16 in the constructor's body passes the constructor's parameter name to member function `setCourseName` (lines 20–23), which simply assigns the value of its parameter to data member `courseName`. You might be wondering why we bother making the call to `setCourseName` in line 16—the constructor certainly could perform the assignment `courseName = name`. In Section 16.9, we modify `setCourseName` to perform validation (ensuring that, in this case, the `courseName` is 25 or fewer characters in length). At that point the benefits of calling `setCourseName` from the constructor will become clear. Both the constructor (line 14) and the `setCourseName` function (line 20) use a parameter called `name`. You can use the same parameter names in different functions because the parameters are local to each function; they do not interfere with one another.

### *Testing Class `GradeBook`*

Lines 43–53 of Fig. 16.7 define the `main` function that tests class `GradeBook` and demonstrates initializing `GradeBook` objects using a constructor. Line 46 creates and initializes a `GradeBook` object called `gradeBook1`. When this line executes, the `GradeBook` constructor (lines 14–17) is called (implicitly by C++) with the argument "CS101 Introduction to C++ Programming" to initialize `gradeBook1`'s course name. Line 47 repeats this process for the `GradeBook` object called `gradeBook2`, this time passing the argument "CS102 Data Structures in C++" to initialize `gradeBook2`'s course name. Lines 50–51 use each object's `getCourseName` member function to obtain the course names and show that they were indeed initialized when the objects were created. The output confirms that each `GradeBook` object maintains its own copy of data member `courseName`.

### *Two Ways to Provide a Default Constructor for a Class*

Any constructor that takes no arguments is called a default constructor. A class gets a default constructor in one of two ways:

1. The compiler implicitly creates a default constructor in a class that does not define a constructor. Such a constructor does not initialize the class's data members, but does call the default constructor for each data member that is an object of another class. An uninitialized variable typically contains a “garbage” value.
2. You explicitly define a constructor that takes no arguments. Such a default constructor will call the default constructor for each data member that is an object of another class and will perform additional initialization specified by you.

If you define a constructor *with* arguments, C++ will not implicitly create a default constructor for that class. For each version of class `GradeBook` in Fig. 16.1, Fig. 16.3 and Fig. 16.5 the compiler implicitly defined a default constructor.



### Error-Prevention Tip 16.2

*Unless no initialization of your class's data members is necessary (almost never), provide a constructor to ensure that your class's data members are initialized with meaningful values when each new object of your class is created.*




### Software Engineering Observation 16.5

*Data members can be initialized in a constructor, or their values may be set later after the object is created. However, it's a good software engineering practice to ensure that an object is fully initialized before the client code invokes the object's member functions. You should not rely on the client code to ensure that an object gets initialized properly.*

### Adding the Constructor to Class `GradeBook`'s UML Class Diagram

The UML class diagram of Fig. 16.8 models class `GradeBook` of Fig. 16.7, which has a constructor with a name parameter of type `string` (represented by type `String` in the UML). Like operations, the UML models constructors in the third compartment of a class in a class diagram. To distinguish a constructor from a class's operations, the UML places the word “constructor” between guillemets (« and ») before the constructor's name. It's customary to list the class's constructor before other operations in the third compartment.



**Fig. 16.8** | UML class diagram indicating that class `GradeBook` has a constructor with a name parameter of UML type `String`.

## 16.7 Placing a Class in a Separate File for Reusability

One of the benefits of creating class definitions is that, when packaged properly, our classes can be reused by programmers—potentially worldwide. For example, we can reuse C++

Standard Library type `string` in any C++ program by including the header file `<string>` (and, as we'll see, by being able to link to the library's object code).

Programmers who wish to use our `GradeBook` class cannot simply include the file from Fig. 16.7 in another program. As you know, function `main` begins the execution of every program, and every program must have exactly one `main` function. If other programmers include the code from Fig. 16.7, they get extra baggage—our `main` function—and their programs will then have two `main` functions. Attempting to compile a program with two `main` functions in Microsoft Visual C++ produces an error such as

```
error C2084: function 'int main(void)' already has a body
```

when the compiler tries to compile the second `main` function it encounters. Similarly, the GNU C++ compiler produces the error

```
redefinition of 'int main()'
```

These errors indicate that a program already has a `main` function. So, placing `main` in the same file with a class definition prevents that class from being reused by other programs. In this section, we demonstrate how to make class `GradeBook` reusable by separating it into another file from the `main` function.

### Header Files

Each of the previous examples in the chapter consists of a single `.cpp` file, also known as a [source-code file](#), that contains a `GradeBook` class definition and a `main` function. When building an object-oriented C++ program, it's customary to define reusable source code (such as a class) in a file that by convention has a `.h` filename extension—known as a [header file](#). Programs use `#include` preprocessor directives to include header files and take advantage of reusable software components, such as type `string` provided in the C++ Standard Library and user-defined types like class `GradeBook`.

Our next example separates the code from Fig. 16.7 into two files—`GradeBook.h` (Fig. 16.9) and `fig16_10.cpp` (Fig. 16.10). As you look at the header file in Fig. 16.9, notice that it contains only the `GradeBook` class definition (lines 8–38), the appropriate header files and a `using` declaration. The `main` function that uses class `GradeBook` is defined in the source-code file `fig16_10.cpp` (Fig. 16.10) in lines 8–18. To help you prepare for the larger programs you'll encounter later in this book and in industry, we often use a separate source-code file containing function `main` to test our classes (this is called a [driver program](#)). You'll soon learn how a source-code file with `main` can use the class definition found in a header file to create objects of a class.

---

```

1 // Fig. 16.9: GradeBook.h
2 // GradeBook class definition in a separate file from main.
3 #include <iostream>
4 #include <string> // class GradeBook uses C++ standard string class
5 using namespace std;
6
7 // GradeBook class definition
8 class GradeBook
9 {
```

---

**Fig. 16.9** | `GradeBook` class definition in a separate file from `main`. (Part I of 2.)

---

```

10 public:
11 // constructor initializes courseName with string supplied as argument
12 GradeBook(string name)
13 {
14 setCourseName(name); // call set function to initialize courseName
15 } // end GradeBook constructor
16
17 // function to set the course name
18 void setCourseName(string name)
19 {
20 courseName = name; // store the course name in the object
21 } // end function setCourseName
22
23 // function to get the course name
24 string getCourseName()
25 {
26 return courseName; // return object's courseName
27 } // end function getCourseName
28
29 // display a welcome message to the GradeBook user
30 void displayMessage()
31 {
32 // call getCourseName to get the courseName
33 cout << "Welcome to the grade book for\n" << getCourseName()
34 << "!" << endl;
35 } // end function displayMessage
36 private:
37 string courseName; // course name for this GradeBook
38 }; // end class GradeBook

```

---

**Fig. 16.9** | GradeBook class definition in a separate file from main. (Part 2 of 2.)

---

```

1 // Fig. 16.10: fig16_10.cpp
2 // Including class GradeBook from file GradeBook.h for use in main.
3 #include <iostream>
4 #include "GradeBook.h" // include definition of class GradeBook
5 using namespace std;
6
7 // function main begins program execution
8 int main()
9 {
10 // create two GradeBook objects
11 GradeBook gradeBook1("CS101 Introduction to C++ Programming");
12 GradeBook gradeBook2("CS102 Data Structures in C++");
13
14 // display initial value of courseName for each GradeBook
15 cout << "gradeBook1 created for course: " << gradeBook1.getCourseName()
16 << "\ngradeBook2 created for course: " << gradeBook2.getCourseName()
17 << endl;
18 } // end main

```

---

**Fig. 16.10** | Including class GradeBook from file GradeBook.h for use in main. (Part 1 of 2.)



```
gradeBook1 created for course: CS101 Introduction to C++ Programming
gradeBook2 created for course: CS102 Data Structures in C++
```

**Fig. 16.10** | Including class `GradeBook` from file `GradeBook.h` for use in `main`. (Part 2 of 2.)

### *Including a Header File That Contains a User-Defined Class*

A header file such as `GradeBook.h` (Fig. 16.9) cannot be used to begin program execution, because it does not contain a `main` function. If you try to compile and link `GradeBook.h` by itself to create an executable application, Microsoft Visual C++ 2008 produces the linker error message:

```
error LNK2001: unresolved external symbol _mainCRTStartup
```

To compile and link with GNU C++ on Linux, you must first include the header file in a `.cpp` source-code file, then GNU C++ produces a linker error message containing:

```
undefined reference to 'main'
```

This error indicates that the linker could not locate the program's `main` function. To test class `GradeBook` (defined in Fig. 16.9), you must write a separate source-code file containing a `main` function (such as Fig. 16.10) that instantiates and uses objects of the class.

The compiler does not know what a `GradeBook` is because it's a user-defined type. In fact, the compiler doesn't even know the classes in the C++ Standard Library. To help it understand how to use a class, we must explicitly provide the compiler with the class's definition—that's why, for example, to use type `string`, a program must include the `<string>` header file. This enables the compiler to determine the amount of memory that it must reserve for each object of the class and ensure that a program calls the class's member functions correctly.

To create `GradeBook` objects `gradeBook1` and `gradeBook2` in lines 11–12 of Fig. 16.10, the compiler must know the size of a `GradeBook` object. While objects conceptually contain data members and member functions, C++ objects contain only data. The compiler creates only *one* copy of the class's member functions and *shares* that copy among all the class's objects. Each object, of course, needs its own copy of the class's data members, because their contents can vary among objects (such as two different `BankAccount` objects having two different balance data members). The member-function code, however, is not modifiable, so it can be shared among all objects of the class. Therefore, the size of an object depends on the amount of memory required to store the class's data members. By including `GradeBook.h` in line 4, we give the compiler access to the information it needs (Fig. 16.9, line 37) to determine the size of a `GradeBook` object and to determine whether objects of the class are used correctly (in lines 11–12 and 15–16 of Fig. 16.10).

Line 4 instructs the C++ preprocessor to replace the directive with a copy of the contents of `GradeBook.h` (i.e., the `GradeBook` class definition) *before* the program is compiled. When the source-code file `fig16_10.cpp` is compiled, it now contains the `GradeBook` class definition (because of the `#include`), and the compiler is able to determine how to create `GradeBook` objects and see that their member functions are called correctly. Now that the class definition is in a header file (without a `main` function), we can include that header in *any* program that needs to reuse our `GradeBook` class.

### How Header Files Are Located

Notice that the name of the `GradeBook.h` header file in line 4 of Fig. 16.10 is enclosed in quotes (" ") rather than angle brackets (< >). Normally, a program's source-code files and user-defined header files are placed in the same directory. When the preprocessor encounters a header file name in quotes, it attempts to locate the header file in the same directory as the file in which the `#include` directive appears. If the preprocessor cannot find the header file in that directory, it searches for it in the same location(s) as the C++ Standard Library header files. When the preprocessor encounters a header file name in angle brackets (e.g., `<iostream>`), it assumes that the header is part of the C++ Standard Library and does not look in the directory of the program that is being preprocessed.



#### Error-Prevention Tip 16.3

*To ensure that the preprocessor can locate header files correctly, `#include` preprocessor directives should place the names of user-defined header files in quotes (e.g., `"GradeBook.h"`) and place the names of C++ Standard Library header files in angle brackets (e.g., `<iostream>`).*

### Additional Software Engineering Issues

Now that class `GradeBook` is defined in a header file, the class is reusable. Unfortunately, placing a class definition in a header file as in Fig. 16.9 still reveals the entire implementation of the class to the class's clients—`GradeBook.h` is simply a text file that anyone can open and read. Conventional software engineering wisdom says that to use an object of a class, the client code needs to know only what member functions to call, what arguments to provide to each member function and what return type to expect from each member function. The client code does not need to know how those functions are implemented.

If client code *does* know how a class is implemented, the client-code programmer might write client code based on the class's implementation details. Ideally, if that implementation changes, the class's clients should not have to change. Hiding the class's implementation details makes it easier to change the class's implementation while minimizing, and hopefully eliminating, changes to client code.

In Section 16.8, we show how to break up the `GradeBook` class into two files so that

1. the class is reusable,
2. the clients of the class know what member functions the class provides, how to call them and what return types to expect, and
3. the clients do *not* know how the class's member functions are implemented.

## 16.8 Separating Interface from Implementation

In the preceding section, we showed how to promote software reusability by separating a class definition from the client code (e.g., function `main`) that uses the class. We now introduce another fundamental principle of good software engineering—**separating interface from implementation**.

### Interface of a Class

**Interfaces** define and standardize the ways in which things such as people and systems interact with one another. For example, a radio's controls serve as an interface between the

radio's users and its internal components. The controls allow users to perform a limited set of operations (such as changing the station, adjusting the volume, and choosing between AM and FM stations). Various radios may implement these operations differently—some provide push buttons, some provide dials and some support voice commands. The interface specifies *what* operations a radio permits users to perform but does not specify *how* the operations are implemented inside the radio.

Similarly, the **interface of a class** describes *what* services a class's clients can use and how to *request* those services, but not *how* the class carries out the services. A class's public interface consists of the class's public member functions (also known as the class's **public services**). For example, class `GradeBook`'s interface (Fig. 16.9) contains a constructor and member functions `setCourseName`, `getCourseName` and `displayMessage`. `GradeBook`'s clients (e.g., `main` in Fig. 16.10) use these functions to request the class's services. As you'll soon see, you can specify a class's interface by writing a class definition that lists only the member-function names, return types and parameter types.

### *Separating the Interface from the Implementation*

In our prior examples, each class definition contained the complete definitions of the class's public member functions and the declarations of its private data members. However, it's better software engineering to define member functions *outside* the class definition, so that their implementation details can be hidden from the client code. This practice *ensures* that you do not write client code that depends on the class's implementation details. If you were to do so, the client code would be more likely to “break” if the class's implementation changed.

The program of Figs. 16.11–16.13 separates class `GradeBook`'s interface from its implementation by splitting the class definition of Fig. 16.9 into two files—the header file `GradeBook.h` (Fig. 16.11) in which class `GradeBook` is defined, and the source-code file `GradeBook.cpp` (Fig. 16.12) in which `GradeBook`'s member functions are defined. By convention, member-function definitions are placed in a source-code file of the same base name (e.g., `GradeBook`) as the class's header file but with a `.cpp` filename extension. The source-code file `fig16_13.cpp` (Fig. 16.13) defines function `main` (the client code). The code and output of Fig. 16.13 are identical to that of Fig. 16.10. Figure 16.14 shows how this three-file program is compiled from the perspectives of the `GradeBook` class programmer and the client-code programmer—we'll explain this figure in detail.

### ***GradeBook.h: Defining a Class's Interface with Function Prototypes***

Header file `GradeBook.h` (Fig. 16.11) contains another version of `GradeBook`'s class definition (lines 9–18). This version is similar to the one in Fig. 16.9, but the function definitions in Fig. 16.9 are replaced here with **function prototypes** (lines 12–15) that describe the class's public interface without revealing the class's member-function implementations. A function prototype is a declaration of a function that tells the compiler the function's name, its return type and the types of its parameters. Also, the header file still specifies the class's private data member (line 17) as well. Again, the compiler must know the data members of the class to determine how much memory to reserve for each object of the class. Including the header file `GradeBook.h` in the client code (line 5 of Fig. 16.13) provides the compiler with the information it needs to ensure that the client code calls the member functions of class `GradeBook` correctly.

```

1 // Fig. 16.11: GradeBook.h
2 // GradeBook class definition. This file presents GradeBook's public
3 // interface without revealing the implementations of GradeBook's member
4 // functions, which are defined in GradeBook.cpp.
5 #include <string> // class GradeBook uses C++ standard string class
6 using namespace std;
7
8 // GradeBook class definition
9 class GradeBook
10 {
11 public:
12 GradeBook(string); // constructor that initializes courseName
13 void setCourseName(string); // function that sets the course name
14 string getCourseName(); // function that gets the course name
15 void displayMessage(); // function that displays a welcome message
16 private:
17 string courseName; // course name for this GradeBook
18 }; // end class GradeBook

```

**Fig. 16.11** | GradeBook class definition containing function prototypes that specify the interface of the class.

The function prototype in line 12 (Fig. 16.11) indicates that the constructor requires one string parameter. Recall that constructors do not have return types, so no return type appears in the function prototype. Member function `setCourseName`'s function prototype indicates that `setCourseName` requires a string parameter and does not return a value (i.e., its return type is `void`). Member function `getCourseName`'s function prototype indicates that the function does not require parameters and returns a string. Finally, member function `displayMessage`'s function prototype (line 15) specifies that `displayMessage` does not require parameters and does not return a value. These function prototypes are the same as the corresponding function headers in Fig. 16.9, except that the parameter names (which are optional in prototypes) are not included and each function prototype must end with a semicolon.



### Common Programming Error 16.8

*Forgetting the semicolon at the end of a function prototype is a syntax error.*



### Good Programming Practice 16.7

*Although parameter names in function prototypes are optional (they're ignored by the compiler), many programmers use these names for documentation purposes.*



### Error-Prevention Tip 16.4

*Parameter names in a function prototype (which, again, are ignored by the compiler) can be misleading if the names used do not match those used in the function definition. For this reason, many programmers create function prototypes by copying the first line of the corresponding function definitions (when the source code for the functions is available), then appending a semicolon to the end of each prototype.*

**GradeBook.cpp: Defining Member Functions in a Separate Source-Code File**

Source-code file `GradeBook.cpp` (Fig. 16.12) *defines* class `GradeBook`'s member functions, which were *declared* in lines 12–15 of Fig. 16.11. The definitions appear in lines 9–32 and are nearly identical to the member-function definitions in lines 12–35 of Fig. 16.9.

---

```

1 // Fig. 16.12: GradeBook.cpp
2 // GradeBook member-function definitions. This file contains
3 // implementations of the member functions prototyped in GradeBook.h.
4 #include <iostream>
5 #include "GradeBook.h" // include definition of class GradeBook
6 using namespace std;
7
8 // constructor initializes courseName with string supplied as argument
9 GradeBook::GradeBook(string name)
10 {
11 setCourseName(name); // call set function to initialize courseName
12 } // end GradeBook constructor
13
14 // function to set the course name
15 void GradeBook::setCourseName(string name)
16 {
17 courseName = name; // store the course name in the object
18 } // end function setCourseName
19
20 // function to get the course name
21 string GradeBook::getCourseName()
22 {
23 return courseName; // return object's courseName
24 } // end function getCourseName
25
26 // display a welcome message to the GradeBook user
27 void GradeBook::displayMessage()
28 {
29 // call getCourseName to get the courseName
30 cout << "Welcome to the grade book for\n" << getCourseName()
31 << "!" << endl;
32 } // end function displayMessage

```

---

**Fig. 16.12** | `GradeBook` member-function definitions represent the implementation of class `GradeBook`.

Notice that each member-function name in the function headers (lines 9, 15, 21 and 27) is preceded by the class name and `::`, which is known as the **binary scope resolution operator**. This “ties” each member function to the (now separate) `GradeBook` class definition (Fig. 16.11), which declares the class’s member functions and data members. Without “`GradeBook::`” preceding each function name, these functions would not be recognized by the compiler as member functions of class `GradeBook`—the compiler would consider them “free” or “loose” functions, like `main`. These are also called global functions. Such functions cannot access `GradeBook`’s private data or call the class’s member functions, without specifying an object. So, the compiler would not be able to compile these functions. For example, lines 17 and 23 that access variable `courseName` would cause compilation errors

because `courseName` is not declared as a local variable in each function—the compiler would not know that `courseName` is already declared as a data member of class `GradeBook`.



### Common Programming Error 16.9

*When defining a class's member functions outside that class, omitting the class name and binary scope resolution operator (`::`) preceding the function names causes compilation errors.*

To indicate that the member functions in `GradeBook.cpp` are part of class `GradeBook`, we must first include the `GradeBook.h` header file (line 5 of Fig. 16.12). This allows us to access the class name `GradeBook` in the `GradeBook.cpp` file. When compiling `GradeBook.cpp`, the compiler uses the information in `GradeBook.h` to ensure that

1. the first line of each member function (lines 9, 15, 21 and 27) matches its prototype in the `GradeBook.h` file—for example, the compiler ensures that `getCourseName` accepts no parameters and returns a string, and that
2. each member function knows about the class's data members and other member functions—for example, lines 17 and 23 can access variable `courseName` because it's declared in `GradeBook.h` as a data member of class `GradeBook`, and lines 11 and 30 can call functions `setCourseName` and `getCourseName`, respectively, because each is declared as a member function of the class in `GradeBook.h` (and because these calls conform with the corresponding prototypes).

### Testing Class `GradeBook`

Figure 16.13 performs the same `GradeBook` object manipulations as Fig. 16.10. Separating `GradeBook`'s interface from the implementation of its member functions does not affect the way that this client code uses the class. It affects only how the program is compiled and linked, which we discuss in detail shortly.

---

```

1 // Fig. 16.13: fig16_13.cpp
2 // GradeBook class demonstration after separating
3 // its interface from its implementation.
4 #include <iostream>
5 #include "GradeBook.h" // include definition of class GradeBook
6 using namespace std;
7
8 // function main begins program execution
9 int main()
10 {
11 // create two GradeBook objects
12 GradeBook gradeBook1("CS101 Introduction to C++ Programming");
13 GradeBook gradeBook2("CS102 Data Structures in C++");
14
15 // display initial value of courseName for each GradeBook
16 cout << "gradeBook1 created for course: " << gradeBook1.getCourseName()
17 << "\ngradeBook2 created for course: " << gradeBook2.getCourseName()
18 << endl;
19 } // end main

```

---

**Fig. 16.13** | `GradeBook` class demonstration after separating its interface from its implementation. (Part 1 of 2.)

```
gradeBook1 created for course: CS101 Introduction to C++ Programming
gradeBook2 created for course: CS102 Data Structures in C++
```

**Fig. 16.13** | GradeBook class demonstration after separating its interface from its implementation. (Part 2 of 2.)

As in Fig. 16.10, line 5 of Fig. 16.13 includes the `GradeBook.h` header file so that the compiler can ensure that `GradeBook` objects are created and manipulated correctly in the client code. Before executing this program, the source-code files in Fig. 16.12 and Fig. 16.13 must both be compiled, then linked together—that is, the member-function calls in the client code need to be tied to the implementations of the class’s member functions—a job performed by the linker.

### *The Compilation and Linking Process*

The diagram in Fig. 16.14 shows the compilation and linking process that results in an executable `GradeBook` application that can be used by instructors. Often a class’s interface and implementation will be created and compiled by one programmer and used by a separate programmer who implements the client code that uses the class. So, the diagram shows what’s required by both the class-implementation programmer and the client-code programmer. The dashed lines in the diagram show the pieces required by the class-implementation programmer, the client-code programmer and the `GradeBook` application user, respectively. [Note: Figure 16.14 is *not* a UML diagram.]


A class-implementation programmer responsible for creating a reusable `GradeBook` class creates the header file `GradeBook.h` and the source-code file `GradeBook.cpp` that `#includes` the header file, then compiles the source-code file to create `GradeBook`’s object code. To hide the class’s member-function implementation details, the class-implementation programmer would provide the client-code programmer with the header file `GradeBook.h` (which specifies the class’s interface and data members) and the `GradeBook` object code (i.e., the machine-language instructions that represent `GradeBook`’s member functions). The client-code programmer is not given `GradeBook.cpp`, so the client remains unaware of how `GradeBook`’s member functions are implemented.

The client code needs to know only `GradeBook`’s interface to use the class and must be able to link its object code. Since the interface of the class is part of the class definition in the `GradeBook.h` header file, the client-code programmer must have access to this file and must `#include` it in the client’s source-code file. When the client code is compiled, the compiler uses the class definition in `GradeBook.h` to ensure that the `main` function creates and manipulates objects of class `GradeBook` correctly.

To create the executable `GradeBook` application, the last step is to link

1. the object code for the `main` function (i.e., the client code),
2. the object code for class `GradeBook`’s member-function implementations and
3. the C++ Standard Library object code for the C++ classes (e.g., `string`) used by the class-implementation programmer and the client-code programmer.

The linker’s output is the executable `GradeBook` application that instructors can use to manage their students’ grades. Compilers and IDEs typically invoke the linker for you after compiling your code.



**Fig. 16.14** | Compilation and linking process that produces an executable application.

For further information on compiling multiple-source-file programs, see your compiler's documentation. We provide links to various C++ compilers in our C++ Resource Center at [www.deitel.com/cppplusplus/](http://www.deitel.com/cppplusplus/).

## 16.9 Validating Data with set Functions

In Section 16.5, we introduced *set* functions for allowing clients of a class to modify the value of a private data member. In Fig. 16.5, class `GradeBook` defines member function



setCourseName to simply assign a value received in its parameter name to data member courseName. This member function does not ensure that the course name adheres to any particular format or follows any other rules regarding what a “valid” course name looks like. As we stated earlier, suppose that a university can print student transcripts containing course names of only 25 characters or less. If the university uses a system containing GradeBook objects to generate the transcripts, we might want class GradeBook to ensure that its data member courseName never contains more than 25 characters. The program of Figs. 16.15–16.17 enhances class GradeBook’s member function setCourseName to perform this **validation** (also known as **validity checking**).

### **GradeBook Class Definition**

Notice that GradeBook’s class definition (Fig. 16.15)—and hence, its interface—is identical to that of Fig. 16.11. Since the interface remains unchanged, clients of this class need not be changed when the definition of member function setCourseName is modified. This enables clients to take advantage of the improved GradeBook class simply by linking the client code to the updated GradeBook’s object code.

---

```

1 // Fig. 16.15: GradeBook.h
2 // GradeBook class definition presents the public interface of
3 // the class. Member-function definitions appear in GradeBook.cpp.
4 #include <string> // program uses C++ standard string class
5 using namespace std;
6
7 // GradeBook class definition
8 class GradeBook
9 {
10 public:
11 GradeBook(string); // constructor that initializes a GradeBook object
12 void setCourseName(string); // function that sets the course name
13 string getCourseName(); // function that gets the course name
14 void displayMessage(); // function that displays a welcome message
15 private:
16 string courseName; // course name for this GradeBook
17 }; // end class GradeBook

```

---

**Fig. 16.15** | GradeBook class definition.

### **Validating the Course Name with GradeBook Member Function setCourseName**

The enhancement to class GradeBook is in the definition of setCourseName (Fig. 16.16, lines 16–29). The if statement in lines 18–19 determines whether parameter name contains a valid course name (i.e., a string of 25 or fewer characters). If the course name is valid, line 19 stores it in data member courseName. Note the expression name.length() in line 18. This is a member-function call just like myGradeBook.displayMessage(). The C++ Standard Library’s string class defines a member function **length** that returns the number of characters in a string object. Parameter name is a string object, so the call name.length() returns the number of characters in name. If this value is less than or equal to 25, name is valid and line 19 executes.

The if statement in lines 21–28 handles the case in which setCourseName receives an invalid course name (i.e., a name that is more than 25 characters long). Even if parameter

---

```

1 // Fig. 16.16: GradeBook.cpp
2 // Implementations of the GradeBook member-function definitions.
3 // The setCourseName function performs validation.
4 #include <iostream>
5 #include "GradeBook.h" // include definition of class GradeBook
6 using namespace std;
7
8 // constructor initializes courseName with string supplied as argument
9 GradeBook::GradeBook(string name)
10 {
11 setCourseName(name); // validate and store courseName
12 } // end GradeBook constructor
13
14 // function that sets the course name;
15 // ensures that the course name has at most 25 characters
16 void GradeBook::setCourseName(string name)
17 {
18 if (name.length() <= 25) // if name has 25 or fewer characters
19 courseName = name; // store the course name in the object
20
21 if (name.length() > 25) // if name has more than 25 characters
22 {
23 // set courseName to first 25 characters of parameter name
24 courseName = name.substr(0, 25); // start at 0, length of 25
25
26 cout << "Name \"" << name << "\" exceeds maximum length (25).\n"
27 << "Limiting courseName to first 25 characters.\n" << endl;
28 } // end if
29 } // end function setCourseName
30
31 // function to get the course name
32 string GradeBook::getCourseName()
33 {
34 return courseName; // return object's courseName
35 } // end function getCourseName
36
37 // display a welcome message to the GradeBook user
38 void GradeBook::displayMessage()
39 {
40 // call getCourseName to get the courseName
41 cout << "Welcome to the grade book for\n" << getCourseName()
42 << "!" << endl;
43 } // end function displayMessage

```

---

**Fig. 16.16** | Member-function definitions for class `GradeBook` with a `set` function that validates the length of data member `courseName`.

name is too long, we still want to leave the `GradeBook` object in a **consistent state**—that is, a state in which the object’s data member `courseName` contains a valid value (i.e., a string of 25 characters or less). Thus, we truncate the specified course name and assign the first 25 characters of `name` to the `courseName` data member (unfortunately, this could truncate the course name awkwardly). Standard class `string` provides member function **`substr`** (short for “substring”) that returns a new `string` object created by copying part of an

existing string object. The call in line 24 (i.e., `name.substr( 0, 25 )`) passes two integers (0 and 25) to `name`'s member function `substr`. These arguments indicate the portion of the string `name` that `substr` should return. The first argument specifies the starting position in the original string from which characters are copied—the first character in every string is considered to be at position 0. The second argument specifies the number of characters to copy. Therefore, the call in line 24 returns a 25-character substring of `name` starting at position 0 (i.e., the first 25 characters in `name`). For example, if `name` holds the value "CS101 Introduction to Programming in C++", `substr` returns "CS101 Introduction to Pro". After the call to `substr`, line 24 assigns the substring returned by `substr` to data member `courseName`. In this way, `setCourseName` ensures that `courseName` is always assigned a string containing 25 or fewer characters. If the member function has to truncate the course name to make it valid, lines 26–27 display a warning message.

The `if` statement in lines 21–28 contains two body statements—one to set the `courseName` to the first 25 characters of parameter `name` and one to print an accompanying message to the user. The statement in lines 26–27 could also appear without a stream insertion operator at the start of the second line of the statement, as in:

```
cout << "Name \"" << name << "\" exceeds maximum length (25).\n"
 "Limiting courseName to first 25 characters.\n" << endl;
```

The C++ compiler combines adjacent string literals, even if they appear on separate lines of a program. Thus, in the statement above, the C++ compiler would combine the string literals `"\" exceeds maximum length (25).\n"` and `"Limiting courseName to first 25 characters.\n"` into a single string literal that produces output identical to that of lines 26–27 in Fig. 16.16. This behavior allows you to print lengthy strings by breaking them across lines in your program without including additional stream insertion operations.

### Testing Class *GradeBook*

Figure 16.17 demonstrates the modified version of class *GradeBook* (Figs. 16.15–16.16) featuring validation. Line 12 creates a *GradeBook* object named `gradeBook1`. Recall that the *GradeBook* constructor calls `setCourseName` to initialize data member `courseName`. In previous versions of the class, the benefit of calling `setCourseName` in the constructor was not evident. Now, however, the constructor takes advantage of the validation provided by `setCourseName`. The constructor simply calls `setCourseName`, rather than duplicating its validation code. When line 12 of Fig. 16.17 passes an initial course name of "CS101 Introduction to Programming in C++" to the *GradeBook* constructor, the constructor passes this value to `setCourseName`, where the actual initialization occurs. Because this course name contains more than 25 characters, the body of the second `if` statement executes, causing `courseName` to be initialized to the truncated 25-character course name "CS101 Introduction to Pro" (the truncated part is highlighted in darker blue in line 12). The output in Fig. 16.17 contains the warning message output by lines 26–27 of Fig. 16.16 in member function `setCourseName`. Line 13 creates another *GradeBook* object called `gradeBook2`—the valid course name passed to the constructor is exactly 25 characters.

Lines 16–19 of Fig. 16.17 display the truncated course name for `gradeBook1` (we highlight this in blue) and the course name for `gradeBook2`. Line 22 calls `gradeBook1`'s `setCourseName` member function directly, to change the course name in the *GradeBook* object

```

1 // Fig. 16.17: fig16_17.cpp
2 // Create and manipulate a GradeBook object; illustrate validation.
3 #include <iostream>
4 #include "GradeBook.h" // include definition of class GradeBook
5 using namespace std;
6
7 // function main begins program execution
8 int main()
9 {
10 // create two GradeBook objects;
11 // initial course name of gradeBook1 is too long
12 GradeBook gradeBook1("CS101 Introduction to Programming in C++");
13 GradeBook gradeBook2("CS102 C++ Data Structures");
14
15 // display each GradeBook's courseName
16 cout << "gradeBook1's initial course name is: "
17 << gradeBook1.getCourseName()
18 << "\ngradeBook2's initial course name is: "
19 << gradeBook2.getCourseName() << endl;
20
21 // modify myGradeBook's courseName (with a valid-length string)
22 gradeBook1.setCourseName("CS101 C++ Programming");
23
24 // display each GradeBook's courseName
25 cout << "\ngradeBook1's course name is: "
26 << gradeBook1.getCourseName()
27 << "\ngradeBook2's course name is: "
28 << gradeBook2.getCourseName() << endl;
29 } // end main

```

Name "CS101 Introduction to Programming in C++" exceeds maximum length (25). Limiting courseName to first 25 characters.

gradeBook1's initial course name is: CS101 Introduction to Pro  
 gradeBook2's initial course name is: CS102 C++ Data Structures

gradeBook1's course name is: CS101 C++ Programming  
 gradeBook2's course name is: CS102 C++ Data Structures

**Fig. 16.17** | Creating and manipulating a GradeBook object in which the course name is limited to 25 characters in length.

to a shorter name that does not need to be truncated. Then, lines 25–28 output the course names for the GradeBook objects again.

### *Additional Notes on Set Functions*

A public *set* function such as `setCourseName` should carefully scrutinize any attempt to modify the value of a data member (e.g., `courseName`) to ensure that the new value is appropriate for that data item. For example, an attempt to *set* the day of the month to 37 should be rejected, an attempt to *set* a person's weight to zero or a negative value should be rejected, an attempt to *set* a grade on an exam to 185 (when the proper range is zero to 100) should be rejected, and so on.



### Software Engineering Observation 16.6

*Making data members private and controlling access, especially write access, to those data members through public member functions helps ensure data integrity.*



### Error-Prevention Tip 16.5

*The benefits of data integrity are not automatic simply because data members are made private—you must provide appropriate validity checking and report the errors.*

A class's *set* functions can return values to the class's clients indicating that attempts were made to assign invalid data to objects of the class. A client can test the return value of a *set* function to determine whether the attempt to modify the object was successful and to take appropriate action. In Chapter 24, we demonstrate how clients of a class can be notified via the exception-handling mechanism when an attempt is made to modify an object with an inappropriate value. To keep the program of Figs. 16.15–16.17 simple at this point in our C++ discussion, `setCourseName` in Fig. 16.16 just prints an appropriate message.

## 16.10 Wrap-Up

In this chapter, you created user-defined classes, and created and used objects of those classes. We declared data members of a class to maintain data for each object of the class. We also defined member functions that operate on that data. You learned how to call an object's member functions to request the services the object provides and how to pass data to those member functions as arguments. We discussed the difference between a local variable of a member function and a data member of a class. We also showed how to use a constructor to specify initial values for an object's data members. You learned how to separate the interface of a class from its implementation to promote good software engineering. We presented a diagram that shows the files that class-implementation programmers and client-code programmers need to compile the code they write. We demonstrated how *set* functions can be used to validate an object's data and ensure that objects are maintained in a consistent state. UML class diagrams were used to model classes and their constructors, member functions and data members.

## Summary

### Section 16.2 Classes, Objects, Member Functions and Data Members

- Performing a task in a program requires a function. The function hides from its user the complex tasks that it performs.
- A function in a class is known as a member function and performs one of the class's tasks.
- You must create an object of a class before a program can perform the tasks the class describes.
- Each message sent to an object is a member-function call that tells the object to perform a task.
- An object has attributes that are carried with the object as it's used in a program. These attributes are specified as data members in the object's class.

### Section 16.3 Defining a Class with a Member Function

- A class definition contains the data members and member functions that define the class's attributes and behaviors, respectively.

- A class definition begins with the keyword `class` followed immediately by the class name.
- By convention, the name of a user-defined class begins with a capital letter and, for readability, each subsequent word in the class name begins with a capital letter.
- Every class's body is enclosed in a pair of braces (`{` and `}`) and ends with a semicolon.
- Member functions that appear after access specifier `public` can be called by other functions in a program and by member functions of other classes.
- Access specifiers are always followed by a colon (`:`).
- Keyword `void` is a special return type which indicates that a function will perform a task but will not return any data to its calling function when it completes its task.
- By convention, function names begin with a lowercase first letter and all subsequent words in the name begin with a capital letter.
- An empty set of parentheses after a function name indicates that the function does not require additional data to perform its task.
- Every function's body is delimited by left and right braces (`{` and `}`).
- Typically, you cannot call a member function until you create an object of its class.
- Each new class you create becomes a new type in C++.
- In the UML, each class is modeled in a class diagram as a rectangle with three compartments. The top compartment contains the class name. The middle compartment contains the class's attributes. The bottom compartment contains the class's operations.
- The UML models operations as the operation name followed by parentheses. A plus sign (+) preceding the name indicates a `public` operation (i.e., a `public` member function in C++).

### *Section 16.4 Defining a Member Function with a Parameter*

- A member function can require one or more parameters that represent additional data it needs to perform its task. A function call supplies arguments for each of the function's parameters.
- A member function is called by following the object name with a dot operator (`.`), the function name and a set of parentheses containing the function's arguments.
- A variable of C++ Standard Library class `string` represents a string of characters. This class is defined in header file `<string>`, and the name `string` belongs to namespace `std`.
- Function `getline` (from header `<string>`) reads characters from its first argument until a newline character is encountered, then places the characters (not including the newline) in the `string` variable specified as its second argument. The newline character is discarded.
- A parameter list may contain any number of parameters, including none at all (represented by empty parentheses) to indicate that a function does not require any parameters.
- The number of arguments in a function call must match the number of parameters in the parameter list of the called member function's header. Also, the argument types in the function call must be consistent with the types of the corresponding parameters in the function header.
- The UML models a parameter of an operation by listing the parameter name, followed by a colon and the parameter type between the parentheses following the operation name.
- The UML has its own data types. Not all the UML data types have the same names as the corresponding C++ types. The UML type `String` corresponds to the C++ type `string`.

### *Section 16.5 Data Members, set Functions and get Functions*

- Variables declared in a function's body are local variables and can be used only from the point of their declaration in the function to the immediately following closing right brace (`}`). When a function terminates, the values of its local variables are lost.

- A local variable must be declared before it can be used in a function. A local variable cannot be accessed outside the function in which it's declared.
- Data members normally are `private`. Variables or functions declared `private` are accessible only to member functions of the class in which they're declared, or to friends of the class.
- When a program creates (instantiates) an object of a class, its `private` data members are encapsulated (hidden) in the object and can be accessed only by member functions of the object's class.
- When a function that specifies a return type other than `void` is called and completes its task, the function returns a result to its calling function.
- By default, the initial value of a `string` is the empty string—i.e., a string that does not contain any characters. Nothing appears on the screen when an empty string is displayed.
- Classes often provide `public` member functions to allow clients of the class to *set* or *get* `private` data members. The names of these member functions normally begin with *set* or *get*.
- *Set* and *get* functions allow clients of a class to indirectly access the hidden data. The client does not know how the object performs these operations.
- A class's *set* and *get* functions should be used by other member functions of the class to manipulate the class's `private` data. If the class's data representation is changed, member functions that access the data only via the *set* and *get* functions will not require modification.
- A `public set` function should carefully scrutinize any attempt to modify the value of a data member to ensure that the new value is appropriate for that data item.
- The UML represents data members as attributes by listing the attribute name, followed by a colon and the attribute type. `Private` attributes are preceded by a minus sign (-) in the UML.
- The UML indicates the return type of an operation by placing a colon and the return type after the parentheses following the operation name.
- UML class diagrams do not specify return types for operations that do not return values.

### Section 16.6 Initializing Objects with Constructors

- Each class should provide a constructor to initialize an object of the class when the object is created. A constructor must be defined with the same name as the class.
- A difference between constructors and functions is that constructors cannot return values, so they cannot specify a return type (not even `void`). Normally, constructors are declared `public`.
- C++ requires a constructor call at the time each object is created, which helps ensure that every object is initialized before it's used in a program.
- A constructor with no parameters is a default constructor. If you do not provide a constructor, the compiler provides a default constructor. You can also define a default constructor explicitly. If you define a constructor for a class, C++ will not create a default constructor.
- The UML models constructors as operations in a class diagram's third compartment with the word "constructor" between guillemets (« and ») before the constructor's name.

### Section 16.7 Placing a Class in a Separate File for Reusability

- Class definitions, when packaged properly, can be reused by programmers worldwide.
- It's customary to define a class in a header file that has a `.h` filename extension.
- If the class's implementation changes, the class's clients should not be required to change.
- Interfaces define and standardize the ways in which things such as people and systems interact.
- A class's `public` interface describes the `public` member functions that are made available to the class's clients. The interface describes *what* services clients can use and how to *request* those services, but does not specify *how* the class carries out the services.

### Section 16.8 Separating Interface from Implementation

- Separating interface from implementation makes programs easier to modify. Changes in the class's implementation do not affect the client as long as the class's interface remains unchanged.
- A function prototype contains a function's name, its return type and the number, types and order of the parameters the function expects to receive.
- Once a class is defined and its member functions are declared (via function prototypes), the member functions should be defined in a separate source-code file
- For each member function defined outside of its corresponding class definition, the function name must be preceded by the class name and the binary scope resolution operator (::).

### Section 16.9 Validating Data with set Functions

- Class `string`'s `length` member function returns the number of characters in a `string` object.
- Class `string`'s member function `substr` returns a new `string` object containing a copy of part of an existing `string` object. The first argument specifies the starting position in the original `string`. The second argument specifies the number of characters to copy.

## Terminology

|                                                                          |                                                                      |
|--------------------------------------------------------------------------|----------------------------------------------------------------------|
| access specifier 564                                                     | interface of a class 584                                             |
| access-specifier label <code>public:</code> 564                          | interface 583                                                        |
| accessor 574                                                             | length member function of class <code>string</code> 590              |
| argument 566                                                             | local variable 569                                                   |
| binary scope resolution operator (::) 586                                | member-function call 562                                             |
| body of a class definition 563                                           | message (send to an object) 562                                      |
| calling function 564                                                     | mutator 574                                                          |
| camel case 563                                                           | parameter 566                                                        |
| class definition 563                                                     | parameter list 568                                                   |
| <code>class</code> keyword 563                                           | <code>private:</code> access specifier 571                           |
| client of an object 574                                                  | public access specifier 564                                          |
| consistent state 591                                                     | public services of a class 584                                       |
| constructor 576                                                          | request a service from an object 562                                 |
| data hiding 572                                                          | return statement 573                                                 |
| data member 569                                                          | return type 564                                                      |
| default constructor 576                                                  | separate interface from implementation 583                           |
| defining a class 563                                                     | <code>set</code> function 574                                        |
| dot operator (.) 565                                                     | source-code file 580                                                 |
| driver program 580                                                       | <code>string</code> class 567                                        |
| empty <code>string</code> 574                                            | <code>&lt;string&gt;</code> header file 567                          |
| extensible language 565                                                  | <code>substr</code> member function of class <code>string</code> 591 |
| function header 564                                                      | UML class diagram 565                                                |
| function prototype 584                                                   | user-defined type 565                                                |
| <code>get</code> function 574                                            | validation 590                                                       |
| <code>getline</code> function of <code>&lt;string&gt;</code> library 567 | validity checking 590                                                |
| header file 580                                                          | void return type 564                                                 |

## Self-Review Exercises

16.1 Fill in the blanks in each of the following:

- A house is to a blueprint as a(n) \_\_\_\_\_ is to a class.
- Every class definition contains the keyword \_\_\_\_\_ followed immediately by the class's name.



- c) A class definition is typically stored in a file with the \_\_\_\_\_ filename extension.
- d) Each parameter in a function header must specify both a(n) \_\_\_\_\_ and a(n) \_\_\_\_\_.
- e) When each object of a class maintains its own copy of an attribute, the variable that represents the attribute is also known as a(n) \_\_\_\_\_.
- f) Keyword `public` is a(n) \_\_\_\_\_.
- g) Return type \_\_\_\_\_ indicates that a function will perform a task but will not return any information when it completes its task.
- h) Function \_\_\_\_\_ from the `<string>` library reads characters until a newline character is encountered, then copies those characters into the specified string.
- i) When a member function is defined outside the class definition, the function header must include the class name and the \_\_\_\_\_, followed by the function name to “tie” the member function to the class definition.
- j) The source-code file and any other files that use a class can include the class’s header file via a(n) \_\_\_\_\_ preprocessor directive.

**16.2** State whether each of the following is *true* or *false*. If *false*, explain why.

- a) By convention, function names begin with a capital letter and all subsequent words in the name begin with a capital letter.
- b) Empty parentheses following a function name in a function prototype indicate that the function does not require any parameters to perform its task.
- c) Data members or member functions declared with access specifier `private` are accessible to member functions of the class in which they’re declared.
- d) Variables declared in the body of a particular member function are known as data members and can be used in all member functions of the class.
- e) Every function’s body is delimited by left and right braces (`{` and `}`).
- f) Any source-code file that contains `int main()` can be used to execute a program.
- g) The types of arguments in a function call must be consistent with the types of the corresponding parameters in the function prototype’s parameter list.

**16.3** What is the difference between a local variable and a data member?

**16.4** Explain the purpose of a function parameter. What’s the difference between a parameter and an argument?

## Answers to Self-Review Exercises

**16.1** a) object. b) `class`. c) `.h`. d) type, name. e) data member. f) access specifier. g) `void`. h) `getline`. i) binary scope resolution operator (`::`). j) `#include`.

**16.2** a) False. Function names begin with a lowercase letter and all subsequent words in the name begin with a capital letter. b) True. c) True. d) False. Such variables are local variables and can be used only in the member function in which they’re declared. e) True. f) True. g) True.

**16.3** A local variable is declared in the body of a function and can be used only from the point at which it’s declared to the closing brace of the block in which it’s declared. A data member is declared in a class, but not in the body of any of the class’s member functions. Every object of a class has a separate copy of the class’s data members. Data members are accessible to all member functions of the class.

**16.4** A parameter represents additional information that a function requires to perform its task. Each parameter required by a function is specified in the function header. An argument is the value supplied in the function call. When the function is called, the argument value is passed into the function parameter so that the function can perform its task.

## Exercises

- 16.5** Explain the difference between a function prototype and a function definition.
- 16.6** What's a default constructor? How are an object's data members initialized if a class has only an implicitly defined default constructor?
- 16.7** Explain the purpose of a data member.
- 16.8** What's a header file? What's a source-code file? Discuss the purpose of each.
- 16.9** Explain how a program could use class `string` without inserting a `using` declaration.
- 16.10** Explain why a class might provide a *set* function and a *get* function for a data member.
- 16.11** (*Modifying Class `GradeBook`*) Modify class `GradeBook` (Figs. 16.11–16.12) as follows:
- Include a second `string` data member that represents the course instructor's name.
  - Provide a *set* function to change the instructor's name and a *get* function to retrieve it.
  - Modify the constructor to specify course name and instructor name parameters.
  - Modify function `displayMessage` to output the welcome message and course name, then the string "This course is presented by: " followed by the instructor's name.

Use your modified class in a test program that demonstrates the class's new capabilities.

**16.12** (*Account Class*) Create an `Account` class that a bank might use to represent customers' bank accounts. Include a data member of type `int` to represent the account balance. Provide a constructor that receives an initial balance and uses it to initialize the data member. The constructor should validate the initial balance to ensure that it's greater than or equal to 0. If not, set the balance to 0 and display an error message indicating that the initial balance was invalid. Provide three member functions. Member function `credit` should add an amount to the current balance. Member function `debit` should withdraw money from the `Account` and ensure that the debit amount does not exceed the `Account`'s balance. If it does, the balance should be left unchanged and the function should print a message indicating "Debit amount exceeded account balance." Member function `getBalance` should return the current balance. Create a program that creates two `Account` objects and tests the member functions of class `Account`.

**16.13** (*Invoice Class*) Create a class called `Invoice` that a hardware store might use to represent an invoice for an item sold at the store. An `Invoice` should include four data members—a part number (type `string`), a part description (type `string`), a quantity of the item being purchased (type `int`) and a price per item (type `int`). Your class should have a constructor that initializes the four data members. Provide a *set* and a *get* function for each data member. In addition, provide a member function named `getInvoiceAmount` that calculates the invoice amount (i.e., multiplies the quantity by the price per item), then returns the amount as an `int` value. If the quantity is not positive, it should be set to 0. If the price per item is not positive, it should be set to 0. Write a test program that demonstrates class `Invoice`'s capabilities.

**16.14** (*Employee Class*) Create a class called `Employee` that includes three pieces of information as data members—a first name (type `string`), a last name (type `string`) and a monthly salary (type `int`). Your class should have a constructor that initializes the three data members. Provide a *set* and a *get* function for each data member. If the monthly salary is not positive, set it to 0. Write a test program that demonstrates class `Employee`'s capabilities. Create two `Employee` objects and display each object's *yearly* salary. Then give each `Employee` a 10 percent raise and display each `Employee`'s yearly salary again.

**16.15** (*Date Class*) Create a class called `Date` that includes three pieces of information as data members—a month (type `int`), a day (type `int`) and a year (type `int`). Your class should have a constructor with three parameters that uses the parameters to initialize the three data members. For the

purpose of this exercise, assume that the values provided for the year and day are correct, but ensure that the month value is in the range 1–12; if it isn't, set the month to 1. Provide a *set* and a *get* function for each data member. Provide a member function `displayDate` that displays the month, day and year separated by forward slashes (/). Write a test program that demonstrates class `Date`'s capabilities.

## Making a Difference

**16.16 (Target-Heart-Rate Calculator)** While exercising, you can use a heart-rate monitor to see that your heart rate stays within a safe range suggested by your trainers and doctors. According to the American Heart Association (AHA) ([www.americanheart.org/presenter.jhtml?identifier=4736](http://www.americanheart.org/presenter.jhtml?identifier=4736)), the formula for calculating your *maximum heart rate* in beats per minute is 220 minus your age in years. Your *target heart rate* is a range that is 50–85% of your maximum heart rate. [Note: *These formulas are estimates provided by the AHA. Maximum and target heart rates may vary based on the health, fitness and gender of the individual. Always consult a physician or qualified health care professional before beginning or modifying an exercise program.*] Create a class called `HeartRates`. The class attributes should include the person's first name, last name and date of birth (consisting of separate attributes for the month, day and year of birth). Your class should have a constructor that receives this data as parameters. For each attribute provide *set* and *get* functions. The class also should include a function `getAge` that calculates and returns the person's age (in years), a function `getMaximumHeartRate` that calculates and returns the person's maximum heart rate and a function `getTargetHeartRate` that calculates and returns the person's target heart rate. Since you do not yet know how to obtain the current date from the computer, function `getAge` should prompt the user to enter the current month, day and year before calculating the person's age. Write an application that prompts for the person's information, instantiates an object of class `HeartRates` and prints the information from that object—including the person's first name, last name and date of birth—then calculates and prints the person's age in (years), maximum heart rate and target-heart-rate range.

**16.17 (Computerization of Health Records)** A health care issue that has been in the news lately is the computerization of health records. This possibility is being approached cautiously because of sensitive privacy and security concerns, among others. [We address such concerns in later exercises.] Computerizing health records could make it easier for patients to share their health profiles and histories among their various health care professionals. This could improve the quality of health care, help avoid drug conflicts and erroneous drug prescriptions, reduce costs and in emergencies, could save lives. In this exercise, you'll design a "starter" `HealthProfile` class for a person. The class attributes should include the person's first name, last name, gender, date of birth (consisting of separate attributes for the month, day and year of birth), height (in inches) and weight (in pounds). Your class should have a constructor that receives this data. For each attribute, provide *set* and *get* functions. The class also should include functions that calculate and return the user's age in years, maximum heart rate and target-heart-rate range (see Exercise 16.16), and body mass index (BMI; see Exercise 2.32). Write an application that prompts for the person's information, instantiates an object of class `HealthProfile` for that person and prints the information from that object—including the person's first name, last name, gender, date of birth, height and weight—then calculates and prints the person's age in years, BMI, maximum heart rate and target-heart-rate range. It should also display the "BMI values" chart from Exercise 2.32. Use the same technique as Exercise 16.16 to calculate the person's age.

# Classes: A Deeper Look, Part I

# 17

*My object all sublime  
I shall achieve in time.*

—W. S. Gilbert

*Is it a world to hide virtues in?*

—William Shakespeare

*Don't be "consistent," but be  
simply true.*

—Oliver Wendell Holmes, Jr.

## Objectives

In this chapter you'll learn:

- How to use a preprocessor wrapper to prevent multiple definition errors.
- To understand class scope and accessing class members via the name of an object, a reference to an object or a pointer to an object.
- To define constructors with default arguments.
- How destructors are used to perform "termination housekeeping" on an object before it's destroyed.
- When constructors and destructors are called and the order in which they're called.
- The logic errors that may occur when a **public** member function returns a reference to **private** data.
- To assign the data members of one object to those of another object by default memberwise assignment.

- |                                                                        |                                                                                                              |
|------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------|
| <b>17.1</b> Introduction                                               | <b>17.7</b> Destructors                                                                                      |
| <b>17.2</b> Time Class Case Study                                      | <b>17.8</b> When Constructors and Destructors are Called                                                     |
| <b>17.3</b> Class Scope and Accessing Class Members                    | <b>17.9</b> Time Class Case Study: A Subtle Trap—Returning a Reference to a <code>private</code> Data Member |
| <b>17.4</b> Separating Interface from Implementation                   | <b>17.10</b> Default Memberwise Assignment                                                                   |
| <b>17.5</b> Access Functions and Utility Functions                     | <b>17.11</b> Wrap-Up                                                                                         |
| <b>17.6</b> Time Class Case Study: Constructors with Default Arguments |                                                                                                              |

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises*

## 17.1 Introduction

In Chapters 15–16, we introduced many basic terms and concepts of C++ object-oriented programming. We also discussed our program development methodology: We selected appropriate attributes and behaviors for each class and specified the manner in which objects of our classes collaborated with objects of C++ Standard Library classes to accomplish each program’s overall goals.

In this chapter, we take a deeper look at classes. We use an integrated `Time` class case study in both this chapter and Chapter 18, *Classes: A Deeper Look, Part 2* to demonstrate several class construction capabilities. We begin with a `Time` class that reviews several of the features presented in the preceding chapters. The example also demonstrates an important C++ software engineering concept—using a “preprocessor wrapper” in header files to prevent the code in the header from being included into the same source code file more than once. Since a class can be defined only once, using such preprocessor directives prevents multiple definition errors.

Next, we discuss class scope and the relationships among class members. We demonstrate how client code can access a class’s public members via three types of “handles”—the name of an object, a reference to an object or a pointer to an object. As you’ll see, object names and references can be used with the dot (`.`) member selection operator to access a public member, and pointers can be used with the arrow (`->`) member selection operator.

We discuss access functions that can read or display data in an object. A common use of access functions is to test the truth or falsity of conditions—such functions are known as predicate functions. We also demonstrate the notion of a utility function (also called a helper function)—a private member function that supports the operation of the class’s public member functions, but is not intended for use by clients of the class.

In the second `Time` class case study example, we demonstrate how to pass arguments to constructors and show how default arguments can be used in a constructor to enable client code to initialize objects using a variety of arguments. Next, we discuss a special member function called a destructor that is part of every class and is used to perform “termination housekeeping” on an object before the object is destroyed. We then demonstrate the order in which constructors and destructors are called, because your programs’ correctness depends on using properly initialized objects that have not yet been destroyed.



Our last example of the Time class case study in this chapter shows a dangerous programming practice in which a member function returns a reference to private data. We discuss how this breaks the encapsulation of a class and allows client code to directly access an object's data. This last example shows that objects of the same class can be assigned to one another using default memberwise assignment, which copies the data members in the object on the right side of the assignment into the corresponding data members of the object on the left side of the assignment. The chapter concludes with a discussion of software reusability.

## 17.2 Time Class Case Study

Our first example (Figs. 17.1–17.3) creates class Time and a driver program that tests the class. In this section, we review many of the concepts covered in Chapter 16 and demonstrate an important C++ software engineering concept—using a “preprocessor wrapper” in header files to prevent the code in the header from being included into the same source code file more than once. Since a class can be defined only once, using such preprocessor directives prevents multiple-definition errors.

---

```

1 // Fig. 17.1: Time.h
2 // Declaration of class Time.
3 // Member functions are defined in Time.cpp
4
5 // prevent multiple inclusions of header file
6 #ifndef TIME_H
7 #define TIME_H
8
9 // Time class definition
10 class Time
11 {
12 public:
13 Time(); // constructor
14 void setTime(int, int, int); // set hour, minute and second
15 void printUniversal(); // print time in universal-time format
16 void printStandard(); // print time in standard-time format
17 private:
18 int hour; // 0 - 23 (24-hour clock format)
19 int minute; // 0 - 59
20 int second; // 0 - 59
21 }; // end class Time
22
23 #endif

```

---

**Fig. 17.1** | Time class definition.

### *Time Class Definition*

The class definition (Fig. 17.1) contains prototypes (lines 13–16) for member functions Time, setTime, printUniversal and printStandard, and includes private integer members hour, minute and second (lines 18–20). Class Time's private data members can be accessed only by its four member functions. Chapter 20 introduces a third access specifier, protected, as we study inheritance and the part it plays in object-oriented programming.



### Good Programming Practice 17.1

*For clarity and readability, use each access specifier only once in a class definition. Place `public` members first, where they're easy to locate.*



### Software Engineering Observation 17.1

*Each element of a class should have private visibility unless it can be proven that the element needs `public` visibility. This is another example of the principle of least privilege.*

In Fig. 17.1, the class definition is enclosed in the following **preprocessor wrapper** (lines 6, 7 and 23):

```
// prevent multiple inclusions of header file
#ifndef TIME_H
#define TIME_H
...
#endif
```

When we build larger programs, other definitions and declarations will also be placed in header files. The preceding preprocessor wrapper prevents the code between `#ifndef` (which means “if not defined”) and `#endif` from being included if the name `TIME_H` has been defined. If the header has not been included previously in a file, the name `TIME_H` is defined by the `#define` directive and the header file statements are included. If the header has been included previously, `TIME_H` is defined already and the header file is not included again. Attempts to include a header file multiple times (inadvertently) typically occur in large programs with many header files that may themselves include other header files. [Note: The commonly used convention for the symbolic constant name in the preprocessor directives is simply the header file name in uppercase with the underscore character replacing the period.]



### Error-Prevention Tip 17.1

*Use `#ifndef`, `#define` and `#endif` preprocessor directives to form a preprocessor wrapper that prevents header files from being included more than once in a program.*



### Good Programming Practice 17.2

*Use the name of the header file in upper case with the period replaced by an underscore in the `#ifndef` and `#define` preprocessor directives of a header file.*

## Time Class Member Functions

In Fig. 17.2, the `Time` constructor (lines 10–13) initializes the data members to 0—the universal-time equivalent of 12 AM. This ensures that the object begins in a consistent state. Invalid values cannot be stored in the data members of a `Time` object, because the constructor is called when the `Time` object is created, and all subsequent attempts by a client to modify the data members are scrutinized by function `setTime` (discussed shortly). You can define several overloaded constructors for a class.

The data members of a class cannot be initialized where they're declared in the class body. It's strongly recommended that these data members be initialized by the class's constructor (as there is no default initialization for fundamental-type data members). Data members can also be assigned values by `Time`'s *set* functions. [Note: Chapter 18 demon-

```

1 // Fig. 17.2: Time.cpp
2 // Member-function definitions for class Time.
3 #include <iostream>
4 #include <iomanip>
5 #include "Time.h" // include definition of class Time from Time.h
6 using namespace std;
7
8 // Time constructor initializes each data member to zero.
9 // Ensures all Time objects start in a consistent state.
10 Time::Time()
11 {
12 hour = minute = second = 0;
13 } // end Time constructor
14
15 // set new Time value using universal time; ensure that
16 // the data remains consistent by setting invalid values to zero
17 void Time::setTime(int h, int m, int s)
18 {
19 hour = (h >= 0 && h < 24) ? h : 0; // validate hour
20 minute = (m >= 0 && m < 60) ? m : 0; // validate minute
21 second = (s >= 0 && s < 60) ? s : 0; // validate second
22 } // end function setTime
23
24 // print Time in universal-time format (HH:MM:SS)
25 void Time::printUniversal()
26 {
27 cout << setfill('0') << setw(2) << hour << ":"
28 << setw(2) << minute << ":" << setw(2) << second;
29 } // end function printUniversal
30
31 // print Time in standard-time format (HH:MM:SS AM or PM)
32 void Time::printStandard()
33 {
34 cout << ((hour == 0 || hour == 12) ? 12 : hour % 12) << ":"
35 << setfill('0') << setw(2) << minute << ":" << setw(2)
36 << second << (hour < 12 ? " AM" : " PM");
37 } // end function printStandard

```

**Fig. 17.2** | Time class member-function definitions.

strates that only a class's static const data members of integral or enum types can be initialized in the class's body.]



### Common Programming Error 17.1

*Attempting to initialize a non-static data member of a class explicitly in the class definition is a syntax error.*

Function `setTime` (lines 17–22) is a public function that declares three `int` parameters and uses them to set the time. A conditional expression tests each argument to determine whether the value is in a specified range. For example, the `hour` value (line 19) must be greater than or equal to 0 and less than 24, because the universal-time format represents hours as integers from 0 to 23 (e.g., 1 PM is hour 13 and 11 PM is hour 23; midnight is hour 0 and noon is hour 12). Similarly, both `minute` and `second` values (lines 20 and 21)



must be greater than or equal to 0 and less than 60. Any values outside these ranges are set to zero to ensure that a `Time` object always contains consistent data—that is, the object’s data values are always kept in range, even if the values provided as arguments to function `setTime` were incorrect. In this example, zero is a consistent value for hour, minute and second.

A value passed to `setTime` is a correct value if it’s in the allowed range for the member it’s initializing. So, any number in the range 0–23 would be a correct value for the hour. A correct value is always a consistent value. However, a consistent value is not necessarily a correct value. If `setTime` sets hour to 0 because the argument received was out of range, then hour is correct only if the current time is coincidentally midnight.

Function `printUniversal` (lines 25–29 of Fig. 17.2) takes no arguments and outputs the time in universal-time format, consisting of three colon-separated pairs of digits for the hour, minute and second. For example, if the time were 1:30:07 PM, function `printUniversal` would return 13:30:07. Line 27 uses parameterized stream manipulator `setfill` to specify the **fill character** that is displayed when an integer is output in a field wider than the number of digits in the value. By default, the fill characters appear to the left of the digits in the number. In this example, if the minute value is 2, it will be displayed as 02, because the fill character is set to zero ('0'). If the number being output fills the specified field, the fill character will not be displayed. Once the fill character is specified with `setfill`, it applies for all subsequent values that are displayed in fields wider than the value being displayed (i.e., `setfill` is a “sticky” setting). This is in contrast to `setw`, which applies only to the next value displayed (`setw` is a “nonsticky” setting).



### Error-Prevention Tip 17.2

*Each sticky setting (such as a fill character or floating-point precision) should be restored to its previous setting when it’s no longer needed. Failure to do so may result in incorrectly formatted output later in a program. Chapter 23, Stream Input/Output, discusses how to reset the fill character and precision.*

Function `printStandard` (lines 32–37) takes no arguments and outputs the date in standard-time format, consisting of the hour, minute and second values separated by colons and followed by an AM or PM indicator (e.g., 1:27:06 PM). Like function `printUniversal`, function `printStandard` uses `setfill('0')` to format the minute and second as two digit values with leading zeros if necessary. Line 34 uses the conditional operator (`?:`) to determine the value of hour to be displayed—if the hour is 0 or 12 (AM or PM), it appears as 12; otherwise, the hour appears as a value from 1 to 11. The conditional operator in line 36 determines whether AM or PM will be displayed.

### Defining Member Functions Outside the Class Definition; Class Scope

Even though a member function declared in a class definition may be defined outside that class definition (and “tied” to the class via the binary scope resolution operator), that member function is still within that **class’s scope**; i.e., its name is known only to other members of the class unless referred to via an object of the class, a reference to an object of the class, a pointer to an object of the class or the binary scope resolution operator. We’ll say more about class scope shortly.

If a member function is defined in the body of a class definition, the compiler attempts to inline calls to the member function. Remember that the compiler reserves the right not to inline any function.



### Performance Tip 17.1

*Defining a member function inside the class definition inlines the member function (if the compiler chooses to do so). This can improve performance.*



### Software Engineering Observation 17.2

*Defining a small member function inside the class definition does not promote the best software engineering, because clients of the class will be able to see the implementation of the function, and the client code must be recompiled if the function definition changes.*



### Software Engineering Observation 17.3

*Only the simplest and most stable member functions (i.e., whose implementations are unlikely to change) should be defined in the class header.*

## Member Functions vs. Global Functions

The `printUniversal` and `printStandard` member functions take no arguments, because these member functions implicitly know that they're to print the data members of the particular `Time` object for which they're invoked. This can make member function calls more concise than conventional function calls in procedural programming.



### Software Engineering Observation 17.4

*Using an object-oriented programming approach often simplifies function calls by reducing the number of parameters. This benefit of object-oriented programming derives from the fact that encapsulating data members and member functions within an object gives the member functions the right to access the data members.*



### Software Engineering Observation 17.5

*Member functions are usually shorter than functions in non-object-oriented programs, because the data stored in data members have ideally been validated by a constructor or by member functions that store new data. Because the data is already in the object, the member-function calls often have no arguments or fewer arguments than typical function calls in non-object-oriented languages. Thus, the calls are shorter, the function definitions are shorter and the function prototypes are shorter. This improves many aspects of program development.*



### Error-Prevention Tip 17.3

*The fact that member function calls generally take either no arguments or substantially fewer arguments than conventional function calls in non-object-oriented languages reduces the likelihood of passing the wrong arguments, the wrong types of arguments or the wrong number of arguments.*

## Using Class `Time`

Once class `Time` has been defined, it can be used as a type in object, array, pointer and reference declarations as follows:

```
Time sunset; // object of type Time
Time arrayOfTimes[5]; // array of 5 Time objects
Time &dinnerTime = sunset; // reference to a Time object
Time *timePtr = &dinnerTime; // pointer to a Time object
```

Figure 17.3 uses class `Time`. Line 10 instantiates a single object of class `Time` called `t`. When the object is instantiated, the `Time` constructor is called to initialize each private data member to 0. Then, lines 14 and 16 print the time in universal and standard formats, respectively, to confirm that the members were initialized properly. Line 18 sets a new time by calling member function `setTime`, and lines 22 and 24 print the time again in

---

```

1 // Fig. 17.3: fig17_03.cpp
2 // Program to test class Time.
3 // NOTE: This file must be compiled with Time.cpp.
4 #include <iostream>
5 #include "Time.h" // include definition of class Time from Time.h
6 using namespace std;
7
8 int main()
9 {
10 Time t; // instantiate object t of class Time
11
12 // output Time object t's initial values
13 cout << "The initial universal time is ";
14 t.printUniversal(); // 00:00:00
15 cout << "\nThe initial standard time is ";
16 t.printStandard(); // 12:00:00 AM
17
18 t.setTime(13, 27, 6); // change time
19
20 // output Time object t's new values
21 cout << "\n\nUniversal time after setTime is ";
22 t.printUniversal(); // 13:27:06
23 cout << "\nStandard time after setTime is ";
24 t.printStandard(); // 1:27:06 PM
25
26 t.setTime(99, 99, 99); // attempt invalid settings
27
28 // output t's values after specifying invalid values
29 cout << "\n\nAfter attempting invalid settings:"
30 << "\nUniversal time: ";
31 t.printUniversal(); // 00:00:00
32 cout << "\nStandard time: ";
33 t.printStandard(); // 12:00:00 AM
34 cout << endl;
35 } // end main

```

```

The initial universal time is 00:00:00
The initial standard time is 12:00:00 AM

```

```

Universal time after setTime is 13:27:06
Standard time after setTime is 1:27:06 PM

```

```

After attempting invalid settings:
Universal time: 00:00:00
Standard time: 12:00:00 AM

```

**Fig. 17.3** | Program to test class `Time`.

both formats. Line 26 attempts to use `setTime` to set the data members to invalid values—function `setTime` recognizes this and sets the invalid values to 0 to maintain the object in a consistent state. Finally, lines 31 and 33 print the time again in both formats.

### *Looking Ahead to Composition and Inheritance*

Often, classes do not have to be created “from scratch.” Rather, they can include objects of other classes as members or they may be **derived** from other classes that provide attributes and behaviors the new classes can use. Such software reuse can greatly enhance productivity and simplify code maintenance. Including class objects as members of other classes is called **composition** (or **aggregation**) and is discussed in Chapter 18. Deriving new classes from existing classes is called **inheritance** and is discussed in Chapter 20.

### *Object Size*

People new to object-oriented programming often suppose that objects must be quite large because they contain data members and member functions. Logically, this is true—you may think of objects as containing data and functions (and our discussion has certainly encouraged this view); physically, however, this is not true.



#### **Performance Tip 17.2**

*Objects contain only data, so objects are much smaller than if they also contained member functions. Applying operator `sizeof` to a class name or to an object of that class will report only the size of the class’s data members. The compiler creates one copy (only) of the member functions separate from all objects of the class. All objects of the class share this one copy. Each object, of course, needs its own copy of the class’s data, because the data can vary among the objects. The function code is nonmodifiable and, hence, can be shared among all objects of one class.*

## **17.3 Class Scope and Accessing Class Members**

A class’s data members (variables declared in the class definition) and member functions (functions declared in the class definition) belong to that class’s scope. Nonmember functions are defined at global namespace scope.

Within a class’s scope, class members are immediately accessible by all of that class’s member functions and can be referenced by name. Outside a class’s scope, `public` class members are referenced through one of the **handles** on an object—an object name, a reference to an object or a pointer to an object. The type of the object, reference or pointer specifies the interface (i.e., the member functions) accessible to the client. [We’ll see in Chapter 18 that an implicit handle is inserted by the compiler on every reference to a data member or member function from within an object.]

Member functions of a class can be overloaded, but only by other member functions of that class. To overload a member function, simply provide in the class definition a prototype for each version of the overloaded function, and provide a separate function definition for each version of the function.

Variables declared in a member function have local scope and are known only to that function. If a member function defines a variable with the same name as a variable with class scope, the class-scope variable is hidden by the block-scope variable in the local scope. Such a hidden variable can be accessed by preceding the variable name with the class name

followed by the scope resolution operator (`::`). Hidden global variables can be accessed with the unary scope resolution operator (see Chapter 15).

The dot member selection operator (`.`) is preceded by an object's name or with a reference to an object to access the object's members. The **arrow member selection operator** (`->`) is preceded by a pointer to an object to access the object's members.

Figure 17.4 uses a simple class called `Count` (lines 7–24) with private data member `x` of type `int` (line 23), public member function `setX` (lines 11–14) and public member function `print` (lines 17–20) to illustrate accessing class members with the member-selection operators. For simplicity, we've included this small class in the same file as `main`. Lines 28–30 create three variables related to type `Count`—`counter` (a `Count` object), `counterPtr` (a pointer to a `Count` object) and `counterRef` (a reference to a `Count` object). Variable `counterRef` refers to `counter`, and variable `counterPtr` points to `counter`. In lines 33–34 and 37–38, the program can invoke member functions `setX` and `print` by using the dot (`.`) member selection operator preceded by either the name of the object (`counter`) or a reference to the object (`counterRef`, which is an alias for `counter`). Similarly, lines 41–42 demonstrate that the program can invoke member functions `setX` and `print` by using a pointer (`counterPtr`) and the arrow (`->`) member-selection operator.

---

```

1 // Fig. 17.4: fig17_04.cpp
2 // Demonstrating the class member access operators . and ->
3 #include <iostream>
4 using namespace std;
5
6 // class Count definition
7 class Count
8 {
9 public: // public data is dangerous
10 // sets the value of private data member x
11 void setX(int value)
12 {
13 x = value;
14 } // end function setX
15
16 // prints the value of private data member x
17 void print()
18 {
19 cout << x << endl;
20 } // end function print
21
22 private:
23 int x;
24 }; // end class Count
25
26 int main()
27 {
28 Count counter; // create counter object
29 Count *counterPtr = &counter; // create pointer to counter
30 Count &counterRef = counter; // create reference to counter

```

---

**Fig. 17.4** | Accessing an object's member functions through each type of object handle—the object's name, a reference to the object and a pointer to the object. (Part I of 2.)

```

31
32 cout << "Set x to 1 and print using the object's name: ";
33 counter.setX(1); // set data member x to 1
34 counter.print(); // call member function print
35
36 cout << "Set x to 2 and print using a reference to an object: ";
37 counterRef.setX(2); // set data member x to 2
38 counterRef.print(); // call member function print
39
40 cout << "Set x to 3 and print using a pointer to an object: ";
41 counterPtr->setX(3); // set data member x to 3
42 counterPtr->print(); // call member function print
43 } // end main

```

```

Set x to 1 and print using the object's name: 1
Set x to 2 and print using a reference to an object: 2
Set x to 3 and print using a pointer to an object: 3

```

**Fig. 17.4** | Accessing an object's member functions through each type of object handle—the object's name, a reference to the object and a pointer to the object. (Part 2 of 2.)

## 17.4 Separating Interface from Implementation

In Chapter 16, we began by including a class's definition and member-function definitions in one file. We then demonstrated separating this code into two files—a header file for the class definition (i.e., the class's interface) and a source code file for the class's member-function definitions (i.e., the class's implementation). Recall that this makes it easier to modify programs—as far as clients of a class are concerned, changes in the class's implementation do not affect the client as long as the class's interface originally provided to the client remains unchanged.



### Software Engineering Observation 17.6

*Clients of a class do not need access to the class's source code to use the class. The clients do, however, need to be able to link to the class's object code (i.e., the compiled version of the class). This encourages independent software vendors (ISVs) to provide class libraries for sale or license. The ISVs provide in their products only the header files and the object modules. No proprietary information is revealed—as would be the case if source code were provided. The C++ user community benefits by having more ISV-produced class libraries available.*

Actually, things are not quite this rosy. Header files do contain some portions of the implementation and hints about others. Inline member functions, for example, should be in a header file, so that when the compiler compiles a client, the client can include the inline function definition in place. A class's private members are listed in the class definition in the header file, so these members are visible to clients even though the clients may not access the private members. In Chapter 18, we show how to use a “proxy class” to hide even the private data of a class from clients of the class.



### Software Engineering Observation 17.7

*Information important to the interface of a class should be included in the header file. Information that will be used only internally in the class and will not be needed by clients of the class should be included in the unpublished source file. This is yet another example of the principle of least privilege.*

## 17.5 Access Functions and Utility Functions

**Access functions** can read or display data. Another common use for access functions is to test the truth or falsity of conditions—such functions are often called **predicate functions**. An example of a predicate function would be an `isEmpty` function for any container class—a class capable of holding many objects, like a vector. A program might test `isEmpty` before attempting to read another item from the container object. An `isFull` predicate function might test a container-class object to determine whether it has no additional room. Useful predicate functions for our `Time` class might be `isAM` and `isPM`.

The program of Figs. 17.5–17.7 demonstrates the notion of a utility function (also called a **helper function**). A utility function is not part of a class's `public` interface; rather, it's a private member function that supports the operation of the class's `public` member functions. Utility functions are not intended to be used by clients of a class (but can be used by friends of a class, as we'll see in Chapter 18).

Class `SalesPerson` (Fig. 17.5) declares an array of 12 monthly sales figures (line 17) and the prototypes for the class's constructor and member functions that manipulate the array.

```

1 // Fig. 17.5: SalesPerson.h
2 // SalesPerson class definition.
3 // Member functions defined in SalesPerson.cpp.
4 #ifndef SALESP_H
5 #define SALESP_H
6
7 class SalesPerson
8 {
9 public:
10 static const int monthsPerYear = 12; // months in one year
11 SalesPerson(); // constructor
12 void getSalesFromUser(); // input sales from keyboard
13 void setSales(int, double); // set sales for a specific month
14 void printAnnualSales(); // summarize and print sales
15 private:
16 double totalAnnualSales(); // prototype for utility function
17 double sales[monthsPerYear]; // 12 monthly sales figures
18 }; // end class SalesPerson
19
20 #endif

```

**Fig. 17.5** | `SalesPerson` class definition.

In Fig. 17.6, the `SalesPerson` constructor (lines 9–13) initializes array `sales` to zero. The `public` member function `setSales` (lines 30–37) sets the sales figure for one month

in array `sales`. The public member function `printAnnualSales` (lines 40–45) prints the total sales for the last 12 months. The private utility function `totalAnnualSales` (lines 48–56) totals the 12 monthly sales figures for the benefit of `printAnnualSales`. Member function `printAnnualSales` edits the sales figures into monetary format.

---

```

1 // Fig. 17.6: SalesPerson.cpp
2 // SalesPerson class member-function definitions.
3 #include <iostream>
4 #include <iomanip>
5 #include "SalesPerson.h" // include SalesPerson class definition
6 using namespace std;
7
8 // initialize elements of array sales to 0.0
9 SalesPerson::SalesPerson()
10 {
11 for (int i = 0; i < monthsPerYear; i++)
12 sales[i] = 0.0;
13 } // end SalesPerson constructor
14
15 // get 12 sales figures from the user at the keyboard
16 void SalesPerson::getSalesFromUser()
17 {
18 double salesFigure;
19
20 for (int i = 1; i <= monthsPerYear; i++)
21 {
22 cout << "Enter sales amount for month " << i << ": ";
23 cin >> salesFigure;
24 setSales(i, salesFigure);
25 } // end for
26 } // end function getSalesFromUser
27
28 // set one of the 12 monthly sales figures; function subtracts
29 // one from month value for proper subscript in sales array
30 void SalesPerson::setSales(int month, double amount)
31 {
32 // test for valid month and amount values
33 if (month >= 1 && month <= monthsPerYear && amount > 0)
34 sales[month - 1] = amount; // adjust for subscripts 0-11
35 else // invalid month or amount value
36 cout << "Invalid month or sales figure" << endl;
37 } // end function setSales
38
39 // print total annual sales (with the help of utility function)
40 void SalesPerson::printAnnualSales()
41 {
42 cout << setprecision(2) << fixed
43 << "\nThe total annual sales are: $"
44 << totalAnnualSales() << endl; // call utility function
45 } // end function printAnnualSales
46

```

---

**Fig. 17.6** | SalesPerson class member-function definitions. (Part I of 2.)



```

47 // private utility function to total annual sales
48 double SalesPerson::totalAnnualSales()
49 {
50 double total = 0.0; // initialize total
51
52 for (int i = 0; i < monthsPerYear; i++) // summarize sales results
53 total += sales[i]; // add month i sales to total
54
55 return total;
56 } // end function totalAnnualSales

```

**Fig. 17.6** | SalesPerson class member-function definitions. (Part 2 of 2.)

In Fig. 17.7, notice that the application's main function includes only a simple sequence of member-function calls—there are no control statements. The logic of manipulating the sales array is completely encapsulated in class SalesPerson's member functions.



#### Software Engineering Observation 17.8

*A phenomenon of object-oriented programming is that once a class is defined, creating and manipulating objects of that class often involve issuing only a simple sequence of member-function calls—few, if any, control statements are needed. By contrast, it's common to have control statements in the implementation of a class's member functions.*

```

1 // Fig. 17.7: fig17_07.cpp
2 // Utility function demonstration.
3 // Compile this program with SalesPerson.cpp
4
5 // include SalesPerson class definition from SalesPerson.h
6 #include "SalesPerson.h"
7
8 int main()
9 {
10 SalesPerson s; // create SalesPerson object s
11
12 s.getSalesFromUser(); // note simple sequential code; there are
13 s.printAnnualSales(); // no control statements in main
14 } // end main

```

```

Enter sales amount for month 1: 5314.76
Enter sales amount for month 2: 4292.38
Enter sales amount for month 3: 4589.83
Enter sales amount for month 4: 5534.03
Enter sales amount for month 5: 4376.34
Enter sales amount for month 6: 5698.45
Enter sales amount for month 7: 4439.22
Enter sales amount for month 8: 5893.57
Enter sales amount for month 9: 4909.67
Enter sales amount for month 10: 5123.45

```

**Fig. 17.7** | Utility function demonstration. (Part 1 of 2.)

```
Enter sales amount for month 11: 4024.97
Enter sales amount for month 12: 5923.92

The total annual sales are: $60120.59
```

**Fig. 17.7** | Utility function demonstration. (Part 2 of 2.)

## 17.6 Time Class Case Study: Constructors with Default Arguments

The program of Figs. 17.8–17.10 enhances class `Time` to demonstrate how arguments are implicitly passed to a constructor. The constructor defined in Fig. 17.2 initialized `hour`, `minute` and `second` to 0 (i.e., midnight in universal time). Like other functions, constructors can specify default arguments. Line 13 of Fig. 17.8 declares the `Time` constructor to include default arguments, specifying a default value of zero for each argument passed to the constructor. In Fig. 17.9, lines 10–13 define the new version of the `Time` constructor that receives values for parameters `hr`, `min` and `sec` that will be used to initialize private data members `hour`, `minute` and `second`, respectively. Class `Time` provides *set* and *get* functions for each data member. The `Time` constructor now calls `setTime`, which calls the `setHour`, `setMinute` and `setSecond` functions to validate and assign values to the data members. The default arguments to the constructor ensure that, even if no values are provided in a constructor call, the constructor still initializes the data members to maintain the `Time` object in a consistent state. A constructor that defaults all its arguments is also a default constructor—i.e., a constructor that can be invoked with no arguments. There can be at most one default constructor per class.

```
1 // Fig. 17.8: Time.h
2 // Time class containing a constructor with default arguments.
3 // Member functions defined in Time.cpp.
4
5 // prevent multiple inclusions of header file
6 #ifndef TIME_H
7 #define TIME_H
8
9 // Time abstract data type definition
10 class Time
11 {
12 public:
13 Time(int = 0, int = 0, int = 0); // default constructor
14
15 // set functions
16 void setTime(int, int, int); // set hour, minute, second
17 void setHour(int); // set hour (after validation)
18 void setMinute(int); // set minute (after validation)
19 void setSecond(int); // set second (after validation)
20
21 // get functions
22 int getHour(); // return hour
```

**Fig. 17.8** | Time class containing a constructor with default arguments. (Part 1 of 2.)

---

```

23 int getMinute(); // return minute
24 int getSecond(); // return second
25
26 void printUniversal(); // output time in universal-time format
27 void printStandard(); // output time in standard-time format
28 private:
29 int hour; // 0 - 23 (24-hour clock format)
30 int minute; // 0 - 59
31 int second; // 0 - 59
32 }; // end class Time
33
34 #endif

```

---

**Fig. 17.8** | Time class containing a constructor with default arguments. (Part 2 of 2.)

In Fig. 17.9, line 12 of the constructor calls member function `setTime` with the values passed to the constructor (or the default values). Function `setTime` calls `setHour` to ensure that the value supplied for hour is in the range 0–23, then calls `setMinute` and `setSecond` to ensure that the values for minute and second are each in the range 0–59. If a value is out of range, that value is set to zero (to ensure that each data member remains in a consistent state). In Chapter 24, Exception Handling, we use exceptions to indicate when a value is out of range, rather than simply assigning a default consistent value.

---

```

1 // Fig. 17.9: Time.cpp
2 // Member-function definitions for class Time.
3 #include <iostream>
4 #include <iomanip>
5 #include "Time.h" // include definition of class Time from Time.h
6 using namespace std;
7
8 // Time constructor initializes each data member to zero;
9 // ensures that Time objects start in a consistent state
10 Time::Time(int hr, int min, int sec)
11 {
12 setTime(hr, min, sec); // validate and set time
13 } // end Time constructor
14
15 // set new Time value using universal time; ensure that
16 // the data remains consistent by setting invalid values to zero
17 void Time::setTime(int h, int m, int s)
18 {
19 setHour(h); // set private field hour
20 setMinute(m); // set private field minute
21 setSecond(s); // set private field second
22 } // end function setTime
23
24 // set hour value
25 void Time::setHour(int h)
26 {

```

---

**Fig. 17.9** | Time class member-function definitions including a constructor that takes arguments. (Part I of 2.)

---

```

27 hour = (h >= 0 && h < 24) ? h : 0; // validate hour
28 } // end function setHour
29
30 // set minute value
31 void Time::setMinute(int m)
32 {
33 minute = (m >= 0 && m < 60) ? m : 0; // validate minute
34 } // end function setMinute
35
36 // set second value
37 void Time::setSecond(int s)
38 {
39 second = (s >= 0 && s < 60) ? s : 0; // validate second
40 } // end function setSecond
41
42 // return hour value
43 int Time::getHour()
44 {
45 return hour;
46 } // end function getHour
47
48 // return minute value
49 int Time::getMinute()
50 {
51 return minute;
52 } // end function getMinute
53
54 // return second value
55 int Time::getSecond()
56 {
57 return second;
58 } // end function getSecond
59
60 // print Time in universal-time format (HH:MM:SS)
61 void Time::printUniversal()
62 {
63 cout << setfill('0') << setw(2) << getHour() << ":"
64 << setw(2) << getMinute() << ":" << setw(2) << getSecond();
65 } // end function printUniversal
66
67 // print Time in standard-time format (HH:MM:SS AM or PM)
68 void Time::printStandard()
69 {
70 cout << ((getHour() == 0 || getHour() == 12) ? 12 : getHour() % 12)
71 << ":" << setfill('0') << setw(2) << getMinute()
72 << ":" << setw(2) << getSecond() << (hour < 12 ? " AM" : " PM");
73 } // end function printStandard

```

---

**Fig. 17.9** | Time class member-function definitions including a constructor that takes arguments.  
(Part 2 of 2.)

The Time constructor could be written to include the same statements as member function setTime, or even the individual statements in the setHour, setMinute and setSecond functions. Calling setHour, setMinute and setSecond from the constructor may

be slightly more efficient because the extra call to `setTime` would be eliminated. Similarly, copying the code from lines 27, 33 and 39 into constructor would eliminate the overhead of calling `setTime`, `setHour`, `setMinute` and `setSecond`. Coding the `Time` constructor or member function `setTime` as a copy of the code in lines 27, 33 and 39 would make maintenance of this class more difficult. If the implementations of `setHour`, `setMinute` and `setSecond` were to change, the implementation of any member function that duplicates lines 27, 33 and 39 would have to change accordingly. Having the `Time` constructor call `setTime` and having `setTime` call `setHour`, `setMinute` and `setSecond` enables us to limit the changes to code that validates the hour, minute or second to the corresponding *set* function. This reduces the likelihood of errors when altering the class's implementation. Also, the performance of the `Time` constructor and `setTime` can be enhanced by explicitly declaring them `inline` or by defining them in the class definition (which implicitly inlines the function definition).



### Software Engineering Observation 17.9

*If a member function of a class already provides all or part of the functionality required by a constructor (or other member function) of the class, call that member function from the constructor (or other member function). This simplifies the maintenance of the code and reduces the likelihood of an error if the implementation of the code is modified. As a general rule: Avoid repeating code.*



### Software Engineering Observation 17.10

*Any change to the default argument values of a function requires the client code to be recompiled (to ensure that the program still functions correctly).*

Function `main` in Fig. 17.10 initializes five `Time` objects—one with all three arguments defaulted in the implicit constructor call (line 9), one with one argument specified (line 10), one with two arguments specified (line 11), one with three arguments specified (line 12) and one with three invalid arguments specified (line 13). Then the program displays each object in universal-time and standard-time formats.

```

1 // Fig. 17.10: fig17_10.cpp
2 // Demonstrating a default constructor for class Time.
3 #include <iostream>
4 #include "Time.h" // include definition of class Time from Time.h
5 using namespace std;
6
7 int main()
8 {
9 Time t1; // all arguments defaulted
10 Time t2(2); // hour specified; minute and second defaulted
11 Time t3(21, 34); // hour and minute specified; second defaulted
12 Time t4(12, 25, 42); // hour, minute and second specified
13 Time t5(27, 74, 99); // all bad values specified
14
15 cout << "Constructed with:\n\nt1: all arguments defaulted\n ";
16 t1.printUniversal(); // 00:00:00
17 cout << "\n ";

```

**Fig. 17.10** | Constructor with default arguments. (Part I of 2.)

```

18 t1.printStandard(); // 12:00:00 AM
19
20 cout << "\n\t2: hour specified; minute and second defaulted\n ";
21 t2.printUniversal(); // 02:00:00
22 cout << "\n ";
23 t2.printStandard(); // 2:00:00 AM
24
25 cout << "\n\t3: hour and minute specified; second defaulted\n ";
26 t3.printUniversal(); // 21:34:00
27 cout << "\n ";
28 t3.printStandard(); // 9:34:00 PM
29
30 cout << "\n\t4: hour, minute and second specified\n ";
31 t4.printUniversal(); // 12:25:42
32 cout << "\n ";
33 t4.printStandard(); // 12:25:42 PM
34
35 cout << "\n\t5: all invalid values specified\n ";
36 t5.printUniversal(); // 00:00:00
37 cout << "\n ";
38 t5.printStandard(); // 12:00:00 AM
39 cout << endl;
40 } // end main

```

Constructed with:

```

t1: all arguments defaulted
 00:00:00
 12:00:00 AM

t2: hour specified; minute and second defaulted
 02:00:00
 2:00:00 AM

t3: hour and minute specified; second defaulted
 21:34:00
 9:34:00 PM

t4: hour, minute and second specified
 12:25:42
 12:25:42 PM

t5: all invalid values specified
 00:00:00
 12:00:00 AM

```

**Fig. 17.10** | Constructor with default arguments. (Part 2 of 2.)

### *Notes Regarding Class Time's Set and Get Functions and Constructor*

Time's *set* and *get* functions are called throughout the class's body. In particular, function `setTime` (lines 17–22 of Fig. 17.9) calls functions `setHour`, `setMinute` and `setSecond`, and functions `printUniversal` and `printStandard` call functions `getHour`, `getMinute` and `getSecond` in line 63–64 and lines 70–72, respectively. In each case, these functions could have accessed the class's private data directly. However, consider changing the rep-

resentation of the time from three `int` values (requiring 12 bytes of memory) to a single `int` value representing the total number of seconds that have elapsed since midnight (requiring only four bytes of memory). If we made such a change, only the bodies of the functions that access the private data directly would need to change—in particular, the individual *set* and *get* functions for the hour, minute and second. There would be no need to modify the bodies of functions `setTime`, `printUniversal` or `printStandard`, because they do not access the data directly. Designing the class in this manner reduces the likelihood of programming errors when altering the class’s implementation.

Similarly, the `Time` constructor could be written to include a copy of the appropriate statements from function `setTime`. Doing so may be slightly more efficient, because the extra constructor call and call to `setTime` are eliminated. However, duplicating statements in multiple functions or constructors makes changing the class’s internal data representation more difficult. Having the `Time` constructor call function `setTime` directly requires any changes to the implementation of `setTime` to be made only once.



### Common Programming Error 17.2

*A constructor can call other member functions of the class, such as *set* or *get* functions, but because the constructor is initializing the object, the data members may not yet be in a consistent state. Using data members before they have been properly initialized can cause logic errors.*

## 17.7 Destructors

A **destructor** is another type of special member function. The name of the destructor for a class is the **tilde character** (~) followed by the class name. This naming convention has intuitive appeal, because as we’ll see in a later chapter, the tilde operator is the bitwise complement operator, and, in a sense, the destructor is the complement of the constructor. A destructor is often referred to with the abbreviation “dtor” in the literature. We prefer not to use this abbreviation.

A class’s destructor is called implicitly when an object is destroyed. This occurs, for example, as an automatic object is destroyed when program execution leaves the scope in which that object was instantiated. *The destructor itself does not actually release the object’s memory*—it performs **termination housekeeping** before the object’s memory is reclaimed, so the memory may be reused to hold new objects.

A destructor receives no parameters and returns no value. A destructor may not specify a return type—not even `void`. A class may have only one destructor—destructor overloading is not allowed. A destructor must be `public`.



### Common Programming Error 17.3

*It’s a syntax error to attempt to pass arguments to a destructor, to specify a return type for a destructor (even *void* cannot be specified), to return values from a destructor or to overload a destructor.*

Even though destructors have not been provided for the classes presented so far, every class has a destructor. If you do not explicitly provide a destructor, the compiler creates an “empty” destructor. [Note: We’ll see that such an implicitly created destructor does, in fact, perform important operations on objects that are created through composition

(Chapter 18) and inheritance (Chapter 20).] In Chapter 19, we'll build destructors appropriate for classes whose objects contain dynamically allocated memory (e.g., for arrays and strings) or use other system resources (e.g., files on disk). We discuss how to dynamically allocate and deallocate memory in Chapter 18.



### Software Engineering Observation 17.11

*Constructors and destructors have much greater prominence in C++ and object-oriented programming than is possible to convey after only our brief introduction here.*

## 17.8 When Constructors and Destructors are Called

Constructors and destructors are called implicitly by the compiler. The order in which these function calls occur depends on the order in which execution enters and leaves the scopes where the objects are instantiated. Generally, destructor calls are made in the reverse order of the corresponding constructor calls, but as we'll see in Figs. 17.11–17.13, the storage classes of objects can alter the order in which destructors are called.

Constructors are called for objects defined in global scope before any other function (including `main`) in that file begins execution (although the order of execution of global object constructors between files is not guaranteed). The corresponding destructors are called when `main` terminates. Function `exit` forces a program to terminate immediately and does not execute the destructors of automatic objects. The function often is used to terminate a program when an error is detected in the input or if a file to be processed by the program cannot be opened. Function `abort` performs similarly to function `exit` but forces the program to terminate immediately, without allowing the destructors of any objects to be called. Function `abort` is usually used to indicate an abnormal termination of the program. (See Chapter 14, for more information on functions `exit` and `abort`.)

The constructor for an automatic local object is called when execution reaches the point where that object is defined—the corresponding destructor is called when execution leaves the object's scope (i.e., the block in which that object is defined has finished executing). Constructors and destructors for automatic objects are called each time execution enters and leaves the scope of the object. Destructors are not called for automatic objects if the program terminates with a call to function `exit` or function `abort`.

The constructor for a static local object is called only once, when execution first reaches the point where the object is defined—the corresponding destructor is called when `main` terminates or the program calls function `exit`. Global and static objects are destroyed in the reverse order of their creation. Destructors are not called for static objects if the program terminates with a call to function `abort`.

The program of Figs. 17.11–17.13 demonstrates the order in which constructors and destructors are called for objects of class `CreateAndDestroy` (Fig. 17.11 and Fig. 17.12) of various storage classes in several scopes. Each object of class `CreateAndDestroy` contains an integer (`objectID`) and a string (`message`) that are used in the program's output to identify the object (Fig. 17.11 lines 16–17). This mechanical example is purely for pedagogic purposes. For this reason, line 21 of the destructor in Fig. 17.12 determines whether the object being destroyed has an `objectID` value 1 or 6 and, if so, outputs a newline character. This line makes the program's output easier to follow.



---

```

1 // Fig. 17.11: CreateAndDestroy.h
2 // CreateAndDestroy class definition.
3 // Member functions defined in CreateAndDestroy.cpp.
4 #include <string>
5 using namespace std;
6
7 #ifndef CREATE_H
8 #define CREATE_H
9
10 class CreateAndDestroy
11 {
12 public:
13 CreateAndDestroy(int, string); // constructor
14 ~CreateAndDestroy(); // destructor
15 private:
16 int objectID; // ID number for object
17 string message; // message describing object
18 }; // end class CreateAndDestroy
19
20 #endif

```

---

**Fig. 17.11** | CreateAndDestroy class definition.

---

```

1 // Fig. 17.12: CreateAndDestroy.cpp
2 // CreateAndDestroy class member-function definitions.
3 #include <iostream>
4 #include "CreateAndDestroy.h" // include CreateAndDestroy class definition
5 using namespace std;
6
7 // constructor
8 CreateAndDestroy::CreateAndDestroy(int ID, string messageString)
9 {
10 objectID = ID; // set object's ID number
11 message = messageString; // set object's descriptive message
12
13 cout << "Object " << objectID << " constructor runs "
14 << message << endl;
15 } // end CreateAndDestroy constructor
16
17 // destructor
18 CreateAndDestroy::~~CreateAndDestroy()
19 {
20 // output newline for certain objects; helps readability
21 cout << (objectID == 1 || objectID == 6 ? "\n" : "");
22
23 cout << "Object " << objectID << " destructor runs "
24 << message << endl;
25 } // end ~CreateAndDestroy destructor

```

---

**Fig. 17.12** | CreateAndDestroy class member-function definitions.

---

Figure 17.13 defines object `first` (line 10) in global scope. Its constructor is actually called before any statements in `main` execute and its destructor is called at program termination after the destructors for all other objects have run.

Function `main` (lines 12–23) declares three objects. Objects `second` (line 15) and `fourth` (line 21) are local automatic objects, and object `third` (line 16) is a static local object. The constructor for each of these objects is called when execution reaches the point where that object is declared. The destructors for objects `fourth` then `second` are called (i.e., the reverse of the order in which their constructors were called) when execution reaches the end of `main`. Because object `third` is static, it exists until program termination. The destructor for object `third` is called before the destructor for global object `first`, but after all other objects are destroyed.

Function `create` (lines 26–33) declares three objects—`fifth` (line 29) and `seventh` (line 31) as local automatic objects, and `sixth` (line 30) as a static local object. The destructors for objects `seventh` then `fifth` are called (i.e., the reverse of the order in which their constructors were called) when `create` terminates. Because `sixth` is static, it exists until program termination. The destructor for `sixth` is called before the destructors for `third` and `first`, but after all other objects are destroyed.

---

```

1 // Fig. 17.13: fig17_13.cpp
2 // Demonstrating the order in which constructors and
3 // destructors are called.
4 #include <iostream>
5 #include "CreateAndDestroy.h" // include CreateAndDestroy class definition
6 using namespace std;
7
8 void create(void); // prototype
9
10 CreateAndDestroy first(1, "(global before main)"); // global object
11
12 int main()
13 {
14 cout << "\nMAIN FUNCTION: EXECUTION BEGINS" << endl;
15 CreateAndDestroy second(2, "(local automatic in main)");
16 static CreateAndDestroy third(3, "(local static in main)");
17
18 create(); // call function to create objects
19
20 cout << "\nMAIN FUNCTION: EXECUTION RESUMES" << endl;
21 CreateAndDestroy fourth(4, "(local automatic in main)");
22 cout << "\nMAIN FUNCTION: EXECUTION ENDS" << endl;
23 } // end main
24
25 // function to create objects
26 void create(void)
27 {
28 cout << "\nCREATE FUNCTION: EXECUTION BEGINS" << endl;
29 CreateAndDestroy fifth(5, "(local automatic in create)");
30 static CreateAndDestroy sixth(6, "(local static in create)");
31 CreateAndDestroy seventh(7, "(local automatic in create)");
32 cout << "\nCREATE FUNCTION: EXECUTION ENDS" << endl;
33 } // end function create

```

---

**Fig. 17.13** | Order in which constructors and destructors are called. (Part I of 2.)

```

Object 1 constructor runs (global before main)

MAIN FUNCTION: EXECUTION BEGINS
Object 2 constructor runs (local automatic in main)
Object 3 constructor runs (local static in main)

CREATE FUNCTION: EXECUTION BEGINS
Object 5 constructor runs (local automatic in create)
Object 6 constructor runs (local static in create)
Object 7 constructor runs (local automatic in create)

CREATE FUNCTION: EXECUTION ENDS
Object 7 destructor runs (local automatic in create)
Object 5 destructor runs (local automatic in create)

MAIN FUNCTION: EXECUTION RESUMES
Object 4 constructor runs (local automatic in main)

MAIN FUNCTION: EXECUTION ENDS
Object 4 destructor runs (local automatic in main)
Object 2 destructor runs (local automatic in main)

Object 6 destructor runs (local static in create)
Object 3 destructor runs (local static in main)

Object 1 destructor runs (global before main)

```

**Fig. 17.13** | Order in which constructors and destructors are called. (Part 2 of 2.)

## 17.9 Time Class Case Study: A Subtle Trap—Returning a Reference to a private Data Member

A reference to an object is an alias for the name of the object and, hence, may be used on the left side of an assignment statement. In this context, the reference makes a perfectly acceptable *lvalue* that can receive a value. One way to use this capability (unfortunately!) is to have a public member function of a class return a reference to a private data member of that class. If a function returns a const reference, that reference cannot be used as a modifiable *lvalue*.

The program of Figs. 17.14–17.16 uses a simplified Time class (Fig. 17.14 and Fig. 17.15) to demonstrate returning a reference to a private data member with member function `badSetHour` (declared in Fig. 17.14 in line 15 and defined in Fig. 17.15 in lines 27–31). Such a reference return actually makes a call to member function `badSetHour` an alias for private data member `hour`! The function call can be used in any way that the private data member can be used, including as an *lvalue* in an assignment statement, thus *enabling clients of the class to clobber the class's private data at will*! The same problem would occur if a pointer to the private data were to be returned by the function.

```

1 // Fig. 17.14: Time.h
2 // Time class declaration.
3 // Member functions defined in Time.cpp
4

```

**Fig. 17.14** | Time class declaration. (Part 1 of 2.)

---

```

5 // prevent multiple inclusions of header file
6 #ifndef TIME_H
7 #define TIME_H
8
9 class Time
10 {
11 public:
12 Time(int = 0, int = 0, int = 0);
13 void setTime(int, int, int);
14 int getHour();
15 int &badSetHour(int); // DANGEROUS reference return
16 private:
17 int hour;
18 int minute;
19 int second;
20 }; // end class Time
21
22 #endif

```

---

**Fig. 17.14** | Time class declaration. (Part 2 of 2.)

---

```

1 // Fig. 17.15: Time.cpp
2 // Time class member-function definitions.
3 #include "Time.h" // include definition of class Time
4
5 // constructor function to initialize private data; calls member function
6 // setTime to set variables; default values are 0 (see class definition)
7 Time::Time(int hr, int min, int sec)
8 {
9 setTime(hr, min, sec);
10 } // end Time constructor
11
12 // set values of hour, minute and second
13 void Time::setTime(int h, int m, int s)
14 {
15 hour = (h >= 0 && h < 24) ? h : 0; // validate hour
16 minute = (m >= 0 && m < 60) ? m : 0; // validate minute
17 second = (s >= 0 && s < 60) ? s : 0; // validate second
18 } // end function setTime
19
20 // return hour value
21 int Time::getHour()
22 {
23 return hour;
24 } // end function getHour
25
26 // POOR PRACTICE: Returning a reference to a private data member.
27 int &Time::badSetHour(int hh)
28 {
29 hour = (hh >= 0 && hh < 24) ? hh : 0;
30 return hour; // DANGEROUS reference return
31 } // end function badSetHour

```

---

**Fig. 17.15** | Time class member-function definitions.

Figure 17.16 declares Time object `t` (line 10) and reference `hourRef` (line 13), which is initialized with the reference returned by the call `t.badSetHour(20)`. Line 15 displays the value of the alias `hourRef`. This shows how `hourRef` breaks the encapsulation of the class—statements in `main` should not have access to the private data of the class. Next, line 16 uses the alias to set the value of `hour` to 30 (an invalid value) and line 17 displays the value returned by function `getHour` to show that assigning a value to `hourRef` actually modifies the private data in the Time object `t`. Finally, line 21 uses the `badSetHour` function call itself as an *lvalue* and assigns 74 (another invalid value) to the reference returned by the function. Line 26 again displays the value returned by function `getHour` to show that assigning a value to the result of the function call in line 21 modifies the private data in the Time object `t`.

```

1 // Fig. 17.16: fig17_16.cpp
2 // Demonstrating a public member function that
3 // returns a reference to a private data member.
4 #include <iostream>
5 #include "Time.h" // include definition of class Time
6 using namespace std;
7
8 int main()
9 {
10 Time t; // create Time object
11
12 // initialize hourRef with the reference returned by badSetHour
13 int &hourRef = t.badSetHour(20); // 20 is a valid hour
14
15 cout << "Valid hour before modification: " << hourRef;
16 hourRef = 30; // use hourRef to set invalid value in Time object t
17 cout << "\nInvalid hour after modification: " << t.getHour();
18
19 // Dangerous: Function call that returns
20 // a reference can be used as an lvalue!
21 t.badSetHour(12) = 74; // assign another invalid value to hour
22
23 cout << "\n\n*****\n"
24 << "POOR PROGRAMMING PRACTICE!!!!!!\n"
25 << "t.badSetHour(12) as an lvalue, invalid hour: "
26 << t.getHour()
27 << "\n*****" << endl;
28 } // end main

```

```

Valid hour before modification: 20
Invalid hour after modification: 30

```

```

POOR PROGRAMMING PRACTICE!!!!!!
t.badSetHour(12) as an lvalue, invalid hour: 74

```

**Fig. 17.16** | Returning a reference to a private data member.

**Error-Prevention Tip 17.4**

*Returning a reference or a pointer to a private data member breaks the encapsulation of the class and makes the client code dependent on the representation of the class's data; this is a dangerous practice that should be avoided.*

## 17.10 Default Memberwise Assignment

The assignment operator (=) can be used to assign an object to another object of the same type. By default, such assignment is performed by **memberwise assignment**—each data member of the object on the right of the assignment operator is assigned individually to the same data member in the object on the left of the assignment operator. Figures 17.17–17.18 define class `Date` for use in this example. Line 18 of Fig. 17.19 uses **default memberwise assignment** to assign the data members of `Date` object `date1` to the corresponding data members of `Date` object `date2`. In this case, the month member of `date1` is assigned to the month member of `date2`, the day member of `date1` is assigned to the day member of `date2` and the year member of `date1` is assigned to the year member of `date2`. [Caution: Memberwise assignment can cause serious problems when used with a class whose data members contain pointers to dynamically allocated memory; we discuss these problems in Chapter 19 and show how to deal with them.] The `Date` constructor does not contain any error checking; we leave this to the exercises.

---

```

1 // Fig. 17.17: Date.h
2 // Date class declaration. Member functions are defined in Date.cpp.
3
4 // prevent multiple inclusions of header file
5 #ifndef DATE_H
6 #define DATE_H
7
8 // class Date definition
9 class Date
10 {
11 public:
12 Date(int = 1, int = 1, int = 2000); // default constructor
13 void print();
14 private:
15 int month;
16 int day;
17 int year;
18 }; // end class Date
19
20 #endif

```

---

**Fig. 17.17** | Date class declaration.

---

```

1 // Fig. 17.18: Date.cpp
2 // Date class member-function definitions.
3 #include <iostream>
4 #include "Date.h" // include definition of class Date from Date.h

```

---

**Fig. 17.18** | Date class member-function definitions. (Part I of 2.)

---

```

5 using namespace std;
6
7 // Date constructor (should do range checking)
8 Date::Date(int m, int d, int y)
9 {
10 month = m;
11 day = d;
12 year = y;
13 } // end constructor Date
14
15 // print Date in the format mm/dd/yyyy
16 void Date::print()
17 {
18 cout << month << '/' << day << '/' << year;
19 } // end function print

```

---

**Fig. 17.18** | Date class member-function definitions. (Part 2 of 2.)

---

```

1 // Fig. 17.19: fig17_19.cpp
2 // Demonstrating that class objects can be assigned
3 // to each other using default memberwise assignment.
4 #include <iostream>
5 #include "Date.h" // include definition of class Date from Date.h
6 using namespace std;
7
8 int main()
9 {
10 Date date1(7, 4, 2004);
11 Date date2; // date2 defaults to 1/1/2000
12
13 cout << "date1 = ";
14 date1.print();
15 cout << "\ndate2 = ";
16 date2.print();
17
18 date2 = date1; // default memberwise assignment
19
20 cout << "\n\nAfter default memberwise assignment, date2 = ";
21 date2.print();
22 cout << endl;
23 } // end main

```

```
date1 = 7/4/2004
```

```
date2 = 1/1/2000
```

```
After default memberwise assignment, date2 = 7/4/2004
```

---

**Fig. 17.19** | Default memberwise assignment.

Objects may be passed as function arguments and may be returned from functions. Such passing and returning is performed using pass-by-value by default—a copy of the object is passed or returned. In such cases, C++ creates a new object and uses a **copy constructor** to copy the original object's values into the new object. For each class, the compiler

provides a default copy constructor that copies each member of the original object into the corresponding member of the new object. Like memberwise assignment, copy constructors can cause serious problems when used with a class whose data members contain pointers to dynamically allocated memory. Chapter 19 discusses how to define customized copy constructors that properly copy objects containing pointers to dynamically allocated memory.



### Performance Tip 17.3

*Passing an object by value is good from a security standpoint, because the called function has no access to the original object in the caller, but pass-by-value can degrade performance when making a copy of a large object. An object can be passed by reference by passing either a pointer or a reference to the object. Pass-by-reference offers good performance but is weaker from a security standpoint, because the called function is given access to the original object. Pass-by-const-reference is a safe, good-performing alternative (this can be implemented with a const reference parameter or with a pointer-to-const-data parameter).*

## 17.11 Wrap-Up

This chapter deepened our coverage of classes, using a rich Time class case study to introduce several new features. You saw that member functions are usually shorter than global functions because member functions can directly access an object's data members, so the member functions can receive fewer arguments than functions in procedural programming languages. You learned how to use the arrow operator to access an object's members via a pointer of the object's class type.

You learned that member functions have class scope—the member function's name is known only to the class's other members unless referred to via an object of the class, a reference to an object of the class, a pointer to an object of the class or the binary scope resolution operator. We also discussed access functions (commonly used to retrieve the values of data members or to test the truth or falsity of conditions) and utility functions (private member functions that support the operation of the class's public member functions).

You learned that a constructor can specify default arguments that enable it to be called in a variety of ways. You also learned that any constructor that can be called with no arguments is a default constructor and that there can be at most one default constructor per class. We discussed destructors and their purpose of performing termination housekeeping on an object of a class before that object is destroyed. We also demonstrated the order in which an object's constructors and destructors are called.

We demonstrated the problems that can occur when a member function returns a reference to a private data member, which breaks the encapsulation of the class. We also showed that objects of the same type can be assigned to one another using default memberwise assignment. We also discussed the benefits of using class libraries to enhance the speed with which code can be created and to increase the quality of software.

Chapter 18 presents additional class features. We'll demonstrate how `const` can be used to indicate that a member function does not modify an object of a class. You'll build classes with composition, which allows a class to contain objects of other classes as members. We'll show how a class can allow so-called "friend" functions to access the class's non-public members. We'll also show how a class's non-static member functions can use a special pointer named `this` to access an object's members.



## Summary

### Section 17.2 Time Class Case Study

- Preprocessor directives `#ifndef` (which means “if not defined”) and `#endif` are used to prevent multiple inclusions of a header file. If the code between these directives has not previously been included in an application, `#define` defines a name that can be used to prevent future inclusions, and the code is included in the source code file.
- Data members cannot be initialized where they’re declared in the class body (except for a class’s static const data members of integral or enum types). Initialize these data members in the class’s constructor (as there is no default initialization for data members of fundamental types).
- Stream manipulator `setfill` specifies the fill character that is displayed when an integer is output in a field that is wider than the number of digits in the value.
- By default, the fill characters appear before the digits in the number.
- Stream manipulator `setfill` is a “sticky” setting, meaning that once the fill character is set, it applies for all subsequent fields being printed.
- Even though a member function declared in a class definition may be defined outside that class definition (and “tied” to the class via the binary scope resolution operator), that member function is still within that class’s scope.
- If a member function is defined in the body of a class definition, the C++ compiler attempts to inline calls to the member function.
- Classes can include objects of other classes as members or they may be derived from other classes that provide attributes and behaviors the new classes can use.

### Section 17.3 Class Scope and Accessing Class Members

- A class’s data members and member functions belong to that class’s scope.
- Nonmember functions are defined at global namespace scope.
- Within a class’s scope, class members are immediately accessible by all of that class’s member functions and can be referenced by name.
- Outside a class’s scope, class members are referenced through one of the handles on an object—an object name, a reference to an object or a pointer to an object.
- Member functions of a class can be overloaded, but only by other member functions of that class.
- To overload a member function, provide in the class definition a prototype for each version of the overloaded function, and provide a separate definition for each version of the function.
- Variables declared in a member function have local scope and are known only to that function.
- If a member function defines a variable with the same name as a variable with class scope, the class-scope variable is hidden by the block-scope variable in the local scope.
- The dot member selection operator (`.`) is preceded by an object’s name or by a reference to an object to access the object’s public members.
- The arrow member selection operator (`->`) is preceded by a pointer to an object to access that object’s public members.

### Section 17.4 Separating Interface from Implementation

- Header files contain some portions of a class’s implementation and hints about others. Inline member functions, for example, should be in a header file, so that when the compiler compiles a client, the client can include the inline function definition in place.
- A class’s private members that are listed in the class definition in the header file are visible to clients, even though the clients may not access the private members.

### Section 17.5 Access Functions and Utility Functions

- A utility function is a private member function that supports the operation of the class's public member functions. Utility functions are not intended to be used by clients of a class.

### Section 17.6 Time Class Case Study: Constructors with Default Arguments

- Like other functions, constructors can specify default arguments.

### Section 17.7 Destructors

- A class's destructor is called implicitly when an object of the class is destroyed.
- The name of the destructor for a class is the tilde (~) character followed by the class name.
- A destructor does not release an object's storage—it performs termination housekeeping before the system reclaims an object's memory, so the memory may be reused to hold new objects.
- A destructor receives no parameters and returns no value. A class may have only one destructor.
- If you do not explicitly provide a destructor, the compiler creates an “empty” destructor, so every class has exactly one destructor.

### Section 17.8 When Constructors and Destructors are Called

- The order in which constructors and destructors are called depends on the order in which execution enters and leaves the scopes where the objects are instantiated.
- Generally, destructor calls are made in the reverse order of the corresponding constructor calls, but the storage classes of objects can alter the order in which destructors are called.

### Section 17.9 Time Class Case Study: A Subtle Trap—Returning a Reference to a private Data Member

- A reference to an object is an alias for the name of the object and, hence, may be used on the left side of an assignment statement. In this context, the reference makes a perfectly acceptable *lvalue* that can receive a value.
- If the function returns a const reference, then the reference cannot be used as a modifiable *lvalue*.

### Section 17.10 Default Memberwise Assignment

- The assignment operator (=) can be used to assign an object to another object of the same type. By default, such assignment is performed by memberwise assignment.
- Objects may be passed by value to or returned by value from functions. C++ creates a new object and uses a copy constructor to copy the original object's values into the new object.
- For each class, the compiler provides a default copy constructor that copies each member of the original object into the corresponding member of the new object.

## Terminology

abort function 621  
 access function 612  
 aggregation 609  
 arrow member selection operator (->) 610  
 class scope 606  
 composition 609  
 copy constructor 628  
 default memberwise assignment 627  
 #define preprocessor directive 604  
 derive one class from another 609  
 derived 609

destructor 620  
 #endif preprocessor directive 604  
 exit function 621  
 fill character 606  
 handle on an object 609  
 helper function 612  
 #ifndef preprocessor directive 604  
 inheritance 609  
 memberwise assignment 627  
 predicate function 612  
 preprocessor wrapper 604

setfill parameterized stream manipulator 606    tilde character (~) in a destructor name 620  
 termination housekeeping 620

## Self-Review Exercises

**17.1** Fill in the blanks in each of the following:

- Class members are accessed via the \_\_\_\_\_ operator in conjunction with the name of an object (or reference to an object) of the class or via the \_\_\_\_\_ operator in conjunction with a pointer to an object of the class.
- Class members specified as \_\_\_\_\_ are accessible only to member functions of the class and friends of the class.
- Class members specified as \_\_\_\_\_ are accessible anywhere an object of the class is in scope.
- \_\_\_\_\_ can be used to assign an object of a class to another object of the same class.

**17.2** Find the error(s) in each of the following and explain how to correct it (them):

- Assume the following prototype is declared in class `Time`:

```
void ~Time(int);
```

- The following is a partial definition of class `Time`:

```
class Time
{
public:
 // function prototypes

private:
 int hour = 0;
 int minute = 0;
 int second = 0;
}; // end class Time
```

- Assume the following prototype is declared in class `Employee`:

```
int Employee(string, string);
```

## Answers to Self-Review Exercises

**17.1** a) dot (`.`), arrow (`->`). b) `private`. c) `public`. d) Default memberwise assignment (performed by the assignment operator).

**17.2** a) *Error:* Destructors are not allowed to return values (or even specify a return type) or take arguments.

*Correction:* Remove the return type `void` and the parameter `int` from the declaration.

- Error:* Members cannot be explicitly initialized in the class definition.

*Correction:* Remove the explicit initialization from the class definition and initialize the data members in a constructor.

- Error:* Constructors are not allowed to return values.

*Correction:* Remove the return type `int` from the declaration.

## Exercises

**17.3** What's the purpose of the scope resolution operator?

**17.4** (*Enhancing Class `Time`*) Provide a constructor that is capable of using the current time from the `time` and `localtime` functions—declared in the C++ Standard Library header `<ctime>`—to initialize an object of the `Time` class.

**17.5 (Complex Class)** Create a class called `Complex` for performing arithmetic with complex numbers. Write a program to test your class. Complex numbers have the form

$$\text{realPart} + \text{imaginaryPart} * i$$

where  $i$  is

$$\sqrt{-1}$$

Use double variables to represent the private data of the class. Provide a constructor that enables an object of this class to be initialized when it's declared. The constructor should contain default values in case no initializers are provided. Provide public member functions that perform the following tasks:

- Adding two `Complex` numbers: The real parts are added together and the imaginary parts are added together.
- Subtracting two `Complex` numbers: The real part of the right operand is subtracted from the real part of the left operand, and the imaginary part of the right operand is subtracted from the imaginary part of the left operand.
- Printing `Complex` numbers in the form  $(a, b)$ , where  $a$  is the real part and  $b$  is the imaginary part.

**17.6 (Rational Class)** Create a class called `Rational` for performing arithmetic with fractions. Write a program to test your class.

Use integer variables to represent the private data of the class—the numerator and the denominator. Provide a constructor that enables an object of this class to be initialized when it's declared. The constructor should contain default values in case no initializers are provided and should store the fraction in reduced form. For example, the fraction

$$\frac{2}{4}$$

would be stored in the object as 1 in the numerator and 2 in the denominator. Provide public member functions that perform each of the following tasks:

- Adding two `Rational` numbers. The result should be stored in reduced form.
- Subtracting two `Rational` numbers. The result should be stored in reduced form.
- Multiplying two `Rational` numbers. The result should be stored in reduced form.
- Dividing two `Rational` numbers. The result should be stored in reduced form.
- Printing `Rational` numbers in the form  $a/b$ , where  $a$  is the numerator and  $b$  is the denominator.
- Printing `Rational` numbers in floating-point format.

**17.7 (Enhancing Class Time)** Modify the `Time` class of Figs. 17.8–17.9 to include a `tick` member function that increments the time stored in a `Time` object by one second. The `Time` object should always remain in a consistent state. Write a program that tests the `tick` member function in a loop that prints the time in standard format during each iteration of the loop to illustrate that the `tick` member function works correctly. Be sure to test the following cases:

- Incrementing into the next minute.
- Incrementing into the next hour.
- Incrementing into the next day (i.e., 11:59:59 PM to 12:00:00 AM).

**17.8 (Enhancing Class Date)** Modify the `Date` class of Figs. 17.17–17.18 to perform error checking on the initializer values for data members `month`, `day` and `year`. Also, provide a member function `nextDay` to increment the day by one. The `Date` object should always remain in a consistent state. Write a program that tests function `nextDay` in a loop that prints the date during each iteration to illustrate that `nextDay` works correctly. Be sure to test the following cases:

- Incrementing into the next month.
- Incrementing into the next year.

**17.9 (Combining Class *Time* and Class *Date*)** Combine the modified *Time* class of Exercise 17.7 and the modified *Date* class of Exercise 17.8 into one class called *DateAndTime*. (In Chapter 20, we'll discuss inheritance, which will enable us to accomplish this task quickly without modifying the existing class definitions.) Modify the *tick* function to call the *nextDay* function if the time increments into the next day. Modify functions *printStandard* and *printUniversal* to output the date and time. Write a program to test the new class *DateAndTime*. Specifically, test incrementing the time into the next day.

**17.10 (Returning Error Indicators from Class *Time*'s *set* Functions)** Modify the *set* functions in the *Time* class of Figs. 17.8–17.9 to return appropriate error values if an attempt is made to *set* a data member of an object of class *Time* to an invalid value. Write a program that tests your new version of class *Time*. Display error messages when *set* functions return error values.

**17.11 (Rectangle Class)** Create a class *Rectangle* with attributes *length* and *width*, each of which defaults to 1. Provide member functions that calculate the perimeter and the area of the rectangle. Also, provide *set* and *get* functions for the *length* and *width* attributes. The *set* functions should verify that *length* and *width* are each floating-point numbers larger than 0.0 and less than 20.0.

**17.12 (Enhancing Class *Rectangle*)** Create a more sophisticated *Rectangle* class than the one you created in Exercise 17.11. This class stores only the Cartesian coordinates of the four corners of the rectangle. The constructor calls a *set* function that accepts four sets of coordinates and verifies that each of these is in the first quadrant with no single *x*- or *y*-coordinate larger than 20.0. The *set* function also verifies that the supplied coordinates do, in fact, specify a rectangle. Provide member functions that calculate the *length*, *width*, *perimeter* and *area*. The *length* is the larger of the two dimensions. Include a predicate function *square* that determines whether the rectangle is a square.

**17.13 (Enhancing Class *Rectangle*)** Modify class *Rectangle* from Exercise 17.12 to include a *draw* function that displays the rectangle inside a 25-by-25 box enclosing the portion of the first quadrant in which the rectangle resides. Include a *setFillCharacter* function to specify the character out of which the body of the rectangle will be drawn. Include a *setPerimeterCharacter* function to specify the character that will be used to draw the border of the rectangle. If you feel ambitious, you might include functions to scale the size of the rectangle, rotate it, and move it around within the designated portion of the first quadrant.

**17.14 (HugeInteger Class)** Create a class *HugeInteger* that uses a 40-element array of digits to store integers as large as 40 digits each. Provide member functions *input*, *output*, *add* and *subtract*. For comparing *HugeInteger* objects, provide functions *isEqualTo*, *isNotEqualTo*, *isGreaterThan*, *isLessThan*, *isGreaterThanOrEqualTo* and *isLessThanOrEqualTo*—each of these is a “predicate” function that simply returns *true* if the relationship holds between the two *HugeIntegers* and returns *false* if the relationship does not hold. Also, provide a predicate function *isZero*. If you feel ambitious, provide member functions *multiply*, *divide* and *modulus*.

**17.15 (TicTacToe Class)** Create a class *TicTacToe* that will enable you to write a complete program to play the game of tic-tac-toe. The class contains as *private* data a 3-by-3 two-dimensional array of integers. The constructor should initialize the empty board to all zeros. Allow two human players. Wherever the first player moves, place a 1 in the specified square. Place a 2 wherever the second player moves. Each move must be to an empty square. After each move, determine whether the game has been won or is a draw. If you feel ambitious, modify your program so that the computer makes the moves for one of the players. Also, allow the player to specify whether he or she wants to go first or second. If you feel exceptionally ambitious, develop a program that will play three-dimensional tic-tac-toe on a 4-by-4-by-4 board. [Caution: This is an extremely challenging project that could take many weeks of effort!]



# Classes: A Deeper Look, Part 2

# 18

*But what, to serve our private ends,  
Forbids the cheating of our friends?*

—Charles Churchill

*Instead of this absurd division  
into sexes they ought to class  
people as static and dynamic.*

—Evelyn Waugh

*Have no friends not equal to  
yourself.*

—Confucius

## Objectives

In this chapter you'll learn:

- To specify `const` (constant) objects and `const` member functions.
- To create objects composed of other objects.
- To use `friend` functions and `friend` classes.
- To use the `this` pointer.
- To use `static` data members and member functions.
- The concept of a container class.
- The notion of iterator classes that walk through the elements of container classes.
- To use proxy classes to hide implementation details from a class's clients.

- |                                                                                           |                                                     |
|-------------------------------------------------------------------------------------------|-----------------------------------------------------|
| <b>18.1</b> Introduction                                                                  | <b>18.5</b> Using the <code>this</code> Pointer     |
| <b>18.2</b> <code>const</code> (Constant) Objects and <code>const</code> Member Functions | <b>18.6</b> <code>static</code> Class Members       |
| <b>18.3</b> Composition: Objects as Members of Classes                                    | <b>18.7</b> Data Abstraction and Information Hiding |
| <b>18.4</b> <code>friend</code> Functions and <code>friend</code> Classes                 | <b>18.8</b> Wrap-Up                                 |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference

## 18.1 Introduction

In this chapter, we continue our study of classes and data abstraction with several more advanced topics. We use `const` objects and `const` member functions to prevent modifications of objects and enforce the principle of least privilege. We discuss composition—a form of reuse in which a class can have objects of other classes as members. Next, we introduce friendship, which enables a class designer to specify nonmember functions that can access a class's non-`public` members—a technique that is often used in operator overloading (Chapter 19) for performance reasons. We discuss a special pointer (called `this`), which is an implicit argument to each of a class's non-`static` member functions. It allows those member functions to access the correct object's data members and other non-`static` member functions. Finally, we motivate the need for `static` class members and show how to use `static` data members and member functions in your own classes.

## 18.2 `const` (Constant) Objects and `const` Member Functions

Let's see how the principle of least privilege applies to objects. Some objects need to be modifiable and some do not. You may use keyword `const` to specify that an object is not modifiable and that any attempt to modify the object should result in a compilation error. The statement

```
const Time noon(12, 0, 0);
```

declares a `const` object `noon` of class `Time` and initializes it to 12 noon.



### Software Engineering Observation 18.1

*Attempts to modify a `const` object are caught at compile time rather than causing execution-time errors.*



### Performance Tip 18.1

*Declaring variables and objects `const` when appropriate can improve performance—compilers can perform certain optimizations on constants that cannot be performed on variables.*

C++ disallows member function calls for `const` objects unless the member functions themselves are also declared `const`. This is true even for *get* member functions that do not modify the object.

A member function is specified as `const` *both* in its prototype (Fig. 18.1; lines 19–24) and in its definition (Fig. 18.2; lines 43, 49, 55 and 61) by inserting the keyword `const` after the function’s parameter list and, in the case of the function definition, before the left brace that begins the function body.



### Common Programming Error 18.1

*Defining as `const` a member function that modifies a data member of the object is a compilation error.*



### Common Programming Error 18.2

*Defining as `const` a member function that calls a non-`const` member function of the class on the same object is a compilation error.*



### Common Programming Error 18.3

*Invoking a non-`const` member function on a `const` object is a compilation error.*



### Software Engineering Observation 18.2

*A `const` member function can be overloaded with a non-`const` version. The compiler chooses which overloaded member function to use based on the object on which the function is invoked. If the object is `const`, the compiler uses the `const` version. If the object is not `const`, the compiler uses the non-`const` version.*

An interesting problem arises for constructors and destructors, each of which typically modifies objects. A constructor must be allowed to modify an object so that the object can be initialized properly. A destructor must be able to perform its termination housekeeping chores before an object’s memory is reclaimed by the system.



### Common Programming Error 18.4

*Attempting to declare a constructor or destructor `const` is a compilation error.*

### Defining and Using `const` Member Functions

The program of Figs. 18.1–18.3 modifies class `Time` of Figs. 17.8–17.9 by making its *get* functions and `printUniversal` function `const`. In the header file `Time.h` (Fig. 18.1), lines 19–21 and 24 now include keyword `const` after each function’s parameter list. The corresponding definition of each function in Fig. 18.2 (lines 43, 49, 55 and 61, respectively) also specifies keyword `const` after each function’s parameter list.

```
1 // Fig. 18.1: Time.h
2 // Time class definition with const member functions.
3 // Member functions defined in Time.cpp.
4 #ifndef TIME_H
5 #define TIME_H
```

**Fig. 18.1** | Time class definition with `const` member functions. (Part I of 2.)



---

```

6
7 class Time
8 {
9 public:
10 Time(int = 0, int = 0, int = 0); // default constructor
11
12 // set functions
13 void setTime(int, int, int); // set time
14 void setHour(int); // set hour
15 void setMinute(int); // set minute
16 void setSecond(int); // set second
17
18 // get functions (normally declared const)
19 int getHour() const; // return hour
20 int getMinute() const; // return minute
21 int getSecond() const; // return second
22
23 // print functions (normally declared const)
24 void printUniversal() const; // print universal time
25 void printStandard(); // print standard time (should be const)
26 private:
27 int hour; // 0 - 23 (24-hour clock format)
28 int minute; // 0 - 59
29 int second; // 0 - 59
30 }; // end class Time
31
32 #endif

```

---

**Fig. 18.1** | Time class definition with `const` member functions. (Part 2 of 2.)

---

```

1 // Fig. 18.2: Time.cpp
2 // Time class member-function definitions.
3 #include <iostream>
4 #include <iomanip>
5 #include "Time.h" // include definition of class Time
6 using namespace std;
7
8 // constructor function to initialize private data;
9 // calls member function setTime to set variables;
10 // default values are 0 (see class definition)
11 Time::Time(int hour, int minute, int second)
12 {
13 setTime(hour, minute, second);
14 } // end Time constructor
15
16 // set hour, minute and second values
17 void Time::setTime(int hour, int minute, int second)
18 {
19 setHour(hour);
20 setMinute(minute);
21 setSecond(second);
22 } // end function setTime

```

---

**Fig. 18.2** | Time class member-function definitions. (Part 1 of 2.)

---

```

23 // set hour value
24 void Time::setHour(int h)
25 {
26 hour = (h >= 0 && h < 24) ? h : 0; // validate hour
27 } // end function setHour
28
29 // set minute value
30 void Time::setMinute(int m)
31 {
32 minute = (m >= 0 && m < 60) ? m : 0; // validate minute
33 } // end function setMinute
34
35 // set second value
36 void Time::setSecond(int s)
37 {
38 second = (s >= 0 && s < 60) ? s : 0; // validate second
39 } // end function setSecond
40
41 // return hour value
42 int Time::getHour() const // get functions should be const
43 {
44 return hour;
45 } // end function getHour
46
47 // return minute value
48 int Time::getMinute() const
49 {
50 return minute;
51 } // end function getMinute
52
53 // return second value
54 int Time::getSecond() const
55 {
56 return second;
57 } // end function getSecond
58
59 // print Time in universal-time format (HH:MM:SS)
60 void Time::printUniversal() const
61 {
62 cout << setfill('0') << setw(2) << hour << ":"
63 << setw(2) << minute << ":" << setw(2) << second;
64 } // end function printUniversal
65
66 // print Time in standard-time format (HH:MM:SS AM or PM)
67 void Time::printStandard() // note lack of const declaration
68 {
69 cout << ((hour == 0 || hour == 12) ? 12 : hour % 12)
70 << ":" << setfill('0') << setw(2) << minute
71 << ":" << setw(2) << second << (hour < 12 ? " AM" : " PM");
72 } // end function printStandard
73

```

---

**Fig. 18.2** | Time class member-function definitions. (Part 2 of 2.)

Figure 18.3 instantiates two `Time` objects—non-const object `wakeUp` (line 7) and const object `noon` (line 8). The program attempts to invoke non-const member functions `setHour` (line 13) and `printStandard` (line 20) on the const object `noon`. In each case, the compiler generates an error message. The program also illustrates the three other member-function-call combinations on objects—a non-const member function on a non-const object (line 11), a const member function on a non-const object (line 15) and a const member function on a const object (lines 17–18). The error messages generated for non-const member functions called on a const object are shown in the output window.

```

1 // Fig. 18.3: fig18_03.cpp
2 // Attempting to access a const object with non-const member functions.
3 #include "Time.h" // include Time class definition
4
5 int main()
6 {
7 Time wakeUp(6, 45, 0); // non-constant object
8 const Time noon(12, 0, 0); // constant object
9
10 // OBJECT MEMBER FUNCTION
11 wakeUp.setHour(18); // non-const non-const
12
13 noon.setHour(12); // const non-const
14
15 wakeUp.getHour(); // non-const const
16
17 noon.getMinute(); // const const
18 noon.printUniversal(); // const const
19
20 noon.printStandard(); // const non-const
21 } // end main

```

*Microsoft Visual C++ compiler error messages:*

```

C:\examples\ch18\Fig18_01_03\fig18_03.cpp(13) : error C2662:
'Time::setHour' : cannot convert 'this' pointer from 'const Time' to
'Time &'
Conversion loses qualifiers
C:\examples\ch18\Fig18_01_03\fig18_03.cpp(20) : error C2662:
'Time::printStandard' : cannot convert 'this' pointer from 'const Time' to
'Time &'
Conversion loses qualifiers

```

*GNU C++ compiler error messages:*

```

fig18_03.cpp:13: error: passing 'const Time' as 'this' argument of
'void Time::setHour(int)' discards qualifiers
fig18_03.cpp:20: error: passing 'const Time' as 'this' argument of
'void Time::printStandard()' discards qualifiers

```

**Fig. 18.3** | const objects and const member functions.

A constructor must be a non-`const` member function (Fig. 18.2, lines 11–14), but it can still be used to initialize a `const` object (Fig. 18.3, line 8). The `Time` constructor’s definition (Fig. 18.2, lines 11–14) shows that it calls another non-`const` member function—`setTime` (lines 17–22)—to perform the initialization of a `Time` object. Invoking a non-`const` member function from the constructor call as part of the initialization of a `const` object is allowed. The “constness” of a `const` object is enforced from the time the constructor completes initialization of the object until that object’s destructor is called.

Also, line 20 in Fig. 18.3 generates a compilation error even though member function `printStandard` of class `Time` does not modify the object on which it’s invoked. The fact that a member function does not modify an object is not sufficient to indicate that the function is constant function—the function must *explicitly* be declared `const`.

### *Initializing a `const` Data Member with a Member Initializer*

The program of Figs. 18.4–18.6 introduces using [member initializer syntax](#). All data members *can* be initialized using member initializer syntax, but `const` data members and data members that are references *must* be initialized using member initializers. Later in this chapter, we’ll see that member objects must be initialized this way as well.

---

```

1 // Fig. 18.4: Increment.h
2 // Definition of class Increment.
3 #ifndef INCREMENT_H
4 #define INCREMENT_H
5
6 class Increment
7 {
8 public:
9 Increment(int c = 0, int i = 1); // default constructor
10
11 // function addIncrement definition
12 void addIncrement()
13 {
14 count += increment;
15 } // end function addIncrement
16
17 void print() const; // prints count and increment
18 private:
19 int count;
20 const int increment; // const data member
21 }; // end class Increment
22
23 #endif

```

---

**Fig. 18.4** | `Increment` class definition containing non-`const` data member `count` and `const` data member `increment`.

---

```

1 // Fig. 18.5: Increment.cpp
2 // Member-function definitions for class Increment demonstrate using a
3 // member initializer to initialize a constant of a built-in data type.

```

---

**Fig. 18.5** | Member initializer used to initialize a constant of a built-in data type. (Part I of 2.)

---

```

4 #include <iostream>
5 #include "Increment.h" // include definition of class Increment
6 using namespace std;
7
8 // constructor
9 Increment::Increment(int c, int i)
10 : count(c), // initializer for non-const member
11 increment(i) // required initializer for const member
12 {
13 // empty body
14 } // end constructor Increment
15
16 // print count and increment values
17 void Increment::print() const
18 {
19 cout << "count = " << count << ", increment = " << increment << endl;
20 } // end function print

```

---

**Fig. 18.5** | Member initializer used to initialize a constant of a built-in data type. (Part 2 of 2.)

---

```

1 // Fig. 18.6: fig18_06.cpp
2 // Program to test class Increment.
3 #include <iostream>
4 #include "Increment.h" // include definition of class Increment
5 using namespace std;
6
7 int main()
8 {
9 Increment value(10, 5);
10
11 cout << "Before incrementing: ";
12 value.print();
13
14 for (int j = 1; j <= 3; j++)
15 {
16 value.addIncrement();
17 cout << "After increment " << j << ": ";
18 value.print();
19 } // end for
20 } // end main

```

```

Before incrementing: count = 10, increment = 5
After increment 1: count = 15, increment = 5
After increment 2: count = 20, increment = 5
After increment 3: count = 25, increment = 5

```

**Fig. 18.6** | Invoking an Increment object's print and addIncrement member functions.

The constructor definition (Fig. 18.5, lines 9–14) uses a **member initializer list** to initialize class Increment's data members—non-const integer count and const integer increment (declared in lines 19–20 of Fig. 18.4). Member initializers appear between a constructor's parameter list and the left brace that begins the constructor's body. The

member initializer list (Fig. 18.5, lines 10–11) is separated from the parameter list with a colon (:). Each member initializer consists of the data member name followed by parentheses containing the member's initial value. In this example, `count` is initialized with the value of constructor parameter `c` and `increment` is initialized with the value of constructor parameter `i`. Multiple member initializers are separated by commas. Also, the member initializer list executes before the body of the constructor executes.



### Software Engineering Observation 18.3

*A const object cannot be modified by assignment, so it must be initialized. When a data member of a class is declared const, a member initializer must be used to provide the constructor with the initial value of the data member for an object of the class. The same is true for references.*

### Erroneously Attempting to Initialize a const Data Member with an Assignment

The program of Figs. 18.7–18.9 illustrates the compilation errors caused by attempting to initialize const data member `increment` with an assignment statement (Fig. 18.8, line 12) in the `Increment` constructor's body rather than with a member initializer. Line 11 of Fig. 18.8 does not generate a compilation error, because `count` is not declared const.



### Common Programming Error 18.5

*Not providing a member initializer for a const data member is a compilation error.*



### Software Engineering Observation 18.4

*Constant data members (const objects and const variables) and data members declared as references must be initialized with member initializer syntax; assignments for these types of data in the constructor body are not allowed.*

```

1 // Fig. 18.7: Increment.h
2 // Definition of class Increment.
3 #ifndef INCREMENT_H
4 #define INCREMENT_H
5
6 class Increment
7 {
8 public:
9 Increment(int c = 0, int i = 1); // default constructor
10
11 // function addIncrement definition
12 void addIncrement()
13 {
14 count += increment;
15 } // end function addIncrement
16
17 void print() const; // prints count and increment
18 private:
19 int count;

```

**Fig. 18.7** | `Increment` class definition containing non-const data member `count` and const data member `increment`. (Part 1 of 2.)

---

```

20 const int increment; // const data member
21 }; // end class Increment
22
23 #endif

```

---

**Fig. 18.7** | Increment class definition containing non-const data member count and const data member increment. (Part 2 of 2.)

---

```

1 // Fig. 18.8: Increment.cpp
2 // Erroneous attempt to initialize a constant of a built-in data
3 // type by assignment.
4 #include <iostream>
5 #include "Increment.h" // include definition of class Increment
6 using namespace std;
7
8 // constructor; constant member 'increment' is not initialized
9 Increment::Increment(int c, int i)
10 {
11 count = c; // allowed because count is not constant
12 increment = i; // ERROR: Cannot modify a const object
13 } // end constructor Increment
14
15 // print count and increment values
16 void Increment::print() const
17 {
18 cout << "count = " << count << ", increment = " << increment << endl;
19 } // end function print

```

---

**Fig. 18.8** | Erroneous attempt to initialize a constant of a built-in data type by assignment.

---

```

1 // Fig. 18.9: fig18_09.cpp
2 // Program to test class Increment.
3 #include <iostream>
4 #include "Increment.h" // include definition of class Increment
5 using namespace std;
6
7 int main()
8 {
9 Increment value(10, 5);
10
11 cout << "Before incrementing: ";
12 value.print();
13
14 for (int j = 1; j <= 3; j++)
15 {
16 value.addIncrement();
17 cout << "After increment " << j << ": ";
18 value.print();
19 } // end for
20 } // end main

```

---

**Fig. 18.9** | Program to test class Increment generates compilation errors. (Part 1 of 2.)

*Microsoft Visual C++ compiler error messages:*

```
C:\examples\ch18\Fig18_07_09\Increment.cpp(10) : error C2758:
'Increment::increment' : must be initialized in constructor base/member
initializer list
C:\cpphttp7_examples\ch18\Fig18_07_09\increment.h(20) : see
declaration of 'Increment::increment'
C:\examples\ch18\Fig18_07_09\Increment.cpp(12) : error C2166:
l-value specifies const object
```

*GNU C++ compiler error messages:*

```
Increment.cpp:9: error: uninitialized member 'Increment::increment' with
'const' type 'const int'
Increment.cpp:12: error: assignment of read-only data-member
'Increment::increment'
```

**Fig. 18.9** | Program to test class `Increment` generates compilation errors. (Part 2 of 2.)

Function `print` (Fig. 18.8, lines 16–19) is declared `const`. It might seem strange to label this function `const`, because a program probably will never have a `const Increment` object. However, it's possible that a program will have a `const` reference to an `Increment` object or a pointer to `const` that points to an `Increment` object. Typically, this occurs when objects of class `Increment` are passed to functions or returned from functions. In these cases, only class `Increment`'s `const` member functions can be called through the reference or pointer. Thus, it's reasonable to declare function `print` as `const`—doing so prevents errors in these situations where an `Increment` object is treated as a `const` object.



#### Error-Prevention Tip 18.1

*Declare as `const` all of a class's member functions that do not modify the object in which they operate. Occasionally this may seem inappropriate, because you'll have no intention of creating `const` objects of that class or accessing objects of that class through `const` references or pointers to `const`. Declaring such member functions `const` does offer a benefit, though. If the member function is inadvertently written to modify the object, the compiler will issue an error message.*

## 18.3 Composition: Objects as Members of Classes

An `AlarmClock` object needs to know when it's supposed to sound its alarm, so why not include a `Time` object as a member of the `AlarmClock` class? Such a capability is called **composition** and is sometimes referred to as a *has-a relationship*—a class can have objects of other classes as members.



#### Software Engineering Observation 18.5

*A common form of software reusability is composition, in which a class has objects of other classes as members.*

When an object is created, its constructor is called automatically. Previously, we saw how to pass arguments to the constructor of an object we created in `main`. This section shows how an object's constructor can pass arguments to member-object constructors via member initializers.





### Software Engineering Observation 18.6

*Member objects are constructed in the order in which they're declared in the class definition (not in the order they're listed in the constructor's member initializer list) and before their enclosing class objects (sometimes called **host objects**) are constructed.*

The next program uses classes `Date` (Figs. 18.10–18.11) and `Employee` (Figs. 18.12–18.13) to demonstrate composition. Class `Employee`'s definition (Fig. 18.12) contains private data members `firstName`, `lastName`, `birthDate` and `hireDate`. Members `birthDate` and `hireDate` are `const` objects of class `Date`, which contains private data members `month`, `day` and `year`. The `Employee` constructor's header (Fig. 18.13, lines 10–11) specifies that the constructor has four parameters (`first`, `last`, `dateOfBirth` and `dateOfHire`). The first two parameters are passed via member initializers to the `string` class constructor. The last two are passed via member initializers to the `Date` class constructor.

---

```

1 // Fig. 18.10: Date.h
2 // Date class definition; Member functions defined in Date.cpp
3 #ifndef DATE_H
4 #define DATE_H
5
6 class Date
7 {
8 public:
9 static const int monthsPerYear = 12; // number of months in a year
10 Date(int = 1, int = 1, int = 1900); // default constructor
11 void print() const; // print date in month/day/year format
12 ~Date(); // provided to confirm destruction order
13 private:
14 int month; // 1-12 (January-December)
15 int day; // 1-31 based on month
16 int year; // any year
17
18 // utility function to check if day is proper for month and year
19 int checkDay(int) const;
20 }; // end class Date
21
22 #endif

```

---

**Fig. 18.10** | Date class definition.

---

```

1 // Fig. 18.11: Date.cpp
2 // Date class member-function definitions.
3 #include <iostream>
4 #include "Date.h" // include Date class definition
5 using namespace std;
6
7 // constructor confirms proper value for month; calls
8 // utility function checkDay to confirm proper value for day

```

---

**Fig. 18.11** | Date class member-function definitions. (Part 1 of 2.)

---

```

 9 Date::Date(int mn, int dy, int yr)
10 {
11 if (mn > 0 && mn <= monthsPerYear) // validate the month
12 month = mn;
13 else
14 {
15 month = 1; // invalid month set to 1
16 cout << "Invalid month (" << mn << ") set to 1.\n";
17 } // end else
18
19 year = yr; // could validate yr
20 day = checkDay(dy); // validate the day
21
22 // output Date object to show when its constructor is called
23 cout << "Date object constructor for date ";
24 print();
25 cout << endl;
26 } // end Date constructor
27
28 // print Date object in form month/day/year
29 void Date::print() const
30 {
31 cout << month << '/' << day << '/' << year;
32 } // end function print
33
34 // output Date object to show when its destructor is called
35 Date::~Date()
36 {
37 cout << "Date object destructor for date ";
38 print();
39 cout << endl;
40 } // end ~Date destructor
41
42 // utility function to confirm proper day value based on
43 // month and year; handles leap years, too
44 int Date::checkDay(int testDay) const
45 {
46 static const int daysPerMonth[monthsPerYear + 1] =
47 { 0, 31, 28, 31, 30, 31, 30, 31, 31, 30, 31, 30, 31 };
48
49 // determine whether testDay is valid for specified month
50 if (testDay > 0 && testDay <= daysPerMonth[month])
51 return testDay;
52
53 // February 29 check for leap year
54 if (month == 2 && testDay == 29 && (year % 400 == 0 ||
55 (year % 4 == 0 && year % 100 != 0)))
56 return testDay;
57
58 cout << "Invalid day (" << testDay << ") set to 1.\n";
59 return 1; // leave object in consistent state if bad value
60 } // end function checkDay

```

---

**Fig. 18.11** | Date class member-function definitions. (Part 2 of 2.)

---

```

1 // Fig. 18.12: Employee.h
2 // Employee class definition showing composition.
3 // Member functions defined in Employee.cpp.
4 #ifndef EMPLOYEE_H
5 #define EMPLOYEE_H
6
7 #include <string>
8 #include "Date.h" // include Date class definition
9 using namespace std;
10
11 class Employee
12 {
13 public:
14 Employee(const string &, const string &,
15 const Date &, const Date &);
16 void print() const;
17 ~Employee(); // provided to confirm destruction order
18 private:
19 string firstName; // composition: member object
20 string lastName; // composition: member object
21 const Date birthDate; // composition: member object
22 const Date hireDate; // composition: member object
23 }; // end class Employee
24
25 #endif

```

---

**Fig. 18.12** | Employee class definition showing composition.

---

```

1 // Fig. 18.13: Employee.cpp
2 // Employee class member-function definitions.
3 #include <iostream>
4 #include "Employee.h" // Employee class definition
5 #include "Date.h" // Date class definition
6 using namespace std;
7
8 // constructor uses member initializer list to pass initializer
9 // values to constructors of member objects
10 Employee::Employee(const string &first, const string &last,
11 const Date &dateOfBirth, const Date &dateOfHire)
12 : firstName(first), // initialize firstName
13 lastName(last), // initialize lastName
14 birthDate(dateOfBirth), // initialize birthDate
15 hireDate(dateOfHire) // initialize hireDate
16 {
17 // output Employee object to show when constructor is called
18 cout << "Employee object constructor: "
19 << firstName << ' ' << lastName << endl;
20 } // end Employee constructor
21

```

---

**Fig. 18.13** | Employee class member-function definitions, including constructor with a member initializer list. (Part 1 of 2.)

---

```

22 // print Employee object
23 void Employee::print() const
24 {
25 cout << lastName << ", " << firstName << " Hired: ";
26 hireDate.print();
27 cout << " Birthday: ";
28 birthDate.print();
29 cout << endl;
30 } // end function print
31
32 // output Employee object to show when its destructor is called
33 Employee::~Employee()
34 {
35 cout << "Employee object destructor: "
36 << lastName << ", " << firstName << endl;
37 } // end ~Employee destructor

```

---

**Fig. 18.13** | *Employee* class member-function definitions, including constructor with a member initializer list. (Part 2 of 2.)

### ***Employee Constructor's Member Initializer List***

The colon (:) following the constructor's header (Fig. 18.13, line 12) begins the member initializer list. The member initializers specify the *Employee* constructor parameters being passed to the constructors of the *string* and *Date* data members. Parameters *first*, *last*, *dateOfBirth* and *dateOfHire* are passed to the constructors for objects *firstName*'s (Fig. 18.13, line 12), *lastName* (Fig. 18.13, line 13), *birthDate* (Fig. 18.13, line 14) and *hireDate* (Fig. 18.13, line 15), respectively. Again, member initializers are separated by commas.

### ***Date Class's Default Copy Constructor***

As you study class *Date* (Fig. 18.10), notice that the class does not provide a constructor that receives a parameter of type *Date*. So, why can the *Employee* constructor's member initializer list initialize the *birthDate* and *hireDate* objects by passing *Date* object's to their *Date* constructors? As we mentioned in Chapter 17, the compiler provides each class with a default copy constructor that copies each data member of the constructor's argument object into the corresponding member of the object being initialized. Chapter 19 discusses how you can define customized copy constructors.

### ***Testing Classes *Date* and *Employee****

Figure 18.14 creates two *Date* objects (lines 9–10) and passes them as arguments to the constructor of the *Employee* object created in line 11. Line 14 outputs the *Employee* object's data. When each *Date* object is created in lines 9–10, the *Date* constructor defined in lines 9–26 of Fig. 18.11 displays a line of output to show that the constructor was called (see the first two lines of the sample output). [Note: Line 11 of Fig. 18.14 causes two additional *Date* constructor calls that do not appear in the program's output. When each of the *Employee*'s *Date* member object's is initialized in the *Employee* constructor's member initializer list (Fig. 18.13, lines 14–15), the default copy constructor for class *Date* is called. Since this constructor is defined implicitly by the compiler, it does not contain any output statements to demonstrate when it's called.]

```

1 // Fig. 18.14: fig18_14.cpp
2 // Demonstrating composition--an object with member objects.
3 #include <iostream>
4 #include "Employee.h" // Employee class definition
5 using namespace std;
6
7 int main()
8 {
9 Date birth(7, 24, 1949);
10 Date hire(3, 12, 1988);
11 Employee manager("Bob", "Blue", birth, hire);
12
13 cout << endl;
14 manager.print();
15
16 cout << "\nTest Date constructor with invalid values:\n";
17 Date lastDayOff(14, 35, 1994); // invalid month and day
18 cout << endl;
19 } // end main

```

Date object constructor for date 7/24/1949  
 Date object constructor for date 3/12/1988  
 Employee object constructor: Bob Blue

Blue, Bob Hired: 3/12/1988 Birthday: 7/24/1949

Test Date constructor with invalid values:  
 Invalid month (14) set to 1.  
 Invalid day (35) set to 1.  
 Date object constructor for date 1/1/1994

Date object destructor for date 1/1/1994  
 Employee object destructor: Blue, Bob  
 Date object destructor for date 3/12/1988  
 Date object destructor for date 7/24/1949  
 Date object destructor for date 3/12/1988  
 Date object destructor for date 7/24/1949

There are actually five constructor calls when an `Employee` is constructed—two calls to the `string` class's constructor (lines 12–13 of Fig. 18.13), two calls to the `Date` class's default copy constructor (lines 14–15 of Fig. 18.13) and the call to the `Employee` class's constructor.

**Fig. 18.14** | Demonstrating composition—an object with member objects.

Class `Date` and class `Employee` each include a destructor (lines 35–40 of Fig. 18.11 and lines 33–37 of Fig. 18.13, respectively) that prints a message when an object of its class is destructed. This enables us to confirm in the program output that objects are constructed from the *inside out* and destroyed in the reverse order, from the *outside in* (i.e., the `Date` member objects are destroyed after the `Employee` object that contains them). Notice the last four lines in the output of Fig. 18.14. The last two lines are the outputs of the `Date` destructor running on `Date` objects `hire` (line 10) and `birth` (line 9), respectively. These outputs confirm that the three objects created in `main` are destructed in the *reverse* of the order in which they were constructed. The `Employee` destructor output is five lines from the bottom. The fourth and third lines from the bottom of the output window show the destructors running for the `Employee`'s member objects `hireDate` (Fig. 18.12, line 22) and `birthDate` (Fig. 18.12, line 21). These outputs confirm that the `Employee` object is destructed from the *outside in*—i.e., the `Employee` destructor runs first (output shown five

lines from the bottom of the output window), then the member objects are destructed in the *reverse order* from which they were constructed. Class `string`'s destructor does not contain output statements, so we do not see the `firstName` and `lastName` objects being destructed. Again, Fig. 18.14's output did not show the constructors running for member objects `birthDate` and `hireDate`, because these objects were initialized with the default `Date` class copy constructors provided by the compiler.

### *What Happens When I Do Not Use the Member\_INITIALIZER List?*

If a member object is not initialized through a member initializer, the member object's default constructor will be called implicitly. Values, if any, established by the default constructor can be overridden by *set* functions. However, for complex initialization, this approach may require significant additional work and time.



#### Common Programming Error 18.6

*A compilation error occurs if a member object is not initialized with a member initializer and the member object's class does not provide a default constructor (i.e., the member object's class defines one or more constructors, but none is a default constructor).*



#### Performance Tip 18.2

*Initialize member objects explicitly through member initializers. This eliminates the overhead of "doubly initializing" member objects—once when the member object's default constructor is called and again when set functions are called in the constructor body (or later) to initialize the member object.*



#### Software Engineering Observation 18.7

*If a class member is an object of another class, making that member object `public` does not violate the encapsulation and hiding of that member object's private members. But, it does violate the encapsulation and hiding of the containing class's implementation, so member objects of class types should still be private, like all other data members.*

## 18.4 friend Functions and friend Classes

A **friend function** of a class is defined outside that class's scope, yet has the right to access the non-`public` (and `public`) members of the class. Standalone functions, entire classes or member functions of other classes may be declared to be friends of another class.

Using friend functions can enhance performance. This section presents a mechanical example of how a friend function works. Later in the book, friend functions are used to overload operators for use with class objects (Chapter 19) and to create iterator classes. Objects of an iterator class can successively select items or perform an operation on items in a container class object. Objects of container classes can store items. Using friends is often appropriate when a member function cannot be used for certain operations, as we'll see in Chapter 19.

To declare a function as a friend of a class, precede the function prototype in the class definition with keyword `friend`. To declare all member functions of class `ClassTwo` as friends of class `ClassOne`, place a declaration of the form

```
friend class ClassTwo;
```

in the definition of class `ClassOne`.

**Software Engineering Observation 18.8**

*Even though the prototypes for friend functions appear in the class definition, friends are not member functions.*

**Software Engineering Observation 18.9**

*Member access notions of private, protected and public are not relevant to friend declarations, so friend declarations can be placed anywhere in a class definition.*

**Good Programming Practice 18.1**

*Place all friendship declarations first inside the class definition's body and do not precede them with any access specifier.*

Friendship is granted, not taken—i.e., for class B to be a friend of class A, class A must explicitly declare that class B is its friend. Also, the friendship relation is neither symmetric nor transitive; i.e., if class A is a friend of class B, and class B is a friend of class C, you cannot infer that class B is a friend of class A (again, friendship is not symmetric), that class C is a friend of class B (also because friendship is not symmetric), or that class A is a friend of class C (friendship is not transitive).

**Software Engineering Observation 18.10**

*Some people in the OOP community feel that “friendship” corrupts information hiding and weakens the value of the object-oriented design approach.*

***Modifying a Class's private Data with a Friend Function***

Figure 18.15 is a mechanical example in which we define friend function `setX` to set the private data member `x` of class `Count`. The friend declaration (line 9) appears first (by convention) in the class definition, even before public member functions are declared. Again, this friend declaration can appear anywhere in the class.

```

1 // Fig. 18.15: fig18_15.cpp
2 // Friends can access private members of a class.
3 #include <iostream>
4 using namespace std;
5
6 // Count class definition
7 class Count
8 {
9 friend void setX(Count &, int); // friend declaration
10 public:
11 // constructor
12 Count()
13 : x(0) // initialize x to 0
14 {
15 // empty body
16 } // end constructor Count
17

```

**Fig. 18.15** | Friends can access private members of a class. (Part 1 of 2.)

```

18 // output x
19 void print() const
20 {
21 cout << x << endl;
22 } // end function print
23 private:
24 int x; // data member
25 }; // end class Count
26
27 // function setX can modify private data of Count
28 // because setX is declared as a friend of Count (line 9)
29 void setX(Count &c, int val)
30 {
31 c.x = val; // allowed because setX is a friend of Count
32 } // end function setX
33
34 int main()
35 {
36 Count counter; // create Count object
37
38 cout << "counter.x after instantiation: ";
39 counter.print();
40
41 setX(counter, 8); // set x using a friend function
42 cout << "counter.x after call to setX friend function: ";
43 counter.print();
44 } // end main

```

```

counter.x after instantiation: 0
counter.x after call to setX friend function: 8

```

**Fig. 18.15** | Friends can access private members of a class. (Part 2 of 2.)

Function `setX` (lines 29–32) is a C-style, stand-alone function—it isn't a member function of class `Count`. For this reason, when `setX` is invoked for object `counter`, line 41 passes `counter` as an argument to `setX` rather than using a handle (such as the name of the object) to call the function, as in

```
counter.setX(8);
```

If you remove the friend declaration in line 9, you'll receive error messages indicating that function `setX` cannot modify class `Count`'s private data member `x`.

As we mentioned, Fig. 18.15 is a mechanical example of using the friend construct. It would normally be appropriate to define function `setX` as a member function of class `Count`. It would also normally be appropriate to separate the program of Fig. 18.15 into three files:

1. A header file (e.g., `Count.h`) containing the `Count` class definition, which in turn contains the prototype of friend function `setX`
2. An implementation file (e.g., `Count.cpp`) containing the definitions of class `Count`'s member functions and the definition of friend function `setX`
3. A test program (e.g., `fig18_15.cpp`) with `main`.



*Overloaded friend Functions*

It's possible to specify overloaded functions as friends of a class. Each function intended to be a friend must be explicitly declared in the class definition as a friend of the class.

## 18.5 Using the `this` Pointer

We've seen that an object's member functions can manipulate the object's data. How do member functions know *which* object's data members to manipulate? Every object has access to its own address through a pointer called `this` (a C++ keyword). The `this` pointer is *not* part of the object itself—i.e., the memory occupied by the `this` pointer is not reflected in the result of a `sizeof` operation on the object. Rather, the `this` pointer is passed (by the compiler) as an implicit argument to each of the object's non-static member functions. Section 18.6 introduces static class members and explains why the `this` pointer is *not* implicitly passed to static member functions.

Objects use the `this` pointer implicitly (as we've done to this point) or explicitly to reference their data members and member functions. The type of the `this` pointer depends on the type of the object and whether the member function in which `this` is used is declared `const`. For example, in a nonconstant member function of class `Employee`, the `this` pointer has type `Employee * const` (a constant pointer to a nonconstant `Employee` object). In a constant member function of the class `Employee`, the `this` pointer has the data type `const Employee * const` (a constant pointer to a constant `Employee` object).

The next example shows implicit and explicit use of the `this` pointer; later in this chapter and in Chapter 19, we show some substantial and subtle examples of using `this`.

*Implicitly and Explicitly Using the `this` Pointer to Access an Object's Data Members*

Figure 18.16 demonstrates the implicit and explicit use of the `this` pointer to enable a member function of class `Test` to print the private data `x` of a `Test` object.

---

```

1 // Fig. 18.16: fig18_16.cpp
2 // Using the this pointer to refer to object members.
3 #include <iostream>
4 using namespace std;
5
6 class Test
7 {
8 public:
9 Test(int = 0); // default constructor
10 void print() const;
11 private:
12 int x;
13 }; // end class Test
14
15 // constructor
16 Test::Test(int value)
17 : x(value) // initialize x to value
18 {
19 // empty body
20 } // end constructor Test

```

---

**Fig. 18.16** | `this` pointer implicitly and explicitly accessing an object's members. (Part 1 of 2.)

```

21
22 // print x using implicit and explicit this pointers;
23 // the parentheses around *this are required
24 void Test::print() const
25 {
26 // implicitly use the this pointer to access the member x
27 cout << " x = " << x;
28
29 // explicitly use the this pointer and the arrow operator
30 // to access the member x
31 cout << "\n this->x = " << this->x;
32
33 // explicitly use the dereferenced this pointer and
34 // the dot operator to access the member x
35 cout << "\n(*this).x = " << (*this).x << endl;
36 } // end function print
37
38 int main()
39 {
40 Test testObject(12); // instantiate and initialize testObject
41
42 testObject.print();
43 } // end main

```

```

 x = 12
 this->x = 12
(*this).x = 12

```

**Fig. 18.16** | `this` pointer implicitly and explicitly accessing an object's members. (Part 2 of 2.)

For illustration purposes, member function `print` (lines 24–36) first prints `x` by using the `this` pointer implicitly (line 27)—only the name of the data member is specified. Then `print` uses two different notations to access `x` through the `this` pointer—the arrow operator (`->`) off the `this` pointer (line 31) and the dot operator (`.`) off the dereferenced `this` pointer (line 35). Note the parentheses around `*this` (line 35) when used with the dot member selection operator (`.`). The parentheses are required because the dot operator has higher precedence than the `*` operator. Without the parentheses, the expression `*this.x` would be evaluated as if it were parenthesized as `*( this.x )`, which is a compilation error, because the dot operator cannot be used with a pointer.



### Common Programming Error 18.7

*Attempting to use the member selection operator (`.`) with a pointer to an object is a compilation error—the dot member selection operator may be used only with an lvalue such as an object's name, a reference to an object or a dereferenced pointer to an object.*

One interesting use of the `this` pointer is to prevent an object from being assigned to itself. As we'll see in Chapter 19, self-assignment can cause serious errors when the object contains pointers to dynamically allocated storage.

### Using the `this` Pointer to Enable Cascaded Function Calls

Another use of the `this` pointer is to enable **cascaded member-function calls**—that is, invoking multiple functions in the same statement (as in line 12 of Fig. 18.19). The program

of Figs. 18.17–18.19 modifies class `Time`'s *set* functions `setTime`, `setHour`, `setMinute` and `setSecond` such that each returns a reference to a `Time` object to enable cascaded member-function calls. Notice in Fig. 18.18 that the last statement in the body of each of these member functions returns `*this` (lines 22, 29, 36 and 43) into a return type of `Time &`.

---

```

1 // Fig. 18.17: Time.h
2 // Cascading member function calls.
3
4 // Time class definition.
5 // Member functions defined in Time.cpp.
6 #ifndef TIME_H
7 #define TIME_H
8
9 class Time
10 {
11 public:
12 Time(int = 0, int = 0, int = 0); // default constructor
13
14 // set functions (the Time & return types enable cascading)
15 Time &setTime(int, int, int); // set hour, minute, second
16 Time &setHour(int); // set hour
17 Time &setMinute(int); // set minute
18 Time &setSecond(int); // set second
19
20 // get functions (normally declared const)
21 int getHour() const; // return hour
22 int getMinute() const; // return minute
23 int getSecond() const; // return second
24
25 // print functions (normally declared const)
26 void printUniversal() const; // print universal time
27 void printStandard() const; // print standard time
28 private:
29 int hour; // 0 - 23 (24-hour clock format)
30 int minute; // 0 - 59
31 int second; // 0 - 59
32 }; // end class Time
33
34 #endif

```

---

**Fig. 18.17** | Time class definition modified to enable cascaded member-function calls.

---

```

1 // Fig. 18.18: Time.cpp
2 // Time class member-function definitions.
3 #include <iostream>
4 #include <iomanip>
5 #include "Time.h" // Time class definition
6 using namespace std;
7

```

---

**Fig. 18.18** | Time class member-function definitions modified to enable cascaded member-function calls. (Part 1 of 3.)

---

```

 8 // constructor function to initialize private data;
 9 // calls member function setTime to set variables;
10 // default values are 0 (see class definition)
11 Time::Time(int hr, int min, int sec)
12 {
13 setTime(hr, min, sec);
14 } // end Time constructor
15
16 // set values of hour, minute, and second
17 Time &Time::setTime(int h, int m, int s) // note Time & return
18 {
19 setHour(h);
20 setMinute(m);
21 setSecond(s);
22 return *this; // enables cascading
23 } // end function setTime
24
25 // set hour value
26 Time &Time::setHour(int h) // note Time & return
27 {
28 hour = (h >= 0 && h < 24) ? h : 0; // validate hour
29 return *this; // enables cascading
30 } // end function setHour
31
32 // set minute value
33 Time &Time::setMinute(int m) // note Time & return
34 {
35 minute = (m >= 0 && m < 60) ? m : 0; // validate minute
36 return *this; // enables cascading
37 } // end function setMinute
38
39 // set second value
40 Time &Time::setSecond(int s) // note Time & return
41 {
42 second = (s >= 0 && s < 60) ? s : 0; // validate second
43 return *this; // enables cascading
44 } // end function setSecond
45
46 // get hour value
47 int Time::getHour() const
48 {
49 return hour;
50 } // end function getHour
51
52 // get minute value
53 int Time::getMinute() const
54 {
55 return minute;
56 } // end function getMinute
57

```

---

**Fig. 18.18** | Time class member-function definitions modified to enable cascaded member-function calls. (Part 2 of 3.)

---

```

58 // get second value
59 int Time::getSecond() const
60 {
61 return second;
62 } // end function getSecond
63
64 // print Time in universal-time format (HH:MM:SS)
65 void Time::printUniversal() const
66 {
67 cout << setfill('0') << setw(2) << hour << ":"
68 << setw(2) << minute << ":" << setw(2) << second;
69 } // end function printUniversal
70
71 // print Time in standard-time format (HH:MM:SS AM or PM)
72 void Time::printStandard() const
73 {
74 cout << ((hour == 0 || hour == 12) ? 12 : hour % 12)
75 << ":" << setfill('0') << setw(2) << minute
76 << ":" << setw(2) << second << (hour < 12 ? " AM" : " PM");
77 } // end function printStandard

```

---

**Fig. 18.18** | Time class member-function definitions modified to enable cascaded member-function calls. (Part 3 of 3.)

---

```

1 // Fig. 18.19: fig18_19.cpp
2 // Cascading member-function calls with the this pointer.
3 #include <iostream>
4 #include "Time.h" // Time class definition
5 using namespace std;
6
7 int main()
8 {
9 Time t; // create Time object
10
11 // cascaded function calls
12 t.setHour(18).setMinute(30).setSecond(22);
13
14 // output time in universal and standard formats
15 cout << "Universal time: ";
16 t.printUniversal();
17
18 cout << "\nStandard time: ";
19 t.printStandard();
20
21 cout << "\n\nNew standard time: ";
22
23 // cascaded function calls
24 t.setTime(20, 20, 20).printStandard();
25 cout << endl;
26 } // end main

```

---

**Fig. 18.19** | Cascading member-function calls with the this pointer. (Part 1 of 2.)

```

Universal time: 18:30:22
Standard time: 6:30:22 PM

New standard time: 8:20:20 PM

```

**Fig. 18.19** | Cascading member-function calls with the `this` pointer. (Part 2 of 2.)

The program of Fig. 18.19 creates `Time` object `t` (line 9), then uses it in cascaded member-function calls (lines 12 and 24). Why does the technique of returning `*this` as a reference work? The dot operator (`.`) associates from left to right, so line 12 first evaluates `t.setHour(18)`, then returns a reference to object `t` as the value of this function call. The remaining expression is then interpreted as

```
t.setMinute(30).setSecond(22);
```

The `t.setMinute( 30 )` call executes and returns a reference to the object `t`. The remaining expression is interpreted as

```
t.setSecond(22);
```

Line 24 also uses cascading. The calls must appear in the order shown in line 24, because `printStandard` as defined in the class does not return a reference to `t`. Placing the call to `printStandard` before the call to `setTime` in line 24 results in a compilation error. Chapter 19 presents several practical examples of using cascaded function calls. One such example uses multiple `<<` operators with `cout` to output multiple values in a single statement.

## 18.6 static Class Members

There is an important exception to the rule that each object of a class has its own copy of all the data members of the class. In certain cases, only one copy of a variable should be shared by all objects of a class. A **static data member** is used for these and other reasons. Such a variable represents “class-wide” information (i.e., a property that is shared by all instances and is not specific to any one object of the class).

### *Motivating Class-Wide Data*

Let’s further motivate the need for static class-wide data with an example. Suppose that we have a video game with Martians and other space creatures. Each Martian tends to be brave and willing to attack other space creatures when the Martian is aware that there are at least five Martians present. If fewer than five are present, each Martian becomes cowardly. So each Martian needs to know the `martianCount`. We could endow each instance of class `Martian` with `martianCount` as a data member. If we do, every Martian will have a separate copy of the data member. Every time we create a new `Martian`, we’ll have to update the data member `martianCount` in all `Martian` objects. Doing this would require every `Martian` object to have, or have access to, handles to all other `Martian` objects in memory. This wastes space with the redundant copies and wastes time in updating the separate copies. Instead, we declare `martianCount` to be `static`. This makes `martianCount` class-wide data. Every `Martian` can access `martianCount` as if it were a data member of the `Martian`, but only one copy of the static variable `martianCount` is maintained by C++.

This saves space. We save time by having the Martian constructor increment static variable `martianCount` and having the Martian destructor decrement `martianCount`. Because there is only one copy, we do not have to increment or decrement separate copies of `martianCount` for each Martian object.



### Performance Tip 18.3

*Use static data members to save storage when a single copy of the data for all objects of a class will suffice.*

### Scope and Initialization of **static** Data Members

Although they may seem like global variables, a class's static data members have class scope. Also, static members can be declared `public`, `private` or `protected`. A fundamental-type static data member is initialized by default to 0. If you want a different initial value, a static data member can be initialized *once*. A static `const` data member of `int` or `enum` type can be initialized in its declaration in the class definition. However, all other static data members must be defined *at global namespace scope* (i.e., outside the body of the class definition) and can be initialized only in those definitions. If a static data member is an object of a class that provides a default constructor, the static data member need not be initialized because its default constructor will be called.

### Accessing **static** Data Members

A class's private and protected static members are normally accessed through the class's public member functions or friends. A class's static members exist even when no objects of that class exist. To access a public static class member when no objects of the class exist, simply prefix the class name and the binary scope resolution operator (`::`) to the name of the data member. For example, if our preceding variable `martianCount` is `public`, it can be accessed with the expression `Martian::martianCount` when there are no Martian objects. (Of course, using public data is discouraged.)

To access a private or protected static class member when no objects of the class exist, provide a public **static member function** and call the function by prefixing its name with the class name and binary scope resolution operator. A static member function is a service of the *class*, not of a specific object of the class.



### Software Engineering Observation 18.11

*A class's static data members and static member functions exist and can be used even if no objects of that class have been instantiated.*

### Demonstrating **static** Data Members

The program of Figs. 18.20–18.22 demonstrates a private static data member called `count` (Fig. 18.20, line 25) and a public static member function called `getCount` (Fig. 18.20, line 19). In Fig. 18.21, line 8 defines and initializes the data member `count` to zero *at global namespace scope* and lines 12–15 define static member function `getCount`. Notice that neither line 8 nor line 12 includes keyword `static`, yet both lines refer to static class members. When `static` is applied to an item at global namespace scope, that item becomes known only in that file. The static class members need to be available to any client code that uses the class, so we declare them `static` only in the `.h` file. Data

member count maintains a count of the number of objects of class `Employee` that have been instantiated. When objects of class `Employee` exist, member count can be referenced through any member function of an `Employee` object—in Fig. 18.21, count is referenced by both line 22 in the constructor and line 32 in the destructor.



### Common Programming Error 18.8

*It's a compilation error to include keyword `static` in the definition of a static data member at global namespace scope.*

---

```

1 // Fig. 18.20: Employee.h
2 // Employee class definition with a static data member to
3 // track the number of Employee objects in memory
4 #ifndef EMPLOYEE_H
5 #define EMPLOYEE_H
6
7 #include <string>
8 using namespace std;
9
10 class Employee
11 {
12 public:
13 Employee(const string &, const string &); // constructor
14 ~Employee(); // destructor
15 string getFirstName() const; // return first name
16 string getLastName() const; // return last name
17
18 // static member function
19 static int getCount(); // return number of objects instantiated
20 private:
21 string firstName;
22 string lastName;
23
24 // static data
25 static int count; // number of objects instantiated
26 }; // end class Employee
27
28 #endif

```

---

**Fig. 18.20** | Employee class definition with a static data member to track the number of Employee objects in memory.

---

```

1 // Fig. 18.21: Employee.cpp
2 // Employee class member-function definitions.
3 #include <iostream>
4 #include "Employee.h" // Employee class definition
5 using namespace std;
6

```

---

**Fig. 18.21** | Employee class member-function definitions. (Part 1 of 2.)



---

```

7 // define and initialize static data member at global namespace scope
8 int Employee::count = 0; // cannot include keyword static
9
10 // define static member function that returns number of
11 // Employee objects instantiated (declared static in Employee.h)
12 int Employee::getCount()
13 {
14 return count;
15 } // end static function getCount
16
17 // constructor initializes non-static data members and
18 // increments static data member count
19 Employee::Employee(const string &first, const string &last)
20 : firstName(first), lastName(last)
21 {
22 ++count; // increment static count of employees
23 cout << "Employee constructor for " << firstName
24 << ' ' << lastName << " called." << endl;
25 } // end Employee constructor
26
27 // destructor deallocates dynamically allocated memory
28 Employee::~Employee()
29 {
30 cout << "~Employee() called for " << firstName
31 << ' ' << lastName << endl;
32 --count; // decrement static count of employees
33 } // end ~Employee destructor
34
35 // return first name of employee
36 string Employee::getFirstName() const
37 {
38 return firstName; // return copy of first name
39 } // end function getFirstName
40
41 // return last name of employee
42 string Employee::getLastName() const
43 {
44 return lastName; // return copy of last name
45 } // end function getLastName

```

---

**Fig. 18.21** | Employee class member-function definitions. (Part 2 of 2.)

Figure 18.22 uses static member function `getCount` to determine the number of `Employee` objects in memory at various points in the program. The program calls `Employee::getCount()` before any `Employee` objects have been created (line 12), after two `Employee` objects have been created (line 23) and after those `Employee` objects have been destroyed (line 34). Lines 16–29 in `main` define a nested scope. Recall that local variables exist until the scope in which they are defined terminates. In this example, we create two `Employee` objects in lines 17–18 inside the nested scope. As each constructor executes, it increments class `Employee`'s static data member `count`. These `Employee` objects are destroyed when the program reaches line 29. At that point, each object's destructor executes and decrements class `Employee`'s static data member `count`.

```

1 // Fig. 18.22: fig18_22.cpp
2 // static data member tracking the number of objects of a class.
3 #include <iostream>
4 #include "Employee.h" // Employee class definition
5 using namespace std;
6
7 int main()
8 {
9 // no objects exist; use class name and binary scope resolution
10 // operator to access static member function getCount
11 cout << "Number of employees before instantiation of any objects is "
12 << Employee::getCount() << endl; // use class name
13
14 // the following scope creates and destroys
15 // Employee objects before main terminates
16 {
17 Employee e1("Susan", "Baker");
18 Employee e2("Robert", "Jones");
19
20 // two objects exist; call static member function getCount again
21 // using the class name and the binary scope resolution operator
22 cout << "Number of employees after objects are instantiated is "
23 << Employee::getCount();
24
25 cout << "\n\nEmployee 1: "
26 << e1.getFirstName() << " " << e1.getLastName()
27 << "\nEmployee 2: "
28 << e2.getFirstName() << " " << e2.getLastName() << "\n\n";
29 } // end nested scope in main
30
31 // no objects exist, so call static member function getCount again
32 // using the class name and the binary scope resolution operator
33 cout << "\nNumber of employees after objects are deleted is "
34 << Employee::getCount() << endl;
35 } // end main

```

Number of employees before instantiation of any objects is 0  
Employee constructor for Susan Baker called.  
Employee constructor for Robert Jones called.  
Number of employees after objects are instantiated is 2

Employee 1: Susan Baker  
Employee 2: Robert Jones

~Employee() called for Robert Jones  
~Employee() called for Susan Baker

Number of employees after objects are deleted is 0

**Fig. 18.22** | static data member tracking the number of objects of a class.

A member function should be declared static if it does not access non-static data members or non-static member functions of the class. Unlike non-static member functions, a static member function does not have a `this` pointer, because static data mem-

bers and static member functions exist independently of any objects of a class. The `this` pointer must refer to a specific object of the class, and when a static member function is called, there might not be any objects of its class in memory.



### Common Programming Error 18.9

*Using the `this` pointer in a static member function is a compilation error.*



### Common Programming Error 18.10

*Declaring a static member function `const` is a compilation error. The `const` qualifier indicates that a function cannot modify the contents of the object in which it operates, but static member functions exist and operate independently of any objects of the class.*

## 18.7 Data Abstraction and Information Hiding

Classes normally hide the details of their implementation from their clients. This is called **information hiding**. As an example, let's consider the stack data structure. Recall that the stack is a last-in-first-out (LIFO) data structure—the last item pushed (inserted) on the stack is the first item popped (removed) off the stack.

Stacks can be implemented with arrays and with other data structures, such as linked lists. (We discuss stacks in Chapter 22.) A client of a stack class need not be concerned with the stack's implementation. The client knows only that when data items are placed in the stack, they will be recalled in last-in, first-out order. The client cares about *what* functionality a stack offers, not about *how* that functionality is implemented. This concept is referred to as **data abstraction**. Although you might know the details of a class's implementation, you should not write code that depends on these details as the details may later change. This enables a particular class (such as one that implements a stack and its operations, *push* and *pop*) to be replaced with another version without affecting the rest of the system. As long as the `public` services of the class do not change (i.e., every original `public` member function still has the same prototype in the new class definition), the rest of the system is not affected.

### Abstract Data Types

Many programming languages emphasize actions. In these languages, data exists to support the actions that programs must take. Data is “less interesting” than actions. Data is “crude.” Only a few built-in data types exist, and it's difficult to create new types. C++ and the object-oriented style of programming elevate the importance of data. The primary activities of object-oriented programming in C++ are the creation of types (i.e., classes) and the expression of the interactions among objects of those types. To create languages that emphasize data, the programming-languages community needed to formalize some notions about data. The formalization we consider here is the notion of **abstract data types (ADTs)**, which improve the application-development process.

What's an abstract data type? Consider the type `int`, which most people would associate with an integer in mathematics. Rather, an `int` is an abstract representation of an integer. Unlike mathematical integers, computer `ints` have a maximum size—on 32-bit machines is typically limited to the range  $-2,147,483,648$  to  $+2,147,483,647$ . If the result of a calculation falls outside this range, an “overflow” error occurs and the computer

responds in some machine-dependent manner. It might, for example, “quietly” produce an incorrect result, such as a value too large to fit in an `int` variable (commonly called **arithmetic overflow**). Mathematical integers do not have this problem. Therefore, the notion of a computer `int` is only an approximation of the notion of a real-world integer.

Types like `int`, `double`, `char` and others are all examples of abstract data types. They’re essentially ways of representing real-world notions to some satisfactory level of precision within a computer system.

An abstract data type actually captures two notions—A **data representation** and the **operations** that can be performed on that data. For example, in C++, an `int` contains an integer value (data) and provides addition, subtraction, multiplication, division and modulus operations (among others)—division by zero is undefined. These allowed operations perform in a manner sensitive to machine parameters, such as the fixed word size of the underlying computer system. Another example is the notion of negative integers, whose operations and data representation are clear, but the operation of taking the square root of a negative integer is undefined. In C++, you can use classes to implement abstract data types and their services. For example, to implement a stack ADT, we create our own stack class in Chapter 22.



### Software Engineering Observation 18.12

*You can create new types through the class mechanism. These new types can be designed to be used as conveniently as the fundamental types. Thus, C++ is an extensible language. Although the language is easy to extend with these new types, the base language itself cannot be changed.*

### Queue Abstract Data Type

Each of us stands in line from time to time. A waiting line is also called a **queue**. Computer systems use waiting lines internally, so we need to write programs that implement queues. A queue is another example of an abstract data type.

Queues offer well-understood behavior to their clients. Clients put things in a queue one at a time—by invoking the queue’s **enqueue** operation—and the clients get those things back one at a time on demand—by invoking the queue’s **dequeue** operation. Conceptually, a queue can become infinitely long; a real queue, of course, is finite. Items are returned from a queue in **first-in, first-out (FIFO)** order—the first item inserted in the queue is the first item removed from the queue.

The queue hides an internal data representation that keeps track of the items currently waiting in line, and offers a set of operations to clients, namely, *enqueue* and *dequeue*. The clients are not concerned about the implementation of the queue. Clients merely want the queue to operate “as advertised.” When a client enqueues a new item, the queue should accept that item and place it internally in some kind of first-in, first-out data structure. When the client wants the next item from the front of the queue, the queue should remove the item from its internal representation and deliver it to the client in FIFO order (i.e., the item that has been in the queue the longest should be the next one returned by the next *dequeue* operation).

The queue ADT guarantees the integrity of its internal data structure. Clients may not manipulate this data structure directly. Only the queue member functions have access to its internal data. Clients may cause only allowable operations to be performed on the data representation; operations not provided in the ADT’s public interface are rejected in some

appropriate manner. This could mean issuing an error message, throwing an exception (see Chapter 24), terminating execution or simply ignoring the operation request.

## 18.8 Wrap-Up

This chapter introduced several advanced topics related to classes and data abstraction. You learned how to specify `const` objects and `const` member functions to prevent modifications to objects, thus enforcing the principle of least privilege. You also learned that, through composition, a class can have objects of other classes as members. We introduced the topic of friendship and presented examples that demonstrate how to use `friend` functions.

You learned that the `this` pointer is passed as an implicit argument to each of a class's non-static member functions, allowing the functions to access the correct object's data members and other non-static member functions. You also saw explicit use of the `this` pointer to access the class's members and to enable cascaded member-function calls. We motivated the need for static data members and demonstrated how to declare and use static data members and static member functions in your own classes.

You learned about data abstraction and information hiding—two of the fundamental concepts of object-oriented programming. Finally, we discussed abstract data types—ways of representing real-world or conceptual notions to some satisfactory level of precision within a computer system.

In Chapter 19, we continue our study of classes and objects by showing how to enable C++'s operators to work with objects—a process called operator overloading. For example, you'll see how to “overload” the `<<` operator so it can be used to output a complete array without explicitly using a repetition statement.

## Summary

### *Section 18.2 `const` (Constant) Objects and `const` Member Functions*

- The keyword `const` can be used to specify that an object is not modifiable and that any attempt to modify the object should result in a compilation error.
- C++ compilers disallow non-`const` member function calls on `const` objects.
- An attempt by a `const` member function to modify an object of its class is a compilation error.
- A member function is specified as `const` both in its prototype and in its definition.
- A `const` object must be initialized.
- Constructors and destructors cannot be declared `const`.
- `const` data member and reference data members *must* be initialized using member initializers.

### *Section 18.3 Composition: Objects as Members of Classes*

- A class can have objects of other classes as members—this concept is called composition.
- Member objects are constructed in the order in which they're declared in the class definition and before their enclosing class objects are constructed.
- If a member initializer is not provided for a member object, the member object's default constructor will be called implicitly.

### Section 18.4 *friend Functions and friend Classes*

- A friend function of a class is defined outside that class's scope, yet has the right to access all of the class's members. Stand-alone functions or entire classes may be declared to be friends.
- A friend declaration can appear anywhere in the class.
- The friendship relation is neither symmetric nor transitive.

### Section 18.5 *Using the this Pointer*

- Every object has access to its own address through the `this` pointer.
- An object's `this` pointer is not part of the object itself—i.e., the size of the memory occupied by the `this` pointer is not reflected in the result of a `sizeof` operation on the object.
- The `this` pointer is passed as an implicit argument to each non-static member function.
- Objects use the `this` pointer implicitly (as we've done to `this` point) or explicitly to reference their data members and member functions.
- The `this` pointer enables cascaded member-function calls in which multiple functions are invoked in the same statement.

### Section 18.6 *static Class Members*

- A static data member represents “class-wide” information (i.e., a property of the class shared by all instances, not a property of a specific object of the class).
- static data members have class scope and can be declared `public`, `private` or `protected`.
- A class's static members exist even when no objects of that class exist.
- To access a `public` static class member when no objects of the class exist, simply prefix the class name and the binary scope resolution operator (`::`) to the name of the data member.
- A member function should be declared `static` if it does not access non-static data members or non-static member functions of the class. Unlike non-static member functions, a static member function does not have a `this` pointer, because static data members and static member functions exist independently of any objects of a class.

### Section 18.7 *Data Abstraction and Information Hiding*

- Abstract data types are ways of representing real-world and conceptual notions to some satisfactory level of precision within a computer system.
- An abstract data type captures two notions: a data representation and the operations that can be performed on that data.

## Terminology

abstract data type (ADT) 664

arithmetic overflow 665

cascaded member-function calls 655

composition 645

data abstraction 664

data representation 665

dequeue (queue operation) 665

enqueue (queue operation) 665

first-in, first-out (FIFO) 665

friend function 651

*has-a* relationship 645

host object 646

information hiding 664

member initializer 641

member initializer list 642

member initializer syntax 641

member object 645

member object constructor 645

operations in an ADT 665

queue 665

queue abstract data type 665

static data member 659

static member function 660

`this` pointer 654

## Self-Review Exercises

- 18.1** Fill in the blanks in each of the following:
- \_\_\_\_\_ must be used to initialize constant members of a class.
  - A nonmember function must be declared as a(n) \_\_\_\_\_ of a class to have access to that class's private data members.
  - A constant object must be \_\_\_\_\_; it cannot be modified after it's created.
  - A(n) \_\_\_\_\_ data member represents class-wide information.
  - An object's non-static member functions have access to a "self pointer" to the object called the \_\_\_\_\_ pointer.
  - Keyword \_\_\_\_\_ specifies that an object or variable is not modifiable.
  - If a member initializer is not provided for a member object of a class, the object's \_\_\_\_\_ is called.
  - A member function should be static if it does not access \_\_\_\_\_ class members.
  - Member objects are constructed \_\_\_\_\_ their enclosing class object.
- 18.2** Find the errors in the following class and explain how to correct them:

```
class Example
{
public:
 Example(int y = 10)
 : data(y)
 {
 // empty body
 } // end Example constructor

 int getIncrementedData() const
 {
 return data++;
 } // end function getIncrementedData

 static int getCount()
 {
 cout << "Data is " << data << endl;
 return count;
 } // end function getCount
private:
 int data;
 static int count;
}; // end class Example
```

## Answers to Self-Review Exercises

**18.1** a) member initializers. b) friend. c) initialized. d) static. e) this. f) const. g) default constructor. h) non-static. i) before.

- 18.2** *Error:* The class definition for Example has two errors. The first occurs in function getIncrementedData. The function is declared const, but it modifies the object.  
*Correction:* To correct the first error, remove the const keyword from the definition of getIncrementedData.  
*Error:* The second error occurs in function getCount. This function is declared static, so it isn't allowed to access any non-static member (i.e., data) of the class.  
*Correction:* To correct the second error, remove the output line from the getCount definition.

## Exercises

- 18.3** Explain the notion of friendship. Explain the negative aspects of friendship as described in the text.

**18.4** Can a correct `Time` class definition include both of the following constructors? If not, explain why not.

```
Time(int h = 0, int m = 0, int s = 0);
Time();
```

**18.5** What happens when a return type, even `void`, is specified for a constructor or destructor?

**18.6** (*Date Class Modification*) Modify class `Date` in Fig. 18.10 to have the following capabilities:

a) Output the date in multiple formats such as

```
DDD YYYY
MM/DD/YY
June 14, 1992
```

- b) Use overloaded constructors to create `Date` objects initialized with dates of the formats in part (a).
- c) Create a `Date` constructor that reads the system date using the standard library functions of the `<ctime>` header and sets the `Date` members. (See your compiler's reference documentation or [www.cplusplus.com/ref/ctime/index.html](http://www.cplusplus.com/ref/ctime/index.html) for information on the functions in header `<ctime>`.)

In Chapter 19, we'll be able to create operators for testing the equality of two dates and for comparing dates to determine whether one date is prior to, or after, another.

**18.7** (*SavingsAccount Class*) Create a `SavingsAccount` class. Use a static data member `annualInterestRate` to store the annual interest rate for each of the savers. Each member of the class contains a private data member `savingsBalance` indicating the amount the saver currently has on deposit. Provide member function `calculateMonthlyInterest` that calculates the monthly interest by multiplying the balance by `annualInterestRate` divided by 12; this interest should be added to `savingsBalance`. Provide a static member function `modifyInterestRate` that sets the static `annualInterestRate` to a new value. Write a driver program to test class `SavingsAccount`. Instantiate two different objects of class `SavingsAccount`, `saver1` and `saver2`, with balances of \$2000.00 and \$3000.00, respectively. Set the `annualInterestRate` to 3 percent. Then calculate the monthly interest and print the new balances for each of the savers. Then set the `annualInterestRate` to 4 percent, calculate the next month's interest and print the new balances for each of the savers.

**18.8** (*IntegerSet Class*) Create class `IntegerSet` for which each object can hold integers in the range 0 through 100. Represent the set internally as a vector of `bool` values. Element `a[i]` is true if integer `i` is in the set. Element `a[j]` is false if integer `j` is not in the set. The default constructor initializes a set to the so-called "empty set," i.e., a set for which all elements contain false.

Provide member functions for the common set operations. For example, provide a `unionOfSets` member function that creates a third set that is the set-theoretic union of two existing sets (i.e., an element of the result is set to true if that element is true in either or both of the existing sets, and an element of the result is set to false if that element is false in each of the existing sets).

Provide an `intersectionOfSets` member function which creates a third set which is the set-theoretic intersection of two existing sets (i.e., an element of the result is set to false if that element is false in either or both of the existing sets, and an element of the result is set to true if that element is true in each of the existing sets).

Provide an `insertElement` member function that places a new integer `k` into a set by setting `a[k]` to true. Provide a `deleteElement` member function that deletes integer `m` by setting `a[m]` to false.

Provide a `printSet` member function that prints a set as a list of numbers separated by spaces. Print only those elements that are present in the set (i.e., their position in the vector has a value of true). Print --- for an empty set.

Provide an `isEqualTo` member function that determines whether two sets are equal.

Provide an additional constructor that receives an array of integers and the size of that array and uses the array to initialize a set object.



Now write a driver program to test your `IntegerSet` class. Instantiate several `IntegerSet` objects. Test that all your member functions work properly.

**18.9 (Time Class Modification)** It would be perfectly reasonable for the `Time` class of Figs. 18.17–18.18 to represent the time internally as the number of seconds since midnight rather than the three integer values `hour`, `minute` and `second`. Clients could use the same public methods and get the same results. Modify the `Time` class of Fig. 18.17 to implement the time as the number of seconds since midnight and show that there is no visible change in functionality to the clients of the class. [Note: This exercise nicely demonstrates the virtues of implementation hiding.]

**18.10 (Card Shuffling and Dealing)** Create a program to shuffle and deal a deck of cards. The program should consist of class `Card`, class `DeckOfCards` and a driver program. Class `Card` should provide:

- Data members `face` and `suit` of type `int`.
- A constructor that receives two `ints` representing the face and suit and uses them to initialize the data members.
- Two static arrays of strings representing the faces and suits.
- A `toString` function that returns the `Card` as a string in the form “*face of suit*.” You can use the `+` operator to concatenate strings.

Class `DeckOfCards` should contain:

- A vector of `Cards` named `deck` to store the `Cards`.
- An integer `currentCard` representing the next card to deal.
- A default constructor that initializes the `Cards` in the deck. The constructor should use vector function `push_back` to add each `Card` to the end of the vector after the `Card` is created and initialized. This should be done for each of the 52 `Cards` in the deck.
- A `shuffle` function that shuffles the `Cards` in the deck. The shuffle algorithm should iterate through the vector of `Cards`. For each `Card`, randomly select another `Card` in the deck and swap the two `Cards`.
- A `dealCard` function that returns the next `Card` object from the deck.
- A `moreCards` function that returns a `bool` value indicating whether there are more `Cards` to deal.

The driver program should create a `DeckOfCards` object, shuffle the cards, then deal the 52 cards.

**18.11 (Card Shuffling and Dealing)** Modify the program you developed in Exercise 18.10 so that it deals a five-card poker hand. Then write functions to accomplish each of the following:

- Determine whether the hand contains a pair.
- Determine whether the hand contains two pairs.
- Determine whether the hand contains three of a kind (e.g., three jacks).
- Determine whether the hand contains four of a kind (e.g., four aces).
- Determine whether the hand contains a flush (i.e., all five cards of the same suit).
- Determine whether the hand contains a straight (i.e., five cards of consecutive face values).

### Card Shuffling and Dealing Projects

**18.12 (Card Shuffling and Dealing)** Use the functions from Exercise 18.11 to write a program that deals two five-card poker hands, evaluates each hand and determines which is the better hand.

**18.13 (Card Shuffling and Dealing)** Modify the program you developed in Exercise 18.12 so that it can simulate the dealer. The dealer’s five-card hand is dealt “face down” so the player cannot see it. The program should then evaluate the dealer’s hand, and, based on the quality of the hand, the dealer should draw one, two or three more cards to replace the corresponding number of unneeded cards in the original hand. The program should then reevaluate the dealer’s hand.

**18.14 (Card Shuffling and Dealing)** Modify the program you developed in Exercise 18.13 so that it handles the dealer’s hand, but the player is allowed to decide which cards of the player’s hand to

replace. The program should then evaluate both hands and determine who wins. Now use this new program to play 20 games against the computer. Who wins more games, you or the computer? Have one of your friends play 20 games against the computer. Who wins more games? Based on the results of these games, make appropriate modifications to refine your poker-playing program. Play 20 more games. Does your modified program play a better game?

## Making a Difference

**18.15 (Air Traffic Control Project)** Every day, according to the National Air Traffic Controllers Association ([www.natca.org/mediacenter/bythenumbers.msp](http://www.natca.org/mediacenter/bythenumbers.msp)), there are more than 87,000 flights in the United States, including commercial flights, cargo flights, and so on, and the long-term trend is that air traffic activity will increase along with the population. As air traffic grows, so do the challenges to air traffic controllers, who monitor the flights and provide instructions to the pilots to ensure safety in the skies.

In this exercise, you'll create a `Flight` class that could be used in a simple air-traffic-control simulator. The application's `main` function will act as air traffic control. Visit sites such as

[www.howstuffworks.com/air-traffic-control.htm](http://www.howstuffworks.com/air-traffic-control.htm)

to research how the air-traffic-control system works. Then identify some key attributes of a `Flight` in an air-traffic-control system. Think about the different states a plane could be in from the time it's parked at an airport gate until it arrives at its destination—parked, taxiing, waiting to take off, taking off, climbing, and so on. Use a `FlightStatus` enumeration to represent these states. The attributes might include the plane's make and model, current air speed, current altitude, direction, carrier, departure time, estimated arrival time, origin and destination. The origin and destination should be specified using standard three-letter airport codes, such as BOS for Boston and LAX for Los Angeles (these codes are available at [world-airport-codes.com](http://world-airport-codes.com)). Provide *set* and *get* functions to manipulate these and any other attributes you identify. Next, identify the class's behaviors and implement them as functions of the class. Include behaviors such as `changeAltitude`, `reduceSpeed` and `beginLandingApproach`. The `Flight` constructor should initialize a `Flight`'s attributes. You should also provide a `toString` function that returns a string representation of a `Flight`'s current status (e.g., parked at the gate, taxiing, taking off, changing altitude). This string should include all of the object's instance-variable values.

When the application executes, `main` will display the message, "Air Traffic Control Simulator", then will create and interact with three `Flight` objects representing planes that are currently flying or preparing to fly. For simplicity, the `Flight`'s confirmation of each action will be a message displayed on the screen when the appropriate function is called on the object. For example, if you call a `flight`'s `changeAltitude` function, the method should:

- Display a message containing the airline, flight number, "changing altitude", the current altitude and the new altitude.
- Change the state of the status data member to `CHANGING_ALTITUDE`.
- Change the value of the `newAltitude` data member.

In `main`, create and initialize three `Flight` objects that are in different states—for example, one could be at the gate, one could be preparing for takeoff and one could be preparing for landing. The `main` function should send messages to (invoke functions on) the `Flight` objects. As a `Flight` object receives each message, it should display a confirmation message from the function being called—such as "[Airline name] [Flight number] changing altitude from 20000 to 25000 feet." The function should also update the appropriate state information in the `Flight` object. For example, if Air Traffic Control sends a message like "[Airline] [flight number] descend to 12000 feet," the program should execute a function call like `flight1.changeAltitude(12000)`, which would display a confirmation message and would set data member `newAltitude` to 12000. [Note: Assume the `Flight`'s `currentAltitude` data member is being set automatically by the plane's altimeter.]

# 19

## Operator Overloading

*The whole difference between construction and creation is exactly this: that a thing constructed can only be loved after it is constructed; but a thing created is loved before it exists.*

—Gilbert Keith Chesterton

*Our doctor would never really operate unless it was necessary. He was just that way. If he didn't need the money, he wouldn't lay a hand on you.*

—Herb Shriner

### Objectives

In this chapter you'll learn:

- What operator overloading is and how it simplifies programming.
- To overload operators for user-defined classes.
- To overload unary and binary operators.
- To convert objects from one class to another class.
- To create `PhoneNumber`, `Array` and `Date` classes that demonstrate operator overloading.
- To use overloaded operators and other features of C++'s `string` class.
- To use keyword `explicit` to prevent the compiler from using single-argument constructors to perform implicit conversions.



|                                                                          |                                                              |
|--------------------------------------------------------------------------|--------------------------------------------------------------|
| <b>19.1</b> Introduction                                                 | <b>19.8</b> Dynamic Memory Management                        |
| <b>19.2</b> Fundamentals of Operator Overloading                         | <b>19.9</b> Case Study: Array Class                          |
| <b>19.3</b> Restrictions on Operator Overloading                         | <b>19.10</b> Converting between Types                        |
| <b>19.4</b> Operator Functions as Class Members vs. Global Function      | <b>19.11</b> Building a <code>String</code> Class            |
| <b>19.5</b> Overloading Stream Insertion and Stream Extraction Operators | <b>19.12</b> Overloading <code>++</code> and <code>--</code> |
| <b>19.6</b> Overloading Unary Operators                                  | <b>19.13</b> Case Study: A <code>Date</code> Class           |
| <b>19.7</b> Overloading Binary Operators                                 | <b>19.14</b> Standard Library Class <code>string</code>      |
|                                                                          | <b>19.15</b> <code>explicit</code> Constructors              |
|                                                                          | <b>19.16</b> Proxy Classes                                   |
|                                                                          | <b>19.17</b> Wrap-Up                                         |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 19.1 Introduction

Chapters 17–18 introduced the basics of C++ classes. Services were obtained from objects by sending messages (in the form of member-function calls) to the objects. This function call notation is cumbersome for certain kinds of classes (such as mathematical classes). Also, many common manipulations are performed with operators (e.g., input and output). We can use C++’s rich set of built-in operators to specify common object manipulations. This chapter shows how to enable C++’s operators to work with objects—a process called **operator overloading**.

One example of an overloaded operator built into C++ is `<<`, which is used both as the stream insertion operator and as the bitwise left-shift operator (which is discussed in Chapter 10). Similarly, `>>` is also overloaded; it’s used both as the stream extraction operator and as the bitwise right-shift operator. Both of these operators are overloaded in the C++ Standard Library.

Although operator overloading sounds like an exotic capability, most programmers implicitly use overloaded operators. For example, the C++ language overloads the addition operator (`+`) and the subtraction operator (`-`). These operators perform differently, depending on their context in integer, floating-point and pointer arithmetic.

C++ enables you to overload most operators to be sensitive to the context in which they’re used—the compiler generates the appropriate code based on the context (in particular, the types of the operands). Some operators are overloaded frequently, especially the assignment, relational and various arithmetic operators such as `+` and `-`. The jobs performed by overloaded operators can also be performed by explicit function calls, but operator notation is often clearer and more familiar to programmers.

We discuss when to, and when not to, use operator overloading. We create classes `PhoneNumber`, `Array` and `Date` to demonstrate how to overload operators, including the stream insertion, stream extraction, assignment, equality, relational, subscript, logical negation and increment operators. We demonstrate C++’s Standard Library class `string`, which provides many overloaded operators. In the exercises, we ask you to implement several classes with overloaded operators. The exercises also use classes `Complex` (for complex numbers) and `HugeInt` (for integers larger than a computer can represent with type `long`) to demonstrate overloaded arithmetic operators `+` and `-`, and ask you to enhance those

classes by overloading other arithmetic operators. Finally, we show how to create a proxy class to hide a class's implementation details (including its private data) from its clients.

## 19.2 Fundamentals of Operator Overloading

C++ programming is a type-sensitive and type-focused process. You can use fundamental types and can define new types. The fundamental types can be used with C++'s rich collection of operators. Operators provide you with a concise notation for expressing manipulations of data of fundamental types.

You can use operators with user-defined types as well. Although C++ does not allow new operators to be created, it does allow most existing operators to be overloaded so that, when they're used with objects, they have meaning appropriate to those objects.



### Software Engineering Observation 19.1

*Operator overloading contributes to C++'s extensibility—one of the language's most appealing attributes.*



### Good Programming Practice 19.1

*Use operator overloading when it makes a program clearer than accomplishing the same operations with function calls.*



### Good Programming Practice 19.2

*Overloaded operators should mimic the functionality of their built-in counterparts—for example, the + operator should be overloaded to perform addition, not subtraction. Avoid excessive or inconsistent use of operator overloading, as this can make a program cryptic and difficult to read.*

An operator is overloaded by writing a non-static member function definition or global function definition as you normally would, except that the function name now becomes the keyword operator followed by the symbol for the operator being overloaded. For example, the function name operator+ would be used to overload the addition operator (+). When operators are overloaded as member functions, they must be non-static, because they must be called on an object of the class and operate on that object.

To use an operator on class objects, that operator *must* be overloaded—with three exceptions. The assignment operator (=) may be used with every class to perform memberwise assignment of the class's data members—each data member is assigned from the assignment's "source" object to the "target" object. Memberwise assignment is dangerous for classes with pointer members; we'll explicitly overload the assignment operator for such classes. The address (&) and comma (,) operators may also be used with objects of any class without overloading. The address operator returns a pointer to the object. The comma operator evaluates the expression to its left then the expression to its right, and returns the value of the latter expression. Both of these operators can also be overloaded.

Overloading is especially appropriate for mathematical classes. These often require that a substantial set of operators be overloaded to ensure consistency with the way these mathematical classes are handled in the real world. For example, it would be unusual to overload only addition for a complex number class, because other arithmetic operators are also commonly used with complex numbers.



Operator overloading provides the same concise and familiar expressions for user-defined types that C++ provides with its rich collection of operators for fundamental types. Operator overloading is not automatic—you must write operator-overloading functions to perform the desired operations. Sometimes these functions are best made member functions; sometimes they’re best as friend functions; occasionally they can be made global, non-friend functions. We present examples of each of these possibilities.

## 19.3 Restrictions on Operator Overloading

Most of C++’s operators can be overloaded. These are shown in Fig. 19.1. Figure 19.2 shows the operators that cannot be overloaded.

| Operators that can be overloaded |          |    |    |    |    |     |        |
|----------------------------------|----------|----|----|----|----|-----|--------|
| +                                | -        | *  | /  | %  | ^  | &   |        |
| ~                                | !        | =  | <  | >  | += | -=  | *=     |
| /=                               | %=       | ^= | &= | =  | << | >>  | >>=    |
| <<=                              | ==       | != | <= | >= | && |     | ++     |
| --                               | ->*      | ,  | -> | [] | () | new | delete |
| new[]                            | delete[] |    |    |    |    |     |        |

**Fig. 19.1** | Operators that can be overloaded.

| Operators that cannot be overloaded |    |    |    |
|-------------------------------------|----|----|----|
| .                                   | .* | :: | ?: |

**Fig. 19.2** | Operators that cannot be overloaded.

### *Precedence, Associativity and Number of Operands*

The precedence of an operator cannot be changed by overloading. This can lead to awkward situations in which an operator is overloaded in a manner for which its fixed precedence is inappropriate. However, parentheses can be used to force the order of evaluation of overloaded operators in an expression.

The associativity of an operator (i.e., whether the operator is applied right-to-left or left-to-right) cannot be changed by overloading.

It isn’t possible to change the “arity” of an operator (i.e., the number of operands an operator takes): Overloaded unary operators remain unary operators; overloaded binary operators remain binary operators. C++’s only ternary operator (?:) cannot be overloaded. Operators &, \*, + and - all have both unary and binary versions; these unary and binary versions can each be overloaded.



### Common Programming Error 19.1

Attempting to change the “arity” of an operator via operator overloading is a compilation error.

### Creating New Operators

It isn't possible to create new operators; only existing operators can be overloaded. Unfortunately, this prevents you from using popular notations like the `**` operator used in some other programming languages for exponentiation. [Note: You could overload an existing operator to perform exponentiation.]



#### Common Programming Error 19.2

*Attempting to create new operators via operator overloading is a syntax error.*

### Operators for Fundamental Types

The meaning of how an operator works on objects of fundamental types cannot be changed by operator overloading. You cannot, for example, change the meaning of how `+` adds two integers. Operator overloading works only with objects of user-defined types or with a mixture of an object of a user-defined type and an object of a fundamental type.



#### Software Engineering Observation 19.2

*At least one argument of an operator function must be an object or reference of a user-defined type. This prevents you from changing how operators work on fundamental types.*



#### Common Programming Error 19.3

*Attempting to modify how an operator works with objects of fundamental types is a compilation error.*

### Related Operators

Overloading an assignment operator and an addition operator to allow statements like

```
object2 = object2 + object1;
```

does not imply that the `+=` operator is also overloaded to allow statements such as

```
object2 += object1;
```

Such behavior can be achieved only by explicitly overloading operator `+=` for that class.



#### Common Programming Error 19.4

*Assuming that overloading an operator such as `+` overloads related operators such as `+=` or that overloading `==` overloads a related operator like `!=` can lead to errors. Operators can be overloaded only explicitly; there is no implicit overloading.*

## 19.4 Operator Functions as Class Members vs. Global Function

Operator functions can be member functions or global functions; global functions are often made friends for performance reasons. Member functions use the `this` pointer implicitly to obtain one of their class object arguments (the left operand for binary operators). Arguments for both operands of a binary operator must be explicitly listed in a global function call.

### *Operators That Must Be Overloaded as Member Functions*

When overloading `()`, `[]`, `->` or any of the assignment operators, the operator overloading function must be declared as a class member. For the other operators, the operator overloading functions can be class members or standalone functions.

### *Operators as Member Functions and Global Functions*

Whether an operator function is implemented as a member function or as a global function, the operator is still used the same way in expressions. So which is best?

When an operator function is implemented as a member function, the leftmost (or only) operand must be an object (or a reference to an object) of the operator's class. If the left operand must be an object of a different class or a fundamental type, this operator function must be implemented as a global function (as we'll do in Section 19.5 when overloading `<<` and `>>` as the stream insertion and stream extraction operators, respectively). A global operator function can be made a friend of a class if that function must access private or protected members of that class directly.

Operator member functions of a specific class are called (implicitly by the compiler) only when the left operand of a binary operator is specifically an object of that class, or when the single operand of a unary operator is an object of that class.

### *Why Overloaded Stream Insertion and Stream Extraction Operators Are Overloaded as Global Functions*

The overloaded stream insertion operator (`<<`) is used in an expression in which the left operand has type `ostream&`, as in `cout << classObject`. To use the operator in this manner where the *right* operand is an object of a user-defined class, it must be overloaded as a global function. To be a member function, operator `<<` would have to be a member of the `ostream` class. This is not possible for user-defined classes, since we're not allowed to modify C++ Standard Library classes. Similarly, the overloaded stream extraction operator (`>>`) is used in an expression in which the left operand has type `istream&`, as in `cin >> classObject`, and the *right* operand is an object of a user-defined class, so it, too, must be a global function. Also, each of these overloaded operator functions may require access to the private data members of the class object being output or input, so these overloaded operator functions can be made friend functions of the class for performance reasons.



#### **Performance Tip 19.1**

*It's possible to overload an operator as a global, non-friend function, but such a function requiring access to a class's private or protected data would need to use set or get functions provided in that class's public interface. The overhead of calling these functions could cause poor performance, so these functions can be inlined to improve performance.*

### *Commutative Operators*

Another reason why one might choose a global function to overload an operator is to enable the operator to be commutative. For example, suppose we have an object, `number`, of type `long int`, and an object `bigInteger1`, of class `HugeInteger` (a class in which integers may be arbitrarily large rather than being limited by the machine word size of the underlying hardware; class `HugeInteger` is developed in the chapter exercises). The addition operator (`+`) produces a temporary `HugeInteger` object as the sum of a `HugeInteger` and a `long int` (as in the expression `bigInteger1 + number`), or as the sum of a `long int` and a `HugeInteger` (as in the expression `number + bigInteger1`). Thus, we require the addition



operator to be commutative (exactly as it is with two fundamental-type operands). The problem is that the class object must appear on the *left* of the addition operator if that operator is to be overloaded as a member function. So, we overload the operator as a global function to allow the `HugeInteger` to appear on the *right* of the addition. The `operator+` function, which deals with the `HugeInteger` on the left, can still be a member function. The global function simply swaps its arguments and calls the member function.

## 19.5 Overloading Stream Insertion and Stream Extraction Operators

You can input and output fundamental-type data using the stream extraction operator `>>` and the stream insertion operator `<<`. The C++ class libraries overload these operators to process each fundamental type, including pointers and C-style `char *` strings. You can also overload these operators to perform input and output for your own types. The program of Figs. 19.3–19.5 overloads these operators to input and output `PhoneNumber` objects in the format “(000) 000-0000.” The program assumes telephone numbers are input correctly.

---

```

1 // Fig. 19.3: PhoneNumber.h
2 // PhoneNumber class definition
3 #ifndef PHONENUMBER_H
4 #define PHONENUMBER_H
5
6 #include <iostream>
7 #include <string>
8 using namespace std;
9
10 class PhoneNumber
11 {
12 friend ostream &operator<<(ostream &, const PhoneNumber &);
13 friend istream &operator>>(istream &, PhoneNumber &);
14 private:
15 string areaCode; // 3-digit area code
16 string exchange; // 3-digit exchange
17 string line; // 4-digit line
18 }; // end class PhoneNumber
19
20 #endif

```

---

**Fig. 19.3** | `PhoneNumber` class with overloaded stream insertion and stream extraction operators as friend functions.

---

```

1 // Fig. 19.4: PhoneNumber.cpp
2 // Overloaded stream insertion and stream extraction operators
3 // for class PhoneNumber.
4 #include <iomanip>
5 #include "PhoneNumber.h"
6 using namespace std;

```

---

**Fig. 19.4** | Overloaded stream insertion and stream extraction operators for class `PhoneNumber`.  
(Part I of 2.)

```

7
8 // overloaded stream insertion operator; cannot be
9 // a member function if we would like to invoke it with
10 // cout << somePhoneNumber;
11 ostream &operator<<(ostream &output, const PhoneNumber &number)
12 {
13 output << "(" << number.areaCode << ") "
14 << number.exchange << "-" << number.line;
15 return output; // enables cout << a << b << c;
16 } // end function operator<<
17
18 // overloaded stream extraction operator; cannot be
19 // a member function if we would like to invoke it with
20 // cin >> somePhoneNumber;
21 istream &operator>>(istream &input, PhoneNumber &number)
22 {
23 input.ignore(); // skip (
24 input >> setw(3) >> number.areaCode; // input area code
25 input.ignore(2); // skip) and space
26 input >> setw(3) >> number.exchange; // input exchange
27 input.ignore(); // skip dash (-)
28 input >> setw(4) >> number.line; // input line
29 return input; // enables cin >> a >> b >> c;
30 } // end function operator>>

```

**Fig. 19.4** | Overloaded stream insertion and stream extraction operators for class `PhoneNumber`. (Part 2 of 2.)

```

1 // Fig. 19.5: fig19_05.cpp
2 // Demonstrating class PhoneNumber's overloaded stream insertion
3 // and stream extraction operators.
4 #include <iostream>
5 #include "PhoneNumber.h"
6 using namespace std;
7
8 int main()
9 {
10 PhoneNumber phone; // create object phone
11
12 cout << "Enter phone number in the form (123) 456-7890:" << endl;
13
14 // cin >> phone invokes operator>> by implicitly issuing
15 // the global function call operator>>(cin, phone)
16 cin >> phone;
17
18 cout << "The phone number entered was: ";
19
20 // cout << phone invokes operator<< by implicitly issuing
21 // the global function call operator<<(cout, phone)
22 cout << phone << endl;
23 } // end main

```

**Fig. 19.5** | Overloaded stream insertion and stream extraction operators. (Part 1 of 2.)

```
Enter phone number in the form (123) 456-7890:
(800) 555-1212
The phone number entered was: (800) 555-1212
```

**Fig. 19.5** | Overloaded stream insertion and stream extraction operators. (Part 2 of 2.)

The stream extraction operator function `operator>>` (Fig. 19.4, lines 21–30) takes `istream` reference `input` and `PhoneNumber` reference `number` as arguments and returns an `istream` reference. Operator function `operator>>` inputs phone numbers of the form

```
(800) 555-1212
```

into objects of class `PhoneNumber`. When the compiler sees the expression

```
cin >> phone
```

in line 16 of Fig. 19.5, the compiler generates the global function call

```
operator>>(cin, phone);
```

When this call executes, reference parameter `input` (Fig. 19.4, line 21) becomes an alias for `cin` and reference parameter `number` becomes an alias for `phone`. The operator function reads as strings the three parts of the telephone number into the `areaCode` (line 24), `exchange` (line 26) and `line` (line 28) members of the `PhoneNumber` object referenced by parameter `number`. Stream manipulator `setw` limits the number of characters read into each string. When used with `cin` and strings, `setw` restricts the number of characters read to the number of characters specified by its argument (i.e., `setw( 3 )` allows three characters to be read). The parentheses, space and dash characters are skipped by calling `istream` member function `ignore` (Fig. 19.4, lines 23, 25 and 27), which discards the specified number of characters in the input stream (one character by default). Function `operator>>` returns `istream` reference `input` (i.e., `cin`). This enables input operations on `PhoneNumber` objects to be cascaded with input operations on other `PhoneNumber` objects or on objects of other data types. For example, a program can input two `PhoneNumber` objects in one statement as follows:

```
cin >> phone1 >> phone2;
```

First, the expression `cin >> phone1` executes by making the global function call

```
operator>>(cin, phone1);
```

This call then returns a reference to `cin` as the value of `cin >> phone1`, so the remaining portion of the expression is interpreted simply as `cin >> phone2`. This executes by making the global function call

```
operator>>(cin, phone2);
```

The stream insertion operator function (Fig. 19.4, lines 11–16) takes an `ostream` reference (output) and a `const PhoneNumber` reference (`number`) as arguments and returns an `ostream` reference. Function `operator<<` displays objects of type `PhoneNumber`. When the compiler sees the expression

```
cout << phone
```

in line 22 of Fig. 19.5, the compiler generates the global function call

```
operator<<(cout, phone);
```

Function operator<< displays the parts of the telephone number as strings, because they're stored as string objects.



### Error-Prevention Tip 19.1

*Returning a reference from an overloaded << or >> operator function is typically successful because cout, cin and most stream objects are global, or at least long-lived. Returning a reference to an automatic variable or other temporary object is dangerous—this can create “dangling references” to nonexistent objects.*

The functions operator>> and operator<< are declared in PhoneNumber as global, friend functions (Fig. 19.3, lines 12–13). They're global functions because the object of class PhoneNumber is the operator's right operand. Remember, overloaded operator functions for binary operators can be member functions only when the left operand is an object of the class in which the function is a member. Overloaded input and output operators are declared as friends if they need to access non-public class members directly for performance reasons or because the class may not offer appropriate *get* functions. Also, the PhoneNumber reference in function operator<<'s parameter list (Fig. 19.4, line 11) is const, because the PhoneNumber will simply be output, and the PhoneNumber reference in function operator>>'s parameter list (line 21) is non-const, because the PhoneNumber object must be modified to store the input telephone number in the object.



### Software Engineering Observation 19.3

*New input/output capabilities for user-defined types are added to C++ without modifying standard input/output library classes. This is another example of C++'s extensibility.*

## 19.6 Overloading Unary Operators

A unary operator for a class can be overloaded as a non-static member function with no arguments or as a global function with one argument that must be an object (or a reference to an object) of the class. Member functions that implement overloaded operators must be non-static so that they can access the non-static data in each object of the class. Remember that static member functions can access only static members of the class.

Later in this chapter, we'll overload unary operator ! to test whether an object of the String class we create (Section 19.11) is empty and return a bool result. Consider the expression !s, in which s is an object of class String. When a unary operator such as ! is overloaded as a member function with no arguments and the compiler sees the expression !s, the compiler generates the function call s.operator!(). The operand s is the class object for which the String class member function operator! is being invoked. The function is declared in the class definition as follows:

```
class String
{
public:
 bool operator!() const;
 ...
}; // end class String
```

A unary operator such as `!` may be overloaded as a global function with one parameter in two different ways—either with a parameter that is an object (this requires a copy of the object, so the side effects of the function are not applied to the original object), or with a parameter that is a reference to an object (no copy of the original object is made, so all side effects of this function are applied to the original object). If `s` is a `String` class object (or a reference to a `String` class object), then `!s` is treated as if the call `operator!(s)` had been written, invoking the global `operator!` function that is declared as follows:

```
bool operator!(const String &);
```

## 19.7 Overloading Binary Operators

A binary operator can be overloaded as a non-static member function with one parameter or as a global function with two parameters (one of those parameters must be either a class object or a reference to a class object).

Later in this chapter, we'll overload `<` to compare two `String` objects. When overloading binary operator `<` as a non-static member function of a `String` class with one argument, if `y` and `z` are `String`-class objects, then `y < z` is treated as if `y.operator<(z)` had been written, invoking the `operator<` member function declared below:

```
class String
{
public:
 bool operator<(const String &) const;
 ...
}; // end class String
```

As a global function, binary operator `<` must take two arguments—one of which must be an object (or a reference to an object) of the class. If `y` and `z` are `String`-class objects or references to `String`-class objects, then `y < z` is treated as if the call `operator<(y, z)` had been written in the program, invoking global-function `operator<` declared as follows:

```
bool operator<(const String &, const String &);
```

## 19.8 Dynamic Memory Management

A standard C++ array data structure is fixed in size once it's created. The size is specified with a constant at compile time. Sometimes it's useful to determine the size of an array dynamically at execution time and then create the array. C++ enables you to control the allocation and deallocation of memory in a program for objects and for arrays of any built-in or user-defined type. This is known as **dynamic memory management** and is performed with the operators `new` and `delete`.

You can use the `new` operator to dynamically **allocate** (i.e., reserve) the exact amount of memory required to hold an object or array at execution time. The object or array is created in the **free store** (also called the **heap**)—a region of memory assigned to each program for storing dynamically allocated objects. Once memory is allocated in the free store, you can access it via the pointer that operator `new` returns. When you no longer need the memory, you can return it to the free store by using the `delete` operator to **deallocate** (i.e., release) the memory, which can then be reused by future `new` operations.

**Obtaining Dynamic Memory with new**

Let's discuss the details of using the `new` and `delete` operators to dynamically allocate memory to store objects, fundamental types and arrays. Consider the following statement:

```
Time *timePtr = new Time;
```

The `new` operator allocates storage of the proper size for an object of type `Time`, calls the default constructor to initialize the object and returns a pointer to the type specified to the right of the `new` operator (i.e., a `Time *`). If `new` is unable to find sufficient space in memory for the object, it indicates that an error occurred by “throwing an exception.” Chapter 24, Exception Handling, discusses how to deal with new failures. In particular, we'll show how to “catch” the exception thrown by `new` and deal with it. When a program does not “catch” an exception, the program terminates immediately.

**Releasing Dynamic Memory with delete**

To destroy a dynamically allocated object and free the space for the object, use the `delete` operator as follows:

```
delete timePtr;
```

This statement first calls the destructor for the object to which `timePtr` points, then deallocates the memory associated with the object, returning the memory to the free store.

**Common Programming Error 19.5**

*Not releasing dynamically allocated memory when it's no longer needed can cause the system to run out of memory prematurely. This is sometimes called a “memory leak.”*

**Initializing Dynamic Memory**

You can provide an **initializer** for a newly created fundamental-type variable, as in

```
double *ptr = new double(3.14159);
```

which initializes a newly created `double` to 3.14159 and assigns the resulting pointer to `ptr`. The same syntax can be used to specify a comma-separated list of arguments to the constructor of an object. For example,

```
Time *timePtr = new Time(12, 45, 0);
```

initializes a new `Time` object to 12:45 PM and assigns the resulting pointer to `timePtr`.

**Dynamically Allocating Arrays with new []**

You can also use the `new` operator to allocate arrays dynamically. For example, a 10-element integer array can be allocated and assigned to `gradesArray` as follows:

```
int *gradesArray = new int[10];
```

which declares `int` pointer `gradesArray` and assigns to it a pointer to the first element of a dynamically allocated 10-element array of `ints`. The size of an array created at compile time must be specified using a constant integral expression; however, a dynamically allocated array's size can be specified using *any* non-negative integral expression that can be evaluated at execution time. Also, when allocating an array of objects dynamically, you *cannot* pass arguments to each object's constructor—each object is initialized by its default constructor. For fundamental types, the elements are initialized to 0 or the equivalent of 0

(e.g., chars are initialized to the null character, '\0'). Although an array name is a pointer to the array's first element, the following is not allowed for dynamically allocated memory:

```
int gradesArray[] = new int[10];
```

### Releasing Dynamically Allocated Arrays with `delete []`

To deallocate the memory to which `gradesArray` points, use the statement

```
delete [] gradesArray;
```

If the pointer points to an array of objects, the statement first calls the destructor for every object in the array, then deallocates the memory. If the preceding statement did not include the square brackets (`[]`) and `gradesArray` pointed to an array of objects, the result is undefined. Some compilers call the destructor only for the first object in the array. Using `delete` on a null pointer (i.e., a pointer with the value 0) has no effect.



### Common Programming Error 19.6

*Using `delete` instead of `delete []` for arrays of objects can lead to runtime logic errors. To ensure that every object in the array receives a destructor call, always delete memory allocated as an array with operator `delete []`. Similarly, always delete memory allocated as an individual element with operator `delete`—the result of deleting a single object with operator `delete []` is undefined.*

## 19.9 Case Study: Array Class

We discussed arrays in Chapter 6. An array is not much more than a pointer to some space in memory. Pointer-based arrays have many problems, including:

- A program can easily “walk off” either end of an array, because C++ does not check whether subscripts fall outside the range of an array (though you can still do this explicitly).
- Arrays of size  $n$  must number their elements 0, ...,  $n - 1$ ; alternate subscript ranges are not allowed.
- An entire array cannot be input or output at once; each array element must be read or written individually (unless the array is a null-terminated C string).
- Two arrays cannot be meaningfully compared with equality or relational operators (because the array names are simply pointers to where the arrays begin in memory and two arrays will always be at different memory locations).
- When an array is passed to a general-purpose function designed to handle arrays of any size, the array's size must be passed as an additional argument.
- One array cannot be assigned to another with the assignment operator(s) (because array names are `const` pointers and a *constant* pointer cannot be used on the left side of an assignment operator).

C++ provides the means to implement more robust array capabilities via classes and operator overloading. You can develop an array class that is preferable to “raw” arrays. In this example, we create a powerful `Array` class that performs range checking to ensure that

subscripts remain within the bounds of the Array. The class allows one array object to be assigned to another with the assignment operator. Array objects know their size, so the size does not need to be passed separately to functions that receive Array parameters. Entire Arrays can be input or output with the stream extraction and stream insertion operators, respectively. You can compare Arrays with the equality operators == and !=. C++ Standard Library class template vector provides many of these capabilities as well.

This example will sharpen your appreciation of data abstraction. Class development is an interesting, creative and intellectually challenging activity—always with the goal of “crafting valuable classes.” The program of Figs. 19.6–19.8 demonstrates class Array and its overloaded operators. First we walk through main (Fig. 19.8), then we consider the class definition (Fig. 19.6) and each of its member-function definitions (Fig. 19.7).

---

```

1 // Fig. 19.6: Array.h
2 // Array class definition with overloaded operators.
3 #ifndef ARRAY_H
4 #define ARRAY_H
5
6 #include <iostream>
7 using namespace std;
8
9 class Array
10 {
11 friend ostream &operator<<(ostream &, const Array &);
12 friend istream &operator>>(istream &, Array &);
13 public:
14 Array(int = 10); // default constructor
15 Array(const Array &); // copy constructor
16 ~Array(); // destructor
17 int getSize() const; // return size
18
19 const Array &operator=(const Array &); // assignment operator
20 bool operator==(const Array &) const; // equality operator
21
22 // inequality operator; returns opposite of == operator
23 bool operator!=(const Array &right) const
24 {
25 return ! (*this == right); // invokes Array::operator==
26 } // end function operator!=
27
28 // subscript operator for non-const objects returns modifiable lvalue
29 int &operator[](int);
30
31 // subscript operator for const objects returns rvalue
32 int operator[](int) const;
33 private:
34 int size; // pointer-based array size
35 int *ptr; // pointer to first element of pointer-based array
36 }; // end class Array
37
38 #endif

```

---

**Fig. 19.6** | Array class definition with overloaded operators.



---

```

1 // Fig 19.7: Array.cpp
2 // Array class member- and friend-function definitions.
3 #include <iostream>
4 #include <iomanip>
5 #include <cstdlib> // exit function prototype
6 #include "Array.h" // Array class definition
7 using namespace std;
8
9 // default constructor for class Array (default size 10)
10 Array::Array(int arraySize)
11 {
12 size = (arraySize > 0 ? arraySize : 10); // validate arraySize
13 ptr = new int[size]; // create space for pointer-based array
14
15 for (int i = 0; i < size; i++)
16 ptr[i] = 0; // set pointer-based array element
17 } // end Array default constructor
18
19 // copy constructor for class Array;
20 // must receive a reference to prevent infinite recursion
21 Array::Array(const Array &arrayToCopy)
22 : size(arrayToCopy.size)
23 {
24 ptr = new int[size]; // create space for pointer-based array
25
26 for (int i = 0; i < size; i++)
27 ptr[i] = arrayToCopy.ptr[i]; // copy into object
28 } // end Array copy constructor
29
30 // destructor for class Array
31 Array::~~Array()
32 {
33 delete [] ptr; // release pointer-based array space
34 } // end destructor
35
36 // return number of elements of Array
37 int Array::getSize() const
38 {
39 return size; // number of elements in Array
40 } // end function getSize
41
42 // overloaded assignment operator;
43 // const return avoids: (a1 = a2) = a3
44 const Array &Array::operator=(const Array &right)
45 {
46 if (&right != this) // avoid self-assignment
47 {
48 // for Arrays of different sizes, deallocate original
49 // left-side array, then allocate new left-side array
50 if (size != right.size)
51 {
52 delete [] ptr; // release space
53 size = right.size; // resize this object

```

---

**Fig. 19.7** | Array class member- and friend-function definitions. (Part I of 3.)

---

```

54 ptr = new int[size]; // create space for array copy
55 } // end inner if
56
57 for (int i = 0; i < size; i++)
58 ptr[i] = right.ptr[i]; // copy array into object
59 } // end outer if
60
61 return *this; // enables x = y = z, for example
62 } // end function operator=
63
64 // determine if two Arrays are equal and
65 // return true, otherwise return false
66 bool Array::operator==(const Array &right) const
67 {
68 if (size != right.size)
69 return false; // arrays of different number of elements
70
71 for (int i = 0; i < size; i++)
72 if (ptr[i] != right.ptr[i])
73 return false; // Array contents are not equal
74
75 return true; // Arrays are equal
76 } // end function operator==
77
78 // overloaded subscript operator for non-const Arrays;
79 // reference return creates a modifiable lvalue
80 int &Array::operator[](int subscript)
81 {
82 // check for subscript out-of-range error
83 if (subscript < 0 || subscript >= size)
84 {
85 cerr << "\nError: Subscript " << subscript
86 << " out of range" << endl;
87 exit(1); // terminate program; subscript out of range
88 } // end if
89
90 return ptr[subscript]; // reference return
91 } // end function operator[]
92
93 // overloaded subscript operator for const Arrays
94 // const reference return creates an rvalue
95 int Array::operator[](int subscript) const
96 {
97 // check for subscript out-of-range error
98 if (subscript < 0 || subscript >= size)
99 {
100 cerr << "\nError: Subscript " << subscript
101 << " out of range" << endl;
102 exit(1); // terminate program; subscript out of range
103 } // end if
104
105 return ptr[subscript]; // returns copy of this element
106 } // end function operator[]

```

---

**Fig. 19.7** | Array class member- and friend-function definitions. (Part 2 of 3.)

---

```

107
108 // overloaded input operator for class Array;
109 // inputs values for entire Array
110 istream &operator>>(istream &input, Array &a)
111 {
112 for (int i = 0; i < a.size; i++)
113 input >> a.ptr[i];
114
115 return input; // enables cin >> x >> y;
116 } // end function
117
118 // overloaded output operator for class Array
119 ostream &operator<<(ostream &output, const Array &a)
120 {
121 int i;
122
123 // output private ptr-based array
124 for (i = 0; i < a.size; i++)
125 {
126 output << setw(12) << a.ptr[i];
127
128 if ((i + 1) % 4 == 0) // 4 numbers per row of output
129 output << endl;
130 } // end for
131
132 if (i % 4 != 0) // end last line of output
133 output << endl;
134
135 return output; // enables cout << x << y;
136 } // end function operator<<

```

---

**Fig. 19.7** | Array class member- and friend-function definitions. (Part 3 of 3.)

---

```

1 // Fig. 19.8: fig19_08.cpp
2 // Array class test program.
3 #include <iostream>
4 #include "Array.h"
5 using namespace std;
6
7 int main()
8 {
9 Array integers1(7); // seven-element Array
10 Array integers2; // 10-element Array by default
11
12 // print integers1 size and contents
13 cout << "Size of Array integers1 is "
14 << integers1.getSize()
15 << "\nArray after initialization:\n" << integers1;
16

```

---

**Fig. 19.8** | Array class test program. (Part 1 of 3.)

```

17 // print integers2 size and contents
18 cout << "\nSize of Array integers2 is "
19 << integers2.getSize()
20 << "\nArray after initialization:\n" << integers2;
21
22 // input and print integers1 and integers2
23 cout << "\nEnter 17 integers:" << endl;
24 cin >> integers1 >> integers2;
25
26 cout << "\nAfter input, the Arrays contain:\n"
27 << "integers1:\n" << integers1
28 << "integers2:\n" << integers2;
29
30 // use overloaded inequality (!=) operator
31 cout << "\nEvaluating: integers1 != integers2" << endl;
32
33 if (integers1 != integers2)
34 cout << "integers1 and integers2 are not equal" << endl;
35
36 // create Array integers3 using integers1 as an
37 // initializer; print size and contents
38 Array integers3(integers1); // invokes copy constructor
39
40 cout << "\nSize of Array integers3 is "
41 << integers3.getSize()
42 << "\nArray after initialization:\n" << integers3;
43
44 // use overloaded assignment (=) operator
45 cout << "\nAssigning integers2 to integers1:" << endl;
46 integers1 = integers2; // note target Array is smaller
47
48 cout << "integers1:\n" << integers1
49 << "integers2:\n" << integers2;
50
51 // use overloaded equality (==) operator
52 cout << "\nEvaluating: integers1 == integers2" << endl;
53
54 if (integers1 == integers2)
55 cout << "integers1 and integers2 are equal" << endl;
56
57 // use overloaded subscript operator to create rvalue
58 cout << "\nintegers1[5] is " << integers1[5];
59
60 // use overloaded subscript operator to create lvalue
61 cout << "\nAssigning 1000 to integers1[5]" << endl;
62 integers1[5] = 1000;
63 cout << "integers1:\n" << integers1;
64
65 // attempt to use out-of-range subscript
66 cout << "\nAttempt to assign 1000 to integers1[15]" << endl;
67 integers1[15] = 1000; // ERROR: out of range
68 } // end main

```

**Fig. 19.8** | Array class test program. (Part 2 of 3.)

```

Size of Array integers1 is 7
Array after initialization:
 0 0 0 0
 0 0 0 0

Size of Array integers2 is 10
Array after initialization:
 0 0 0 0
 0 0 0 0
 0 0 0 0

Enter 17 integers:
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17

After input, the Arrays contain:
integers1:
 1 2 3 4
 5 6 7 0
integers2:
 8 9 10 11
 12 13 14 15
 16 17 0 0

Evaluating: integers1 != integers2
integers1 and integers2 are not equal

Size of Array integers3 is 7
Array after initialization:
 1 2 3 4
 5 6 7 0

Assigning integers2 to integers1:
integers1:
 8 9 10 11
 12 13 14 15
 16 17 0 0
integers2:
 8 9 10 11
 12 13 14 15
 16 17 0 0

Evaluating: integers1 == integers2
integers1 and integers2 are equal

integers1[5] is 13

Assigning 1000 to integers1[5]
integers1:
 8 9 10 11
 12 1000 14 15
 16 17 0 0

Attempt to assign 1000 to integers1[15]

Error: Subscript 15 out of range

```

**Fig. 19.8** | Array class test program. (Part 3 of 3.)

*Creating Arrays, Outputting Their Size and Displaying Their Contents*

The program begins by instantiating two objects of class `Array`—`integers1` (Fig. 19.8, line 9) with seven elements, and `integers2` (Fig. 19.8, line 10) with the default `Array` size—10 elements (specified by the `Array` default constructor’s prototype in Fig. 19.6, line 14). Lines 13–15 use member function `getSize` to determine the size of `integers1` and output `integers1`, using the `Array` overloaded stream insertion operator. The sample output confirms that the `Array` elements were set correctly to zeros by the constructor. Next, lines 18–20 output the size of `Array` `integers2` and output `integers2`, using the `Array` overloaded stream insertion operator.

*Using the Overloaded Stream Insertion Operator to Fill an Array*

Line 23 prompts the user to input 17 integers. Line 24 uses the `Array` overloaded stream extraction operator to read these values into both arrays. The first seven values are stored in `integers1` and the remaining 10 values are stored in `integers2`. Lines 26–28 output the two arrays with the overloaded `Array` stream insertion operator to confirm that the input was performed correctly.

*Using the Overloaded Inequality Operator*

Line 33 tests the overloaded inequality operator by evaluating the condition

```
integers1 != integers2
```

The program output shows that the `Arrays` are not equal.

*Initializing a New Array with a Copy of an Existing Array’s Contents*

Line 38 instantiates a third `Array` called `integers3` and initializes it with a copy of `Array` `integers1`. This invokes the `Array` [copy constructor](#) to copy the elements of `integers1` into `integers3`. We discuss the details of the copy constructor shortly. The copy constructor can also be invoked by writing line 38 as follows:

```
Array integers3 = integers1;
```

The equal sign in the preceding statement is *not* the assignment operator. When an equal sign appears in the declaration of an object, it invokes a constructor for that object. This form can be used to pass only a single argument to a constructor.

Lines 40–42 output the size of `integers3` and output `integers3`, using the `Array` overloaded stream insertion operator to confirm that the `Array` elements were set correctly by the copy constructor.

*Using the Overloaded Assignment Operator*

Next, line 46 tests the overloaded assignment operator (`=`) by assigning `integers2` to `integers1`. Lines 48–49 print both `Array` objects to confirm that the assignment was successful. Note that `integers1` originally held 7 integers and was resized to hold a copy of the 10 elements in `integers2`. As we’ll see, the overloaded assignment operator performs this resizing operation in a manner that is transparent to the client code.

*Using the Overloaded Equality Operator*

Next, line 54 uses the overloaded equality operator (`==`) to confirm that objects `integers1` and `integers2` are indeed identical after the assignment.

*Using the Overloaded Subscript Operator*

Line 58 uses the overloaded subscript operator to refer to `integers1[5]`—an in-range element of `integers1`. This subscripted name is used as an *rvalue* to print the value stored in `integers1[5]`. Line 62 uses `integers1[5]` as a modifiable *lvalue* on the left side of an assignment statement to assign a new value, 1000, to element 5 of `integers1`. We'll see that `operator[]` returns a reference to use as the modifiable *lvalue* after the operator confirms that 5 is a valid subscript for `integers1`.

Line 67 attempts to assign the value 1000 to `integers1[15]`—an out-of-range element. In this example, `operator[]` determines that the subscript is out of range, prints a message and terminates the program. We highlighted line 67 of the program in darker blue to emphasize that it's an error to access an element that is out of range. This is a runtime logic error.

Interestingly, the array subscript operator `[]` is not restricted for use only with arrays; it also can be used, for example, to select elements from other kinds of container classes, such as linked lists, strings and dictionaries. Also, when `operator[]` functions are defined, subscripts no longer have to be integers—characters, strings, floats or even objects of user-defined classes also could be used.

*Array Class Definition*

Now that we've seen how this program operates, let's walk through the class header (Fig. 19.6). As we refer to each member function in the header, we discuss that function's implementation in Fig. 19.7. In Fig. 19.6, lines 34–35 represent the private data members of class `Array`. Each `Array` object consists of a `size` member indicating the number of elements in the `Array` and an `int` pointer—`ptr`—that points to the dynamically allocated pointer-based array of integers managed by the `Array` object.

*Overloading the Stream Insertion and Stream Extraction Operators as **friends***

Lines 11–12 of Fig. 19.6 declare the overloaded stream insertion operator and the overloaded stream extraction operator to be friends of class `Array`. When the compiler sees an expression like `cout << arrayObject`, it invokes global function `operator<<` with the call

```
operator<<(cout, arrayObject)
```

When the compiler sees an expression like `cin >> arrayObject`, it invokes global function `operator>>` with the call

```
operator>>(cin, arrayObject)
```

We note again that these stream insertion and stream extraction operator functions cannot be members of class `Array`, because the `Array` object is always mentioned on the right side of the stream insertion operator and the stream extraction operator. If these operator functions were to be members of class `Array`, the following awkward statements would have to be used to output and input an `Array`:

```
arrayObject << cout;
arrayObject >> cin;
```

Such statements would be confusing to most C++ programmers, who are familiar with `cout` and `cin` appearing as the left operands of `<<` and `>>`, respectively.

Function operator<< (defined in Fig. 19.7, lines 119–136) prints the number of elements indicated by size from the integer array to which ptr points. Function operator>> (defined in Fig. 19.7, lines 110–116) inputs directly into the array to which ptr points. Each of these operator functions returns an appropriate reference to enable cascaded output or input statements, respectively. Each of these functions has access to an Array's private data because these functions are declared as friends of class Array. Also, class Array's getSize and operator[] functions could be used by operator<< and operator>>, in which case these operator functions would not need to be friends of class Array. However, the additional function calls might increase execution-time overhead.

### Array Default Constructor

Line 14 of Fig. 19.6 declares the default constructor for the class and specifies a default size of 10 elements. When the compiler sees a declaration like line 10 in Fig. 19.8, it invokes class Array's default constructor (remember that the default constructor in this example actually receives a single int argument that has a default value of 10). The default constructor (defined in Fig. 19.7, lines 10–17) validates and assigns the argument to data member size, uses new to obtain the memory for the internal pointer-based representation of this array and assigns the pointer returned by new to data member ptr. Then the constructor uses a for statement to set all the elements of the array to zero. It's possible to have an Array class that does not initialize its members if, for example, these members are to be read at some later time; but this is considered to be a poor programming practice. Arrays, and objects in general, should be properly initialized and maintained in a consistent state.

### Array Copy Constructor

Line 15 of Fig. 19.6 declares a copy constructor (defined in Fig. 19.7, lines 21–28) that initializes an Array by making a copy of an existing Array object. Such copying must be done carefully to avoid the pitfall of leaving both Array objects pointing to the same dynamically allocated memory. This is exactly the problem that would occur with default memberwise copying, if the compiler is allowed to define a default copy constructor for this class. Copy constructors are invoked whenever a copy of an object is needed, such as in passing an object by value to a function, returning an object by value from a function or initializing an object with a copy of another object of the same class. The copy constructor is called in a declaration when an object of class Array is instantiated and initialized with another object of class Array, as in the declaration in line 38 of Fig. 19.8.



#### Software Engineering Observation 19.4

*The argument to a copy constructor should be a const reference to allow a const object to be copied.*



#### Common Programming Error 19.7

*A copy constructor must receive its argument by reference, not by value. Otherwise, the copy constructor call results in infinite recursion (a fatal logic error) because receiving an object by value requires the copy constructor to make a copy of the argument object. Recall that any time a copy of an object is required, the class's copy constructor is called. If the copy constructor received its argument by value, the copy constructor would call itself recursively to make a copy of its argument!*



The copy constructor for `Array` uses a member initializer (Fig. 19.7, line 22) to copy the size of the initializer `Array` into data member `size`, uses `new` (line 24) to obtain the memory for the internal pointer-based representation of this `Array` and assigns the pointer returned by `new` to data member `ptr`.<sup>1</sup> Then the copy constructor uses a `for` statement to copy all the elements of the initializer `Array` into the new `Array` object. An object of a class can look at the private data of any other object of that class (using a handle that indicates which object to access).



### Common Programming Error 19.8

*If the copy constructor simply copied the pointer in the source object to the target object's pointer, then both objects would point to the same dynamically allocated memory. The first destructor to execute would then delete the dynamically allocated memory, and the other object's `ptr` would be undefined, a situation called a **dangling pointer**—this would likely result in a serious run-time error (such as early program termination) when the pointer was used.*

### Array Destructor

Line 16 of Fig. 19.6 declares the class's destructor (defined in Fig. 19.7, lines 31–34). The destructor is invoked when an object of class `Array` goes out of scope. The destructor uses `delete []` to release the memory allocated dynamically by `new` in the constructor.



### Error-Prevention Tip 19.2

*If after deleting dynamically allocated memory, the pointer will continue to exist in memory, set the pointer's value to 0 to indicate that the pointer no longer points to memory in the free store. By setting the pointer to 0, the program loses access to that free-store space, which could be reallocated for a different purpose. If you do not set the pointer to 0, your code could inadvertently access the reallocated memory, causing subtle, nonrepeatable logic errors.*

### getSize Member Function

Line 17 of Fig. 19.6 declares function `getSize` (defined in Fig. 19.7, lines 37–40) that returns the number of elements in the `Array`.

### Overloaded Assignment Operator

Line 19 of Fig. 19.6 declares the overloaded assignment operator function for the class. When the compiler sees the expression `integers1 = integers2` in line 46 of Fig. 19.8, the compiler invokes member function `operator=` with the call

```
integers1.operator=(integers2)
```

Member function `operator=`'s implementation (Fig. 19.7, lines 44–62) tests for **self-assignment** (line 46) in which an `Array` object is being assigned to itself. When `this` is equal to the right operand's address, a self-assignment is being attempted, so the assignment is skipped (i.e., the object already is itself; in a moment we'll see why self-assignment is dangerous). If it isn't a self-assignment, then the function determines whether the sizes of the

1. Operator `new` could fail to obtain the needed memory. We deal with new failures in Chapter 24.

two arrays are identical (line 50); in that case, the original array of integers in the left-side Array object is not reallocated. Otherwise, `operator=` uses `delete` (line 52) to release the memory originally allocated to the target array, copies the size of the source array to the size of the target array (line 53), uses `new` to allocate memory for the target array and places the pointer returned by `new` into the array's `ptr` member. Then the `for` statement in lines 57–58 copies the array elements from the source array to the target array. Regardless of whether this is a self-assignment, the member function returns the current object (i.e., `*this` in line 61) as a constant reference; this enables cascaded Array assignments such as `x = y = z`, but prevents ones like `(x = y) = z` because `z` cannot be assigned to the const Array reference that is returned by `(x = y)`. If self-assignment occurs, and function `operator=` did not test for this case, `operator=` would unnecessarily copy the elements of the Array into itself.



### Software Engineering Observation 19.5

*A copy constructor, a destructor and an overloaded assignment operator are usually provided as a group for any class that uses dynamically allocated memory.*



### Common Programming Error 19.9

*Not providing an overloaded assignment operator and a copy constructor for a class when objects of that class contain pointers to dynamically allocated memory is a logic error.*



### Software Engineering Observation 19.6

*It's possible to prevent one object of a class from being assigned to another. This is done by declaring the assignment operator as a private member of the class.*



### Software Engineering Observation 19.7

*It's possible to prevent class objects from being copied; to do this, simply make both the overloaded assignment operator and the copy constructor of that class private.*

## Overloaded Equality and Inequality Operators

Line 20 of Fig. 19.6 declares the overloaded equality operator (`==`) for the class. When the compiler sees the expression `integers1 == integers2` in line 54 of Fig. 19.8, the compiler invokes member function `operator==` with the call

```
integers1.operator==(integers2)
```

Member function `operator==` (defined in Fig. 19.7, lines 66–76) immediately returns `false` if the size members of the arrays are not equal. Otherwise, `operator==` compares each pair of elements. If they're all equal, the function returns `true`. The first pair of elements to differ causes the function to return `false` immediately.

Lines 23–26 of the header file define the overloaded inequality operator (`!=`) for the class. Member function `operator!=` uses the overloaded `operator==` function to determine whether one Array is equal to another, then returns the opposite of that result. Writing `operator!=` in this manner enables you to reuse `operator==`, which reduces the amount of code that must be written in the class. Also, the full function definition for `operator!=` is in the Array header file. This allows the compiler to inline the definition of `operator!=` to eliminate the overhead of the extra function call.

*Overloaded Subscript Operators*

Lines 29 and 32 of Fig. 19.6 declare two overloaded subscript operators (defined in Fig. 19.7 in lines 80–91 and 95–106, respectively). When the compiler sees the expression `integers1[5]` (Fig. 19.8, line 58), it invokes the appropriate overloaded `operator[]` member function by generating the call

```
integers1.operator[](5)
```

The compiler creates a call to the `const` version of `operator[]` (Fig. 19.7, lines 95–106) when the subscript operator is used on a `const` `Array` object. For example, if `const` object `z` is instantiated with the statement

```
const Array z(5);
```

then the `const` version of `operator[]` is required to execute a statement such as

```
cout << z[3] << endl;
```

Remember, a program can invoke only the `const` member functions of a `const` object.

Each definition of `operator[]` determines whether the subscript it receives as an argument is in range. If it isn't, each function prints an error message and terminates the program with a call to function `exit` (header `<cstdlib>`).<sup>2</sup> If the subscript is in range, the non-`const` version of `operator[]` returns the appropriate array element as a reference so that it may be used as a modifiable *lvalue* (e.g., on the left side of an assignment statement). If the subscript is in range, the `const` version of `operator[]` returns a copy of the appropriate element of the array. The returned character is an *rvalue*.

## 19.10 Converting between Types

Most programs process information of many types. Sometimes all the operations “stay within a type.” For example, adding an `int` to an `int` produces an `int`. It's often necessary, however, to convert data of one type to data of another type. This can happen in assignments, in calculations, in passing values to functions and in returning values from functions. The compiler knows how to perform certain conversions among fundamental types. You can use cast operators to force conversions among fundamental types.

But what about user-defined types? The compiler cannot know in advance how to convert among user-defined types, and between user-defined types and fundamental types, so you must specify how to do this. Such conversions can be performed with **conversion constructors**—**single-argument constructors** that turn objects of other types (including fundamental types) into objects of a particular class.

A **conversion operator** (also called a cast operator) can be used to convert an object of one class into an object of another class or into an object of a fundamental type. Such a conversion operator must be a non-static member function. The function prototype

```
A::operator char *() const;
```

2. It's more appropriate when a subscript is out of range to “throw an exception” indicating the out-of-range subscript. Then the program can “catch” that exception, process it and possibly continue execution. See Chapter 24 for more information on exceptions.

declares an overloaded cast operator function for converting an object of user-defined type `A` into a temporary `char *` object. The operator function is declared `const` because it does not modify the original object. An overloaded **cast operator function** does not specify a return type—the return type is the type to which the object is being converted. If `s` is a class object, when the compiler sees the expression `static_cast< char *>( s )`, the compiler generates the call

```
s.operator char *()
```

The operand `s` is the class object `s` for which the member function operator `char *` is being invoked.

Overloaded cast operator functions can be defined to convert objects of user-defined types into fundamental types or into objects of other user-defined types. The prototypes

```
A::operator int() const;
A::operator OtherClass() const;
```

declare overloaded cast operator functions that can convert an object of user-defined type `A` into an integer or into an object of user-defined type `OtherClass`, respectively.

One of the nice features of cast operators and conversion constructors is that, when necessary, the compiler can call these functions implicitly to create temporary objects. For example, if an object `s` of a user-defined `String` class appears in a program at a location where an ordinary `char *` is expected, such as

```
cout << s;
```

the compiler can call the overloaded cast-operator function operator `char *` to convert the object into a `char *` and use the resulting `char *` in the expression. With this cast operator provided for a `String` class, the stream insertion operator does not have to be overloaded to output a `String` using `cout`.

## 19.11 Building a String Class

In Chapter 8, we introduced C-style, pointer-based string processing with character arrays. As part of our coverage of crafting valuable classes, we implement our own `String` class that encapsulates a dynamically allocated C string and provides many capabilities that are similar to those we introduced in the `Array` class. To implement this class, we use several of the capabilities introduced in Chapter 8. Because classes `Array` and `String` are so similar, we placed the `String` class code and discussion online at [www.deitel.com/books/cpphttp7/](http://www.deitel.com/books/cpphttp7/) under **Downloads and Resources for Registered Users**.

In this section, we discuss some of the features that are defined in the `String` class. The C++ standard library includes the similar, more robust `string` class.

### *String Conversion Constructor*

Our `String` class provides a conversion constructor that takes a `const char *` argument and initializes a `String` object containing that same character string. Recall that any single-argument constructor can be thought of as a conversion constructor. Such constructors are helpful when we're doing any `String` operation using `char *` arguments. The conversion constructor can convert a `char *` string into a `String` object, which can then be assigned to the target `String` object. The availability of this conversion constructor means that it

isn't necessary to supply an overloaded assignment operator for assigning character strings to `String` objects. When the compiler encounters the statement

```
myString = "he11o";
```

where `myString` is a `String` object, the compiler invokes the conversion constructor to create a temporary `String` object containing the character string "hello"; then class `String`'s overloaded assignment operator is invoked to assign the temporary `String` object to `String` object `myString`.



### Software Engineering Observation 19.8

*When a conversion constructor is used to perform an implicit conversion, C++ can apply only one implicit constructor call (i.e., a single user-defined conversion) to try to match the needs of another overloaded operator. The compiler will not satisfy an overloaded operator's needs by performing a series of implicit, user-defined conversions.*

The `String` conversion constructor could be invoked in a declaration such as

```
String s1("happy");
```

It can also be invoked when you pass a C string to a function that expects a `String` argument or when you return a C string from a function with a `String` return type.

### Overloaded Unary Negation Operator

The overloaded negation operator determines whether a `String` object is empty. For example, when the compiler sees the expression `!string1`, it generates the function call

```
string1.operator!()
```

This function returns `true` if the `String`'s length is equal to zero, and `false` otherwise.

### Overloaded Function Call Operator

Overloading the **function call operator** `()` is powerful, because functions can take an arbitrary number of parameters. In class `String`, we overload this operator to select a substring from a `String`. The operator's two integer parameters specify the start location and the length of the substring to be selected. If the start location is out of range or the substring length is negative, the operator simply returns an empty `String`. If the substring length is 0, then the substring is selected to the end of the `String` object. Suppose `string1` is a `String` object containing the string "AEIOU". When the compiler encounters the expression `string1(2, 2)`, it generates the member-function call

```
string1.operator()(2, 2)
```

which returns a `String` containing "IO".

## 19.12 Overloading ++ and --

The prefix and postfix versions of the increment and decrement operators can all be overloaded. We'll see how the compiler distinguishes between the prefix version and the postfix version of an increment or decrement operator.

To overload the increment operator to allow both prefix and postfix increment usage, each overloaded operator function must have a distinct signature, so that the compiler will

be able to determine which version of ++ is intended. The prefix versions are overloaded exactly as any other prefix unary operator would be.

### *Overloading the Prefix Increment Operator*

Suppose, for example, that we want to add 1 to the day in Date object d1. When the compiler sees the preincrementing expression ++d1, the compiler generates the member-function call

```
d1.operator++()
```

The prototype for this operator function would be

```
Date &operator++();
```

If the prefix increment operator is implemented as a global function, then, when the compiler sees the expression ++d1, the compiler generates the function call

```
operator++(d1)
```

The prototype for this operator function would be declared in the Date class as

```
Date &operator++(Date &);
```

### *Overloading the Postfix Increment Operator*

Overloading the postfix increment operator presents a challenge, because the compiler must be able to distinguish between the signatures of the overloaded prefix and postfix increment operator functions. The *convention* that has been adopted in C++ is that, when the compiler sees the postincrementing expression d1++, it generates the member-function call

```
d1.operator++(0)
```

The prototype for this function is

```
Date operator++(int)
```

The argument 0 is strictly a “dummy value” that enables the compiler to distinguish between the prefix and postfix increment operator functions. The same syntax is used to differentiate between the prefix and postfix decrement operator functions.

If the postfix increment is implemented as a global function, then, when the compiler sees the expression d1++, the compiler generates the function call

```
operator++(d1, 0)
```

The prototype for this function would be

```
Date operator++(Date &, int);
```

Once again, the 0 argument is used by the compiler to distinguish between the prefix and postfix increment operators implemented as global functions. Note that the postfix increment operator returns Date objects by value, whereas the prefix increment operator returns Date objects by reference, because the postfix increment operator typically returns a temporary object that contains the original value of the object before the increment occurred. C++ treats such objects as *rvalues*, which cannot be used on the left side of an assignment. The prefix increment operator returns the actual incremented object with its new value. Such an object can be used as an *lvalue* in a continuing expression.

**Performance Tip 19.2**

*The extra object that is created by the postfix increment (or decrement) operator can result in a significant performance problem—especially when the operator is used in a loop. For this reason, you should use the postfix increment (or decrement) operator only when the logic of the program requires postincrementing (or postdecrementing).*

Everything stated in this section for overloading prefix and postfix increment operators applies to overloading predecrement and postdecrement operators. Next, we examine a Date class with overloaded prefix and postfix increment operators.

## 19.13 Case Study: A Date Class

The program of Figs. 19.9–19.11 demonstrates a Date class, which uses overloaded prefix and postfix increment operators to add 1 to the day in a Date object, while causing appropriate increments to the month and year if necessary. The Date header file (Fig. 19.9) specifies that Date’s public interface includes an overloaded stream insertion operator (line 11), a default constructor (line 13), a setDate function (line 14), an overloaded prefix increment operator (line 15), an overloaded postfix increment operator (line 16), an overloaded += addition assignment operator (line 17), a function to test for leap years (line 18) and a function to determine whether a day is the last day of the month (line 19).

---

```

1 // Fig. 19.9: Date.h
2 // Date class definition with overloaded increment operators.
3 #ifndef DATE_H
4 #define DATE_H
5
6 #include <iostream>
7 using namespace std;
8
9 class Date
10 {
11 friend ostream &operator<<(ostream &, const Date &);
12 public:
13 Date(int m = 1, int d = 1, int y = 1900); // default constructor
14 void setDate(int, int, int); // set month, day, year
15 Date &operator++(); // prefix increment operator
16 Date operator++(int); // postfix increment operator
17 const Date &operator+=(int); // add days, modify object
18 static bool leapYear(int); // is date in a leap year?
19 bool endOfMonth(int) const; // is date at the end of month?
20 private:
21 int month;
22 int day;
23 int year;
24
25 static const int days[]; // array of days per month
26 void helpIncrement(); // utility function for incrementing date
27 }; // end class Date
28
29 #endif

```

---

**Fig. 19.9** | Date class definition with overloaded increment operators.

```

1 // Fig. 19.10: Date.cpp
2 // Date class member- and friend-function definitions.
3 #include <iostream>
4 #include <string>
5 #include "Date.h"
6 using namespace std;
7
8 // initialize static member; one classwide copy
9 const int Date::days[] =
10 { 0, 31, 28, 31, 30, 31, 30, 31, 31, 30, 31, 30, 31 };
11
12 // Date constructor
13 Date::Date(int m, int d, int y)
14 {
15 setDate(m, d, y);
16 } // end Date constructor
17
18 // set month, day and year
19 void Date::setDate(int mm, int dd, int yy)
20 {
21 month = (mm >= 1 && mm <= 12) ? mm : 1;
22 year = (yy >= 1900 && yy <= 2100) ? yy : 1900;
23
24 // test for a leap year
25 if (month == 2 && leapYear(year))
26 day = (dd >= 1 && dd <= 29) ? dd : 1;
27 else
28 day = (dd >= 1 && dd <= days[month]) ? dd : 1;
29 } // end function setDate
30
31 // overloaded prefix increment operator
32 Date &Date::operator++()
33 {
34 helpIncrement(); // increment date
35 return *this; // reference return to create an lvalue
36 } // end function operator++
37
38 // overloaded postfix increment operator; note that the
39 // dummy integer parameter does not have a parameter name
40 Date Date::operator++(int)
41 {
42 Date temp = *this; // hold current state of object
43 helpIncrement();
44
45 // return unincremented, saved, temporary object
46 return temp; // value return; not a reference return
47 } // end function operator++
48
49 // add specified number of days to date
50 const Date &Date::operator+=(int additionalDays)
51 {
52 for (int i = 0; i < additionalDays; i++)
53 helpIncrement();

```

**Fig. 19.10** | Date class member- and friend-function definitions. (Part I of 2.)



---

```

54
55 return *this; // enables cascading
56 } // end function operator+=
57
58 // if the year is a leap year, return true; otherwise, return false
59 bool Date::leapYear(int testYear)
60 {
61 if (testYear % 400 == 0 ||
62 (testYear % 100 != 0 && testYear % 4 == 0))
63 return true; // a leap year
64 else
65 return false; // not a leap year
66 } // end function leapYear
67
68 // determine whether the day is the last day of the month
69 bool Date::endOfMonth(int testDay) const
70 {
71 if (month == 2 && leapYear(year))
72 return testDay == 29; // last day of Feb. in leap year
73 else
74 return testDay == days[month];
75 } // end function endOfMonth
76
77 // function to help increment the date
78 void Date::helpIncrement()
79 {
80 // day is not end of month
81 if (!endOfMonth(day))
82 day++; // increment day
83 else
84 if (month < 12) // day is end of month and month < 12
85 {
86 month++; // increment month
87 day = 1; // first day of new month
88 } // end if
89 else // last day of year
90 {
91 year++; // increment year
92 month = 1; // first month of new year
93 day = 1; // first day of new month
94 } // end else
95 } // end function helpIncrement
96
97 // overloaded output operator
98 ostream &operator<<(ostream &output, const Date &d)
99 {
100 static string monthName[13] = { "", "January", "February",
101 "March", "April", "May", "June", "July", "August",
102 "September", "October", "November", "December" };
103 output << monthName[d.month] << " " << d.day << ", " << d.year;
104 return output; // enables cascading
105 } // end function operator<<

```

---

**Fig. 19.10** | Date class member- and friend-function definitions. (Part 2 of 2.)

```

1 // Fig. 19.11: fig19_11.cpp
2 // Date class test program.
3 #include <iostream>
4 #include "Date.h" // Date class definition
5 using namespace std;
6
7 int main()
8 {
9 Date d1; // defaults to January 1, 1900
10 Date d2(12, 27, 1992); // December 27, 1992
11 Date d3(0, 99, 8045); // invalid date
12
13 cout << "d1 is " << d1 << "\nd2 is " << d2 << "\nd3 is " << d3;
14 cout << "\nd2 += 7 is " << (d2 += 7);
15
16 d3.setDate(2, 28, 1992);
17 cout << "\n\n d3 is " << d3;
18 cout << "\n++d3 is " << ++d3 << " (leap year allows 29th)";
19
20 Date d4(7, 13, 2002);
21
22 cout << "\n\nTesting the prefix increment operator:\n"
23 << " d4 is " << d4 << endl;
24 cout << "++d4 is " << ++d4 << endl;
25 cout << " d4 is " << d4;
26
27 cout << "\n\nTesting the postfix increment operator:\n"
28 << " d4 is " << d4 << endl;
29 cout << "d4++ is " << d4++ << endl;
30 cout << " d4 is " << d4 << endl;
31 } // end main

```

```

d1 is January 1, 1900
d2 is December 27, 1992
d3 is January 1, 1900

d2 += 7 is January 3, 1993

d3 is February 28, 1992
++d3 is February 29, 1992 (leap year allows 29th)

Testing the prefix increment operator:
d4 is July 13, 2002
++d4 is July 14, 2002
d4 is July 14, 2002

Testing the postfix increment operator:
d4 is July 14, 2002
d4++ is July 14, 2002
d4 is July 15, 2002

```

**Fig. 19.11** | Date class test program.

Function `main` (Fig. 19.11) creates three `Date` objects (lines 9–11)—`d1` is initialized by default to January 1, 1900; `d2` is initialized to December 27, 1992; and `d3` is initialized to an invalid date. The `Date` constructor (defined in Fig. 19.10, lines 13–16) calls `setDate` to validate the month, day and year specified. An invalid month is set to 1, an invalid year is set to 1900 and an invalid day is set to 1.

Line 13 of `main` output each of the constructed `Date` objects, using the overloaded stream insertion operator (defined in Fig. 19.10, lines 98–105). Line 14 of `main` uses the overloaded operator `+=` to add seven days to `d2`. Line 16 uses function `setDate` to set `d3` to February 28, 1992, which is a leap year. Then, line 18 preincrements `d3` to show that the date increments properly to February 29. Next, line 20 creates a `Date` object, `d4`, which is initialized with the date July 13, 2002. Then line 24 increments `d4` by 1 with the overloaded prefix increment operator. Lines 22–25 output `d4` before and after the preincrement operation to confirm that it worked correctly. Finally, line 29 increments `d4` with the overloaded postfix increment operator. Lines 27–30 output `d4` before and after the postincrement operation to confirm that it worked correctly.

Overloading the prefix increment operator is straightforward. The prefix increment operator (defined in Fig. 19.10, lines 32–36) calls utility function `helpIncrement` (defined in Fig. 19.10, lines 78–95) to increment the date. This function deals with “wraparounds” or “carries” that occur when we increment the last day of the month. These carries require incrementing the month. If the month is already 12, then the year must also be incremented and the month must be set to 1. Function `helpIncrement` uses function `endOfMonth` to increment the day correctly.

The overloaded prefix increment operator returns a reference to the current `Date` object (i.e., the one that was just incremented). This occurs because the current object, `*this`, is returned as a `Date &`. This enables a preincremented `Date` object to be used as an *lvalue*, which is how the built-in prefix increment operator works for fundamental types.

Overloading the postfix increment operator (defined in Fig. 19.10, lines 40–47) is trickier. To emulate the effect of the postincrement, we must return an unincremented copy of the `Date` object. For example, if `int` variable `x` has the value 7, the statement

```
cout << x++ << endl;
```

outputs the original value of variable `x`. So we’d like our postfix increment operator to operate the same way on a `Date` object. On entry to `operator++`, we save the current object (`*this`) in `temp` (line 42). Next, we call `helpIncrement` to increment the current `Date` object. Then, line 46 returns the unincremented copy of the object previously stored in `temp`. This function cannot return a reference to the local `Date` object `temp`, because a local variable is destroyed when the function in which it’s declared exits. Thus, declaring the return type to this function as `Date &` would return a reference to an object that no longer exists. Returning a reference (or a pointer) to a local variable is a common error for which most compilers will issue a warning.

## 19.14 Standard Library Class `string`

Building useful, reusable classes such as `Array` (Figs. 19.6–19.8) takes work. However, once such classes are tested and debugged, they can be reused by you, your colleagues, your company, many companies, an entire industry or even many industries (if they’re placed

in public or for-sale libraries). The designers of C++ did exactly that, building class `string` and class template `vector` into standard C++. These classes are available to anyone building applications with C++.

Figure 19.12 demonstrates many of class `string`'s overloaded operators, its conversion constructor for C strings and several other useful member functions, including `empty`, `substr` and `at`. Function `empty` determines whether a `string` is empty, function `substr` returns a `string` that represents a portion of an existing `string` and function `at` returns the character at a specific index in a `string` (after checking that the index is in range).

---

```

1 // Fig. 19.12: fig19_12.cpp
2 // Standard Library string class test program.
3 #include <iostream>
4 #include <string>
5 using namespace std;
6
7 int main()
8 {
9 string s1("happy");
10 string s2(" birthday");
11 string s3;
12
13 // test overloaded equality and relational operators
14 cout << "s1 is \" " << s1 << "\"; s2 is \" " << s2
15 << "\"; s3 is \" " << s3 << "\"
16 << "\n\nThe results of comparing s2 and s1:"
17 << "\ns2 == s1 yields " << (s2 == s1 ? "true" : "false")
18 << "\ns2 != s1 yields " << (s2 != s1 ? "true" : "false")
19 << "\ns2 > s1 yields " << (s2 > s1 ? "true" : "false")
20 << "\ns2 < s1 yields " << (s2 < s1 ? "true" : "false")
21 << "\ns2 >= s1 yields " << (s2 >= s1 ? "true" : "false")
22 << "\ns2 <= s1 yields " << (s2 <= s1 ? "true" : "false");
23
24 // test string member-function empty
25 cout << "\n\nTesting s3.empty():" << endl;
26
27 if (s3.empty())
28 {
29 cout << "s3 is empty; assigning s1 to s3;" << endl;
30 s3 = s1; // assign s1 to s3
31 cout << "s3 is \" " << s3 << "\"";
32 } // end if
33
34 // test overloaded string concatenation operator
35 cout << "\n\ns1 += s2 yields s1 = ";
36 s1 += s2; // test overloaded concatenation
37 cout << s1;
38
39 // test overloaded string concatenation operator with C-style string
40 cout << "\n\ns1 += \" to you\" yields" << endl;
41 s1 += " to you";
42 cout << "s1 = " << s1 << "\n\n";

```

---

**Fig. 19.12** | Standard Library class `string`. (Part I of 3.)

```

43
44 // test string member function substr
45 cout << "The substring of s1 starting at location 0 for\n"
46 << "14 characters, s1.substr(0, 14), is:\n"
47 << s1.substr(0, 14) << "\n\n";
48
49 // test substr "to-end-of-string" option
50 cout << "The substring of s1 starting at\n"
51 << "location 15, s1.substr(15), is:\n"
52 << s1.substr(15) << endl;
53
54 // test copy constructor
55 string s4(s1);
56 cout << "\ns4 = " << s4 << "\n\n";
57
58 // test overloaded assignment (=) operator with self-assignment
59 cout << "assigning s4 to s4" << endl;
60 s4 = s4;
61 cout << "s4 = " << s4 << endl;
62
63 // test using overloaded subscript operator to create lvalue
64 s1[0] = 'H';
65 s1[6] = 'B';
66 cout << "\ns1 after s1[0] = 'H' and s1[6] = 'B' is: "
67 << s1 << "\n\n";
68
69 // test subscript out of range with string member function "at"
70 cout << "Attempt to assign 'd' to s1.at(30) yields:" << endl;
71 s1.at(30) = 'd'; // ERROR: subscript out of range
72 } // end main

```

s1 is "happy"; s2 is " birthday"; s3 is ""

The results of comparing s2 and s1:

```

s2 == s1 yields false
s2 != s1 yields true
s2 > s1 yields false
s2 < s1 yields true
s2 >= s1 yields false
s2 <= s1 yields true

```

Testing s3.empty():

```

s3 is empty; assigning s1 to s3;
s3 is "happy"

```

s1 += s2 yields s1 = happy birthday

```

s1 += " to you" yields
s1 = happy birthday to you

```

The substring of s1 starting at location 0 for  
14 characters, s1.substr(0, 14), is:  
happy birthday

**Fig. 19.12** | Standard Library class string. (Part 2 of 3.)

```

The substring of s1 starting at
location 15, s1.substr(15), is:
to you

s4 = happy birthday to you
assigning s4 to s4
s4 = happy birthday to you

s1 after s1[0] = 'H' and s1[6] = 'B' is: Happy Birthday to you

Attempt to assign 'd' to s1.at(30) yields:

This application has requested the Runtime to terminate it in an unusual way.
Please contact the application's support team for more information.

```

**Fig. 19.12** | Standard Library class `string`. (Part 3 of 3.)

Lines 9–11 create three string objects—`s1` is initialized with the literal "happy", `s2` is initialized with the literal " birthday" and `s3` uses the default string constructor to create an empty string. Lines 14–15 output these three objects, using `cout` and operator `<<`, which the `string` class designers overloaded to handle string objects. Then lines 16–22 show the results of comparing `s2` to `s1` by using class `string`'s overloaded equality and relational operators, which perform lexicographical comparisons using the numerical values of the characters (see Appendix B, ASCII Character Set) in each string.

Class `string` provides member function `empty` to determine whether a string is empty, which we demonstrate in line 27. Member function `empty` returns `true` if the string is empty; otherwise, it returns `false`.

Line 30 demonstrates class `string`'s overloaded assignment operator by assigning `s1` to `s3`. Line 31 outputs `s3` to demonstrate that the assignment worked correctly.

Line 36 demonstrates class `string`'s overloaded `+=` operator for string concatenation. In this case, the contents of `s2` are appended to `s1`. Then line 37 outputs the resulting string that is stored in `s1`. Line 41 demonstrates that a C-style string literal can be appended to a string object by using operator `+=`. Line 42 displays the result.

Class `string` provides member function `substr` (lines 47 and 52) to return a portion of a string as a string object. The call to `substr` in line 47 obtains a 14-character substring (specified by the second argument) of `s1` starting at position 0 (specified by the first argument). The call to `substr` in line 52 obtains a substring starting from position 15 of `s1`. When the second argument is not specified, `substr` returns the remainder of the string on which it's called.

Line 55 creates string object `s4` and initializes it with a copy of `s1`. This results in a call to class `string`'s copy constructor. Line 60 uses class `string`'s overloaded `=` operator to demonstrate that it handles self-assignment properly.

Lines 64–65 use class `string`'s overloaded `[]` operator to create *lvalues* that enable new characters to replace existing characters in `s1`. Line 67 outputs the new value of `s1`. *Class `string`'s overloaded `[]` operator does not perform any bounds checking.* Therefore, you must ensure that operations using standard class `string`'s overloaded `[]` operator do not accidentally manipulate elements outside the bounds of the string. Class `string` does provide bounds checking in its member function `at`, which "throws an exception" if its argument is an invalid subscript. By default, this causes a C++ program to terminate and display a system-specific error message.<sup>3</sup> If the subscript is valid, function `at` returns the

character at the specified location as a modifiable *lvalue* or an unmodifiable *lvalue* (i.e., a `const` reference), depending on the context in which the call appears. Line 71 demonstrates a call to function `at` with an invalid subscript. The error message shown at the end of this program's output was produced when running the program on Windows Vista.

## 19.15 explicit Constructors

In Sections 19.9–19.10, we discussed that any single-argument constructor can be used by the compiler to perform an implicit conversion—the type received by the constructor is converted to an object of the class in which the constructor is defined. The conversion is automatic and you need not use a cast operator. In some situations, implicit conversions are undesirable or error-prone. For example, our `Array` class in Fig. 19.6 defines a constructor that takes a single `int` argument. The intent of this constructor is to create an `Array` object containing the number of elements specified by the `int` argument. However, this constructor can be misused by the compiler to perform an implicit conversion.



### Common Programming Error 19.10

*Unfortunately, the compiler might use implicit conversions in cases that you do not expect, resulting in ambiguous expressions that generate compilation errors or result in execution-time logic errors.*

#### *Accidentally Using a Single-Argument Constructor as a Conversion Constructor*

The program (Fig. 19.13) uses the `Array` class of Figs. 19.6–19.7 to demonstrate an improper implicit conversion.

---

```

1 // Fig. 19.13: Fig19_13.cpp
2 // Driver for simple class Array.
3 #include <iostream>
4 #include "Array.h"
5 using namespace std;
6
7 void outputArray(const Array &); // prototype
8
9 int main()
10 {
11 Array integers1(7); // 7-element array
12 outputArray(integers1); // output Array integers1
13 outputArray(3); // convert 3 to an Array and output Array's contents
14 } // end main
15
16 // print Array contents
17 void outputArray(const Array &arrayToOutput)
18 {
19 cout << "The Array received has " << arrayToOutput.getSize()
20 << " elements. The contents are:\n" << arrayToOutput << endl;
21 } // end outputArray

```

---

**Fig. 19.13** | Single-argument constructors and implicit conversions. (Part 1 of 2.)

---

3. Again, Chapter 24 demonstrates how to “catch” and handle such exceptions.

```

The Array received has 7 elements. The contents are:
 0 0 0 0
 0 0 0
The Array received has 3 elements. The contents are:
 0 0 0

```

**Fig. 19.13** | Single-argument constructors and implicit conversions. (Part 2 of 2.)

Line 11 in `main` instantiates `Array` object `integers1` and calls the single argument constructor with the `int` value 7 to specify the number of elements in the `Array`. Recall from Fig. 19.7 that the `Array` constructor that receives an `int` argument initializes all the array elements to 0. Line 12 calls function `outputArray` (defined in lines 17–21), which receives as its argument a `const Array &` to an `Array`. The function outputs the number of elements in its `Array` argument and the contents of the `Array`. In this case, the size of the `Array` is 7, so seven 0s are output.

Line 13 calls function `outputArray` with the `int` value 3 as an argument. However, this program does not contain a function called `outputArray` that takes an `int` argument. So, the compiler determines whether class `Array` provides a conversion constructor that can convert an `int` into an `Array`. Since any constructor that receives a single argument is considered to be a conversion constructor, the compiler assumes the `Array` constructor that receives a single `int` is a conversion constructor and uses it to convert the argument 3 into a temporary `Array` object that contains three elements. Then, the compiler passes the temporary `Array` object to function `outputArray` to output the `Array`'s contents. Thus, even though we do not explicitly provide an `outputArray` function that receives an `int` argument, the compiler is able to compile line 13. The output shows the contents of the three-element `Array` containing 0s.

### *Preventing Implicit Conversions with Single-Argument Constructors*

C++ provides the keyword `explicit` to suppress implicit conversions via conversion constructors when such conversions should not be allowed. A constructor that is declared `explicit` cannot be used in an implicit conversion. Figure 19.14 declares an `explicit` constructor in class `Array`. The only modification to `Array.h` was the addition of the keyword `explicit` to the declaration of the single-argument constructor in line 14. No modifications are required to the source-code file containing class `Array`'s member-function definitions.

```

1 // Fig. 19.14: Array.h
2 // Array class for storing arrays of integers.
3 #ifndef ARRAY_H
4 #define ARRAY_H
5
6 #include <iostream>
7 using namespace std;
8

```

**Fig. 19.14** | `Array` class definition with `explicit` constructor. (Part 1 of 2.)



---

```

9 class Array
10 {
11 friend ostream &operator<<(ostream &, const Array &);
12 friend istream &operator>>(istream &, Array &);
13 public:
14 explicit Array(int = 10); // default constructor
15 Array(const Array &); // copy constructor
16 ~Array(); // destructor
17 int getSize() const; // return size
18
19 const Array &operator=(const Array &); // assignment operator
20 bool operator==(const Array &) const; // equality operator
21
22 // inequality operator; returns opposite of == operator
23 bool operator!=(const Array &right) const
24 {
25 return ! (*this == right); // invokes Array::operator==
26 } // end function operator!=
27
28 // subscript operator for non-const objects returns lvalue
29 int &operator[](int);
30
31 // subscript operator for const objects returns rvalue
32 const int &operator[](int) const;
33 private:
34 int size; // pointer-based array size
35 int *ptr; // pointer to first element of pointer-based array
36 }; // end class Array
37
38 #endif

```

---

**Fig. 19.14** | Array class definition with `explicit` constructor. (Part 2 of 2.)

Figure 19.15 presents a slightly modified version of the program in Fig. 19.13. When this program is compiled, the compiler produces an error message indicating that the integer value passed to `outputArray` in line 13 cannot be converted to a `const Array &`. The compiler error message (from Visual C++) is shown in the output window. Line 14 demonstrates how the `explicit` constructor can be used to create a temporary `Array` of 3 elements and pass it to function `outputArray`.

---

```

1 // Fig. 19.15: Fig19_15.cpp
2 // Driver for simple class Array.
3 #include <iostream>
4 #include "Array.h"
5 using namespace std;
6
7 void outputArray(const Array &); // prototype
8

```

---

**Fig. 19.15** | Demonstrating an `explicit` constructor. (Part 1 of 2.)

```

9 int main()
10 {
11 Array integers1(7); // 7-element array
12 outputArray(integers1); // output Array integers1
13 outputArray(3); // convert 3 to an Array and output Array's contents
14 outputArray(Array(3)); // explicit single-argument constructor call
15 } // end main
16
17 // print array contents
18 void outputArray(const Array &arrayToOutput)
19 {
20 cout << "The Array received has " << arrayToOutput.getSize()
21 << " elements. The contents are:\n" << arrayToOutput << endl;
22 } // end outputArray

```

```

c:\examples\ch19\fig19_14_15\fig19_15.cpp(13) : error C2664:
'outputArray' : cannot convert parameter 1 from 'int' to 'const Array &'
Reason: cannot convert from 'int' to 'const Array'
Constructor for class 'Array' is declared 'explicit'

```

**Fig. 19.15** | Demonstrating an explicit constructor. (Part 2 of 2.)



### Common Programming Error 19.11

*Attempting to invoke an explicit constructor for an implicit conversion is a compilation error.*



### Error-Prevention Tip 19.3

*Use the explicit keyword on single-argument constructors that should not be used by the compiler to perform implicit conversions.*

## 19.16 Proxy Classes

Recall that two of the fundamental principles of good software engineering are separating interface from implementation and hiding implementation details. We strive to achieve these goals by defining a class in a header file and implementing its member functions in a separate implementation file. As we pointed out in Chapter 17, however, header files *do* contain a portion of a class's implementation and hints about others. For example, a class's private members are listed in the class definition in a header file, so these members are visible to clients, even though the clients may not access the private members. Revealing a class's private data in this manner potentially exposes proprietary information to clients of the class. We now introduce the notion of a **proxy class** that allows you to hide even the private data of a class from clients of the class. Providing clients of your class with a proxy class that knows only the public interface to your class enables the clients to use your class's services without giving the clients access to your class's implementation details.

Implementing a proxy class requires several steps, which we demonstrate in Figs. 19.16–19.19. First, we create the class definition for the class that contains the proprietary implementation we'd like to hide. Our example class, called `Implementation`, is

shown in Fig. 19.16. The proxy class `Interface` is shown in Figs. 19.17–19.18. The test program and sample output are shown in Fig. 19.19.

Class `Implementation` (Fig. 19.16) provides a single private data member called `value` (the data we'd like to hide from the client), a constructor to initialize `value` and functions `setValue` and `getValue`.

---

```

1 // Fig. 19.16: Implementation.h
2 // Implementation class definition.
3
4 class Implementation
5 {
6 public:
7 // constructor
8 Implementation(int v)
9 : value(v) // initialize value with v
10 {
11 // empty body
12 } // end constructor Implementation
13
14 // set value to v
15 void setValue(int v)
16 {
17 value = v; // should validate v
18 } // end function setValue
19
20 // return value
21 int getValue() const
22 {
23 return value;
24 } // end function getValue
25 private:
26 int value; // data that we would like to hide from the client
27 }; // end class Implementation

```

---

**Fig. 19.16** | Implementation class definition.

We define a proxy class called `Interface` (Fig. 19.17) with an identical public interface (except for the constructor and destructor names) to that of class `Implementation`. The proxy class's only private member is a pointer to an `Implementation` object. Using a pointer in this manner allows us to hide class `Implementation`'s implementation details from the client. Notice that the only mentions in class `Interface` of the proprietary `Implementation` class are in the pointer declaration (line 17) and in line 6, a **forward class declaration**. When a class definition uses only a pointer or reference to an object of another class (as in this case), the class header file for that other class (which would ordinarily reveal the private data of that class) is not required to be included with `#include`. This is because the compiler doesn't need to reserve space for an object of the class. The compiler does need to reserve space for the pointer or reference. The sizes of pointers and references are characteristics of the hardware platform on which the compiler runs, so the compiler already knows those sizes. You can simply declare that other class as a data type with a forward class declaration (line 6) before the type is used in the file.

---

```

1 // Fig. 19.17: Interface.h
2 // Proxy class Interface definition.
3 // Client sees this source code, but the source code does not reveal
4 // the data layout of class Implementation.
5
6 class Implementation; // forward class declaration required by line 17
7
8 class Interface
9 {
10 public:
11 Interface(int); // constructor
12 void setValue(int); // same public interface as
13 int getValue() const; // class Implementation has
14 ~Interface(); // destructor
15 private:
16 // requires previous forward declaration (line 6)
17 Implementation *ptr;
18 }; // end class Interface

```

---

**Fig. 19.17** | Proxy class `Interface` definition.

The member-function implementation file for proxy class `Interface` (Fig. 19.18) is the only file that includes the header file `Implementation.h` (line 5) containing class `Implementation`. The file `Interface.cpp` (Fig. 19.18) is provided to the client as a pre-compiled object code file along with the header file `Interface.h` that includes the function prototypes of the services provided by the proxy class. Because file `Interface.cpp` is made available to the client only as object code, the client is not able to see the interactions between the proxy class and the proprietary class (lines 9, 17, 23 and 29). The proxy class imposes an extra “layer” of function calls as the “price to pay” for hiding the private data of class `Implementation`. Given the speed of today’s computers and the fact that many compilers can inline simple function calls automatically, the effect of these extra function calls on performance is often negligible.

---

```

1 // Fig. 19.18: Interface.cpp
2 // Implementation of class Interface--client receives this file only
3 // as precompiled object code, keeping the implementation hidden.
4 #include "Interface.h" // Interface class definition
5 #include "Implementation.h" // Implementation class definition
6
7 // constructor
8 Interface::Interface(int v)
9 : ptr (new Implementation(v)) // initialize ptr to point to
10 { // a new Implementation object
11 // empty body
12 } // end Interface constructor
13
14 // call Implementation's setValue function
15 void Interface::setValue(int v)
16 {

```

---

**Fig. 19.18** | Interface class member-function definitions. (Part I of 2.)

```

17 ptr->setValue(v);
18 } // end function setValue
19
20 // call Implementation's getValue function
21 int Interface::getValue() const
22 {
23 return ptr->getValue();
24 } // end function getValue
25
26 // destructor
27 Interface::~Interface()
28 {
29 delete ptr;
30 } // end ~Interface destructor

```

**Fig. 19.18** | Interface class member-function definitions. (Part 2 of 2.)

Figure 19.19 tests class `Interface`. Notice that only the header file for `Interface` is included in the client code (line 4)—there is no mention of the existence of a separate class called `Implementation`. Thus, the client never sees the private data of class `Implementation`, nor can the client code become dependent on the `Implementation` code.



### Software Engineering Observation 19.9

*A proxy class insulates client code from implementation changes.*

```

1 // Fig. 19.19: fig19_19.cpp
2 // Hiding a class's private data with a proxy class.
3 #include <iostream>
4 #include "Interface.h" // Interface class definition
5 using namespace std;
6
7 int main()
8 {
9 Interface i(5); // create Interface object
10
11 cout << "Interface contains: " << i.getValue()
12 << " before setValue" << endl;
13
14 i.setValue(10);
15
16 cout << "Interface contains: " << i.getValue()
17 << " after setValue" << endl;
18 } // end main

```

```

Interface contains: 5 before setValue
Interface contains: 10 after setValue

```

**Fig. 19.19** | Implementing a proxy class.

## 19.17 Wrap-Up

In this chapter, you learned how to build more robust classes by defining overloaded operators that enable you to use operators with objects of your classes. We presented basic operator overloading concepts, as well as several restrictions that the C++ standard places on overloaded operators. You learned reasons for implementing overloaded operators as member functions or as global functions. We discussed the differences between overloading unary and binary operators as member functions and global functions. With global functions, we showed how to input and output objects of our classes using the overloaded stream extraction and stream insertion operators, respectively. We introduced the concept of dynamic memory management. You learned that you can create and destroy objects dynamically with the `new` and `delete` operators, respectively. We showed a special syntax that is required to differentiate between the prefix and postfix versions of the increment (`++`) operator. We also demonstrated standard C++ class `string`, which makes extensive use of overloaded operators to create a robust, reusable class that can replace C-style, pointer-based strings. You learned how to use keyword `explicit` to prevent the compiler from using a single-argument constructor to perform implicit conversions. Finally, we showed how to create a proxy class to hide the implementation details of a class from the class's clients. In the next chapter, we continue our discussion of classes by introducing a form of software reuse called inheritance. We'll see that when classes share common attributes and behaviors, it's possible to define those attributes and behaviors in a common "base" class and "inherit" those capabilities into new class definitions, enabling you to create the new classes with a minimal amount of code.

## Summary

### Section 19.1 Introduction

- C++ enables you to overload most operators to be sensitive to the context in which they're used—the compiler generates the appropriate code based on the context (in particular, the types of the operands).
- Many of C++'s operators can be overloaded to work with user-defined types.
- One example of an overloaded operator built into C++ is operator `<<`, which is used both as the stream insertion operator and as the bitwise left-shift operator. Similarly, `>>` is also overloaded; it's used both as the stream extraction operator and as the bitwise right-shift operator. Both of these operators are overloaded in the C++ Standard Library.
- The C++ language itself overloads `+` and `-`. These operators perform differently, depending on their context in integer arithmetic, floating-point arithmetic and pointer arithmetic.
- The jobs performed by overloaded operators can also be performed by function calls, but operator notation is often clearer and more familiar to programmers.

### Section 19.2 Fundamentals of Operator Overloading

- An operator is overloaded by writing a non-static member-function definition or global function definition in which the function name is the keyword `operator` followed by the symbol for the operator being overloaded.
- When operators are overloaded as member functions, they must be non-static, because they must be called on an object of the class and operate on that object.

- To use an operator on class objects, that operator *must* be overloaded, with three exceptions—the assignment operator (=), the address operator (&) and the comma operator (,).

### Section 19.3 Restrictions on Operator Overloading

- You cannot change the precedence and associativity of an operator by overloading.
- You cannot change the “arity” of an operator (i.e., the number of operands an operator takes).
- You cannot create new operators—only existing operators can be overloaded.
- You cannot change the meaning of how an operator works on objects of fundamental types.
- Overloading an assignment operator and an addition operator for a class does not imply that the += operator is also overloaded. Such behavior can be achieved only by explicitly overloading operator += for that class.

### Section 19.4 Operator Functions as Class Members vs. Global Function

- Operator functions can be member functions or global functions—global functions are often made friends for performance reasons. Member functions use the `this` pointer implicitly to obtain one of their class object arguments (the left operand for binary operators). Arguments for both operands of a binary operator must be explicitly listed in a global function call.
- Overloaded `()`, `[]`, `->` and assignment operators must be declared as class members. For the other operators, the operator overloading functions can be class members or global functions.
- When an operator function is implemented as a member function, the leftmost (or only) operand must be an object (or a reference to an object) of the operator’s class.
- If the left operand must be an object of a different class or a fundamental type, this operator function must be implemented as a global function.
- A global operator function can be made a friend of a class if that function must access private or protected members of that class directly.

### Section 19.5 Overloading Stream Insertion and Stream Extraction Operators

- The overloaded stream insertion operator (`<<`) is used in an expression in which the left operand has type `ostream&`. For this reason, it must be overloaded as a global function. To be a member function, operator `<<` would have to be a member of the `ostream` class, but this is not possible, since we’re not allowed to modify C++ Standard Library classes. Similarly, the overloaded stream extraction operator (`>>`) must be a global function.
- Another reason to choose a global function to overload an operator is to enable the operator to be commutative.
- When used with `cin`, `setw` restricts the number of characters read to the number of characters specified by its argument.
- `istream` member function `ignore` discards the specified number of characters in the input stream (one character by default).
- Overloaded input and output operators are declared as friends if they need to access non-`public` class members directly for performance reasons.

### Section 19.6 Overloading Unary Operators

- A unary operator for a class can be overloaded as a non-static member function with no arguments or as a global function with one argument; that argument must be either an object of the class or a reference to an object of the class.
- Member functions that implement overloaded operators must be non-static so that they can access the non-static data in each object of the class.

### Section 19.7 Overloading Binary Operators

- A binary operator can be overloaded as a non-static member function with one argument or as a global function with two arguments (one of those arguments must be either a class object or a reference to a class object).

### Section 19.8 Dynamic Memory Management

- Dynamic memory management enables you to control the allocation and deallocation of memory in a program for any built-in or user-defined type.
- The free store (sometimes called the heap) is a region of memory assigned to each program for storing objects dynamically allocated at execution time.
- The `new` operator allocates storage of the proper size for an object, runs the object's constructor and returns a pointer of the correct type. The `new` operator can be used to dynamically allocate any fundamental type (such as `int` or `double`) or class type. If `new` is unable to find space in memory for the object, it indicates that an error occurred by "throwing" an "exception." This usually causes the program to terminate immediately, unless the exception is handled.
- To destroy a dynamically allocated object and free its space, use the `delete` operator.
- An array of objects can be allocated dynamically with `new` as in

```
int *ptr = new int[100];
```

which allocates an array of 100 integers and assigns the starting location of the array to `ptr`. The preceding array of integers is deleted with the statement

```
delete [] ptr;
```

### Section 19.9 Case Study: Array Class

- A copy constructor initializes a new object of a class by copying the members of an existing one. Classes that contain dynamically allocated memory, typically provide a copy constructor, a destructor and an overloaded assignment operator.
- The implementation of member function `operator=` should test for self-assignment, in which an object is being assigned to itself.
- The compiler calls the `const` version of `operator[]` when the subscript operator is used on a `const` object and calls the non-`const` version of the operator when it's used on a non-`const` object.
- The array subscript operator (`[]`) can be used to select elements from other types of containers. Also, with overloading, the index values no longer need to be integers.

### Section 19.10 Converting between Types

- The compiler cannot know in advance how to convert among user-defined types, and between user-defined types and fundamental types, so you must specify how to do this. Such conversions can be performed with conversion constructors—single-argument constructors that turn objects of other types (including fundamental types) into objects of a particular class.
- Any single-argument constructor can be thought of as a conversion constructor.
- A conversion operator can be used to convert an object of one class into an object of another class or into an object of a fundamental type. Such a conversion operator must be a non-static member function. Overloaded cast-operator functions can be defined for converting objects of user-defined types into fundamental types or into objects of other user-defined types.
- An overloaded cast operator function does not specify a return type—the return type is the type to which the object is being converted.
- When necessary, the compiler can call cast operators and conversion constructors implicitly to create temporary objects.



**Section 19.11 Building a *String* Class**

- Overloading the function call operator `()` is powerful, because functions can take an arbitrary number of parameters.

**Section 19.12 Overloading *++* and *--***

- The prefix and postfix increment and decrement operator can all be overloaded.
- To overload the pre- and post-increment operators, each overloaded operator function must have a distinct signature. The prefix versions are overloaded like any other unary operator. The postfix increment operator's unique signature is accomplished by providing a second argument, which must be of type `int`. This argument is not supplied in the client code. It's used implicitly by the compiler to distinguish between the prefix and postfix versions of the increment operator. The same syntax is used to differentiate between the prefix and postfix decrement operator functions.

**Section 19.14 Standard Library Class *string***

- Standard class `string` is defined in header `<string>` and belongs to namespace `std`.
- Class `string` provides many overloaded operators, including equality, relational, assignment, addition assignment (for concatenation) and subscript operators.
- Class `string` provides member function `empty`, which returns `true` if the `string` is empty; otherwise, it returns `false`.
- Standard class `string` member function `substr` obtains a substring of a length specified by the second argument, starting at the position specified by the first argument. When the second argument is not specified, `substr` returns the remainder of the `string` on which it's called.
- Class `string`'s overloaded `[]` operator does not perform any bounds checking. Therefore, you must ensure that operations using standard class `string`'s overloaded `[]` operator do not accidentally manipulate elements outside the bounds of the `string`.
- Standard class `string` provides bounds checking with member function `at`, which "throws an exception" if its argument is an invalid subscript. By default, this causes the program to terminate. If the subscript is valid, function `at` returns a reference or a `const` reference to the character at the specified location depending on the context.

**Section 19.15 *explicit* Constructors**

- C++ provides the keyword `explicit` to suppress implicit conversions via conversion constructors when such conversions should not be allowed. A constructor that is declared `explicit` cannot be used in an implicit conversion.

**Section 19.16 Proxy Classes**

- Providing clients of your class with a proxy class that knows only the `public` interface to your class enables the clients to use your class's services without giving the clients access to your class's implementation details, such as its `private` data.
- When a class definition uses only a pointer or reference to an object of another class, the class header file for that other class (which would ordinarily reveal the `private` data of that class) is not required to be included with `#include`. You can simply declare that other class as a data type with a forward class declaration before the type is used in the file.
- The implementation file containing the member functions for a proxy class is the only file that includes the header file for the class whose `private` data we'd like to hide.
- The implementation file containing the member functions for the proxy class is provided to the client as a precompiled object code file along with the header file that includes the function prototypes of the services provided by the proxy class.

## Terminology

- at member function of class string 707
- allocate memory 682
- cast operator function 697
- conversion constructor 696
- conversion operator 696
- copy constructor 691
- dangling pointer 694
- deallocate memory 682
- delete operator 682
- delete[] operator 682
- dynamic memory management 682
- empty member function of string 707
- explicit constructor 709
- forward class declaration 712
- free store 682
- function call operator `()` 698
- heap 682
- initializer 683
- memory leak 683
- new operator 682
- new[] operator 683
- operator overloading 673
- proxy class 711
- self-assignment 694
- single-argument constructor 696
- substr member function of class string 707

## Self-Review Exercises

**19.1** Fill in the blanks in each of the following:

- a) Suppose `a` and `b` are integer variables and we form the sum `a + b`. Now suppose `c` and `d` are floating-point variables and we form the sum `c + d`. The two `+` operators here are clearly being used for different purposes. This is an example of \_\_\_\_\_.
- b) Keyword \_\_\_\_\_ introduces an overloaded-operator function definition.
- c) To use operators on class objects, they must be overloaded, with the exception of operators \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- d) The \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_ of an operator cannot be changed by overloading the operator.
- e) The operators that cannot be overloaded are \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- f) The \_\_\_\_\_ operator reclaims memory previously allocated by `new`.
- g) The \_\_\_\_\_ operator dynamically allocates memory for an object of a specified type and returns a(n) \_\_\_\_\_ to that type.

**19.2** Explain the multiple meanings of the operators `<<` and `>>`.

**19.3** In what context might the name operator/ be used?

**19.4** (True/False) Only existing operators can be overloaded.

**19.5** How does the precedence of an overloaded operator compare with the precedence of the original operator?

## Answers to Self-Review Exercises

**19.1** a) operator overloading. b) operator. c) assignment (`=`), address (`&`), comma (`,`). d) precedence, associativity, “arity.” e) `.`, `?:`, `.*`, and `::`. f) `delete`. g) `new`, pointer.

**19.2** Operator `>>` is both the right-shift operator and the stream extraction operator, depending on its context. Operator `<<` is both the left-shift operator and the stream insertion operator, depending on its context.

**19.3** For operator overloading: It would be the name of a function that would provide an overloaded version of the `/` operator for a specific class.

**19.4** True.

**19.5** The precedence is identical.

## Exercises

**19.6** Compare and contrast dynamic memory allocation and deallocation operators `new`, `new []`, `delete` and `delete []`.

**19.7** (*Overloading the Parentheses Operator*) One nice example of overloading the function call operator `()` is to allow another form of double-array subscripting popular in some programming languages. Instead of saying

```
chessBoard[row][column]
```

for an array of objects, overload the function call operator to allow the alternate form

```
chessBoard(row, column)
```

Create a class `DoubleSubscriptedArray` that has similar features to class `Array` in Figs. 19.6–19.7. At construction time, the class should be able to create an array of any number of rows and any number of columns. The class should supply `operator()` to perform double-subscripting operations. For example, in a 3-by-5 `DoubleSubscriptedArray` called `a`, the user could write `a(1, 3)` to access the element at row 1 and column 3. Remember that `operator()` can receive any number of arguments. The underlying representation of the double-subscripted array should be a single-subscripted array of integers with `rows * columns` number of elements. Function `operator()` should perform the proper pointer arithmetic to access each element of the array. There should be two versions of `operator()`—one that returns `int &` (so that an element of a `DoubleSubscriptedArray` can be used as an *lvalue*) and one that returns `const int &`. The class should also provide the following operators: `==`, `!=`, `=`, `<<` (for outputting the array in row and column format) and `>>` (for inputting the entire array contents).

**19.8** (*Complex Class*) Consider class `Complex` shown in Figs. 19.20–19.22. The class enables operations on so-called *complex numbers*. These are numbers of the form `realPart + imaginaryPart * i`, where *i* has the value

$$\sqrt{-1}$$

- Modify the class to enable input and output of complex numbers via overloaded `>>` and `<<` operators, respectively (you should remove the `print` function from the class).
- Overload the multiplication operator to enable multiplication of two complex numbers as in algebra.
- Overload the `==` and `!=` operators to allow comparisons of complex numbers.

```

1 // Fig. 19.20: Complex.h
2 // Complex class definition.
3 #ifndef COMPLEX_H
4 #define COMPLEX_H
5
6 class Complex
7 {
8 public:
9 Complex(double = 0.0, double = 0.0); // constructor
10 Complex operator+(const Complex &) const; // addition
11 Complex operator-(const Complex &) const; // subtraction
12 void print() const; // output
13 private:
14 double real; // real part
15 double imaginary; // imaginary part
16 }; // end class Complex

```

**Fig. 19.20** | `Complex` class definition. (Part I of 2.)

```

17
18 #endif

```

**Fig. 19.20** | Complex class definition. (Part 2 of 2.)

```

1 // Fig. 19.21: Complex.cpp
2 // Complex class member-function definitions.
3 #include <iostream>
4 #include "Complex.h" // Complex class definition
5 using namespace std;
6
7 // Constructor
8 Complex::Complex(double realPart, double imaginaryPart)
9 : real(realPart),
10 imaginary(imaginaryPart)
11 {
12 // empty body
13 } // end Complex constructor
14
15 // addition operator
16 Complex Complex::operator+(const Complex &operand2) const
17 {
18 return Complex(real + operand2.real,
19 imaginary + operand2.imaginary);
20 } // end function operator+
21
22 // subtraction operator
23 Complex Complex::operator-(const Complex &operand2) const
24 {
25 return Complex(real - operand2.real,
26 imaginary - operand2.imaginary);
27 } // end function operator-
28
29 // display a Complex object in the form: (a, b)
30 void Complex::print() const
31 {
32 cout << '(' << real << ", " << imaginary << ')';
33 } // end function print

```

**Fig. 19.21** | Complex class member-function definitions.

```

1 // Fig. 19.22: fig19_22.cpp
2 // Complex class test program.
3 #include <iostream>
4 #include "Complex.h"
5 using namespace std;
6
7 int main()
8 {
9 Complex x;
10 Complex y(4.3, 8.2);
11 Complex z(3.3, 1.1);
12
13 cout << "x: ";
14 x.print();
15 cout << "\ny: ";

```

**Fig. 19.22** | Complex numbers. (Part 1 of 2.)

```

16 y.print();
17 cout << "\nz: ";
18 z.print();
19
20 x = y + z;
21 cout << "\n\nx = y + z:" << endl;
22 x.print();
23 cout << " = ";
24 y.print();
25 cout << " + ";
26 z.print();
27
28 x = y - z;
29 cout << "\n\nx = y - z:" << endl;
30 x.print();
31 cout << " = ";
32 y.print();
33 cout << " - ";
34 z.print();
35 cout << endl;
36 } // end main

```

```

x: (0, 0)
y: (4.3, 8.2)
z: (3.3, 1.1)

x = y + z:
(7.6, 9.3) = (4.3, 8.2) + (3.3, 1.1)

x = y - z:
(1, 7.1) = (4.3, 8.2) - (3.3, 1.1)

```

**Fig. 19.22** | Complex numbers. (Part 2 of 2.)

**19.9 (HugeInt Class)** A machine with 32-bit integers can represent integers in the range of approximately  $-2$  billion to  $+2$  billion. This fixed-size restriction is rarely troublesome, but there are applications in which we'd like to be able to use a much wider range of integers. This is what C++ was built to do, namely, create powerful new data types. Consider class `HugeInt` of Figs. 19.23–19.25. Study the class carefully, then answer the following:

- Describe precisely how it operates.
- What restrictions does the class have?
- Overload the `*` multiplication operator.
- Overload the `/` division operator.
- Overload all the relational and equality operators.

[*Note:* We do not show an assignment operator or copy constructor for class `HugeInteger`, because the assignment operator and copy constructor provided by the compiler are capable of copying the entire array data member properly.]

```

1 // Fig. 19.23: Hugeint.h
2 // HugeInt class definition.
3 #ifndef HUGEINT_H
4 #define HUGEINT_H
5
6 #include <iostream>
7 #include <string>

```

**Fig. 19.23** | `HugeInt` class definition. (Part 1 of 2.)

```

8 using namespace std;
9
10 class HugeInt
11 {
12 friend ostream &operator<<(ostream &, const HugeInt &);
13 public:
14 static const int digits = 30; // maximum digits in a HugeInt
15
16 HugeInt(long = 0); // conversion/default constructor
17 HugeInt(const string &); // conversion constructor
18
19 // addition operator; HugeInt + HugeInt
20 HugeInt operator+(const HugeInt &) const;
21
22 // addition operator; HugeInt + int
23 HugeInt operator+(int) const;
24
25 // addition operator;
26 // HugeInt + string that represents large integer value
27 HugeInt operator+(const string &) const;
28 private:
29 short integer[digits];
30 }; // end class HugeInt
31
32 #endif

```

**Fig. 19.23** | HugeInt class definition. (Part 2 of 2.)

```

1 // Fig. 19.24: Hugeint.cpp
2 // HugeInt member-function and friend-function definitions.
3 #include <cctype> // isdigit function prototype
4 #include "Hugeint.h" // HugeInt class definition
5 using namespace std;
6
7 // default constructor; conversion constructor that converts
8 // a long integer into a HugeInt object
9 HugeInt::HugeInt(long value)
10 {
11 // initialize array to zero
12 for (int i = 0; i < digits; i++)
13 integer[i] = 0;
14
15 // place digits of argument into array
16 for (int j = digits - 1; value != 0 && j >= 0; j--)
17 {
18 integer[j] = value % 10;
19 value /= 10;
20 } // end for
21 } // end HugeInt default/conversion constructor
22
23 // conversion constructor that converts a character string
24 // representing a large integer into a HugeInt object
25 HugeInt::HugeInt(const string &number)
26 {
27 // initialize array to zero
28 for (int i = 0; i < digits; i++)
29 integer[i] = 0;

```

**Fig. 19.24** | HugeInt class member-function and friend-function definitions. (Part 1 of 3.)

```

30 // place digits of argument into array
31 int length = number.size();
32
33 for (int j = digits - length, k = 0; j < digits; j++, k++)
34 if (isdigit(number[k])) // ensure that character is a digit
35 integer[j] = number[k] - '0';
36 } // end HugeInt conversion constructor
37
38 // addition operator; HugeInt + HugeInt
39 HugeInt HugeInt::operator+(const HugeInt &op2) const
40 {
41 HugeInt temp; // temporary result
42 int carry = 0;
43
44 for (int i = digits - 1; i >= 0; i--)
45 {
46 temp.integer[i] = integer[i] + op2.integer[i] + carry;
47
48 // determine whether to carry a 1
49 if (temp.integer[i] > 9)
50 {
51 temp.integer[i] %= 10; // reduce to 0-9
52 carry = 1;
53 } // end if
54 else // no carry
55 carry = 0;
56 } // end for
57
58 return temp; // return copy of temporary object
59 } // end function operator+
60
61 // addition operator; HugeInt + int
62 HugeInt HugeInt::operator+(int op2) const
63 {
64 // convert op2 to a HugeInt, then invoke
65 // operator+ for two HugeInt objects
66 return *this + HugeInt(op2);
67 } // end function operator+
68
69 // addition operator;
70 // HugeInt + string that represents large integer value
71 HugeInt HugeInt::operator+(const string &op2) const
72 {
73 // convert op2 to a HugeInt, then invoke
74 // operator+ for two HugeInt objects
75 return *this + HugeInt(op2);
76 } // end operator+
77
78 // overloaded output operator
79 ostream& operator<<(ostream &output, const HugeInt &num)
80 {
81 int i;
82
83 for (i = 0; (num.integer[i] == 0) && (i <= HugeInt::digits); i++)
84 ; // skip leading zeros
85
86 if (i == HugeInt::digits)
87 output << 0;
88

```

**Fig. 19.24** | HugeInt class member-function and friend-function definitions. (Part 2 of 3.)

```

89 else
90 for (; i < HugeInt::digits; i++)
91 output << num.integer[i];
92
93 return output;
94 } // end function operator<<

```

**Fig. 19.24** | HugeInt class member-function and friend-function definitions. (Part 3 of 3.)

[illegible][illegible]

**Fig. 19.25** | Huge integers.

**19.10 (RationalNumber Class)** Create a class `RationalNumber` (fractions) with the following capabilities:

- a) Create a constructor that prevents a 0 denominator in a fraction, reduces or simplifies fractions that are not in reduced form and avoids negative denominators.



- b) Overload the addition, subtraction, multiplication and division operators for this class.
- c) Overload the relational and equality operators for this class.

**19.11 (Polynomial Class)** Develop class `Polynomial`. The internal representation of a `Polynomial` is an array of terms. Each term contains a coefficient and an exponent, e.g., the term

$$2x^4$$

has the coefficient 2 and the exponent 4. Develop a complete class containing proper constructor and destructor functions as well as *set* and *get* functions. The class should also provide the following overloaded operator capabilities:

- a) Overload the addition operator (+) to add two `Polynomial`s.
- b) Overload the subtraction operator (-) to subtract two `Polynomial`s.
- c) Overload the assignment operator to assign one `Polynomial` to another.
- d) Overload the multiplication operator (\*) to multiply two `Polynomial`s.
- e) Overload the addition assignment operator (+=), subtraction assignment operator (-=), and multiplication assignment operator (\*=).

# Object-Oriented Programming: Inheritance

# 20

*Say not you know another entirely, till you have divided an inheritance with him.*

—Johann Kasper Lavater

*This method is to define as the number of a class the class of all classes similar to the given class.*

—Bertrand Russell

*Good as it is to inherit a library, it is better to collect one.*

—Augustine Birrell

*Save base authority from others' books.*

—William Shakespeare

## Objectives

In this chapter you'll learn:

- To create classes by inheriting from existing classes.
- The notions of base classes and derived classes and the relationships between them.
- The **protected** member access specifier.
- The use of constructors and destructors in inheritance hierarchies.
- The order in which constructors and destructors are called in inheritance hierarchies.
- The differences between **public**, **protected** and **private** inheritance.
- To use inheritance to customize existing software.

|             |                                                                                       |             |                                                                                                           |
|-------------|---------------------------------------------------------------------------------------|-------------|-----------------------------------------------------------------------------------------------------------|
| <b>20.1</b> | Introduction                                                                          | 20.4.4      | CommissionEmployee–<br>BasePlusCommissionEmployee<br>Inheritance Hierarchy Using<br><b>protected</b> Data |
| <b>20.2</b> | Base Classes and Derived Classes                                                      | 20.4.5      | CommissionEmployee–<br>BasePlusCommissionEmployee<br>Inheritance Hierarchy Using <b>private</b><br>Data   |
| <b>20.3</b> | <b>protected</b> Members                                                              | <b>20.5</b> | Constructors and Destructors in<br>Derived Classes                                                        |
| <b>20.4</b> | Relationship between Base Classes<br>and Derived Classes                              | <b>20.6</b> | <b>public</b> , <b>protected</b> and <b>private</b><br>Inheritance                                        |
| 20.4.1      | Creating and Using a<br>CommissionEmployee Class                                      | <b>20.7</b> | Software Engineering with Inheritance                                                                     |
| 20.4.2      | Creating a<br>BasePlusCommissionEmployee<br>Class Without Using Inheritance           | <b>20.8</b> | Wrap-Up                                                                                                   |
| 20.4.3      | Creating a CommissionEmployee–<br>BasePlusCommissionEmployee<br>Inheritance Hierarchy |             |                                                                                                           |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 20.1 Introduction

This chapter continues our discussion of object-oriented programming (OOP) by introducing another of its key features—**inheritance**. Inheritance is a form of software reuse in which you create a class that absorbs an existing class’s data and behaviors and enhances them with new capabilities. Software reusability saves time during program development. It also encourages the reuse of proven, debugged, high-quality software, which increases the likelihood that a system will be implemented effectively.

When creating a class, instead of writing completely new data members and member functions, you can designate that the new class should **inherit** the members of an existing class. This existing class is called the **base class**, and the new class is referred to as the **derived class**. (Other programming languages, such as Java, refer to the base class as the **superclass** and the derived class as the **subclass**.) A derived class represents a more specialized group of objects. Typically, a derived class contains behaviors inherited from its base class plus additional behaviors. As we’ll see, a derived class can also customize behaviors inherited from the base class. A **direct base class** is the base class from which a derived class explicitly inherits. An **indirect base class** is inherited from two or more levels up in the **class hierarchy**. In the case of **single inheritance**, a class is derived from one base class. C++ also supports **multiple inheritance**, in which a derived class inherits from multiple (possibly unrelated) base classes. Single inheritance is straightforward—we show several examples that should enable you to become proficient quickly. Multiple inheritance can be complex and error prone.

C++ offers **public**, **protected** and **private** inheritance. In this chapter, we concentrate on **public** inheritance and briefly explain the other two. We do not discuss **private** inheritance in detail. The third form, **protected** inheritance, is rarely used. With **public** inheritance, every object of a derived class is also an object of that derived class’s base class. However, base-class objects are not objects of their derived classes. For example, if we have **vehicle** as a base class and **car** as a derived class, then all cars are vehicles, but not all vehicles are cars. As we continue our study of object-oriented programming in this chapter and

Chapter 21, we take advantage of this relationship to perform some interesting manipulations.

Experience in building software systems indicates that significant amounts of code deal with closely related special cases. When you're preoccupied with special cases, the details can obscure the big picture. With object-oriented programming, you focus on the commonalities among objects in the system rather than on the special cases.

We distinguish between the *is-a relationship* and the *has-a relationship*. The *is-a* relationship represents inheritance. In an *is-a* relationship, an object of a derived class also can be treated as an object of its base class—for example, a car *is a* vehicle, so any attributes and behaviors of a vehicle are also attributes and behaviors of a car. By contrast, the *has-a* relationship represents composition. (Composition was discussed in Chapter 18.) In a *has-a* relationship, an object contains one or more objects of other classes as members. For example, a car includes many components—it *has a* steering wheel, *has a* brake pedal, *has a* transmission and *has* many other components.

Derived-class member functions might require access to base-class data members and member functions. A derived class can access the non-private members of its base class. Base-class members that should not be accessible to the member functions of derived classes should be declared `private` in the base class. A derived class *can* change the values of `private` base-class members, but only through non-private member functions provided in the base class and inherited into the derived class.



#### Software Engineering Observation 20.1

*Member functions of a derived class cannot directly access private members of the base class.*



#### Software Engineering Observation 20.2

*If a derived class could access its base class's private members, classes that inherit from that derived class could access that data as well. This would propagate access to what should be private data, and the benefits of information hiding would be lost.*

One problem with inheritance is that a derived class can inherit data members and member functions it does not need or should not have. It's the class designer's responsibility to ensure that the capabilities provided by a class are appropriate for future derived classes. Even when a base-class member function is appropriate for a derived class, the derived class often requires that the member function behave in a manner specific to the derived class. In such cases, the base-class member function can be redefined in the derived class with an appropriate implementation.

## 20.2 Base Classes and Derived Classes

Often, an object of one class *is an* object of another class, as well. For example, in geometry, a rectangle *is a* quadrilateral (as are squares, parallelograms and trapezoids). Thus, in C++, class `Rectangle` can be said to *inherit* from class `Quadrilateral`. In this context, class `Quadrilateral` is a base class, and class `Rectangle` is a derived class. A rectangle *is a* specific type of quadrilateral, but it's incorrect to claim that a quadrilateral *is a* rectangle—the quadrilateral could be a parallelogram or some other shape. Figure 20.1 lists several simple examples of base classes and derived classes.

| Base class | Derived classes                            |
|------------|--------------------------------------------|
| Student    | GraduateStudent, UndergraduateStudent      |
| Shape      | Circle, Triangle, Rectangle, Sphere, Cube  |
| Loan       | CarLoan, HomeImprovementLoan, MortgageLoan |
| Employee   | Faculty, Staff                             |
| Account    | CheckingAccount, SavingsAccount            |

Fig. 20.1 | Inheritance examples.

Because every derived-class object *is an* object of its base class, and one base class can have many derived classes, the set of objects represented by a base class typically is larger than the set of objects represented by any of its derived classes. For example, the base class `Vehicle` represents all vehicles, including cars, trucks, boats, airplanes, bicycles and so on. By contrast, derived class `Car` represents a smaller, more specific subset of all vehicles.

Inheritance relationships form treelike hierarchical structures. A base class exists in a hierarchical relationship with its derived classes. Although classes can exist independently, once they’re employed in inheritance relationships, they become affiliated with other classes. A class becomes either a base class—supplying members to other classes, a derived class—inheriting its members from other classes, or both.

Let’s develop a simple inheritance hierarchy with five levels (represented by the UML class diagram in Fig. 20.2). A university community has thousands of members.




Fig. 20.2 | Inheritance hierarchy for university `CommunityMembers`.

These members consist of employees, students and alumni. Employees are either faculty members or staff members. Faculty members are either administrators (such as deans and department chairpersons) or teachers. Some administrators, however, also teach

classes. Note that we've used multiple inheritance to form class `AdministratorTeacher`. Also, this inheritance hierarchy could contain many other classes. For example, students can be graduate or undergraduate students. Undergraduate students can be freshmen, sophomores, juniors and seniors.


Each arrow in the hierarchy (Fig. 20.2) represents an *is-a* relationship. For example, as we follow the arrows in this class hierarchy, we can state “an `Employee` *is a* `CommunityMember`” and “a `Teacher` *is a* `Faculty member`.” `CommunityMember` is the direct base class of `Employee`, `Student` and `Alumnus`. In addition, `CommunityMember` is an indirect base class of all the other classes in the diagram. Starting from the bottom of the diagram, you can follow the arrows and apply the *is-a* relationship to the topmost base class. For example, an `AdministratorTeacher` *is an* `Administrator`, *is a* `Faculty member`, *is an* `Employee` and *is a* `CommunityMember`.

Now consider the `Shape` inheritance hierarchy in Fig. 20.3. This hierarchy begins with base class `Shape`. Classes `TwoDimensionalShape` and `ThreeDimensionalShape` derive from base class `Shape`—Shapes are either `TwoDimensionalShapes` or `ThreeDimensionalShapes`. The third level of this hierarchy contains some more specific types of `TwoDimensionalShapes` and `ThreeDimensionalShapes`. As in Fig. 20.2, we can follow the arrows from the bottom of the diagram to the topmost base class in this class hierarchy to identify several *is-a* relationships. For instance, a `Triangle` *is a* `TwoDimensionalShape` and *is a* `Shape`, while a `Sphere` *is a* `ThreeDimensionalShape` and *is a* `Shape`. This hierarchy could contain many other classes, such as `Rectangles`, `Ellipses` and `Trapezoids`, which are all `TwoDimensionalShapes`.

To specify that class `TwoDimensionalShape` (Fig. 20.3) is derived from (or inherits from) class `Shape`, class `TwoDimensionalShape`'s definition could begin as follows:

```
class TwoDimensionalShape : public Shape
```

This is an example of **public inheritance**, the most commonly used form. We also will discuss **private inheritance** and **protected inheritance** (Section 20.6). With all forms of inheritance, private members of a base class are not accessible directly from that class's derived classes, but these private base-class members are still inherited (i.e., they're still considered parts of the derived classes). With **public inheritance**, all other base-class members retain their original member access when they become members of the derived class (e.g., **public** members of the base class become **public** members of the derived class, and, as we'll soon see, **protected** members of the base class become **protected** members of the



**Fig. 20.3** | Inheritance hierarchy for Shapes.



derived class). Through these inherited base-class members, the derived class can manipulate private members of the base class (if these inherited members provide such functionality in the base class). Note that `friend` functions are not inherited.

Inheritance is not appropriate for every class relationship. In Chapter 18, we discussed the *has-a* relationship, in which classes have members that are objects of other classes. Such relationships create classes by composition of existing classes. For example, given the classes `Employee`, `BirthDate` and `TelephoneNumber`, it's improper to say that an `Employee` *is a* `BirthDate` or that an `Employee` *is a* `TelephoneNumber`. However, it's appropriate to say that an `Employee` *has a* `BirthDate` and that an `Employee` *has a* `TelephoneNumber`.

It's possible to treat base-class objects and derived-class objects similarly; their commonalities are expressed in the members of the base class. Objects of all classes derived from a common base class can be treated as objects of that base class (i.e., such objects have an *is-a* relationship with the base class). In Chapter 21, we consider many examples that take advantage of this relationship.

## 20.3 protected Members

Chapter 16 introduced access specifiers `public` and `private`. A base class's `public` members are accessible within its body and anywhere that the program has a handle (i.e., a name, reference or pointer) to an object of that class or one of its derived classes. A base class's `private` members are accessible only within its body and to the `friends` of that base class. In this section, we introduce the access specifier `protected`.

Using `protected` access offers an intermediate level of protection between `public` and `private` access. A base class's `protected` members can be accessed within the body of that base class, by members and `friends` of that base class, and by members and `friends` of any classes derived from that base class.

Derived-class member functions can refer to `public` and `protected` members of the base class simply by using the member names. When a derived-class member function redefines a base-class member function, the base-class member can be accessed from the derived class by preceding the base-class member name with the base-class name and the binary scope resolution operator (`::`). We discuss accessing redefined members of the base class in Section 20.4.5 and using `protected` data in Section 20.4.4.

## 20.4 Relationship between Base Classes and Derived Classes

In this section, we use an inheritance hierarchy containing types of employees in a company's payroll application to discuss the relationship between a base class and a derived class. Commission employees (who will be represented as objects of a base class) are paid a percentage of their sales, while base-salaried commission employees (who will be represented as objects of a derived class) receive a base salary plus a percentage of their sales. We divide our discussion of the relationship between commission employees and base-salaried commission employees into a carefully paced series of five examples:

1. In the first example, we create class `CommissionEmployee`, which contains as `private` data members a first name, last name, social security number, commission rate (percentage) and gross (i.e., total) sales amount.

2. The second example defines class `BasePlusCommissionEmployee`, which contains as private data members a first name, last name, social security number, commission rate, gross sales amount and base salary. We create the latter class by writing every line of code the class requires—we'll soon see that it's much more efficient to create this class simply by inheriting from class `CommissionEmployee`.
3. The third example defines a new version of class `BasePlusCommissionEmployee` class that inherits directly from class `CommissionEmployee` (i.e., a `BasePlusCommissionEmployee` *is a* `CommissionEmployee` who also has a base salary) and attempts to access class `CommissionEmployee`'s private members—this results in compilation errors, because the derived class does not have access to the base class's private data.
4. The fourth example shows that if `CommissionEmployee`'s data is declared as protected, a new version of class `BasePlusCommissionEmployee` that inherits from class `CommissionEmployee` *can* access that data directly. For this purpose, we define a new version of class `CommissionEmployee` with protected data. Both the inherited and noninherited `BasePlusCommissionEmployee` classes contain identical functionality, but we show how the version of `BasePlusCommissionEmployee` that inherits from class `CommissionEmployee` is easier to create and manage.
5. After we discuss the convenience of using protected data, we create the fifth example, which sets the `CommissionEmployee` data members back to private to enforce good software engineering. This example demonstrates that derived class `BasePlusCommissionEmployee` can use base class `CommissionEmployee`'s public member functions to manipulate `CommissionEmployee`'s private data.

### 20.4.1 Creating and Using a `CommissionEmployee` Class

Let's examine `CommissionEmployee`'s class definition (Figs. 20.4–20.5). The `CommissionEmployee` header file (Fig. 20.4) specifies class `CommissionEmployee`'s public services, which include a constructor (lines 12–13) and member functions `earnings` (line 30) and `print` (line 31). Lines 15–28 declare public *get* and *set* functions that manipulate the class's data members (declared in lines 33–37) `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate`. The `CommissionEmployee` header file specifies that these data members are private, so objects of other classes cannot directly access this data. Declaring data members as private and providing non-private *get* and *set* functions to manipulate and validate the data members helps enforce good software engineering. Member functions `setGrossSales` (defined in lines 56–59 of Fig. 20.5) and `setCommissionRate` (defined in lines 68–71 of Fig. 20.5), for example, validate their arguments before assigning the values to data members `grossSales` and `commissionRate`, respectively.

---

```

1 // Fig. 20.4: CommissionEmployee.h
2 // CommissionEmployee class definition represents a commission employee.
3 #ifndef COMMISSION_H
4 #define COMMISSION_H
5
```

---

**Fig. 20.4** | `CommissionEmployee` class header file. (Part I of 2.)



---

```

6 #include <string> // C++ standard string class
7 using namespace std;
8
9 class CommissionEmployee
10 {
11 public:
12 CommissionEmployee(const string &, const string &, const string &,
13 double = 0.0, double = 0.0);
14
15 void setFirstName(const string &); // set first name
16 string getFirstName() const; // return first name
17
18 void setLastName(const string &); // set last name
19 string getLastName() const; // return last name
20
21 void setSocialSecurityNumber(const string &); // set SSN
22 string getSocialSecurityNumber() const; // return SSN
23
24 void setGrossSales(double); // set gross sales amount
25 double getGrossSales() const; // return gross sales amount
26
27 void setCommissionRate(double); // set commission rate (percentage)
28 double getCommissionRate() const; // return commission rate
29
30 double earnings() const; // calculate earnings
31 void print() const; // print CommissionEmployee object
32 private:
33 string firstName;
34 string lastName;
35 string socialSecurityNumber;
36 double grossSales; // gross weekly sales
37 double commissionRate; // commission percentage
38 }; // end class CommissionEmployee
39
40 #endif

```

---

**Fig. 20.4** | CommissionEmployee class header file. (Part 2 of 2.)

---

```

1 // Fig. 20.5: CommissionEmployee.cpp
2 // Class CommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "CommissionEmployee.h" // CommissionEmployee class definition
5 using namespace std;
6
7 // constructor
8 CommissionEmployee::CommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate)
11 {
12 firstName = first; // should validate

```

---

**Fig. 20.5** | Implementation file for CommissionEmployee class that represents an employee who is paid a percentage of gross sales. (Part 1 of 3.)

```

13 lastName = last; // should validate
14 socialSecurityNumber = ssn; // should validate
15 setGrossSales(sales); // validate and store gross sales
16 setCommissionRate(rate); // validate and store commission rate
17 } // end CommissionEmployee constructor
18
19 // set first name
20 void CommissionEmployee::setFirstName(const string &first)
21 {
22 firstName = first; // should validate
23 } // end function setFirstName
24
25 // return first name
26 string CommissionEmployee::getFirstName() const
27 {
28 return firstName;
29 } // end function getFirstName
30
31 // set last name
32 void CommissionEmployee::setLastName(const string &last)
33 {
34 lastName = last; // should validate
35 } // end function setLastName
36
37 // return last name
38 string CommissionEmployee::getLastName() const
39 {
40 return lastName;
41 } // end function getLastName
42
43 // set social security number
44 void CommissionEmployee::setSocialSecurityNumber(const string &ssn)
45 {
46 socialSecurityNumber = ssn; // should validate
47 } // end function setSocialSecurityNumber
48
49 // return social security number
50 string CommissionEmployee::getSocialSecurityNumber() const
51 {
52 return socialSecurityNumber;
53 } // end function getSocialSecurityNumber
54
55 // set gross sales amount
56 void CommissionEmployee::setGrossSales(double sales)
57 {
58 grossSales = (sales < 0.0) ? 0.0 : sales;
59 } // end function setGrossSales
60
61 // return gross sales amount
62 double CommissionEmployee::getGrossSales() const
63 {

```

**Fig. 20.5** | Implementation file for `CommissionEmployee` class that represents an employee who is paid a percentage of gross sales. (Part 2 of 3.)

---

```

64 return grossSales;
65 } // end function getGrossSales
66
67 // set commission rate
68 void CommissionEmployee::setCommissionRate(double rate)
69 {
70 commissionRate = (rate > 0.0 && rate < 1.0) ? rate : 0.0;
71 } // end function setCommissionRate
72
73 // return commission rate
74 double CommissionEmployee::getCommissionRate() const
75 {
76 return commissionRate;
77 } // end function getCommissionRate
78
79 // calculate earnings
80 double CommissionEmployee::earnings() const
81 {
82 return commissionRate * grossSales;
83 } // end function earnings
84
85 // print CommissionEmployee object
86 void CommissionEmployee::print() const
87 {
88 cout << "commission employee: " << firstName << ' ' << lastName
89 << "\nsocial security number: " << socialSecurityNumber
90 << "\ngross sales: " << grossSales
91 << "\ncommission rate: " << commissionRate;
92 } // end function print

```

---

**Fig. 20.5** | Implementation file for `CommissionEmployee` class that represents an employee who is paid a percentage of gross sales. (Part 3 of 3.)

The `CommissionEmployee` constructor definition purposely does not use member-initializer syntax in the first several examples of this section, so that we can demonstrate how private and protected specifiers affect member access in derived classes. As shown in Fig. 20.5, lines 12–14, we assign values to data members `firstName`, `lastName` and `socialSecurityNumber` in the constructor body. Later in this section, we'll return to using member-initializer lists in the constructors.

We do not validate the values of the constructor's arguments `first`, `last` and `ssn` before assigning them to the corresponding data members. We certainly could validate the first and last names—perhaps by ensuring that they're of a reasonable length. Similarly, a social security number could be validated to ensure that it contains nine digits, with or without dashes (e.g., 123-45-6789 or 123456789).

Member function `earnings` (lines 80–83) calculates a `CommissionEmployee`'s earnings. Line 82 multiplies the `commissionRate` by the `grossSales` and returns the result. Member function `print` (lines 86–92) displays the values of a `CommissionEmployee` object's data members.

Figure 20.6 tests class `CommissionEmployee`. Lines 11–12 instantiate object `employee` of class `CommissionEmployee` and invoke `CommissionEmployee`'s constructor to initialize the object with "Sue" as the first name, "Jones" as the last name, "222-22-2222" as the

```

1 // Fig. 20.6: fig20_06.cpp
2 // Testing class CommissionEmployee.
3 #include <iostream>
4 #include <iomanip>
5 #include "CommissionEmployee.h" // CommissionEmployee class definition
6 using namespace std;
7
8 int main()
9 {
10 // instantiate a CommissionEmployee object
11 CommissionEmployee employee(
12 "Sue", "Jones", "222-22-2222", 10000, .06);
13
14 // set floating-point output formatting
15 cout << fixed << setprecision(2);
16
17 // get commission employee data
18 cout << "Employee information obtained by get functions: \n"
19 << "\nFirst name is " << employee.getFirstName()
20 << "\nLast name is " << employee.getLastName()
21 << "\nSocial security number is "
22 << employee.getSocialSecurityNumber()
23 << "\nGross sales is " << employee.getGrossSales()
24 << "\nCommission rate is " << employee.getCommissionRate() << endl;
25
26 employee.setGrossSales(8000); // set gross sales
27 employee.setCommissionRate(.1); // set commission rate
28
29 cout << "\nUpdated employee information output by print function: \n"
30 << endl;
31 employee.print(); // display the new employee information
32
33 // display the employee's earnings
34 cout << "\n\nEmployee's earnings: $" << employee.earnings() << endl;
35 } // end main

```

Employee information obtained by get functions:

First name is Sue  
 Last name is Jones  
 Social security number is 222-22-2222  
 Gross sales is 10000.00  
 Commission rate is 0.06

Updated employee information output by print function:

commission employee: Sue Jones  
 social security number: 222-22-2222  
 gross sales: 8000.00  
 commission rate: 0.10

Employee's earnings: \$800.00

**Fig. 20.6** | CommissionEmployee class test program.

social security number, 10000 as the gross sales amount and .06 as the commission rate. Lines 19–24 use `employee`'s *get* functions to display the values of its data members. Lines 26–27 invoke the object's member functions `setGrossSales` and `setCommissionRate` to change the values of data members `grossSales` and `commissionRate`, respectively. Line 31 then calls `employee`'s `print` member function to output the updated `CommissionEmployee` information. Finally, line 34 displays the `CommissionEmployee`'s earnings, calculated by the object's `earnings` member function using the updated values of data members `grossSales` and `commissionRate`.

### 20.4.2 Creating a `BasePlusCommissionEmployee` Class Without Using Inheritance

We now discuss the second part of our introduction to inheritance by creating and testing (a completely new and independent) class `BasePlusCommissionEmployee` (Figs. 20.7–20.8), which contains a first name, last name, social security number, gross sales amount, commission rate *and* base salary.

---

```

1 // Fig. 20.7: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class definition represents an employee
3 // that receives a base salary in addition to commission.
4 #ifndef BASEPLUS_H
5 #define BASEPLUS_H
6
7 #include <string> // C++ standard string class
8 using namespace std;
9
10 class BasePlusCommissionEmployee
11 {
12 public:
13 BasePlusCommissionEmployee(const string &, const string &,
14 const string &, double = 0.0, double = 0.0, double = 0.0);
15
16 void setFirstName(const string &); // set first name
17 string getFirstName() const; // return first name
18
19 void setLastName(const string &); // set last name
20 string getLastName() const; // return last name
21
22 void setSocialSecurityNumber(const string &); // set SSN
23 string getSocialSecurityNumber() const; // return SSN
24
25 void setGrossSales(double); // set gross sales amount
26 double getGrossSales() const; // return gross sales amount
27
28 void setCommissionRate(double); // set commission rate
29 double getCommissionRate() const; // return commission rate
30
31 void setBaseSalary(double); // set base salary
32 double getBaseSalary() const; // return base salary
33

```

---

**Fig. 20.7** | `BasePlusCommissionEmployee` class header file. (Part 1 of 2.)

---

```

34 double earnings() const; // calculate earnings
35 void print() const; // print BasePlusCommissionEmployee object
36 private:
37 string firstName;
38 string lastName;
39 string socialSecurityNumber;
40 double grossSales; // gross weekly sales
41 double commissionRate; // commission percentage
42 double baseSalary; // base salary
43 }; // end class BasePlusCommissionEmployee
44
45 #endif

```

---

**Fig. 20.7** | BasePlusCommissionEmployee class header file. (Part 2 of 2.)

---

```

1 // Fig. 20.8: BasePlusCommissionEmployee.cpp
2 // Class BasePlusCommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "BasePlusCommissionEmployee.h"
5 using namespace std;
6
7 // constructor
8 BasePlusCommissionEmployee::BasePlusCommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate, double salary)
11 {
12 firstName = first; // should validate
13 lastName = last; // should validate
14 socialSecurityNumber = ssn; // should validate
15 setGrossSales(sales); // validate and store gross sales
16 setCommissionRate(rate); // validate and store commission rate
17 setBaseSalary(salary); // validate and store base salary
18 } // end BasePlusCommissionEmployee constructor
19
20 // set first name
21 void BasePlusCommissionEmployee::setFirstName(const string &first)
22 {
23 firstName = first; // should validate
24 } // end function setFirstName
25
26 // return first name
27 string BasePlusCommissionEmployee::getFirstName() const
28 {
29 return firstName;
30 } // end function getFirstName
31
32 // set last name
33 void BasePlusCommissionEmployee::setLastName(const string &last)
34 {
35 lastName = last; // should validate
36 } // end function setLastName

```

---

**Fig. 20.8** | BasePlusCommissionEmployee class represents an employee who receives a base salary in addition to a commission. (Part 1 of 3.)

---

```

37
38 // return last name
39 string BasePlusCommissionEmployee::getLastName() const
40 {
41 return lastName;
42 } // end function getLastName
43
44 // set social security number
45 void BasePlusCommissionEmployee::setSocialSecurityNumber(
46 const string &ssn)
47 {
48 socialSecurityNumber = ssn; // should validate
49 } // end function setSocialSecurityNumber
50
51 // return social security number
52 string BasePlusCommissionEmployee::getSocialSecurityNumber() const
53 {
54 return socialSecurityNumber;
55 } // end function getSocialSecurityNumber
56
57 // set gross sales amount
58 void BasePlusCommissionEmployee::setGrossSales(double sales)
59 {
60 grossSales = (sales < 0.0) ? 0.0 : sales;
61 } // end function setGrossSales
62
63 // return gross sales amount
64 double BasePlusCommissionEmployee::getGrossSales() const
65 {
66 return grossSales;
67 } // end function getGrossSales
68
69 // set commission rate
70 void BasePlusCommissionEmployee::setCommissionRate(double rate)
71 {
72 commissionRate = (rate > 0.0 && rate < 1.0) ? rate : 0.0;
73 } // end function setCommissionRate
74
75 // return commission rate
76 double BasePlusCommissionEmployee::getCommissionRate() const
77 {
78 return commissionRate;
79 } // end function getCommissionRate
80
81 // set base salary
82 void BasePlusCommissionEmployee::setBaseSalary(double salary)
83 {
84 baseSalary = (salary < 0.0) ? 0.0 : salary;
85 } // end function setBaseSalary
86

```

---

**Fig. 20.8** | BasePlusCommissionEmployee class represents an employee who receives a base salary in addition to a commission. (Part 2 of 3.)

---

```

87 // return base salary
88 double BasePlusCommissionEmployee::getBaseSalary() const
89 {
90 return baseSalary;
91 } // end function getBaseSalary
92
93 // calculate earnings
94 double BasePlusCommissionEmployee::earnings() const
95 {
96 return baseSalary + (commissionRate * grossSales);
97 } // end function earnings
98
99 // print BasePlusCommissionEmployee object
100 void BasePlusCommissionEmployee::print() const
101 {
102 cout << "base-salaried commission employee: " << firstName << ' '
103 << lastName << "\nsocial security number: " << socialSecurityNumber
104 << "\ngross sales: " << grossSales
105 << "\ncommission rate: " << commissionRate
106 << "\nbase salary: " << baseSalary;
107 } // end function print

```

---

**Fig. 20.8** | `BasePlusCommissionEmployee` class represents an employee who receives a base salary in addition to a commission. (Part 3 of 3.)

### Defining Class `BasePlusCommissionEmployee`

The `BasePlusCommissionEmployee` header file (Fig. 20.7) specifies class `BasePlusCommissionEmployee`'s public services, which include the `BasePlusCommissionEmployee` constructor (lines 13–14) and member functions `earnings` (line 34) and `print` (line 35). Lines 16–32 declare public *get* and *set* functions for the class's private data members (declared in lines 37–42) `firstName`, `lastName`, `socialSecurityNumber`, `grossSales`, `commissionRate` and `baseSalary`. These variables and member functions encapsulate all the necessary features of a base-salaried commission employee. Note the similarity between this class and class `CommissionEmployee` (Figs. 20.4–20.5)—in this example, we won't yet exploit that similarity.

Class `BasePlusCommissionEmployee`'s `earnings` member function (defined in lines 94–97 of Fig. 20.8) computes the earnings of a base-salaried commission employee. Line 96 returns the result of adding the employee's base salary to the product of the commission rate and the employee's gross sales.

### Testing Class `BasePlusCommissionEmployee`

Figure 20.9 tests class `BasePlusCommissionEmployee`. Lines 11–12 instantiate object `employee` of class `BasePlusCommissionEmployee`, passing "Bob", "Lewis", "333-33-3333", 5000, .04 and 300 to the constructor as the first name, last name, social security number, gross sales, commission rate and base salary, respectively. Lines 19–25 use `BasePlusCommissionEmployee`'s *get* functions to retrieve the values of the object's data members for output. Line 27 invokes the object's `setBaseSalary` member function to change the base salary. Member function `setBaseSalary` (Fig. 20.8, lines 82–85) ensures that data member `baseSalary` is not assigned a negative value, because an employee's base salary cannot



```

1 // Fig. 20.9: fig20_09.cpp
2 // Testing class BasePlusCommissionEmployee.
3 #include <iostream>
4 #include <iomanip>
5 #include "BasePlusCommissionEmployee.h"
6 using namespace std;
7
8 int main()
9 {
10 // instantiate BasePlusCommissionEmployee object
11 BasePlusCommissionEmployee
12 employee("Bob", "Lewis", "333-33-3333", 5000, .04, 300);
13
14 // set floating-point output formatting
15 cout << fixed << setprecision(2);
16
17 // get commission employee data
18 cout << "Employee information obtained by get functions: \n"
19 << "\nFirst name is " << employee.getFirstName()
20 << "\nLast name is " << employee.getLastName()
21 << "\nSocial security number is "
22 << employee.getSocialSecurityNumber()
23 << "\nGross sales is " << employee.getGrossSales()
24 << "\nCommission rate is " << employee.getCommissionRate()
25 << "\nBase salary is " << employee.getBaseSalary() << endl;
26
27 employee.setBaseSalary(1000); // set base salary
28
29 cout << "\nUpdated employee information output by print function: \n"
30 << endl;
31 employee.print(); // display the new employee information
32
33 // display the employee's earnings
34 cout << "\n\nEmployee's earnings: $" << employee.earnings() << endl;
35 } // end main

```

Employee information obtained by get functions:

First name is Bob  
 Last name is Lewis  
 Social security number is 333-33-3333  
 Gross sales is 5000.00  
 Commission rate is 0.04  
 Base salary is 300.00

Updated employee information output by print function:

base-salaried commission employee: Bob Lewis  
 social security number: 333-33-3333  
 gross sales: 5000.00  
 commission rate: 0.04  
 base salary: 1000.00

Employee's earnings: \$1200.00

**Fig. 20.9** | BasePlusCommissionEmployee class test program.

be negative. Line 31 of Fig. 20.9 invokes the object's `print` member function to output the updated `BasePlusCommissionEmployee`'s information, and line 34 calls member function `earnings` to display the `BasePlusCommissionEmployee`'s earnings.

### *Exploring the Similarities Between Class `BasePlusCommissionEmployee` and Class `CommissionEmployee`*

Most of the code for class `BasePlusCommissionEmployee` (Figs. 20.7–20.8) is similar, if not identical, to the code for class `CommissionEmployee` (Figs. 20.4–20.5). For example, in class `BasePlusCommissionEmployee`, private data members `firstName` and `lastName` and member functions `setFirstName`, `getFirstName`, `setLastName` and `getLastName` are identical to those of class `CommissionEmployee`. Classes `CommissionEmployee` and `BasePlusCommissionEmployee` also both contain private data members `socialSecurityNumber`, `commissionRate` and `grossSales`, as well as *get* and *set* functions to manipulate these members. In addition, the `BasePlusCommissionEmployee` constructor is almost identical to that of class `CommissionEmployee`, except that `BasePlusCommissionEmployee`'s constructor also sets the `baseSalary`. The other additions to class `BasePlusCommissionEmployee` are private data member `baseSalary` and member functions `setBaseSalary` and `getBaseSalary`. Class `BasePlusCommissionEmployee`'s `print` member function is nearly identical to that of class `CommissionEmployee`, except that `BasePlusCommissionEmployee`'s `print` also outputs the value of data member `baseSalary`.

We literally copied code from class `CommissionEmployee` and pasted it into class `BasePlusCommissionEmployee`, then modified class `BasePlusCommissionEmployee` to include a base salary and member functions that manipulate the base salary. This “copy-and-paste” approach is error prone and time consuming. Worse yet, it can spread many physical copies of the same code throughout a system, creating a code-maintenance nightmare. Is there a way to “absorb” the data members and member functions of a class in a way that makes them part of another class without duplicating code? In the next several examples, we do exactly this, using inheritance.



#### Software Engineering Observation 20.3

*Copying and pasting code from one class to another can spread errors across multiple source code files. To avoid duplicating code (and possibly errors), use inheritance, rather than the “copy-and-paste” approach, in situations where you want one class to “absorb” the data members and member functions of another class.*



#### Software Engineering Observation 20.4

*With inheritance, the common data members and member functions of all the classes in the hierarchy are declared in a base class. When changes are required for these common features, you need to make the changes only in the base class—derived classes then inherit the changes. Without inheritance, changes would need to be made to all the source code files that contain a copy of the code in question.*

### 20.4.3 Creating a `CommissionEmployee`–`BasePlusCommissionEmployee` Inheritance Hierarchy

Now we create and test a new `BasePlusCommissionEmployee` class (Figs. 20.10–20.11) that derives from class `CommissionEmployee` (Figs. 20.4–20.5). In this example, a `BasePlusCommissionEmployee` object *is a* `CommissionEmployee` (because inheritance

passes on the capabilities of class `CommissionEmployee`), but class `BasePlusCommissionEmployee` also has data member `baseSalary` (Fig. 20.10, line 23). The colon (`:`) in line 11 of the class definition indicates inheritance. Keyword `public` indicates the type of inheritance. As a derived class (formed with `public` inheritance), `BasePlusCommissionEmployee` inherits all the members of class `CommissionEmployee`, except for the constructor—each class provides its own constructors that are specific to the class. (Destructors, too, are not inherited.) Thus, the public services of `BasePlusCommissionEmployee` include its constructor (lines 14–15) and the public member functions inherited from class `CommissionEmployee`—although we cannot see these inherited member functions in `BasePlusCommissionEmployee`’s source code, they’re nevertheless a part of derived class `BasePlusCommissionEmployee`. The derived class’s public services also include member functions `setBaseSalary`, `getBaseSalary`, `earnings` and `print` (lines 17–21).

---

```

1 // Fig. 20.10: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class derived from class
3 // CommissionEmployee.
4 #ifndef BASEPLUS_H
5 #define BASEPLUS_H
6
7 #include <string> // C++ standard string class
8 #include "CommissionEmployee.h" // CommissionEmployee class declaration
9 using namespace std;
10
11 class BasePlusCommissionEmployee : public CommissionEmployee
12 {
13 public:
14 BasePlusCommissionEmployee(const string &, const string &,
15 const string &, double = 0.0, double = 0.0, double = 0.0);
16
17 void setBaseSalary(double); // set base salary
18 double getBaseSalary() const; // return base salary
19
20 double earnings() const; // calculate earnings
21 void print() const; // print BasePlusCommissionEmployee object
22 private:
23 double baseSalary; // base salary
24 }; // end class BasePlusCommissionEmployee
25
26 #endif

```

---

**Fig. 20.10** | `BasePlusCommissionEmployee` class definition indicating inheritance relationship with class `CommissionEmployee`.

---

```

1 // Fig. 20.11: BasePlusCommissionEmployee.cpp
2 // Class BasePlusCommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "BasePlusCommissionEmployee.h"
5 using namespace std;

```

---

**Fig. 20.11** | `BasePlusCommissionEmployee` implementation file: private base-class data cannot be accessed from derived class. (Part I of 3.)

```

6
7 // constructor
8 BasePlusCommissionEmployee::BasePlusCommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate, double salary)
11 // explicitly call base-class constructor
12 : CommissionEmployee(first, last, ssn, sales, rate)
13 {
14 setBaseSalary(salary); // validate and store base salary
15 } // end BasePlusCommissionEmployee constructor
16
17 // set base salary
18 void BasePlusCommissionEmployee::setBaseSalary(double salary)
19 {
20 baseSalary = (salary < 0.0) ? 0.0 : salary;
21 } // end function setBaseSalary
22
23 // return base salary
24 double BasePlusCommissionEmployee::getBaseSalary() const
25 {
26 return baseSalary;
27 } // end function getBaseSalary
28
29 // calculate earnings
30 double BasePlusCommissionEmployee::earnings() const
31 {
32 // derived class cannot access the base class's private data
33 return baseSalary + (commissionRate * grossSales);
34 } // end function earnings
35
36 // print BasePlusCommissionEmployee object
37 void BasePlusCommissionEmployee::print() const
38 {
39 // derived class cannot access the base class's private data
40 cout << "base-salaried commission employee: " << firstName << ' '
41 << lastName << "\nsocial security number: " << socialSecurityNumber
42 << "\ngross sales: " << grossSales
43 << "\ncommission rate: " << commissionRate
44 << "\nbase salary: " << baseSalary;
45 } // end function print

```

```

C:\examples\ch20\Fig20_10_11\BasePlusCommissionEmployee.cpp(33) :
error C2248: 'CommissionEmployee::commissionRate' :
cannot access private member declared in class 'CommissionEmployee'

C:\examples\ch20\Fig20_10_11\BasePlusCommissionEmployee.cpp(33) :
error C2248: 'CommissionEmployee::grossSales' :
cannot access private member declared in class 'CommissionEmployee'

C:\examples\ch20\Fig20_10_11\BasePlusCommissionEmployee.cpp(40) :
error C2248: 'CommissionEmployee::firstName' :
cannot access private member declared in class 'CommissionEmployee'

```

**Fig. 20.11** | BasePlusCommissionEmployee implementation file: private base-class data cannot be accessed from derived class. (Part 2 of 3.)

```

C:\examples\ch20\Fig20_10_11\BasePlusCommissionEmployee.cpp(41) :
error C2248: 'CommissionEmployee::lastName' :
cannot access private member declared in class 'CommissionEmployee'

C:\examples\ch20\Fig20_10_11\BasePlusCommissionEmployee.cpp(41) :
error C2248: 'CommissionEmployee::socialSecurityNumber' :
cannot access private member declared in class 'CommissionEmployee'

C:\examples\ch20\Fig20_10_11\BasePlusCommissionEmployee.cpp(42) :
error C2248: 'CommissionEmployee::grossSales' :
cannot access private member declared in class 'CommissionEmployee'

C:\examples\ch20\Fig20_10_11\BasePlusCommissionEmployee.cpp(43) :
error C2248: 'CommissionEmployee::commissionRate' :
cannot access private member declared in class 'CommissionEmployee'

```

**Fig. 20.11** | BasePlusCommissionEmployee implementation file: private base-class data cannot be accessed from derived class. (Part 3 of 3.)

Figure 20.11 shows BasePlusCommissionEmployee's member-function implementations. The constructor (lines 8–15) introduces **base-class initializer syntax** (line 12), which uses a member initializer to pass arguments to the base-class (CommissionEmployee) constructor. C++ requires that a derived-class constructor call its base-class constructor to initialize the base-class data members that are inherited into the derived class. Line 12 accomplishes this task by invoking the CommissionEmployee constructor by name, passing the constructor's parameters first, last, ssn, sales and rate as arguments to initialize base-class data members firstName, lastName, socialSecurityNumber, grossSales and commissionRate. If BasePlusCommissionEmployee's constructor did not invoke class CommissionEmployee's constructor explicitly, C++ would attempt to invoke class CommissionEmployee's default constructor—but the class does not have such a constructor, so the compiler would issue an error. Recall from Chapter 16 that the compiler provides a default constructor with no parameters in any class that does not explicitly include a constructor. However, CommissionEmployee *does* explicitly include a constructor, so a default constructor is not provided, and any attempts to implicitly call CommissionEmployee's default constructor would result in compilation errors.



### Common Programming Error 20.1

*When a derived-class constructor calls a base-class constructor, the arguments passed to the base-class constructor must be consistent with the number and types of parameters specified in one of the base-class constructors; otherwise, a compilation error occurs.*



### Performance Tip 20.1

*In a derived-class constructor, initializing member objects and invoking base-class constructors explicitly in the member initializer list prevents duplicate initialization in which a default constructor is called, then data members are modified again in the derived-class constructor's body.*

The compiler generates errors for line 33 of Fig. 20.11 because base class CommissionEmployee's data members commissionRate and grossSales are private—derived class BasePlusCommissionEmployee's member functions are not allowed to access base class

CommissionEmployee's private data. We used darker blue text in Fig. 20.11 to indicate erroneous code. The compiler issues additional errors in lines 40–43 of BasePlusCommissionEmployee's print member function for the same reason. As you can see, C++ rigidly enforces restrictions on accessing private data members, so that even a derived class (which is intimately related to its base class) cannot access the base class's private data. [Note: To save space, we show only the error messages from Visual C++ in this example and we removed some of the error messages. The error messages produced by your compiler may differ from those shown here.]

We purposely included the erroneous code in Fig. 20.11 to emphasize that a derived class's member functions cannot access its base class's private data. The errors in BasePlusCommissionEmployee could have been prevented by using the *get* member functions inherited from class CommissionEmployee. For example, line 33 could have invoked *getCommissionRate* and *getGrossSales* to access CommissionEmployee's private data members *commissionRate* and *grossSales*, respectively. Similarly, lines 40–43 could have used appropriate *get* member functions to retrieve the values of the base class's data members. In the next example, we show how using protected data also allows us to avoid the errors encountered in this example.

### ***Including the Base-Class Header File in the Derived-Class Header File with #include***

Notice that we *#include* the base class's header file in the derived class's header file (line 8 of Fig. 20.10). This is necessary for three reasons. First, for the derived class to use the base class's name in line 10, we must tell the compiler that the base class exists—the class definition in *CommissionEmployee.h* does exactly that.

The second reason is that the compiler uses a class definition to determine the size of an object of that class. A client program that creates an object of a class must *#include* the class definition to enable the compiler to reserve the proper amount of memory for the object. When using inheritance, a derived-class object's size depends on the data members declared explicitly in its class definition *and* the data members inherited from its direct and indirect base classes. Including the base class's definition in line 8 allows the compiler to determine the memory requirements for the base class's data members that become part of a derived-class object and thus contribute to the total size of the derived-class object.

The last reason for line 8 is to allow the compiler to determine whether the derived class uses the base class's inherited members properly. For example, in the program of Figs. 20.10–20.11, the compiler uses the base-class header file to determine that the data members being accessed by the derived class are *private* in the base class. Since these are inaccessible to the derived class, the compiler generates errors. The compiler also uses the base class's function prototypes to validate function calls made by the derived class to the inherited base-class functions—you'll see an example of such a function call in Fig. 20.15.

### ***Linking Process in an Inheritance Hierarchy***

In Section 16.8, we discussed the linking process for creating an executable GradeBook application. In that example, you saw that the client's object code was linked with the object code for class GradeBook, as well as the object code for any C++ Standard Library classes used in either the client code or in class GradeBook.

The linking process is similar for a program that uses classes in an inheritance hierarchy. The process requires the object code for all classes used in the program and the object code for the direct and indirect base classes of any derived classes used by the pro-

gram. Suppose a client wants to create an application that uses class `BasePlusCommissionEmployee`, which is a derived class of `CommissionEmployee` (we'll see an example of this in Section 20.4.4). When compiling the client application, the client's object code must be linked with the object code for classes `BasePlusCommissionEmployee` and `CommissionEmployee`, because `BasePlusCommissionEmployee` inherits member functions from its base class `CommissionEmployee`. The code is also linked with the object code for any C++ Standard Library classes used in class `CommissionEmployee`, class `BasePlusCommissionEmployee` or the client code. This provides the program with access to the implementations of all of the functionality that the program may use.

#### 20.4.4 `CommissionEmployee`–`BasePlusCommissionEmployee` Inheritance Hierarchy Using protected Data

To enable class `BasePlusCommissionEmployee` to directly access `CommissionEmployee` data members `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate`, we can declare those members as protected in the base class. As we discussed in Section 20.3, a base class's protected members can be accessed by members and friends of the base class and by members and friends of any classes derived from that base class.



#### Good Programming Practice 20.1

*Declare public members first, protected members second and private members last.*

#### Defining Base Class `CommissionEmployee` with protected Data

Class `CommissionEmployee` (Figs. 20.12–20.13) now declares data members `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate` as protected (Fig. 20.12, lines 32–37) rather than private. The member-function implementations in Fig. 20.13 are identical to those in Fig. 20.5.

---

```

1 // Fig. 20.12: CommissionEmployee.h
2 // CommissionEmployee class definition with protected data.
3 #ifndef COMMISSION_H
4 #define COMMISSION_H
5
6 #include <string> // C++ standard string class
7 using namespace std;
8
9 class CommissionEmployee
10 {
11 public:
12 CommissionEmployee(const string &, const string &, const string &,
13 double = 0.0, double = 0.0);
14
15 void setFirstName(const string &); // set first name
16 string getFirstName() const; // return first name

```

---

**Fig. 20.12** | `CommissionEmployee` class definition that declares protected data to allow access by derived classes. (Part 1 of 2.)

---

```

17
18 void setLastName(const string &); // set last name
19 string getLastName() const; // return last name
20
21 void setSocialSecurityNumber(const string &); // set SSN
22 string getSocialSecurityNumber() const; // return SSN
23
24 void setGrossSales(double); // set gross sales amount
25 double getGrossSales() const; // return gross sales amount
26
27 void setCommissionRate(double); // set commission rate
28 double getCommissionRate() const; // return commission rate
29
30 double earnings() const; // calculate earnings
31 void print() const; // print CommissionEmployee object
32 protected:
33 string firstName;
34 string lastName;
35 string socialSecurityNumber;
36 double grossSales; // gross weekly sales
37 double commissionRate; // commission percentage
38 }; // end class CommissionEmployee
39
40 #endif

```

---

**Fig. 20.12** | *CommissionEmployee* class definition that declares protected data to allow access by derived classes. (Part 2 of 2.)

---

```

1 // Fig. 20.13: CommissionEmployee.cpp
2 // Class CommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "CommissionEmployee.h" // CommissionEmployee class definition
5 using namespace std;
6
7 // constructor
8 CommissionEmployee::CommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate)
11 {
12 firstName = first; // should validate
13 lastName = last; // should validate
14 socialSecurityNumber = ssn; // should validate
15 setGrossSales(sales); // validate and store gross sales
16 setCommissionRate(rate); // validate and store commission rate
17 } // end CommissionEmployee constructor
18
19 // set first name
20 void CommissionEmployee::setFirstName(const string &first)
21 {
22 firstName = first; // should validate
23 } // end function setFirstName

```

---

**Fig. 20.13** | *CommissionEmployee* class with protected data. (Part 1 of 3.)



```
24
25 // return first name
26 string CommissionEmployee::getFirstName() const
27 {
28 return firstName;
29 } // end function getFirstName
30
31 // set last name
32 void CommissionEmployee::setLastName(const string &last)
33 {
34 lastName = last; // should validate
35 } // end function setLastName
36
37 // return last name
38 string CommissionEmployee::getLastName() const
39 {
40 return lastName;
41 } // end function getLastName
42
43 // set social security number
44 void CommissionEmployee::setSocialSecurityNumber(const string &ssn)
45 {
46 socialSecurityNumber = ssn; // should validate
47 } // end function setSocialSecurityNumber
48
49 // return social security number
50 string CommissionEmployee::getSocialSecurityNumber() const
51 {
52 return socialSecurityNumber;
53 } // end function getSocialSecurityNumber
54
55 // set gross sales amount
56 void CommissionEmployee::setGrossSales(double sales)
57 {
58 grossSales = (sales < 0.0) ? 0.0 : sales;
59 } // end function setGrossSales
60
61 // return gross sales amount
62 double CommissionEmployee::getGrossSales() const
63 {
64 return grossSales;
65 } // end function getGrossSales
66
67 // set commission rate
68 void CommissionEmployee::setCommissionRate(double rate)
69 {
70 commissionRate = (rate > 0.0 && rate < 1.0) ? rate : 0.0;
71 } // end function setCommissionRate
72
73 // return commission rate
74 double CommissionEmployee::getCommissionRate() const
75 {
```

**Fig. 20.13** | CommissionEmployee class with protected data. (Part 2 of 3.)

---

```

76 return commissionRate;
77 } // end function getCommissionRate
78
79 // calculate earnings
80 double CommissionEmployee::earnings() const
81 {
82 return commissionRate * grossSales;
83 } // end function earnings
84
85 // print CommissionEmployee object
86 void CommissionEmployee::print() const
87 {
88 cout << "commission employee: " << firstName << ' ' << lastName
89 << "\nsocial security number: " << socialSecurityNumber
90 << "\ngross sales: " << grossSales
91 << "\ncommission rate: " << commissionRate;
92 } // end function print

```

---

**Fig. 20.13** | CommissionEmployee class with protected data. (Part 3 of 3.)

### *Modifying Derived Class BasePlusCommissionEmployee*

The version of class BasePlusCommissionEmployee in Figs. 20.14–20.15 inherits from class CommissionEmployee in Figs. 20.12–20.13. Objects of class BasePlusCommissionEmployee can access inherited data members that are declared protected in class CommissionEmployee (i.e., data members firstName, lastName, socialSecurityNumber, grossSales and commissionRate). As a result, the compiler does not generate errors when compiling the BasePlusCommissionEmployee earnings and print member-function definitions in Fig. 20.15 (lines 30–34 and 37–45, respectively). This shows the special privileges that a derived class is granted to access protected base-class data members. Objects of a derived class also can access protected members in any of that derived class's indirect base classes.

---

```

1 // Fig. 20.14: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class derived from class
3 // CommissionEmployee.
4 #ifndef BASEPLUS_H
5 #define BASEPLUS_H
6
7 #include <string> // C++ standard string class
8 #include "CommissionEmployee.h" // CommissionEmployee class declaration
9 using namespace std;
10
11 class BasePlusCommissionEmployee : public CommissionEmployee
12 {
13 public:
14 BasePlusCommissionEmployee(const string &, const string &,
15 const string &, double = 0.0, double = 0.0, double = 0.0);
16

```

---

**Fig. 20.14** | BasePlusCommissionEmployee class header file. (Part 1 of 2.)

---

```

17 void setBaseSalary(double); // set base salary
18 double getBaseSalary() const; // return base salary
19
20 double earnings() const; // calculate earnings
21 void print() const; // print BasePlusCommissionEmployee object
22 private:
23 double baseSalary; // base salary
24 }; // end class BasePlusCommissionEmployee
25
26 #endif

```

---

**Fig. 20.14** | BasePlusCommissionEmployee class header file. (Part 2 of 2.)

---

```

1 // Fig. 20.15: BasePlusCommissionEmployee.cpp
2 // Class BasePlusCommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "BasePlusCommissionEmployee.h"
5 using namespace std;
6
7 // constructor
8 BasePlusCommissionEmployee::BasePlusCommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate, double salary)
11 // explicitly call base-class constructor
12 : CommissionEmployee(first, last, ssn, sales, rate)
13 {
14 setBaseSalary(salary); // validate and store base salary
15 } // end BasePlusCommissionEmployee constructor
16
17 // set base salary
18 void BasePlusCommissionEmployee::setBaseSalary(double salary)
19 {
20 baseSalary = (salary < 0.0) ? 0.0 : salary;
21 } // end function setBaseSalary
22
23 // return base salary
24 double BasePlusCommissionEmployee::getBaseSalary() const
25 {
26 return baseSalary;
27 } // end function getBaseSalary
28
29 // calculate earnings
30 double BasePlusCommissionEmployee::earnings() const
31 {
32 // can access protected data of base class
33 return baseSalary + (commissionRate * grossSales);
34 } // end function earnings
35

```

---

**Fig. 20.15** | BasePlusCommissionEmployee implementation file for BasePlusCommissionEmployee class that inherits protected data from CommissionEmployee. (Part 1 of 2.)

---

```

36 // print BasePlusCommissionEmployee object
37 void BasePlusCommissionEmployee::print() const
38 {
39 // can access protected data of base class
40 cout << "base-salaried commission employee: " << firstName << ' '
41 << lastName << "\nsocial security number: " << socialSecurityNumber
42 << "\ngross sales: " << grossSales
43 << "\ncommission rate: " << commissionRate
44 << "\nbase salary: " << baseSalary;
45 } // end function print

```

---

**Fig. 20.15** | BasePlusCommissionEmployee implementation file for

BasePlusCommissionEmployee class that inherits protected data from CommissionEmployee. (Part 2 of 2.)

Class BasePlusCommissionEmployee does not inherit class CommissionEmployee's constructor. However, class BasePlusCommissionEmployee's constructor (Fig. 20.15, lines 8–15) calls class CommissionEmployee's constructor explicitly with member initializer syntax (line 12). Recall that BasePlusCommissionEmployee's constructor must explicitly call the constructor of class CommissionEmployee, because CommissionEmployee does not contain a default constructor that could be invoked implicitly.

### *Testing the Modified BasePlusCommissionEmployee Class*

Figure 20.16 uses a BasePlusCommissionEmployee object to perform the same tasks that Fig. 20.9 performed on an object of the first version of class BasePlusCommissionEmployee (Figs. 20.7–20.8). The code and outputs of the two programs are identical. We created the first class BasePlusCommissionEmployee without using inheritance and created this version of BasePlusCommissionEmployee using inheritance; however, both classes provide the same functionality. The code for class BasePlusCommissionEmployee (i.e., the header and implementation files), which is 71 lines, is considerably shorter than the code for the noninherited version of the class, which is 152 lines, because the inherited version absorbs part of its functionality from CommissionEmployee, whereas the noninherited version does not absorb any functionality. Also, there is now only one copy of the CommissionEmployee functionality declared and defined in class CommissionEmployee. This makes the source code easier to maintain, modify and debug, because the source code related to a CommissionEmployee exists only in the files of Figs. 20.12–20.13.

---

```

1 // Fig. 20.16: fig20_16.cpp
2 // Testing class BasePlusCommissionEmployee.
3 #include <iostream>
4 #include <iomanip>
5 #include "BasePlusCommissionEmployee.h"
6 using namespace std;
7
8 int main()
9 {

```

---

**Fig. 20.16** | protected base-class data can be accessed from derived class. (Part 1 of 2.)

```

10 // instantiate BasePlusCommissionEmployee object
11 BasePlusCommissionEmployee
12 employee("Bob", "Lewis", "333-33-3333", 5000, .04, 300);
13
14 // set floating-point output formatting
15 cout << fixed << setprecision(2);
16
17 // get commission employee data
18 cout << "Employee information obtained by get functions: \n"
19 << "\nFirst name is " << employee.getFirstName()
20 << "\nLast name is " << employee.getLastName()
21 << "\nSocial security number is "
22 << employee.getSocialSecurityNumber()
23 << "\nGross sales is " << employee.getGrossSales()
24 << "\nCommission rate is " << employee.getCommissionRate()
25 << "\nBase salary is " << employee.getBaseSalary() << endl;
26
27 employee.setBaseSalary(1000); // set base salary
28
29 cout << "\nUpdated employee information output by print function: \n"
30 << endl;
31 employee.print(); // display the new employee information
32
33 // display the employee's earnings
34 cout << "\n\nEmployee's earnings: $" << employee.earnings() << endl;
35 } // end main

```

Employee information obtained by get functions:

First name is Bob  
 Last name is Lewis  
 Social security number is 333-33-3333  
 Gross sales is 5000.00  
 Commission rate is 0.04  
 Base salary is 300.00

Updated employee information output by print function:

base-salaried commission employee: Bob Lewis  
 social security number: 333-33-3333  
 gross sales: 5000.00  
 commission rate: 0.04  
 base salary: 1000.00

Employee's earnings: \$1200.00

**Fig. 20.16** | protected base-class data can be accessed from derived class. (Part 2 of 2.)

### Notes on Using *protected* Data

In this example, we declared base-class data members as *protected*, so derived classes can modify the data directly. Inheriting *protected* data members slightly increases performance, because we can directly access the members without incurring the overhead of calls to *set* or *get* member functions. In most cases, however, it's better to use *private* data members to encourage proper software engineering, and leave code optimization issues to the compiler. Your code will be easier to maintain, modify and debug.

Using protected data members creates two serious problems. First, the derived-class object does not have to use a member function to set the value of the base class's protected data member. An invalid value can easily be assigned to the protected data member, thus leaving the object in an inconsistent state—e.g., with `CommissionEmployee`'s data member `grossSales` declared as protected, a derived-class object can assign a negative value to `grossSales`. The second problem with using protected data members is that derived-class member functions are more likely to be written so that they depend on the base-class implementation. Derived classes should depend only on the base-class services (i.e., non-private member functions) and not on the base-class implementation. With protected data members in the base class, if the base-class implementation changes, we may need to modify all derived classes of that base class. For example, if for some reason we were to change the names of data members `firstName` and `lastName` to `first` and `last`, then we'd have to do so for all occurrences in which a derived class references these base-class data members directly. Such software is said to be **fragile** or **brittle**, because a small change in the base class can “break” derived-class implementation. You should be able to change the base-class implementation while still providing the same services to derived classes. (Of course, if the base-class services change, we must reimplement our derived classes—good object-oriented design attempts to prevent this.)



#### Software Engineering Observation 20.5

*It's appropriate to use the protected access specifier when a base class should provide a service (i.e., a member function) only to its derived classes and friends.*



#### Software Engineering Observation 20.6

*Declaring base-class data members private (as opposed to declaring them protected) enables you to change the base-class implementation without having to change derived-class implementations.*



#### Error-Prevention Tip 20.1

*When possible, avoid including protected data members in a base class. Rather, include non-private member functions that access private data members, ensuring that the object maintains a consistent state.*

### 20.4.5 `CommissionEmployee`–`BasePlusCommissionEmployee` Inheritance Hierarchy Using private Data

We now reexamine our hierarchy once more, this time using the best software engineering practices. Class `CommissionEmployee` (Figs. 20.17–20.18) now declares data members `firstName`, `lastName`, `socialSecurityNumber`, `grossSales` and `commissionRate` as private (Fig. 20.17, lines 32–37) and provides public member functions `setFirstName`, `getFirstName`, `setLastName`, `getLastName`, `setSocialSecurityNumber`, `getSocialSecurityNumber`, `setGrossSales`, `getGrossSales`, `setCommissionRate`, `getCommissionRate`, `earnings` and `print` for manipulating these values. If we decide to change the data member names, the `earnings` and `print` definitions will not require modification—only the definitions of the *get* and *set* member functions that directly manipulate the data members will need to change. These changes occur solely within the base class—no changes to the derived class are needed. Localizing the effects of changes like this is a good

software engineering practice. Derived class `BasePlusCommissionEmployee` (Figs. 20.19–20.20) inherits `CommissionEmployee`'s member functions and can access the private base-class members via the inherited non-private member functions.

---

```

1 // Fig. 20.17: CommissionEmployee.h
2 // CommissionEmployee class definition with good software engineering.
3 #ifndef COMMISSION_H
4 #define COMMISSION_H
5
6 #include <string> // C++ standard string class
7 using namespace std;
8
9 class CommissionEmployee
10 {
11 public:
12 CommissionEmployee(const string &, const string &, const string &,
13 double = 0.0, double = 0.0);
14
15 void setFirstName(const string &); // set first name
16 string getFirstName() const; // return first name
17
18 void setLastName(const string &); // set last name
19 string getLastName() const; // return last name
20
21 void setSocialSecurityNumber(const string &); // set SSN
22 string getSocialSecurityNumber() const; // return SSN
23
24 void setGrossSales(double); // set gross sales amount
25 double getGrossSales() const; // return gross sales amount
26
27 void setCommissionRate(double); // set commission rate
28 double getCommissionRate() const; // return commission rate
29
30 double earnings() const; // calculate earnings
31 void print() const; // print CommissionEmployee object
32 private:
33 string firstName;
34 string lastName;
35 string socialSecurityNumber;
36 double grossSales; // gross weekly sales
37 double commissionRate; // commission percentage
38 }; // end class CommissionEmployee
39
40 #endif

```

---

**Fig. 20.17** | `CommissionEmployee` class defined using good software engineering practices.

In the `CommissionEmployee` constructor implementation (Fig. 20.18, lines 8–15), we use member initializers (line 11) to set the values of members `firstName`, `lastName` and `socialSecurityNumber`. We show how derived-class `BasePlusCommissionEmployee` (Figs. 20.19–20.20) can invoke non-private base-class member functions (`setFirstName`, `getFirstName`, `setLastName`, `getLastName`, `setSocialSecurityNumber` and `getSocialSecurityNumber`) to manipulate these data members.



### Performance Tip 20.2

*Using a member function to access a data member's value can be slightly slower than accessing the data directly. However, today's optimizing compilers are carefully designed to perform many optimizations implicitly (such as inlining set and get member-function calls). You should write code that adheres to proper software engineering principles, and leave optimization to the compiler. A good rule is, "Do not second-guess the compiler."*

```

1 // Fig. 20.18: CommissionEmployee.cpp
2 // Class CommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "CommissionEmployee.h" // CommissionEmployee class definition
5 using namespace std;
6
7 // constructor
8 CommissionEmployee::CommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate)
11 : firstName(first), lastName(last), socialSecurityNumber(ssn)
12 {
13 setGrossSales(sales); // validate and store gross sales
14 setCommissionRate(rate); // validate and store commission rate
15 } // end CommissionEmployee constructor
16
17 // set first name
18 void CommissionEmployee::setFirstName(const string &first)
19 {
20 firstName = first; // should validate
21 } // end function setFirstName
22
23 // return first name
24 string CommissionEmployee::getFirstName() const
25 {
26 return firstName;
27 } // end function getFirstName
28
29 // set last name
30 void CommissionEmployee::setLastName(const string &last)
31 {
32 lastName = last; // should validate
33 } // end function setLastName
34
35 // return last name
36 string CommissionEmployee::getLastName() const
37 {
38 return lastName;
39 } // end function getLastName
40
41 // set social security number
42 void CommissionEmployee::setSocialSecurityNumber(const string &ssn)
43 {

```

**Fig. 20.18** | CommissionEmployee class implementation file: CommissionEmployee class uses member functions to manipulate its private data. (Part 1 of 2.)



---

```

44 socialSecurityNumber = ssn; // should validate
45 } // end function setSocialSecurityNumber
46
47 // return social security number
48 string CommissionEmployee::getSocialSecurityNumber() const
49 {
50 return socialSecurityNumber;
51 } // end function getSocialSecurityNumber
52
53 // set gross sales amount
54 void CommissionEmployee::setGrossSales(double sales)
55 {
56 grossSales = (sales < 0.0) ? 0.0 : sales;
57 } // end function setGrossSales
58
59 // return gross sales amount
60 double CommissionEmployee::getGrossSales() const
61 {
62 return grossSales;
63 } // end function getGrossSales
64
65 // set commission rate
66 void CommissionEmployee::setCommissionRate(double rate)
67 {
68 commissionRate = (rate > 0.0 && rate < 1.0) ? rate : 0.0;
69 } // end function setCommissionRate
70
71 // return commission rate
72 double CommissionEmployee::getCommissionRate() const
73 {
74 return commissionRate;
75 } // end function getCommissionRate
76
77 // calculate earnings
78 double CommissionEmployee::earnings() const
79 {
80 return getCommissionRate() * getGrossSales();
81 } // end function earnings
82
83 // print CommissionEmployee object
84 void CommissionEmployee::print() const
85 {
86 cout << "commission employee: "
87 << getFirstName() << " " << getLastName()
88 << "\nsocial security number: " << getSocialSecurityNumber()
89 << "\ngross sales: " << getGrossSales()
90 << "\ncommission rate: " << getCommissionRate();
91 } // end function print

```

---

**Fig. 20.18** | `CommissionEmployee` class implementation file: `CommissionEmployee` class uses member functions to manipulate its private data. (Part 2 of 2.)

Class `BasePlusCommissionEmployee` (Figs. 20.19–20.20) has several changes to its member-function implementations (Fig. 20.20) that distinguish it from the previous version

of the class (Figs. 20.14–20.15). Member functions `earnings` (Fig. 20.20, lines 30–33) and `print` (lines 36–44) each invoke member function `getBaseSalary` to obtain the base salary value, rather than accessing `baseSalary` directly. This insulates `earnings` and `print` from potential changes to the implementation of data member `baseSalary`. For example, if we decide to rename data member `baseSalary` or change its type, only member functions `setBaseSalary` and `getBaseSalary` will need to change.

---

```

1 // Fig. 20.19: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class derived from class
3 // CommissionEmployee.
4 #ifndef BASEPLUS_H
5 #define BASEPLUS_H
6
7 #include <string> // C++ standard string class
8 #include "CommissionEmployee.h" // CommissionEmployee class declaration
9 using namespace std;
10
11 class BasePlusCommissionEmployee : public CommissionEmployee
12 {
13 public:
14 BasePlusCommissionEmployee(const string &, const string &,
15 const string &, double = 0.0, double = 0.0, double = 0.0);
16
17 void setBaseSalary(double); // set base salary
18 double getBaseSalary() const; // return base salary
19
20 double earnings() const; // calculate earnings
21 void print() const; // print BasePlusCommissionEmployee object
22 private:
23 double baseSalary; // base salary
24 }; // end class BasePlusCommissionEmployee
25
26 #endif

```

---

**Fig. 20.19** | `BasePlusCommissionEmployee` class header file.

---

```

1 // Fig. 20.20: BasePlusCommissionEmployee.cpp
2 // Class BasePlusCommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "BasePlusCommissionEmployee.h"
5 using namespace std;
6
7 // constructor
8 BasePlusCommissionEmployee::BasePlusCommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate, double salary)
11 // explicitly call base-class constructor
12 : CommissionEmployee(first, last, ssn, sales, rate)
13 {

```

---

**Fig. 20.20** | `BasePlusCommissionEmployee` class that inherits from class `CommissionEmployee` but cannot directly access the class's private data. (Part I of 2.)

---

```

14 setBaseSalary(salary); // validate and store base salary
15 } // end BasePlusCommissionEmployee constructor
16
17 // set base salary
18 void BasePlusCommissionEmployee::setBaseSalary(double salary)
19 {
20 baseSalary = (salary < 0.0) ? 0.0 : salary;
21 } // end function setBaseSalary
22
23 // return base salary
24 double BasePlusCommissionEmployee::getBaseSalary() const
25 {
26 return baseSalary;
27 } // end function getBaseSalary
28
29 // calculate earnings
30 double BasePlusCommissionEmployee::earnings() const
31 {
32 return getBaseSalary() + CommissionEmployee::earnings();
33 } // end function earnings
34
35 // print BasePlusCommissionEmployee object
36 void BasePlusCommissionEmployee::print() const
37 {
38 cout << "base-salaried ";
39
40 // invoke CommissionEmployee's print function
41 CommissionEmployee::print();
42
43 cout << "\nbase salary: " << getBaseSalary();
44 } // end function print

```

---

**Fig. 20.20** | BasePlusCommissionEmployee class that inherits from class CommissionEmployee but cannot directly access the class's private data. (Part 2 of 2.)

Class BasePlusCommissionEmployee's earnings function (Fig. 20.20, lines 30–33) redefines class CommissionEmployee's earnings member function (Fig. 20.18, lines 78–81) to calculate the earnings of a base-salaried commission employee. Class BasePlusCommissionEmployee's version of earnings obtains the portion of the employee's earnings based on commission alone by calling base-class CommissionEmployee's earnings function with the expression `CommissionEmployee::earnings()` (Fig. 20.20, line 32). BasePlusCommissionEmployee's earnings function then adds the base salary to this value to calculate the total earnings of the employee. Note the syntax used to invoke a redefined base-class member function from a derived class—place the base-class name and the binary scope resolution operator (`::`) before the base-class member-function name. This member-function invocation is a good software engineering practice: If an object's member function performs the actions needed by another object, call that member function rather than duplicating its code body. By having BasePlusCommissionEmployee's earnings function invoke CommissionEmployee's earnings function to calculate part of a BasePlusCommissionEmployee object's earnings, we avoid duplicating the code and reduce code-maintenance problems.



### Common Programming Error 20.2

*When a base-class member function is redefined in a derived class, the derived-class version often calls the base-class version to do additional work. Failure to use the `::` operator prefixed with the name of the base class when referencing the base class's member function causes infinite recursion, because the derived-class member function would then call itself.*

Similarly, `BasePlusCommissionEmployee`'s `print` function (Fig. 20.20, lines 36–44) redefines class `CommissionEmployee`'s `print` function (Fig. 20.18, lines 84–91) to output the appropriate base-salaried commission employee information. The new version displays part of a `BasePlusCommissionEmployee` object's information (i.e., the string "commission employee" and the values of class `CommissionEmployee`'s private data members) by calling `CommissionEmployee`'s `print` member function with the qualified name `CommissionEmployee::print()` (Fig. 20.20, line 41). `BasePlusCommissionEmployee`'s `print` function then outputs the remainder of a `BasePlusCommissionEmployee` object's information (i.e., the value of class `BasePlusCommissionEmployee`'s base salary).

Figure 20.21 performs the same manipulations on a `BasePlusCommissionEmployee` object as did Fig. 20.9 and Fig. 20.16 on objects of classes `CommissionEmployee` and `BasePlusCommissionEmployee`, respectively. Although each "base-salaried commission employee" class behaves identically, class `BasePlusCommissionEmployee` is the best engineered. By using inheritance and by calling member functions that hide the data and ensure consistency, we've efficiently and effectively constructed a well-engineered class.

```

1 // Fig. 20.21: fig20_21.cpp
2 // Testing class BasePlusCommissionEmployee.
3 #include <iostream>
4 #include <iomanip>
5 #include "BasePlusCommissionEmployee.h"
6 using namespace std;
7
8 int main()
9 {
10 // instantiate BasePlusCommissionEmployee object
11 BasePlusCommissionEmployee
12 employee("Bob", "Lewis", "333-33-3333", 5000, .04, 300);
13
14 // set floating-point output formatting
15 cout << fixed << setprecision(2);
16
17 // get commission employee data
18 cout << "Employee information obtained by get functions: \n"
19 << "\nFirst name is " << employee.getFirstName()
20 << "\nLast name is " << employee.getLastName()
21 << "\nSocial security number is "
22 << employee.getSocialSecurityNumber()
23 << "\nGross sales is " << employee.getGrossSales()
24 << "\nCommission rate is " << employee.getCommissionRate()
25 << "\nBase salary is " << employee.getBaseSalary() << endl;

```

**Fig. 20.21** | Base-class private data is accessible to a derived class via public or protected member function inherited by the derived class. (Part I of 2.)

```

26
27 employee.setBaseSalary(1000); // set base salary
28
29 cout << "\nUpdated employee information output by print function: \n"
30 << endl;
31 employee.print(); // display the new employee information
32
33 // display the employee's earnings
34 cout << "\n\nEmployee's earnings: $" << employee.earnings() << endl;
35 } // end main

```

Employee information obtained by get functions:

```

First name is Bob
Last name is Lewis
Social security number is 333-33-3333
Gross sales is 5000.00
Commission rate is 0.04
Base salary is 300.00

```

Updated employee information output by print function:

```

base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 1000.00

```

Employee's earnings: \$1200.00

**Fig. 20.21** | Base-class private data is accessible to a derived class via public or protected member function inherited by the derived class. (Part 2 of 2.)

In this section, you saw an evolutionary set of examples that was carefully designed to teach key capabilities for good software engineering with inheritance. You learned how to create a derived class using inheritance, how to use protected base-class members to enable a derived class to access inherited base-class data members and how to redefine base-class functions to provide versions that are more appropriate for derived-class objects. In addition, you learned how to apply software engineering techniques from Chapters 17–18 and this chapter to create classes that are easy to maintain, modify and debug.

## 20.5 Constructors and Destructors in Derived Classes

As we explained in the preceding section, instantiating a derived-class object begins a chain of constructor calls in which the derived-class constructor, before performing its own tasks, invokes its direct base class's constructor either explicitly (via a base-class member initializer) or implicitly (calling the base class's default constructor). Similarly, if the base class is derived from another class, the base-class constructor is required to invoke the constructor of the next class up in the hierarchy, and so on. The last constructor called in this chain is the constructor of the class at the base of the hierarchy, whose body actually finishes executing first. The original derived-class constructor's body finishes executing last. Each base-class constructor initializes the base-class data members that the derived-class

object inherits. For example, consider the `CommissionEmployee/BasePlusCommissionEmployee` hierarchy from Figs. 20.17–20.20. When a program creates an object of class `BasePlusCommissionEmployee`, the `CommissionEmployee` constructor is called. Since class `CommissionEmployee` is at the base of the hierarchy, its constructor executes, initializing the private data members of `CommissionEmployee` that are part of the `BasePlusCommissionEmployee` object. When `CommissionEmployee`'s constructor completes execution, it returns control to `BasePlusCommissionEmployee`'s constructor, which initializes the `BasePlusCommissionEmployee` object's `baseSalary`.



### Software Engineering Observation 20.7

*When a program creates a derived-class object, the derived-class constructor immediately calls the base-class constructor, the base-class constructor's body executes, then the derived class's member initializers execute and finally the derived-class constructor's body executes. This process cascades up the hierarchy if it contains more than two levels.*

When a derived-class object is destroyed, the program calls that object's destructor. This begins a chain (or cascade) of destructor calls in which the derived-class destructor and the destructors of the direct and indirect base classes and the classes' members execute in reverse of the order in which the constructors executed. When a derived-class object's destructor is called, the destructor performs its task, then invokes the destructor of the next base class up the hierarchy. This process repeats until the destructor of the final base class at the top of the hierarchy is called. Then the object is removed from memory.



### Software Engineering Observation 20.8

*Suppose that we create an object of a derived class where both the base class and the derived class contain (via composition) objects of other classes. When an object of that derived class is created, first the constructors for the base class's member objects execute, then the base-class constructor executes, then the constructors for the derived class's member objects execute, then the derived class's constructor executes. Destructors for derived-class objects are called in the reverse of the order in which their corresponding constructors are called.*

Base-class constructors, destructors and overloaded assignment operators (see Chapter 19) are not inherited by derived classes. Derived-class constructors, destructors and overloaded assignment operators, however, can call base-class constructors, destructors and overloaded assignment operators.

Our next example defines class `CommissionEmployee` (Figs. 20.22–20.23) and class `BasePlusCommissionEmployee` (Figs. 20.24–20.25) with constructors and destructors that each print a message when invoked. As you'll see in the output in Fig. 20.26, these messages demonstrate the order in which the constructors and destructors are called for objects in an inheritance hierarchy.

```
1 // Fig. 20.22: CommissionEmployee.h
2 // CommissionEmployee class definition represents a commission employee.
3 #ifndef COMMISSION_H
4 #define COMMISSION_H
5
```

**Fig. 20.22** | `CommissionEmployee` class header file. (Part 1 of 2.)

---

```

6 #include <string> // C++ standard string class
7 using namespace std;
8
9 class CommissionEmployee
10 {
11 public:
12 CommissionEmployee(const string &, const string &, const string &,
13 double = 0.0, double = 0.0);
14 ~CommissionEmployee(); // destructor
15
16 void setFirstName(const string &); // set first name
17 string getFirstName() const; // return first name
18
19 void setLastName(const string &); // set last name
20 string getLastName() const; // return last name
21
22 void setSocialSecurityNumber(const string &); // set SSN
23 string getSocialSecurityNumber() const; // return SSN
24
25 void setGrossSales(double); // set gross sales amount
26 double getGrossSales() const; // return gross sales amount
27
28 void setCommissionRate(double); // set commission rate
29 double getCommissionRate() const; // return commission rate
30
31 double earnings() const; // calculate earnings
32 void print() const; // print CommissionEmployee object
33 private:
34 string firstName;
35 string lastName;
36 string socialSecurityNumber;
37 double grossSales; // gross weekly sales
38 double commissionRate; // commission percentage
39 }; // end class CommissionEmployee
40
41 #endif

```

---

**Fig. 20.22** | CommissionEmployee class header file. (Part 2 of 2.)

---

```

1 // Fig. 20.23: CommissionEmployee.cpp
2 // Class CommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "CommissionEmployee.h" // CommissionEmployee class definition
5 using namespace std;
6
7 // constructor
8 CommissionEmployee::CommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate)
11 : firstName(first), lastName(last), socialSecurityNumber(ssn)
12 {

```

---

**Fig. 20.23** | CommissionEmployee's constructor and destructor output text. (Part 1 of 3.)

```

13 setGrossSales(sales); // validate and store gross sales
14 setCommissionRate(rate); // validate and store commission rate
15
16 cout << "CommissionEmployee constructor: " << endl;
17 print();
18 cout << "\n\n";
19 } // end CommissionEmployee constructor
20
21 // destructor
22 CommissionEmployee::~CommissionEmployee()
23 {
24 cout << "CommissionEmployee destructor: " << endl;
25 print();
26 cout << "\n\n";
27 } // end CommissionEmployee destructor
28
29 // set first name
30 void CommissionEmployee::setFirstName(const string &first)
31 {
32 firstName = first; // should validate
33 } // end function setFirstName
34
35 // return first name
36 string CommissionEmployee::getFirstName() const
37 {
38 return firstName;
39 } // end function getFirstName
40
41 // set last name
42 void CommissionEmployee::setLastName(const string &last)
43 {
44 lastName = last; // should validate
45 } // end function setLastName
46
47 // return last name
48 string CommissionEmployee::getLastName() const
49 {
50 return lastName;
51 } // end function getLastName
52
53 // set social security number
54 void CommissionEmployee::setSocialSecurityNumber(const string &ssn)
55 {
56 socialSecurityNumber = ssn; // should validate
57 } // end function setSocialSecurityNumber
58
59 // return social security number
60 string CommissionEmployee::getSocialSecurityNumber() const
61 {
62 return socialSecurityNumber;
63 } // end function getSocialSecurityNumber
64

```

**Fig. 20.23** | CommissionEmployee's constructor and destructor output text. (Part 2 of 3.)



---

```

65 // set gross sales amount
66 void CommissionEmployee::setGrossSales(double sales)
67 {
68 grossSales = (sales < 0.0) ? 0.0 : sales;
69 } // end function setGrossSales
70
71 // return gross sales amount
72 double CommissionEmployee::getGrossSales() const
73 {
74 return grossSales;
75 } // end function getGrossSales
76
77 // set commission rate
78 void CommissionEmployee::setCommissionRate(double rate)
79 {
80 commissionRate = (rate > 0.0 && rate < 1.0) ? rate : 0.0;
81 } // end function setCommissionRate
82
83 // return commission rate
84 double CommissionEmployee::getCommissionRate() const
85 {
86 return commissionRate;
87 } // end function getCommissionRate
88
89 // calculate earnings
90 double CommissionEmployee::earnings() const
91 {
92 return getCommissionRate() * getGrossSales();
93 } // end function earnings
94
95 // print CommissionEmployee object
96 void CommissionEmployee::print() const
97 {
98 cout << "commission employee: "
99 << getFirstName() << ' ' << getLastName()
100 << "\nsocial security number: " << getSocialSecurityNumber()
101 << "\ngross sales: " << getGrossSales()
102 << "\ncommission rate: " << getCommissionRate();
103 } // end function print

```

---

**Fig. 20.23** | CommissionEmployee's constructor and destructor output text. (Part 3 of 3.)

---

```

1 // Fig. 20.24: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class derived from class
3 // CommissionEmployee.
4 #ifndef BASEPLUS_H
5 #define BASEPLUS_H
6
7 #include <string> // C++ standard string class
8 #include "CommissionEmployee.h" // CommissionEmployee class declaration
9 using namespace std;
10

```

---

**Fig. 20.24** | BasePlusCommissionEmployee class header file. (Part 1 of 2.)

---

```

11 class BasePlusCommissionEmployee : public CommissionEmployee
12 {
13 public:
14 BasePlusCommissionEmployee(const string &, const string &,
15 const string &, double = 0.0, double = 0.0, double = 0.0);
16 ~BasePlusCommissionEmployee(); // destructor
17
18 void setBaseSalary(double); // set base salary
19 double getBaseSalary() const; // return base salary
20
21 double earnings() const; // calculate earnings
22 void print() const; // print BasePlusCommissionEmployee object
23 private:
24 double baseSalary; // base salary
25 }; // end class BasePlusCommissionEmployee
26
27 #endif

```

---

**Fig. 20.24** | BasePlusCommissionEmployee class header file. (Part 2 of 2.)

---



---

```

1 // Fig. 20.25: BasePlusCommissionEmployee.cpp
2 // Class BasePlusCommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "BasePlusCommissionEmployee.h"
5 using namespace std;
6
7 // constructor
8 BasePlusCommissionEmployee::BasePlusCommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate, double salary)
11 // explicitly call base-class constructor
12 : CommissionEmployee(first, last, ssn, sales, rate)
13 {
14 setBaseSalary(salary); // validate and store base salary
15
16 cout << "BasePlusCommissionEmployee constructor: " << endl;
17 print();
18 cout << "\n\n";
19 } // end BasePlusCommissionEmployee constructor
20
21 // destructor
22 BasePlusCommissionEmployee::~BasePlusCommissionEmployee()
23 {
24 cout << "BasePlusCommissionEmployee destructor: " << endl;
25 print();
26 cout << "\n\n";
27 } // end BasePlusCommissionEmployee destructor
28
29 // set base salary
30 void BasePlusCommissionEmployee::setBaseSalary(double salary)
31 {

```

---

**Fig. 20.25** | BasePlusCommissionEmployee's constructor and destructor output text. (Part 1 of 2.)

---

```

32 baseSalary = (salary < 0.0) ? 0.0 : salary;
33 } // end function setBaseSalary
34
35 // return base salary
36 double BasePlusCommissionEmployee::getBaseSalary() const
37 {
38 return baseSalary;
39 } // end function getBaseSalary
40
41 // calculate earnings
42 double BasePlusCommissionEmployee::earnings() const
43 {
44 return getBaseSalary() + CommissionEmployee::earnings();
45 } // end function earnings
46
47 // print BasePlusCommissionEmployee object
48 void BasePlusCommissionEmployee::print() const
49 {
50 cout << "base-salaried ";
51
52 // invoke CommissionEmployee's print function
53 CommissionEmployee::print();
54
55 cout << "\nbase salary: " << getBaseSalary();
56 } // end function print

```

---

**Fig. 20.25** | BasePlusCommissionEmployee's constructor and destructor output text. (Part 2 of 2.)

In this example, we modified the `CommissionEmployee` constructor (lines 8–19 of Fig. 20.23) and included a `CommissionEmployee` destructor (lines 22–27), each of which outputs a line of text upon its invocation. We also modified the `BasePlusCommissionEmployee` constructor (lines 8–19 of Fig. 20.25) and included a `BasePlusCommissionEmployee` destructor (lines 22–27), each of which outputs a line of text upon its invocation.

Figure 20.26 demonstrates the order in which constructors and destructors are called for objects of classes that are part of an inheritance hierarchy. Function `main` instantiates `CommissionEmployee` object `employee1` (lines 15–16) in a separate block inside `main` (lines 14–17). The object goes in and out of scope—the end of the block is reached immediately after the object is created—so both the `CommissionEmployee` constructor and destructor are called. Next, lines 20–21 instantiate `BasePlusCommissionEmployee` object `employee2`. This invokes the `CommissionEmployee` constructor to display outputs with values passed from the `BasePlusCommissionEmployee` constructor, then the output specified in the `BasePlusCommissionEmployee` constructor is performed. Lines 24–25 then instantiate `BasePlusCommissionEmployee` object `employee3`. Again, the `CommissionEmployee` and `BasePlusCommissionEmployee` constructors are both called. In each case, the body of the `CommissionEmployee` constructor executes before the body of the `BasePlusCommissionEmployee` constructor executes. When the end of `main` is reached, the destructors are called for objects `employee2` and `employee3`. But, because destructors are called in the reverse order of their corresponding constructors, the `BasePlusCommissionEmployee` destructor and `CommissionEmployee` destructor are called (in that order) for object `employee3`, then

the `BasePlusCommissionEmployee` and `CommissionEmployee` destructors are called (in that order) for object `employee2`.

```

1 // Fig. 20.26: fig20_26.cpp
2 // Display order in which base-class and derived-class constructors
3 // and destructors are called.
4 #include <iostream>
5 #include <iomanip>
6 #include "BasePlusCommissionEmployee.h"
7 using namespace std;
8
9 int main()
10 {
11 // set floating-point output formatting
12 cout << fixed << setprecision(2);
13
14 { // begin new scope
15 CommissionEmployee employee1(
16 "Bob", "Lewis", "333-33-3333", 5000, .04);
17 } // end scope
18
19 cout << endl;
20 BasePlusCommissionEmployee
21 employee2("Lisa", "Jones", "555-55-5555", 2000, .06, 800);
22
23 cout << endl;
24 BasePlusCommissionEmployee
25 employee3("Mark", "Sands", "888-88-8888", 8000, .15, 2000);
26 cout << endl;
27 } // end main

```

CommissionEmployee constructor:  
 commission employee: Bob Lewis  
 social security number: 333-33-3333  
 gross sales: 5000.00  
 commission rate: 0.04

CommissionEmployee destructor:  
 commission employee: Bob Lewis  
 social security number: 333-33-3333  
 gross sales: 5000.00  
 commission rate: 0.04

CommissionEmployee constructor:  
 commission employee: Lisa Jones  
 social security number: 555-55-5555  
 gross sales: 2000.00  
 commission rate: 0.06

BasePlusCommissionEmployee constructor:  
 base-salaried commission employee: Lisa Jones  
 social security number: 555-55-5555

**Fig. 20.26** | Constructor and destructor call order. (Part I of 2.)

```

gross sales: 2000.00
commission rate: 0.06
base salary: 800.00

CommissionEmployee constructor:
commission employee: Mark Sands
social security number: 888-88-8888
gross sales: 8000.00
commission rate: 0.15

BasePlusCommissionEmployee constructor:
base-salaried commission employee: Mark Sands
social security number: 888-88-8888
gross sales: 8000.00
commission rate: 0.15
base salary: 2000.00

BasePlusCommissionEmployee destructor:
base-salaried commission employee: Mark Sands
social security number: 888-88-8888
gross sales: 8000.00
commission rate: 0.15
base salary: 2000.00

CommissionEmployee destructor:
commission employee: Mark Sands
social security number: 888-88-8888
gross sales: 8000.00
commission rate: 0.15

BasePlusCommissionEmployee destructor:
base-salaried commission employee: Lisa Jones
social security number: 555-55-5555
gross sales: 2000.00
commission rate: 0.06
base salary: 800.00

CommissionEmployee destructor:
commission employee: Lisa Jones
social security number: 555-55-5555
gross sales: 2000.00
commission rate: 0.06

```

**Fig. 20.26** | Constructor and destructor call order. (Part 2 of 2.)

## 20.6 public, protected and private Inheritance

When deriving a class from a base class, the base class may be inherited through `public`, `protected` or `private` inheritance. Use of `protected` and `private` inheritance is rare, and each should be used only with great care; we normally use `public` inheritance in this book. Figure 20.27 summarizes for each type of inheritance the accessibility of base-class members in a derived class. The first column contains the base-class access specifiers.

| Base-class member-access specifier | Type of inheritance                                                                                                                                                       |                                                                                                                                                                           |                                                                                                                                                                           |
|------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                    | public inheritance                                                                                                                                                        | protected inheritance                                                                                                                                                     | private inheritance                                                                                                                                                       |
| public                             | <b>public</b> in derived class.<br>Can be accessed directly by member functions, <b>friend</b> functions and nonmember functions.                                         | <b>protected</b> in derived class.<br>Can be accessed directly by member functions and <b>friend</b> functions.                                                           | <b>private</b> in derived class.<br>Can be accessed directly by member functions and <b>friend</b> functions.                                                             |
| protected                          | <b>protected</b> in derived class.<br>Can be accessed directly by member functions and <b>friend</b> functions.                                                           | <b>protected</b> in derived class.<br>Can be accessed directly by member functions and <b>friend</b> functions.                                                           | <b>private</b> in derived class.<br>Can be accessed directly by member functions and <b>friend</b> functions.                                                             |
| private                            | Hidden in derived class.<br>Can be accessed by member functions and <b>friend</b> functions through <b>public</b> or <b>protected</b> member functions of the base class. | Hidden in derived class.<br>Can be accessed by member functions and <b>friend</b> functions through <b>public</b> or <b>protected</b> member functions of the base class. | Hidden in derived class.<br>Can be accessed by member functions and <b>friend</b> functions through <b>public</b> or <b>protected</b> member functions of the base class. |

**Fig. 20.27** | Summary of base-class member accessibility in a derived class.

When deriving a class from a **public** base class, **public** members of the base class become **public** members of the derived class, and **protected** members of the base class become **protected** members of the derived class. A base class's **private** members are never accessible directly from a derived class, but can be accessed through calls to the **public** and **protected** members of the base class.

When deriving from a **protected** base class, **public** and **protected** members of the base class become **protected** members of the derived class. When deriving from a **private** base class, **public** and **protected** members of the base class become **private** members (e.g., the functions become utility functions) of the derived class. **Private** and **protected** inheritance are not *is-a* relationships.

## 20.7 Software Engineering with Inheritance

In this section, we discuss the use of inheritance to customize existing software. When we use inheritance to create a new class from an existing one, the new class inherits the data members and member functions of the existing class, as described in Fig. 20.27. We can customize the new class to meet our needs by including additional members and by redefining base-class members. The derived-class programmer does this in C++ without accessing the base class's source code. The derived class must be able to link to the base class's object code. This powerful capability is attractive to independent software vendors (ISVs).

ISVs can develop proprietary classes for sale or license and make these classes available to users in object-code format. Users then can derive new classes from these library classes rapidly and without accessing the ISVs' proprietary source code. All the ISVs need to supply with the object code are the header files.

Sometimes it's difficult for students to appreciate the scope of problems faced by designers who work on large-scale software projects in industry. People experienced with such projects say that effective software reuse improves the software development process. Object-oriented programming facilitates software reuse, thus shortening development times and enhancing software quality.

The availability of substantial and useful class libraries delivers the maximum benefits of software reuse through inheritance. Just as shrink-wrapped software produced by independent software vendors became an explosive-growth industry with the arrival of the personal computer, interest in the creation and sale of class libraries is growing exponentially. Application designers build their applications with these libraries, and library designers are rewarded by having their libraries included with the applications. The standard C++ libraries that are shipped with C++ compilers tend to be rather general purpose and limited in scope. However, there is massive worldwide commitment to the development of class libraries for a huge variety of applications arenas.



### Software Engineering Observation 20.9

*At the design stage in an object-oriented system, the designer often determines that certain classes are closely related. The designer should “factor out” common attributes and behaviors and place these in a base class, then use inheritance to form derived classes, endowing them with capabilities beyond those inherited from the base class.*



### Software Engineering Observation 20.10

*The creation of a derived class does not affect its base class's source code. Inheritance preserves the integrity of a base class.*



### Performance Tip 20.3

*If classes produced through inheritance are larger than they need to be (i.e., contain too much functionality), memory and processing resources might be wasted. Inherit from the class whose functionality is “closest” to what's needed.*

Reading derived-class definitions can be confusing, because inherited members are not shown physically in the derived classes, but nevertheless are present. A similar problem exists when documenting derived-class members.

## 20.8 Wrap-Up

This chapter introduced inheritance—the ability to create a class by absorbing an existing class's data members and member functions and embellishing them with new capabilities. Through a series of examples using an employee inheritance hierarchy, you learned the notions of base classes and derived classes and used `public` inheritance to create a derived class that inherits members from a base class. The chapter introduced the access specifier `protected`—derived-class member functions can access `protected` base-class members. You learned how to access redefined base-class members by qualifying their names with the base-class name and binary scope resolution operator (`::`). You also saw the order in

which constructors and destructors are called for objects of classes that are part of an inheritance hierarchy. Finally, we explained the three types of inheritance—`public`, `protected` and `private`—and the accessibility of base-class members in a derived class when using each type.

In Chapter 21, we build on our discussion of inheritance by introducing polymorphism—an object-oriented concept that enables us to write programs that handle, in a more general manner, objects of a wide variety of classes related by inheritance. After studying Chapter 21, you'll be familiar with classes, objects, encapsulation, inheritance and polymorphism—the essential concepts of object-oriented programming.

## Summary

### *Section 20.1 Introduction*

- Software reuse reduces program development time and cost.

### *Section 20.2 Base Classes and Derived Classes*

- Inheritance is a form of software reuse in which you create a class that absorbs an existing class's data and behaviors and enhances them with new capabilities. The existing class is called the base class, and the new class is referred to as the derived class.
- A direct base class is the one from which a derived class explicitly inherits. An indirect base class is inherited from two or more levels up the class hierarchy.
- With single inheritance, a class is derived from one base class. With multiple inheritance, a class inherits from multiple (possibly unrelated) base classes.
- A derived class represents a more specialized group of objects. Typically, a derived class contains behaviors inherited from its base class plus additional behaviors. A derived class can also customize behaviors inherited from the base class.
- Every object of a derived class is also an object of that class's base class. However, a base-class object is not an object of that class's derived classes.
- The *is-a* relationship represents inheritance. In an *is-a* relationship, an object of a derived class also can be treated as an object of its base class.
- The *has-a* relationship represents composition—an object contains one or more objects of other classes as members, but does not disclose their behavior directly in its interface.
- A derived class cannot access the `private` members of its base class directly. A derived class can access the `public` and `protected` members of its base class directly.
- A derived class can effect state changes in `private` base-class members, but only through non-`private` member functions provided in the base class and inherited into the derived class.
- A base-class member function can be redefined in a derived class.
- Single-inheritance relationships form treelike hierarchical structures.
- It's possible to treat base-class objects and derived-class objects similarly; the commonality shared between the object types is expressed in the base class's data members and member functions.

### *Section 20.3 protected Members*

- A base class's `public` members are accessible anywhere that the program has a handle to an object of that base class or to an object of one of that base class's derived classes—or, when using the binary scope resolution operator, whenever the class's name is in scope.



- A base class's private members are accessible only within the base class or from its friends.
- A base class's protected members can be accessed by members and friends of that base class and by members and friends of any classes derived from that base class.
- When a derived-class member function redefines a base-class member function, the base-class member function can be accessed from the derived class by qualifying the base-class member function name with the base-class name and the binary scope resolution operator (`::`).

### Section 20.5 Constructors and Destructors in Derived Classes

- When an object of a derived class is instantiated, the base class's constructor is called immediately to initialize the base-class data members in the derived-class object, then the derived-class constructor initializes the additional derived-class data members.
- When a derived-class object is destroyed, the destructors are called in the reverse order of the constructors—first the derived-class destructor is called, then the base-class destructor is called.

### Section 20.6 public, protected and private Inheritance

- Declaring data members private, while providing non-private member functions to manipulate and perform validity checking on this data, enforces good software engineering.
- When deriving a class, the base class may be declared as either public, protected or private.
- When deriving a class from a public base class, public members of the base class become public members of the derived class, and protected members of the base class become protected members of the derived class.
- When deriving a class from a protected base class, public and protected members of the base class become protected members of the derived class.
- When deriving a class from a private base class, public and protected members of the base class become private members of the derived class.

## Terminology

base class 728  
base-class initializer syntax 746  
brittle software 755  
class hierarchy 728  
derived class 728  
direct base class 728  
fragile software 755  
*has-a* relationship 729  
indirect base class 728  
inheritance 728

*is-a* relationship 729  
multiple inheritance 728  
private inheritance 731  
protected inheritance 731  
protected keyword 732  
public inheritance 731  
single inheritance 728  
subclass 728  
superclass 728

## Self-Review Exercises

**20.1** Fill in the blanks in each of the following statements:

- \_\_\_\_\_ is a form of software reuse in which new classes absorb the data and behaviors of existing classes and embellish these classes with new capabilities.
- A base class's \_\_\_\_\_ members can be accessed in the base-class definition, in derived-class definitions and in friends of the base class its derived classes.
- In a(n) \_\_\_\_\_ relationship, an object of a derived class also can be treated as an object of its base class.

- d) In a(n) \_\_\_\_\_ relationship, a class object has one or more objects of other classes as members.
- e) In single inheritance, a class exists in a(n) \_\_\_\_\_ relationship with its derived classes.
- f) A base class's \_\_\_\_\_ members are accessible within that base class and anywhere that the program has a handle to an object of that class or one of its derived classes.
- g) A base class's protected access members have a level of protection between those of public and \_\_\_\_\_ access.
- h) C++ provides for \_\_\_\_\_, which allows a derived class to inherit from many base classes, even if the base classes are unrelated.
- i) When an object of a derived class is instantiated, the base class's \_\_\_\_\_ is called implicitly or explicitly to do any necessary initialization of the base-class data members in the derived-class object.
- j) When deriving a class from a base class with public inheritance, public members of the base class become \_\_\_\_\_ members of the derived class, and protected members of the base class become \_\_\_\_\_ members of the derived class.
- k) When deriving a class from a base class with protected inheritance, public members of the base class become \_\_\_\_\_ members of the derived class, and protected members of the base class become \_\_\_\_\_ members of the derived class.

**20.2** State whether each of the following is *true* or *false*. If *false*, explain why.

- a) Base-class constructors are not inherited by derived classes.
- b) A *has-a* relationship is implemented via inheritance.
- c) A Car class has an *is-a* relationship with the SteeringWheel and Brakes classes.
- d) Inheritance encourages the reuse of proven high-quality software.
- e) When a derived-class object is destroyed, the destructors are called in the reverse order of the constructors.

## Answers to Self-Review Exercises

**20.1** a) Inheritance. b) protected. c) *is-a* or inheritance. d) *has-a* or composition or aggregation. e) hierarchical. f) public. g) private. h) multiple inheritance. i) constructor. j) public, protected. k) protected, protected.

**20.2** a) True. b) False. A *has-a* relationship is implemented via composition. An *is-a* relationship is implemented via inheritance. c) False. This is an example of a *has-a* relationship. Class Car has an *is-a* relationship with class Vehicle. d) True. e) True.

## Exercises

**20.3** (*Composition as an Alternative to Inheritance*) Many programs written with inheritance could be written with composition instead, and vice versa. Rewrite class BasePlusCommissionEmployee of the CommissionEmployee–BasePlusCommissionEmployee hierarchy to use composition rather than inheritance. After you do this, assess the relative merits of the two approaches for designing classes CommissionEmployee and BasePlusCommissionEmployee, as well as for object-oriented programs in general. Which approach is more natural? Why?

**20.4** (*Inheritance Advantage*) Discuss the ways in which inheritance promotes software reuse, saves time during program development and helps prevent errors.

**20.5** (*Protected vs. Private Base Classes*) Some programmers prefer not to use protected access because they believe it breaks the encapsulation of the base class. Discuss the relative merits of using protected access vs. using private access in base classes.

**20.6** (*Student Inheritance Hierarchy*) Draw an inheritance hierarchy for students at a university similar to the hierarchy shown in Fig. 20.2. Use Student as the base class of the hierarchy, then in-

clude classes `UndergraduateStudent` and `GraduateStudent` that derive from `Student`. Continue to extend the hierarchy as deep (i.e., as many levels) as possible. For example, `Freshman`, `Sophomore`, `Junior` and `Senior` might derive from `UndergraduateStudent`, and `DoctoralStudent` and `MastersStudent` might derive from `GraduateStudent`. After drawing the hierarchy, discuss the relationships that exist between the classes. [Note: You do not need to write any code for this exercise.]

**20.7 (Richer Shape Hierarchy)** The world of shapes is much richer than the shapes included in the inheritance hierarchy of Fig. 20.3. Write down all the shapes you can think of—both two-dimensional and three-dimensional—and form them into a more complete `Shape` hierarchy with as many levels as possible. Your hierarchy should have the base class `Shape` from which class `TwoDimensionalShape` and class `ThreeDimensionalShape` are derived. [Note: You do not need to write any code for this exercise.] We'll use this hierarchy in the exercises of Chapter 21 to process a set of distinct shapes as objects of base-class `Shape`. (This technique, called *polymorphism*, is the subject of Chapter 21.)

**20.8 (Quadrilateral Inheritance Hierarchy)** Draw an inheritance hierarchy for classes `Quadrilateral`, `Trapezoid`, `Parallelogram`, `Rectangle` and `Square`. Use `Quadrilateral` as the base class of the hierarchy. Make the hierarchy as deep as possible.

**20.9 (Package Inheritance Hierarchy)** Package-delivery services, such as `FedEx®`, `DHL®` and `UPS®`, offer a number of different shipping options, each with specific costs associated. Create an inheritance hierarchy to represent various types of packages. Use `Package` as the base class of the hierarchy, then include classes `TwoDayPackage` and `OvernightPackage` that derive from `Package`. Base class `Package` should include data members representing the name, address, city, state and ZIP code for both the sender and the recipient of the package, in addition to data members that store the weight (in ounces) and cost per ounce to ship the package. `Package`'s constructor should initialize these data members. Ensure that the weight and cost per ounce contain positive values. `Package` should provide a `public` member function `calculateCost` that returns a `double` indicating the cost associated with shipping the package. `Package`'s `calculateCost` function should determine the cost by multiplying the weight by the cost per ounce. Derived class `TwoDayPackage` should inherit the functionality of base class `Package`, but also include a data member that represents a flat fee that the shipping company charges for two-day-delivery service. `TwoDayPackage`'s constructor should receive a value to initialize this data member. `TwoDayPackage` should redefine member function `calculateCost` so that it computes the shipping cost by adding the flat fee to the weight-based cost calculated by base class `Package`'s `calculateCost` function. Class `OvernightPackage` should inherit directly from class `Package` and contain an additional data member representing an additional fee per ounce charged for overnight-delivery service. `OvernightPackage` should redefine member function `calculateCost` so that it adds the additional fee per ounce to the standard cost per ounce before calculating the shipping cost. Write a test program that creates objects of each type of `Package` and tests member function `calculateCost`.

**20.10 (Account Inheritance Hierarchy)** Create an inheritance hierarchy that a bank might use to represent customers' bank accounts. All customers at this bank can deposit (i.e., credit) money into their accounts and withdraw (i.e., debit) money from their accounts. More specific types of accounts also exist. Savings accounts, for instance, earn interest on the money they hold. Checking accounts, on the other hand, charge a fee per transaction (i.e., credit or debit).

Create an inheritance hierarchy containing base class `Account` and derived classes `SavingsAccount` and `CheckingAccount` that inherit from class `Account`. Base class `Account` should include one data member of type `double` to represent the account balance. The class should provide a constructor that receives an initial balance and uses it to initialize the data member. The constructor should validate the initial balance to ensure that it's greater than or equal to 0.0. If not, the balance should be set to 0.0 and the constructor should display an error message, indicating that the initial balance was invalid. The class should provide three member functions. Member function `credit`

should add an amount to the current balance. Member function `debit` should withdraw money from the `Account` and ensure that the debit amount does not exceed the `Account`'s balance. If it does, the balance should be left unchanged and the function should print the message "Debit amount exceeded account balance." Member function `getBalance` should return the current balance.

Derived class `SavingsAccount` should inherit the functionality of an `Account`, but also include a data member of type `double` indicating the interest rate (percentage) assigned to the `Account`. `SavingsAccount`'s constructor should receive the initial balance, as well as an initial value for the `SavingsAccount`'s interest rate. `SavingsAccount` should provide a public member function `calculateInterest` that returns a `double` indicating the amount of interest earned by an account. Member function `calculateInterest` should determine this amount by multiplying the interest rate by the account balance. [Note: `SavingsAccount` should inherit member functions `credit` and `debit` as is without redefining them.]

Derived class `CheckingAccount` should inherit from base class `Account` and include an additional data member of type `double` that represents the fee charged per transaction. `CheckingAccount`'s constructor should receive the initial balance, as well as a parameter indicating a fee amount. Class `CheckingAccount` should redefine member functions `credit` and `debit` so that they subtract the fee from the account balance whenever either transaction is performed successfully. `CheckingAccount`'s versions of these functions should invoke the base-class `Account` version to perform the updates to an account balance. `CheckingAccount`'s `debit` function should charge a fee only if money is actually withdrawn (i.e., the debit amount does not exceed the account balance). [Hint: Define `Account`'s `debit` function so that it returns a `bool` indicating whether money was withdrawn. Then use the return value to determine whether a fee should be charged.]

After defining the classes in this hierarchy, write a program that creates objects of each class and tests their member functions. Add interest to the `SavingsAccount` object by first invoking its `calculateInterest` function, then passing the returned interest amount to the object's `credit` function.

# 21

## Object-Oriented Programming: Polymorphism

*One Ring to rule them all,  
One Ring to find them,  
One Ring to bring them all  
and in the darkness bind them.*

—John Ronald Reuel Tolkien

*The silence often of pure  
innocence  
Persuades when speaking fails.*

—William Shakespeare

*General propositions do not  
decide concrete cases.*

—Oliver Wendell Holmes

*A philosopher of imposing  
stature doesn't think in a  
vacuum. Even his most abstract  
ideas are, to some extent,  
conditioned by what is or is not  
known in the time when he lives.*

—Alfred North Whitehead

### Objectives

In this chapter you'll learn:

- How polymorphism makes programming more convenient and systems more extensible.
- The distinction between abstract and concrete classes and how to create abstract classes.
- To use runtime type information (RTTI).
- How C++ implements `virtual` functions and dynamic binding.
- How `virtual` destructors ensure that all appropriate destructors run on an object.





- 21.1** Introduction
- 21.2** Polymorphism Examples
- 21.3** Relationships Among Objects in an Inheritance Hierarchy
  - 21.3.1 Invoking Base-Class Functions from Derived-Class Objects
  - 21.3.2 Aiming Derived-Class Pointers at Base-Class Objects
  - 21.3.3 Derived-Class Member-Function Calls via Base-Class Pointers
  - 21.3.4 Virtual Functions
  - 21.3.5 Summary of the Allowed Assignments Between Base-Class and Derived-Class Objects and Pointers
- 21.4** Type Fields and `switch` Statements
- 21.5** Abstract Classes and Pure `virtual` Functions
- 21.6** Case Study: Payroll System Using Polymorphism
  - 21.6.1 Creating Abstract Base Class `Employee`
  - 21.6.2 Creating Concrete Derived Class `SalariedEmployee`
  - 21.6.3 Creating Concrete Derived Class `HourlyEmployee`
  - 21.6.4 Creating Concrete Derived Class `CommissionEmployee`
  - 21.6.5 Creating Indirect Concrete Derived Class `BasePlusCommissionEmployee`
  - 21.6.6 Demonstrating Polymorphic Processing
- 21.7** (Optional) Polymorphism, Virtual Functions and Dynamic Binding “Under the Hood”
- 21.8** Case Study: Payroll System Using Polymorphism and Runtime Type Information with Downcasting, `dynamic_cast`, `typeid` and `type_info`
- 21.9** Virtual Destructors
- 21.10** Wrap-Up

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises | Making a Difference*

## 21.1 Introduction

In Chapters 15–20, we discussed key object-oriented programming technologies including classes, objects, encapsulation, operator overloading and inheritance. We now continue our study of OOP by explaining and demonstrating **polymorphism** with inheritance hierarchies. Polymorphism enables us to “program in the general” rather than “program in the specific.” In particular, polymorphism enables us to write programs that process objects of classes that are part of the same class hierarchy as if they were all objects of the hierarchy’s base class. As we’ll soon see, polymorphism works off base-class pointer handles and base-class reference handles, but not off name handles.

Suppose we create a polymorphic program that simulates the movement of several types of animals for a biological study. Classes `Fish`, `Frog` and `Bird` represent the three types of animals under investigation. Imagine that each of these classes inherits from base class `Animal`, which contains a function `move` and maintains an animal’s current location. Each derived class implements `move`. Our program maintains a vector of `Animal` pointers to objects of the derived classes. To simulate the animals’ movements, the program sends each object the same message once per second—namely, `move`. However, each specific type of `Animal` responds to a `move` message in its own way—a `Fish` might swim two feet, a `Frog` might jump three feet and a `Bird` might fly ten feet. The program issues the same message (i.e., `move`) to each animal object, but each object knows how to modify its location for its specific type of movement. Relying on each object to know how to “do the right thing” in response to the same function call is the key concept of polymorphism. The same message sent to a variety of objects has “many forms” of results—hence the term polymorphism.

With polymorphism, we can design and implement systems that are easily extensible—new classes can be added with little or no modification to the general portions of the program, as long as the new classes are part of the inheritance hierarchy that the program processes generically. The only parts of a program that must be altered to accommodate new classes are those that require direct knowledge of the new classes that you add to the hierarchy. For example, if we create class `Tortoise` that inherits from class `Animal` (which might respond to a move message by crawling one inch), we need to write only the `Tortoise` class and the part of the simulation that instantiates a `Tortoise` object. The portions of the simulation that process each `Animal` generically can remain the same.

We begin with a sequence of small, focused examples that lead up to an understanding of virtual functions and dynamic binding—polymorphism’s two underlying technologies. We then present a case study that revisits Chapter 20’s `Employee` hierarchy. In the case study, we define a common “interface” (i.e., set of functionality) for all the classes in the hierarchy. This common functionality among employees is defined in a so-called abstract base class, `Employee`, from which classes `SalariedEmployee`, `HourlyEmployee` and `CommissionEmployee` inherit directly and class `BaseCommissionEmployee` inherits indirectly. We’ll soon see what makes a class “abstract” or its opposite—“concrete.”

In this hierarchy, every employee has an `earnings` function to calculate the employee’s weekly pay. These earnings functions vary by employee type—for instance, `SalariedEmployees` are paid a fixed weekly salary regardless of the number of hours worked, while `HourlyEmployees` are paid by the hour and receive overtime pay. We show how to process each employee “in the general”—that is, using base-class pointers to call the `earnings` function of several derived-class objects. This way, you need to be concerned with only one type of function call, which can be used to execute several different functions based on the objects referred to by the base-class pointers.

A key feature of this chapter is its (optional) detailed discussion of polymorphism, virtual functions and dynamic binding “under the hood,” which uses a detailed diagram to explain how polymorphism can be implemented in C++.

Occasionally, when performing polymorphic processing, we need to program “in the specific,” meaning that operations need to be performed on a specific type of object in a hierarchy—the operation cannot be generally applied to several types of objects. We reuse our `Employee` hierarchy to demonstrate the powerful capabilities of **runtime type information (RTTI)** and **dynamic casting**, which enable a program to determine the type of an object at execution time and act on that object accordingly. We use these capabilities to determine whether a particular employee object is a `BasePlusCommissionEmployee`, then give that employee a 10 percent bonus on his or her base salary.

## 21.2 Polymorphism Examples

In this section, we discuss several polymorphism examples. With polymorphism, one function can cause different actions to occur, depending on the type of the object on which the function is invoked. This gives you tremendous expressive capability. If class `Rectangle` is derived from class `Quadrilateral`, then a `Rectangle` object is a more specific version of a `Quadrilateral` object. Therefore, any operation (such as calculating the perimeter or the area) that can be performed on an object of class `Quadrilateral` also can be performed on an object of class `Rectangle`. Such operations also can be performed on other kinds of `Quadrilaterals`, such as `Squares`, `Parallelograms` and `Trapezoids`. The poly-

morphism occurs when a program invokes a virtual function through a base-class (i.e., `Quadrilateral`) pointer or reference—C++ dynamically (i.e., at execution time) chooses the correct function for the class from which the object was instantiated. You’ll see a code example that illustrates this process in Section 21.3.

As another example, suppose that we design a video game that manipulates objects of many different types, including objects of classes `Martian`, `Venutian`, `Plutonian`, `SpaceShip` and `LaserBeam`. Imagine that each of these classes inherits from the common base class `SpaceObject`, which contains member function `draw`. Each derived class implements this function in a manner appropriate for that class. A screen-manager program maintains a container (e.g., a vector) that holds `SpaceObject` pointers to objects of the various classes. To refresh the screen, the screen manager periodically sends each object the same message—namely, `draw`. Each type of object responds in a unique way. For example, a `Martian` object might draw itself in red with the appropriate number of antennae. A `SpaceShip` object might draw itself as a silver flying saucer. A `LaserBeam` object might draw itself as a bright red beam across the screen. Again, the same message (in this case, `draw`) sent to a variety of objects has “many forms” of results.

A polymorphic screen manager facilitates adding new classes to a system with minimal modifications to its code. Suppose that we want to add objects of class `Mercurian` to our video game. To do so, we must build a class `Mercurian` that inherits from `SpaceObject`, but provides its own definition of member function `draw`. Then, when pointers to objects of class `Mercurian` appear in the container, you do not need to modify the code for the screen manager. The screen manager invokes member function `draw` on every object in the container, regardless of the object’s type, so the new `Mercurian` objects simply “plug right in.” Thus, without modifying the system (other than to build and include the classes themselves), you can use polymorphism to accommodate additional classes, including ones that were not even envisioned when the system was created.



#### Software Engineering Observation 21.1

*With virtual functions and polymorphism, you can deal in generalities and let the execution-time environment concern itself with the specifics. You can direct a variety of objects to behave in manners appropriate to those objects without even knowing their types—as long as those objects belong to the same inheritance hierarchy and are being accessed off a common base-class pointer or a common base-class reference.*



#### Software Engineering Observation 21.2

*Polymorphism promotes extensibility: Software written to invoke polymorphic behavior is written independently of the types of the objects to which messages are sent. Thus, new types of objects that can respond to existing messages can be incorporated into such a system without modifying the base system. Only client code that instantiates new objects must be modified to accommodate new types.*

## 21.3 Relationships Among Objects in an Inheritance Hierarchy

Section 20.4 created an employee class hierarchy, in which class `BasePlusCommissionEmployee` inherited from class `CommissionEmployee`. The Chapter 20 examples manipulated `CommissionEmployee` and `BasePlusCommissionEmployee` objects by using the



objects' names to invoke their member functions. We now examine the relationships among classes in a hierarchy more closely. The next several sections present a series of examples that demonstrate how base-class and derived-class pointers can be aimed at base-class and derived-class objects, and how those pointers can be used to invoke member functions that manipulate those objects. In Section 21.3.4, we demonstrate how to get polymorphic behavior from base-class pointers aimed at derived-class objects.

In Section 21.3.1, we assign the address of a derived-class object to a base-class pointer, then show that invoking a function via the base-class pointer invokes the base-class functionality—i.e., the type of the handle determines which function is called. In Section 21.3.2, we assign the address of a base-class object to a derived-class pointer, which results in a compilation error. We discuss the error message and investigate why the compiler does not allow such an assignment. In Section 21.3.3, we assign the address of a derived-class object to a base-class pointer, then examine how the base-class pointer can be used to invoke only the base-class functionality—when we attempt to invoke derived-class member functions through the base-class pointer, compilation errors occur. Finally, in Section 21.3.4, we introduce `virtual` functions and polymorphism by declaring a base-class function as `virtual`. We then assign the address of a derived-class object to the base-class pointer and use that pointer to invoke derived-class functionality—precisely the capability we need to achieve polymorphic behavior.

A key concept in these examples is to demonstrate that an object of a derived class can be treated as an object of its base class. This enables various interesting manipulations. For example, a program can create an array of base-class pointers that point to objects of many derived-class types. Despite the fact that the derived-class objects are of different types, the compiler allows this because each derived-class object *is an* object of its base class. However, we cannot treat a base-class object as an object of any of its derived classes. For example, a `CommissionEmployee` is not a `BasePlusCommissionEmployee` in the hierarchy defined in Chapter 20—a `CommissionEmployee` does not have a `baseSalary` data member and does not have member functions `setBaseSalary` and `getBaseSalary`. The *is-a* relationship applies only from a derived class to its direct and indirect base classes.

### 21.3.1 Invoking Base-Class Functions from Derived-Class Objects

The example in Figs. 21.1–21.5 demonstrates three ways to aim base and derived-class pointers at base and derived-class objects. The first two are straightforward—we aim a base-class pointer at a base-class object (and invoke base-class functionality), and we aim a derived-class pointer at a derived-class object (and invoke derived-class functionality). Then, we demonstrate the relationship between derived classes and base classes (i.e., the *is-a* relationship of inheritance) by aiming a base-class pointer at a derived-class object (and showing that the base-class functionality is indeed available in the derived-class object).

Class `CommissionEmployee` (Figs. 21.1–21.2), which we discussed in Chapter 20, is used to represent employees who are paid a percentage of their sales. Class `BasePlusCommissionEmployee` (Figs. 21.3–21.4), which we also discussed in Chapter 20, is used to represent employees who receive a base salary plus a percentage of their sales. Each `BasePlusCommissionEmployee` object *is a* `CommissionEmployee` that also has a base salary. Class `BasePlusCommissionEmployee`'s `earnings` member function (lines 30–33 of Fig. 21.4) redefines class `CommissionEmployee`'s `earnings` member function (lines 78–81 of Fig. 21.2) to include the object's base salary. Class `BasePlusCommissionEmployee`'s

print member function (lines 36–44 of Fig. 21.4) redefines class `CommissionEmployee`'s version (lines 84–91 of Fig. 21.2) to display the same information plus the employee's base salary.

---

```

1 // Fig. 21.1: CommissionEmployee.h
2 // CommissionEmployee class definition represents a commission employee.
3 #ifndef COMMISSION_H
4 #define COMMISSION_H
5
6 #include <string> // C++ standard string class
7 using namespace std;
8
9 class CommissionEmployee
10 {
11 public:
12 CommissionEmployee(const string &, const string &, const string &,
13 double = 0.0, double = 0.0);
14
15 void setFirstName(const string &); // set first name
16 string getFirstName() const; // return first name
17
18 void setLastName(const string &); // set last name
19 string getLastName() const; // return last name
20
21 void setSocialSecurityNumber(const string &); // set SSN
22 string getSocialSecurityNumber() const; // return SSN
23
24 void setGrossSales(double); // set gross sales amount
25 double getGrossSales() const; // return gross sales amount
26
27 void setCommissionRate(double); // set commission rate
28 double getCommissionRate() const; // return commission rate
29
30 double earnings() const; // calculate earnings
31 void print() const; // print CommissionEmployee object
32 private:
33 string firstName;
34 string lastName;
35 string socialSecurityNumber;
36 double grossSales; // gross weekly sales
37 double commissionRate; // commission percentage
38 }; // end class CommissionEmployee
39
40 #endif

```

---

**Fig. 21.1** | `CommissionEmployee` class header file.

---

```

1 // Fig. 21.2: CommissionEmployee.cpp
2 // Class CommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "CommissionEmployee.h" // CommissionEmployee class definition

```

---

**Fig. 21.2** | `CommissionEmployee` class implementation file. (Part I of 3.)

---

```

5 using namespace std;
6
7 // constructor
8 CommissionEmployee::CommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate)
11 : firstName(first), lastName(last), socialSecurityNumber(ssn)
12 {
13 setGrossSales(sales); // validate and store gross sales
14 setCommissionRate(rate); // validate and store commission rate
15 } // end CommissionEmployee constructor
16
17 // set first name
18 void CommissionEmployee::setFirstName(const string &first)
19 {
20 firstName = first; // should validate
21 } // end function setFirstName
22
23 // return first name
24 string CommissionEmployee::getFirstName() const
25 {
26 return firstName;
27 } // end function getFirstName
28
29 // set last name
30 void CommissionEmployee::setLastName(const string &last)
31 {
32 lastName = last; // should validate
33 } // end function setLastName
34
35 // return last name
36 string CommissionEmployee::getLastName() const
37 {
38 return lastName;
39 } // end function getLastName
40
41 // set social security number
42 void CommissionEmployee::setSocialSecurityNumber(const string &ssn)
43 {
44 socialSecurityNumber = ssn; // should validate
45 } // end function setSocialSecurityNumber
46
47 // return social security number
48 string CommissionEmployee::getSocialSecurityNumber() const
49 {
50 return socialSecurityNumber;
51 } // end function getSocialSecurityNumber
52
53 // set gross sales amount
54 void CommissionEmployee::setGrossSales(double sales)
55 {
56 grossSales = (sales < 0.0) ? 0.0 : sales;
57 } // end function setGrossSales

```

---

**Fig. 21.2** | CommissionEmployee class implementation file. (Part 2 of 3.)

---

```

58
59 // return gross sales amount
60 double CommissionEmployee::getGrossSales() const
61 {
62 return grossSales;
63 } // end function getGrossSales
64
65 // set commission rate
66 void CommissionEmployee::setCommissionRate(double rate)
67 {
68 commissionRate = (rate > 0.0 && rate < 1.0) ? rate : 0.0;
69 } // end function setCommissionRate
70
71 // return commission rate
72 double CommissionEmployee::getCommissionRate() const
73 {
74 return commissionRate;
75 } // end function getCommissionRate
76
77 // calculate earnings
78 double CommissionEmployee::earnings() const
79 {
80 return getCommissionRate() * getGrossSales();
81 } // end function earnings
82
83 // print CommissionEmployee object
84 void CommissionEmployee::print() const
85 {
86 cout << "commission employee: "
87 << getFirstName() << ' ' << getLastName()
88 << "\nsocial security number: " << getSocialSecurityNumber()
89 << "\ngross sales: " << getGrossSales()
90 << "\ncommission rate: " << getCommissionRate();
91 } // end function print

```

---

**Fig. 21.2** | CommissionEmployee class implementation file. (Part 3 of 3.)

---

```

1 // Fig. 21.3: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class derived from class
3 // CommissionEmployee.
4 #ifndef BASEPLUS_H
5 #define BASEPLUS_H
6
7 #include <string> // C++ standard string class
8 #include "CommissionEmployee.h" // CommissionEmployee class declaration
9 using namespace std;
10
11 class BasePlusCommissionEmployee : public CommissionEmployee
12 {
13 public:
14 BasePlusCommissionEmployee(const string &, const string &,
15 const string &, double = 0.0, double = 0.0, double = 0.0);

```

---

**Fig. 21.3** | BasePlusCommissionEmployee class header file. (Part 1 of 2.)

---

```

16
17 void setBaseSalary(double); // set base salary
18 double getBaseSalary() const; // return base salary
19
20 double earnings() const; // calculate earnings
21 void print() const; // print BasePlusCommissionEmployee object
22 private:
23 double baseSalary; // base salary
24 }; // end class BasePlusCommissionEmployee
25
26 #endif

```

---

**Fig. 21.3** | BasePlusCommissionEmployee class header file. (Part 2 of 2.)

---

```

1 // Fig. 21.4: BasePlusCommissionEmployee.cpp
2 // Class BasePlusCommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "BasePlusCommissionEmployee.h"
5 using namespace std;
6
7 // constructor
8 BasePlusCommissionEmployee::BasePlusCommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate, double salary)
11 // explicitly call base-class constructor
12 : CommissionEmployee(first, last, ssn, sales, rate)
13 {
14 setBaseSalary(salary); // validate and store base salary
15 } // end BasePlusCommissionEmployee constructor
16
17 // set base salary
18 void BasePlusCommissionEmployee::setBaseSalary(double salary)
19 {
20 baseSalary = (salary < 0.0) ? 0.0 : salary;
21 } // end function setBaseSalary
22
23 // return base salary
24 double BasePlusCommissionEmployee::getBaseSalary() const
25 {
26 return baseSalary;
27 } // end function getBaseSalary
28
29 // calculate earnings
30 double BasePlusCommissionEmployee::earnings() const
31 {
32 return getBaseSalary() + CommissionEmployee::earnings();
33 } // end function earnings
34
35 // print BasePlusCommissionEmployee object
36 void BasePlusCommissionEmployee::print() const
37 {
38 cout << "base-salaried ";

```

---

**Fig. 21.4** | BasePlusCommissionEmployee class implementation file. (Part 1 of 2.)

---

```

39
40 // invoke CommissionEmployee's print function
41 CommissionEmployee::print();
42
43 cout << "\nbase salary: " << getBaseSalary();
44 } // end function print

```

---

**Fig. 21.4** | BasePlusCommissionEmployee class implementation file. (Part 2 of 2.)

In Fig. 21.5, lines 13–14 create a `CommissionEmployee` object and line 17 creates a pointer to a `CommissionEmployee` object; lines 20–21 create a `BasePlusCommissionEmployee` object and line 24 creates a pointer to a `BasePlusCommissionEmployee` object. Lines 31 and 33 use each object’s name to invoke its `print` member function. Line 36 assigns the address of base-class object `commissionEmployee` to base-class pointer `commissionEmployeePtr`, which line 39 uses to invoke member function `print` on that `CommissionEmployee` object. This invokes the version of `print` defined in base class `CommissionEmployee`. Similarly, line 42 assigns the address of derived-class object `basePlusCommissionEmployee` to derived-class pointer `basePlusCommissionEmployeePtr`, which line 46 uses to invoke member function `print` on that `BasePlusCommissionEmployee` object. This invokes the version of `print` defined in derived class `BasePlusCommissionEmployee`. Line 49 then assigns the address of derived-class object `basePlusCommissionEmployee` to base-class pointer `commissionEmployeePtr`, which line 53 uses to invoke member function `print`. This “crossover” is allowed because an object of a derived class *is an* object of its base class. Note that despite the fact that the base class `CommissionEmployee` pointer points to a derived class `BasePlusCommissionEmployee` object, the base class `CommissionEmployee`’s `print` member function is invoked (rather than `BasePlusCommissionEmployee`’s `print` function). The output of each `print` member-function invocation in this program reveals that *the invoked functionality depends on the type of the handle (i.e., the pointer or reference type) used to invoke the function, not the type of the object to which the handle points*. In Section 21.3.4, when we introduce virtual functions, we demonstrate that it’s possible to invoke the object type’s functionality, rather than invoke the handle type’s functionality. We’ll see that this is crucial to implementing polymorphic behavior—the key topic of this chapter.

---

```

1 // Fig. 21.5: fig21_05.cpp
2 // Aiming base-class and derived-class pointers at base-class
3 // and derived-class objects, respectively.
4 #include <iostream>
5 #include <iomanip>
6 #include "CommissionEmployee.h"
7 #include "BasePlusCommissionEmployee.h"
8 using namespace std;
9
10 int main()
11 {

```

---

**Fig. 21.5** | Assigning addresses of base-class and derived-class objects to base-class and derived-class pointers. (Part 1 of 3.)

```

12 // create base-class object
13 CommissionEmployee commissionEmployee(
14 "Sue", "Jones", "222-22-2222", 10000, .06);
15
16 // create base-class pointer
17 CommissionEmployee *commissionEmployeePtr = 0;
18
19 // create derived-class object
20 BasePlusCommissionEmployee basePlusCommissionEmployee(
21 "Bob", "Lewis", "333-33-3333", 5000, .04, 300);
22
23 // create derived-class pointer
24 BasePlusCommissionEmployee *basePlusCommissionEmployeePtr = 0;
25
26 // set floating-point output formatting
27 cout << fixed << setprecision(2);
28
29 // output objects commissionEmployee and basePlusCommissionEmployee
30 cout << "Print base-class and derived-class objects:\n\n";
31 commissionEmployee.print(); // invokes base-class print
32 cout << "\n\n";
33 basePlusCommissionEmployee.print(); // invokes derived-class print
34
35 // aim base-class pointer at base-class object and print
36 commissionEmployeePtr = &commissionEmployee; // perfectly natural
37 cout << "\n\n\nCalling print with base-class pointer to "
38 << "\nbase-class object invokes base-class print function:\n\n";
39 commissionEmployeePtr->print(); // invokes base-class print
40
41 // aim derived-class pointer at derived-class object and print
42 basePlusCommissionEmployeePtr = &basePlusCommissionEmployee; // natural
43 cout << "\n\n\nCalling print with derived-class pointer to "
44 << "\nderived-class object invokes derived-class "
45 << "print function:\n\n";
46 basePlusCommissionEmployeePtr->print(); // invokes derived-class print
47
48 // aim base-class pointer at derived-class object and print
49 commissionEmployeePtr = &basePlusCommissionEmployee;
50 cout << "\n\n\nCalling print with base-class pointer to "
51 << "derived-class object\ninvokes base-class print "
52 << "function on that derived-class object:\n\n";
53 commissionEmployeePtr->print(); // invokes base-class print
54 cout << endl;
55 } // end main

```

Print base-class and derived-class objects:

```

commission employee: Sue Jones
social security number: 222-22-2222
gross sales: 10000.00
commission rate: 0.06

```

**Fig. 21.5** | Assigning addresses of base-class and derived-class objects to base-class and derived-class pointers. (Part 2 of 3.)

```
base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 300.00
```

Calling print with base-class pointer to  
base-class object invokes base-class print function:

```
commission employee: Sue Jones
social security number: 222-22-2222
gross sales: 10000.00
commission rate: 0.06
```

Calling print with derived-class pointer to  
derived-class object invokes derived-class print function:

```
base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 300.00
```

Calling print with base-class pointer to derived-class object  
invokes base-class print function on that derived-class object:

```
commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
```

**Fig. 21.5** | Assigning addresses of base-class and derived-class objects to base-class and derived-class pointers. (Part 3 of 3.)

### 21.3.2 Aiming Derived-Class Pointers at Base-Class Objects

In Section 21.3.1, we assigned the address of a derived-class object to a base-class pointer and explained that the C++ compiler allows this assignment, because a derived-class object *is a* base-class object. We take the opposite approach in Fig. 21.6, as we aim a derived-class pointer at a base-class object. [Note: This program uses classes `CommissionEmployee` and `BasePlusCommissionEmployee` of Figs. 21.1–21.4.] Lines 8–9 of Fig. 21.6 create a `CommissionEmployee` object, and line 10 creates a `BasePlusCommissionEmployee` pointer. Line 14 attempts to assign the address of base-class object `commissionEmployee` to derived-class pointer `basePlusCommissionEmployeePtr`, but the C++ compiler generates an error. The compiler prevents this assignment, because a `CommissionEmployee` is not a `BasePlusCommissionEmployee`. Consider the consequences if the compiler were to allow this assignment. Through a `BasePlusCommissionEmployee` pointer, we can invoke every `BasePlusCommissionEmployee` member function, including `setBaseSalary`, for the object to which the pointer points (i.e., the base-class object `commissionEmployee`). However, the `CommissionEmployee` object does not provide a `setBaseSalary` member function,



nor does it provide a `baseSalary` data member to set. This could lead to problems, because member function `setBaseSalary` would assume that there is a `baseSalary` data member to set at its “usual location” in a `BasePlusCommissionEmployee` object. This memory does not belong to the `CommissionEmployee` object, so member function `setBaseSalary` might overwrite other important data in memory, possibly data that belongs to a different object.

```

1 // Fig. 21.6: fig21_06.cpp
2 // Aiming a derived-class pointer at a base-class object.
3 #include "CommissionEmployee.h"
4 #include "BasePlusCommissionEmployee.h"
5
6 int main()
7 {
8 CommissionEmployee commissionEmployee(
9 "Sue", "Jones", "222-22-2222", 10000, .06);
10 BasePlusCommissionEmployee *basePlusCommissionEmployeePtr = 0;
11
12 // aim derived-class pointer at base-class object
13 // Error: a CommissionEmployee is not a BasePlusCommissionEmployee
14 basePlusCommissionEmployeePtr = &commissionEmployee;
15 } // end main

```

*Microsoft Visual C++ compiler error messages:*

```

C:\examples\ch21\Fig21_06\fig21_06.cpp(14) : error C2440: '=' :
cannot convert from 'CommissionEmployee *' to 'BasePlusCommissionEmployee *'
 Cast from base to derived requires dynamic_cast or static_cast

```

*GNU C++ compiler error messages:*

```

fig21_06.cpp:14: error: invalid conversion from 'CommissionEmployee*' to
'BasePlusCommissionEmployee*'

```

**Fig. 21.6** | Aiming a derived-class pointer at a base-class object.

### 21.3.3 Derived-Class Member-Function Calls via Base-Class Pointers

Off a base-class pointer, the compiler allows us to invoke only base-class member functions. Thus, if a base-class pointer is aimed at a derived-class object, and an attempt is made to access a *derived-class-only member function*, a compilation error will occur.

Figure 21.7 shows the consequences of attempting to invoke a derived-class member function off a base-class pointer. [Note: We’re again using classes `CommissionEmployee` and `BasePlusCommissionEmployee` of Figs. 21.1–21.4.] Line 9 creates `commissionEmployeePtr`—a pointer to a `CommissionEmployee` object—and lines 10–11 create a `BasePlusCommissionEmployee` object. Line 14 aims `commissionEmployeePtr` at derived-class object `basePlusCommissionEmployee`. Recall from Section 21.3.1 that this is allowed, because a `BasePlusCommissionEmployee` *is a* `CommissionEmployee` (in the sense that a `BasePlusCommissionEmployee` object contains all the functionality of a `CommissionEmployee` object). Lines 18–22 invoke base-class member functions `getFirstName`, `getLastName`, `getSocialSecurityNumber`, `getGrossSales` and `getCommissionRate` off the

base-class pointer. All of these calls are legitimate, because `BasePlusCommissionEmployee` inherits these member functions from `CommissionEmployee`. We know that `commissionEmployeePtr` is aimed at a `BasePlusCommissionEmployee` object, so in lines 26–27 we attempt to invoke `BasePlusCommissionEmployee` member functions `getBaseSalary` and `setBaseSalary`. The compiler generates errors on both of these calls, because they're not made to member functions of base-class `CommissionEmployee`. The handle can be used to invoke only those functions that are members of that handle's associated class type. (In this case, off a `CommissionEmployee *`, we can invoke only `CommissionEmployee` member functions `setFirstName`, `getFirstName`, `setLastName`, `getLastName`, `setSocialSecurityNumber`, `getSocialSecurityNumber`, `setGrossSales`, `getGrossSales`, `setCommissionRate`, `getCommissionRate`, `earnings` and `print`.)

```

1 // Fig. 21.7: fig21_07.cpp
2 // Attempting to invoke derived-class-only member functions
3 // through a base-class pointer.
4 #include "CommissionEmployee.h"
5 #include "BasePlusCommissionEmployee.h"
6
7 int main()
8 {
9 CommissionEmployee *commissionEmployeePtr = 0; // base class
10 BasePlusCommissionEmployee basePlusCommissionEmployee(
11 "Bob", "Lewis", "333-33-3333", 5000, .04, 300); // derived class
12
13 // aim base-class pointer at derived-class object
14 commissionEmployeePtr = &basePlusCommissionEmployee;
15
16 // invoke base-class member functions on derived-class
17 // object through base-class pointer (allowed)
18 string firstName = commissionEmployeePtr->getFirstName();
19 string lastName = commissionEmployeePtr->getLastName();
20 string ssn = commissionEmployeePtr->getSocialSecurityNumber();
21 double grossSales = commissionEmployeePtr->getGrossSales();
22 double commissionRate = commissionEmployeePtr->getCommissionRate();
23
24 // attempt to invoke derived-class-only member functions
25 // on derived-class object through base-class pointer (disallowed)
26 double baseSalary = commissionEmployeePtr->getBaseSalary();
27 commissionEmployeePtr->setBaseSalary(500);
28 } // end main

```

*Microsoft Visual C++ compiler error messages:*

```

C:\examples\ch21\Fig21_07\fig21_07.cpp(26) : error C2039:
'getBaseSalary' : is not a member of 'CommissionEmployee'
C:\cpphttp7_examples\ch21\Fig21_07\CommissionEmployee.h(10) :
 see declaration of 'CommissionEmployee'
C:\examples\ch21\Fig21_07\fig21_07.cpp(27) : error C2039:
'setBaseSalary' : is not a member of 'CommissionEmployee'
C:\cpphttp7_examples\ch21\Fig21_07\CommissionEmployee.h(10) :
 see declaration of 'CommissionEmployee'

```

**Fig. 21.7** | Attempting to invoke derived-class-only functions via a base-class pointer. (Part I of 2.)

GNU C++ compiler error messages:

```
fig21_07.cpp:26: error: `getBaseSalary' undeclared (first use this function)
fig21_07.cpp:26: error: (Each undeclared identifier is reported only once for
 each function it appears in.)
fig21_07.cpp:27: error: `setBaseSalary' undeclared (first use this function)
```

**Fig. 21.7** | Attempting to invoke derived-class-only functions via a base-class pointer. (Part 2 of 2.)

The compiler allows access to derived-class-only members from a base-class pointer that is aimed at a derived-class object *if* we explicitly cast the base-class pointer to a derived-class pointer—known as **downcasting**. As you know, it's possible to aim a base-class pointer at a derived-class object. However, as we demonstrated in Fig. 21.7, a base-class pointer can be used to invoke only the functions declared in the base class. Downcasting allows a derived-class-specific operation on a derived-class object pointed to by a base-class pointer. After a downcast, the program can invoke derived-class functions that are not in the base class. Section 21.8 shows a concrete example of downcasting.



### Software Engineering Observation 21.3

*If the address of a derived-class object has been assigned to a pointer of one of its direct or indirect base classes, it's acceptable to cast that base-class pointer back to a pointer of the derived-class type. In fact, this must be done to send that derived-class object messages that do not appear in the base class.*

## 21.3.4 Virtual Functions

In Section 21.3.1, we aimed a base-class `CommissionEmployee` pointer at a derived-class `BasePlusCommissionEmployee` object, then invoked member function `print` through that pointer. Recall that the type of the handle determines which class's functionality to invoke. In that case, the `CommissionEmployee` pointer invoked the `CommissionEmployee` member function `print` on the `BasePlusCommissionEmployee` object, even though the pointer was aimed at a `BasePlusCommissionEmployee` object that has its own customized `print` function. *With virtual functions, the type of the object being pointed to, not the type of the handle, determines which version of a virtual function to invoke.*

First, we consider why virtual functions are useful. Suppose that shape classes such as `Circle`, `Triangle`, `Rectangle` and `Square` are all derived from base class `Shape`. Each of these classes might be endowed with the ability to draw itself via a member function `draw`. Although each class has its own `draw` function, the function for each shape is quite different. In a program that draws a set of shapes, it would be useful to be able to treat all the shapes generically as objects of the base class `Shape`. Then, to draw any shape, we could simply use a base-class `Shape` pointer to invoke function `draw` and let the program determine *dynamically* (i.e., at runtime) which derived-class `draw` function to use, based on the type of the object to which the base-class `Shape` pointer points at any given time.

To enable this behavior, we declare `draw` in the base class as a **virtual function**, and we **override** `draw` in each of the derived classes to draw the appropriate shape. From an implementation perspective, overriding a function is no different than redefining one (which is the approach we've been using until now). An overridden function in a derived class has the same signature and return type (i.e., prototype) as the function it overrides in

its base class. If we do not declare the base-class function as `virtual`, we can redefine that function. By contrast, if we declare the base-class function as `virtual`, we can override that function to enable polymorphic behavior. We declare a `virtual` function by preceding the function's prototype with the keyword `virtual` in the base class. For example,

```
virtual void draw() const;
```

would appear in base class `Shape`. The preceding prototype declares that function `draw` is a `virtual` function that takes no arguments and returns nothing. This function is declared `const` because a `draw` function typically would not make changes to the `Shape` object on which it's invoked—virtual functions do not have to be `const` functions.



#### Software Engineering Observation 21.4

*Once a function is declared `virtual`, it remains `virtual` all the way down the inheritance hierarchy from that point, even if that function is not explicitly declared `virtual` when a derived class overrides it.*



#### Good Programming Practice 21.1

*Even though certain functions are implicitly `virtual` because of a declaration made higher in the class hierarchy, explicitly declare these functions `virtual` at every level of the hierarchy to promote program clarity.*



#### Error-Prevention Tip 21.1

*When you browse a class hierarchy to locate a class to reuse, it's possible that a function in that class will exhibit `virtual` function behavior even though it isn't explicitly declared `virtual`. This happens when the class inherits a `virtual` function from its base class, and it can lead to subtle logic errors. Such errors can be avoided by explicitly declaring all `virtual` functions `virtual` throughout the inheritance hierarchy.*



#### Software Engineering Observation 21.5

*When a derived class chooses not to override a `virtual` function from its base class, the derived class simply inherits its base class's `virtual` function implementation.*

If a program invokes a `virtual` function through a base-class pointer to a derived-class object (e.g., `shapePtr->draw()`) or a base-class reference to a derived-class object (e.g., `shapeRef.draw()`), the program will choose the correct derived-class `draw` function dynamically (i.e., at execution time) based on the object type—not the pointer or reference type. Choosing the appropriate function to call at execution time (rather than at compile time) is known as **dynamic binding** or **late binding**.

When a `virtual` function is called by referencing a specific object by name and using the dot member-selection operator (e.g., `squareObject.draw()`), the function invocation is resolved at compile time (this is called **static binding**) and the `virtual` function that is called is the one defined for (or inherited by) the class of that particular object—this is not polymorphic behavior. Thus, dynamic binding with `virtual` functions occurs only off pointer (and, as we'll soon see, reference) handles.

Now let's see how `virtual` functions can enable polymorphic behavior in our employee hierarchy. Figures 21.8–21.9 are the header files for classes `CommissionEmployee` and `BasePlusCommissionEmployee`, respectively. The only difference between these files and those of Fig. 21.1 and Fig. 21.3 is that we specify each class's earnings and

print member functions as virtual (lines 30–31 of Fig. 21.8 and lines 20–21 of Fig. 21.9). Because functions earnings and print are virtual in class `CommissionEmployee`, class `BasePlusCommissionEmployee`'s earnings and print functions override class `CommissionEmployee`'s. Now, if we aim a base-class `CommissionEmployee` pointer at a derived-class `BasePlusCommissionEmployee` object, and the program uses that pointer to call either function earnings or print, the `BasePlusCommissionEmployee` object's corresponding function will be invoked. There were no changes to the member-function implementations of classes `CommissionEmployee` and `BasePlusCommissionEmployee`, so we reuse the versions of Fig. 21.2 and Fig. 21.4.

---

```

1 // Fig. 21.8: CommissionEmployee.h
2 // CommissionEmployee class definition represents a commission employee.
3 #ifndef COMMISSION_H
4 #define COMMISSION_H
5
6 #include <string> // C++ standard string class
7 using namespace std;
8
9 class CommissionEmployee
10 {
11 public:
12 CommissionEmployee(const string &, const string &, const string &,
13 double = 0.0, double = 0.0);
14
15 void setFirstName(const string &); // set first name
16 string getFirstName() const; // return first name
17
18 void setLastName(const string &); // set last name
19 string getLastName() const; // return last name
20
21 void setSocialSecurityNumber(const string &); // set SSN
22 string getSocialSecurityNumber() const; // return SSN
23
24 void setGrossSales(double); // set gross sales amount
25 double getGrossSales() const; // return gross sales amount
26
27 void setCommissionRate(double); // set commission rate
28 double getCommissionRate() const; // return commission rate
29
30 virtual double earnings() const; // calculate earnings
31 virtual void print() const; // print CommissionEmployee object
32 private:
33 string firstName;
34 string lastName;
35 string socialSecurityNumber;
36 double grossSales; // gross weekly sales
37 double commissionRate; // commission percentage
38 }; // end class CommissionEmployee
39
40 #endif

```

---

**Fig. 21.8** | `CommissionEmployee` class header file declares earnings and print functions as virtual.

---

```

1 // Fig. 21.9: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class derived from class
3 // CommissionEmployee.
4 #ifndef BASEPLUS_H
5 #define BASEPLUS_H
6
7 #include <string> // C++ standard string class
8 #include "CommissionEmployee.h" // CommissionEmployee class declaration
9 using namespace std;
10
11 class BasePlusCommissionEmployee : public CommissionEmployee
12 {
13 public:
14 BasePlusCommissionEmployee(const string &, const string &,
15 const string &, double = 0.0, double = 0.0, double = 0.0);
16
17 void setBaseSalary(double); // set base salary
18 double getBaseSalary() const; // return base salary
19
20 virtual double earnings() const; // calculate earnings
21 virtual void print() const; // print BasePlusCommissionEmployee object
22 private:
23 double baseSalary; // base salary
24 }; // end class BasePlusCommissionEmployee
25
26 #endif

```

---

**Fig. 21.9** | BasePlusCommissionEmployee class header file declares earnings and print functions as virtual.

We modified Fig. 21.5 to create the program of Fig. 21.10. Lines 40–51 demonstrate again that a `CommissionEmployee` pointer aimed at a `CommissionEmployee` object can be used to invoke `CommissionEmployee` functionality, and a `BasePlusCommissionEmployee` pointer aimed at a `BasePlusCommissionEmployee` object can be used to invoke `BasePlusCommissionEmployee` functionality. Line 54 aims base-class pointer `commissionEmployeePtr` at derived-class object `basePlusCommissionEmployee`. Note that when line 61 invokes member function `print` off the base-class pointer, the derived-class `BasePlusCommissionEmployee`'s `print` member function is invoked, so line 61 outputs different text than line 53 does in Fig. 21.5 (when member function `print` was not declared `virtual`). We see that declaring a member function `virtual` causes the program to dynamically determine which function to invoke based on the type of object to which the handle points, rather than on the type of the handle. Note again that when `commissionEmployeePtr` points to a `CommissionEmployee` object (line 40), class `CommissionEmployee`'s `print` function is invoked, and when `commissionEmployeePtr` points to a `BasePlusCommissionEmployee` object, class `BasePlusCommissionEmployee`'s `print` function is invoked. Thus, the same message—`print`, in this case—sent (off a base-class pointer) to a variety of objects related by inheritance to that base class, takes on many forms—this is polymorphic behavior.

---

```

1 // Fig. 21.10: fig21_10.cpp
2 // Introducing polymorphism, virtual functions and dynamic binding.
3 #include <iostream>
4 #include <iomanip>
5 #include "CommissionEmployee.h"
6 #include "BasePlusCommissionEmployee.h"
7 using namespace std;
8
9 int main()
10 {
11 // create base-class object
12 CommissionEmployee commissionEmployee(
13 "Sue", "Jones", "222-22-2222", 10000, .06);
14
15 // create base-class pointer
16 CommissionEmployee *commissionEmployeePtr = 0;
17
18 // create derived-class object
19 BasePlusCommissionEmployee basePlusCommissionEmployee(
20 "Bob", "Lewis", "333-33-3333", 5000, .04, 300);
21
22 // create derived-class pointer
23 BasePlusCommissionEmployee *basePlusCommissionEmployeePtr = 0;
24
25 // set floating-point output formatting
26 cout << fixed << setprecision(2);
27
28 // output objects using static binding
29 cout << "Invoking print function on base-class and derived-class "
30 << "\nobjects with static binding\n\n";
31 commissionEmployee.print(); // static binding
32 cout << "\n\n";
33 basePlusCommissionEmployee.print(); // static binding
34
35 // output objects using dynamic binding
36 cout << "\n\n\nInvoking print function on base-class and "
37 << "derived-class \nobjects with dynamic binding";
38
39 // aim base-class pointer at base-class object and print
40 commissionEmployeePtr = &commissionEmployee;
41 cout << "\n\nCalling virtual function print with base-class pointer "
42 << "\nto base-class object invokes base-class "
43 << "print function:\n\n";
44 commissionEmployeePtr->print(); // invokes base-class print
45
46 // aim derived-class pointer at derived-class object and print
47 basePlusCommissionEmployeePtr = &basePlusCommissionEmployee;
48 cout << "\n\nCalling virtual function print with derived-class "
49 << "pointer\nto derived-class object invokes derived-class "
50 << "print function:\n\n";
51 basePlusCommissionEmployeePtr->print(); // invokes derived-class print

```

---

**Fig. 21.10** | Demonstrating polymorphism by invoking a derived-class virtual function via a base-class pointer to a derived-class object. (Part I of 2.)

```

52
53 // aim base-class pointer at derived-class object and print
54 commissionEmployeePtr = &basePlusCommissionEmployee;
55 cout << "\n\nCalling virtual function print with base-class pointer"
56 << "\nto derived-class object invokes derived-class "
57 << "print function:\n\n";
58
59 // polymorphism; invokes BasePlusCommissionEmployee's print;
60 // base-class pointer to derived-class object
61 commissionEmployeePtr->print();
62 cout << endl;
63 } // end main

```

Invoking print function on base-class and derived-class objects with static binding

```

commission employee: Sue Jones
social security number: 222-22-2222
gross sales: 10000.00
commission rate: 0.06

```

```

base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 300.00

```

Invoking print function on base-class and derived-class objects with dynamic binding

Calling virtual function print with base-class pointer to base-class object invokes base-class print function:

```

commission employee: Sue Jones
social security number: 222-22-2222
gross sales: 10000.00
commission rate: 0.06

```

Calling virtual function print with derived-class pointer to derived-class object invokes derived-class print function:

```

base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 300.00

```

Calling virtual function print with base-class pointer to derived-class object invokes derived-class print function:

```

base-salaried commission employee: Bob Lewis
social security number: 333-33-3333
gross sales: 5000.00
commission rate: 0.04
base salary: 300.00

```

**Fig. 21.10** | Demonstrating polymorphism by invoking a derived-class virtual function via a base-class pointer to a derived-class object. (Part 2 of 2.)



### 21.3.5 Summary of the Allowed Assignments Between Base-Class and Derived-Class Objects and Pointers

Now that you've seen a complete application that processes diverse objects polymorphically, we summarize what you can and cannot do with base-class and derived-class objects and pointers. Although a derived-class object also *is a* base-class object, the two objects are nevertheless different. As discussed previously, derived-class objects can be treated as if they were base-class objects. This is a logical relationship, because the derived class contains all the members of the base class. However, base-class objects cannot be treated as if they were derived-class objects—the derived class can have additional derived-class-only members. For this reason, aiming a derived-class pointer at a base-class object is not allowed without an explicit cast—such an assignment would leave the derived-class-only members undefined on the base-class object. The cast relieves the compiler of the responsibility of issuing an error message. In a sense, by using the cast you're saying, “I know that what I'm doing is dangerous and I take full responsibility for my actions.”

We've discussed four ways to aim base-class pointers and derived-class pointers at base-class objects and derived-class objects:

1. Aiming a base-class pointer at a base-class object is straightforward—calls made off the base-class pointer simply invoke base-class functionality.
2. Aiming a derived-class pointer at a derived-class object is straightforward—calls made off the derived-class pointer simply invoke derived-class functionality.
3. Aiming a base-class pointer at a derived-class object is safe, because the derived-class object *is an* object of its base class. However, this pointer can be used to invoke only base-class member functions. If you attempt to refer to a derived-class-only member through the base-class pointer, the compiler reports an error. To avoid this error, you must cast the base-class pointer to a derived-class pointer. The derived-class pointer can then be used to invoke the derived-class object's complete functionality. This technique, called *downcasting*, is a potentially dangerous operation—Section 21.8 demonstrates how to safely use downcasting. If a `virtual` function is defined in the base and derived classes (either by inheritance or overriding), and if that function is invoked on a derived-class object via a base-class pointer, then the derived-class version of that function is called. This is an example of the polymorphic behavior that occurs only with `virtual` functions.
4. Aiming a derived-class pointer at a base-class object generates a compilation error. The *is-a* relationship applies only from a derived class to its direct and indirect base classes, and not vice versa. A base-class object does not contain the derived-class-only members that can be invoked off a derived-class pointer.



#### Common Programming Error 21.1

*After aiming a base-class pointer at a derived-class object, attempting to reference derived-class-only members with the base-class pointer is a compilation error.*



#### Common Programming Error 21.2

*Treating a base-class object as a derived-class object can cause errors.*

## 21.4 Type Fields and switch Statements

One way to determine the type of an object is to use a `switch` statement to check the value of a field in the object. This allows us to distinguish among object types, then invoke an appropriate action for a particular object. For example, in a hierarchy of shapes in which each shape object has a `shapeType` attribute, a `switch` statement could check the object's `shapeType` to determine which `print` function to call.

Using `switch` logic exposes programs to a variety of potential problems. For example, you might forget to include a type test when one is warranted, or might forget to test all possible cases in a `switch` statement. When modifying a `switch`-based system by adding new types, you might forget to insert the new cases in all relevant `switch` statements. Every addition or deletion of a class requires the modification of every `switch` statement in the system; tracking these statements down can be time consuming and error prone.



### Software Engineering Observation 21.6

*Polymorphic programming can eliminate the need for switch logic. By using the polymorphism mechanism to perform the equivalent logic, you can avoid the kinds of errors typically associated with switch logic.*



### Software Engineering Observation 21.7

*An interesting consequence of using polymorphism is that programs take on a simplified appearance. They contain less branching logic and simpler sequential code. This simplification facilitates testing, debugging and program maintenance.*

## 21.5 Abstract Classes and Pure virtual Functions

When we think of a class as a type, we assume that programs will create objects of that type. However, there are cases in which it's useful to define classes from which you never intend to instantiate any objects. Such classes are called **abstract classes**. Because these classes normally are used as base classes in inheritance hierarchies, we refer to them as **abstract base classes**. These classes cannot be used to instantiate objects, because, as we'll soon see, abstract classes are incomplete—derived classes must define the “missing pieces.” We build programs with abstract classes in Section 21.6.

An abstract class provides a base class from which other classes can inherit. Classes that can be used to instantiate objects are called **concrete classes**. Such classes define every member function they declare. We could have an abstract base class `TwoDimensionalShape` and derive such concrete classes as `Square`, `Circle` and `Triangle`. We could also have an abstract base class `ThreeDimensionalShape` and derive such concrete classes as `Cube`, `Sphere` and `Cylinder`. Abstract base classes are too generic to define real objects; we need to be more specific before we can think of instantiating objects. For example, if someone tells you to “draw the two-dimensional shape,” what shape would you draw? Concrete classes provide the specifics that make it reasonable to instantiate objects.

An inheritance hierarchy does not need to contain any abstract classes, but many object-oriented systems have class hierarchies headed by abstract base classes. In some cases, abstract classes constitute the top few levels of the hierarchy. A good example of this is the shape hierarchy in Fig. 20.3, which begins with abstract base class `Shape`. On the next level of the hierarchy we have two more abstract base classes, namely, `TwoDimension-`

alShape and ThreeDimensionalShape. The next level of the hierarchy defines concrete classes for two-dimensional shapes (namely, Circle, Square and Triangle) and for three-dimensional shapes (namely, Sphere, Cube and Tetrahedron).

A class is made abstract by declaring one or more of its virtual functions to be “pure.” A **pure virtual function** is specified by placing “= 0” in its declaration, as in

```
virtual void draw() const = 0; // pure virtual function
```

The “= 0” is a **pure specifier**. Pure virtual functions do not provide implementations. Every concrete derived class *must* override all base-class pure virtual functions with concrete implementations of those functions. The difference between a virtual function and a pure virtual function is that a virtual function has an implementation and gives the derived class the *option* of overriding the function; by contrast, a pure virtual function does not provide an implementation and *requires* the derived class to override the function for that derived class to be concrete; otherwise the derived class remains abstract.

Pure virtual functions are used when it does not make sense for the base class to have an implementation of a function, but you want all concrete derived classes to implement the function. Returning to our earlier example of space objects, it does not make sense for the base class SpaceObject to have an implementation for function draw (as there is no way to draw a generic space object without having more information about what type of space object is being drawn). An example of a function that would be defined as virtual (and not pure virtual) would be one that returns a name for the object. We can name a generic SpaceObject (for instance, as “space object”), so a default implementation for this function can be provided, and the function does not need to be pure virtual. The function is still declared virtual, however, because it’s expected that derived classes will override this function to provide more specific names for the derived-class objects.



### Software Engineering Observation 21.8

*An abstract class defines a common public interface for the various classes in a class hierarchy. An abstract class contains one or more pure virtual functions that concrete derived classes must override.*



### Common Programming Error 21.3

*Attempting to instantiate an object of an abstract class causes a compilation error.*



### Common Programming Error 21.4

*Failure to override a pure virtual function in a derived class, then attempting to instantiate objects of that class, is a compilation error.*



### Software Engineering Observation 21.9

*An abstract class has at least one pure virtual function. An abstract class also can have data members and concrete functions (including constructors and destructors), which are subject to the normal rules of inheritance by derived classes.*

Although we cannot instantiate objects of an abstract base class, we *can* use the abstract base class to declare pointers and references that can refer to objects of any concrete classes derived from the abstract class. Programs typically use such pointers and references to manipulate derived-class objects polymorphically.

Consider another application of polymorphism. A screen manager needs to display a variety of objects, including new types of objects that you'll add to the system after writing the screen manager. The system might need to display various shapes, such as `Circles`, `Triangles` or `Rectangles`, which are derived from abstract base class `Shape`. The screen manager uses `Shape` pointers to manage the objects that are displayed. To draw any object (regardless of the level at which that object's class appears in the inheritance hierarchy), the screen manager uses a base-class pointer to the object to invoke the object's `draw` function, which is a pure `virtual` function in base class `Shape`; therefore, each concrete derived class must implement function `draw`. Each `Shape` object in the inheritance hierarchy knows how to draw itself. The screen manager does not have to worry about the type of each object or whether the screen manager has ever encountered objects of that type.

Polymorphism is particularly effective for implementing layered software systems. In operating systems, for example, each type of physical device could operate quite differently from the others. Even so, commands to *read* or *write* data from and to devices may have a certain uniformity. The *write* message sent to a device-driver object needs to be interpreted specifically in the context of that device driver and how that device driver manipulates devices of a specific type. However, the *write* call itself really is no different from the *write* to any other device in the system—place some number of bytes from memory onto that device. An object-oriented operating system might use an abstract base class to provide an interface appropriate for all device drivers. Then, through inheritance from that abstract base class, derived classes are formed that all operate similarly. The capabilities (i.e., the `public` functions) offered by the device drivers are provided as pure `virtual` functions in the abstract base class. The implementations of these pure `virtual` functions are provided in the derived classes that correspond to the specific types of device drivers. This architecture also allows new devices to be added to a system easily, even after the operating system has been defined. The user can just plug in the device and install its new device driver. The operating system “talks” to this new device through its device driver, which has the same `public` member functions as all other device drivers—those defined in the device driver abstract base class.


It's common in object-oriented programming to define an **iterator class** that can traverse all the objects in a container (such as an array). For example, a program can print a list of objects in a vector by creating an iterator object, then using the iterator to obtain the next element of the list each time the iterator is called. Iterators often are used in polymorphic programming to traverse an array or a linked list of pointers to objects from various levels of a hierarchy. The pointers in such a list are all base-class pointers. A list of pointers to objects of base class `TwoDimensionalShape` could contain pointers to objects of classes `Square`, `Circle`, `Triangle` and so on. Using polymorphism to send a `draw` message, off a `TwoDimensionalShape * pointer`, to each object in the list would draw each object correctly on the screen.

## 21.6 Case Study: Payroll System Using Polymorphism

This section reexamines the `CommissionEmployee-BasePlusCommissionEmployee` hierarchy that we explored throughout Section 20.4. In this example, we use an abstract class and polymorphism to perform payroll calculations based on the type of employee. We create an enhanced employee hierarchy to solve the following problem:

*A company pays its employees weekly. The employees are of four types: Salaried employees are paid a fixed weekly salary regardless of the number of hours worked, hourly employees are paid by the hour and receive overtime pay for all hours worked in excess of 40 hours, commission employees are paid a percentage of their sales and base-salary-plus-commission employees receive a base salary plus a percentage of their sales. For the current pay period, the company has decided to reward base-salary-plus-commission employees by adding 10 percent to their base salaries. The company wants to implement a C++ program that performs its payroll calculations polymorphically.*

We use abstract class `Employee` to represent the general concept of an employee. The classes that derive directly from `Employee` are `SalariedEmployee`, `CommissionEmployee` and `HourlyEmployee`. Class `BasePlusCommissionEmployee`—derived from `CommissionEmployee`—represents the last employee type. The UML class diagram in Fig. 21.11 shows the inheritance hierarchy for our polymorphic employee payroll application. The abstract class name `Employee` is italicized, as per the convention of the UML.



**Fig. 21.11** | Employee hierarchy UML class diagram.

Abstract base class `Employee` declares the “interface” to the hierarchy—that is, the set of member functions that a program can invoke on all `Employee` objects. Each employee, regardless of the way his or her earnings are calculated, has a first name, a last name and a social security number, so private data members `firstName`, `lastName` and `socialSecurityNumber` appear in abstract base class `Employee`.



### Software Engineering Observation 21.10

*A derived class can inherit interface or implementation from a base class. Hierarchies designed for **implementation inheritance** tend to have their functionality high in the hierarchy—each new derived class inherits one or more member functions that were defined in a base class, and the derived class uses the base-class definitions. Hierarchies designed for **interface inheritance** tend to have their functionality lower in the hierarchy—a base class specifies one or more functions that should be defined for each class in the hierarchy (i.e., they have the same prototype), but the individual derived classes provide their own implementations of the function(s).*

The following sections implement the `Employee` class hierarchy. The first five each implement one of the abstract or concrete classes. The last section implements a test program that builds objects of all these classes and processes the objects polymorphically.

### 21.6.1 Creating Abstract Base Class Employee

Class `Employee` (Figs. 21.13–21.14, discussed in further detail shortly) provides functions `earnings` and `print`, in addition to various *get* and *set* functions that manipulate `Employee`'s data members. An `earnings` function certainly applies generically to all employees, but each earnings calculation depends on the employee's class. So we declare `earnings` as pure `virtual` in base class `Employee` because a default implementation does not make sense for that function—there is not enough information to determine what amount earnings should return. Each derived class overrides `earnings` with an appropriate implementation. To calculate an employee's earnings, the program assigns the address of an employee's object to a base class `Employee` pointer, then invokes the `earnings` function on that object. We maintain a vector of `Employee` pointers, each of which points to an `Employee` object (of course, there cannot be `Employee` objects, because `Employee` is an abstract class—because of inheritance, however, all objects of all derived classes of `Employee` may nevertheless be thought of as `Employee` objects). The program iterates through the vector and calls function `earnings` for each `Employee` object. C++ processes these function calls polymorphically. Including `earnings` as a pure `virtual` function in `Employee` forces every direct derived class of `Employee` that wishes to be a concrete class to override `earnings`. This enables the designer of the class hierarchy to demand that each derived class provide an appropriate pay calculation, if indeed that derived class is to be concrete.

Function `print` in class `Employee` displays the first name, last name and social security number of the employee. As we'll see, each derived class of `Employee` overrides function `print` to output the employee's type (e.g., "salaried employee:") followed by the rest of the employee's information. Function `print` could also call `earnings`, even though `print` is a pure-virtual function in class `Employee`.

The diagram in Fig. 21.12 shows each of the five classes in the hierarchy down the left side and functions `earnings` and `print` across the top. For each class, the diagram shows the desired results of each function. Class `Employee` specifies "= 0" for function `earnings` to indicate that this is a pure `virtual` function. Each derived class overrides this function to provide an appropriate implementation. We do not list base class `Employee`'s *get* and *set* functions because they're not overridden in any of the derived classes—each of these functions is inherited and used "as is" by each of the derived classes.

Let's consider class `Employee`'s header file (Fig. 21.13). The public member functions include a constructor that takes the first name, last name and social security number as arguments (line 12); *set* functions that set the first name, last name and social security number (lines 14, 17 and 20, respectively); *get* functions that return the first name, last name and social security number (lines 15, 18 and 21, respectively); pure `virtual` function `earnings` (line 24) and `virtual` function `print` (line 25).

Recall that we declared `earnings` as a pure `virtual` function because first we must know the specific `Employee` type to determine the appropriate earnings calculations. Declaring this function as pure `virtual` indicates that each concrete derived class *must* provide an `earnings` implementation and that a program can use base-class `Employee` pointers to invoke function `earnings` polymorphically for any type of `Employee`.

Figure 21.14 contains the member-function implementations for class `Employee`. No implementation is provided for `virtual` function `earnings`. The `Employee` constructor (lines 9–14) does not validate the social security number. Normally, such validation should be provided.

|                                      | earnings                                                                                                                                                 | print                                                                                                                                                                                                                   |
|--------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Employee                             | = 0                                                                                                                                                      | <i>firstName lastName</i><br>social security number: <i>SSN</i>                                                                                                                                                         |
| Salaried-<br>Employee                | weeklySalary                                                                                                                                             | salaried employee: <i>firstName lastName</i><br>social security number: <i>SSN</i><br>weekly salary: <i>weeklySalary</i>                                                                                                |
| Hourly-<br>Employee                  | <i>If hours &lt;= 40</i><br><i>wage * hours</i><br><i>If hours &gt; 40</i><br>( 40 * <i>wage</i> ) +<br>( ( <i>hours</i> - 40 )<br>* <i>wage</i> * 1.5 ) | hourly employee: <i>firstName lastName</i><br>social security number: <i>SSN</i><br>hourly wage: <i>wage</i> ; hours worked: <i>hours</i>                                                                               |
| Commission-<br>Employee              | commissionRate *<br>grossSales                                                                                                                           | commission employee: <i>firstName lastName</i><br>social security number: <i>SSN</i><br>gross sales: <i>grossSales</i> ;<br>commission rate: <i>commissionRate</i>                                                      |
| BasePlus-<br>Commission-<br>Employee | baseSalary +<br>( commissionRate *<br>grossSales )                                                                                                       | base salaried commission employee:<br><i>firstName lastName</i><br>social security number: <i>SSN</i><br>gross sales: <i>grossSales</i> ;<br>commission rate: <i>commissionRate</i> ;<br>base salary: <i>baseSalary</i> |

Fig. 21.12 | Polymorphic interface for the Employee hierarchy classes.

```

1 // Fig. 21.13: Employee.h
2 // Employee abstract base class.
3 #ifndef EMPLOYEE_H
4 #define EMPLOYEE_H
5
6 #include <string> // C++ standard string class
7 using namespace std;
8
9 class Employee
10 {
11 public:
12 Employee(const string &, const string &, const string &);
13
14 void setFirstName(const string &); // set first name
15 string getFirstName() const; // return first name
16
17 void setLastName(const string &); // set last name
18 string getLastName() const; // return last name
19
20 void setSocialSecurityNumber(const string &); // set SSN
21 string getSocialSecurityNumber() const; // return SSN

```

Fig. 21.13 | Employee class header file. (Part I of 2.)

---

```

22
23 // pure virtual function makes Employee abstract base class
24 virtual double earnings() const = 0; // pure virtual
25 virtual void print() const; // virtual
26 private:
27 string firstName;
28 string lastName;
29 string socialSecurityNumber;
30 }; // end class Employee
31
32 #endif // EMPLOYEE_H

```

---

**Fig. 21.13** | Employee class header file. (Part 2 of 2.)

---

```

1 // Fig. 21.14: Employee.cpp
2 // Abstract-base-class Employee member-function definitions.
3 // Note: No definitions are given for pure virtual functions.
4 #include <iostream>
5 #include "Employee.h" // Employee class definition
6 using namespace std;
7
8 // constructor
9 Employee::Employee(const string &first, const string &last,
10 const string &ssn)
11 : firstName(first), lastName(last), socialSecurityNumber(ssn)
12 {
13 // empty body
14 } // end Employee constructor
15
16 // set first name
17 void Employee::setFirstName(const string &first)
18 {
19 firstName = first;
20 } // end function setFirstName
21
22 // return first name
23 string Employee::getFirstName() const
24 {
25 return firstName;
26 } // end function getFirstName
27
28 // set last name
29 void Employee::setLastName(const string &last)
30 {
31 lastName = last;
32 } // end function setLastName
33
34 // return last name
35 string Employee::getLastName() const
36 {
37 return lastName;
38 } // end function getLastName

```

---

**Fig. 21.14** | Employee class implementation file. (Part 1 of 2.)



---

```

39
40 // set social security number
41 void Employee::setSocialSecurityNumber(const string &ssn)
42 {
43 socialSecurityNumber = ssn; // should validate
44 } // end function setSocialSecurityNumber
45
46 // return social security number
47 string Employee::getSocialSecurityNumber() const
48 {
49 return socialSecurityNumber;
50 } // end function getSocialSecurityNumber
51
52 // print Employee's information (virtual, but not pure virtual)
53 void Employee::print() const
54 {
55 cout << getFirstName() << ' ' << getLastName()
56 << "\nsocial security number: " << getSocialSecurityNumber();
57 } // end function print

```

---

**Fig. 21.14** | Employee class implementation file. (Part 2 of 2.)

Note that virtual function `print` (Fig. 21.14, lines 53–57) provides an implementation that will be overridden in each of the derived classes. Each of these functions will, however, use the abstract class's version of `print` to print information common to all classes in the `Employee` hierarchy.

### 21.6.2 Creating Concrete Derived Class `SalariedEmployee`

Class `SalariedEmployee` (Figs. 21.15–21.16) derives from class `Employee` (line 8 of Fig. 21.15). The public member functions include a constructor that takes a first name, a last name, a social security number and a weekly salary as arguments (lines 11–12); a *set* function to assign a new nonnegative value to data member `weeklySalary` (line 14); a *get* function to return `weeklySalary`'s value (line 15); a virtual function `earnings` that calculates a `SalariedEmployee`'s earnings (line 18) and a virtual function `print` (line 19) that outputs the employee's type, namely, "salaried employee: " followed by employee-specific information produced by base class `Employee`'s `print` function and `SalariedEmployee`'s `getWeeklySalary` function.

---

```

1 // Fig. 21.15: SalariedEmployee.h
2 // SalariedEmployee class derived from Employee.
3 #ifndef SALARIED_H
4 #define SALARIED_H
5
6 #include "Employee.h" // Employee class definition
7
8 class SalariedEmployee : public Employee
9 {

```

---

**Fig. 21.15** | `SalariedEmployee` class header file. (Part 1 of 2.)

---

```

10 public:
11 SalariedEmployee(const string &, const string &,
12 const string &, double = 0.0);
13
14 void setWeeklySalary(double); // set weekly salary
15 double getWeeklySalary() const; // return weekly salary
16
17 // keyword virtual signals intent to override
18 virtual double earnings() const; // calculate earnings
19 virtual void print() const; // print SalariedEmployee object
20 private:
21 double weeklySalary; // salary per week
22 }; // end class SalariedEmployee
23
24 #endif // SALARIED_H

```

---

**Fig. 21.15** | SalariedEmployee class header file. (Part 2 of 2.)

Figure 21.16 contains the member-function implementations for SalariedEmployee. The class's constructor passes the first name, last name and social security number to the Employee constructor (line 10) to initialize the private data members that are inherited from the base class, but not accessible in the derived class. Function earnings (line 29–32) overrides pure virtual function earnings in Employee to provide a concrete implementation that returns the SalariedEmployee's weekly salary. If we did not implement earnings, class SalariedEmployee would be an abstract class, and any attempt to instantiate an object of the class would result in a compilation error (and, of course, we want SalariedEmployee here to be a concrete class). In class SalariedEmployee's header file, we declared member functions earnings and print as virtual (lines 18–19 of Fig. 21.15)—actually, placing the virtual keyword before these member functions is redundant. We defined them as virtual in base class Employee, so they remain virtual functions throughout the class hierarchy. Recall from **Good Programming Practice 21.1** that explicitly declaring such functions virtual at every level of the hierarchy can promote program clarity.

---

```

1 // Fig. 21.16: SalariedEmployee.cpp
2 // SalariedEmployee class member-function definitions.
3 #include <iostream>
4 #include "SalariedEmployee.h" // SalariedEmployee class definition
5 using namespace std;
6
7 // constructor
8 SalariedEmployee::SalariedEmployee(const string &first,
9 const string &last, const string &ssn, double salary)
10 : Employee(first, last, ssn)
11 {
12 setWeeklySalary(salary);
13 } // end SalariedEmployee constructor

```

---

**Fig. 21.16** | SalariedEmployee class implementation file. (Part 1 of 2.)

---

```

14
15 // set salary
16 void SalariedEmployee::setWeeklySalary(double salary)
17 {
18 weeklySalary = (salary < 0.0) ? 0.0 : salary;
19 } // end function setWeeklySalary
20
21 // return salary
22 double SalariedEmployee::getWeeklySalary() const
23 {
24 return weeklySalary;
25 } // end function getWeeklySalary
26
27 // calculate earnings;
28 // override pure virtual function earnings in Employee
29 double SalariedEmployee::earnings() const
30 {
31 return getWeeklySalary();
32 } // end function earnings
33
34 // print SalariedEmployee's information
35 void SalariedEmployee::print() const
36 {
37 cout << "salaried employee: ";
38 Employee::print(); // reuse abstract base-class print function
39 cout << "\nweekly salary: " << getWeeklySalary();
40 } // end function print

```

---

**Fig. 21.16** | SalariedEmployee class implementation file. (Part 2 of 2.)

Function `print` of class `SalariedEmployee` (lines 35–40 of Fig. 21.16) overrides `Employee` function `print`. If class `SalariedEmployee` did not override `print`, `SalariedEmployee` would inherit the `Employee` version of `print`. In that case, `SalariedEmployee`'s `print` function would simply return the employee's full name and social security number, which does not adequately represent a `SalariedEmployee`. To print a `SalariedEmployee`'s complete information, the derived class's `print` function outputs "salaried employee: " followed by the base-class `Employee`-specific information (i.e., first name, last name and social security number) printed by invoking the base class's `print` function using the scope resolution operator (line 38)—this is a nice example of code reuse. The output produced by `SalariedEmployee`'s `print` function contains the employee's weekly salary obtained by invoking the class's `getWeeklySalary` function.

### 21.6.3 Creating Concrete Derived Class `HourlyEmployee`

Class `HourlyEmployee` (Figs. 21.17–21.18) also derives from class `Employee` (line 8 of Fig. 21.17). The public member functions include a constructor (lines 13–14) that takes as arguments a first name, a last name, a social security number, an hourly wage and the number of hours worked; *set* functions that assign new values to data members `wage` and `hours`, respectively (lines 16 and 19); *get* functions to return the values of `wage` and `hours`,

respectively (lines 17 and 20); a virtual function `earnings` that calculates an `HourlyEmployee`'s earnings (line 23) and a virtual function `print` that outputs the employee's type, namely, "hourly employee: " and employee-specific information (line 24).

---

```

1 // Fig. 21.17: HourlyEmployee.h
2 // HourlyEmployee class definition.
3 #ifndef HOURLY_H
4 #define HOURLY_H
5
6 #include "Employee.h" // Employee class definition
7
8 class HourlyEmployee : public Employee
9 {
10 public:
11 static const int hoursPerWeek = 168; // hours in one week
12
13 HourlyEmployee(const string &, const string &,
14 const string &, double = 0.0, double = 0.0);
15
16 void setWage(double); // set hourly wage
17 double getWage() const; // return hourly wage
18
19 void setHours(double); // set hours worked
20 double getHours() const; // return hours worked
21
22 // keyword virtual signals intent to override
23 virtual double earnings() const; // calculate earnings
24 virtual void print() const; // print HourlyEmployee object
25 private:
26 double wage; // wage per hour
27 double hours; // hours worked for week
28 }; // end class HourlyEmployee
29
30 #endif // HOURLY_H

```

---

**Fig. 21.17** | `HourlyEmployee` class header file.

Figure 21.18 contains the member-function implementations for class `HourlyEmployee`. Lines 17–20 and 29–33 define *set* functions that assign new values to data members `wage` and `hours`, respectively. Function `setWage` (lines 17–20) ensures that `wage` is non-negative, and function `setHours` (lines 29–33) ensures that data member `hours` is between 0 and `hoursPerWeek` (i.e., 168). Class `HourlyEmployee`'s *get* functions are implemented in lines 23–26 and 36–39. We do not declare these functions `virtual`, so classes derived from class `HourlyEmployee` cannot override them (although derived classes certainly can redefine them). The `HourlyEmployee` constructor, like the `SalariedEmployee` constructor, passes the first name, last name and social security number to the base class `Employee` constructor (line 10) to initialize the inherited private data members declared in the base class. In addition, `HourlyEmployee`'s `print` function calls base-class function `print` (line 55) to output the `Employee`-specific information (i.e., first name, last name and social security number)—this is another nice example of code reuse.

---

```

1 // Fig. 21.18: HourlyEmployee.cpp
2 // HourlyEmployee class member-function definitions.
3 #include <iostream>
4 #include "HourlyEmployee.h" // HourlyEmployee class definition
5 using namespace std;
6
7 // constructor
8 HourlyEmployee::HourlyEmployee(const string &first, const string &last,
9 const string &ssn, double hourlyWage, double hoursWorked)
10 : Employee(first, last, ssn)
11 {
12 setWage(hourlyWage); // validate hourly wage
13 setHours(hoursWorked); // validate hours worked
14 } // end HourlyEmployee constructor
15
16 // set wage
17 void HourlyEmployee::setWage(double hourlyWage)
18 {
19 wage = (hourlyWage < 0.0 ? 0.0 : hourlyWage);
20 } // end function setWage
21
22 // return wage
23 double HourlyEmployee::getWage() const
24 {
25 return wage;
26 } // end function getWage
27
28 // set hours worked
29 void HourlyEmployee::setHours(double hoursWorked)
30 {
31 hours = (((hoursWorked >= 0.0) &&
32 (hoursWorked <= hoursPerWeek)) ? hoursWorked : 0.0);
33 } // end function setHours
34
35 // return hours worked
36 double HourlyEmployee::getHours() const
37 {
38 return hours;
39 } // end function getHours
40
41 // calculate earnings;
42 // override pure virtual function earnings in Employee
43 double HourlyEmployee::earnings() const
44 {
45 if (getHours() <= 40) // no overtime
46 return getWage() * getHours();
47 else
48 return 40 * getWage() + ((getHours() - 40) * getWage() * 1.5);
49 } // end function earnings
50
51 // print HourlyEmployee's information
52 void HourlyEmployee::print() const
53 {

```

---

**Fig. 21.18** | HourlyEmployee class implementation file. (Part I of 2.)

---

```

54 cout << "hourly employee: ";
55 Employee::print(); // code reuse
56 cout << "\nhourly wage: " << getWage() <<
57 "; hours worked: " << getHours();
58 } // end function print

```

---

**Fig. 21.18** | HourlyEmployee class implementation file. (Part 2 of 2.)

### 21.6.4 Creating Concrete Derived Class CommissionEmployee

Class `CommissionEmployee` (Figs. 21.19–21.20) derives from `Employee` (Fig. 21.19, line 8). The member-function implementations (Fig. 21.20) include a constructor (lines 8–14) that takes a first name, last name, social security number, sales amount and commission rate; *set* functions (lines 17–20 and 29–32) to assign new values to data members `commissionRate` and `grossSales`, respectively; *get* functions (lines 23–26 and 35–38) that retrieve their values; function `earnings` (lines 41–44) to calculate a `CommissionEmployee`'s earnings; and function `print` (lines 47–53) to output the employee's type, namely, "commission employee: " and employee-specific information. The constructor passes the first name, last name and social security number to the `Employee` constructor (line 10) to initialize `Employee`'s private data members. Function `print` calls base-class function `print` (line 50) to display the `Employee`-specific information.

---

```

1 // Fig. 21.19: CommissionEmployee.h
2 // CommissionEmployee class derived from Employee.
3 #ifndef COMMISSION_H
4 #define COMMISSION_H
5
6 #include "Employee.h" // Employee class definition
7
8 class CommissionEmployee : public Employee
9 {
10 public:
11 CommissionEmployee(const string &, const string &,
12 const string &, double = 0.0, double = 0.0);
13
14 void setCommissionRate(double); // set commission rate
15 double getCommissionRate() const; // return commission rate
16
17 void setGrossSales(double); // set gross sales amount
18 double getGrossSales() const; // return gross sales amount
19
20 // keyword virtual signals intent to override
21 virtual double earnings() const; // calculate earnings
22 virtual void print() const; // print CommissionEmployee object
23 private:
24 double grossSales; // gross weekly sales
25 double commissionRate; // commission percentage
26 }; // end class CommissionEmployee
27
28 #endif // COMMISSION_H

```

---

**Fig. 21.19** | CommissionEmployee class header file.

---

```

1 // Fig. 21.20: CommissionEmployee.cpp
2 // CommissionEmployee class member-function definitions.
3 #include <iostream>
4 #include "CommissionEmployee.h" // CommissionEmployee class definition
5 using namespace std;
6
7 // constructor
8 CommissionEmployee::CommissionEmployee(const string &first,
9 const string &last, const string &ssn, double sales, double rate)
10 : Employee(first, last, ssn)
11 {
12 setGrossSales(sales);
13 setCommissionRate(rate);
14 } // end CommissionEmployee constructor
15
16 // set commission rate
17 void CommissionEmployee::setCommissionRate(double rate)
18 {
19 commissionRate = ((rate > 0.0 && rate < 1.0) ? rate : 0.0);
20 } // end function setCommissionRate
21
22 // return commission rate
23 double CommissionEmployee::getCommissionRate() const
24 {
25 return commissionRate;
26 } // end function getCommissionRate
27
28 // set gross sales amount
29 void CommissionEmployee::setGrossSales(double sales)
30 {
31 grossSales = ((sales < 0.0) ? 0.0 : sales);
32 } // end function setGrossSales
33
34 // return gross sales amount
35 double CommissionEmployee::getGrossSales() const
36 {
37 return grossSales;
38 } // end function getGrossSales
39
40 // calculate earnings; override pure virtual function earnings in Employee
41 double CommissionEmployee::earnings() const
42 {
43 return getCommissionRate() * getGrossSales();
44 } // end function earnings
45
46 // print CommissionEmployee's information
47 void CommissionEmployee::print() const
48 {
49 cout << "commission employee: ";
50 Employee::print(); // code reuse
51 cout << "\ngross sales: " << getGrossSales()
52 << "; commission rate: " << getCommissionRate();
53 } // end function print

```

---

**Fig. 21.20** | CommissionEmployee class implementation file.

### 21.6.5 Creating Indirect Concrete Derived Class BasePlusCommissionEmployee

Class `BasePlusCommissionEmployee` (Figs. 21.21–21.22) directly inherits from class `CommissionEmployee` (line 8 of Fig. 21.21) and therefore is an *indirect* derived class of class `Employee`. Class `BasePlusCommissionEmployee`'s member-function implementations include a constructor (lines 8–14 of Fig. 21.22) that takes as arguments a first name, a last name, a social security number, a sales amount, a commission rate and a base salary. It then passes the first name, last name, social security number, sales amount and commission rate to the `CommissionEmployee` constructor (line 11) to initialize the inherited members. `BasePlusCommissionEmployee` also contains a *set* function (lines 17–20) to assign a new value to data member `baseSalary` and a *get* function (lines 23–26) to return `baseSalary`'s value. Function `earnings` (lines 30–33) calculates a `BasePlusCommissionEmployee`'s earnings. Line 32 in function `earnings` calls base-class `CommissionEmployee`'s `earnings` function to calculate the commission-based portion of the employee's earnings. This is a nice example of code reuse. `BasePlusCommissionEmployee`'s `print` function (lines 36–41) outputs "base-salaried", followed by the output of base-class `CommissionEmployee`'s `print` function (another example of code reuse), then the base salary. The resulting output begins with "base-salaried commission employee: " followed by the rest of the `BasePlusCommissionEmployee`'s information. Recall that `CommissionEmployee`'s `print` displays the employee's first name, last name and social security number by invoking the `print` function of its base class (i.e., `Employee`)—yet another example of code reuse. `BasePlusCommissionEmployee`'s `print` initiates a chain of functions calls that spans all three levels of the `Employee` hierarchy.

---

```

1 // Fig. 21.21: BasePlusCommissionEmployee.h
2 // BasePlusCommissionEmployee class derived from CommissionEmployee.
3 #ifndef BASEPLUS_H
4 #define BASEPLUS_H
5
6 #include "CommissionEmployee.h" // CommissionEmployee class definition
7
8 class BasePlusCommissionEmployee : public CommissionEmployee
9 {
10 public:
11 BasePlusCommissionEmployee(const string &, const string &,
12 const string &, double = 0.0, double = 0.0, double = 0.0);
13
14 void setBaseSalary(double); // set base salary
15 double getBaseSalary() const; // return base salary
16
17 // keyword virtual signals intent to override
18 virtual double earnings() const; // calculate earnings
19 virtual void print() const; // print BasePlusCommissionEmployee object
20 private:
21 double baseSalary; // base salary per week
22 }; // end class BasePlusCommissionEmployee
23
24 #endif // BASEPLUS_H

```

---

**Fig. 21.21** | `BasePlusCommissionEmployee` class header file.



---

```

1 // Fig. 21.22: BasePlusCommissionEmployee.cpp
2 // BasePlusCommissionEmployee member-function definitions.
3 #include <iostream>
4 #include "BasePlusCommissionEmployee.h"
5 using namespace std;
6
7 // constructor
8 BasePlusCommissionEmployee::BasePlusCommissionEmployee(
9 const string &first, const string &last, const string &ssn,
10 double sales, double rate, double salary)
11 : CommissionEmployee(first, last, ssn, sales, rate)
12 {
13 setBaseSalary(salary); // validate and store base salary
14 } // end BasePlusCommissionEmployee constructor
15
16 // set base salary
17 void BasePlusCommissionEmployee::setBaseSalary(double salary)
18 {
19 baseSalary = ((salary < 0.0) ? 0.0 : salary);
20 } // end function setBaseSalary
21
22 // return base salary
23 double BasePlusCommissionEmployee::getBaseSalary() const
24 {
25 return baseSalary;
26 } // end function getBaseSalary
27
28 // calculate earnings;
29 // override virtual function earnings in CommissionEmployee
30 double BasePlusCommissionEmployee::earnings() const
31 {
32 return getBaseSalary() + CommissionEmployee::earnings();
33 } // end function earnings
34
35 // print BasePlusCommissionEmployee's information
36 void BasePlusCommissionEmployee::print() const
37 {
38 cout << "base-salaried ";
39 CommissionEmployee::print(); // code reuse
40 cout << "; base salary: " << getBaseSalary();
41 } // end function print

```

---

**Fig. 21.22** | BasePlusCommissionEmployee class implementation file.

### 21.6.6 Demonstrating Polymorphic Processing

To test our Employee hierarchy, the program in Fig. 21.23 creates an object of each of the four concrete classes SalariedEmployee, HourlyEmployee, CommissionEmployee and BasePlusCommissionEmployee. The program manipulates these objects, first with static binding, then polymorphically, using a vector of Employee pointers. Lines 23–30 create objects of each of the four concrete Employee derived classes. Lines 35–43 output each Employee’s information and earnings. Each member-function invocation in lines 35–43 is an example of static binding—at compile time, because we’re using name handles (not

pointers or references that could be set at execution time), the compiler can identify each object's type to determine which print and earnings functions are called.

---

```

1 // Fig. 21.23: fig21_23.cpp
2 // Processing Employee derived-class objects individually
3 // and polymorphically using dynamic binding.
4 #include <iostream>
5 #include <iomanip>
6 #include <vector>
7 #include "Employee.h"
8 #include "SalariedEmployee.h"
9 #include "HourlyEmployee.h"
10 #include "CommissionEmployee.h"
11 #include "BasePlusCommissionEmployee.h"
12 using namespace std;
13
14 void virtualViaPointer(const Employee * const); // prototype
15 void virtualViaReference(const Employee &); // prototype
16
17 int main()
18 {
19 // set floating-point output formatting
20 cout << fixed << setprecision(2);
21
22 // create derived-class objects
23 SalariedEmployee salariedEmployee(
24 "John", "Smith", "111-11-1111", 800);
25 HourlyEmployee hourlyEmployee(
26 "Karen", "Price", "222-22-2222", 16.75, 40);
27 CommissionEmployee commissionEmployee(
28 "Sue", "Jones", "333-33-3333", 10000, .06);
29 BasePlusCommissionEmployee basePlusCommissionEmployee(
30 "Bob", "Lewis", "444-44-4444", 5000, .04, 300);
31
32 cout << "Employees processed individually using static binding:\n\n";
33
34 // output each Employee's information and earnings using static binding
35 salariedEmployee.print();
36 cout << "\nearned $" << salariedEmployee.earnings() << "\n\n";
37 hourlyEmployee.print();
38 cout << "\nearned $" << hourlyEmployee.earnings() << "\n\n";
39 commissionEmployee.print();
40 cout << "\nearned $" << commissionEmployee.earnings() << "\n\n";
41 basePlusCommissionEmployee.print();
42 cout << "\nearned $" << basePlusCommissionEmployee.earnings()
43 << "\n\n";
44
45 // create vector of four base-class pointers
46 vector < Employee * > employees(4);
47
48 // initialize vector with Employees
49 employees[0] = &salariedEmployee;

```

---

**Fig. 21.23** | Employee class hierarchy driver program. (Part I of 3.)

```

50 employees[1] = &hourlyEmployee;
51 employees[2] = &commissionEmployee;
52 employees[3] = &basePlusCommissionEmployee;
53
54 cout << "Employees processed polymorphically via dynamic binding:\n\n";
55
56 // call virtualViaPointer to print each Employee's information
57 // and earnings using dynamic binding
58 cout << "Virtual function calls made off base-class pointers:\n\n";
59
60 for (size_t i = 0; i < employees.size(); i++)
61 virtualViaPointer(employees[i]);
62
63 // call virtualViaReference to print each Employee's information
64 // and earnings using dynamic binding
65 cout << "Virtual function calls made off base-class references:\n\n";
66
67 for (size_t i = 0; i < employees.size(); i++)
68 virtualViaReference(*employees[i]); // note dereferencing
69 } // end main
70
71 // call Employee virtual functions print and earnings off a
72 // base-class pointer using dynamic binding
73 void virtualViaPointer(const Employee * baseClassPtr)
74 {
75 baseClassPtr->print();
76 cout << "\nearned $" << baseClassPtr->earnings() << "\n\n";
77 } // end function virtualViaPointer
78
79 // call Employee virtual functions print and earnings off a
80 // base-class reference using dynamic binding
81 void virtualViaReference(const Employee &baseClassRef)
82 {
83 baseClassRef.print();
84 cout << "\nearned $" << baseClassRef.earnings() << "\n\n";
85 } // end function virtualViaReference

```

Employees processed individually using static binding:

```

salaried employee: John Smith
social security number: 111-11-1111
weekly salary: 800.00
earned $800.00

hourly employee: Karen Price
social security number: 222-22-2222
hourly wage: 16.75; hours worked: 40.00
earned $670.00

commission employee: Sue Jones
social security number: 333-33-3333
gross sales: 10000.00; commission rate: 0.06
earned $600.00

```

**Fig. 21.23** | Employee class hierarchy driver program. (Part 2 of 3.)

```
base-salaried commission employee: Bob Lewis
social security number: 444-44-4444
gross sales: 5000.00; commission rate: 0.04; base salary: 300.00
earned $500.00

Employees processed polymorphically using dynamic binding:
Virtual function calls made off base-class pointers:

salaried employee: John Smith
social security number: 111-11-1111
weekly salary: 800.00
earned $800.00

hourly employee: Karen Price
social security number: 222-22-2222
hourly wage: 16.75; hours worked: 40.00
earned $670.00

commission employee: Sue Jones
social security number: 333-33-3333
gross sales: 10000.00; commission rate: 0.06
earned $600.00

base-salaried commission employee: Bob Lewis
social security number: 444-44-4444
gross sales: 5000.00; commission rate: 0.04; base salary: 300.00
earned $500.00

Virtual function calls made off base-class references:

salaried employee: John Smith
social security number: 111-11-1111
weekly salary: 800.00
earned $800.00

hourly employee: Karen Price
social security number: 222-22-2222
hourly wage: 16.75; hours worked: 40.00
earned $670.00

commission employee: Sue Jones
social security number: 333-33-3333
gross sales: 10000.00; commission rate: 0.06
earned $600.00

base-salaried commission employee: Bob Lewis
social security number: 444-44-4444
gross sales: 5000.00; commission rate: 0.04; base salary: 300.00
earned $500.00
```

**Fig. 21.23** | Employee class hierarchy driver program. (Part 3 of 3.)

Line 46 allocates vector `employees`, which contains four `Employee` pointers. Line 49 aims `employees[ 0 ]` at object `salariedEmployee`. Line 50 aims `employees[ 1 ]` at object `hourlyEmployee`. Line 51 aims `employees[ 2 ]` at object `commissionEmployee`. Line 52 aims `employee[ 3 ]` at object `basePlusCommissionEmployee`. The compiler allows these

assignments, because a `SalariedEmployee` *is an* `Employee`, an `HourlyEmployee` *is an* `Employee`, a `CommissionEmployee` *is an* `Employee` and a `BasePlusCommissionEmployee` *is an* `Employee`. Therefore, we can assign the addresses of `SalariedEmployee`, `HourlyEmployee`, `CommissionEmployee` and `BasePlusCommissionEmployee` objects to base-class `Employee` pointers (even though `Employee` is an abstract class).

The loop in lines 60–61 traverses vector `employees` and invokes function `virtualViaPointer` (lines 73–77) for each element in `employees`. Function `virtualViaPointer` receives in parameter `baseClassPtr` (of type `const Employee * const`) the address stored in an `employees` element. Each call to `virtualViaPointer` uses `baseClassPtr` to invoke virtual functions `print` (line 75) and `earnings` (line 76). Note that function `virtualViaPointer` does not contain any `SalariedEmployee`, `HourlyEmployee`, `CommissionEmployee` or `BasePlusCommissionEmployee` type information. The function knows only about base-class type `Employee`. Therefore, the compiler cannot know which concrete class’s functions to call through `baseClassPtr`. Yet at execution time, each virtual-function invocation calls the function on the object to which `baseClassPtr` points at that moment. The output illustrates that the appropriate functions for each class are indeed invoked and that each object’s proper information is displayed. For instance, the weekly salary is displayed for the `SalariedEmployee`, and the gross sales are displayed for the `CommissionEmployee` and `BasePlusCommissionEmployee`. Also, obtaining the earnings of each `Employee` polymorphically in line 76 produces the same results as obtaining these employees’ earnings via static binding in lines 36, 38, 40 and 42. All virtual function calls to `print` and `earnings` are resolved at runtime with dynamic binding.

Finally, another for statement (lines 67–68) traverses `employees` and invokes function `virtualViaReference` (lines 81–85) for each element in the vector. Function `virtualViaReference` receives in its parameter `baseClassRef` (of type `const Employee &`) a reference to the object obtained by dereferencing the pointer stored in each `employees` element (line 68). Each call to `virtualViaReference` invokes virtual functions `print` (line 83) and `earnings` (line 84) via reference `baseClassRef` to demonstrate that polymorphic processing occurs with base-class references as well. Each virtual-function invocation calls the function on the object to which `baseClassRef` refers at runtime. This is another example of dynamic binding. The output produced using base-class references is identical to the output produced using base-class pointers.

## 21.7 (Optional) Polymorphism, Virtual Functions and Dynamic Binding “Under the Hood”

C++ makes polymorphism easy to program. It’s certainly possible to program for polymorphism in non-object-oriented languages such as C, but doing so requires complex and potentially dangerous pointer manipulations. This section discusses how C++ can implement polymorphism, virtual functions and dynamic binding internally. This will give you a solid understanding of how these capabilities really work. More importantly, it will help you appreciate the overhead of polymorphism—in terms of additional memory consumption and processor time. This will help you determine when to use polymorphism and when to avoid it. The STL components were implemented without polymorphism and virtual functions—this was done to avoid the associated execution-time overhead and achieve optimal performance to meet the unique requirements of the STL.

First, we’ll explain the data structures that the C++ compiler builds at compile time to support polymorphism at execution time. You’ll see that polymorphism is accomplished through three levels of pointers (i.e., “triple indirection”). Then we’ll show how an executing program uses these data structures to execute virtual functions and achieve the dynamic binding associated with polymorphism. Our discussion explains one possible implementation; this is not a language requirement.

When C++ compiles a class that has one or more virtual functions, it builds a **virtual function table** (*vtable*) for that class. An executing program uses the *vtable* to select the proper function implementation each time a virtual function of that class is called. The leftmost column of Fig. 21.24 illustrates the *vtables* for classes `Employee`, `SalariedEmployee`, `HourlyEmployee`, `CommissionEmployee` and `BasePlusCommissionEmployee`.

In the *vtable* for class `Employee`, the first function pointer is set to 0 (i.e., the null pointer). This is done because function `earnings` is a pure virtual function and therefore lacks an implementation. The second function pointer points to function `print`, which displays the employee’s full name and social security number. [Note: We’ve abbreviated the output of each `print` function in this figure to conserve space.] Any class that has one or more null pointers in its *vtable* is an abstract class. Classes without any null *vtable* pointers (such as `SalariedEmployee`, `HourlyEmployee`, `CommissionEmployee` and `BasePlusCommissionEmployee`) are concrete classes.

Class `SalariedEmployee` overrides function `earnings` to return the employee’s weekly salary, so the function pointer points to the `earnings` function of class `SalariedEmployee`. `SalariedEmployee` also overrides `print`, so the corresponding function pointer points to the `SalariedEmployee` member function that prints “salaried employee: ” followed by the employee’s name, social security number and weekly salary.

The `earnings` function pointer in the *vtable* for class `HourlyEmployee` points to `HourlyEmployee`’s `earnings` function that returns the employee’s wage multiplied by the number of hours worked. To conserve space, we’ve omitted the fact that hourly employees receive time-and-a-half pay for overtime hours worked. The `print` function pointer points to the `HourlyEmployee` version of the function, which prints “hourly employee: ”, the employee’s name, social security number, hourly wage and hours worked. Both functions override the functions in class `Employee`.

The `earnings` function pointer in the *vtable* for class `CommissionEmployee` points to `CommissionEmployee`’s `earnings` function that returns the employee’s gross sales multiplied by the commission rate. The `print` function pointer points to the `CommissionEmployee` version of the function, which prints the employee’s type, name, social security number, commission rate and gross sales. As in class `HourlyEmployee`, both functions override the functions in class `Employee`.

The `earnings` function pointer in the *vtable* for class `BasePlusCommissionEmployee` points to the `BasePlusCommissionEmployee`’s `earnings` function, which returns the employee’s base salary plus gross sales multiplied by commission rate. The `print` function pointer points to the `BasePlusCommissionEmployee` version of the function, which prints the employee’s base salary plus the type, name, social security number, commission rate and gross sales. Both functions override the functions in class `CommissionEmployee`.

Notice that in our `Employee` case study, each concrete class provides its own implementation for virtual functions `earnings` and `print`. You’ve learned that each class which inherits directly from abstract base class `Employee` must implement `earnings` to be




Fig. 21.24 | How virtual function calls work.

a concrete class, because `earnings` is a pure virtual function. These classes do not need to implement function `print`, however, to be considered concrete—`print` is not a pure virtual function and derived classes can inherit class `Employee`’s implementation of `print`. Furthermore, class `BasePlusCommissionEmployee` does not have to implement either function `print` or `earnings`—both function implementations can be inherited from class `CommissionEmployee`. If a class in our hierarchy were to inherit function implementations in this manner, the *vtable* pointers for these functions would simply point to the function implementation that was being inherited. For example, if `BasePlusCommissionEmployee` did not override `earnings`, the `earnings` function pointer in the *vtable* for class `BasePlusCommissionEmployee` would point to the same `earnings` function as the *vtable* for class `CommissionEmployee` points to.

Polymorphism is accomplished through an elegant data structure involving three levels of pointers. We’ve discussed one level—the function pointers in the *vtable*. These point to the actual functions that execute when a virtual function is invoked.

Now we consider the second level of pointers. Whenever an object of a class with one or more virtual functions is instantiated, the compiler attaches to the object a pointer to the *vtable* for that class. This pointer is normally at the front of the object, but it isn’t required to be implemented that way. In Fig. 21.24, these pointers are associated with the objects created in Fig. 21.23 (one object for each of the types `SalariedEmployee`, `HourlyEmployee`, `CommissionEmployee` and `BasePlusCommissionEmployee`). Notice that the diagram displays each of the object’s data member values. For example, the `salariedEmployee` object contains a pointer to the `SalariedEmployee vtable`; the object also contains the values John Smith, 111-11-1111 and \$800.00.

The third level of pointers simply contains the handles to the objects that receive the virtual function calls. The handles in this level may also be references. Fig. 21.24 depicts the vector `employees` that contains `Employee` pointers.

Now let’s see how a typical virtual function call executes. Consider the call `baseClassPtr->print()` in function `virtualViaPointer` (line 75 of Fig. 21.23). Assume that `baseClassPtr` contains `employees[1]` (i.e., the address of object `hourlyEmployee` in `employees`). When the compiler compiles this statement, it determines that the call is indeed being made via a base-class pointer and that `print` is a virtual function.

The compiler determines that `print` is the *second* entry in each of the *vtables*. To locate this entry, the compiler notes that it will need to skip the first entry. Thus, the compiler compiles an **offset** or **displacement** of four bytes (four bytes for each pointer on today’s popular 32-bit machines, and only one pointer needs to be skipped) into the table of machine-language object-code pointers to find the code that will execute the virtual function call.

The compiler generates code that performs the following operations [*Note:* The numbers in the list correspond to the circled numbers in Fig. 21.24]:

1. Select the  $i^{\text{th}}$  entry of `employees` (in this case, the address of object `hourlyEmployee`), and pass it as an argument to function `virtualViaPointer`. This sets parameter `baseClassPtr` to point to `hourlyEmployee`.
2. Dereference that pointer to get to the `hourlyEmployee` object—which, as you recall, begins with a pointer to the `HourlyEmployee vtable`.
3. Dereference `hourlyEmployee`’s *vtable* pointer to get to the `HourlyEmployee vtable`.



4. Skip the offset of four bytes to select the print function pointer.
5. Dereference the print function pointer to form the “name” of the actual function to execute, and use the function call operator () to execute the appropriate print function, which in this case prints the employee’s type, name, social security number, hourly wage and hours worked.

Fig. 21.24’s data structures may appear to be complex, but this complexity is managed by the compiler and hidden from you, making polymorphic programming straightforward. The pointer dereferencing operations and memory accesses that occur on every virtual function call require some additional execution time. The *vtables* and the *vtable* pointers added to the objects require some additional memory. You now have enough information to determine whether virtual functions are appropriate for your programs.



### Performance Tip 21.1

*Polymorphism, as typically implemented with virtual functions and dynamic binding in C++, is efficient. You can use these capabilities with nominal impact on performance.*



### Performance Tip 21.2

*Virtual functions and dynamic binding enable polymorphic programming as an alternative to switch logic programming. Optimizing compilers normally generate polymorphic code that runs as efficiently as hand-coded switch-based logic. Polymorphism’s overhead is acceptable for most applications. But in some situations—such as real-time applications with stringent performance requirements—polymorphism’s overhead may be too high.*



### Software Engineering Observation 21.1.1

*Dynamic binding enables independent software vendors (ISVs) to distribute software without revealing proprietary secrets. Software distributions can consist of only header files and object files—no source code needs to be revealed. Software developers can then use inheritance to derive new classes from those provided by the ISVs. Other software that worked with the classes the ISVs provided will still work with the derived classes and will use the overridden virtual functions provided in these classes (via dynamic binding).*

## 21.8 Case Study: Payroll System Using Polymorphism and Runtime Type Information with Downcasting, `dynamic_cast`, `typeid` and `type_info`

Recall from the problem statement at the beginning of Section 21.6 that, for the current pay period, our fictitious company has decided to reward `BasePlusCommissionEmployees` by adding 10 percent to their base salaries. When processing `Employee` objects polymorphically in Section 21.6.6, we did not need to worry about the “specifics.” Now, however, to adjust the base salaries of `BasePlusCommissionEmployees`, we have to determine the specific type of each `Employee` object at execution time, then act appropriately. This section demonstrates the powerful capabilities of runtime type information (RTTI) and dynamic casting, which enable a program to determine the type of an object at execution time and act on that object accordingly.

[Note: Some compilers require that RTTI be enabled before it can be used in a program. In Visual C++ 2008, this option is enabled by default.]

Figure 21.25 uses the `Employee` hierarchy developed in Section 21.6 and increases by 10 percent the base salary of each `BasePlusCommissionEmployee`. Line 22 declares four-element vector `employees` that stores pointers to `Employee` objects. Lines 25–32 populate the vector with the addresses of dynamically allocated objects of classes `SalariedEmployee` (Figs. 21.15–21.16), `HourlyEmployee` (Figs. 21.17–21.18), `CommissionEmployee` (Figs. 21.19–21.20) and `BasePlusCommissionEmployee` (Figs. 21.21–21.22).

---

```

1 // Fig. 21.25: fig21_25.cpp
2 // Demonstrating downcasting and runtime type information.
3 // NOTE: You may need to enable RTTI on your compiler
4 // before you can execute this application.
5 #include <iostream>
6 #include <iomanip>
7 #include <vector>
8 #include <typeinfo>
9 #include "Employee.h"
10 #include "SalariedEmployee.h"
11 #include "HourlyEmployee.h"
12 #include "CommissionEmployee.h"
13 #include "BasePlusCommissionEmployee.h"
14 using namespace std;
15
16 int main()
17 {
18 // set floating-point output formatting
19 cout << fixed << setprecision(2);
20
21 // create vector of four base-class pointers
22 vector < Employee * > employees(4);
23
24 // initialize vector with various kinds of Employees
25 employees[0] = new SalariedEmployee(
26 "John", "Smith", "111-11-1111", 800);
27 employees[1] = new HourlyEmployee(
28 "Karen", "Price", "222-22-2222", 16.75, 40);
29 employees[2] = new CommissionEmployee(
30 "Sue", "Jones", "333-33-3333", 10000, .06);
31 employees[3] = new BasePlusCommissionEmployee(
32 "Bob", "Lewis", "444-44-4444", 5000, .04, 300);
33
34 // polymorphically process each element in vector employees
35 for (size_t i = 0; i < employees.size(); i++)
36 {
37 employees[i]->print(); // output employee information
38 cout << endl;
39
40 // downcast pointer
41 BasePlusCommissionEmployee *derivedPtr =
42 dynamic_cast < BasePlusCommissionEmployee * >
43 (employees[i]);
44

```

---

**Fig. 21.25** | Demonstrating downcasting and runtime type information. (Part I of 2.)

```

45 // determine whether element points to base-salaried
46 // commission employee
47 if (derivedPtr != 0) // 0 if not a BasePlusCommissionEmployee
48 {
49 double oldBaseSalary = derivedPtr->getBaseSalary();
50 cout << "old base salary: $" << oldBaseSalary << endl;
51 derivedPtr->setBaseSalary(1.10 * oldBaseSalary);
52 cout << "new base salary with 10% increase is: $"
53 << derivedPtr->getBaseSalary() << endl;
54 } // end if
55
56 cout << "earned $" << employees[i]->earnings() << "\n\n";
57 } // end for
58
59 // release objects pointed to by vector's elements
60 for (size_t j = 0; j < employees.size(); j++)
61 {
62 // output class name
63 cout << "deleting object of "
64 << typeid(*employees[j]).name() << endl;
65
66 delete employees[j];
67 } // end for
68 } // end main

```

```

salaried employee: John Smith
social security number: 111-11-1111
weekly salary: 800.00
earned $800.00

hourly employee: Karen Price
social security number: 222-22-2222
hourly wage: 16.75; hours worked: 40.00
earned $670.00

commission employee: Sue Jones
social security number: 333-33-3333
gross sales: 10000.00; commission rate: 0.06
earned $600.00

base-salaried commission employee: Bob Lewis
social security number: 444-44-4444
gross sales: 5000.00; commission rate: 0.04; base salary: 300.00
old base salary: $300.00
new base salary with 10% increase is: $330.00
earned $530.00

deleting object of class SalariedEmployee
deleting object of class HourlyEmployee
deleting object of class CommissionEmployee
deleting object of class BasePlusCommissionEmployee

```

**Fig. 21.25** | Demonstrating downcasting and runtime type information. (Part 2 of 2.)

The for statement in lines 35–57 iterates through the `employees` vector and displays each `Employee`'s information by invoking member function `print` (line 37). Recall that

because `print` is declared `virtual` in base class `Employee`, the system invokes the appropriate derived-class object's `print` function.

In this example, as we encounter `BasePlusCommissionEmployee` objects, we wish to increase their base salary by 10 percent. Since we process the employees generically (i.e., polymorphically), we cannot (with the techniques we've learned) be certain as to which type of `Employee` is being manipulated at any given time. This creates a problem, because `BasePlusCommissionEmployee` employees must be identified when we encounter them so they can receive the 10 percent salary increase. To accomplish this, we use operator `dynamic_cast` (line 42) to determine whether the type of each object is `BasePlusCommissionEmployee`. This is the downcast operation we referred to in Section 21.3.3. Lines 41–43 dynamically downcast `employees[i]` from type `Employee *` to type `BasePlusCommissionEmployee *`. If the vector element points to an object that *is a* `BasePlusCommissionEmployee` object, then that object's address is assigned to `commissionPtr`; otherwise, 0 is assigned to derived-class pointer `derivedPtr`.

If the value returned by the `dynamic_cast` operator in lines 41–43 is not 0, the object is the correct type, and the `if` statement (lines 47–54) performs the special processing required for the `BasePlusCommissionEmployee` object. Lines 49, 51 and 53 invoke `BasePlusCommissionEmployee` functions `getBaseSalary` and `setBaseSalary` to retrieve and update the employee's salary.

Line 56 invokes member function `earnings` on the object to which `employees[i]` points. Recall that `earnings` is declared `virtual` in the base class, so the program invokes the derived-class object's `earnings` function—another example of dynamic binding.

Lines 60–67 display each employee's object type and uses the `delete` operator to deallocate the dynamic memory to which each vector element points. Operator `typeid` (line 64) returns a reference to an object of class `type_info` that contains the information about the type of its operand, including the name of that type. When invoked, `type_info` member function `name` (line 64) returns a pointer-based string that contains the type name (e.g., "class `BasePlusCommissionEmployee`") of the argument passed to `typeid`. To use `typeid`, the program must include header file `<typeinfo>` (line 8).



### Portability Tip 21.1

*The string returned by `type_info` member function `name` may vary by compiler.*

We avoid several compilation errors in this example by downcasting an `Employee` pointer to a `BasePlusCommissionEmployee` pointer (lines 41–43). If we remove the `dynamic_cast` from line 42 and attempt to assign the current `Employee` pointer directly to `BasePlusCommissionEmployee` pointer `derivedPtr`, we'll receive a compilation error. C++ does not allow a program to assign a base-class pointer to a derived-class pointer because the *is-a* relationship does not apply—a `CommissionEmployee` is *not* a `BasePlusCommissionEmployee`. The *is-a* relationship applies only between the derived class and its base classes, not vice versa.

Similarly, if lines 49, 51 and 53 used the current base-class pointer from `employees`, rather than derived-class pointer `derivedPtr`, to invoke derived-class-only functions `getBaseSalary` and `setBaseSalary`, we'd receive a compilation error at each of these lines. As you learned in Section 21.3.3, attempting to invoke derived-class-only functions through a base-class pointer is not allowed. Although lines 49, 51 and 53 execute only if

`commissionPtr` is not 0 (i.e., if the cast can be performed), we cannot attempt to invoke derived-class `BasePlusCommissionEmployee` functions `getBaseSalary` and `setBaseSalary` on the base-class `Employee` pointer. Recall that, using a base class `Employee` pointer, we can invoke only functions found in base class `Employee`—`earnings`, `print` and `Employee`’s *get* and *set* functions.

## 21.9 Virtual Destructors

A problem can occur when using polymorphism to process dynamically allocated objects of a class hierarchy. So far you’ve seen **nonvirtual destructors**—destructors that are not declared with keyword `virtual`. If a derived-class object with a nonvirtual destructor is destroyed explicitly by applying the `delete` operator to a base-class pointer to the object, the C++ standard specifies that the behavior is undefined.

The simple solution to this problem is to create a **virtual destructor** (i.e., a destructor that is declared with keyword `virtual`) in the base class. This makes all derived-class destructors *virtual even though they do not have the same name as the base-class destructor*. Now, if an object in the hierarchy is destroyed explicitly by applying the `delete` operator to a base-class pointer, the destructor for the appropriate class is called based on the object to which the base-class pointer points. Remember, when a derived-class object is destroyed, the base-class part of the derived-class object is also destroyed, so it’s important for the destructors of both the derived class and base class to execute. The base-class destructor automatically executes after the derived-class destructor.



### Error-Prevention Tip 21.2

*If a class has `virtual` functions, provide a `virtual` destructor, even if one is not required for the class. This ensures that a custom derived-class destructor (if there is one) will be invoked when a derived-class object is deleted via a base class pointer.*



### Common Programming Error 21.5

*Constructors cannot be `virtual`. Declaring a constructor `virtual` is a compilation error.*

## 21.10 Wrap-Up

In this chapter we discussed polymorphism, which enables us to “program in the general” rather than “program in the specific,” and we showed how this makes programs more extensible. We began with an example of how polymorphism would allow a screen manager to display several “space” objects. We then demonstrated how base-class and derived-class pointers can be aimed at base-class and derived-class objects. We said that aiming base-class pointers at base-class objects is natural, as is aiming derived-class pointers at derived-class objects. Aiming base-class pointers at derived-class objects is also natural because a derived-class object *is an* object of its base class. You learned why aiming derived-class pointers at base-class objects is dangerous and why the compiler disallows such assignments. We introduced `virtual` functions, which enable the proper functions to be called when objects at various levels of an inheritance hierarchy are referenced (at execution time) via base-class pointers. This is known as dynamic or late binding. We then discussed pure `virtual` functions (`virtual` functions that do not provide an implementation) and abstract classes

(classes with one or more pure virtual functions). You learned that abstract classes cannot be used to instantiate objects, while concrete classes can. We then demonstrated using abstract classes in an inheritance hierarchy. You learned how polymorphism works “under the hood” with *vtables* that are created by the compiler. We used runtime type information (RTTI) and dynamic casting to determine the type of an object at execution time and act on that object accordingly. The chapter concluded with a discussion of virtual destructors, and how they ensure that all appropriate destructors in an inheritance hierarchy run on a derived-class object when that object is deleted via a base-class pointer.

In the next chapter, we discuss templates, a sophisticated feature of C++ that enables you to define a family of related classes or functions with a single code segment.

## Summary

### Section 21.1 Introduction

- Polymorphism enables us to “program in the general” rather than “program in the specific.”
- Polymorphism enables us to write programs that process objects of classes that are part of the same class hierarchy as if they were all objects of the hierarchy’s base class.
- With polymorphism, we can design and implement systems that are easily extensible—new classes can be added with little or no modification to the general portions of the program. The only parts of a program that must be altered to accommodate new classes are those that require direct knowledge of the new classes that you add to the hierarchy.
- Runtime type information (RTTI) and dynamic casting enable a program to determine the type of an object at execution time and act on that object accordingly.

### Section 21.2 Polymorphism Examples

- With polymorphism, one function can cause different actions to occur, depending on the type of the object on which the function is invoked.
- This makes it possible to design and implement more extensible systems. Programs can be written to process objects of types that may not exist when the program is under development.

### Section 21.3 Relationships Among Objects in an Inheritance Hierarchy

- C++ enables polymorphism—the ability for objects of different classes related by inheritance to respond differently to the same member-function call.
- Polymorphism is implemented via virtual functions and dynamic binding.
- When a base-class pointer or reference is used to call a virtual function, C++ chooses the correct overridden function in the appropriate derived class associated with the object.
- If a virtual function is called by referencing a specific object by name and using the dot member-selection operator, the reference is resolved at compile time (this is called static binding); the virtual function that is called is the one defined for the class of that particular object.
- Derived classes can provide their own implementations of a base-class virtual function if necessary, but if they do not, the base class’s implementation is used.

### Section 21.4 Type Fields and switch Statements

- Polymorphic programming with virtual functions can eliminate the need for switch logic. You can use the virtual function mechanism to perform the equivalent logic automatically, thus avoiding the kinds of errors typically associated with switch logic.

### Section 21.5 Abstract Classes and Pure **virtual** Functions

- Abstract classes are typically used as base classes, so we refer to them as abstract base classes. No objects of an abstract class may be instantiated.
- Classes from which objects can be instantiated are concrete classes.
- You create an abstract class by declaring one or more pure **virtual** functions with pure specifiers (`= 0`) in their declarations.
- If a class is derived from a class with a pure **virtual** function and that derived class does not supply a definition for that pure **virtual** function, then that **virtual** function remains pure in the derived class. Consequently, the derived class is also an abstract class.
- Although we cannot instantiate objects of abstract base classes, we can declare pointers and references to objects of abstract base classes. Such pointers and references can be used to enable polymorphic manipulations of derived-class objects instantiated from concrete derived classes.

### Section 21.7 (Optional) Polymorphism, Virtual Functions and Dynamic Binding “Under the Hood”

- Dynamic binding requires that at runtime, the call to a virtual member function be routed to the virtual function version appropriate for the class. A virtual function table called the *vtable* is implemented as an array containing function pointers. Each class with virtual functions has a *vtable*. For each virtual function in the class, the *vtable* has an entry containing a function pointer to the version of the virtual function to use for an object of that class. The virtual function to use for a particular class could be the function defined in that class, or it could be a function inherited either directly or indirectly from a base class higher in the hierarchy.
- When a base class provides a virtual member function, derived classes can override the virtual function, but they do not have to override it.
- Each object of a class with virtual functions contains a pointer to the *vtable* for that class. When a function call is made from a base-class pointer to a derived-class object, the appropriate function pointer in the *vtable* is obtained and dereferenced to complete the call at execution time.
- Any class that has one or more 0 pointers in its *vtable* is an abstract class. Classes without any 0 *vtable* pointers are concrete classes.
- New kinds of classes are regularly added to systems and accommodated by dynamic binding.

### Section 21.8 Case Study: Payroll System Using Polymorphism and Runtime Type Information with **Downcasting**, **dynamic\_cast**, **typeid** and **type\_info**

- Operator **dynamic\_cast** checks the type of the object to which a pointer points, then determines whether the type has an *is-a* relationship with the type to which the pointer is being converted. If so, **dynamic\_cast** returns the object's address. If not, **dynamic\_cast** returns 0.
- Operator **typeid** returns a reference to a **type\_info** object that contains information about the operand's type, including the type name. To use **typeid**, the program must include header file `<typeinfo>`.
- When invoked, **type\_info** member function **name** returns a pointer-based string that contains the name of the type that the **type\_info** object represents.
- Operators **dynamic\_cast** and **typeid** are part of C++'s runtime type information (RTTI) feature, which allows a program to determine an object's type at runtime.

### Section 21.9 Virtual Destructors

- Declare the base-class destructor **virtual** if the class contains virtual functions. This makes all derived-class destructors virtual, even though they do not have the same name as the base-class destructor. If an object in the hierarchy is destroyed explicitly by applying the **delete** operator

to a base-class pointer to a derived-class object, the destructor for the appropriate class is called. After a derived-class destructor runs, the destructors for all of that class's base classes run all the way up the hierarchy.

## Terminology

- abstract base classes 799
- abstract classes 799
- concrete classes 799
- displacement into a *vtable* 821
- downcasting 792
- dynamic binding 793
- dynamic casting 780
- `dynamic_cast` 825
- implementation inheritance 802
- interface inheritance 802
- iterator class 801
- late binding 793
- name function of class `type_info` 825
- nonvirtual destructor 826
- offset into a *vtable* 821
- override 792
- polymorphism 779
- pure specifier (with virtual functions) 800
- pure virtual function 800
- runtime type information (RTTI) 780
- static binding 793
- `typeid` operator 825
- `type_info` class 825
- `<typeinfo>` header file 825
- virtual destructor 826
- virtual function 792
- virtual function table (*vtable*) 819

## Self-Review Exercises

- 21.1** Fill in the blanks in each of the following statements:
- a) Treating a base-class object as a(n) \_\_\_\_\_ can cause errors.
  - b) Polymorphism helps eliminate \_\_\_\_\_ logic.
  - c) If a class contains at least one pure virtual function, it's a(n) \_\_\_\_\_ class.
  - d) Classes from which objects can be instantiated are called \_\_\_\_\_ classes.
  - e) Operator \_\_\_\_\_ can be used to downcast base-class pointers safely.
  - f) Operator `typeid` returns a reference to a(n) \_\_\_\_\_ object.
  - g) \_\_\_\_\_ involves using a base-class pointer or reference to invoke virtual functions on base-class and derived-class objects.
  - h) Overridable functions are declared using keyword \_\_\_\_\_.
  - i) Casting a base-class pointer to a derived-class pointer is called \_\_\_\_\_.
- 21.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- a) All virtual functions in an abstract base class must be declared as pure virtual functions.
  - b) Referring to a derived-class object with a base-class handle is dangerous.
  - c) A class is made abstract by declaring that class `virtual`.
  - d) If a base class declares a pure virtual function, a derived class must implement that function to become a concrete class.
  - e) Polymorphic programming can eliminate the need for switch logic.

## Answers to Self-Review Exercises

**21.1** a) derived-class object. b) switch. c) abstract. d) concrete. e) `dynamic_cast`. f) `type_info`. g) Polymorphism. h) `virtual`. i) downcasting.

**21.2** a) False. An abstract base class can include virtual functions with implementations. b) False. Referring to a base-class object with a derived-class handle is dangerous. c) False. Classes are never declared `virtual`. Rather, a class is made abstract by including at least one pure virtual function in the class. d) True. e) True.



## Exercises

**21.3** How is it that polymorphism enables you to program “in the general” rather than “in the specific”? Discuss the key advantages of programming “in the general.”

**21.4** Discuss the problems of programming with `switch` logic. Explain why polymorphism can be an effective alternative to using `switch` logic.

**21.5** Distinguish between inheriting interface and inheriting implementation. How do inheritance hierarchies designed for inheriting interface differ from those designed for inheriting implementation?

**21.6** What are virtual functions? Describe a circumstance in which virtual functions would be appropriate.

**21.7** Distinguish between static binding and dynamic binding. Explain the use of virtual functions and the *virtual* in dynamic binding.

**21.8** Distinguish between virtual functions and pure virtual functions.

**21.9** (*Abstract Base Classes*) Suggest one or more levels of abstract base classes for the Shape hierarchy discussed in this chapter and shown in Fig. 20.3. (The first level is Shape, and the second level consists of the classes `TwoDimensionalShape` and `ThreeDimensionalShape`.)

**21.10** How does polymorphism promote extensibility?

**21.11** You’ve been asked to develop a flight simulator that will have elaborate graphical outputs. Explain why polymorphic programming could be especially effective for a problem of this nature.

**21.12** (*Payroll System Modification*) Modify the payroll system of Figs. 21.13–21.23 to include private data member `birthDate` in class `Employee`. Use class `Date` from Figs. 19.9–19.10 to represent an employee’s birthday. Assume that payroll is processed once per month. Create a vector of `Employee` references to store the various employee objects. In a loop, calculate the payroll for each `Employee` (polymorphically), and add a \$100.00 bonus to the person’s payroll amount if the current month is the month in which the `Employee`’s birthday occurs.

**21.13** (*Shape Hierarchy*) Implement the Shape hierarchy designed in Exercise 20.7 (which is based on the hierarchy in Fig. 20.3). Each `TwoDimensionalShape` should contain function `getArea` to calculate the area of the two-dimensional shape. Each `ThreeDimensionalShape` should have member functions `getArea` and `getVolume` to calculate the surface area and volume, respectively, of the three-dimensional shape. Create a program that uses a vector of Shape pointers to objects of each concrete class in the hierarchy. The program should print the object to which each vector element points. Also, in the loop that processes all the shapes in the vector, determine whether each shape is a `TwoDimensionalShape` or a `ThreeDimensionalShape`. If a shape is a `TwoDimensionalShape`, display its area. If a shape is a `ThreeDimensionalShape`, display its area and volume.

**21.14** (*Project: Polymorphic Screen Manager Using Shape Hierarchy*) Develop a basic graphics package. Use the Shape hierarchy implemented in Exercise 21.13. Limit yourself to two-dimensional shapes such as squares, rectangles, triangles and circles. Interact with the user. Let the user specify the position, size, shape and fill characters to be used in drawing each shape. The user can specify more than one of the same shape. As you create each shape, place a `Shape *` pointer to each new Shape object into an array. Each Shape class should now have its own draw member function. Write a polymorphic screen manager that walks through the array, sending draw messages to each object in the array to form a screen image. Redraw the screen image each time the user specifies an additional shape.

**21.15** (*Package Inheritance Hierarchy*) Use the Package inheritance hierarchy created in Exercise 20.9 to create a program that displays the address information and calculates the shipping costs for several Packages. The program should contain a vector of Package pointers to objects of

classes `TwoDayPackage` and `OvernightPackage`. Loop through the vector to process the Packages polymorphically. For each Package, invoke *get* functions to obtain the address information of the sender and the recipient, then print the two addresses as they would appear on mailing labels. Also, call each Package's `calculateCost` member function and print the result. Keep track of the total shipping cost for all Packages in the vector, and display this total when the loop terminates.

**21.16** (*Polymorphic Banking Program Using Account Hierarchy*) Develop a polymorphic banking program using the Account hierarchy created in Exercise 20.10. Create a vector of Account pointers to `SavingsAccount` and `CheckingAccount` objects. For each Account in the vector, allow the user to specify an amount of money to withdraw from the Account using member function `debit` and an amount of money to deposit into the Account using member function `credit`. As you process each Account, determine its type. If an Account is a `SavingsAccount`, calculate the amount of interest owed to the Account using member function `calculateInterest`, then add the interest to the account balance using member function `credit`. After processing an Account, print the updated account balance obtained by invoking base-class member function `getBalance`.

## Making a Difference

**21.17** (*CarbonFootprint Abstract Class: Polymorphism*) Using an abstract class with only pure virtual functions, you can specify similar behaviors for possibly disparate classes. Governments and companies worldwide are becoming increasingly concerned with carbon footprints (annual releases of carbon dioxide into the atmosphere) from buildings burning various types of fuels for heat, vehicles burning fuels for power, and the like. Many scientists blame these greenhouse gases for the phenomenon called global warming. Create three small classes unrelated by inheritance—classes `Building`, `Car` and `Bicycle`. Give each class some unique appropriate attributes and behaviors that it does not have in common with other classes. Write an abstract class `CarbonFootprint` with only a pure virtual `getCarbonFootprint` method. Have each of your classes inherit from that abstract class and implement the `getCarbonFootprint` method to calculate an appropriate carbon footprint for that class (check out a few websites that explain how to calculate carbon footprints). Write an application that creates objects of each of the three classes, places pointers to those objects in a vector of `CarbonFootprint` pointers, then iterates through the vector, polymorphically invoking each object's `getCarbonFootprint` method. For each object, print some identifying information and the object's carbon footprint.

# 22

## Templates

*Behind that outside pattern  
the dim shapes get clearer every  
day.*

*It is always the same shape, only  
very numerous.*

—Charlotte Perkins Gilman

*Every man of genius sees the  
world at a different angle from  
his fellows.*

—Havelock Ellis

*...our special individuality, as  
distinguished from our generic  
humanity.*

—Oliver Wendell Holmes, Sr.

### Objectives

In this chapter you'll learn:

- To use function templates to conveniently create a group of related (overloaded) functions.
- To distinguish between function templates and function-template specializations.
- To use class templates to create groups of related types.
- To distinguish between class templates and class-template specializations.
- To overload function templates.
- To understand the relationships among templates, friends, inheritance and static members.



|                                                                      |                                                                |
|----------------------------------------------------------------------|----------------------------------------------------------------|
| <b>22.1</b> Introduction                                             | <b>22.6</b> Notes on Templates and Inheritance                 |
| <b>22.2</b> Function Templates                                       | <b>22.7</b> Notes on Templates and Friends                     |
| <b>22.3</b> Overloading Function Templates                           | <b>22.8</b> Notes on Templates and <code>static</code> Members |
| <b>22.4</b> Class Templates                                          | <b>22.9</b> Wrap-Up                                            |
| <b>22.5</b> Nontype Parameters and Default Types for Class Templates |                                                                |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 22.1 Introduction

In this chapter, we discuss one of C++’s more powerful software reuse features, namely **templates**. **Function templates** and **class templates** enable you to specify, with a single code segment, an entire range of related (overloaded) functions—called **function-template specializations**—or an entire range of related classes—called **class-template specializations**. This technique is called **generic programming**.

We might write a single function template for an array-sort function, then have C++ generate separate function-template specializations that will sort `int` arrays, `float` arrays, `string` arrays and so on. We introduced function templates in Chapter 15. We present an additional discussion and example in this chapter.

We might write a single class template for a stack class, then have C++ generate separate class-template specializations, such as a stack-of-`int` class, a stack-of-`float` class, a stack-of-`string` class and so on.

Note the distinction between templates and template specializations: Function templates and class templates are like stencils out of which we trace shapes; function-template specializations and class-template specializations are like the separate tracings that all have the same shape, but could, for example, be drawn in different colors.

In this chapter, we present a function template and a class template. We also consider the relationships between templates and other C++ features, such as overloading, inheritance, friends and `static` members. The design and details of the template mechanisms discussed here are based on the work of Bjarne Stroustrup as presented in his paper, “Parameterized Types for C++”—published in the *Proceedings of the USENIX C++ Conference* held in Denver, Colorado, in October 1988.



### Software Engineering Observation 22.1

*Most C++ compilers require the complete definition of a template to appear in the client source-code file that uses the template. For this reason and for reusability, templates are often defined in header files, which are then `#include`d into the appropriate client source-code files. For class templates, this means that the member functions are also defined in the header file.*

## 22.2 Function Templates

Overloaded functions normally perform *similar* or *identical* operations on different types of data. If the operations are *identical* for each type, they can be expressed more compactly

and conveniently using function templates. Initially, you write a single function-template definition. Based on the argument types provided explicitly or inferred from calls to this function, the compiler generates separate source-code functions (i.e., function-template specializations) to handle each function call appropriately. In C, this task can be performed using **macros** created with the preprocessor directive `#define` (see Chapter 13). However, macros can have serious side effects and do not enable the compiler to perform type checking. Function templates provide a compact solution, like macros, but enable full type checking.



### Error-Prevention Tip 22.1

*Function templates, like macros, enable software reuse. Unlike macros, function templates help eliminate many types of errors through the scrutiny of full C++ type checking.*

All **function-template definitions** begin with keyword **template** followed by a list of **template parameters** to the function template enclosed in **angle brackets** (`<` and `>`); each template parameter that represents a type must be preceded by either of the interchangeable keywords `class` or **typename**, as in

```
template< typename T >
```

or

```
template< class ElementType >
```

or

```
template< typename BorderType, typename FillType >
```

The type template parameters of a function-template definition are used to specify the types of the arguments to the function, to specify the return type of the function and to declare variables within the function. The function definition follows and appears like any other function definition. Keywords `typename` and `class` used to specify function-template parameters actually mean “any fundamental type or user-defined type.”



### Common Programming Error 22.1

*Not placing keyword `class` or keyword `typename` before each type template parameter of a function template is a syntax error.*

### Example: Function Template **printArray**

Let’s examine function template `printArray` in Fig. 22.1, lines 7–14. Function template `printArray` declares (line 7) a single template parameter `T` (`T` can be any valid identifier) for the type of the array to be printed by function `printArray`; `T` is referred to as a **type template parameter**, or type parameter. You’ll see nontype template parameters in Section 22.5.

```
1 // Fig. 22.1: fig22_01.cpp
2 // Using template functions.
3 #include <iostream>
```

**Fig. 22.1** | Function-template specializations of function template `printArray`. (Part 1 of 2.)

```

4 using namespace std;
5
6 // function template printArray definition
7 template< typename T >
8 void printArray(const T * const array, int count)
9 {
10 for (int i = 0; i < count; i++)
11 cout << array[i] << " ";
12
13 cout << endl;
14 } // end function template printArray
15
16 int main()
17 {
18 const int aCount = 5; // size of array a
19 const int bCount = 7; // size of array b
20 const int cCount = 6; // size of array c
21
22 int a[aCount] = { 1, 2, 3, 4, 5 };
23 double b[bCount] = { 1.1, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7 };
24 char c[cCount] = "HELLO"; // 6th position for null
25
26 cout << "Array a contains:" << endl;
27
28 // call integer function-template specialization
29 printArray(a, aCount);
30
31 cout << "Array b contains:" << endl;
32
33 // call double function-template specialization
34 printArray(b, bCount);
35
36 cout << "Array c contains:" << endl;
37
38 // call character function-template specialization
39 printArray(c, cCount);
40 } // end main

```

```

Array a contains:
1 2 3 4 5
Array b contains:
1.1 2.2 3.3 4.4 5.5 6.6 7.7
Array c contains:
H E L L O

```

**Fig. 22.1** | Function-template specializations of function template `printArray`. (Part 2 of 2.)

When the compiler detects a `printArray` function invocation in the client program (e.g., lines 29, 34 and 39), the compiler uses its overload resolution capabilities to find a definition of function `printArray` that best matches the function call. In this case, the only `printArray` function with the appropriate number of parameters is the `printArray` function template (lines 7–14). Consider the function call at line 29. The compiler com-



compares the type of `printArray`'s first argument (`int *` at line 29) to the `printArray` function template's first parameter (`const T * const` at line 8) and deduces that replacing the type parameter `T` with `int` would make the argument consistent with the parameter. Then, the compiler substitutes `int` for `T` throughout the template definition and compiles a `printArray` specialization that can display an array of `int` values. In Fig. 22.1, the compiler creates three `printArray` specializations—one that expects an `int` array, one that expects a `double` array and one that expects a `char` array. For example, the function-template specialization for type `int` is

```
void printArray(const int * const array, int count)
{
 for (int i = 0; i < count; i++)
 cout << array[i] << " ";

 cout << endl;
} // end function printArray
```

As with function parameters, the names of template parameters must be unique inside a template definition. Template parameter names need not be unique across different function templates.

Figure 22.1 demonstrates function template `printArray` (lines 7–14). The program begins by declaring five-element `int` array `a`, seven-element `double` array `b` and six-element `char` array `c` (lines 22–24, respectively). Then, the program outputs each array by calling `printArray`—once with a first argument `a` of type `int *` (line 29), once with a first argument `b` of type `double *` (line 34) and once with a first argument `c` of type `char *` (line 39). The call in line 29, for example, causes the compiler to infer that `T` is `int` and to instantiate a `printArray` function-template specialization, for which type parameter `T` is `int`. The call in line 34 causes the compiler to infer that `T` is `double` and to instantiate a second `printArray` function-template specialization, for which type parameter `T` is `double`. The call in line 39 causes the compiler to infer that `T` is `char` and to instantiate a third `printArray` function-template specialization, for which type parameter `T` is `char`. It's important to note that if `T` (line 7) represents a user-defined type (which it does not in Fig. 22.1), there must be an overloaded stream insertion operator for that type; otherwise, the first stream insertion operator in line 11 will not compile.



### Common Programming Error 22.2

*If a template is invoked with a user-defined type, and if that template uses functions or operators (e.g., `==`, `+`, `<=`) with objects of that class type, then those functions and operators must be overloaded for the user-defined type. Forgetting to overload such operators causes compilation errors.*

In this example, the template mechanism saves you from having to write three separate overloaded functions with prototypes

```
void printArray(const int * const, int);
void printArray(const double * const, int);
void printArray(const char * const, int);
```

that all use the same code, except for type `T` (as used in line 8).



### Performance Tip 22.1

*Although templates offer software-reusability benefits, remember that multiple function-template specializations and class-template specializations are instantiated in a program (at compile time), despite the fact that the templates are written only once. These copies can consume considerable memory. This is not normally an issue, though, because the code generated by the template is the same size as the code you'd have written to produce the separate overloaded functions.*

## 22.3 Overloading Function Templates

Function templates and overloading are intimately related. The function-template specializations generated from a function template all have the same name, so the compiler uses overloading resolution to invoke the proper function.

A function template may be overloaded in several ways. We can provide other function templates that specify the same function name but different function parameters. For example, function template `printArray` of Fig. 22.1 could be overloaded with another `printArray` function template with additional parameters `lowSubscript` and `highSubscript` to specify the portion of the array to output (see Exercise 22.4).

A function template also can be overloaded by providing nontemplate functions with the same function name but different function arguments. For example, function template `printArray` of Fig. 22.1 could be overloaded with a nontemplate version that specifically prints an array of character strings in neat, tabular format (see Exercise 22.5).

The compiler performs a matching process to determine what function to call when a function is invoked. First, the compiler tries to find and use a precise match in which the function names and argument types are consistent with those of the function call. If this fails, the compiler determines whether a function template is available that can be used to generate a function-template specialization with a precise match of function name and argument types. If such a function template is found, the compiler generates and uses the appropriate function-template specialization. If not, the compiler generates an error message. Also, if there are multiple matches for the function call, the compiler considers the call to be ambiguous and the compiler generates an error message.



### Common Programming Error 22.3

*A compilation error occurs if no matching function definition can be found for a particular function call or if there are multiple matches that the compiler considers ambiguous.*

## 22.4 Class Templates

It's possible to understand the concept of a “stack” (a data structure into which we insert items at the top and retrieve those items in last-in, first-out order) independent of the type of the items being placed in the stack. However, to instantiate a stack, a data type must be specified. This creates a wonderful opportunity for software reusability. We need the means for describing the notion of a stack generically and instantiating classes that are type-specific versions of this generic stack class. C++ provides this capability through class templates.





### Software Engineering Observation 22.2

*Class templates encourage software reusability by enabling type-specific versions of generic classes to be instantiated.*

Class templates are called **parameterized types**, because they require one or more type parameters to specify how to customize a “generic class” template to form a class-template specialization.

To produce a variety of class-template specializations you write only one class-template definition. Each time an additional class-template specialization is needed, you use a concise, simple notation, and the compiler writes the source code for the specialization you require. One `Stack` class template, for example, could thus become the basis for creating many `Stack` classes (such as “`Stack of double`,” “`Stack of int`,” “`Stack of char`,” “`Stack of Employee`,” etc.) used in a program.

#### Creating Class Template `Stack<T>`

Note the `Stack` class-template definition in Fig. 22.2. It looks like a conventional class definition, except that it’s preceded by the header (line 6)

```
template< typename T >
```

to specify a class-template definition with type parameter `T` which acts as a placeholder for the type of the `Stack` class to be created. You need not specifically use identifier `T`—any valid identifier can be used. The type of element to be stored on this `Stack` is mentioned generically as `T` throughout the `Stack` class header and member-function definitions. In a moment, we show how `T` becomes associated with a specific type, such as `double` or `int`. Due to the way this class template is designed, there are two constraints for nonfundamental data types used with this `Stack`—they must have a default constructor (for use in line 44 to create the array that stores the stack elements), and their assignment operators must properly copy objects into the `Stack` (lines 56 and 70).

```
1 // Fig. 22.2: Stack.h
2 // Stack class template.
3 #ifndef STACK_H
4 #define STACK_H
5
6 template< typename T >
7 class Stack
8 {
9 public:
10 Stack(int = 10); // default constructor (Stack size 10)
11
12 // destructor
13 ~Stack()
14 {
15 delete [] stackPtr; // deallocate internal space for Stack
16 } // end ~Stack destructor
17
18 bool push(const T &); // push an element onto the Stack
19 bool pop(T &); // pop an element off the Stack
```

**Fig. 22.2** | Class template `Stack`. (Part I of 3.)

```

20
21 // determine whether Stack is empty
22 bool isEmpty() const
23 {
24 return top == -1;
25 } // end function isEmpty
26
27 // determine whether Stack is full
28 bool isFull() const
29 {
30 return top == size - 1;
31 } // end function isFull
32
33 private:
34 int size; // # of elements in the Stack
35 int top; // location of the top element (-1 means empty)
36 T *stackPtr; // pointer to internal representation of the Stack
37 }; // end class template Stack
38
39 // constructor template
40 template< typename T >
41 Stack< T >::Stack(int s)
42 : size(s > 0 ? s : 10), // validate size
43 top(-1), // Stack initially empty
44 stackPtr(new T[size]) // allocate memory for elements
45 {
46 // empty body
47 } // end Stack constructor template
48
49 // push element onto Stack;
50 // if successful, return true; otherwise, return false
51 template< typename T >
52 bool Stack< T >::push(const T &pushValue)
53 {
54 if (!isFull())
55 {
56 stackPtr[++top] = pushValue; // place item on Stack
57 return true; // push successful
58 } // end if
59
60 return false; // push unsuccessful
61 } // end function template push
62
63 // pop element off Stack;
64 // if successful, return true; otherwise, return false
65 template< typename T >
66 bool Stack< T >::pop(T &popValue)
67 {
68 if (!isEmpty())
69 {
70 popValue = stackPtr[top--]; // remove item from Stack
71 return true; // pop successful
72 } // end if

```

**Fig. 22.2** | Class template Stack. (Part 2 of 3.)

```

73
74 return false; // pop unsuccessful
75 } // end function template pop
76
77 #endif

```

**Fig. 22.2** | Class template *Stack*. (Part 3 of 3.)

The member-function definitions of a class template are function templates. The member-function definitions that appear outside the class template definition each begin with the header

```
template< typename T >
```

(lines 40, 51 and 65). Thus, each definition resembles a conventional function definition, except that the *Stack* element type always is listed generically as type parameter *T*. The binary scope resolution operator is used with the class-template name *Stack*< *T* > (lines 41, 52 and 66) to tie each member-function definition to the class template's scope. In this case, the generic class name is *Stack*< *T* >. When *doubleStack* is instantiated as type *Stack*<*double*>, the *Stack* constructor function-template specialization uses *new* to create an array of elements of type *double* to represent the stack (line 44). The statement

```
stackPtr(new T[size]);
```

in the *Stack* class-template definition is generated by the compiler in the class-template specialization *Stack*<*double*> as

```
stackPtr(new double[size]);
```

### *Creating a Driver to Test Class Template Stack< T >*

Now, let's consider the driver (Fig. 22.3) that exercises the *Stack* class template. The driver begins by instantiating object *doubleStack* of size 5 (line 9). This object is declared to be of class *Stack*< *double* > (pronounced "Stack of *double*"). The compiler associates type *double* with type parameter *T* in the class template to produce the source code for a *Stack* class of type *double*. Although templates offer software-reusability benefits, remember that multiple class-template specializations are instantiated in a program (at compile time), even though the template is written only once.

```

1 // Fig. 22.3: fig22_03.cpp
2 // Stack class template test program.
3 #include <iostream>
4 #include "Stack.h" // Stack class template definition
5 using namespace std;
6
7 int main()
8 {
9 Stack< double > doubleStack(5); // size 5
10 double doubleValue = 1.1;
11

```

**Fig. 22.3** | Class template *Stack* test program. (Part 1 of 2.)

```

12 cout << "Pushing elements onto doubleStack\n";
13
14 // push 5 doubles onto doubleStack
15 while (doubleStack.push(doubleValue))
16 {
17 cout << doubleValue << ' ';
18 doubleValue += 1.1;
19 } // end while
20
21 cout << "\nStack is full. Cannot push " << doubleValue
22 << "\n\nPopping elements from doubleStack\n";
23
24 // pop elements from doubleStack
25 while (doubleStack.pop(doubleValue))
26 cout << doubleValue << ' ';
27
28 cout << "\nStack is empty. Cannot pop\n";
29
30 Stack< int > intStack; // default size 10
31 int intValue = 1;
32 cout << "\nPushing elements onto intStack\n";
33
34 // push 10 integers onto intStack
35 while (intStack.push(intValue))
36 {
37 cout << intValue++ << ' ';
38 } // end while
39
40 cout << "\nStack is full. Cannot push " << intValue
41 << "\n\nPopping elements from intStack\n";
42
43 // pop elements from intStack
44 while (intStack.pop(intValue))
45 cout << intValue << ' ';
46
47 cout << "\nStack is empty. Cannot pop" << endl;
48 } // end main

```

```

Pushing elements onto doubleStack
1.1 2.2 3.3 4.4 5.5
Stack is full. Cannot push 6.6

Popping elements from doubleStack
5.5 4.4 3.3 2.2 1.1
Stack is empty. Cannot pop

Pushing elements onto intStack
1 2 3 4 5 6 7 8 9 10
Stack is full. Cannot push 11

Popping elements from intStack
10 9 8 7 6 5 4 3 2 1
Stack is empty. Cannot pop

```

**Fig. 22.3** | Class template Stack test program. (Part 2 of 2.)

Lines 15–19 invoke `push` to place the `double` values 1.1, 2.2, 3.3, 4.4 and 5.5 onto `doubleStack`. The `while` loop terminates when the driver attempts to push a sixth value onto `doubleStack` (which is full, because it holds a maximum of five elements). Function `push` returns `false` when it's unable to push a value onto the stack.<sup>1</sup>

Lines 25–26 invoke `pop` in a `while` loop to remove the five values from the stack (note, in the output of Fig. 22.3, that the values do pop off in last-in, first-out order). When the driver attempts to pop a sixth value, the `doubleStack` is empty, so the `pop` loop terminates.

Line 30 instantiates integer stack `intStack` with the declaration

```
Stack< int > intStack;
```

(pronounced “`intStack` is a `Stack` of `int`”). Because no size is specified, the size defaults to 10 as specified in the default constructor (Fig. 22.2, line 10). Lines 35–38 loop and invoke `push` to place values onto `intStack` until it's full, then lines 44–45 loop and invoke `pop` to remove values from `intStack` until it's empty. Once again, notice in the output that the values pop off in last-in, first-out order.

### *Creating Function Templates to Test Class Template `Stack< T >`*

Notice that the code in function `main` of Fig. 22.3 is almost identical for both the `doubleStack` manipulations in lines 9–28 and the `intStack` manipulations in lines 30–47. This presents another opportunity to use a function template. Figure 22.4 defines function template `testStack` (lines 10–34) to perform the same tasks as `main` in Fig. 22.3—push a series of values onto a `Stack< T >` and pop the values off a `Stack< T >`. Function template `testStack` uses template parameter `T` (specified at line 10) to represent the data type stored in the `Stack< T >`. The function template takes four arguments (lines 12–15)—a reference to an object of type `Stack< T >`, a value of type `T` that will be the first value pushed onto the `Stack< T >`, a value of type `T` used to increment the values pushed onto the `Stack< T >` and a string that represents the name of the `Stack< T >` object for output purposes. Function `main` (lines 36–43) instantiates an object of type `Stack< double >` called `doubleStack` (line 38) and an object of type `Stack< int >` called `intStack` (line 39) and uses these objects in lines 41 and 42. The compiler infers the type of `T` for `testStack` from the type used to instantiate the function's first argument (i.e., the type used to instantiate `doubleStack` or `intStack`). The output of Fig. 22.4 precisely matches the output of Fig. 22.3.

---

```
1 // Fig. 22.4: fig22_04.cpp
2 // Stack class template test program. Function main uses a
3 // function template to manipulate objects of type Stack< T >.
4 #include <iostream>
5 #include <string>
6 #include "Stack.h" // Stack class template definition
```

---

**Fig. 22.4** | Passing a `Stack` template object to a function template. (Part I of 2.)

- 
1. Class `Stack` (Fig. 22.2) provides the function `isFull`, which you can use to determine whether the stack is full before attempting a push operation. This would avoid the potential error of pushing onto a full stack. As we discuss in Chapter 24, Exception Handling, if the operation cannot be completed, function `push` would “throw an exception.” You can write code to “catch” that exception, then decide how to handle it appropriately for the application. The same technique can be used with function `pop` when an attempt is made to pop an element from an empty stack.

```

7 using namespace std;
8
9 // function template to manipulate Stack< T >
10 template< typename T >
11 void testStack(
12 Stack< T > &theStack, // reference to Stack< T >
13 T value, // initial value to push
14 T increment, // increment for subsequent values
15 const string stackName) // name of the Stack< T > object
16 {
17 cout << "\nPushing elements onto " << stackName << '\n';
18
19 // push element onto Stack
20 while (theStack.push(value))
21 {
22 cout << value << ' ';
23 value += increment;
24 } // end while
25
26 cout << "\nStack is full. Cannot push " << value
27 << "\n\nPopping elements from " << stackName << '\n';
28
29 // pop elements from Stack
30 while (theStack.pop(value))
31 cout << value << ' ';
32
33 cout << "\nStack is empty. Cannot pop" << endl;
34 } // end function template testStack
35
36 int main()
37 {
38 Stack< double > doubleStack(5); // size 5
39 Stack< int > intStack; // default size 10
40
41 testStack(doubleStack, 1.1, 1.1, "doubleStack");
42 testStack(intStack, 1, 1, "intStack");
43 } // end main

```

```

Pushing elements onto doubleStack
1.1 2.2 3.3 4.4 5.5
Stack is full. Cannot push 6.6

Popping elements from doubleStack
5.5 4.4 3.3 2.2 1.1
Stack is empty. Cannot pop

Pushing elements onto intStack
1 2 3 4 5 6 7 8 9 10
Stack is full. Cannot push 11

Popping elements from intStack
10 9 8 7 6 5 4 3 2 1
Stack is empty. Cannot pop

```

**Fig. 22.4** | Passing a Stack template object to a function template. (Part 2 of 2.)

## 22.5 Nontype Parameters and Default Types for Class Templates

Class template `Stack` of Section 22.4 used only a type parameter in the template header (Fig. 22.2, line 6). It's also possible to use **nontype template parameters**, which can have default arguments and are treated as `constexpr`. For example, the template header could be modified to take an `int` `elements` parameter as follows:

```
template< typename T, int elements > // nontype parameter elements
```

Then, a declaration such as

```
Stack< double, 100 > mostRecentSalesFigures;
```

could be used to instantiate (at compile time) a 100-element `Stack` class-template specialization of `double` values named `mostRecentSalesFigures`; this class-template specialization would be of type `Stack< double, 100 >`. The class definition then might contain a private data member with an array declaration such as

```
T stackHolder[elements]; // array to hold Stack contents
```

In addition, a type parameter can specify a **default type**. For example,

```
template< typename T = string > // defaults to type string
```

might specify that a `Stack` contains `string` objects by default. Then, a declaration such as

```
Stack<> jobDescriptions;
```

could be used to instantiate a `Stack` class-template specialization of `strings` named `jobDescriptions`; this class-template specialization would be of type `Stack< string >`. Default type parameters must be the rightmost (trailing) parameters in a template's type-parameter list. When one is instantiating a class with two or more default types, if an omitted type is not the rightmost type parameter in the type-parameter list, then all type parameters to the right of that type also must be omitted.



### Performance Tip 22.2

*When appropriate, specify the size of a container class (such as an array class or a stack class) at compile time (possibly through a nontype template parameter). This eliminates the execution-time overhead of using `new` to create the space dynamically.*



### Software Engineering Observation 22.3

*Specifying the size of a container at compile time avoids the potentially fatal execution-time error if `new` is unable to obtain the needed memory.*

In the exercises, you'll be asked to use a nontype parameter to create a template for our class `Array` from Chapter 19. This template will enable `Array` objects to be instantiated with a specified number of elements of a specified type at compile time, rather than creating space for the `Array` objects at execution time.

In some cases, it may not be possible to use a particular type with a class template. For example, the `Stack` template of Fig. 22.2 requires that user-defined types that will be stored in a `Stack` must provide a default constructor and an assignment operator that

properly copies objects. If a particular user-defined type will not work with our `Stack` template or requires customized processing, you can define an **explicit specialization** of the class template for a particular type. Let's assume we want to create an explicit specialization `Stack` for `Employee` objects. To do this, form a new class with the name `Stack<Employee>` as follows:

```
template<>
class Stack< Employee >
{
 // body of class definition
};
```

The `Stack<Employee>` explicit specialization is a complete replacement for the `Stack` class template that is specific to type `Employee`—it does not use anything from the original class template and can even have different members.

## 22.6 Notes on Templates and Inheritance

Templates and inheritance relate in several ways:

- A class template can be derived from a class-template specialization.
- A class template can be derived from a nontemplate class.
- A class-template specialization can be derived from a class-template specialization.
- A nontemplate class can be derived from a class-template specialization.

## 22.7 Notes on Templates and Friends

We've seen that functions and entire classes can be declared as `friends` of nontemplate classes. With class templates, friendship can be established between a class template and a global function, a member function of another class (possibly a class-template specialization), or even an entire class (possibly a class-template specialization).

Throughout this section, we assume that we've defined a class template for a class named `X` with a single type parameter `T`, as in:

```
template< typename T > class X
```

Under this assumption, it's possible to make a function `f1` a friend of every class-template specialization instantiated from the class template for class `X`. To do so, use a friendship declaration of the form

```
friend void f1();
```

For example, function `f1` is a friend of `X< double >`, `X< string >` and `X< Employee >`, etc.

It's also possible to make a function `f2` a friend of only a class-template specialization with the same type argument. To do so, use a friendship declaration of the form

```
friend void f2(X< T > &);
```

For example, if `T` is a `float`, function `f2( X< float > & )` is a friend of class-template specialization `X< float >` but not a friend of class-template specification `X< string >`.

You can declare that a member function of another class is a friend of any class-template specialization generated from the class template. To do so, the friend declaration



must qualify the name of the other class's member function using the class name and the binary scope resolution operator, as in:

```
friend void A::f3();
```

The declaration makes member function `f3` of class `A` a friend of every class-template specialization instantiated from the preceding class template. For example, function `f3` of class `A` is a friend of `X< double >`, `X< string >` and `X< Employee >`, etc.

As with a global function, another class's member function can be a friend of only a class-template specialization with the same type argument. A friendship declaration of the form

```
friend void C< T >::f4(X< T > &);
```

for a particular type `T` such as `float` makes class `C`'s member function

```
C< float >::f4(X< float > &)
```

a friend function of *only* class-template specialization `X< float >`.

In some cases, it's desirable to make an entire class's set of member functions friends of a class template. In this case, a friend declaration of the form

```
friend class Y;
```

makes every member function of class `Y` a friend of every class-template specialization produced from the class template `X`.

Finally, it's possible to make all member functions of one class-template specialization friends of another class-template specialization with the same type argument. For example, a friend declaration of the form:

```
friend class Z< T >;
```

indicates that when a class-template specialization is instantiated with a particular type for `T` (such as `float`), all members of class `Z< float >` become friends of class-template specialization `X< float >`.

## 22.8 Notes on Templates and static Members

What about static data members? Recall that, with a nontemplate class, one copy of each static data member is shared among all objects of the class, and the static data member must be initialized at global namespace scope.

Each class-template specialization instantiated from a class template has its own copy of each static data member of the class template; all objects of that specialization share that one static data member. In addition, as with static data members of nontemplate classes, static data members of class-template specializations must be defined and, if necessary, initialized at global namespace scope. Each class-template specialization gets its own copy of the class template's static member functions.

## 22.9 Wrap-Up

This chapter introduced one of C++'s most powerful features—templates. You learned how to use function templates to enable the compiler to produce a set of function-template specializations that represent a group of related overloaded functions. We also discussed

how to overload a function template to create a specialized version of a function that handles a particular data type's processing in a manner that differs from the other function-template specializations. Next, you learned about class templates and class-template specializations. You saw examples of how to use a class template to create a group of related types that each perform identical processing on different data types. Finally, you learned about some of the relationships among templates, friends, inheritance and static members. In the next chapter, we discuss many of C++'s I/O capabilities and demonstrate several stream manipulators that perform various formatting tasks.

## Summary

### *Section 22.1 Introduction*

- Templates enable us to specify a range of related (overloaded) functions—called function-template specializations—or a range of related classes—called class-template specializations.

### *Section 22.2 Function Templates*

- To use function-template specializations, you write a single function-template definition. Based on the argument types provided in calls to this function, C++ generates separate specializations to handle each type of call appropriately.
- All function-template definitions begin with the keyword `template` followed by template parameters enclosed in angle brackets (`<` and `>`); each template parameter that represents a type must be preceded by keyword `class` or `typename`. Keywords `typename` and `class` used to specify function-template parameters mean “any fundamental type or user-defined type.”
- Template-definition template parameters are used to specify the kinds of arguments to the function, the return type of the function and to declare variables in the function.
- As with function parameters, the names of template parameters must be unique inside a template definition. Template parameter names need not be unique across different function templates.

### *Section 22.3 Overloading Function Templates*

- A function template may be overloaded in several ways. We can provide other function templates that specify the same function name but different function parameters. A function template can also be overloaded by providing other nontemplate functions with the same function name, but different function parameters. If both the template and non-template versions match a call, the non-template version will be used.

### *Section 22.4 Class Templates*

- Class templates provide the means for describing a class generically and for instantiating classes that are type-specific versions of this generic class.
- Class templates are called parameterized types; they require type parameters to specify how to customize a generic class template to form a specific class-template specialization.
- To use class-template specializations you write one class template. When you need a new type-specific class, the compiler writes the source code for the class-template specialization.
- A class-template definition looks like a conventional class definition, except that it's preceded by `template< typename T >` (or `template< class T >`) to indicate this is a class-template definition. Type parameter `T` acts as a placeholder for the type of the class to create. The type `T` is mentioned throughout the class definition and member-function definitions as a generic type name.

- Member-function definitions outside a class template each begin with `template<typename T>` (or `template<class T>`). Then, each function definition resembles a conventional function definition, except that the generic data in the class always is listed generically as type parameter `T`. The binary scope-resolution operator is used with the class-template name to tie each member-function definition to the class template's scope.

### Section 22.5 Nontype Parameters and Default Types for Class Templates

- It's possible to use nontype parameters in the header of a class or function template.
- You can specify a default type for a type parameter in the type-parameter list.
- An explicit specialization of a class template overrides a class template for a specific type.

### Section 22.6 Notes on Templates and Inheritance

- A class template can be derived from a class-template specialization. A class template can be derived from a nontemplate class. A class-template specialization can be derived from a class-template specialization. A nontemplate class can be derived from a class-template specialization.

### Section 22.7 Notes on Templates and Friends

- Functions and entire classes can be declared as friends of nontemplate classes. With class templates, friendship arrangements can be declared. Friendship can be established between a class template and a global function, a member function of another class (possibly a class-template specialization) or even an entire class (possibly a class-template specialization).

### Section 22.8 Notes on Templates and `static` Members

- Each class-template specialization has its own copy of each `static` data member; all objects of that specialization share that `static` data member. Such data members must be defined and, if necessary, initialized at global namespace scope.
- Each class-template specialization gets a copy of the class template's `static` member functions.

## Terminology

angle brackets (`<` and `>`) 834

`class` keyword in a template type parameter 834

class template 833

class-template definition 838

class-template specialization 833

default type for a type parameter 844

explicit specialization 845

friend of a template 845

function template 833

function-template definition 834

function-template specialization 833

generic programming 833

macro 834

member function of a class-template specialization 845

nontype template parameter 844

overloading a function template 837

parameterized type 838

template 833

`template` keyword 834

template parameter 834

type parameter 834

type template parameter 834

`typename` keyword 834

## Self-Review Exercises

**22.1** State which of the following are *true* and which are *false*. If *false*, explain why.

- The template parameters of a function-template definition are used to specify the types of the arguments to the function, to specify the return type of the function and to declare variables within the function.
- Keywords `typename` and `class` as used with a template type parameter specifically mean “any user-defined class type.”

- c) A function template can be overloaded by another function template with the same function name.
- d) Template parameter names among template definitions must be unique.
- e) Each member-function definition outside a class template must begin with a template header.
- f) A friend function of a class template must be a function-template specialization.
- g) If several class-template specializations are generated from a single class template with a single static data member, each of the class-template specializations shares a single copy of the class template's static data member.

**22.2** Fill in the blanks in each of the following:

- a) Templates enable us to specify, with a single code segment, an entire range of related functions called \_\_\_\_\_, or an entire range of related classes called \_\_\_\_\_.
- b) All function-template definitions begin with the keyword \_\_\_\_\_, followed by a list of template parameters to the function template enclosed in \_\_\_\_\_.
- c) The related functions generated from a function template all have the same name, so the compiler uses \_\_\_\_\_ resolution to invoke the proper function.
- d) Class templates also are called \_\_\_\_\_ types.
- e) The \_\_\_\_\_ operator is used with a class-template name to tie each member-function definition to the class template's scope.
- f) As with static data members of nontemplate classes, static data members of class-template specializations must also be defined and, if necessary, initialized at \_\_\_\_\_ scope.

## Answers to Self-Review Exercises

**22.1** a) True. b) False. Keywords `typename` and `class` in this context also allow for a type parameter of a fundamental type. c) True. d) False. Template parameter names among function templates need not be unique. e) True. f) False. It could be a nontemplate function. g) False. Each class-template specialization will have its own copy of the static data member.

**22.2** a) function-template specializations, class-template specializations. b) `template`, angle brackets (`<` and `>`). c) overloading. d) parameterized. e) binary scope resolution. f) global namespace.

## Exercises

**22.3** (*Selection Sort Function Template*) Write a function template `selectionSort` (see Appendix F for information on this sorting technique). Write a driver program that inputs, sorts and outputs an `int` array and a `float` array.

**22.4** (*Print Array Range*) Overload function template `printArray` of Fig. 22.1 so that it takes two additional integer arguments, namely `int lowSubscript` and `int highSubscript`. A call to this function will print only the designated portion of the array. Validate `lowSubscript` and `highSubscript`; if either is out of range or if `highSubscript` is less than or equal to `lowSubscript`, the overloaded `printArray` function should return 0; otherwise, `printArray` should return the number of elements printed. Then modify `main` to exercise both versions of `printArray` on arrays `a`, `b` and `c` (lines 22–24 of Fig. 22.1). Be sure to test all capabilities of both versions of `printArray`.

**22.5** (*Function Template Overloading*) Overload function template `printArray` of Fig. 22.1 with a nontemplate version that prints an array of character strings in neat, tabular, column format.

**22.6** (*Operator Overloading in Templates*) Write a simple function template for predicate function `isEqualTo` that compares its two arguments of the same type with the equality operator (`==`) and returns true if they are equal and false otherwise. Use this function template in a program that calls `isEqualTo` only with a variety of fundamental types. Now write a separate version of the program that calls `isEqualTo` with a user-defined class type, but does not overload the equality operator. What

happens when you attempt to run this program? Now overload the equality operator (with the operator function) `operator==`. Now what happens when you attempt to run this program?

**22.7 (Array Class Template)** Use an `int` template nontype parameter `numberOfElements` and a type parameter `elementType` to help create a template for the `Array` class (Figs. 19.6–19.7) we developed in Chapter 19. This template will enable `Array` objects to be instantiated with a specified number of elements of a specified element type at compile time.

Write a program with class template `Array`. The template can instantiate an `Array` of any element type. Override the template with a specific definition for an `Array` of `float` elements (`class Array<float>`). The driver should demonstrate the instantiation of an `Array` of `int` through the template and should show that an attempt to instantiate an `Array` of `float` uses the definition provided in `class Array<float>`.

**22.8** Distinguish between the terms “function template” and “function-template specialization.”

**22.9** Explain which is more like a stencil—a class template or a class-template specialization?

**22.10** What’s the relationship between function templates and overloading?

**22.11** Why might you choose to use a function template instead of a macro?

**22.12** What performance problem can result from using function templates and class templates?

**22.13** The compiler performs a matching process to determine which function-template specialization to call when a function is invoked. Under what circumstances does an attempt to make a match result in a compile error?

**22.14** Why is it appropriate to refer to a class template as a parameterized type?

**22.15** Explain why a C++ program would use the statement

```
Array< Employee > workerList(100);
```

**22.16** Review your answer to Exercise 22.15. Explain why a C++ program might use the statement

```
Array< Employee > workerList;
```

**22.17** Explain the use of the following notation in a C++ program:

```
template< typename T > Array< T >::Array(int s)
```

**22.18** Why might you use a nontype parameter with a class template for a container such as an array or stack?

**22.19** Suppose that a class template has the header

```
template< typename T > class Ct1
```

Describe the friendship relationships established by placing each of the following `friend` declarations inside this class template. Identifiers beginning with “f” are functions, identifiers beginning with “C” are classes, identifiers beginning with “Ct” are class templates and `T` is a template type parameter (i.e., `T` can represent any fundamental or class type).

- `friend void f1();`
- `friend void f2( Ct1< T > & );`
- `friend void C2::f3();`
- `friend void Ct3< T >::f4( Ct1< T > & );`
- `friend class C4;`
- `friend class Ct5< T >;`

**22.20** Suppose that class template `Employee` has a static data member `count`. Suppose that three class-template specializations are instantiated from the class template. How many copies of the static data member will exist? How will the use of each be constrained (if at all)?



*Consciousness ... does not appear to itself chopped up in bits ... A “river” or a “stream” are the metaphors by which it is most naturally described.*

—William James

## Objectives

In this chapter you'll learn:

- To use C++ object-oriented stream input/output.
- To format input and output.
- The stream-I/O class hierarchy.
- To use stream manipulators.
- To control justification and padding.
- To determine the success or failure of input/output operations.
- To tie output streams to input streams.



- 23.1** Introduction
- 23.2** Streams
  - 23.2.1 Classic Streams vs. Standard Streams
  - 23.2.2 **istream** Library Header Files
  - 23.2.3 Stream Input/Output Classes and Objects
- 23.3** Stream Output
  - 23.3.1 Output of **char \*** Variables
  - 23.3.2 Character Output Using Member Function **put**
- 23.4** Stream Input
  - 23.4.1 **get** and **getline** Member Functions
  - 23.4.2 **istream** Member Functions **peek**, **putback** and **ignore**
  - 23.4.3 Type-Safe I/O
- 23.5** Unformatted I/O Using **read**, **write** and **gcount**
- 23.6** Introduction to Stream Manipulators
  - 23.6.1 Integral Stream Base: **dec**, **oct**, **hex** and **setbase**
  - 23.6.2 Floating-Point Precision (**precision**, **setprecision**)
  - 23.6.3 Field Width (**width**, **setw**)
  - 23.6.4 User-Defined Output Stream Manipulators
- 23.7** Stream Format States and Stream Manipulators
  - 23.7.1 Trailing Zeros and Decimal Points (**showpoint**)
  - 23.7.2 Justification (**left**, **right** and **internal**)
  - 23.7.3 Padding (**fill**, **setfill**)
  - 23.7.4 Integral Stream Base (**dec**, **oct**, **hex**, **showbase**)
  - 23.7.5 Floating-Point Numbers; Scientific and Fixed Notation (**scientific**, **fixed**)
  - 23.7.6 Uppercase/Lowercase Control (**uppercase**)
  - 23.7.7 Specifying Boolean Format (**boolalpha**)
  - 23.7.8 Setting and Resetting the Format State via Member-Function **flags**
- 23.8** Stream Error States
- 23.9** Tying an Output Stream to an Input Stream
- 23.10** Wrap-Up

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 23.1 Introduction

The C++ standard libraries provide an extensive set of input/output capabilities. This chapter discusses a range of capabilities sufficient for performing most common I/O operations and overviews the remaining capabilities. We discussed some of these features earlier in the text; now we provide a more complete treatment. Many of the I/O features that we'll discuss are object oriented. This style of I/O makes use of other C++ features, such as references, function overloading and operator overloading.

C++ uses **type-safe I/O**. Each I/O operation is executed in a manner sensitive to the data type. If an I/O member function has been defined to handle a particular data type, then that member function is called to handle that data type. If there is no match between the type of the actual data and a function for handling that data type, the compiler generates an error. Thus, improper data cannot “sneak” through the system (as can occur in C, allowing for some subtle and bizarre errors).

Users can specify how to perform I/O for objects of user-defined types by overloading the stream insertion operator (**<<**) and the stream extraction operator (**>>**). This **extensibility** is one of C++'s most valuable features.



### Software Engineering Observation 23.1

Use the C++-style I/O exclusively in C++ programs, even though C-style I/O is available to C++ programmers.



### Error-Prevention Tip 23.1

*C++ I/O is type safe.*



### Software Engineering Observation 23.2

*C++ enables a common treatment of I/O for predefined types and user-defined types. This commonality facilitates software development and reuse.*

## 23.2 Streams

C++ I/O occurs in **streams**, which are sequences of bytes. In input operations, the bytes flow from a device (e.g., a keyboard, a disk drive, a network connection, etc.) to main memory. In output operations, bytes flow from main memory to a device (e.g., a display screen, a printer, a disk drive, a network connection, etc.).

An application associates meaning with bytes. The bytes could represent characters, raw data, graphics images, digital speech, digital video or any other information an application may require.

The system I/O mechanisms should transfer bytes from devices to memory (and vice versa) consistently and reliably. Such transfers often involve some mechanical motion, such as the rotation of a disk or a tape, or the typing of keystrokes at a keyboard. The time these transfers take is typically much greater than the time the processor requires to manipulate data internally. Thus, I/O operations require careful planning and tuning to ensure optimal performance.

C++ provides both “low-level” and “high-level” I/O capabilities. Low-level I/O capabilities (i.e., **unformatted I/O**) specify that some number of bytes should be transferred device-to-memory or memory-to-device. In such transfers, the individual byte is the item of interest. Such low-level capabilities provide high-speed, high-volume transfers but are not particularly convenient.

Programmers generally prefer a higher-level view of I/O (i.e., **formatted I/O**), in which bytes are grouped into meaningful units, such as integers, floating-point numbers, characters, strings and user-defined types. These type-oriented capabilities are satisfactory for most I/O other than high-volume file processing.



### Performance Tip 23.1

*Use unformatted I/O for the best performance in high-volume file processing.*



### Portability Tip 23.1

*Using unformatted I/O can lead to portability problems, because unformatted data is not portable across all platforms.*

### 23.2.1 Classic Streams vs. Standard Streams

In the past, the C++ **classic stream libraries** enabled input and output of chars. Because a char normally occupies one byte, it can represent only a limited set of characters (such as those in the ASCII character set). However, many languages use alphabets that contain more characters than a single-byte char can represent. The ASCII character set does not provide these characters; the **Unicode® character set** does. Unicode is an extensive inter-



national character set that represents the majority of the world’s “commercially viable” languages, mathematical symbols and much more. For more information on Unicode, visit [www.unicode.org](http://www.unicode.org).

C++ includes the [standard stream libraries](#), which enable developers to build systems capable of performing I/O operations with Unicode characters. For this purpose, C++ includes an additional character type called [wchar\\_t](#), which can store 2-byte Unicode characters. The C++ standard also redesigned the classic C++ stream classes, which processed only chars, as class templates with separate specializations for processing characters of types `char` and `wchar_t`, respectively. We use the `char` type of class templates throughout this book.

### 23.2.2 `iostream` Library Header Files

The C++ `iostream` library provides hundreds of I/O capabilities. Several header files contain portions of the library interface.

Most C++ programs include the `<iostream>` header file, which declares basic services required for all stream-I/O operations. The `<iostream>` header file defines the `cin`, `cout`, `cerr` and `clog` objects, which correspond to the standard input stream, the standard output stream, the unbuffered standard error stream and the buffered standard error stream, respectively. (`cerr` and `clog` are discussed in Section 23.2.3.) Both unformatted- and formatted-I/O services are provided.

The `<iomanip>` header declares services useful for performing formatted I/O with so-called [parameterized stream manipulators](#), such as `setw` and `setprecision`. The `<fstream>` header declares services for user-controlled file processing.

C++ implementations generally contain other I/O-related libraries that provide system-specific capabilities, such as the controlling of special-purpose devices for audio and video I/O.

### 23.2.3 Stream Input/Output Classes and Objects


The `iostream` library provides many templates for handling common I/O operations. For example, class template [basic\\_istream](#) supports stream-input operations, class template [basic\\_ostream](#) supports stream-output operations, and class template `basic_iostream` supports both stream-input and stream-output operations. Each template has a predefined template specialization that enables `char` I/O. In addition, the `iostream` library provides a set of typedefs that provide aliases for these template specializations. The [typedef](#) specifier declares synonyms (aliases) for previously defined data types. Programmers sometimes use `typedef` to create shorter or more readable type names. For example, the statement

```
typedef Card *CardPtr;
```

defines an additional type name, `CardPtr`, as a synonym for type `Card *`. Creating a name using `typedef` does not create a data type; `typedef` creates only a type name that may be used in the program. Section 10.6 discusses `typedef` in detail. The `typedef` [istream](#) represents a specialization of `basic_istream` that enables `char` input. Similarly, the `typedef` [ostream](#) represents a specialization of `basic_ostream` that enables `char` output. Also, the `typedef` [iostream](#) represents a specialization of `basic_iostream` that enables both `char` input and output. We use these typedefs throughout this chapter.

### Stream-I/O Template Hierarchy and Operator Overloading

Templates `basic_istream` and `basic_ostream` both derive through single inheritance from base template `basic_ios`.<sup>1</sup> Template `basic_istream` derives through multiple inheritance from templates `basic_istream` and `basic_ostream`. The UML class diagram of Fig. 23.1 summarizes these inheritance relationships.



**Fig. 23.1** | Stream-I/O template hierarchy portion.

Operator overloading provides a convenient notation for performing input/output. The left-shift operator (`<<`) is overloaded to designate stream output and is referred to as the stream insertion operator. The right-shift operator (`>>`) is overloaded to designate stream input and is referred to as the stream extraction operator. These operators are used with the standard stream objects `cin`, `cout`, `cerr` and `clog` and, commonly, with user-defined stream objects.

### Standard Stream Objects `cin`, `cout`, `cerr` and `clog`

Predefined object `cin` is an `istream` instance and is said to be “connected to” (or attached to) the standard input device, which usually is the keyboard. The stream extraction operator (`>>`) as used in the following statement causes a value for integer variable `grade` (assuming that `grade` has been declared as an `int` variable) to be input from `cin` to memory:

```
cin >> grade; // data "flows" in the direction of the arrows
```

The compiler determines the data type of `grade` and selects the appropriate overloaded stream extraction operator. Assuming that `grade` has been declared properly, the stream extraction operator does not require additional type information (as is the case, for example, in C-style I/O). The `>>` operator is overloaded to input data items of fundamental types, strings and pointer values.

The predefined object `cout` is an `ostream` instance and is said to be “connected to” the standard output device, which usually is the display screen. The stream insertion operator (`<<`), as used in the following statement, causes the value of variable `grade` to be output from memory to the standard output device:

```
cout << grade; // data "flows" in the direction of the arrows
```

1. This chapter discusses templates only in the context of the template specializations for char I/O.


The compiler determines the data type of `grade` (assuming `grade` has been declared properly) and selects the appropriate stream insertion operator. The `<<` operator is overloaded to output data items of fundamental types, strings and pointer values.

The predefined object `cerr` is an `ostream` instance and is said to be “connected to” the standard error device, normally the screen. Outputs to object `cerr` are **unbuffered**, implying that each stream insertion to `cerr` causes its output to appear immediately—this is appropriate for notifying a user promptly about errors.

The predefined object `clog` is an instance of the `ostream` class and is said to be “connected to” the standard error device. Outputs to `clog` are **buffered**. This means that each insertion to `clog` could cause its output to be held in a buffer until the buffer is filled or until the buffer is flushed. Buffering is an I/O performance-enhancement technique discussed in operating-systems courses.

### *File-Processing Templates*

C++ file processing uses class templates **basic\_ifstream** (for file input), **basic\_ofstream** (for file output) and **basic\_fstream** (for file input and output). Each class template has a predefined template specialization that enables char I/O. C++ provides a set of typedefs that provide aliases for these template specializations. For example, the typedef **ifstream** represents a specialization of `basic_ifstream` that enables char input from a file. Similarly, typedef **ofstream** represents a specialization of `basic_ofstream` that enables char output to a file. Also, typedef **fstream** represents a specialization of `basic_fstream` that enables char input from, and output to, a file. Template `basic_ifstream` inherits from `basic_istream`, `basic_ofstream` inherits from `basic_ostream` and `basic_fstream` inherits from `basic_iostream`. The UML class diagram of Fig. 23.2 summarizes the various inheritance relationships of the I/O-related classes. The full stream-I/O class hierarchy provides most of the capabilities that you need. Consult the class-library reference for your C++ system for additional file-processing information.



**Fig. 23.2** | Stream-I/O template hierarchy portion showing the main file-processing templates.

## 23.3 Stream Output

Formatted and unformatted output capabilities are provided by `ostream`. Capabilities include output of standard data types with the stream insertion operator (`<<`); output of characters via the `put` member function; unformatted output via the `write` member function (Section 23.5); output of integers in decimal, octal and hexadecimal formats (Section 23.6.1); output of floating-point values with various precision (Section 23.6.2), with forced decimal points (Section 23.7.1), in scientific notation and in fixed notation (Section 23.7.5); output of data justified in fields of designated widths (Section 23.7.2); output of data in fields padded with specified characters (Section 23.7.3); and output of uppercase letters in scientific notation and hexadecimal notation (Section 23.7.6).

### 23.3.1 Output of `char *` Variables

C++ determines data types automatically—an improvement over C. This feature sometimes “gets in the way.” For example, suppose we want to print the address stored in a `char *` pointer. The `<<` operator has been overloaded to output a `char *` as a null-terminated string. To output the address, you can cast the `char *` to a `void *` (this can be done to any pointer variable). Figure 23.3 demonstrates printing a `char *` variable in both string and address formats. The address prints as a hexadecimal (base-16) number, which might differ among computers. To learn more about hexadecimal numbers, read Appendix C. We say more about controlling the bases of numbers in Section 23.6.1 and Section 23.7.4.

```

1 // Fig. 23.3: Fig23_03.cpp
2 // Printing the address stored in a char * variable.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 const char *const word = "again";
9
10 // display value of char *, then display value of char *
11 // static_cast to void *
12 cout << "Value of word is: " << word << endl
13 << "Value of static_cast< void * >(word) is: "
14 << static_cast< void * >(word) << endl;
15 } // end main

```

```

Value of word is: again
Value of static_cast< void * >(word) is: 00428300

```

**Fig. 23.3** | Printing the address stored in a `char *` variable.

### 23.3.2 Character Output Using Member Function `put`

We can use the `put` member function to output characters. For example, the statement

```
cout.put('A');
```

displays a single character A. Calls to `put` may be cascaded, as in the statement

```
cout.put('A').put('\n');
```

which outputs the letter A followed by a newline character. As with `<<`, the preceding statement executes in this manner, because the dot operator (`.`) associates from left to right, and the `put` member function returns a reference to the ostream object (`cout`) that received the `put` call. The `put` function also may be called with a numeric expression that represents an ASCII value, as in the following statement

```
cout.put(65);
```

which also outputs A.

## 23.4 Stream Input

Now let's consider stream input. Formatted and unformatted input capabilities are provided by `istream`. The stream extraction operator (`>>`) normally skips **white-space characters** (such as blanks, tabs and newlines) in the input stream; later we'll see how to change this behavior. After each input, the stream extraction operator returns a reference to the stream object that received the extraction message (e.g., `cin` in the expression `cin >> grade`). If that reference is used as a condition (e.g., in a `while` statement's loop-continuation condition), the stream's overloaded `void *` cast operator function is implicitly invoked to convert the reference into a non-null pointer value or the null pointer based on the success or failure of the last input operation. A non-null pointer converts to the `bool` value `true` to indicate success and the null pointer converts to the `bool` value `false` to indicate failure. When an attempt is made to read past the end of a stream, the stream's overloaded `void *` cast operator returns the null pointer to indicate end-of-file.

Each stream object contains a set of **state bits** used to control the stream's state (i.e., formatting, setting error states, etc.). These bits are used by the stream's overloaded `void *` cast operator to determine whether to return a non-null pointer or the null pointer. Stream extraction causes the stream's **failbit** to be set if data of the wrong type is input and causes the stream's **badbit** to be set if the operation fails. Section 23.7 and Section 23.8 discuss stream state bits in detail, then show how to test these bits after an I/O operation.

### 23.4.1 `get` and `getline` Member Functions

The **`get`** member function with no arguments inputs one character from the designated stream (including white-space characters and other nongraphic characters, such as the key sequence that represents end-of-file) and returns it as the value of the function call. This version of `get` returns EOF when end-of-file is encountered on the stream.

#### *Using Member Functions `eof`, `get` and `put`*

Figure 23.4 demonstrates the use of member functions `eof` and `get` on input stream `cin` and member function `put` on output stream `cout`. The program first prints the value of `cin.eof()`—i.e., `false` (0 on the output)—to show that end-of-file has not occurred on `cin`. The user enters a line of text and presses *Enter* followed by end-of-file (`<Ctrl>-z` on Microsoft Windows systems, `<Ctrl>-d` on UNIX and Macintosh systems). Line 15 reads each character, which line 16 outputs to `cout` using member function `put`. When end-of-file is encountered, the `while` statement ends, and line 20 displays the value of `cin.eof()`,

which is now true (1 on the output), to show that end-of-file has been set on cin. This program uses the version of istream member function get that takes no arguments and returns the character being input (line 15). Function eof returns true only after the program attempts to read past the last character in the stream.

```

1 // Fig. 23.4: Fig23_04.cpp
2 // Using member functions get, put and eof.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 int character; // use int, because char cannot represent EOF
9
10 // prompt user to enter line of text
11 cout << "Before input, cin.eof() is " << cin.eof() << endl;
12 << "Enter a sentence followed by end-of-file:" << endl;
13
14 // use get to read each character; use put to display it
15 while ((character = cin.get()) != EOF)
16 cout.put(character);
17
18 // display end-of-file character
19 cout << "\nEOF in this system is: " << character << endl;
20 cout << "After input of EOF, cin.eof() is " << cin.eof() << endl;
21 } // end main

```

```

Before input, cin.eof() is 0
Enter a sentence followed by end-of-file:
Testing the get and put member functions
Testing the get and put member functions
^Z

EOF in this system is: -1
After input of EOF, cin.eof() is 1

```

**Fig. 23.4** | get, put and eof member functions.

The get member function with a character-reference argument inputs the next character from the input stream (even if this is a white-space character) and stores it in the character argument. This version of get returns a reference to the istream object for which the get member function is being invoked.

A third version of get takes three arguments—a character array, a size limit and a delimiter (with default value '\n'). This version reads characters from the input stream. It either reads one fewer than the specified maximum number of characters and terminates or terminates as soon as the delimiter is read. A null character is inserted to terminate the input string in the character array used as a buffer by the program. The delimiter is not placed in the character array but does remain in the input stream (the delimiter will be the next character read). Thus, the result of a second consecutive get is an empty line, unless the delimiter character is removed from the input stream (possibly with cin.ignore()).

*Comparing cin and cin.get*

Figure 23.5 compares input using stream extraction with `cin` (which reads characters until a white-space character is encountered) and input using `cin.get`. The call to `cin.get` (line 22) does not specify a delimiter, so the default `'\n'` character is used.

---

```

1 // Fig. 23.5: Fig23_05.cpp
2 // Contrasting input of a string via cin and cin.get.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 // create two char arrays, each with 80 elements
9 const int SIZE = 80;
10 char buffer1[SIZE];
11 char buffer2[SIZE];
12
13 // use cin to input characters into buffer1
14 cout << "Enter a sentence:" << endl;
15 cin >> buffer1;
16
17 // display buffer1 contents
18 cout << "\nThe string read with cin was:" << endl
19 << buffer1 << endl << endl;
20
21 // use cin.get to input characters into buffer2
22 cin.get(buffer2, SIZE);
23
24 // display buffer2 contents
25 cout << "The string read with cin.get was:" << endl
26 << buffer2 << endl;
27 } // end main

```

Enter a sentence:  
**Contrasting string input with cin and cin.get**

The string read with cin was:  
 Contrasting

The string read with cin.get was:  
 string input with cin and cin.get

**Fig. 23.5** | Input of a string using `cin` with stream extraction contrasted with input using `cin.get`.

*Using Member Function getline*

Member function `getline` operates similarly to the third version of the `get` member function and inserts a null character after the line in the character array. The `getline` function removes the delimiter from the stream (i.e., reads the character and discards it), but does not store it in the character array. The program of Fig. 23.6 demonstrates the use of the `getline` member function to input a line of text (line 13).

```

1 // Fig. 23.6: Fig23_06.cpp
2 // Inputting characters using cin member function getline.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 const int SIZE = 80;
9 char buffer[SIZE]; // create array of 80 characters
10
11 // input characters in buffer via cin function getline
12 cout << "Enter a sentence:" << endl;
13 cin.getline(buffer, SIZE);
14
15 // display buffer contents
16 cout << "\nThe sentence entered is:" << endl << buffer << endl;
17 } // end main

```

```

Enter a sentence:
Using the getline member function

The sentence entered is:
Using the getline member function

```

**Fig. 23.6** | Inputting character data with cin member function getline.

### 23.4.2 istream Member Functions peek, putback and ignore

The **ignore** member function of **istream** reads and discards a designated number of characters (the default is one) or terminates upon encountering a designated delimiter (the default is EOF, which causes **ignore** to skip to the end of the file when reading from a file).

The **putback** member function places the previous character obtained by a **get** from an input stream back into that stream. This function is useful for applications that scan an input stream looking for a field beginning with a specific character. When that character is input, the application returns the character to the stream, so the character can be included in the input data.

The **peek** member function returns the next character from an input stream but does not remove the character from the stream.

### 23.4.3 Type-Safe I/O

C++ offers type-safe I/O. The **<<** and **>>** operators are overloaded to accept data items of specific types. If unexpected data is processed, various error bits are set, which the user may test to determine whether an I/O operation succeeded or failed. If operator **<<** has not been overloaded for a user-defined type and you attempt to input into or output the contents of an object of that user-defined type, the compiler reports an error. This enables the program to “stay in control.” We discuss these error states in Section 23.8.

## 23.5 Unformatted I/O Using read, write and gcount

Unformatted input/output is performed using the **read** and **write** member functions of **istream** and **ostream**, respectively. Member function **read** inputs bytes to a character ar-



ray in memory; member function `write` outputs bytes from a character array. These bytes are not formatted in any way. They're input or output as raw bytes. For example, the call

```
char buffer[] = "HAPPY BIRTHDAY";
cout.write(buffer, 10);
```

outputs the first 10 bytes of `buffer` (including null characters, if any, that would cause output with `cout` and `<<` to terminate). The call

```
cout.write("ABCDEFGHIJKLMNOPQRSTUVWXYZ", 10);
```

displays the first 10 characters of the alphabet.

The `read` member function inputs a designated number of characters into a character array. If fewer than the designated number of characters are read, `failbit` is set. Section 23.8 shows how to determine whether `failbit` has been set. Member function `gcount` reports the number of characters read by the last input operation.

Figure 23.7 demonstrates `istream` member functions `read` and `gcount`, and `ostream` member function `write`. The program inputs 20 characters (from a longer input sequence) into the array `buffer` with `read` (line 13), determines the number of characters input with `gcount` (line 17) and outputs the characters in `buffer` with `write` (line 17).

---

```
1 // Fig. 23.7: Fig23_07.cpp
2 // Unformatted I/O using read, gcount and write.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 const int SIZE = 80;
9 char buffer[SIZE]; // create array of 80 characters
10
11 // use function read to input characters into buffer
12 cout << "Enter a sentence:" << endl;
13 cin.read(buffer, 20);
14
15 // use functions write and gcount to display buffer characters
16 cout << endl << "The sentence entered was:" << endl;
17 cout.write(buffer, cin.gcount());
18 cout << endl;
19 }
```

```
Enter a sentence:
Using the read, write, and gcount member functions
The sentence entered was:
Using the read, writ
```

**Fig. 23.7** | Unformatted I/O using the `read`, `gcount` and `write` member functions.

## 23.6 Introduction to Stream Manipulators

C++ provides various **stream manipulators** that perform formatting tasks. The stream manipulators provide capabilities such as setting field widths, setting precision, setting and

unsetting format state, setting the fill character in fields, flushing streams, inserting a new-line into the output stream (and flushing the stream), inserting a null character into the output stream and skipping white space in the input stream. These features are described in the following sections.

### 23.6.1 Integral Stream Base: dec, oct, hex and setbase

Integers are interpreted normally as decimal (base-10) values. To change the base in which integers are interpreted on a stream, insert the **hex** manipulator to set the base to hexadecimal (base 16) or insert the **oct** manipulator to set the base to octal (base 8). Insert the **dec** manipulator to reset the stream base to decimal. These are all sticky manipulators.

The base of a stream also may be changed by the **setbase** stream manipulator, which takes one integer argument of 10, 8, or 16 to set the base to decimal, octal or hexadecimal, respectively. Because **setbase** takes an argument, it's called a parameterized stream manipulator. Using **setbase** (or any other parameterized manipulator) requires the inclusion of the `<iomanip>` header file. The stream base value remains the same until changed explicitly; **setbase** settings are "sticky." Figure 23.8 demonstrates stream manipulators **hex**, **oct**, **dec** and **setbase**.

---

```

1 // Fig. 23.8: Fig23_08.cpp
2 // Using stream manipulators hex, oct, dec and setbase.
3 #include <iostream>
4 #include <iomanip>
5 using namespace std;
6
7 int main()
8 {
9 int number;
10
11 cout << "Enter a decimal number: ";
12 cin >> number; // input number
13
14 // use hex stream manipulator to show hexadecimal number
15 cout << number << " in hexadecimal is: " << hex
16 << number << endl;
17
18 // use oct stream manipulator to show octal number
19 cout << dec << number << " in octal is: "
20 << oct << number << endl;
21
22 // use setbase stream manipulator to show decimal number
23 cout << setbase(10) << number << " in decimal is: "
24 << number << endl;
25 } // end main

```

```

Enter a decimal number: 20
20 in hexadecimal is: 14
20 in octal is: 24
20 in decimal is: 20

```

**Fig. 23.8** | Stream manipulators **hex**, **oct**, **dec** and **setbase**.

### 23.6.2 Floating-Point Precision (precision, setprecision)

We can control the **precision** of floating-point numbers (i.e., the number of digits to the right of the decimal point) by using either the `setprecision` stream manipulator or the **precision** member function of `ios_base`. A call to either of these sets the precision for all subsequent output operations until the next precision-setting call. A call to member function `precision` with no argument returns the current precision setting (this is what you need to use so that you can restore the original precision eventually after a “sticky” setting is no longer needed). The program of Fig. 23.9 uses both member function `precision` (line 22) and the `setprecision` manipulator (line 31) to print a table that shows the square root of 2, with precision varying from 0 to 9.

---

```

1 // Fig. 23.9: Fig23_09.cpp
2 // Controlling precision of floating-point values.
3 #include <iostream>
4 #include <iomanip>
5 #include <cmath>
6 using namespace std;
7
8 int main()
9 {
10 double root2 = sqrt(2.0); // calculate square root of 2
11 int places; // precision, vary from 0-9
12
13 cout << "Square root of 2 with precisions 0-9." << endl
14 << "Precision set by ios_base member function "
15 << "precision:" << endl;
16
17 cout << fixed; // use fixed-point notation
18
19 // display square root using ios_base function precision
20 for (places = 0; places <= 9; places++)
21 {
22 cout.precision(places);
23 cout << root2 << endl;
24 } // end for
25
26 cout << "\nPrecision set by stream manipulator "
27 << "setprecision:" << endl;
28
29 // set precision for each digit, then display square root
30 for (places = 0; places <= 9; places++)
31 cout << setprecision(places) << root2 << endl;
32 } // end main

```

```

Square root of 2 with precisions 0-9.
Precision set by ios_base member function precision:
1
1.4
1.41
1.414

```

**Fig. 23.9** | Precision of floating-point values. (Part I of 2.)

```

1.4142
1.41421
1.414214
1.4142136
1.41421356
1.414213562

Precision set by stream manipulator setprecision:
1
1.4
1.41
1.414
1.4142
1.41421
1.414214
1.4142136
1.41421356
1.414213562

```

**Fig. 23.9** | Precision of floating-point values. (Part 2 of 2.)

### 23.6.3 Field Width (`width`, `setw`)

The `width` member function (of base class `ios_base`) sets the field width (i.e., the number of character positions in which a value should be output or the maximum number of characters that should be input) and returns the previous width. If values output are narrower than the field width, **fill characters** are inserted as **padding**. A value wider than the designated width will not be truncated—the full number will be printed. The `width` function with no argument returns the current setting.



#### Common Programming Error 23.1

*The width setting applies only for the next insertion or extraction (i.e., the width setting is not “sticky”); afterward, the width is set implicitly to 0 (i.e., input and output will be performed with default settings). Assuming that the width setting applies to all subsequent outputs is a logic error.*



#### Common Programming Error 23.2

*When a field is not sufficiently wide to handle outputs, the outputs print as wide as necessary, which can yield confusing outputs.*

Figure 23.10 demonstrates the use of the `width` member function on both input and output. On input into a `char` array, a maximum of one fewer characters than the width will be read, because provision is made for the null character to be placed in the input string. Remember that stream extraction terminates when nonleading white space is encountered. The `setw` stream manipulator also may be used to set the field width.

```

1 // Fig. 23.10: Fig23_10.cpp
2 // Demonstrating member function width.
3 #include <iostream>
4 using namespace std;

```

**Fig. 23.10** | `width` member function of class `ios_base`. (Part 1 of 2.)

```

5
6 int main()
7 {
8 int widthValue = 4;
9 char sentence[10];
10
11 cout << "Enter a sentence:" << endl;
12 cin.width(5); // input only 5 characters from sentence
13
14 // set field width, then display characters based on that width
15 while (cin >> sentence)
16 {
17 cout.width(widthValue++);
18 cout << sentence << endl;
19 cin.width(5); // input 5 more characters from sentence
20 } // end while
21 } // end main

```

```

Enter a sentence:
This is a test of the width member function
This
 is
 a
 test
 of
 the
 widt
 h
 memb
 er
 func
 tion

```

**Fig. 23.10** | width member function of class `ios_base`. (Part 2 of 2.)

[*Note:* When prompted for input in Fig. 23.10, the user should enter a line of text and press *Enter* followed by end-of-file (<Ctrl>-z on Microsoft Windows systems, <Ctrl>-d on UNIX and Macintosh systems).]

### 23.6.4 User-Defined Output Stream Manipulators

You can create your own stream manipulators.<sup>2</sup> Figure 23.11 shows the creation and use of new nonparameterized stream manipulators `bell` (lines 8–11), `carriageReturn` (lines 14–17), `tab` (lines 20–23) and `endLine` (lines 27–30). For output stream manipulators, the return type and parameter must be of type `ostream &`. When line 35 inserts the `endLine` manipulator in the output stream, function `endLine` is called and line 29 outputs the escape sequence `\n` and the `flush` manipulator to the standard output stream `cout`. Similarly, when lines 35–44 insert the manipulators `tab`, `bell` and `carriageReturn` in the output stream, their corresponding functions—`tab` (line 20), `bell` (line 8) and `carriageReturn` (line 14) are called, which in turn output various escape sequences.

2. You also may create your own parameterized stream manipulators. This concept is beyond the scope of this book.

```

1 // Fig. 23.11: Fig23_11.cpp
2 // Creating and testing user-defined, nonparameterized
3 // stream manipulators.
4 #include <iostream>
5 using namespace std;
6
7 // bell manipulator (using escape sequence \a)
8 ostream& bell(ostream& output)
9 {
10 return output << '\a'; // issue system beep
11 } // end bell manipulator
12
13 // carriageReturn manipulator (using escape sequence \r)
14 ostream& carriageReturn(ostream& output)
15 {
16 return output << '\r'; // issue carriage return
17 } // end carriageReturn manipulator
18
19 // tab manipulator (using escape sequence \t)
20 ostream& tab(ostream& output)
21 {
22 return output << '\t'; // issue tab
23 } // end tab manipulator
24
25 // endLine manipulator (using escape sequence \n and member
26 // function flush)
27 ostream& endLine(ostream& output)
28 {
29 return output << '\n' << flush; // issue endl-like end of line
30 } // end endLine manipulator
31
32 int main()
33 {
34 // use tab and endLine manipulators
35 cout << "Testing the tab manipulator:" << endLine
36 << 'a' << tab << 'b' << tab << 'c' << endLine;
37
38 cout << "Testing the carriageReturn and bell manipulators:"
39 << endLine << ".....";
40
41 cout << bell; // use bell manipulator
42
43 // use carriageReturn and endLine manipulators
44 cout << carriageReturn << "-----" << endLine;
45 } // end main

```

```

Testing the tab manipulator:
a b c
Testing the carriageReturn and bell manipulators:
-----.....

```

**Fig. 23.11** | User-defined, nonparameterized stream manipulators.

## 23.7 Stream Format States and Stream Manipulators

Various stream manipulators can be used to specify the kinds of formatting to be performed during stream-I/O operations. Stream manipulators control the output’s format settings. Figure 23.12 lists each stream manipulator that controls a given stream’s format state. All these manipulators belong to class `ios_base`. We show examples of most of these stream manipulators in the next several sections.

| Stream manipulator      | Description                                                                                                                                                                                                                                                                                         |
|-------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>skipws</code>     | Skip white-space characters on an input stream. This setting is reset with stream manipulator <code>noskipws</code> .                                                                                                                                                                               |
| <code>left</code>       | Left justify output in a field. Padding characters appear to the right if necessary.                                                                                                                                                                                                                |
| <code>right</code>      | Right justify output in a field. Padding characters appear to the left if necessary.                                                                                                                                                                                                                |
| <code>internal</code>   | Indicate that a number’s sign should be left justified in a field and a number’s magnitude should be right justified in that same field (i.e., padding characters appear between the sign and the number).                                                                                          |
| <code>dec</code>        | Specify that integers should be treated as decimal (base 10) values.                                                                                                                                                                                                                                |
| <code>oct</code>        | Specify that integers should be treated as octal (base 8) values.                                                                                                                                                                                                                                   |
| <code>hex</code>        | Specify that integers should be treated as hexadecimal (base 16) values.                                                                                                                                                                                                                            |
| <code>showbase</code>   | Specify that the base of a number is to be output ahead of the number (a leading 0 for octals; a leading 0x or 0X for hexadecimal). This setting is reset with stream manipulator <code>noshowbase</code> .                                                                                         |
| <code>showpoint</code>  | Specify that floating-point numbers should be output with a decimal point. This is used normally with <code>fixed</code> to guarantee a certain number of digits to the right of the decimal point, even if they’re zeros. This setting is reset with stream manipulator <code>noshowpoint</code> . |
| <code>uppercase</code>  | Specify that uppercase letters (i.e., X and A through F) should be used in a hexadecimal integer and that uppercase E should be used when representing a floating-point value in scientific notation. This setting is reset with stream manipulator <code>nouppercase</code> .                      |
| <code>showpos</code>    | Specify that positive numbers should be preceded by a plus sign (+). This setting is reset with stream manipulator <code>noshowpos</code> .                                                                                                                                                         |
| <code>scientific</code> | Specify output of a floating-point value in scientific notation.                                                                                                                                                                                                                                    |
| <code>fixed</code>      | Specify output of a floating-point value in fixed-point notation with a specific number of digits to the right of the decimal point.                                                                                                                                                                |

**Fig. 23.12** | Format state stream manipulators from `<iostream>`.

### 23.7.1 Trailing Zeros and Decimal Points (`showpoint`)

Stream manipulator `showpoint` forces a floating-point number to be output with its decimal point and trailing zeros. For example, the floating-point value 79.0 prints as 79 with-

out using `showpoint` and prints as 79.000000 (or as many trailing zeros as are specified by the current precision) using `showpoint`. To reset the `showpoint` setting, output the stream manipulator `noshowpoint`. The program in Fig. 23.13 shows how to use stream manipulator `showpoint` to control the printing of trailing zeros and decimal points for floating-point values. Recall that the default precision of a floating-point number is 6. When neither the `fixed` nor the `scientific` stream manipulator is used, the precision represents the number of significant digits to display (i.e., the total number of digits to display), not the number of digits to display after decimal point.

---

```

1 // Fig. 23.13: Fig23_13.cpp
2 // Controlling the printing of trailing zeros and
3 // decimal points in floating-point values.
4 #include <iostream>
5 using namespace std;
6
7 int main()
8 {
9 // display double values with default stream format
10 cout << "Before using showpoint" << endl
11 << "9.9900 prints as: " << 9.9900 << endl
12 << "9.9000 prints as: " << 9.9000 << endl
13 << "9.0000 prints as: " << 9.0000 << endl << endl;
14
15 // display double value after showpoint
16 cout << showpoint
17 << "After using showpoint" << endl
18 << "9.9900 prints as: " << 9.9900 << endl
19 << "9.9000 prints as: " << 9.9000 << endl
20 << "9.0000 prints as: " << 9.0000 << endl;
21 } // end main

```

```

Before using showpoint
9.9900 prints as: 9.99
9.9000 prints as: 9.9
9.0000 prints as: 9

After using showpoint
9.9900 prints as: 9.990000
9.9000 prints as: 9.900000
9.0000 prints as: 9.000000

```

**Fig. 23.13** | Controlling the printing of trailing zeros and decimal points in floating-point values.

### 23.7.2 Justification (left, right and internal)

Stream manipulators `left` and `right` enable fields to be left justified with padding characters to the right or right justified with padding characters to the left, respectively. The padding character is specified by the `fill` member function or the `setfill` parameterized stream manipulator (which we discuss in Section 23.7.3). Figure 23.14 uses the `setw`, `left` and `right` manipulators to left justify and right justify integer data in a field.



---

```

1 // Fig. 23.14: Fig23_14.cpp
2 // Left and right justification with stream manipulators left and right.
3 #include <iostream>
4 #include <iomanip>
5 using namespace std;
6
7 int main()
8 {
9 int x = 12345;
10
11 // display x right justified (default)
12 cout << "Default is right justified:" << endl
13 << setw(10) << x;
14
15 // use left manipulator to display x left justified
16 cout << "\n\nUse std::left to left justify x:\n"
17 << left << setw(10) << x;
18
19 // use right manipulator to display x right justified
20 cout << "\n\nUse std::right to right justify x:\n"
21 << right << setw(10) << x << endl;
22 } // end main

```

```

Default is right justified:
12345

Use std::left to left justify x:
12345

Use std::right to right justify x:
12345

```

**Fig. 23.14** | Left justification and right justification with stream manipulators `left` and `right`.

Stream manipulator `internal` indicates that a number's sign (or base when using stream manipulator `showbase`) should be left justified within a field, that the number's magnitude should be right justified and that intervening spaces should be padded with the fill character. Figure 23.15 shows the `internal` stream manipulator specifying internal spacing (line 10). Note that `showpos` forces the plus sign to print (line 10). To reset the `showpos` setting, output the stream manipulator `noshowpos`.

---

```

1 // Fig. 23.15: Fig23_15.cpp
2 // Printing an integer with internal spacing and plus sign.
3 #include <iostream>
4 #include <iomanip>
5 using namespace std;
6
7 int main()
8 {

```

**Fig. 23.15** | Printing an integer with internal spacing and plus sign. (Part I of 2.)

```

9 // display value with internal spacing and plus sign
10 cout << internal << showpos << setw(10) << 123 << endl;
11 } // end main

```

```
+ 123
```

**Fig. 23.15** | Printing an integer with internal spacing and plus sign. (Part 2 of 2.)

### 23.7.3 Padding (fill, setfill)

The **fill member function** specifies the fill character to be used with justified fields; if no value is specified, spaces are used for padding. The fill function returns the prior padding character. The **setfill manipulator** also sets the padding character. Figure 23.16 demonstrates using member function fill (line 30) and stream manipulator setfill (lines 34 and 37) to set the fill character.

```

1 // Fig. 23.16: Fig23_16.cpp
2 // Using member function fill and stream manipulator setfill to change
3 // the padding character for fields larger than the printed value.
4 #include <iostream>
5 #include <iomanip>
6 using namespace std;
7
8 int main()
9 {
10 int x = 10000;
11
12 // display x
13 cout << x << " printed as int right and left justified\n"
14 << "and as hex with internal justification.\n"
15 << "Using the default pad character (space):" << endl;
16
17 // display x with base
18 cout << showbase << setw(10) << x << endl;
19
20 // display x with left justification
21 cout << left << setw(10) << x << endl;
22
23 // display x as hex with internal justification
24 cout << internal << setw(10) << hex << x << endl << endl;
25
26 cout << "Using various padding characters:" << endl;
27
28 // display x using padded characters (right justification)
29 cout << right;
30 cout.fill('*');
31 cout << setw(10) << dec << x << endl;
32
33 // display x using padded characters (left justification)
34 cout << left << setw(10) << setfill('%') << x << endl;

```

**Fig. 23.16** | Using member function fill and stream manipulator setfill to change the padding character for fields larger than the values being printed. (Part 1 of 2.)

```

35
36 // display x using padded characters (internal justification)
37 cout << internal << setw(10) << setfill('^') << hex
38 << x << endl;
39 } // end main

```

10000 printed as int right and left justified  
and as hex with internal justification.  
Using the default pad character (space):

```

10000
10000
0x 2710

```

Using various padding characters:

```

*****10000
10000%%%%%
0x^^^^2710

```

**Fig. 23.16** | Using member function `fill` and stream manipulator `setfill` to change the padding character for fields larger than the values being printed. (Part 2 of 2.)

### 23.7.4 Integral Stream Base (dec, oct, hex, showbase)

C++ provides stream manipulators `dec`, `hex` and `oct` to specify that integers are to be displayed as decimal, hexadecimal and octal values, respectively. Stream insertions default to decimal if none of these manipulators is used. With stream extraction, integers prefixed with 0 (zero) are treated as octal values, integers prefixed with 0x or 0X are treated as hexadecimal values, and all other integers are treated as decimal values. Once a particular base is specified for a stream, all integers on that stream are processed using that base until a different base is specified or until the program terminates.

Stream manipulator `showbase` forces the base of an integral value to be output. Decimal numbers are output by default, octal numbers are output with a leading 0, and hexadecimal numbers are output with either a leading 0x or a leading 0X (as we discuss in Section 23.7.6, stream manipulator `uppercase` determines which option is chosen). Figure 23.17 demonstrates the use of stream manipulator `showbase` to force an integer to print in decimal, octal and hexadecimal formats. To reset the `showbase` setting, output the stream manipulator `noshowbase`.

```

1 // Fig. 23.17: Fig23_17.cpp
2 // Using stream manipulator showbase.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 int x = 100;
9
10 // use showbase to show number base
11 cout << "Printing integers preceded by their base:" << endl
12 << showbase;

```

**Fig. 23.17** | Stream manipulator `showbase`. (Part 1 of 2.)

```
13
14 cout << x << endl; // print decimal value
15 cout << oct << x << endl; // print octal value
16 cout << hex << x << endl; // print hexadecimal value
17 } // end main
```

Printing integers preceded by their base:

```
100
0144
0x64
```

**Fig. 23.17** | Stream manipulator `showbase`. (Part 2 of 2.)

### 23.7.5 Floating-Point Numbers; Scientific and Fixed Notation (scientific, fixed)

Stream manipulators `scientific` and `fixed` control the output format of floating-point numbers. Stream manipulator `scientific` forces the output of a floating-point number to display in scientific format. Stream manipulator `fixed` forces a floating-point number to display a specific number of digits (as specified by member function `precision` or stream manipulator `setprecision`) to the right of the decimal point. Without using another manipulator, the floating-point-number value determines the output format.

Figure 23.18 demonstrates displaying floating-point numbers in fixed and scientific formats using stream manipulators `scientific` (line 18) and `fixed` (line 22). The exponent format in scientific notation might differ across different compilers.

```
1 // Fig. 23.18: Fig23_18.cpp
2 // Displaying floating-point values in system default,
3 // scientific and fixed formats.
4 #include <iostream>
5 using namespace std;
6
7 int main()
8 {
9 double x = 0.001234567;
10 double y = 1.946e9;
11
12 // display x and y in default format
13 cout << "Displayed in default format:" << endl
14 << x << '\t' << y << endl;
15
16 // display x and y in scientific format
17 cout << "\nDisplayed in scientific format:" << endl
18 << scientific << x << '\t' << y << endl;
19
20 // display x and y in fixed format
21 cout << "\nDisplayed in fixed format:" << endl
22 << fixed << x << '\t' << y << endl;
23 }
```

**Fig. 23.18** | Floating-point values displayed in default, scientific and fixed formats. (Part 1 of 2.)

```

Displayed in default format:
0.00123457 1.946e+009

Displayed in scientific format:
1.234567e-003 1.946000e+009

Displayed in fixed format:
0.001235 1946000000.000000

```

**Fig. 23.18** | Floating-point values displayed in default, scientific and fixed formats. (Part 2 of 2.)

### 23.7.6 Uppercase/Lowercase Control (uppercase)

Stream manipulator **uppercase** outputs an uppercase X or E with hexadecimal-integer values or with scientific notation floating-point values, respectively (Fig. 23.19). Using stream manipulator **uppercase** also causes all letters in a hexadecimal value to be uppercase. By default, the letters for hexadecimal values and the exponents in scientific notation floating-point values appear in lowercase. To reset the uppercase setting, output the stream manipulator **nouppercase**.

```

1 // Fig. 23.19: Fig23_19.cpp
2 // Stream manipulator uppercase.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 cout << "Printing uppercase letters in scientific" << endl
9 << "notation exponents and hexadecimal values:" << endl;
10
11 // use std::uppercase to display uppercase letters; use std::hex and
12 // std::showbase to display hexadecimal value and its base
13 cout << uppercase << 4.345e10 << endl
14 << hex << showbase << 123456789 << endl;
15 } // end main

```

```

Printing uppercase letters in scientific
notation exponents and hexadecimal values:
4.345E+010
0X75BCD15

```

**Fig. 23.19** | Stream manipulator **uppercase**.

### 23.7.7 Specifying Boolean Format (boolalpha)

C++ provides data type **bool**, whose values may be **false** or **true**, as a preferred alternative to the old style of using 0 to indicate **false** and nonzero to indicate **true**. A **bool** variable outputs as 0 or 1 by default. However, we can use stream manipulator **boolalpha** to set the output stream to display **bool** values as the strings "true" and "false". Use stream manipulator **noboolalpha** to set the output stream to display **bool** values as integers (i.e., the default setting). The program of Fig. 23.20 demonstrates these stream manipulators.

Line 11 displays the `bool` value, which line 8 sets to `true`, as an integer. Line 15 uses manipulator `boolalpha` to display the `bool` value as a string. Lines 18–19 then change the `bool`'s value and use manipulator `noboolalpha`, so line 22 can display the `bool` value as an integer. Line 26 uses manipulator `boolalpha` to display the `bool` value as a string. Both `boolalpha` and `noboolalpha` are “sticky” settings.



### Good Programming Practice 23.1

*Displaying `bool` values as `true` or `false`, rather than `nonzero` or `0`, respectively, makes program outputs clearer.*

```

1 // Fig. 23.20: Fig23_20.cpp
2 // Demonstrating stream manipulators boolalpha and noboolalpha.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 bool booleanValue = true;
9
10 // display default true booleanValue
11 cout << "booleanValue is " << booleanValue << endl;
12
13 // display booleanValue after using boolalpha
14 cout << "booleanValue (after using boolalpha) is "
15 << boolalpha << booleanValue << endl << endl;
16
17 cout << "switch booleanValue and use noboolalpha" << endl;
18 booleanValue = false; // change booleanValue
19 cout << noboolalpha << endl; // use noboolalpha
20
21 // display default false booleanValue after using noboolalpha
22 cout << "booleanValue is " << booleanValue << endl;
23
24 // display booleanValue after using boolalpha again
25 cout << "booleanValue (after using boolalpha) is "
26 << boolalpha << booleanValue << endl;
27 } // end main

```

```

booleanValue is 1
booleanValue (after using boolalpha) is true

switch booleanValue and use noboolalpha

booleanValue is 0
booleanValue (after using boolalpha) is false

```

**Fig. 23.20** | Stream manipulators `boolalpha` and `noboolalpha`.

### 23.7.8 Setting and Resetting the Format State via Member Function `flags`

Throughout Section 23.7, we’ve been using stream manipulators to change output format characteristics. We now discuss how to return an output stream’s format to its default state

after having applied several manipulations. Member function `flags` without an argument returns the current format settings as a `fmtFlags` data type (of class `ios_base`), which represents the **format state**. Member function `flags` with a `fmtFlags` argument sets the format state as specified by the argument and returns the prior state settings. The initial settings of the value that `flags` returns might differ across several systems. The program of Fig. 23.21 uses member function `flags` to save the stream's original format state (line 17), then restore the original format settings (line 25).

```

1 // Fig. 23.21: Fig23_21.cpp
2 // Demonstrating the flags member function.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 int integerValue = 1000;
9 double doubleValue = 0.0947628;
10
11 // display flags value, int and double values (original format)
12 cout << "The value of the flags variable is: " << cout.flags()
13 << "\nPrint int and double in original format:\n"
14 << integerValue << '\t' << doubleValue << endl << endl;
15
16 // use cout flags function to save original format
17 ios_base::fmtflags originalFormat = cout.flags();
18 cout << showbase << oct << scientific; // change format
19
20 // display flags value, int and double values (new format)
21 cout << "The value of the flags variable is: " << cout.flags()
22 << "\nPrint int and double in a new format:\n"
23 << integerValue << '\t' << doubleValue << endl << endl;
24
25 cout.flags(originalFormat); // restore format
26
27 // display flags value, int and double values (original format)
28 cout << "The restored value of the flags variable is: "
29 << cout.flags()
30 << "\nPrint values in original format again:\n"
31 << integerValue << '\t' << doubleValue << endl;
32 } // end main

```

```

The value of the flags variable is: 513
Print int and double in original format:
1000 0.0947628

```

```

The value of the flags variable is: 012011
Print int and double in a new format:
01750 9.476280e-002

```

```

The restored value of the flags variable is: 513
Print values in original format again:
1000 0.0947628

```

**Fig. 23.21** | `flags` member function.

## 23.8 Stream Error States

The state of a stream may be tested through bits in class `ios_base`. In a moment, we show how to test these bits, in the example of Fig. 23.22.

The `eofbit` is set for an input stream after end-of-file is encountered. A program can use member function `eof` to determine whether end-of-file has been encountered on a stream after an attempt to extract data beyond the end of the stream. The call

```
cin.eof()
```

returns `true` if end-of-file has been encountered on `cin` and `false` otherwise.

The `failbit` is set for a stream when a format error occurs on the stream and no characters are input (e.g., when you attempt to read a number and the user enters a string). When such an error occurs, the characters are not lost. The `fail` member function reports whether a stream operation has failed. Usually, recovering from such errors is possible.

---

```

1 // Fig. 23.22: Fig23_22.cpp
2 // Testing error states.
3 #include <iostream>
4 using namespace std;
5
6 int main()
7 {
8 int integerValue;
9
10 // display results of cin functions
11 cout << "Before a bad input operation:"
12 << "\ncin.rdstate(): " << cin.rdstate()
13 << "\n cin.eof(): " << cin.eof()
14 << "\n cin.fail(): " << cin.fail()
15 << "\n cin.bad(): " << cin.bad()
16 << "\n cin.good(): " << cin.good()
17 << "\n\nExpects an integer, but enter a character: ";
18
19 cin >> integerValue; // enter character value
20 cout << endl;
21
22 // display results of cin functions after bad input
23 cout << "After a bad input operation:"
24 << "\ncin.rdstate(): " << cin.rdstate()
25 << "\n cin.eof(): " << cin.eof()
26 << "\n cin.fail(): " << cin.fail()
27 << "\n cin.bad(): " << cin.bad()
28 << "\n cin.good(): " << cin.good() << endl << endl;
29
30 cin.clear(); // clear stream
31
32 // display results of cin functions after clearing cin
33 cout << "After cin.clear()" << "\ncin.fail(): " << cin.fail()
34 << "\ncin.good(): " << cin.good() << endl;
35 } // end main

```

---

**Fig. 23.22** | Testing error states. (Part I of 2.)



```

Before a bad input operation:
cin.rdstate(): 0
 cin.eof(): 0
 cin.fail(): 0
 cin.bad(): 0
 cin.good(): 1

Expects an integer, but enter a character: A

After a bad input operation:
cin.rdstate(): 2
 cin.eof(): 0
 cin.fail(): 1
 cin.bad(): 0
 cin.good(): 0

After cin.clear()
cin.fail(): 0
cin.good(): 1

```

**Fig. 23.22** | Testing error states. (Part 2 of 2.)

The **badbit** is set for a stream when an error occurs that results in the loss of data. The **bad** member function reports whether a stream operation failed. Generally, such serious failures are nonrecoverable.

The **goodbit** is set for a stream if none of the bits **eofbit**, **failbit** or **badbit** is set for the stream.

The **good** member function returns **true** if the **bad**, **fail** and **eof** functions would all return **false**. I/O operations should be performed only on “good” streams.

The **rdstate** member function returns the stream’s error state. Calling **cout.rdstate**, for example, would return the stream’s state, which then could be tested by a switch statement that examines **eofbit**, **badbit**, **failbit** and **goodbit**. The preferred means of testing the state of a stream is to use member functions **eof**, **bad**, **fail** and **good**—using these functions does not require you to be familiar with particular status bits.

The **clear** member function is used to restore a stream’s state to “good,” so that I/O may proceed on that stream. The default argument for **clear** is **goodbit**, so the statement

```
cin.clear();
```

clears **cin** and sets **goodbit** for the stream. The statement

```
cin.clear(ios::failbit)
```

sets the **failbit**. You might want to do this when performing input on **cin** with a user-defined type and encountering a problem. The name **clear** might seem inappropriate in this context, but it’s correct.

The program of Fig. 23.22 demonstrates member functions **rdstate**, **eof**, **fail**, **bad**, **good** and **clear**. [Note: The actual values output may differ across different compilers.]

The operator **!** member function of **basic\_ios** returns **true** if the **badbit** is set, the **failbit** is set or both are set. The operator **void \*** member function returns **false** (0) if the **badbit** is set, the **failbit** is set or both are set. These functions are useful in file processing when a **true/false** condition is being tested under the control of a selection statement or repetition statement.

## 23.9 Tying an Output Stream to an Input Stream

Interactive applications generally involve an `istream` for input and an `ostream` for output. When a prompting message appears on the screen, the user responds by entering the appropriate data. Obviously, the prompt needs to appear before the input operation proceeds. With output buffering, outputs appear only when the buffer fills, when outputs are flushed explicitly by the program or automatically at the end of the program. C++ provides member function `tie` to synchronize (i.e., “tie together”) the operation of an `istream` and an `ostream` to ensure that outputs appear before their subsequent inputs. The call

```
cin.tie(&cout);
```

ties `cout` (an `ostream`) to `cin` (an `istream`). Actually, this particular call is redundant, because C++ performs this operation automatically to create a user's standard input/output environment. However, the user would tie other `istream/ostream` pairs explicitly. To untie an input stream, `inputStream`, from an output stream, use the call

```
inputStream.tie(0);
```

## 23.10 Wrap-Up

This chapter summarized how C++ performs input/output using streams. You learned about the stream-I/O classes and objects, as well as the stream I/O template class hierarchy. We discussed `ostream`'s formatted and unformatted output capabilities performed by the `put` and `write` functions. You saw examples using `istream`'s formatted and unformatted input capabilities performed by the `eof`, `get`, `getline`, `peek`, `putback`, `ignore` and `read` functions. Next, we discussed stream manipulators and member functions that perform formatting tasks—`dec`, `oct`, `hex` and `setbase` for displaying integers; `precision` and `setprecision` for controlling floating-point precision; and `width` and `setw` for setting field width. You also learned additional formatting `istream` manipulators and member functions—`showpoint` for displaying decimal point and trailing zeros; `left`, `right` and `internal` for justification; `fill` and `setfill` for padding; `scientific` and `fixed` for displaying floating-point numbers in scientific and fixed notation; `uppercase` for uppercase/lowercase control; `boolalpha` for specifying boolean format; and `flags` and `fmtflags` for resetting the format state.

In the next chapter, we introduce exception handling, which allows you to deal with certain problems that may occur during a program's execution. We demonstrate basic exception-handling techniques that often permit a program to continue executing as if no problem had been encountered. We also present several classes that the C++ Standard Library provides for handling exceptions.

## Summary

### Section 23.1 Introduction

- I/O operations are performed in a manner sensitive to the type of the data.

### Section 23.2 Streams

- C++ I/O occurs in streams. A stream is a sequence of bytes.

- I/O mechanisms move bytes from devices to memory and vice versa efficiently and reliably.
- C++ provides “low-level” and “high-level” I/O capabilities. Low-level I/O capabilities specify that bytes should be transferred device-to-memory or memory-to-device. High-level I/O is performed with bytes grouped into meaningful units such as integers, strings and user-defined types.
- C++ provides both unformatted-I/O and formatted-I/O operations. Unformatted-I/O transfers are fast, but process raw data that is difficult for people to use. Formatted I/O processes data in meaningful units, but requires extra processing time that can degrade the performance.
- The `<iostream>` header file declares all stream-I/O operations.
- The `<iomanip>` header declares the parameterized stream manipulators.
- The `<fstream>` header declares file-processing operations.
- The `basic_istream` template supports stream-input operations.
- The `basic_ostream` template supports stream-output operations.
- The `basic_iostream` template supports both stream-input and stream-output operations.
- Templates `basic_istream` and the `basic_ostream` each derive from the `basic_ios` template.
- Template `basic_iostream` derives from both the `basic_istream` and `basic_ostream` templates.
- The `istream` object `cin` is tied to the standard input device, normally the keyboard.
- The `ostream` object `cout` is tied to the standard output device, normally the screen.
- The `ostream` object `cerr` is tied to the standard error device, normally the screen. Outputs to `cerr` are unbuffered; each insertion to `cerr` appears immediately.
- The `ostream` object `clog` is tied to the standard error device, normally the screen. Outputs to `clog` are buffered.
- The C++ compiler determines data types automatically for input and output.

### Section 23.3 Stream Output

- Addresses are displayed in hexadecimal format by default.
- To print the address in a pointer variable, cast the pointer to `void *`.
- Member function `put` outputs one character. Calls to `put` may be cascaded.

### Section 23.4 Stream Input

- Stream input is performed with the stream extraction operator `>>`, which automatically skips white-space characters in the input stream and returns `false` after end-of-file is encountered.
- Stream extraction causes `failbit` to be set for improper input and `badbit` to be set if the operation fails.
- A series of values can be input using the stream extraction operation in a `while` loop header. The extraction returns 0 when end-of-file is encountered or an error occurs.
- The `get` member function with no arguments inputs one character and returns the character; EOF is returned if end-of-file is encountered on the stream.
- Member function `get` with a character-reference argument inputs the next character from the input stream and stores it in the character argument. This version of `get` returns a reference to the `istream` object for which the `get` member function is being invoked.
- Member function `get` with three arguments—a character array, a size limit and a delimiter (with default value `newline`)—reads characters from the input stream up to a maximum of `limit - 1` characters, or until the delimiter is read. The input string is terminated with a null character. The delimiter is not placed in the character array but remains in the input stream.
- The `getline` member function operates like the three-argument `get` member function. The `getline` function removes the delimiter from the input stream but does not store it in the string.

- Member function `ignore` skips the specified number of characters (the default is 1) in the input stream; it terminates if the specified delimiter is encountered (the default delimiter is EOF).
- The `putback` member function places the previous character obtained by a `get` on a stream back into that stream.
- The `peek` member function returns the next character from an input stream but does not extract (remove) the character from the stream.
- C++ offers type-safe I/O. If unexpected data is processed by the `<<` and `>>` operators, various error bits are set, which can be tested to determine whether an I/O operation succeeded or failed. If operator `<<` has not been overloaded for a user-defined type, a compiler error is reported.

### *Section 23.5 Unformatted I/O Using `read`, `write` and `gcount`*

- Unformatted I/O is performed with member functions `read` and `write`. These input or output bytes to or from memory, beginning at a designated memory address.
- The `gcount` member function returns the number of characters input by the previous `read` operation on that stream.
- Member function `read` inputs a specified number of characters into a character array. `failbit` is set if fewer than the specified number of characters are read.

### *Section 23.6 Introduction to Stream Manipulators*

- To change the base in which integers output, use the manipulator `hex` to set the base to hexadecimal (base 16) or `oct` to set the base to octal (base 8). Use manipulator `dec` to reset the base to decimal. The base remains the same until changed explicitly.
- The parameterized stream manipulator `setbase` also sets the base for integer output. `setbase` takes one integer argument of 10, 8 or 16 to set the base.
- Floating-point precision can be controlled with the `setprecision` stream manipulator or the `precision` member function. Both set the precision for all subsequent output operations until the next precision-setting call. The `precision` member function with no argument returns the current precision value.
- Parameterized manipulators require the inclusion of the `<iomanip>` header file.
- Member function `width` sets the field width and returns the previous width. Values narrower than the field are padded with fill characters. The field-width setting applies only for the next insertion or extraction; the field width is set to 0 implicitly (subsequent values will be output as large as necessary). Values wider than a field are printed in their entirety. Function `width` with no argument returns the current width setting. Manipulator `setw` also sets the width.
- For input, the `setw` stream manipulator establishes a maximum string size; if a larger string is entered, the larger line is broken into pieces no larger than the designated size.
- You can create your own stream manipulators.

### *Section 23.7 Stream Format States and Stream Manipulators*

- Stream manipulator `showpoint` forces a floating-point number to be output with a decimal point and with the number of significant digits specified by the `precision`.
- Stream manipulators `left` and `right` cause fields to be left justified with padding characters to the right or right justified with padding characters to the left.
- Stream manipulator `internal` indicates that a number's sign (or base when using stream manipulator `showbase`) should be left justified within a field, its magnitude should be right justified and intervening spaces should be padded with the fill character.

- Member function `fill` specifies the fill character to be used with stream manipulators `left`, `right` and `internal` (space is the default); the prior padding character is returned. Stream manipulator `setfill` also sets the fill character.
- Stream manipulators `oct`, `hex` and `dec` specify that integers are to be treated as octal, hexadecimal or decimal values, respectively. Integer output defaults to decimal if none of these bits is set; stream extractions process the data in the form the data is supplied.
- Stream manipulator `showbase` forces the base of an integral value to be output.
- Stream manipulator `scientific` is used to output a floating-point number in scientific format. Stream manipulator `fixed` is used to output a floating-point number with the precision specified by the `precision` member function.
- Stream manipulator `uppercase` outputs an uppercase X or E for hexadecimal integers and scientific notation floating-point values, respectively. Hexadecimal values appear in all uppercase.
- Member function `flags` with no argument returns the `long` value of the current format state settings. Function `flags` with a `long` argument sets the format state specified by the argument.

### Section 23.8 Stream Error States

- The state of a stream may be tested through bits in class `ios_base`.
- The `eofbit` is set for an input stream after end-of-file is encountered during an input operation. The `eof` member function reports whether the `eofbit` has been set.
- A stream's `failbit` is set when a format error occurs. The `fail` member function reports whether a stream operation has failed; it's normally possible to recover from such errors.
- A stream's `badbit` is set when an error occurs that results in data loss. Member function `bad` reports whether such a stream operation failed. Such serious failures are normally nonrecoverable.
- The `good` member function returns `true` if the `bad`, `fail` and `eof` functions would all return `false`. I/O operations should be performed only on “good” streams.
- The `rdstate` member function returns the error state of the stream.
- Member function `clear` restores a stream's state to “good,” so that I/O may proceed.

### Section 23.9 Tying an Output Stream to an Input Stream

- C++ provides the `tie` member function to synchronize `istream` and `ostream` operations to ensure that outputs appear before subsequent inputs.

## Terminology

`bad` member function of `basic_ios` 878  
`badbit` 858  
`basic_fstream` class template 856  
`basic_ifstream` class template 856  
`basic_ios` class template 855  
`basic_istream` class template 854  
`basic_ostream` class template 856  
`basic_ostream` class template 854  
`boolalpha` stream manipulator 874  
`buffered` 856  
`classic` stream libraries 853

`clear` member function of `basic_ios` 878  
`dec` stream manipulator 863  
`eof` member function of `basic_ios` 878  
`eofbit` 877  
`fail` member function of `basic_ios` 878  
`failbit` 858  
`fill` character 865  
`fill` member function of `basic_ios` 871  
`fixed` stream manipulator 873  
`flags` member function of `ios_base` 876  
`fmtflags` 876  
`format` state 876

fstream 856  
 gcount member function of basic\_istream 862  
 get member function of basic\_istream 858  
 getline member function of basic\_istream 860  
 good member function of basic\_ios 878  
 goodbit 878  
 hex stream manipulator 863  
 ifstream 856  
 ignore member function of basic\_istream 861  
 internal stream manipulator 870  
 istream 854  
 istream 854  
 left stream manipulator 869  
 noboolalpha stream manipulator 874  
 noshowbase stream manipulator 872  
 noshowpoint stream manipulator 869  
 noshowpos stream manipulator 870  
 nouppercase stream manipulator 874  
 oct stream manipulator 863  
 ofstream 856  
 ostream 854  
 padding 865  
 parameterized stream manipulators 854  
 peek member function of basic\_istream 861  
 precision 864  
 precision member function of ios\_base 864  
 putback member function of  
     basic\_istream 861  
 rdstate member function of basic\_ios 878  
 read member function of basic\_istream 861  
 right stream manipulator 869  
 scientific stream manipulator 873  
 setbase stream manipulator 863  
 setfill stream manipulator 871  
 showbase stream manipulator 872  
 showpoint stream manipulator 868  
 showpos stream manipulator 870  
 standard stream libraries 854  
 state bit 858  
 stream 853  
 stream manipulator 862  
 tie member function of basic\_ios 879  
 typedef 854  
 type-safe I/O 852  
 unbuffered 856  
 unformatted I/O 853  
 Unicode® character set 853  
 uppercase stream manipulator 868  
 wchar\_t 854  
 white-space character 858  
 width stream manipulator 865  
 write member function of basic\_ostream 861

## Self-Review Exercises

### 23.1 Answer each of the following:

- Input/output in C++ occurs as \_\_\_\_\_ of bytes.
- The stream manipulators that format justification are \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- Member function \_\_\_\_\_ can be used to set and reset format state.
- Most C++ programs that do I/O should include the \_\_\_\_\_ header file that contains the declarations required for all stream-I/O operations.
- When using parameterized manipulators, the header file \_\_\_\_\_ must be included.
- Header file \_\_\_\_\_ contains the declarations required for file processing.
- The ostream member function \_\_\_\_\_ is used to perform unformatted output.
- Input operations are supported by class \_\_\_\_\_.
- Standard error stream outputs are directed to the stream objects \_\_\_\_\_ or \_\_\_\_\_.
- Output operations are supported by class \_\_\_\_\_.
- The symbol for the stream insertion operator is \_\_\_\_\_.
- The four objects that correspond to the standard devices on the system include \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_.
- The symbol for the stream extraction operator is \_\_\_\_\_.
- The stream manipulators \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_ specify that integers should be displayed in octal, hexadecimal and decimal formats, respectively.
- The \_\_\_\_\_ stream manipulator causes positive numbers to display with a plus sign.

**23.2** State whether the following are *true* or *false*. If the answer is *false*, explain why.

- a) The stream member function `flags` with a `long` argument sets the `flags` state variable to its argument and returns its previous value.
- b) The stream insertion operator `<<` and the stream extraction operator `>>` are overloaded to handle all standard data types—including strings and memory addresses (stream insertion only)—and all user-defined data types.
- c) The stream member function `flags` with no arguments resets the stream's format state.
- d) The stream extraction operator `>>` can be overloaded with an operator function that takes an `istream` reference and a reference to a user-defined type as arguments and returns an `istream` reference.
- e) The stream insertion operator `<<` can be overloaded with an operator function that takes an `istream` reference and a reference to a user-defined type as arguments and returns an `istream` reference.
- f) Input with the stream extraction operator `>>` always skips leading white-space characters in the input stream, by default.
- g) The stream member function `rdstate` returns the current state of the stream.
- h) The `cout` stream normally is connected to the display screen.
- i) The stream member function `good` returns `true` if the `bad`, `fail` and `eof` member functions all return `false`.
- j) The `cin` stream normally is connected to the display screen.
- k) If a nonrecoverable error occurs during a stream operation, the `bad` member function will return `true`.
- l) Output to `cerr` is unbuffered and output to `clog` is buffered.
- m) Stream manipulator `showpoint` forces floating-point values to print with the default six digits of precision unless the precision value has been changed, in which case floating-point values print with the specified precision.
- n) The `ostream` member function `put` outputs the specified number of characters.
- o) The stream manipulators `dec`, `oct` and `hex` affect only the next integer output operation.
- p) By default, memory addresses are displayed as `long` integers.

**23.3** For each of the following, write a single statement that performs the indicated task.

- a) Output the string "Enter your name: ".
- b) Use a stream manipulator that causes the exponent in scientific notation and the letters in hexadecimal values to print in capital letters.
- c) Output the address of the variable `myString` of type `char *`.
- d) Use a stream manipulator to ensure that floating-point values print in scientific notation.
- e) Output the address in variable `integerPtr` of type `int *`.
- f) Use a stream manipulator such that, when integer values are output, the integer base for octal and hexadecimal values is displayed.
- g) Output the value pointed to by `floatPtr` of type `float *`.
- h) Use a stream member function to set the fill character to '\*' for printing in field widths larger than the values being output. Repeat this statement with a stream manipulator.
- i) Output the characters '0' and 'K' in one statement with `ostream` function `put`.
- j) Get the value of the next character to input without extracting it from the stream.
- k) Input a single character into variable `charValue` of type `char`, using the `istream` member function `get` in two different ways.
- l) Input and discard the next six characters in the input stream.
- m) Use `istream` member function `read` to input 50 characters into `char` array `line`.
- n) Read 10 characters into character array `name`. Stop reading characters if the '.' delimiter is encountered. Do not remove the delimiter from the input stream. Write another statement that performs this task and removes the delimiter from the input.

- o) Use the `istream` member function `gcount` to determine the number of characters input into character array `line` by the last call to `istream` member function `read`, and output that number of characters, using `ostream` member function `write`.
- p) Output 124, 18.376, 'Z', 1000000 and "String", separated by spaces.
- q) Print the current precision setting, using a member function of object `cout`.
- r) Input an integer value into `int` variable `months` and a floating-point value into `float` variable `percentageRate`.
- s) Print 1.92, 1.925 and 1.9258 separated by tabs and with 3 digits of precision, using a stream manipulator.
- t) Print integer 100 in octal, hexadecimal and decimal, using stream manipulators and separated by tabs.
- u) Print integer 100 in decimal, octal and hexadecimal separated by tabs, using a stream manipulator to change the base.
- v) Print 1234 right justified in a 10-digit field.
- w) Read characters into character array `line` until the character 'z' is encountered, up to a limit of 20 characters (including a terminating null character). Do not extract the delimiter character from the stream.
- x) Use integer variables `x` and `y` to specify the field width and precision used to display the `double` value 87.4573, and display the value.

**23.4** Identify the error in each of the following statements and explain how to correct it.

- a) `cout << "Value of x <= y is: " << x <= y;`
- b) The following statement should print the integer value of 'c'.  
`cout << 'c';`
- c) `cout << ""A string in quotes"";`

**23.5** For each of the following, show the output.

- a) `cout << "12345" << endl;`  
`cout.width( 5 );`  
`cout.fill( '*' );`  
`cout << 123 << endl << 123;`
- b) `cout << setw( 10 ) << setfill( '$' ) << 10000;`
- c) `cout << setw( 8 ) << setprecision( 3 ) << 1024.987654;`
- d) `cout << showbase << oct << 99 << endl << hex << 99;`
- e) `cout << 100000 << endl << showpos << 100000;`
- f) `cout << setw( 10 ) << setprecision( 2 ) << scientific << 444.93738;`

## Answers to Self-Review Exercises

**23.1** a) streams. b) left, right and internal. c) flags. d) `<iostream>`. e) `<iomanip>`. f) `<fstream>`. g) `write`. h) `istream`. i) `cerr` or `clog`. j) `ostream`. k) `<<`. l) `cin`, `cout`, `cerr` and `clog`. m) `>>`. n) oct, hex and dec. o) `showpos`.

**23.2** a) False. The stream member function `flags` with a `fmtflags` argument sets the flags state variable to its argument and returns the prior state settings. b) False. The stream insertion and stream extraction operators are not overloaded for all user-defined types. You must specifically provide the overloaded operator functions to overload the stream operators for use with each user-defined type you create. c) False. The stream member function `flags` with no arguments returns the current format settings as a `fmtflags` data type, which represents the format state. d) True. e) False. To overload the stream insertion operator `<<`, the overloaded operator function must take an `ostream` reference and a reference to a user-defined type as arguments and return an `ostream` reference. f) True. g) True. h) True. i) True. j) False. The `cin` stream is connected to the standard input



of the computer, which normally is the keyboard. k) True. l) True. m) True. n) False. The ostream member function put outputs its single-character argument. o) False. The stream manipulators dec, oct and hex set the output format state for integers to the specified base until the base is changed again or the program terminates. p) False. Memory addresses are displayed in hexadecimal format by default. To display addresses as long integers, the address must be cast to a long value.

**23.3**

```

a) cout << "Enter your name: ";
b) cout << uppercase;
c) cout << static_cast< void * >(myString);
d) cout << scientific;
e) cout << integerPtr;
f) cout << showbase;
g) cout << *floatPtr;
h) cout.fill('*');
 cout << setfill('*');
i) cout.put('O').put('K');
j) cin.peek();
k) charValue = cin.get();
 cin.get(charValue);
l) cin.ignore(6);
m) cin.read(line, 50);
n) cin.get(name, 10, '.');
 cin.getline(name, 10, '.');
o) cout.write(line, cin.gcount());
p) cout << 124 << ' ' << 18.376 << ' ' << "Z " << 1000000 << " String";
q) cout << cout.precision();
r) cin >> months >> percentageRate;
s) cout << setprecision(3) << 1.92 << '\t' << 1.925 << '\t' << 1.9258;
t) cout << oct << 100 << '\t' << hex << 100 << '\t' << dec << 100;
u) cout << 100 << '\t' << setbase(8) << 100 << '\t' << setbase(16) << 100;
v) cout << setw(10) << 1234;
w) cin.get(line, 20, 'z');
x) cout << setw(x) << setprecision(y) << 87.4573;

```

**23.4**

a) *Error:* The precedence of the << operator is higher than that of <=, which causes the statement to be evaluated improperly and also causes a compiler error.  
*Correction:* Place parentheses around the expression `x <= y`.

b) *Error:* In C++, characters are not treated as small integers, as they are in C.  
*Correction:* To print the numerical value for a character in the computer's character set, the character must be cast to an integer value, as in the following:

```
cout << static_cast< int >('c');
```

c) *Error:* Quote characters cannot be printed in a string unless an escape sequence is used.  
*Correction:* Print the string in one of the following ways:

```
cout << "\"A string in quotes\"";
```

**23.5**

```

a) 12345
 **123
 123
b) $$$$10000
c) 1024.988
d) 0143
 0x63

```

- e) 100000  
+100000
- f) 4.45e+002

## Exercises

**23.6** Write a statement for each of the following:

- a) Print integer 40000 left justified in a 15-digit field.
- b) Read a string into character array variable state.
- c) Print 200 with and without a sign.
- d) Print the decimal value 100 in hexadecimal form preceded by 0x.
- e) Read characters into array charArray until the character 'p' is encountered, up to a limit of 10 characters (including the terminating null character). Extract the delimiter from the input stream, and discard it.
- f) Print 1.234 in a 9-digit field with preceding zeros.

**23.7** (*Inputting Decimal, Octal and Hexadecimal Values*) Write a program to test the inputting of integer values in decimal, octal and hexadecimal formats. Output each integer read by the program in all three formats. Test the program with the following input data: 10, 010, 0x10.

**23.8** (*Printing Pointer Values as Integers*) Write a program that prints pointer values, using casts to all the integer data types. Which ones print strange values? Which ones cause errors?

**23.9** (*Printing with Field Widths*) Write a program to test the results of printing the integer value 12345 and the floating-point value 1.2345 in various-sized fields. What happens when the values are printed in fields containing fewer digits than the values?

**23.10** (*Rounding*) Write a program that prints the value 100.453627 rounded to the nearest digit, tenth, hundredth, thousandth and ten-thousandth.

**23.11** Write a program that inputs a string from the keyboard and determines the length of the string. Print the string in a field width that is twice the length of the string.

**23.12** (*Converting Fahrenheit to Celsius*) Write a program that converts integer Fahrenheit temperatures from 0 to 212 degrees to floating-point Celsius temperatures with 3 digits of precision. Use the formula

```
celsius = 5.0 / 9.0 * (fahrenheit - 32);
```

to perform the calculation. The output should be printed in two right-justified columns and the Celsius temperatures should be preceded by a sign for both positive and negative values.

**23.13** In some programming languages, strings are entered surrounded by either single or double quotation marks. Write a program that reads the three strings suzy, "suzy" and 'suzy'. Are the single and double quotes ignored or read as part of the string?

**23.14** (*Reading Phone Numbers with and Overloaded Stream Extraction Operator*) In Fig. 19.5, the stream extraction and stream insertion operators were overloaded for input and output of objects of the PhoneNumber class. Rewrite the stream extraction operator to perform the following error checking on input. The operator>> function will need to be reimplemented.

- a) Input the entire phone number into an array. Test that the proper number of characters has been entered. There should be a total of 14 characters read for a phone number of the form (800) 555-1212. Use ios\_base-member-function clear to set failbit for improper input.
- b) The area code and exchange do not begin with 0 or 1. Test the first digit of the area-code and exchange portions of the phone number to be sure that neither begins with 0 or 1. Use ios\_base-member-function clear to set failbit for improper input.

- c) The middle digit of an area code used to be limited to 0 or 1 (although this has changed recently). Test the middle digit for a value of 0 or 1. Use the `ios_base`-member-function `clear` to set `failbit` for improper input. If none of the above operations results in `failbit` being set for improper input, copy the three parts of the telephone number into the `areaCode`, `exchange` and `line` members of the `PhoneNumber` object. If `failbit` has been set on the input, have the program print an error message and end, rather than print the phone number.

**23.15** (*Point Class*) Write a program that accomplishes each of the following:

- a) Create a user-defined class `Point` that contains the private integer data members `xCoordinate` and `yCoordinate` and declares stream insertion and stream extraction overloaded operator functions as friends of the class.
- b) Define the stream insertion and stream extraction operator functions. The stream extraction operator function should determine whether the data entered is valid, and, if not, it should set the `failbit` to indicate improper input. The stream insertion operator should not be able to display the point after an input error occurred.
- c) Write a main function that tests input and output of user-defined class `Point`, using the overloaded stream extraction and stream insertion operators.

**23.16** (*Complex Class*) Write a program that accomplishes each of the following:

- a) Create a user-defined class `Complex` that contains the private integer data members `real` and `imaginary` and declares stream insertion and stream extraction overloaded operator functions as friends of the class.
- b) Define the stream insertion and stream extraction operator functions. The stream extraction operator function should determine whether the data entered is valid, and, if not, it should set `failbit` to indicate improper input. The input should be of the form
 
$$3 + 8i$$
- c) The values can be negative or positive, and it's possible that one of the two values is not provided, in which case the appropriate data member should be set to 0. The stream insertion operator should not be able to display the point if an input error occurred. For negative imaginary values, a minus sign should be printed rather than a plus sign.
- d) Write a main function that tests input and output of user-defined class `Complex`, using the overloaded stream extraction and stream insertion operators.

**23.17** (*Printing a Table of ASCII Values*) Write a program that uses a `for` statement to print a table of ASCII values for the characters in the ASCII character set from 33 to 126. The program should print the decimal value, octal value, hexadecimal value and character value for each character. Use the stream manipulators `dec`, `oct` and `hex` to print the integer values.

**23.18** Write a program to show that the `getline` and three-argument `get` istream member functions both end the input string with a string-terminating null character. Also, show that `get` leaves the delimiter character on the input stream, whereas `getline` extracts the delimiter character and discards it. What happens to the unread characters in the stream?

# Exception Handling

# 24

*It is common sense to take a method and try it. If it fails, admit it frankly and try another. But above all, try something.*

—Franklin Delano Roosevelt

*If they're running and they don't look where they're going I have to come out from somewhere and catch them.*

—Jerome David Salinger

*I never forget a face, but in your case I'll make an exception.*

—Groucho Marx

## Objectives

In this chapter you'll learn:

- What exceptions are and when to use them.
- To use **try**, **catch** and **throw** to detect, handle and indicate exceptions, respectively.
- To process uncaught and unexpected exceptions.
- To declare new exception classes.
- How stack unwinding enables exceptions not caught in one scope to be caught in another scope.
- To handle **new** failures.
- To use **auto\_ptr** to prevent memory leaks.
- To understand the standard exception hierarchy.

|                                                            |                                                                        |
|------------------------------------------------------------|------------------------------------------------------------------------|
| <b>24.1</b> Introduction                                   | <b>24.9</b> Constructors, Destructors and Exception Handling           |
| <b>24.2</b> Exception-Handling Overview                    | <b>24.10</b> Exceptions and Inheritance                                |
| <b>24.3</b> Example: Handling an Attempt to Divide by Zero | <b>24.11</b> Processing new Failures                                   |
| <b>24.4</b> When to Use Exception Handling                 | <b>24.12</b> Class <code>auto_ptr</code> and Dynamic Memory Allocation |
| <b>24.5</b> Rethrowing an Exception                        | <b>24.13</b> Standard Library Exception Hierarchy                      |
| <b>24.6</b> Exception Specifications                       | <b>24.14</b> Other Error-Handling Techniques                           |
| <b>24.7</b> Processing Unexpected Exceptions               | <b>24.15</b> Wrap-Up                                                   |
| <b>24.8</b> Stack Unwinding                                |                                                                        |

Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises

## 24.1 Introduction

In this chapter, we introduce **exception handling**. An **exception** is an indication of a problem that occurs during a program's execution. The name "exception" implies that the problem occurs infrequently—if the "rule" is that a statement normally executes correctly, then the "exception to the rule" is that a problem occurs. Exception handling enables you to create applications that can resolve (or handle) exceptions. In many cases, handling an exception allows a program to continue executing as if no problem had been encountered. A more severe problem could prevent a program from continuing normal execution, instead requiring the program to notify the user of the problem before terminating in a controlled manner. The features presented in this chapter enable you to write **robust** and **fault-tolerant programs** that can deal with problems that may arise and continue executing or terminate gracefully. The style and details of C++ exception handling are based in part on the work of Andrew Koenig and Bjarne Stroustrup, as presented in their paper, "Exception Handling for C++ (revised)."<sup>1</sup>



### Error-Prevention Tip 24.1

*Exception handling helps improve a program's fault tolerance.*



### Software Engineering Observation 24.1

*Exception handling provides a standard mechanism for processing errors. This is especially important when working on a project with a large team of programmers.*

We begin with an overview of exception-handling concepts, then demonstrates basic exception-handling techniques. We show these techniques via an example that demonstrates handling an exception that occurs when a function attempts to divide by zero. We then discuss additional exception-handling issues, such as how to handle exceptions that occur in a constructor or destructor and how to handle exceptions that occur if operator new fails to allocate memory for an object. We conclude the chapter by introducing several classes that the C++ Standard Library provides for handling exceptions.

1. Koenig, A., and B. Stroustrup, "Exception Handling for C++ (revised)," *Proceedings of the Usenix C++ Conference*, pp. 149–176, San Francisco, April 1990.

## 24.2 Exception-Handling Overview

Program logic frequently tests conditions that determine how program execution proceeds. Consider the following pseudocode:

```
Perform a task
If the preceding task did not execute correctly
 Perform error processing
Perform next task
If the preceding task did not execute correctly
 Perform error processing
...
```

In this pseudocode, we begin by performing a task. We then test whether that task executed correctly. If not, we perform error processing. Otherwise, we continue with the next task. Although this form of error handling works, intermixing program logic with error-handling logic can make the program difficult to read, modify, maintain and debug—especially in large applications.



### Performance Tip 24.1

*If the potential problems occur infrequently, intermixing program logic and error-handling logic can degrade a program's performance, because the program must (potentially frequently) perform tests to determine whether the task executed correctly and the next task can be performed.*

Exception handling enables you to remove error-handling code from the “main line” of the program’s execution, which improves program clarity and enhances modifiability. You can decide to handle any exceptions you choose—all exceptions, all exceptions of a certain type or all exceptions of a group of related types (e.g., exception types that belong to an inheritance hierarchy). Such flexibility reduces the likelihood that errors will be overlooked and thereby makes a program more robust.

With programming languages that do not support exception handling, programmers often delay writing error-processing code or sometimes forget to include it. This results in less robust software products. C++ enables you to deal with exception handling easily from the inception of a project.

## 24.3 Example: Handling an Attempt to Divide by Zero

Let’s consider a simple example of exception handling (Figs. 24.1–24.2). The purpose of this example is to show how to prevent a common arithmetic problem—division by zero. In C++, division by zero using integer arithmetic typically causes a program to terminate prematurely. In floating-point arithmetic, some C++ implementations allow division by zero, in which case positive or negative infinity is displayed as INF or -INF, respectively.

In this example, we define a function named `quotient` that receives two integers input by the user and divides its first `int` parameter by its second `int` parameter. Before performing the division, the function casts the first `int` parameter’s value to type `double`.



Then, the second `int` parameter's value is promoted to type `double` for the calculation. So function `quotient` actually performs the division using two `double` values and returns a `double` result.

Although division by zero is allowed in floating-point arithmetic, for the purpose of this example we treat any attempt to divide by zero as an error. Thus, function `quotient` tests its second parameter to ensure that it isn't zero before allowing the division to proceed. If the second parameter is zero, the function uses an exception to indicate to the caller that a problem occurred. The caller (`main` in this example) can then process the exception and allow the user to type two new values before calling function `quotient` again. In this way, the program can continue to execute even after an improper value is entered, thus making the program more robust.

The example consists of two files. `DivideByZeroException.h` (Fig. 24.1) defines an exception class that represents the type of the problem that might occur in the example, and `fig24_02.cpp` (Fig. 24.2) defines the `quotient` function and the `main` function that calls it. Function `main` contains the code that demonstrates exception handling.

### *Defining an Exception Class to Represent the Type of Problem That Might Occur*

Figure 24.1 defines class `DivideByZeroException` as a derived class of Standard Library class `runtime_error` (defined in header file `<stdexcept>`). Class `runtime_error`—a derived class of Standard Library class `exception` (defined in header file `<exception>`)—is the C++ standard base class for representing runtime errors. Class `exception` is the standard C++ base class for all exceptions. (Section 24.13 discusses class `exception` and its derived classes in detail.) A typical exception class that derives from the `runtime_error` class defines only a constructor (e.g., lines 12–13) that passes an error-message string to the base-class `runtime_error` constructor. Every exception class that derives directly or indirectly from `exception` contains the virtual function `what`, which returns an exception object's error message. You're not required to derive a custom exception class, such as `DivideByZeroException`, from the standard exception classes provided by C++. However, doing so allows you to use the virtual function `what` to obtain an appropriate error message. We use an object of this `DivideByZeroException` class in Fig. 24.2 to indicate when an attempt is made to divide by zero.

---

```

1 // Fig. 24.1: DivideByZeroException.h
2 // Class DivideByZeroException definition.
3 #include <stdexcept> // stdexcept header file contains runtime_error
4 using namespace std;
5
6 // DivideByZeroException objects should be thrown by functions
7 // upon detecting division-by-zero exceptions
8 class DivideByZeroException : public runtime_error
9 {
10 public:
11 // constructor specifies default error message
12 DivideByZeroException()
13 : runtime_error("attempted to divide by zero") {}
14 }; // end class DivideByZeroException

```

---

**Fig. 24.1** | Class `DivideByZeroException` definition.

*Demonstrating Exception Handling*

The program in Fig. 24.2 uses exception handling to wrap code that might throw a “divide-by-zero” exception and to handle that exception, should one occur. The application enables the user to enter two integers, which are passed as arguments to function `quotient` (lines 10–18). This function divides its first parameter (numerator) by its second parameter (denominator). Assuming that the user does not specify 0 as the denominator for the division, function `quotient` returns the division result. However, if the user inputs 0 for the denominator, function `quotient` throws an exception. In the sample output, the first two lines show a successful calculation, and the next two lines show a failed calculation due to an attempt to divide by zero. When the exception occurs, the program informs the user of the mistake and prompts the user to input two new integers. After we discuss the code, we’ll consider the user inputs and flow of program control that yield these outputs.

---

```

1 // Fig. 24.2: Fig24_02.cpp
2 // A simple exception-handling example that checks for
3 // divide-by-zero exceptions.
4 #include <iostream>
5 #include "DivideByZeroException.h" // DivideByZeroException class
6 using namespace std;
7
8 // perform division and throw DivideByZeroException object if
9 // divide-by-zero exception occurs
10 double quotient(int numerator, int denominator)
11 {
12 // throw DivideByZeroException if trying to divide by zero
13 if (denominator == 0)
14 throw DivideByZeroException(); // terminate function
15
16 // return division result
17 return static_cast< double >(numerator) / denominator;
18 } // end function quotient
19
20 int main()
21 {
22 int number1; // user-specified numerator
23 int number2; // user-specified denominator
24 double result; // result of division
25
26 cout << "Enter two integers (end-of-file to end): ";
27
28 // enable user to enter two integers to divide
29 while (cin >> number1 >> number2)
30 {
31 // try block contains code that might throw exception
32 // and code that should not execute if an exception occurs
33 try
34 {
35 result = quotient(number1, number2);

```

---

**Fig. 24.2** | Exception-handling example that throws exceptions on attempts to divide by zero.  
(Part I of 2.)



```

36 cout << "The quotient is: " << result << endl;
37 } // end try
38 catch (DivideByZeroException ÷ByZeroException)
39 {
40 cout << "Exception occurred: "
41 << divideByZeroException.what() << endl;
42 } // end catch
43
44 cout << "\nEnter two integers (end-of-file to end): ";
45 } // end while
46
47 cout << endl;
48 } // end main

```

```

Enter two integers (end-of-file to end): 100 7
The quotient is: 14.2857

```

```

Enter two integers (end-of-file to end): 100 0
Exception occurred: attempted to divide by zero

```

```

Enter two integers (end-of-file to end): ^Z

```

**Fig. 24.2** | Exception-handling example that throws exceptions on attempts to divide by zero. (Part 2 of 2.)

### Enclosing Code in a try Block

The program begins by prompting the user to enter two integers. The integers are input in the condition of the while loop (line 29). Line 35 passes the values to function `quotient` (lines 10–18), which either divides the integers and returns a result, or **throws an exception** (i.e., indicates that an error occurred) on an attempt to divide by zero. Exception handling is geared to situations in which the function that detects an error is unable to handle it.

C++ provides **try blocks** to enable exception handling. A try block consists of keyword **try** followed by braces (`{}`) that define a block of code in which exceptions might occur. The try block encloses statements that might cause exceptions and statements that should be skipped if an exception occurs.

A try block (lines 33–37) encloses the invocation of function `quotient` and the statement that displays the division result. In this example, because the invocation of function `quotient` (line 35) can throw an exception, we enclose this function invocation in a try block. Enclosing the output statement (line 36) in the try block ensures that the output will occur only if function `quotient` returns a result.



### Software Engineering Observation 24.2

Exceptions may surface through explicitly mentioned code in a try block, through calls to other functions and through deeply nested function calls initiated by code in a try block.

### Defining a catch Handler to Process a DivideByZeroException

Exceptions are processed by **catch handlers** (also called **exception handlers**), which catch and handle exceptions. At least one catch handler (lines 38–42) must immediately follow

each try block. Each catch handler begins with the keyword **catch** and specifies in parentheses an **exception parameter** that represents the type of exception the catch handler can process (DivideByZeroException in this case). When an exception occurs in a try block, the catch handler that executes is the one whose type matches the type of the exception that occurred (i.e., the type in the catch block matches the thrown exception type exactly or is a base class of it). If an exception parameter includes an optional parameter name, the catch handler can use that parameter name to interact with the caught exception in the body of the catch handler, which is delimited by braces ({ and }). A catch handler typically reports the error to the user, logs it to a file, terminates the program gracefully or tries an alternate strategy to accomplish the failed task. In this example, the catch handler simply reports that the user attempted to divide by zero. Then the program prompts the user to enter two new integer values.



#### Common Programming Error 24.1

*It's a syntax error to place code between a try block and its corresponding catch handlers or between its catch handlers.*



#### Common Programming Error 24.2

*Each catch handler can have only a single parameter—specifying a comma-separated list of exception parameters is a syntax error.*



#### Common Programming Error 24.3

*It's a logic error to catch the same type in two different catch handlers following a single try block.*

### *Termination Model of Exception Handling*

If an exception occurs as the result of a statement in a try block, the try block expires (i.e., terminates immediately). Next, the program searches for the first catch handler that can process the type of exception that occurred. The program locates the matching catch by comparing the thrown exception's type to each catch's exception-parameter type until the program finds a match. A match occurs if the types are identical or if the thrown exception's type is a derived class of the exception-parameter type. When a match occurs, the code contained in the matching catch handler executes. When a catch handler finishes processing by reaching its closing right brace (}), the exception is considered handled and the local variables defined within the catch handler (including the catch parameter) go out of scope. Program control does not return to the point at which the exception occurred (known as the **throw point**), because the try block has expired. Rather, control resumes with the first statement (line 44) after the last catch handler following the try block. This is known as the **termination model of exception handling**. [Note: Some languages use the **resumption model of exception handling**, in which, after an exception is handled, control resumes just after the throw point.] As with any other block of code, when a try block terminates, local variables defined in the block go out of scope.



#### Common Programming Error 24.4

*Logic errors can occur if you assume that after an exception is handled, control will return to the first statement after the throw point.*



### Error-Prevention Tip 24.2

*With exception handling, a program can continue executing (rather than terminating) after dealing with a problem. This helps ensure the kind of robust applications that contribute to what's called mission-critical computing or business-critical computing.*

If the try block completes its execution successfully (i.e., no exceptions occur in the try block), then the program ignores the catch handlers and program control continues with the first statement after the last catch following that try block.

If an exception that occurs in a try block has no matching catch handler, or if an exception occurs in a statement that is not in a try block, the function that contains the statement terminates immediately, and the program attempts to locate an enclosing try block in the calling function. This process is called **stack unwinding** and is discussed in Section 24.8.

### *Flow of Program Control When the User Enters a Nonzero Denominator*

Consider the flow of control when the user inputs the numerator 100 and the denominator 7 (i.e., the first two lines of output in Fig. 24.2). In line 13, function `quotient` determines that the denominator does not equal zero, so line 17 performs the division and returns the result (14.2857) to line 35 as a `double`. Program control then continues sequentially from line 35, so line 36 displays the division result—line 37 ends the try block. Because the try block completed successfully and did not throw an exception, the program does not execute the statements contained in the catch handler (lines 38–42), and control continues to line 44 (the first line of code after the catch handler), which prompts the user to enter two more integers.

### *Flow of Program Control When the User Enters a Denominator of Zero*

Now let's consider a more interesting case in which the user inputs the numerator 100 and the denominator 0 (i.e., the third and fourth lines of output in Fig. 24.2). In line 13, `quotient` determines that the denominator equals zero, which indicates an attempt to divide by zero. Line 14 throws an exception, which we represent as an object of class `DivideByZeroException` (Fig. 24.1).

To throw an exception, line 14 uses keyword **throw** followed by an operand that represents the type of exception to throw. Normally, a `throw` statement specifies one operand. (In Section 24.5, we discuss how to use a `throw` statement with no operand.) The operand of a `throw` can be of any type. If the operand is an object, we call it an **exception object**—in this example, the exception object is an object of type `DivideByZeroException`. However, a `throw` operand also can assume other values, such as the value of an expression that does not result in an object (e.g., `throw x > 5`) or the value of an `int` (e.g., `throw 5`). The examples in this chapter focus exclusively on throwing exception objects.



### Common Programming Error 24.5

*Use caution when throwing the result of a conditional expression (`?:`)—promotion rules could cause the value to be of a type different from the one expected. For example, when throwing an `int` or a `double` from the same conditional expression, the `int` is promoted to a `double`. So, a catch handler that catches an `int` would never execute based on such a conditional expression.*

As part of throwing an exception, the `throw` operand is created and used to initialize the parameter in the catch handler, which we discuss momentarily. In this example, the `throw` statement in line 14 creates an object of class `DivideByZeroException`. When line 14 throws the exception, function `quotient` exits immediately. Therefore, line 14 throws the exception before function `quotient` can perform the division in line 17. This is a central characteristic of exception handling: A function should throw an exception *before* the error has an opportunity to occur.

Because we enclosed the call to `quotient` (line 35) in a try block, program control enters the catch handler (lines 38–42) that immediately follows the try block. This catch handler serves as the exception handler for the divide-by-zero exception. In general, when an exception is thrown within a try block, the exception is caught by a catch handler that specifies the type matching the thrown exception. In this program, the catch handler specifies that it catches `DivideByZeroException` objects—this type matches the object type thrown in function `quotient`. Actually, the catch handler catches a reference to the `DivideByZeroException` object created by function `quotient`'s `throw` statement (line 14). The exception object is maintained by the exception-handling mechanism.



#### Performance Tip 24.2

*Catching an exception object by reference eliminates the overhead of copying the object that represents the thrown exception.*



#### Good Programming Practice 24.1

*Associating each type of runtime error with an appropriately named exception object improves program clarity.*

The catch handler's body (lines 40–41) prints the associated error message returned by calling function `what` of base-class `runtime_error`. This function returns the string that the `DivideByZeroException` constructor (lines 12–13 in Fig. 24.1) passed to the `runtime_error` base-class constructor.

## 24.4 When to Use Exception Handling

Exception handling is designed to process **synchronous errors**, which occur when a statement executes. Common examples of these errors are out-of-range array subscripts, arithmetic overflow (i.e., a value outside the representable range of values), division by zero, invalid function parameters and unsuccessful memory allocation (due to lack of memory). Exception handling is not designed to process errors associated with **asynchronous events** (e.g., disk I/O completions, network message arrivals, mouse clicks and keystrokes), which occur in parallel with, and independent of, the program's flow of control.



#### Software Engineering Observation 24.3

*Incorporate your exception-handling strategy into your system from inception. Including effective exception handling after a system has been implemented can be difficult.*



#### Software Engineering Observation 24.4

*Exception handling provides a single, uniform technique for processing problems. This helps programmers on large projects understand each other's error-processing code.*



### Software Engineering Observation 24.5

*Avoid using exception handling as an alternate form of flow of control. These “additional” exceptions can “get in the way” of genuine error-type exceptions.*



### Software Engineering Observation 24.6

*Exception handling enables predefined software components to communicate problems to application-specific components, which can then process the problems in an application-specific manner.*

The exception-handling mechanism also is useful for processing problems that occur when a program interacts with software elements, such as member functions, constructors, destructors and classes. Rather than handling problems internally, such software elements often use exceptions to notify programs when problems occur. This enables you to implement customized error handling for each application.



### Performance Tip 24.3

*When no exceptions occur, exception-handling code incurs little or no performance penalty. Thus, programs that implement exception handling operate more efficiently than do programs that intermix error-handling code with program logic.*



### Software Engineering Observation 24.7

*Functions with common error conditions should return 0 or NULL (or other appropriate values) rather than throw exceptions. A program calling such a function can check the return value to determine success or failure of the function call.*

Complex applications normally consist of predefined software components and application-specific components that use the predefined components. When a predefined component encounters a problem, that component needs a mechanism to communicate the problem to the application-specific component—the predefined component cannot know in advance how each application processes a problem that occurs.

## 24.5 Rethrowing an Exception

It’s possible that an exception handler, upon receiving an exception, might decide either that it cannot process that exception or that it can process the exception only partially. In such cases, the exception handler can defer the exception handling (or perhaps a portion of it) to another exception handler. In either case, you achieve this by **rethrowing the exception** via the statement

```
throw;
```

Regardless of whether a handler can process (even partially) an exception, the handler can rethrow the exception for further processing outside the handler. The next enclosing try block detects the rethrown exception, which a catch handler listed after that enclosing try block attempts to handle.



### Common Programming Error 24.6

*Executing an empty throw statement outside a catch handler calls function **terminate**, which abandons exception processing and terminates the program immediately.*

The program of Fig. 24.3 demonstrates rethrowing an exception. In main's try block (lines 29–34), line 32 calls function `throwException` (lines 8–24). The `throwException` function also contains a try block (lines 11–15), from which the `throw` statement in line 14 throws an instance of standard-library-class `exception`. Function `throwException`'s catch handler (lines 16–21) catches this exception, prints an error message (lines 18–19) and rethrows the exception (line 20). This terminates function `throwException` and returns control to line 32 in the try...catch block in main. The try block terminates (so line 33 does not execute), and the catch handler in main (lines 35–38) catches this exception and prints an error message (line 37). [Note: Since we do not use the exception parameters in the catch handlers of this example, we omit the exception parameter names and specify only the type of exception to catch (lines 16 and 35).]

---

```

1 // Fig. 24.3: Fig24_03.cpp
2 // Demonstrating exception rethrowing.
3 #include <iostream>
4 #include <exception>
5 using namespace std;
6
7 // throw, catch and rethrow exception
8 void throwException()
9 {
10 // throw exception and catch it immediately
11 try
12 {
13 cout << " Function throwException throws an exception\n";
14 throw exception(); // generate exception
15 } // end try
16 catch (exception &) // handle exception
17 {
18 cout << " Exception handled in function throwException"
19 << "\n Function throwException rethrows exception";
20 throw; // rethrow exception for further processing
21 } // end catch
22
23 cout << "This also should not print\n";
24 } // end function throwException
25
26 int main()
27 {
28 // throw exception
29 try
30 {
31 cout << "\nmain invokes function throwException\n";
32 throwException();
33 cout << "This should not print\n";
34 } // end try
35 catch (exception &) // handle exception
36 {
37 cout << "\n\nException handled in main\n";
38 } // end catch

```

---

**Fig. 24.3** | Rethrowing an exception. (Part I of 2.)

```

39
40 cout << "Program control continues after catch in main\n";
41 } // end main

```

```

main invokes function throwException
 Function throwException throws an exception
 Exception handled in function throwException
 Function throwException rethrows exception

Exception handled in main
Program control continues after catch in main

```

**Fig. 24.3** | Rethrowing an exception. (Part 2 of 2.)

## 24.6 Exception Specifications

An optional **exception specification** (also called a **throw list**) enumerates a list of exceptions that a function can throw. For example, consider the function declaration

```

int someFunction(double value)
 throw (ExceptionA, ExceptionB, ExceptionC)
{
 // function body
}

```

In this definition, the exception specification, which begins with keyword **throw** immediately following the closing parenthesis of the function's parameter list, indicates that function `someFunction` can throw exceptions of types `ExceptionA`, `ExceptionB` and `ExceptionC`. A function can throw only exceptions of the types indicated by the specification or exceptions of any type derived from these types. If the function throws an exception that does not belong to a specified type, the exception-handling mechanism calls function **unexpected**, which terminates the program.

A function that does not provide an exception specification can throw any exception. Placing `throw()`—an **empty exception specification**—after a function's parameter list states that the function does not throw exceptions. If the function attempts to throw an exception, function `unexpected` is invoked. Section 24.7 shows how function `unexpected` can be customized by calling function **set\_unexpected**. [Note: Some compilers ignore exception specifications.]



### Common Programming Error 24.7

*Throwing an exception that has not been declared in a function's exception specification causes a call to function `unexpected`.*



### Error-Prevention Tip 24.3

*The compiler will not generate a compilation error if a function contains a `throw` expression for an exception not listed in the function's exception specification. An error occurs only when that function attempts to throw that exception at execution time. To avoid surprises at execution time, carefully check your code to ensure that functions do not throw exceptions not listed in their exception specifications.*



### Software Engineering Observation 24.8

*It's generally recommended that you do not use exception specifications unless you're overriding a base-class member function that already has an exception specification. In this case, the exception specification is required for the derived-class member function.*

## 24.7 Processing Unexpected Exceptions

Function `unexpected` calls the function registered with function `set_unexpected` (defined in header file `<exception>`). If no function has been registered in this manner, function `terminate` is called by default. Cases in which function `terminate` is called include:

1. The exception mechanism cannot find a matching catch for a thrown exception.
2. A destructor attempts to throw an exception during stack unwinding.
3. An attempt is made to rethrow an exception when there is no exception currently being handled.
4. A call to function `unexpected` defaults to calling function `terminate`.

(Section 15.5.1 of the C++ Standard Document discusses several additional cases.) Function `set_terminate` can specify the function to invoke when `terminate` is called. Otherwise, `terminate` calls `abort`, which terminates the program without calling the destructors of any remaining objects of automatic or static storage class. This could lead to resource leaks when a program terminates prematurely.



### Common Programming Error 24.8

*Aborting a program component due to an uncaught exception could leave a resource—such as a file stream or an I/O device—in a state in which other programs are unable to acquire the resource. This is known as a **resource leak**.*

Function `set_terminate` and function `set_unexpected` each return a pointer to the last function called by `terminate` and `unexpected`, respectively (0, the first time each is called). This enables you to save the function pointer so it can be restored later. Functions `set_terminate` and `set_unexpected` take as arguments pointers to functions with void return types and no arguments.

If the last action of a programmer-defined termination function is not to exit a program, function `abort` will be called to end program execution after the other statements of the programmer-defined termination function are executed.

## 24.8 Stack Unwinding

When an exception is thrown but not caught in a particular scope, the function call stack is “unwound,” and an attempt is made to catch the exception in the next outer try...catch block. Unwinding the function call stack means that the function in which the exception was not caught terminates, all local variables in that function are destroyed and control returns to the statement that originally invoked that function. If a try block encloses that statement, an attempt is made to catch the exception. If a try block does not enclose that statement, stack unwinding occurs again. If no catch handler ever catches this exception, function `terminate` is called to terminate the program. The program of Fig. 24.4 demonstrates stack unwinding.



```

1 // Fig. 24.4: Fig24_04.cpp
2 // Demonstrating stack unwinding.
3 #include <iostream>
4 #include <stdexcept>
5 using namespace std;
6
7 // function3 throws runtime error
8 void function3() throw (runtime_error)
9 {
10 cout << "In function 3" << endl;
11
12 // no try block, stack unwinding occurs, return control to function2
13 throw runtime_error("runtime_error in function3"); // no print
14 } // end function3
15
16 // function2 invokes function3
17 void function2() throw (runtime_error)
18 {
19 cout << "function3 is called inside function2" << endl;
20 function3(); // stack unwinding occurs, return control to function1
21 } // end function2
22
23 // function1 invokes function2
24 void function1() throw (runtime_error)
25 {
26 cout << "function2 is called inside function1" << endl;
27 function2(); // stack unwinding occurs, return control to main
28 } // end function1
29
30 // demonstrate stack unwinding
31 int main()
32 {
33 // invoke function1
34 try
35 {
36 cout << "function1 is called inside main" << endl;
37 function1(); // call function1 which throws runtime_error
38 } // end try
39 catch (runtime_error &error) // handle runtime error
40 {
41 cout << "Exception occurred: " << error.what() << endl;
42 cout << "Exception handled in main" << endl;
43 } // end catch
44 } // end main

```

```

function1 is called inside main
function2 is called inside function1
function3 is called inside function2
In function 3
Exception occurred: runtime_error in function3
Exception handled in main

```

**Fig. 24.4** | Stack unwinding.

In `main`, the `try` block (lines 34–38) calls `function1` (lines 24–28). Next, `function1` calls `function2` (lines 17–21), which in turn calls `function3` (lines 8–14). Line 13 of `function3` throws a `runtime_error` object. However, because no `try` block encloses the `throw` statement in line 13, stack unwinding occurs—`function3` terminates at line 13, then returns control to the statement in `function2` that invoked `function3` (i.e., line 20). Because no `try` block encloses line 20, stack unwinding occurs again—`function2` terminates at line 20 and returns control to the statement in `function1` that invoked `function2` (i.e., line 27). Because no `try` block encloses line 27, stack unwinding occurs one more time—`function1` terminates at line 27 and returns control to the statement in `main` that invoked `function1` (i.e., line 37). The `try` block of lines 34–38 encloses this statement, so the first matching catch handler located after this `try` block (line 39–43) catches and processes the exception. Line 41 uses `function what` to display the exception message. Recall that `function what` is a `virtual` function of class `exception` that can be overridden by a derived class to return an appropriate error message.

## 24.9 Constructors, Destructors and Exception Handling

First, let's discuss an issue that we've mentioned but not yet resolved satisfactorily: What happens when an error is detected in a constructor? For example, how should an object's constructor respond when `new` fails because it was unable to allocate required memory for storing that object's internal representation? Because the constructor cannot return a value to indicate an error, we must choose an alternative means of indicating that the object has not been constructed properly. One scheme is to return the improperly constructed object and hope that anyone using it would make appropriate tests to determine that it's in an inconsistent state. Another scheme is to set some variable outside the constructor. The preferred alternative is to require the constructor to throw an exception that contains the error information, thus offering an opportunity for the program to handle the failure.

Before an exception is thrown by a constructor, destructors are called for any member objects built as part of the object being constructed. Destructors are called for every automatic object constructed in a `try` block before an exception is thrown. Stack unwinding is guaranteed to have been completed at the point that an exception handler begins executing. If a destructor invoked as a result of stack unwinding throws an exception, `terminate` is called.

If an object has member objects, and if an exception is thrown before the outer object is fully constructed, then destructors will be executed for the member objects that have been constructed prior to the occurrence of the exception. If an array of objects has been partially constructed when an exception occurs, only the destructors for the constructed objects in the array will be called.

An exception could preclude the operation of code that would normally release a resource (such as memory or a file), thus causing a resource leak. One technique to resolve this problem is to initialize a local object to acquire the resource. When an exception occurs, the destructor for that object will be invoked and can free the resource.



### Error-Prevention Tip 24.4

*When an exception is thrown from the constructor for an object that is created in a new expression, the dynamically allocated memory for that object is released.*

## 24.10 Exceptions and Inheritance

Various exception classes can be derived from a common base class, as we discussed in Section 24.3, when we created class `DivideByZeroException` as a derived class of class `exception`. If a catch handler catches a pointer or reference to an exception object of a base-class type, it also can catch a pointer or reference to all objects of classes publicly derived from that base class—this allows for polymorphic processing of related errors.



### Error-Prevention Tip 24.5

*Using inheritance with exceptions enables an exception handler to catch related errors with concise notation. One approach is to catch each type of pointer or reference to a derived-class exception object individually, but a more concise approach is to catch pointers or references to base-class exception objects instead. Also, catching pointers or references to derived-class exception objects individually is error prone, especially if you forget to test explicitly for one or more of the derived-class pointer or reference types.*

## 24.11 Processing new Failures

The C++ standard specifies that, when operator `new` fails, it throws a `bad_alloc` exception (defined in header file `<new>`). In this section, we present two examples of `new` failing. The first uses the version of `new` that throws a `bad_alloc` exception when `new` fails. The second uses function `set_new_handler` to handle `new` failures. [Note: The examples in Figs. 24.5–24.6 allocate large amounts of dynamic memory, which could cause your computer to become sluggish.]

### *new Throwing bad\_alloc on Failure*

Figure 24.5 demonstrates `new` throwing `bad_alloc` on failure to allocate the requested memory. The `for` statement (lines 16–20) inside the `try` block should loop 50 times and, on each pass, allocate an array of 50,000,000 `double` values. If `new` fails and throws a `bad_alloc` exception, the loop terminates, and the program continues in line 22, where the catch handler catches and processes the exception. Lines 24–25 print the message "Exception occurred:" followed by the message returned from the base-class-exception version of function `what` (i.e., an implementation-defined exception-specific message, such as "Allocation Failure" in Microsoft Visual C++). The output shows that the program performed only four iterations of the loop before `new` failed and threw the `bad_alloc` exception. Your output might differ based on the physical memory, disk space available for virtual memory on your system and the compiler you're using.

---

```

1 // Fig. 24.5: Fig24_05.cpp
2 // Demonstrating standard new throwing bad_alloc when memory
3 // cannot be allocated.
4 #include <iostream>
5 #include <new> // bad_alloc class is defined here
6 using namespace std;
7
```

---

**Fig. 24.5** | `new` throwing `bad_alloc` on failure. (Part I of 2.)

```

8 int main()
9 {
10 double *ptr[50];
11
12 // aim each ptr[i] at a big block of memory
13 try
14 {
15 // allocate memory for ptr[i]; new throws bad_alloc on failure
16 for (int i = 0; i < 50; i++)
17 {
18 ptr[i] = new double[50000000]; // may throw exception
19 cout << "ptr[" << i << "] points to 50,000,000 new doubles\n";
20 } // end for
21 } // end try
22 catch (bad_alloc &memoryAllocationException)
23 {
24 cerr << "Exception occurred: "
25 << memoryAllocationException.what() << endl;
26 } // end catch
27 } // end main

```

```

ptr[0] points to 50,000,000 new doubles
ptr[1] points to 50,000,000 new doubles
ptr[2] points to 50,000,000 new doubles
ptr[3] points to 50,000,000 new doubles
Exception occurred: bad allocation

```

**Fig. 24.5** | new throwing bad\_alloc on failure. (Part 2 of 2.)

### *new* Returning 0 on Failure

In old versions of C++, operator *new* returned 0 when it failed to allocate memory. The C++ standard specifies that standard-compliant compilers can continue to use a version of *new* that returns 0 upon failure. For this purpose, header file `<new>` defines object **nothrow** (of type `nothrow_t`), which is used as follows:

```
double *ptr = new(nothrow) double[50000000];
```

The preceding statement uses the version of *new* that does not throw `bad_alloc` exceptions (i.e., `nothrow`) to allocate an array of 50,000,000 doubles.



### Software Engineering Observation 24.9

*To make programs more robust, use the version of new that throws bad\_alloc exceptions on failure.*

### Handling new Failures Using Function `set_new_handler`

An additional feature for handling *new* failures is function `set_new_handler` (prototyped in standard header file `<new>`). This function takes as its argument a pointer to a function that takes no arguments and returns `void`. This pointer points to the function that will be called if *new* fails. This provides you with a uniform approach to handling all *new* failures, regardless of where a failure occurs in the program. Once `set_new_handler` registers a **new handler** in the program, operator *new* does not throw `bad_alloc` on failure; rather, it defers the error handling to the new-handler function.

If `new` allocates memory successfully, it returns a pointer to that memory. If `new` fails to allocate memory and `set_new_handler` did not register a new-handler function, `new` throws a `bad_alloc` exception. If `new` fails to allocate memory and a new-handler function has been registered, the new-handler function is called. The C++ standard specifies that the new-handler function should perform one of the following tasks:

1. Make more memory available by deleting other dynamically allocated memory (or telling the user to close other applications) and return to operator `new` to attempt to allocate memory again.
2. Throw an exception of type `bad_alloc`.
3. Call function `abort` or `exit` (both found in header file `<cstdlib>`) to terminate the program.

Figure 24.6 demonstrates `set_new_handler`. Function `customNewHandler` (lines 9–13) prints an error message (line 11), then calls `abort` (line 12) to terminate the program. The output shows that the loop iterated four times before `new` failed and invoked function `customNewHandler`. Your output might differ based on the physical memory, disk space available for virtual memory on your system and your compiler.

---

```

1 // Fig. 24.6: Fig24_06.cpp
2 // Demonstrating set_new_handler.
3 #include <iostream>
4 #include <new> // set_new_handler function prototype
5 #include <cstdlib> // abort function prototype
6 using namespace std;
7
8 // handle memory allocation failure
9 void customNewHandler()
10 {
11 cerr << "customNewHandler was called";
12 abort();
13 } // end function customNewHandler
14
15 // using set_new_handler to handle failed memory allocation
16 int main()
17 {
18 double *ptr[50];
19
20 // specify that customNewHandler should be called on
21 // memory allocation failure
22 set_new_handler(customNewHandler);
23
24 // aim each ptr[i] at a big block of memory; customNewHandler will be
25 // called on failed memory allocation
26 for (int i = 0; i < 50; i++)
27 {
28 ptr[i] = new double[5000000]; // may throw exception
29 cout << "ptr[" << i << "] points to 50,000,000 new doubles\n";
30 } // end for
31 } // end main

```

---

**Fig. 24.6** | `set_new_handler` specifying the function to call when `new` fails. (Part I of 2.)

```
ptr[0] points to 50,000,000 new doubles
ptr[1] points to 50,000,000 new doubles
ptr[2] points to 50,000,000 new doubles
ptr[3] points to 50,000,000 new doubles
customNewHandler was called
This application has requested the Runtime to terminate it in an unusual way.
Please contact the application's support team for more information.
```

**Fig. 24.6** | `set_new_handler` specifying the function to call when `new` fails. (Part 2 of 2.)

## 24.12 Class `auto_ptr` and Dynamic Memory Allocation

A common programming practice is to allocate dynamic memory, assign the address of that memory to a pointer, use the pointer to manipulate the memory and deallocate the memory with `delete` when the memory is no longer needed. If an exception occurs after successful memory allocation but before the `delete` statement executes, a memory leak could occur. The C++ standard provides class template `auto_ptr` in header file `<memory>` to deal with this situation.

An object of class `auto_ptr` maintains a pointer to dynamically allocated memory. When an `auto_ptr` object destructor is called (for example, when an `auto_ptr` object goes out of scope), it performs a `delete` operation on its pointer data member. Class template `auto_ptr` provides overloaded operators `*` and `->` so that an `auto_ptr` object can be used just as a regular pointer variable is. Figure 24.9 demonstrates an `auto_ptr` object that points to a dynamically allocated object of class `Integer` (Figs. 24.7–24.8).

---

```
1 // Fig. 24.7: Integer.h
2 // Integer class definition.
3
4 class Integer
5 {
6 public:
7 Integer(int i = 0); // Integer default constructor
8 ~Integer(); // Integer destructor
9 void setInteger(int i); // functions to set Integer
10 int getInteger() const; // function to return Integer
11 private:
12 int value;
13 }; // end class Integer
```

---

**Fig. 24.7** | `Integer` class definition.

---

```
1 // Fig. 24.8: Integer.cpp
2 // Integer member function definitions.
3 #include <iostream>
4 #include "Integer.h"
5 using namespace std;
6
```

---

**Fig. 24.8** | Member function definitions of class `Integer`. (Part 1 of 2.)

---

```

7 // Integer default constructor
8 Integer::Integer(int i)
9 : value(i)
10 {
11 cout << "Constructor for Integer " << value << endl;
12 } // end Integer constructor
13
14 // Integer destructor
15 Integer::~Integer()
16 {
17 cout << "Destructor for Integer " << value << endl;
18 } // end Integer destructor
19
20 // set Integer value
21 void Integer::setInteger(int i)
22 {
23 value = i;
24 } // end function setInteger
25
26 // return Integer value
27 int Integer::getInteger() const
28 {
29 return value;
30 } // end function getInteger

```

---

**Fig. 24.8** | Member function definitions of class `Integer`. (Part 2 of 2.)

Line 15 of Fig. 24.9 creates `auto_ptr` object `ptrToInteger` and initializes it with a pointer to a dynamically allocated `Integer` object that contains the value 7. Line 18 uses the `auto_ptr` overloaded `->` operator to invoke function `setInteger` on the `Integer` object that `ptrToInteger` manages. Line 21 uses the `auto_ptr` overloaded `*` operator to dereference `ptrToInteger`, then uses the dot (`.`) operator to invoke function `getInteger` on the `Integer` object. Like a regular pointer, an `auto_ptr`'s `->` and `*` overloaded operators can be used to access the object to which the `auto_ptr` points.

---

```

1 // Fig. 24.9: Fig24_09.cpp
2 // Demonstrating auto_ptr.
3 #include <iostream>
4 #include <memory>
5 using namespace std;
6
7 #include "Integer.h"
8
9 // use auto_ptr to manipulate Integer object
10 int main()
11 {
12 cout << "Creating an auto_ptr object that points to an Integer\n";
13
14 // "aim" auto_ptr at Integer object
15 auto_ptr< Integer > ptrToInteger(new Integer(7));

```

---

**Fig. 24.9** | `auto_ptr` object manages dynamically allocated memory. (Part 1 of 2.)

```

16
17 cout << "\nUsing the auto_ptr to manipulate the Integer\n";
18 ptrToInteger->setInteger(99); // use auto_ptr to set Integer value
19
20 // use auto_ptr to get Integer value
21 cout << "Integer after setInteger: " << (*ptrToInteger).getInteger()
22 } // end main

```

Creating an auto\_ptr object that points to an Integer  
 Constructor for Integer 7

Using the auto\_ptr to manipulate the Integer  
 Integer after setInteger: 99

Destructor for Integer 99

**Fig. 24.9** | auto\_ptr object manages dynamically allocated memory. (Part 2 of 2.)

Because ptrToInteger is a local automatic variable in main, ptrToInteger is destroyed when main terminates. The auto\_ptr destructor forces a delete of the Integer object pointed to by ptrToInteger, which in turn calls the Integer class destructor. The memory that Integer occupies is released, regardless of how control leaves the block (e.g., by a return statement or by an exception). Most importantly, using this technique can prevent memory leaks. For example, suppose a function returns a pointer aimed at some object. Unfortunately, the function caller that receives this pointer might not delete the object, thus resulting in a memory leak. However, if the function returns an auto\_ptr to the object, the object will be deleted automatically when the auto\_ptr object's destructor gets called.

Only one auto\_ptr at a time can own a dynamically allocated object and the object cannot be an array. By using its overloaded assignment operator or copy constructor, an auto\_ptr can transfer ownership of the dynamic memory it manages. The last auto\_ptr object that maintains the pointer to the dynamic memory will delete the memory. This makes auto\_ptr an ideal mechanism for returning dynamically allocated memory to client code. When the auto\_ptr goes out of scope in the client code, the auto\_ptr's destructor deletes the dynamic memory.



### Common Programming Error 24.9


*Because auto\_ptr objects transfer ownership of memory when they are copied, they cannot be used with Standard Library container classes like vector. Container classes often make copies of objects. This causes ownership of a container element to be transferred to another object, which might then be accidentally deleted when the copy goes out of scope. The Boost.Smart\_ptr library provides memory management features similar auto\_ptr that can be used with containers.*

## 24.13 Standard Library Exception Hierarchy

Experience has shown that exceptions fall nicely into a number of categories. The C++ Standard Library includes a hierarchy of exception classes, some of which are shown in Fig. 24.10. As we first discussed in Section 24.3, this hierarchy is headed by base-class ex-



ception (defined in header file `<exception>`), which contains virtual function `what`, which derived classes can override to issue appropriate error messages.



**Fig. 24.10** | Some of the Standard Library exception classes.

Immediate derived classes of base-class `exception` include `runtime_error` and `logic_error` (both defined in header `<stdexcept>`), each of which has several derived classes. Also derived from `exception` are the exceptions thrown by C++ operators—for example, `bad_alloc` is thrown by `new` (Section 24.11), `bad_cast` is thrown by `dynamic_cast` (Chapter 21) and `bad_typeid` is thrown by `typeid` (Chapter 21). Including `bad_exception` in the throw list of a function means that, if an unexpected exception occurs, function `unexpected` can throw `bad_exception` rather than terminating the program's execution (by default) or calling another function specified by `set_unexpected`.



### Common Programming Error 24.10

*Placing a catch handler that catches a base-class object before a catch that catches an object of a class derived from that base class is a logic error. The base-class catch catches all objects of classes derived from that base class, so the derived-class catch will never execute.*

Class `logic_error` is the base class of several standard exception classes that indicate errors in program logic. For example, class `invalid_argument` indicates that an invalid argument was passed to a function. (Proper coding can, of course, prevent invalid arguments from reaching a function.) Class `length_error` indicates that a length larger than the maximum size allowed for the object being manipulated was used for that object. Class `out_of_range` indicates that a value, such as a subscript into an array, exceeded its allowed range of values.

Class `runtime_error`, which we used briefly in Section 24.8, is the base class of several other standard exception classes that indicate execution-time errors. For example, class `overflow_error` describes an **arithmetic overflow error** (i.e., the result of an arithmetic operation is larger than the largest number that can be stored in the computer) and class

`underflow_error` describes an **arithmetic underflow error** (i.e., the result of an arithmetic operation is smaller than the smallest number that can be stored in the computer).



#### Common Programming Error 24.11

*Exception classes need not be derived from class `exception`, so catching type `exception` is not guaranteed to catch all exceptions a program could encounter.*



#### Error-Prevention Tip 24.6

*To catch all exceptions potentially thrown in a try block, use `catch(...)`. One weakness with catching exceptions in this way is that the type of the caught exception is unknown at compile time. Another weakness is that, without a named parameter, there is no way to refer to the exception object inside the exception handler.*



#### Software Engineering Observation 24.10

*The standard exception hierarchy is a good starting point for creating exceptions. You can build programs that can throw standard exceptions, throw exceptions derived from the standard exceptions or throw your own exceptions not derived from the standard exceptions.*



#### Software Engineering Observation 24.11

*Use `catch(...)` to perform recovery that does not depend on the exception type (e.g., releasing common resources). The exception can be rethrown to alert more specific enclosing catch handlers.*

## 24.14 Other Error-Handling Techniques

We've discussed several ways to deal with exceptional situations prior to this chapter. The following summarizes these and other error-handling techniques:

- Ignore the exception. If an exception occurs, the program might fail as a result of the uncaught exception. This is devastating for commercial software products and special-purpose mission-critical software, but, for software developed for your own purposes, ignoring many kinds of errors is common.
- Abort the program. This, of course, prevents a program from running to completion and producing incorrect results. For many types of errors, this is appropriate, especially for nonfatal errors that enable a program to run to completion (potentially misleading you to think that the program functioned correctly). This strategy is inappropriate for mission-critical applications. Resource issues also are important here—if a program obtains a resource, the program should release that resource before program termination.
- Set error indicators. The problem with this approach is that programs might not check these error indicators at all points at which the errors could be troublesome. Another problem is that the program, after processing the problem, might not clear the error indicators.
- Test for the error condition, issue an error message and call `exit` (in `<cstdlib>`) to pass an appropriate error code to the program's environment.

- Certain kinds of errors have dedicated capabilities for handling them. For example, when operator `new` fails to allocate memory, a `new_handler` function can be called to handle the error. This function can be customized by supplying a function name as the argument to `set_new_handler`, as we discussed in Section 24.11.

## 24.15 Wrap-Up

In this chapter, you learned how to use exception handling to deal with errors in a program. You learned that exception handling enables you to remove error-handling code from the “main line” of the program’s execution. We demonstrated exception handling in the context of a divide-by-zero example. We also showed how to use `try` blocks to enclose code that may throw an exception, and how to use catch handlers to deal with exceptions that may arise. You learned how to throw and rethrow exceptions, and how to handle the exceptions that occur in constructors. The chapter continued with discussions of processing new failures, dynamic memory allocation with class `auto_ptr` and the standard library exception hierarchy.

## Summary

### *Section 24.1 Introduction*

- An exception is an indication of a problem that occurs during a program’s execution.
- Exception handling enables you to create programs that can resolve problems that occur at execution time—often allowing programs to continue executing as if no problems had been encountered. More severe problems may require a program to notify the user of the problem before terminating in a controlled manner.

### *Section 24.2 Exception-Handling Overview*

- Exception handling enables you to remove error-handling code from the “main line” of the program’s execution, which improves program clarity and enhances modifiability.

### *Section 24.3 Example: Handling an Attempt to Divide by Zero*

- Class `exception` is the standard C++ base class for exceptions. Class `exception` provides virtual function `what` that returns an appropriate error message and can be overridden in derived classes.
- Class `runtime_error` (defined in header `<stdexcept>`) is the C++ standard base class for representing runtime errors.
- C++ uses the termination model of exception handling.
- A `try` block consists of keyword `try` followed by braces `{ }` that define a block of code in which exceptions might occur. The `try` block encloses statements that might cause exceptions and statements that should not execute if exceptions occur.
- At least one catch handler must immediately follow a `try` block. Each catch handler specifies an exception parameter that represents the type of exception the catch handler can process.
- If an exception parameter includes an optional parameter name, the catch handler can use that parameter name to interact with a caught exception object.
- The point in the program at which an exception occurs is called the throw point.

- If an exception occurs in a try block, the try block expires and program control transfers to the first catch in which the exception parameter's type matches that of the thrown exception.
- When a try block terminates, local variables defined in the block go out of scope.
- When a try block terminates due to an exception, the program searches for the first catch handler that matches the type of exception that occurred. A match occurs if the types are identical or if the thrown exception's type is a derived class of the exception-parameter type. When a match occurs, the code contained within the matching catch handler executes.
- When a catch handler finishes processing, the catch parameter and local variables defined within the catch handler go out of scope. Any remaining catch handlers that correspond to the try block are ignored, and execution resumes at the first line of code after the try...catch sequence.
- If no exceptions occur in a try block, the program ignores the catch handler(s) for that block. Program execution resumes with the next statement after the try...catch sequence.
- If an exception that occurs in a try block has no matching catch handler, or if an exception occurs in a statement that is not in a try block, the function that contains the statement terminates immediately, and the program attempts to locate an enclosing try block in the calling function. This process is called stack unwinding.
- To throw an exception, use keyword `throw` followed by an operand that represents the type of exception to throw. The operand of a `throw` can be of any type.

#### *Section 24.4 When to Use Exception Handling*

- Exception handling is for synchronous errors, which occur when a statement executes.
- Exception handling is not designed to process errors associated with asynchronous events, which occur in parallel with, and independent of, the program's flow of control.

#### *Section 24.5 Rethrowing an Exception*

- The exception handler can defer the exception handling (or perhaps a portion of it) to another exception handler. In either case, the handler achieves this by rethrowing the exception.
- Common examples of exceptions are out-of-range array subscripts, arithmetic overflow, division by zero, invalid function parameters and unsuccessful memory allocations.

#### *Section 24.6 Exception Specifications*

- An optional exception specification enumerates a list of exceptions that a function can throw. A function can throw only exceptions of the types indicated by the exception specification or exceptions of any type derived from these types. If the function throws an exception that does not belong to a specified type, function `unexpected` is called and the program terminates.
- A function with no exception specification can throw any exception. The empty exception specification `throw()` indicates that a function does not throw exceptions. If a function with an empty exception specification attempts to throw an exception, function `unexpected` is invoked.

#### *Section 24.7 Processing Unexpected Exceptions*

- Function `unexpected` calls the function registered with function `set_unexpected`. If no function has been registered in this manner, function `terminate` is called by default.
- Function `set_terminate` can specify the function to invoke when `terminate` is called. Otherwise, `terminate` calls `abort`, which terminates the program without calling the destructors of objects that are declared `static` and `auto`.
- Functions `set_terminate` and `set_unexpected` each return a pointer to the last function called by `terminate` and `unexpected`, respectively (0, the first time each is called). This enables you to save the function pointer so it can be restored later.

- Functions `set_terminate` and `set_unexpected` take as arguments pointers to functions with `void` return types and no arguments.
- If a programmer-defined termination function does not exit a program, function `abort` will be called after the programmer-defined termination function completes execution.

### *Section 24.8 Stack Unwinding*

- Unwinding the function call stack means that the function in which the exception was not caught terminates, all local variables in that function are destroyed and control returns to the statement that originally invoked that function.

### *Section 24.9 Constructors, Destructors and Exception Handling*

- Exceptions thrown by a constructor cause destructors to be called for any objects built as part of the object being constructed before the exception is thrown.
- Each automatic object constructed in a `try` block is destructed before an exception is thrown.
- Stack unwinding completes before an exception handler begins executing.
- If a destructor invoked as a result of stack unwinding throws an exception, `terminate` is called.
- If an object has member objects, and if an exception is thrown before the outer object is fully constructed, then destructors will be executed for the member objects that have been constructed before the exception occurs.
- If an array of objects has been partially constructed when an exception occurs, only the destructors for the constructed array element objects will be called.
- When an exception is thrown from the constructor for an object that is created in a `new` expression, the dynamically allocated memory for that object is released.

### *Section 24.10 Exceptions and Inheritance*

- If a catch handler catches a pointer or reference to an exception object of a base-class type, it also can catch a pointer or reference to all objects of classes derived publicly from that base class—this allows for polymorphic processing of related errors.

### *Section 24.11 Processing new Failures*

- The C++ standard document specifies that, when operator `new` fails, it throws a `bad_alloc` exception (defined in header file `<new>`).
- Function `set_new_handler` takes as its argument a pointer to a function that takes no arguments and returns `void`. This pointer points to the function that will be called if `new` fails.
- Once `set_new_handler` registers a new handler in the program, operator `new` does not throw `bad_alloc` on failure; rather, it defers the error handling to the new-handler function.
- If `new` allocates memory successfully, it returns a pointer to that memory.
- If an exception occurs after successful memory allocation but before the `delete` statement executes, a memory leak could occur.

### *Section 24.12 Class `auto_ptr` and Dynamic Memory Allocation*

- The C++ Standard Library provides class template `auto_ptr` to deal with memory leaks.
- An object of class `auto_ptr` maintains a pointer to dynamically allocated memory. An `auto_ptr` object's destructor performs a `delete` operation on the `auto_ptr`'s pointer data member.
- Class template `auto_ptr` provides overloaded operators `*` and `->` so that an `auto_ptr` object can be used just as a regular pointer variable is. An `auto_ptr` also transfers ownership of the dynamic memory it manages via its copy constructor and overloaded assignment operator.

### Section 24.13 Standard Library Exception Hierarchy

- The C++ Standard Library includes a hierarchy of exception classes. This hierarchy is headed by base-class exception.
- Immediate derived classes of base class exception include `runtime_error` and `logic_error` (both defined in header `<stdexcept>`), each of which has several derived classes.
- Several operators throw standard exceptions—operator `new` throws `bad_alloc`, operator `dynamic_cast` throws `bad_cast` and operator `typeid` throws `bad_typeid`.
- Including `bad_exception` in the throw list of a function means that, if an unexpected exception occurs, function `unexpected` can throw `bad_exception` rather than terminating the program's execution or calling another function specified by `set_unexpected`.

## Terminology

abort function 901  
 arithmetic overflow error 910  
 arithmetic underflow error 911  
 asynchronous event 897  
`auto_ptr` class template 907  
`bad_alloc` exception 904  
`bad_cast` exception 910  
`bad_exception` exception 910  
`bad_typeid` exception 910  
 catch handler 894  
 catch keyword 895  
 empty exception specification 900  
 exception 890  
 exception class 892  
 exception handler 894  
 exception handling 890  
`<exception>` header file 892  
 exception object 896  
 exception parameter 895  
 exception specification 900  
 fault-tolerant program 890  
`invalid_argument` exception 910  
`length_error` exception 910  
`logic_error` exception 910  
`<memory>` header file 907  
 new handler 905

nothrow object 905  
`out_of_range` exception 910  
`overflow_error` exception 910  
 resource leak 901  
 resumption model of exception handling 895  
 rethrowing the exception 898  
 robust program 890  
`runtime_error` exception 892  
`set_new_handler` function 904  
`set_terminate` function 901  
`set_unexpected` function 900  
 stack unwinding 896  
`<stdexcept>` header file 892  
 synchronous error 897  
 terminate function 898  
 termination model of exception handling 895  
 throw 896  
 throws an exception 894  
 throw keyword 896  
 throw list 900  
 throw point 895  
 try block 894  
 try keyword 894  
`underflow_error` exception 911  
 unexpected function 900  
 what virtual function of class exception 892

## Self-Review Exercises

- 24.1** List five common examples of exceptions.
- 24.2** Give several reasons why exception-handling techniques should not be used for conventional program control.
- 24.3** Why are exceptions appropriate for dealing with errors produced by library functions?
- 24.4** What's a "resource leak"?
- 24.5** If no exceptions are thrown in a try block, where does control proceed to after the try block completes execution?

- 24.6** What happens if an exception is thrown outside a try block?
- 24.7** Give a key advantage and a key disadvantage of using `catch(...)`.
- 24.8** What happens if no catch handler matches the type of a thrown object?
- 24.9** What happens if several handlers match the type of the thrown object?
- 24.10** Why would you specify a base-class type as the type of a catch handler, then throw objects of derived-class types?
- 24.11** Suppose a catch handler with a precise match to an exception object type is available. Under what circumstances might a different handler be executed for exception objects of that type?
- 24.12** Must throwing an exception cause program termination?
- 24.13** What happens when a catch handler throws an exception?
- 24.14** What does the statement `throw;` do?
- 24.15** How do you restrict the exception types that a function can throw?
- 24.16** What happens if a function throws an exception of a type not allowed by the exception specification for the function?
- 24.17** What happens to the automatic objects that have been constructed in a try block when that block throws an exception?

## Answers to Self-Review Exercises

- 24.1** Insufficient memory to satisfy a new request, array subscript out of bounds, arithmetic overflow, division by zero, invalid function parameters.
- 24.2** (a) Exception handling is designed to handle infrequently occurring situations that often result in program termination, so compiler writers are not required to implement exception handling to perform optimally. (b) Flow of control with conventional control structures generally is clearer and more efficient than with exceptions. (c) Problems can occur because the stack is unwound when an exception occurs and resources allocated prior to the exception might not be freed. (d) The “additional” exceptions make it more difficult for you to handle the larger number of exception cases.
- 24.3** It’s unlikely that a library function will perform error processing that will meet the unique needs of all users.
- 24.4** A program that terminates abruptly could leave a resource in a state in which other programs would not be able to acquire the resource, or the program itself might not be able to reacquire a “leaked” resource.
- 24.5** The exception handlers (in the catch handlers) for that try block are skipped, and the program resumes execution after the last catch handler.
- 24.6** An exception thrown outside a try block causes a call to `terminate`.
- 24.7** The form `catch(...)` catches any type of exception thrown in a try block. An advantage is that all possible exceptions will be caught. A disadvantage is that the catch has no parameter, so it cannot reference information in the thrown object and cannot know the cause of the exception.
- 24.8** This causes the search for a match to continue in the next enclosing try block if there is one. As this process continues, it might eventually be determined that there is no handler in the program that matches the type of the thrown object; in this case, `terminate` is called, which by default calls `abort`. An alternative `terminate` function can be provided as an argument to `set_terminate`.
- 24.9** The first matching exception handler after the try block is executed.

- 24.10 This is a nice way to catch related types of exceptions.
- 24.11 A base-class handler would catch objects of all derived-class types.
- 24.12 No, but it does terminate the block in which the exception is thrown.
- 24.13 The exception will be processed by a catch handler (if one exists) associated with the try block (if one exists) enclosing the catch handler that caused the exception.
- 24.14 It rethrows the exception if it appears in a catch handler; otherwise, function `unexpected` is called.
- 24.15 Provide an exception specification listing the exception types that the function can throw.
- 24.16 Function `unexpected` is called.
- 24.17 The try block expires, causing destructors to be called for each of these objects.

## Exercises

24.18 List various exceptional conditions that have occurred throughout this text. List as many additional exceptional conditions as you can. For each of these exceptions, describe briefly how a program typically would handle the exception, using the exception-handling techniques discussed in this chapter. Some typical exceptions are division by zero, arithmetic overflow, array subscript out of bounds, exhaustion of the free store, etc.

24.19 Under what circumstances would you not provide a parameter name when defining the type of the object that will be caught by a handler?

24.20 A program contains the statement

```
throw;
```

Where would you normally expect to find such a statement? What if that statement appeared in a different part of the program?

24.21 Compare and contrast exception handling with the various other error-processing schemes discussed in the text.

24.22 Why should exceptions not be used as an alternate form of program control?

24.23 Describe a technique for handling related exceptions.

24.24 (*Throwing Exceptions from a catch*) Suppose a program throws an exception and the appropriate exception handler begins executing. Now suppose that the exception handler itself throws the same exception. Does this create infinite recursion? Write a program to check your observation.

24.25 (*Catching Derived-Class Exceptions*) Use inheritance to create various derived classes of `runtime_error`. Then show that a catch handler specifying the base class can catch derived-class exceptions.

24.26 (*Throwing the Result of a Conditional Expression*) Throw the result of a conditional expression that returns either a `double` or an `int`. Provide an `int` catch handler and a `double` catch handler. Show that only the `double` catch handler executes, regardless of whether the `int` or the `double` is returned.

24.27 (*Local Variable Destructors*) Write a program illustrating that all destructors for objects constructed in a block are called before an exception is thrown from that block.

24.28 (*Member Object Destructors*) Write a program illustrating that member object destructors are called for only those member objects that were constructed before an exception occurred.

24.29 (*Catching All Exceptions*) Write a program that demonstrates several exception types being caught with the `catch(...)` exception handler.



**24.30** (*Order of Exception Handlers*) Write a program illustrating that the order of exception handlers is important. The first matching handler is the one that executes. Attempt to compile and run your program two different ways to show that two different handlers execute with two different effects.

**24.31** (*Constructors Throwing Exceptions*) Write a program that shows a constructor passing information about constructor failure to an exception handler after a try block.

**24.32** (*Rethrowing Exceptions*) Write a program that illustrates rethrowing an exception.

**24.33** (*Uncaught Exceptions*) Write a program that illustrates that a function with its own try block does not have to catch every possible error generated within the try. Some exceptions can slip through to, and be handled in, outer scopes.

**24.34** (*Stack Unwinding*) Write a program that throws an exception from a deeply nested function and still has the catch handler following the try block enclosing the call chain catch the exception.

# Operator Precedence Charts

Operators are shown in decreasing order of precedence from top to bottom (Figs. A.1–A.2).

| C Operator | Type                                 | Associativity |
|------------|--------------------------------------|---------------|
| ()         | parentheses (function call operator) | left to right |
| []         | array subscript                      |               |
| .          | member selection via object          |               |
| ->         | member selection via pointer         |               |
| ++         | unary postincrement                  |               |
| --         | unary postdecrement                  | right to left |
| ++         | unary preincrement                   |               |
| --         | unary predecrement                   |               |
| +          | unary plus                           |               |
| -          | unary minus                          |               |
| !          | unary logical negation               |               |
| ~          | unary bitwise complement             |               |
| ( type )   | C-style unary cast                   |               |
| *          | dereference                          |               |
| &          | address                              |               |
| sizeof     | determine size in bytes              | left to right |
| *          | multiplication                       |               |
| /          | division                             |               |
| %          | modulus                              | left to right |
| +          | addition                             |               |
| -          | subtraction                          | left to right |
| <<         | bitwise left shift                   |               |
| >>         | bitwise right shift                  | left to right |
| <          | relational less than                 |               |
| <=         | relational less than or equal to     |               |
| >          | relational greater than              |               |
| >=         | relational greater than or equal to  |               |

**Fig. A.1** | C operator precedence chart. (Part 1 of 2.)

| C Operator | Type                            | Associativity |
|------------|---------------------------------|---------------|
| ==         | relational is equal to          | left to right |
| !=         | relational is not equal to      |               |
| &          | bitwise AND                     | left to right |
| ^          | bitwise exclusive OR            | left to right |
|            | bitwise inclusive OR            | left to right |
| &&         | logical AND                     | left to right |
|            | logical OR                      | left to right |
| ?:         | ternary conditional             | right to left |
| =          | assignment                      | right to left |
| +=         | addition assignment             |               |
| -=         | subtraction assignment          |               |
| *=         | multiplication assignment       |               |
| /=         | division assignment             |               |
| %=         | modulus assignment              |               |
| &=         | bitwise AND assignment          |               |
| ^=         | bitwise exclusive OR assignment |               |
| =          | bitwise inclusive OR assignment |               |
| <<=        | bitwise left shift assignment   |               |
| >>=        | bitwise right shift with sign   |               |
| ,          | comma                           | left to right |

**Fig. A.1** | C operator precedence chart. (Part 2 of 2.)

| C++ Operator           | Type                                 | Associativity |
|------------------------|--------------------------------------|---------------|
| ::                     | binary scope resolution              | left to right |
| ::                     | unary scope resolution               |               |
| ()                     | parentheses (function call operator) | left to right |
| []                     | array subscript                      |               |
| .                      | member selection via object          |               |
| ->                     | member selection via pointer         |               |
| ++                     | unary postincrement                  |               |
| --                     | unary postdecrement                  |               |
| typeid                 | runtime type information             |               |
| dynamic_cast<type>     | runtime type-checked cast            |               |
| static_cast<type>      | compile-time type-checked cast       |               |
| reinterpret_cast<type> | cast for nonstandard conversions     |               |
| const_cast<type>       | cast away const-ness                 |               |

**Fig. A.2** | C++ operator precedence chart. (Part 1 of 3.)

| C++ Operator    | Type                                | Associativity |
|-----------------|-------------------------------------|---------------|
| ++              | unary preincrement                  | right to left |
| --              | unary predecrement                  |               |
| +               | unary plus                          |               |
| -               | unary minus                         |               |
| !               | unary logical negation              |               |
| ~               | unary bitwise complement            |               |
| ( <i>type</i> ) | C-style unary cast                  |               |
| sizeof          | determine size in bytes             |               |
| &               | address                             |               |
| *               | dereference                         |               |
| new             | dynamic memory allocation           |               |
| new[]           | dynamic array allocation            |               |
| delete          | dynamic memory deallocation         |               |
| delete[]        | dynamic array deallocation          |               |
| .*              | pointer to member via object        | left to right |
| ->*             | pointer to member via pointer       |               |
| *               | multiplication                      | left to right |
| /               | division                            |               |
| %               | modulus                             |               |
| +               | addition                            | left to right |
| -               | subtraction                         |               |
| <<              | bitwise left shift                  | left to right |
| >>              | bitwise right shift                 |               |
| <               | relational less than                | left to right |
| <=              | relational less than or equal to    |               |
| >               | relational greater than             |               |
| >=              | relational greater than or equal to |               |
| ==              | relational is equal to              | left to right |
| !=              | relational is not equal to          |               |
| &               | bitwise AND                         | left to right |
| ^               | bitwise exclusive OR                | left to right |
|                 | bitwise inclusive OR                | left to right |
| &&              | logical AND                         | left to right |
|                 | logical OR                          | left to right |
| ?:              | ternary conditional                 | right to left |

**Fig. A.2** | C++ operator precedence chart. (Part 2 of 3.)

| C++ Operator | Type                            | Associativity |
|--------------|---------------------------------|---------------|
| =            | assignment                      | right to left |
| +=           | addition assignment             |               |
| -=           | subtraction assignment          |               |
| *=           | multiplication assignment       |               |
| /=           | division assignment             |               |
| %=           | modulus assignment              |               |
| &=           | bitwise AND assignment          |               |
| ^=           | bitwise exclusive OR assignment |               |
| =            | bitwise inclusive OR assignment |               |
| <<=          | bitwise left shift assignment   |               |
| >>=          | bitwise right shift with sign   |               |
| ,            | comma                           | left to right |

**Fig. A.2**    C++ operator precedence chart. (Part 3 of 3.)

## ASCII Character Set

| ASCII character set |     |     |     |     |     |     |     |     |     |     |
|---------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
|                     | 0   | 1   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   |
| 0                   | nul | soh | stx | etx | eot | enq | ack | bel | bs  | ht  |
| 1                   | lf  | vt  | ff  | cr  | so  | si  | dle | dc1 | dc2 | dc3 |
| 2                   | dc4 | nak | syn | etb | can | em  | sub | esc | fs  | gs  |
| 3                   | rs  | us  | sp  | !   | "   | #   | \$  | %   | &   | '   |
| 4                   | (   | )   | *   | +   | ,   | -   | .   | /   | 0   | 1   |
| 5                   | 2   | 3   | 4   | 5   | 6   | 7   | 8   | 9   | :   | ;   |
| 6                   | <   | =   | >   | ?   | @   | A   | B   | C   | D   | E   |
| 7                   | F   | G   | H   | I   | J   | K   | L   | M   | N   | O   |
| 8                   | P   | Q   | R   | S   | T   | U   | V   | W   | X   | Y   |
| 9                   | Z   | [   | \   | ]   | ^   | _   | '   | a   | b   | c   |
| 10                  | d   | e   | f   | g   | h   | i   | j   | k   | l   | m   |
| 11                  | n   | o   | p   | q   | r   | s   | t   | u   | v   | w   |
| 12                  | x   | y   | z   | {   |     | }   | ~   | del |     |     |

**Fig. B.1** | ASCII Character Set.

The digits at the left of the table are the left digits of the decimal equivalent (0–127) of the character code, and the digits at the top of the table are the right digits of the character code. For example, the character code for “F” is 70, and the character code for “&” is 38.

# C

## Number Systems

*Here are only numbers ratified.*

—William Shakespeare

### Objectives

In this appendix, you'll learn:

- To understand basic number systems concepts such as base, positional value and symbol value.
- To understand how to work with numbers represented in the binary, octal and hexadecimal number systems
- To be able to abbreviate binary numbers as octal numbers or hexadecimal numbers.
- To be able to convert octal numbers and hexadecimal numbers to binary numbers.
- To be able to convert back and forth between decimal numbers and their binary, octal and hexadecimal equivalents.
- To understand binary arithmetic and how negative binary numbers are represented using two's complement notation.





- C.1** Introduction
- C.2** Abbreviating Binary Numbers as Octal and Hexadecimal Numbers
- C.3** Converting Octal and Hexadecimal Numbers to Binary Numbers
- C.4** Converting from Binary, Octal or Hexadecimal to Decimal
- C.5** Converting from Decimal to Binary, Octal or Hexadecimal
- C.6** Negative Binary Numbers: Two's Complement Notation

*Summary | Terminology | Self-Review Exercises | Answers to Self-Review Exercises | Exercises*

## C.1 Introduction

In this appendix, we introduce the key number systems that programmers use, especially when they are working on software projects that require close interaction with machine-level hardware. Projects like this include operating systems, computer networking software, compilers, database systems and applications requiring high performance.

When we write an integer such as 227 or -63 in a program, the number is assumed to be in the **decimal (base 10) number system**. The **digits** in the decimal number system are 0, 1, 2, 3, 4, 5, 6, 7, 8 and 9. The lowest digit is 0 and the highest digit is 9—one less than the **base** of 10. Internally, computers use the **binary (base 2) number system**. The binary number system has only two digits, namely 0 and 1. Its lowest digit is 0 and its highest digit is 1—one less than the base of 2.

As we'll see, binary numbers tend to be much longer than their decimal equivalents. Programmers who work in assembly languages and in high-level languages like C that enable programmers to reach down to the machine level, find it cumbersome to work with binary numbers. So two other number systems—the **octal number system (base 8)** and the **hexadecimal number system (base 16)**—are popular primarily because they make it convenient to abbreviate binary numbers.

In the octal number system, the digits range from 0 to 7. Because both the binary number system and the octal number system have fewer digits than the decimal number system, their digits are the same as the corresponding digits in decimal.

The hexadecimal number system poses a problem because it requires 16 digits—a lowest digit of 0 and a highest digit with a value equivalent to decimal 15 (one less than the base of 16). By convention, we use the letters A through F to represent the hexadecimal digits corresponding to decimal values 10 through 15. Thus in hexadecimal we can have numbers like 876 consisting solely of decimal-like digits, numbers like 8A55F consisting of digits and letters and numbers like FFE consisting solely of letters. Occasionally, a hexadecimal number spells a common word such as FACE or FEED—this can appear strange to programmers accustomed to working with numbers. The digits of the binary, octal, decimal and hexadecimal number systems are summarized in Figs. C.1–C.2.

Each of these number systems uses **positional notation**—each position in which a digit is written has a different **positional value**. For example, in the decimal number 937 (the 9, the 3 and the 7 are referred to as **symbol values**), we say that the 7 is written in the ones position, the 3 is written in the tens position and the 9 is written in the hundreds position. Each of these positions is a power of the base (base 10) and these powers begin at 0 and increase by 1 as we move left in the number (Fig. C.3).



| Binary digit | Octal digit | Decimal digit | Hexadecimal digit       |
|--------------|-------------|---------------|-------------------------|
| 0            | 0           | 0             | 0                       |
| 1            | 1           | 1             | 1                       |
|              | 2           | 2             | 2                       |
|              | 3           | 3             | 3                       |
|              | 4           | 4             | 4                       |
|              | 5           | 5             | 5                       |
|              | 6           | 6             | 6                       |
|              | 7           | 7             | 7                       |
|              |             | 8             | 8                       |
|              |             | 9             | 9                       |
|              |             |               | A (decimal value of 10) |
|              |             |               | B (decimal value of 11) |
|              |             |               | C (decimal value of 12) |
|              |             |               | D (decimal value of 13) |
|              |             |               | E (decimal value of 14) |
|              |             |               | F (decimal value of 15) |

**Fig. C.1** | Digits of the binary, octal, decimal and hexadecimal number systems.

| Attribute     | Binary | Octal | Decimal | Hexadecimal |
|---------------|--------|-------|---------|-------------|
| Base          | 2      | 8     | 10      | 16          |
| Lowest digit  | 0      | 0     | 0       | 0           |
| Highest digit | 1      | 7     | 9       | F           |

**Fig. C.2** | Comparing the binary, octal, decimal and hexadecimal number systems.

| Positional values in the decimal number system |                 |                 |                 |
|------------------------------------------------|-----------------|-----------------|-----------------|
| Decimal digit                                  | 9               | 3               | 7               |
| Position name                                  | Hundreds        | Tens            | Ones            |
| Positional value                               | 100             | 10              | 1               |
| Positional value as a power of the base (10)   | 10 <sup>2</sup> | 10 <sup>1</sup> | 10 <sup>0</sup> |

**Fig. C.3** | Positional values in the decimal number system.

For longer decimal numbers, the next positions to the left would be the thousands position (10 to the 3rd power), the ten-thousands position (10 to the 4th power), the hundred-thousands position (10 to the 5th power), the millions position (10 to the 6th power), the ten-millions position (10 to the 7th power) and so on.

In the binary number 101, the rightmost 1 is written in the ones position, the 0 is written in the twos position and the leftmost 1 is written in the fours position. Each position is a power of the base (base 2) and these powers begin at 0 and increase by 1 as we move left in the number (Fig. C.4). So,  $101 = 1 * 2^2 + 0 * 2^1 + 1 * 2^0 = 4 + 0 + 1 = 5$ .

| Positional values in the binary number system |       |       |       |
|-----------------------------------------------|-------|-------|-------|
| Binary digit                                  | 1     | 0     | 1     |
| Position name                                 | Fours | Twos  | Ones  |
| Positional value                              | 4     | 2     | 1     |
| Positional value as a power of the base (2)   | $2^2$ | $2^1$ | $2^0$ |

Fig. C.4 | Positional values in the binary number system.

For longer binary numbers, the next positions to the left would be the eights position (2 to the 3rd power), the sixteens position (2 to the 4th power), the thirty-twos position (2 to the 5th power), the sixty-fours position (2 to the 6th power) and so on.

In the octal number 425, we say that the 5 is written in the ones position, the 2 is written in the eights position and the 4 is written in the sixty-fours position. Each of these positions is a power of the base (base 8) and that these powers begin at 0 and increase by 1 as we move left in the number (Fig. C.5).

| Positional values in the octal number system |             |        |       |
|----------------------------------------------|-------------|--------|-------|
| Decimal digit                                | 4           | 2      | 5     |
| Position name                                | Sixty-fours | Eights | Ones  |
| Positional value                             | 64          | 8      | 1     |
| Positional value as a power of the base (8)  | $8^2$       | $8^1$  | $8^0$ |

Fig. C.5 | Positional values in the octal number system.

For longer octal numbers, the next positions to the left would be the five-hundred-and-twelves position (8 to the 3rd power), the four-thousand-and-ninety-sixes position (8 to the 4th power), the thirty-two-thousand-seven-hundred-and-sixty-eights position (8 to the 5th power) and so on.

In the hexadecimal number 3DA, we say that the A is written in the ones position, the D is written in the sixteens position and the 3 is written in the two-hundred-and-fifty-sixes position. Each of these positions is a power of the base (base 16) and these powers begin at 0 and increase by 1 as we move left in the number (Fig. C.6).

For longer hexadecimal numbers, the next positions to the left would be the four-thousand-and-ninety-sixes position (16 to the 3rd power), the sixty-five-thousand-five-hundred-and-thirty-sixes position (16 to the 4th power) and so on.

| Positional values in the hexadecimal number system |                             |          |        |
|----------------------------------------------------|-----------------------------|----------|--------|
| Decimal digit                                      | 3                           | D        | A      |
| Position name                                      | Two-hundred-and-fifty-sixes | Sixteens | Ones   |
| Positional value                                   | 256                         | 16       | 1      |
| Positional value as a power of the base (16)       | $16^2$                      | $16^1$   | $16^0$ |

**Fig. C.6** | Positional values in the hexadecimal number system.

## C.2 Abbreviating Binary Numbers as Octal and Hexadecimal Numbers

The main use for octal and hexadecimal numbers in computing is for abbreviating lengthy binary representations. Figure C.7 highlights the fact that lengthy binary numbers can be expressed concisely in number systems with higher bases than the binary number system.

| Decimal number | Binary representation | Octal representation | Hexadecimal representation |
|----------------|-----------------------|----------------------|----------------------------|
| 0              | 0                     | 0                    | 0                          |
| 1              | 1                     | 1                    | 1                          |
| 2              | 10                    | 2                    | 2                          |
| 3              | 11                    | 3                    | 3                          |
| 4              | 100                   | 4                    | 4                          |
| 5              | 101                   | 5                    | 5                          |
| 6              | 110                   | 6                    | 6                          |
| 7              | 111                   | 7                    | 7                          |
| 8              | 1000                  | 10                   | 8                          |
| 9              | 1001                  | 11                   | 9                          |
| 10             | 1010                  | 12                   | A                          |
| 11             | 1011                  | 13                   | B                          |
| 12             | 1100                  | 14                   | C                          |
| 13             | 1101                  | 15                   | D                          |
| 14             | 1110                  | 16                   | E                          |
| 15             | 1111                  | 17                   | F                          |
| 16             | 10000                 | 20                   | 10                         |

**Fig. C.7** | Decimal, binary, octal and hexadecimal equivalents.

A particularly important relationship that both the octal number system and the hexadecimal number system have to the binary system is that the bases of octal and hexadec-

imal (8 and 16 respectively) are powers of the base of the binary number system (base 2). Consider the following 12-digit binary number and its octal and hexadecimal equivalents. See if you can determine how this relationship makes it convenient to abbreviate binary numbers in octal or hexadecimal. The answer follows the numbers.

| Binary number | Octal equivalent | Hexadecimal equivalent |
|---------------|------------------|------------------------|
| 100011010001  | 4321             | 8D1                    |

To see how the binary number converts easily to octal, simply break the 12-digit binary number into groups of three consecutive bits each and write those groups over the corresponding digits of the octal number as follows:

|     |     |     |     |
|-----|-----|-----|-----|
| 100 | 011 | 010 | 001 |
| 4   | 3   | 2   | 1   |

The octal digit you have written under each group of three bits corresponds precisely to the octal equivalent of that 3-digit binary number, as shown in Fig. C.7.

The same kind of relationship can be observed in converting from binary to hexadecimal. Break the 12-digit binary number into groups of four consecutive bits each and write those groups over the corresponding digits of the hexadecimal number as follows:

|      |      |      |
|------|------|------|
| 1000 | 1101 | 0001 |
| 8    | D    | 1    |

The hexadecimal digit you wrote under each group of four bits corresponds precisely to the hexadecimal equivalent of that 4-digit binary number as shown in Fig. C.7.

C.3 Converting Octal and Hexadecimal Numbers to Binary Numbers

In the previous section, we saw how to convert binary numbers to their octal and hexadecimal equivalents by forming groups of binary digits and simply rewriting them as their equivalent octal digit values or hexadecimal digit values. This process may be used in reverse to produce the binary equivalent of a given octal or hexadecimal number.

For example, the octal number 653 is converted to binary simply by writing the 6 as its 3-digit binary equivalent 110, the 5 as its 3-digit binary equivalent 101 and the 3 as its 3-digit binary equivalent 011 to form the 9-digit binary number 110101011.

The hexadecimal number FAD5 is converted to binary simply by writing the F as its 4-digit binary equivalent 1111, the A as its 4-digit binary equivalent 1010, the D as its 4-digit binary equivalent 1101 and the 5 as its 4-digit binary equivalent 0101 to form the 16-digit 1111101011010101.

C.4 Converting from Binary, Octal or Hexadecimal to Decimal

We’re accustomed to working in decimal, and therefore it is often convenient to convert a binary, octal, or hexadecimal number to decimal to get a sense of what the number is “really” worth. Our tables in Section C.1 express the positional values in decimal. To convert a number to decimal from another base, multiply the decimal equivalent of each digit by its positional value and sum these products. For example, the binary number 110101 is converted to decimal 53, as shown in Fig. C.8.

| Converting a binary number to decimal |                                |         |       |       |       |       |
|---------------------------------------|--------------------------------|---------|-------|-------|-------|-------|
| Positional values:                    | 32                             | 16      | 8     | 4     | 2     | 1     |
| Symbol values:                        | 1                              | 1       | 0     | 1     | 0     | 1     |
| Products:                             | 1*32=32                        | 1*16=16 | 0*8=0 | 1*4=4 | 0*2=0 | 1*1=1 |
| Sum:                                  | = 32 + 16 + 0 + 4 + 0 + 1 = 53 |         |       |       |       |       |

**Fig. C.8** | Converting a binary number to decimal.

To convert octal 7614 to decimal 3980, we use the same technique, this time using appropriate octal positional values, as shown in Fig. C.9.

| Converting an octal number to decimal |                             |          |       |       |
|---------------------------------------|-----------------------------|----------|-------|-------|
| Positional values:                    | 512                         | 64       | 8     | 1     |
| Symbol values:                        | 7                           | 6        | 1     | 4     |
| Products                              | 7*512=3584                  | 6*64=384 | 1*8=8 | 4*1=4 |
| Sum:                                  | = 3584 + 384 + 8 + 4 = 3980 |          |       |       |

**Fig. C.9** | Converting an octal number to decimal.

To convert hexadecimal AD3B to decimal 44347, we use the same technique, this time using appropriate hexadecimal positional values, as shown in Fig. C.10.

| Converting a hexadecimal number to decimal |                                  |            |         |        |
|--------------------------------------------|----------------------------------|------------|---------|--------|
| Positional values:                         | 4096                             | 256        | 16      | 1      |
| Symbol values:                             | A                                | D          | 3       | B      |
| Products                                   | A*4096=40960                     | D*256=3328 | 3*16=48 | B*1=11 |
| Sum:                                       | = 40960 + 3328 + 48 + 11 = 44347 |            |         |        |

**Fig. C.10** | Converting a hexadecimal number to decimal.

## C.5 Converting from Decimal to Binary, Octal or Hexadecimal

The **conversions** in Section C.4 follow naturally from the positional notation conventions. Converting from decimal to binary, octal, or hexadecimal also follows these conventions.

Suppose we wish to convert decimal 57 to binary. We begin by writing the positional values of the columns right to left until we reach a column whose positional value is greater than the decimal number. We do not need that column, so we discard it. Thus, we first write:

|                    |    |    |    |   |   |   |   |
|--------------------|----|----|----|---|---|---|---|
| Positional values: | 64 | 32 | 16 | 8 | 4 | 2 | 1 |
|--------------------|----|----|----|---|---|---|---|

Then we discard the column with positional value 64, leaving:

|                    |    |    |   |   |   |   |
|--------------------|----|----|---|---|---|---|
| Positional values: | 32 | 16 | 8 | 4 | 2 | 1 |
|--------------------|----|----|---|---|---|---|

Next we work from the leftmost column to the right. We divide 32 into 57 and observe that there is one 32 in 57 with a remainder of 25, so we write 1 in the 32 column. We divide 16 into 25 and observe that there is one 16 in 25 with a remainder of 9 and write 1 in the 16 column. We divide 8 into 9 and observe that there is one 8 in 9 with a remainder of 1. The next two columns each produce quotients of 0 when their positional values are divided into 1, so we write 0s in the 4 and 2 columns. Finally, 1 into 1 is 1, so we write 1 in the 1 column. This yields:

|                    |    |    |   |   |   |   |
|--------------------|----|----|---|---|---|---|
| Positional values: | 32 | 16 | 8 | 4 | 2 | 1 |
| Symbol values:     | 1  | 1  | 1 | 0 | 0 | 1 |

and thus decimal 57 is equivalent to binary 111001.

To convert decimal 103 to octal, we begin by writing the positional values of the columns until we reach a column whose positional value is greater than the decimal number. We do not need that column, so we discard it. Thus, we first write:

|                    |     |    |   |   |
|--------------------|-----|----|---|---|
| Positional values: | 512 | 64 | 8 | 1 |
|--------------------|-----|----|---|---|

Then we discard the column with positional value 512, yielding:

|                    |    |   |   |
|--------------------|----|---|---|
| Positional values: | 64 | 8 | 1 |
|--------------------|----|---|---|

Next we work from the leftmost column to the right. We divide 64 into 103 and observe that there is one 64 in 103 with a remainder of 39, so we write 1 in the 64 column. We divide 8 into 39 and observe that there are four 8s in 39 with a remainder of 7 and write 4 in the 8 column. Finally, we divide 1 into 7 and observe that there are seven 1s in 7 with no remainder, so we write 7 in the 1 column. This yields:

|                    |    |   |   |
|--------------------|----|---|---|
| Positional values: | 64 | 8 | 1 |
| Symbol values:     | 1  | 4 | 7 |

and thus decimal 103 is equivalent to octal 147.

To convert decimal 375 to hexadecimal, we begin by writing the positional values of the columns until we reach a column whose positional value is greater than the decimal number. We do not need that column, so we discard it. Thus, we first write:

|                    |      |     |    |   |
|--------------------|------|-----|----|---|
| Positional values: | 4096 | 256 | 16 | 1 |
|--------------------|------|-----|----|---|

Then we discard the column with positional value 4096, yielding:

|                    |     |    |   |
|--------------------|-----|----|---|
| Positional values: | 256 | 16 | 1 |
|--------------------|-----|----|---|

Next we work from the leftmost column to the right. We divide 256 into 375 and observe that there is one 256 in 375 with a remainder of 119, so we write 1 in the 256 column. We divide 16 into 119 and observe that there are seven 16s in 119 with a remainder of 7 and write 7 in the 16 column. Finally, we divide 1 into 7 and observe that there are seven 1s in 7 with no remainder, so we write 7 in the 1 column. This yields:

|                    |     |    |   |
|--------------------|-----|----|---|
| Positional values: | 256 | 16 | 1 |
| Symbol values:     | 1   | 7  | 7 |

and thus decimal 375 is equivalent to hexadecimal 177.

## C.6 Negative Binary Numbers: Two's Complement Notation

The discussion so far in this appendix has focused on positive numbers. In this section, we explain how computers represent negative numbers using **two's complement notation**. First we explain how the two's complement of a binary number is formed, then we show why it represents the **negative value** of the given binary number.

Consider a machine with 32-bit integers. Suppose

```
int value = 13;
```

The 32-bit representation of `value` is

```
00000000 00000000 00000000 00001101
```

To form the negative of `value` we first form its **one's complement** by applying C's **bitwise complement operator** (`~`):

```
onesComplementOfValue = ~value;
```

Internally, `~value` is now `value` with each of its bits reversed—ones become zeros and zeros become ones, as follows:

```
value:
00000000 00000000 00000000 00001101
~value (i.e., value's ones complement):
11111111 11111111 11111111 11110010
```

To form the two's complement of `value`, we simply add 1 to `value`'s one's complement. Thus

```
Two's complement of value:
11111111 11111111 11111111 11110011
```

Now if this is in fact equal to  $-13$ , we should be able to add it to binary 13 and obtain a result of 0. Let's try this:

```
00000000 00000000 00000000 00001101
+11111111 11111111 11111111 11110011

00000000 00000000 00000000 00000000
```

The carry bit coming out of the leftmost column is discarded and we indeed get 0 as a result. If we add the one's complement of a number to the number, the result would be all 1s. The key to getting a result of all zeros is that the two's complement is one more than the one's complement. The addition of 1 causes each column to add to 0 with a carry of 1. The carry keeps moving leftward until it is discarded from the leftmost bit, and thus the resulting number is all zeros.

Computers actually perform a subtraction, such as

```
x = a - value;
```

by adding the two's complement of `value` to `a`, as follows:

```
x = a + (~value + 1);
```

Suppose `a` is 27 and `value` is 13 as before. If the two's complement of `value` is actually the negative of `value`, then adding the two's complement of `value` to `a` should produce the result 14. Let's try this:

|                             |                                      |
|-----------------------------|--------------------------------------|
| <code>a</code> (i.e., 27)   | 00000000 00000000 00000000 00011011  |
| <code>+ (~value + 1)</code> | +11111111 11111111 11111111 11110011 |
|                             | -----                                |
|                             | 00000000 00000000 00000000 00001110  |

which is indeed equal to 14.

## Summary

- An integer such as 19 or 227 or -63 in a program is assumed to be in the decimal (base 10) number system. The digits in the decimal number system are 0, 1, 2, 3, 4, 5, 6, 7, 8 and 9. The lowest digit is 0 and the highest digit is 9—one less than the base of 10.
- Internally, computers use the binary (base 2) number system. The binary number system has only two digits, namely 0 and 1. Its lowest digit is 0 and its highest digit is 1—one less than the base of 2.
- The octal number system (base 8) and the hexadecimal number system (base 16) are popular primarily because they make it convenient to abbreviate binary numbers.
- The digits of the octal number system range from 0 to 7.
- The hexadecimal number system poses a problem because it requires 16 digits—a lowest digit of 0 and a highest digit with a value equivalent to decimal 15 (one less than the base of 16). By convention, we use the letters A through F to represent the hexadecimal digits corresponding to decimal values 10 through 15.
- Each number system uses positional notation—each position in which a digit is written has a different positional value.
- A particularly important relationship of both the octal number system and the hexadecimal number system to the binary system is that the bases of octal and hexadecimal (8 and 16 respectively) are powers of the base of the binary number system (base 2).
- To convert an octal to a binary number, replace each octal digit with its three-digit binary equivalent.
- To convert a hexadecimal number to a binary number, simply replace each hexadecimal digit with its four-digit binary equivalent.
- Because we're accustomed to working in decimal, it is convenient to convert a binary, octal or hexadecimal number to decimal to get a sense of the number's "real" worth.
- To convert a number to decimal from another base, multiply the decimal equivalent of each digit by its positional value and sum the products.
- Computers represent negative numbers using two's complement notation.
- To form the negative of a value in binary, first form its one's complement by applying C's bitwise complement operator (~). This reverses the bits of the value. To form the two's complement of a value, simply add one to the value's one's complement.

## Terminology

base 925  
base 2 number system 925

base 8 number system 925  
base 10 number system 925



|                                     |                               |
|-------------------------------------|-------------------------------|
| base 16 number system 925           | negative value 932            |
| binary number system 925            | octal number system 925       |
| bitwise complement operator (~) 932 | one's complement notation 932 |
| conversion 930                      | positional notation 925       |
| decimal number system 925           | positional value 925          |
| digit 925                           | symbol value 925              |
| hexadecimal number system 925       | two's complement notation 932 |

## Self-Review Exercises

- C.1** Fill in the blanks in each of the following statements:
- The bases of the decimal, binary, octal and hexadecimal number systems are \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_ and \_\_\_\_\_ respectively.
  - The positional value of the rightmost digit of any number in either binary, octal, decimal or hexadecimal is always \_\_\_\_\_.
  - The positional value of the digit to the left of the rightmost digit of any number in binary, octal, decimal or hexadecimal is always equal to \_\_\_\_\_.
- C.2** State whether each of the following is *true* or *false*. If *false*, explain why.
- A popular reason for using the decimal number system is that it forms a convenient notation for abbreviating binary numbers simply by substituting one decimal digit per group of four binary bits.
  - The highest digit in any base is one more than the base.
  - The lowest digit in any base is one less than the base.
- C.3** In general, the decimal, octal and hexadecimal representations of a given binary number contain (more/fewer) digits than the binary number contains.
- C.4** The (octal / hexadecimal / decimal) representation of a large binary value is the most concise (of the given alternatives).
- C.5** Fill in the missing values in this chart of positional values for the rightmost four positions in each of the indicated number systems:
- |             |      |     |     |     |
|-------------|------|-----|-----|-----|
| decimal     | 1000 | 100 | 10  | 1   |
| hexadecimal | ...  | 256 | ... | ... |
| binary      | ...  | ... | ... | ... |
| octal       | 512  | ... | 8   | ... |
- C.6** Convert binary 110101011000 to octal and to hexadecimal.
- C.7** Convert hexadecimal FACE to binary.
- C.8** Convert octal 7316 to binary.
- C.9** Convert hexadecimal 4FEC to octal. [*Hint*: First convert 4FEC to binary, then convert that binary number to octal.]
- C.10** Convert binary 1101110 to decimal.
- C.11** Convert octal 317 to decimal.
- C.12** Convert hexadecimal EFD4 to decimal.
- C.13** Convert decimal 177 to binary, to octal and to hexadecimal.
- C.14** Show the binary representation of decimal 417. Then show the one's complement of 417 and the two's complement of 417.
- C.15** What is the result when a number and its two's complement are added to each other?

## Answers to Self-Review Exercises

**C.1** a) 10, 2, 8, 16. b) 1 (the base raised to the zero power). c) The base of the number system.

**C.2** a) False. Hexadecimal does this. b) False. The highest digit in any base is one less than the base. c) False. The lowest digit in any base is zero.

**C.3** Fewer.

**C.4** Hexadecimal.

|            |             |      |     |    |   |
|------------|-------------|------|-----|----|---|
| <b>C.5</b> | decimal     | 1000 | 100 | 10 | 1 |
|            | hexadecimal | 4096 | 256 | 16 | 1 |
|            | binary      | 8    | 4   | 2  | 1 |
|            | octal       | 512  | 64  | 8  | 1 |

**C.6** Octal 6530; Hexadecimal D58.

**C.7** Binary 1111 1010 1100 1110.

**C.8** Binary 111 011 001 110.

**C.9** Binary 0 100 111 111 101 100; Octal 47754.

**C.10** Decimal  $2+4+8+32+64=110$ .

**C.11** Decimal  $7+1*8+3*64=7+8+192=207$ .

**C.12** Decimal  $4+13*16+15*256+14*4096=61396$ .

**C.13** Decimal 177

to binary:

256 128 64 32 16 8 4 2 1  
 128 64 32 16 8 4 2 1  
 $(1*128)+(0*64)+(1*32)+(1*16)+(0*8)+(0*4)+(0*2)+(1*1)$   
 10110001

to octal:

512 64 8 1  
 64 8 1  
 $(2*64)+(6*8)+(1*1)$   
 261

to hexadecimal:

256 16 1  
 16 1  
 $(11*16)+(1*1)$   
 $(B*16)+(1*1)$   
 B1

**C.14** Binary:

512 256 128 64 32 16 8 4 2 1  
 256 128 64 32 16 8 4 2 1  
 $(1*256)+(1*128)+(0*64)+(1*32)+(0*16)+(0*8)+(0*4)+(0*2)+(1*1)$   
 110100001

One's complement: 001011110

Two's complement: 001011111

Check: Original binary number + its two's complement

```

110100001
001011111

000000000

```

**C.15**    Zero.

## Exercises

**C.16**    Some people argue that many of our calculations would be easier in the base 12 number system because 12 is divisible by so many more numbers than 10 (for base 10). What is the lowest digit in base 12? What would be the highest symbol for the digit in base 12? What are the positional values of the rightmost four positions of any number in the base 12 number system?

**C.17**    Complete the following chart of positional values for the rightmost four positions in each of the indicated number systems:

|         |      |     |     |     |
|---------|------|-----|-----|-----|
| decimal | 1000 | 100 | 10  | 1   |
| base 6  | ...  | ... | 6   | ... |
| base 13 | ...  | 169 | ... | ... |
| base 3  | 27   | ... | ... | ... |

**C.18**    Convert binary 100101111010 to octal and to hexadecimal.

**C.19**    Convert hexadecimal 3A7D to binary.

**C.20**    Convert hexadecimal 765F to octal. (*Hint:* First convert 765F to binary, then convert that binary number to octal.)

**C.21**    Convert binary 1011110 to decimal.

**C.22**    Convert octal 426 to decimal.

**C.23**    Convert hexadecimal FFFF to decimal.

**C.24**    Convert decimal 299 to binary, to octal and to hexadecimal.

**C.25**    Show the binary representation of decimal 779. Then show the one's complement of 779 and the two's complement of 779.

**C.26**    Show the two's complement of integer value  $-1$  on a machine with 32-bit integers.

# Game Programming: Solving Sudoku

## D.1 Introduction

The game of Sudoku exploded in popularity worldwide in 2005. Almost every major newspaper now publishes a Sudoku puzzle daily. Handheld game players let you play anytime, anywhere and create puzzles on demand at various levels of difficulty.

A completed **Sudoku puzzle** is a  $9 \times 9$  grid (i.e., a two-dimensional array) in which the digits 1 through 9 appear once and only once in each row, each column and each of nine  $3 \times 3$  grids. In the partially completed  $9 \times 9$  grid of Fig. D.1, row 1, column 1, and the  $3 \times 3$  grid in the upper-left corner of the board each contain the digits 1 through 9 once and only once. We use C's two-dimensional array row and column-numbering conventions, but we're ignoring row 0 and column 0 in conformance with Sudoku community conventions.

---

|   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
|---|---|---|---|---|---|---|---|---|---|
| 1 | 5 | 1 | 3 | 4 | 9 | 7 | 6 | 2 | 8 |
| 2 | 4 | 6 | 8 |   |   |   |   |   |   |
| 3 | 7 | 9 | 2 |   |   |   |   |   |   |
| 4 | 2 |   |   |   |   |   |   |   |   |
| 5 | 9 |   |   |   |   |   |   |   |   |
| 6 | 3 |   |   |   |   |   |   |   |   |
| 7 | 8 |   |   |   |   |   |   |   |   |
| 8 | 1 |   |   |   |   |   |   |   |   |
| 9 | 6 |   |   |   |   |   |   |   |   |

---

**Fig. D.1** | Partially completed  $9 \times 9$  Sudoku grid. Note the nine  $3 \times 3$  grids.

The typical Sudoku puzzle provides many filled-in cells and many blanks, often arranged in a symmetrical pattern as is typical with crossword puzzles. The player's task is to fill in the blanks to complete the puzzle. Some puzzles are easy to solve; some are quite difficult, requiring sophisticated solution strategies.

We'll discuss various simple solution strategies, and suggest what to do when these fail. We'll also present approaches for programming Sudoku puzzle creators and solvers in C. Unfortunately, Standard C does not include graphics and GUI (graphical user interface) capabilities, so our repre-

sensation of the board won't be as elegant as we could make it in Java and other programming languages that support these capabilities. You may want to revisit your Sudoku programs after you read Appendix E, Game Programming with the Allegro C Library. Allegro, which is not part of Standard C, offers capabilities that will help you add graphics and even sounds to your Sudoku programs.

## D.2 Deitel Sudoku Resource Center

Check out our [Sudoku Resource Center](http://www.deitel.com/sudoku) at [www.deitel.com/sudoku](http://www.deitel.com/sudoku). It contains downloads, tutorials, books, e-books and more that will help you master the game. Trace the history of Sudoku from its origin in the eighth century through modern times. Download free Sudoku puzzles at various levels of difficulty, enter daily game contests to win Sudoku books, and get a daily Sudoku puzzle to post on your web site. Get great beginner's resources—learn the rules of Sudoku, receive hints on solving sample puzzles, learn the best solution strategies and get free Sudoku solvers—just type in the puzzle from your newspaper or favorite Sudoku site and get an immediate solution; some Sudoku solvers even provide detailed step-by-step explanations. Get mobile device Sudoku games that can be installed on cell phones, Palm® devices, Game Boy® players and Java-enabled devices. Some Sudoku sites have timers, signal when an incorrect number is placed and provide hints. Purchase T-shirts and coffee mugs with Sudoku puzzles on them, participate in Sudoku player forums, get blank Sudoku worksheets that can be printed and check out hand-held Sudoku game players—one offers a million puzzles at five levels of difficulty. Download free Sudoku puzzle maker software. And not for the faint of heart—try fiendishly difficult Sudokus with tricky twists, a circular Sudoku and a variant of the puzzle with five interlocking grids. Subscribe to our free newsletter, the *Deitel® Buzz Online*, for notifications of updates to our Sudoku Resource Center and to other Deitel Resource Centers at [www.deitel.com](http://www.deitel.com) that provide games, puzzles and other interesting programming projects.

## D.3 Solution Strategies

When we refer to a Sudoku 9×9 grid, we'll call it array *s*. By looking at all the filled-in cells in the row, column and 3×3 grid that includes a particular empty cell, the value for that cell might become obvious. Trivially, cell *s*[1][7] in Fig. D.2 *must* be 6.

---

|   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
|---|---|---|---|---|---|---|---|---|---|
| 1 | 2 | 9 | 3 | 1 | 8 | 7 | — | 5 | 4 |
| 2 |   |   |   |   |   |   |   |   |   |
| 3 |   |   |   |   |   |   |   |   |   |
| 4 |   |   |   |   |   |   |   |   |   |
| 5 |   |   |   |   |   |   |   |   |   |
| 6 |   |   |   |   |   |   |   |   |   |
| 7 |   |   |   |   |   |   |   |   |   |
| 8 |   |   |   |   |   |   |   |   |   |
| 9 |   |   |   |   |   |   |   |   |   |

---

**Fig. D.2** | Determining the value of a cell by checking all filled-in cells in the same row.

Less trivially, to determine the value of  $s[1][7]$  in Fig. D.3, you have to pick up hints from row 1 (i.e., the digits 3, 6 and 9 are taken), column 7 (i.e., the digits 4, 7 and 1 are taken) and the upper-right  $3 \times 3$  grid (i.e., the digits 9, 8, 4 and 2 are taken). Here the empty cell  $s[1][7]$  *must* be 5—the only number not already mentioned in row 1, column 7 or the upper-right  $3 \times 3$  grid.

|   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
|---|---|---|---|---|---|---|---|---|---|
| 1 |   |   | 3 |   |   | 6 | — |   | 9 |
| 2 |   |   |   |   |   |   |   | 8 |   |
| 3 |   |   |   |   |   |   | 4 |   | 2 |
| 4 |   |   |   |   |   |   |   |   |   |
| 5 |   |   |   |   |   |   |   |   |   |
| 6 |   |   |   |   |   |   | 7 |   |   |
| 7 |   |   |   |   |   |   | 1 |   |   |
| 8 |   |   |   |   |   |   |   |   |   |
| 9 |   |   |   |   |   |   |   |   |   |

**Fig. D.3** | Determining the value of a cell by checking all filled-in cells in the same row, column and  $3 \times 3$  grid.

### Singletons

The strategies we've discussed so far can easily determine the final digits for some open cells, but you'll often have to dig deeper. Column 6 of Fig. D.4 shows cells with already determined values (e.g.,  $s[1][6]$  is a 9,  $s[3][6]$  is a 6, etc.), and cells indicating the set of values (which we call “possibles”) that at this point are still possible for that cell.


Cell  $s[6][6]$  contains 257, indicating that only the values 2, 5 or 7 can eventually be assigned to this cell. The other two open cells in column 6— $s[2][6]$  and  $s[5][6]$ —are both 27, indicating that *only* the values 2 or 7 can eventually be assigned to these cells. Thus  $s[6][6]$ , the only cell in column 6 that lists 5 as a remaining possible value, *must* be 5. We call that value 5 a **singleton**. So we can commit cell  $s[6][6]$  to a 5 (Fig. D.5), somewhat simplifying the puzzle.

### Doubles


Consider the upper-right  $3 \times 3$  grid in Fig. D.6. The dashed cells could already be committed or could have lists of possible values. Notice the **doubles**—the two cells  $s[1][9]$  and  $s[2][7]$  containing only the two possibilities 15. If  $s[1][9]$  ultimately becomes 1, then  $s[2][7]$  *must* be 5; if  $s[1][9]$  ultimately becomes 5, then  $s[2][7]$  *must* be 1. So between them, those two cells will definitely “use up” the 1 and the 5. Thus 1 and 5 can be eliminated from cell  $s[3][9]$  that contains the possible values 1357, so we can rewrite its contents as 37, simplifying the puzzle a bit. If cell  $s[3][9]$  had originally contained only 135, then eliminating the 1 and the 5 would enable us to force the cell to the value 3.

Doubles can be more subtle. For example, suppose two cells of a row, column or  $3 \times 3$  grid have possibles lists of 2467 and 257 and that no other cell in that row, column or  $3 \times 3$  grid mentions 2 or 7 as a possible value. Then, 27 is a **hidden double**—one of those two cells must be 2 and the other must be 7, so all digits other than 2 and 7 can be removed from the possibles lists of those

two cells (i.e., 2467 becomes 27 and 257 becomes 27—creating a pair of doubles—thus somewhat simplifying the puzzle).



**Fig. D.4** | Notation showing the complete sets of possible values for open cells.



**Fig. D.5** | Committing cell `s[6][6]` to the singleton value 5.

|   | 1 | 2 | 3 | 4 | 5 | 6 | 7                         | 8 | 9                                                   |
|---|---|---|---|---|---|---|---------------------------|---|-----------------------------------------------------|
| 1 |   |   |   |   |   |   | —                         | — | <sup>1</sup> <sub>5</sub>                           |
| 2 |   |   |   |   |   |   | <sup>1</sup> <sub>5</sub> | — | —                                                   |
| 3 |   |   |   |   |   |   | —                         | — | <sup>1</sup> <sub>5</sub> <sup>3</sup> <sub>7</sub> |
| 4 |   |   |   |   |   |   |                           |   |                                                     |
| 5 |   |   |   |   |   |   |                           |   |                                                     |
| 6 |   |   |   |   |   |   |                           |   |                                                     |
| 7 |   |   |   |   |   |   |                           |   |                                                     |
| 8 |   |   |   |   |   |   |                           |   |                                                     |
| 9 |   |   |   |   |   |   |                           |   |                                                     |

**Fig. D.6** | Using doubles to simplify a puzzle.

### *Triples*

Consider column 5 of Fig. D.7. The dashed cells could already be committed or could have lists of possible values. Notice the **triples**—the three cells containing the exact same three possibilities 467, namely cells  $s[1][5]$ ,  $s[6][5]$  and  $s[9][5]$ . If one of those three cells ultimately becomes 4, then

|   | 1 | 2 | 3 | 4 | 5                                                     | 6 | 7 | 8 | 9 |
|---|---|---|---|---|-------------------------------------------------------|---|---|---|---|
| 1 |   |   |   |   | <sup>4</sup> <sub>7</sub> 6                           |   |   |   |   |
| 2 |   |   |   |   | —                                                     |   |   |   |   |
| 3 |   |   |   |   | —                                                     |   |   |   |   |
| 4 |   |   |   |   | <sup>1</sup> <sub>4</sub> <sup>5</sup> <sub>7</sub> 6 |   |   |   |   |
| 5 |   |   |   |   | —                                                     |   |   |   |   |
| 6 |   |   |   |   | <sup>4</sup> <sub>7</sub> 6                           |   |   |   |   |
| 7 |   |   |   |   | —                                                     |   |   |   |   |
| 8 |   |   |   |   | —                                                     |   |   |   |   |
| 9 |   |   |   |   | <sup>4</sup> <sub>7</sub> 6                           |   |   |   |   |

**Fig. D.7** | Using triples to simplify a puzzle.



the others reduce to doubles of 67; if one of those three cells ultimately becomes 6, then the others reduce to doubles of 47; and if one of those three cells ultimately becomes 7, then the others reduce to doubles of 46. Among the three cells containing 467, one must ultimately be 4, one must be 6, and one must be 7. Thus the 4, 6 and 7 can be eliminated from cell `s[4][5]` that contains the possibles 14567, so we can rewrite its contents as 15, simplifying the puzzle a bit. If cell `s[4][5]` had originally contained 1467, then eliminating the 4, 6 and 7 would enable us to force the value 1 in that cell.

Triples can be more subtle. Suppose a row, column or 3×3 grid contains cells with possibles lists of 467, 46, and 67. Clearly one of those cells must be 4, one must be 6 and one must be 7. Thus 4, 6 and 7 can be removed from all the other possibles lists in that row, column or 3×3 grid.

Triples can also be hidden. Suppose that a row, column or 3×3 grid contains the possibles lists 5789, 259 and 13789, and that no other cell in that row, column or 3×3 grid mentions 5, 7 or 9. Then one of those cells must be 5, one must be 7 and one must be 9. We call 579 a **hidden triple** and all possibles other than 5, 7 and 9 can be deleted from those three cells (i.e., 5789 becomes 579, 259 becomes 59 and 13789 becomes 79), thus somewhat simplifying the puzzle.

### *Other Sudoku Solution Strategies*

There are a number of other Sudoku solution strategies. Here are two of the many sites we recommend in our Sudoku Resource Center ([www.deitel.com/sudoku](http://www.deitel.com/sudoku)) that will help you dig deeper:

[www.sudokuoftheday.com/pages/techniques-overview.php](http://www.sudokuoftheday.com/pages/techniques-overview.php)  
[www.angusj.com/sudoku/hints.php](http://www.angusj.com/sudoku/hints.php)

## **D.4 Programming Sudoku Puzzle Solvers**

In this section we suggest how to program Sudoku solvers. We use a variety of approaches. Some may seem unintelligent, but if they can solve Sudokus faster than any human on the planet, then perhaps they are in some sense intelligent.

If you’ve done our Knight’s Tour exercises (Exercises 6.24, 6.25 and 6.29) and Eight Queens exercises (Exercises 6.26 and 6.27), you’ve implemented various brute force and heuristic problem-solving approaches. In the next several sections, we suggest brute force and heuristic Sudoku-solving strategies. You should try programming them, as well as creating and programming your own. Our goal is simply to acquaint you with Sudoku, and some of its challenges and problem-solving strategies. Along the way, you’ll become more facile with manipulating two-dimensional arrays and with nested iteration structures. We have made no attempt to produce optimal strategies, so once you analyze our strategies, you’ll want to consider how you can improve upon them.

### *Programming a Solution for “Easy” Sudokus*

The strategies we’ve shown—eliminating possibilities based on values already committed in a cell’s row, column and 3×3 grid; and simplifying a puzzle using singletons, doubles (and hidden doubles) and triples (and hidden triples)—are sometimes sufficient to solve a puzzle. You can program the strategies then iterate on them until all 81 squares are filled. To confirm that the filled puzzle is a valid Sudoku, you can write a function to check that each row, column and 3×3 grid contains the digits 1 through 9 once and only once. Your program should apply the strategies in order. Each of them either forces a digit in a cell or simplifies the puzzle a bit. When any one of the strategies works, return to the beginning of your loop and reapply the strategies in order. When a strategy doesn’t work, try the next. For “easy” Sudokus, these techniques should generate a solution.

### *Programming a Solution for Harder Sudokus*

For harder Sudokus, your program will eventually reach a point where it still has uncommitted cells with possibles lists, and none of the simple strategies we’ve discussed will work. If this hap-

pens, first save the state of the board, then generate the next move by randomly choosing one of the possible values in any of the remaining cells. Then reevaluate the board, enumerating the remaining possibilities for each cell. Then try the basic strategies again, looping through them repeatedly, until either the Sudoku is solved, or the strategies once again no longer improve the board, at which point you can again try another move at random. If you reach a point where there are still empty cells, but no possible digits for at least one of those cells, the program should abandon that attempt, restore the board state that you saved, and begin the random approach again. Keep looping until a solution is found.

## D.5 Generating New Sudoku Puzzles

First, let's consider approaches for generating valid finished 9×9 Sudokus with all 81 squares filled in. Then, we'll suggest how to empty some cells to create puzzles that people can attempt.

### *Brute Force Approaches*

When personal computers appeared in the late 1970s, they processed tens of thousands of instructions per second. Today's desktop computers commonly process *billions* of instructions per second and the world's fastest supercomputers can process *trillions* of instructions per second! Brute force approaches that might have required months of computing in the 1970s can now produce solutions in seconds! This encourages people who need results quickly to program simple brute force approaches and get solutions sooner than by taking the time to develop more sophisticated “intelligent” problem solving strategies. Although our brute force approaches may seem ponderous, they will mechanically grind out solutions.

For these approaches you'll need some utility functions. Create the function

```
int validSudoku(int sudokuBoard[10][10]);
```

which receives a Sudoku board as a two-dimensional array of integers (recall that we're ignoring row 0 and column 0). This function should return 1 if a completed board is valid, 2 if a partially completed board is valid and 0 otherwise.

### *An Exhaustive Brute Force Approach*

One brute force approach is simply to select all possible placements of the digits 1 through 9 in every cell. This could be done with 81 nested for statements that each loop from 1 through 9. The number of possibilities ( $9^{81}$ ) is so vast that you might say it's not worth trying. But this approach does have the advantage that it will eventually stumble onto *every* possible solution, some of which could show up fortuitously early on.

A slightly more intelligent version of this exhaustive brute-force approach would be to check each digit you're about to place to see if it leaves the board in a valid state. If it does, then move on to placing a digit in the next cell. If the digit you're attempting to place leaves the board in an invalid state, then try all other eight digits on that cell in order. If one of them works, then move on to the next cell. If none of them works, then move back up to the previous cell and try its next value. Nested for statements can handle this automatically.

### *Brute Force Approach with Randomly Selected Row Permutations*

Every row, column, and 3×3 grid on a valid Sudoku contains a permutation of the digits 1 through 9. There are 9! (i.e.,  $9 \cdot 8 \cdot 7 \cdot 6 \cdot 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1 = 362,880$ ) such permutations. Write a function

```
void permutations(int sudokuBoard[10][10]);
```

that receives a 10×10 two-dimensional array and in the 9×9 portion of it that corresponds to a Sudoku grid fills each of the nine rows with a randomly selected permutation of the digits 1 through 9.

Here's one way to generate a random permutation of the digits 1 through 9—for the first digit, simply choose a random digit from 1 through 9; for the second digit, use a loop to repeatedly generate a random digit from 1 through 9 until a digit *different* from the first digit is selected; for the third digit, use a loop to repeatedly generate a random digit from 1 through 9 until a digit different from the first two digits is selected; and so on.

After placing nine randomly selected permutations into the nine rows of your Sudoku array, run function `validSudoku` on the array. If it returns 1, you're done. If it returns 0, simply loop again, generating another nine randomly selected permutations of the digits 1 through 9 into the nine successive rows of the array `Sudoku`. The simple process will generate valid Sudokus. By the way, this approach guarantees that all the rows are valid permutations of the digits 1 through 9, so you should add an option to your function `validSudoku` that will have it check only columns and  $3 \times 3$  grids.

### *Heuristic Solution Strategies*

When we studied the Knight's Tour in Exercises 6.24, 6.25 and 6.29, we developed a “keep your options open” heuristic. To review, a heuristic is a guideline. It “sounds good” and seems like a reasonable rule to follow. It's programmable, so it gives us a way to direct a computer to attempt to solve a problem. But heuristic approaches don't necessarily guarantee success. For complex problems like solving a Sudoku puzzle, the number of possible placements of the digits 1–9 is enormous, so the hope in using a reasonable heuristic is that it will avoid wasting time on fruitless possibilities and instead focus on solution attempts much more likely to yield success.

#### *A “Keep Your Options Open” Sudoku-Solving Heuristic*

Let's develop a “keep your options open” heuristic for solving Sudokus. At any point in solving a Sudoku, we can categorize the board by listing in each empty cell the digits from 1 to 9 which are still open possibilities for that cell. For example, if a cell contains 3578, then the cell must eventually become 3, 5, 7 or 8. When attempting to solve a Sudoku, we reach a dead end when the number of possible digits that can be placed in an empty cell becomes zero. So, consider the following strategy:

1. Associate with every empty square a possible list of the digits that can still be placed in that square.
2. Characterize the state of the board by simply counting the number of possible placements for the entire board.
3. For each possible placement for each empty cell, associate with that placement the count that would characterize the state of the board after that placement.
4. Then, place the particular digit in the particular empty square (of all those that remain) that leaves the board count the highest (in case of a tie, pick one at random). This is a key to “keeping your options open.”

### *Lookahead Heuristic*

This is simply an embellishment of our “keep your options open” heuristic. In case of a tie, look ahead one more placement. Place the particular digit in the particular square whose subsequent placement leaves the board count the highest after two moves out.

### *Forming Sudoku Puzzles with Empty Cells*

Once you get your Sudoku generator program running, you should be able to generate lots of valid Sudokus quickly. To form a puzzle, save the solved grid, then empty some cells. One way to do this is to empty randomly chosen cells. A general observation is that Sudokus tend to become more difficult as the empty cells increase (there are exceptions to this).

Another approach is to empty the cells in a manner that leaves the resulting board symmetric. This can be done programmatically by randomly picking a cell to empty, then emptying its “reflecting cell.” For example, if you empty the top-left cell `s[1][1]`, you might empty the bottom-left cell `s[9][1]` as well. Such reflections are calculated by presenting the column, but determining the row by subtracting the initial row from 10. You could also do the reflections by subtracting both the row and column of the cell you’re emptying from 10. Hence, the reflecting cell to `s[1][1]` would be `s[10-1][10-1]` or `s[9][9]`.

### *A Programming Challenge*

Published Sudoku puzzles typically have exactly one solution, but it’s still satisfying to solve any Sudoku, even ones that have multiple solutions. Develop a means of demonstrating that a particular Sudoku puzzle has *exactly one* solution.

## D.6 Conclusion

This appendix on solving and programming Sudoku puzzles has presented you with many challenges. Be sure to check out our Sudoku Resource Center ([www.deitel.com/sudoku/](http://www.deitel.com/sudoku/)) for numerous web resources that will help you master Sudoku and develop various approaches for writing programs to create and solve existing Sudoku puzzles.



## Appendices on the Web

The following appendices are available as PDF documents from this book's Companion Website ([www.pearsonhighered.com/deitel/](http://www.pearsonhighered.com/deitel/)):

- Appendix E, Game Programming with the Allegro C Library
- Appendix F, Sorting: A Deeper Look
- Appendix G, Introduction to C99
- Appendix H, Using the Visual Studio Debugger
- Appendix I, Using the GNU Debugger

These files can be viewed in Adobe® Reader® ([get.adobe.com/reader](http://get.adobe.com/reader)). The index entries for these appendices have uppercase Roman numeral page numbers.

New copies of this book come with a Companion Website access code that is located on the card inside the book's front cover. If the access code is already visible or there is no card, you purchased a used book or an edition that does not come with an access code. In this case, you can purchase access directly from the Companion Website.

# Index

## Symbols

`\t` horizontal-tab escape sequence 26  
`^` bitwise exclusive OR operator 373, 395  
`^=` bitwise exclusive OR assignment operator 402  
`__func__` predefined identifier [XCVIII](#)  
`__VA_ARGS__` [XCV](#)  
`_Pragma` operator [XCV](#)  
`::` (binary scope resolution operator) [586](#), 660  
`::`, unary scope resolution operator [544](#)  
`!=` inequality operator 38, 39, 676  
`? 60`  
`?:` conditional operator [60](#), [80](#), 173  
`.` dot operator [386](#)  
`.` structure member operator 386  
`.h` filename extension 580  
`" 368`  
`"w"` file open mode 422  
`*` assignment suppression character [374](#)  
`*` multiplication operator [34](#), [72](#)  
`*=` multiplication assignment operator [80](#)  
`/` division operator [72](#)  
`//` single-line comment [25](#), 530, [LXXX](#)  
`/=` division assignment operator [80](#)  
`\\` backslash-character escape sequence 26  
`\?` escape sequence 369  
`\'` single-quote-character escape sequence 369  
`\"` double-quote-character escape sequence 369  
`\\` backslash-character escape sequence 369  
`\0` null character escape sequence 207  
`\a` alert escape sequence 26, 369  
`\b` escape sequence 369  
`\f` escape sequence 312  
`\f` form-feed escape sequence 369  
`\n` escape sequence 312  
`\n` newline escape sequence 26, 369  
`\r` carriage-return escape sequence 369  
`\r` escape sequence 312  
`\t` escape sequence 312  
`\t` horizontal-tab escape sequence 369  
`\v` escape sequence 312, 369  
`&` address operator [31](#)  
`&` and `*` pointer operators 256  
`&` bitwise AND operator 395  
`&` to declare reference 538  
    in a parameter list 540  
`&&` operator [116](#), 119, 173  
`&=` bitwise AND assignment operator 402  
`#` flag [367](#)  
`#` preprocessor operator 25, 500  
`##` preprocessor operator 500

`#define` [496](#)  
`#elif` [499](#)  
`#endif` [499](#)  
`#error` [500](#)  
`#error` [500](#)  
`#if` [499](#)  
`#pragma` [500](#)  
`#undef` [501](#)  
`%` character in a conversion specifier [72](#), [357](#), [362](#)  
`%` remainder operator [34](#), 34, 153  
`%%` conversion specifier 363  
`%=` remainder assignment operator [80](#)  
`%c` conversion specifier 150, 361, [372](#)  
`%d` conversion specifier 150  
`%E` conversion specifier [360](#), 371  
`%e` conversion specifier [360](#), 371  
`%f` conversion specifier 72, 150  
`%g` conversion specifier 371  
`%hd` conversion specifier 150  
`%hu` conversion specifier 150  
`%i` conversion specifier [371](#)  
`%ld` conversion specifier 150  
`%Lf` conversion specifier 150  
`%lf` conversion specifier 150  
`%lu` conversion specifier 150  
`%n` conversion specifier [362](#)  
`%p` conversion specifier 256, [362](#)  
`%s` conversion specifier 283, 361, [372](#)  
`%u` conversion specifier 150, [359](#)  
`%X` conversion specifier 370  
    + flag [367](#)  
    + flag 366  
    - minus operator [80](#)  
    + unary plus operator [80](#)  
    -- operator [78](#), [80](#), 274  
    ++ operator [78](#), 79, [80](#), 274  
    += addition assignment operator 77, [80](#), 676  
    < less than operator 38  
    < redirect input symbol 508  
    << left-shift operator 395  
    << stream insertion operator 532  
    <= left-shift assignment operator 402  
    <= less-than-or-equal-to operator 38  
    = assignment operator [80](#)  
    -= subtraction assignment operator [80](#)  
    == equality operator 38, 120, 676  
    > greater than operator 38  
    > redirect output symbol 509  
    -> structure pointer operator 386  
    >= greater-than-or-equal-to operator 38  
    >> append output symbol 509  
    >> right-shift operator 395  
    >>= right shift assignment operator 402  
    | bitwise inclusive OR operator 395  
    | pipe 508

|= bitwise inclusive OR assignment operator 402  
|| 174  
~ bitwise one's complement 395  
~, bitwise complement operator [400](#)

## Numerics

0 Conversion specifier 30, 31, 370, 371  
0X 868  
0x 367, 868

## A

a file open mode 425  
a.out 14  
a+ file open mode 425  
ab binary file open mode 516  
ab file open mode 425  
ab+ binary file open mode 516  
ab+ file open mode 425  
abnormal program termination 518  
abort a program 911  
abort function 502, [502](#), [621](#), [901](#), 906  
absolute-value 143  
abstract base class 780, [799](#), 800  
Abstract Base Classes 830  
abstract class [799](#), 800, 801, 819  
abstract data type (ADT) [664](#)  
abstraction [144](#)  
access function [612](#)  
access global variable 544  
access non-static class data members and member functions 663  
access private member of a class 572  
access privileges 33, 262  
access specifier [564](#), 571, 652  
    private 571  
    protected 603  
    public [564](#), 571  
access-specifier label  
    private: 571  
    public: [564](#)  
access the caller's data 537  
access violation 33, 312, 361  
accessibility heuristic 249  
accessor [574](#)  
accounts receivable 135  
accumulated outputs 531  
accumulator 302, 304, 306  
action [26](#), 27, 38, 56, 63, 664  
action oriented [552](#)  
action statement 56  
action symbol [57](#)  
action/decision model [27](#), 59  
actions [38](#), [55](#)  
actions (computers perform) [2](#)

- activation record [151](#)
  - active window CVIII
  - Ada Lovelace 10
  - Ada programming language [10](#)
  - add an integer to a pointer 273
  - add instruction 304
  - addition 4
  - addition assignment operator (**+=**) [77](#)
  - addition program that displays the sum of two numbers 530
  - address 463
  - address of a bit field 406
  - address operator (**&**) [31](#), 152, 208, [255](#), 258, 268, 674
  - `adjust_sample` XVII
  - "administrative" section of the computer 4
  - ADT (abstract data type) [664](#)
  - Advanced string manipulation exercises 350, 351, 352, 354
  - aggregate data types 265
  - aggregates [383](#)
  - aggregation [609](#)
  - aiming a derived-class pointer at a base-class object 790
  - Air Traffic Control Project 671
  - airline reservation system 246
  - alert (**\a**) 26
  - algebra 34
  - algorithm [55](#), 66
    - insertion sort [LXIV](#)
    - merge sort [LXVII](#)
    - selection sort [LX](#)
  - `<algorithm>` header file 534
  - alias 540
    - for a variable (reference) 540
    - for the name of an object 624
  - aligning 357
  - Allegro [2](#), [II](#), V, VI
  - `allegro_init` III, IV
  - `allegro_message` IV
  - `allegro.h` III, IV
  - `allegro-config` program III
  - allocate [682](#)
  - allocate dynamic memory 534, 907
  - allocate memory 682
  - ALU [4](#)
  - American National Standards Committee on Computers and Information Processing 8
  - American National Standards Institute (ANSI) [2](#), 8
  - `ampersand` (**&**) [31](#), 33
  - Analytical Engine 10
  - analyze a requirements document 553
  - AND 394
  - angle brackets (**<** and **>**)
    - in templates 549
  - angle brackets (**<** and **>**) in templates [834](#)
  - animating bitmaps IX
  - Animation in Allegro [IX](#)
  - Another dangling else problem 93
  - ANSI 2
  - ANSI C 261
  - ANSI C standard document 15
  - append output symbol **>>** [509](#)
  - Apple Computer, Inc. 5
  - area of a circle 95
  - `argc` [511](#)
  - argument [26](#), 498
  - argument (of a function) [142](#), 157
  - argument to a function [566](#)
  - arguments [497](#)
  - arguments passed to member-object constructors 645
  - `argv` [511](#)
  - arithmetic 14
  - arithmetic and logic unit (ALU) [4](#)
  - arithmetic assignment operators 77
    - +=**, **-=**, **\*=**, **/=**, and **%=** 77
  - arithmetic expressions 273
  - arithmetic mean 36
  - arithmetic operations 303
  - arithmetic operators [34](#)
  - arithmetic overflow [665](#), 897
  - arithmetic overflow error [910](#)
  - arithmetic underflow error [911](#)
  - "arity" of an operator 675
  - array 196, 684
  - array bounds checking 205
  - Array class 685
  - Array class definition with overloaded operators 685, 709
  - Array class member-function and friend function definitions 686
  - Array class test program 688
  - array initializer list 200
  - Array name is the same as the address of the array's first element 213
  - array notation 278
  - array of pointers [280](#), 289
    - to functions 301
  - array of pointers to functions 289
  - array of strings [280](#)
  - array subscript notation 207, 267, 279
  - array subscript operator (**[]**) 692
  - Arrays [196](#)
  - array-sort function 833
  - arrow member selection operator (**->**) 610
  - arrow operator (**->**) [386](#), 655
  - ASCII [330](#)
  - ASCII (American Standard Code for Information Interchange) [110](#), 330, 858
  - ASCII character set 110
  - assembler [6](#)
  - assembly language [6](#)
  - `assert` macro 502, [502](#)
  - `<assert.h>` 152, [502](#)
  - assigning addresses of base-class and derived-class objects to base-class and derived-class pointers 787
  - assigning character strings to `String` objects 698
  - assigning class objects 627
  - Assigning elements of an array in C89 LXXXIV
  - assignment expressions 273
  - assignment operator
    - =** 627
  - assignment operator (**=**) 39, 673, 674
  - assignment operator functions 694
  - assignment operators
    - =**, **+=**, **-=**, **\*=**, **/=**, and **%=** 77
  - assignment statement [31](#)
  - assignment suppression character **\*** 374
  - associate from right-to-left 41, 72
  - association (in the UML) [552](#)
  - associativity [35](#), 41, 80, 197, 256, 402
  - associativity not changed by overloading 675
  - asterisk (**\***) [34](#)
  - asynchronous event [897](#)
  - at** member function of `string` [707](#)
  - AT&T 11
  - `atexit` function [514](#), 514
  - `atof` function [318](#)
  - `atoi` function [318](#)
  - `atol` function [319](#)
  - attribute 552, [569](#)
    - in the UML [551](#), 565
  - audible (bell) 369
  - `auto` [161](#)
  - `auto_ptr` class [907](#), 907, 908
  - `auto_ptr` object goes out of scope 907
  - `auto_ptr` object manages dynamically allocated memory 908
  - `auto_ptr` overloaded **\*** operator 908
  - `auto_ptr` overloaded **->** operator 908
  - automatic array 200
  - automatic local object 621
  - automatic local variable 541
  - automatic object 903
  - automatic storage 162, 196
  - automatic storage duration [162](#), 210
  - automatic variable 162, [162](#), 163
  - Autos window [CXIV](#)
    - displaying state of objects CXV
  - Autos window displaying the state of `localTime` CXV
  - Autos window displaying the state of `localTime` CXV
  - average 36
  - avoid repeating code 618
- ## B
- B 7
  - Babbage, Charles 10
  - backslash (**\**) 26, 369
  - backslash (**\**) [498](#)
  - `bad` member function 878
  - `bad_alloc` exception [904](#), 905, 910
  - `bad_cast` exception [910](#)
  - `bad_exception` exception [910](#)
  - `bad_typeid` exception [910](#)
  - `badbit` of stream [858](#), 878
  - bank account program 438
  - bar chart 135, 205
  - base [925](#)
  - base 10 number system 320, 868
  - base 16 number system 320, 868
  - base 8 number system 320, 868
  - base case(s) [167](#)
  - base class [728](#), 729, 731
  - base-class catch 910
  - base-class constructor 763
  - base-class exception 909
  - base-class initializer syntax [746](#)
  - base-class member accessibility in derived class 771
  - base-class pointer to a derived-class object 826
  - base-class `private` member 732
  - base specified for a stream 872



- base-class member function redefined in a derived class 761
  - BASIC (Beginner's All-Purpose Symbolic Instruction Code) 10
  - `basic_fstream` template **856**
  - `basic_ifstream` template **856**
  - `basic_ios` template 855
  - `basic_iostream` class 856
  - `basic_iostream` template 855
  - `basic_istream` template **854**
  - `basic_ofstream` template **856**
  - `basic_ostream` class 856
  - BCPL 7
  - Beginner's All-Purpose Symbolic Instruction Code (BASIC) 10
  - behavior of an object 552
  - behaviors in the UML **551**
  - bell 26
  - Bell Laboratories 7, 9
  - Big O notation **LIX**, **LXIII**
  - binary 312
  - binary (base 2) number system **925**
  - binary arithmetic operators 72
  - binary digits **418**
  - binary file 516
  - binary file modes 516
  - binary number 137
  - binary operator 31, 34
  - binary scope resolution operator (`::`) **586**, 660
  - binary search 175, 189, **223**, 225, 226, 251
  - binary search tree **479**, 482, 483, 492
  - binary-to-decimal conversion problem 94
  - binary tree **455**, **478**
  - binary tree delete 492
  - binary tree insert 176
  - binary tree sort **482**
  - bit **418**
  - bit field **403**, 404
  - bit field member name **403**
  - bit manipulation 406
  - bitmap IV, V, VI
  - `BITMAP` type **IV**, **VIII**
  - `<bitset>` header file 533
  - bitwise AND (`&`) operator **394**, 399, 414
  - bitwise AND, bitwise inclusive OR, bitwise exclusive OR and bitwise complement operators 397
  - bitwise assignment operators **402**
  - bitwise complement operator (`~`) 397, **400**, **932**
  - bitwise data manipulations 394
  - bitwise exclusive OR (`^`) operator **394**, 400
  - bitwise inclusive OR (`|`) operator **394**, 399
  - bitwise left-shift operator (`<<`) 673
  - bitwise operators 394
  - bitwise right-shift operator (`<CDT>>`) 673
  - bitwise shift operators 400
  - blank 58
  - blank insertion 51
  - blank line 531
  - `blit` **VII**
  - Blitting **IV**
  - block 25, **62**, **146**, 569
  - block of data 337
  - block scope **164**
    - variable 609
  - body **25**, **41**
  - body mass index (BMI) 22
    - calculator 22
  - Body Mass Index Calculator (Test Drive) 22
  - body of a class definition **563**
  - body of a function 25
  - body of a `while` 63
  - Bohm, C. 56
  - "bombing" **68**
  - Booch, Grady 553, 554
  - `_Bool` **LXXXVII**
  - `bool` primitive type (C++) **536**
  - `boolalpha` stream manipulator **874**
  - boolean type **LXXXVII**
  - bounds checking 205
  - braces (`{}`) 62
  - branching instructions 306
  - `break` 112, 114, 116, 138
  - `break` debugger command **CXXI**
  - `break` mode **CVII**, **CXXI**
  - breakpoint **CV**, **CXIX**
    - inserting **CXXI**, **CXXIV**
    - yellow arrow in `break` mode **CVIII**
  - breakpoints
    - inserting **CVII**, **CX**
    - red circle **CVII**
  - brittle software **755**
  - brute force problem solving approach 942, 943
  - bubble sort **216**, 243, 267, 269, 270, 285, **LXXVI**
  - `bubble` sort 218
  - bubble sort with call by reference 267, 268
  - Bucket Sort **LXXV**
  - bucket sort **LXXV**, **LXXVI**
  - buffer **XIII**
  - buffer is filled 856
  - buffer is flushed 856
  - buffered output **856**
  - buffered standard error stream 854
  - buffering 879
  - bug **CV**
  - building block approach **8**
  - building-block approach 532
  - "building blocks" 552
  - business-critical computing 896
  - business software 10
  - byte 394, **418**
- C**
- C 7, 15
  - C compiler 24
  - C development environment 13
  - C Environment 12
  - C language 7
  - C preprocessor **12**, **25**, **496**
  - C program and sample execution for the class average problem with counter-controlled repetition 65
  - C program and sample execution for the class average problem with sentinel-controlled repetition 69
  - C program and sample executions for examination results problem 75
  - C programming language 7
  - C Resource Center 12
  - C standard document (INCITS/ISO/IEC 9899-1999) 8
  - C Standard Library **8**, 12, **141**, 153
  - C standard library 263
  - C Standard Library documentation 8
  - C# programming language **10**
  - C++ **xxviii**, 7
  - C++ 148
  - C++ Boost Libraries **xxviii**
  - C++ Game Programming **xxviii**
  - C++ keywords 537
  - C++ programming language 11
  - C++ Resource Center 9
  - C++ Standard Library 532
    - `<string>` header file **567**
    - header file location 583
    - header files 533
    - `string` class **567**
  - C1X 2
  - C95 **LXXX**
  - C95 headers **LXXX**
  - C99 2, **LXXIX**
  - C99 headers **LXXX**
  - calculations 5, 31, 42
  - call a function **142**, 566
  - call-by-reference **152**, 254, **257**, 259, 262, 265, 267, 388
  - call-by-value **152**, **257**, 260, 262, 265, 388
  - called **145**
  - called function 141, **142**
  - caller **142**
  - calling function **142**
  - calling function (caller) **564**, 573
  - `callloc` **521**
  - camel case **563**
  - capital letter 29
  - carbon footprint calculator 22
  - Carbon Footprint Calculator (Test Drive) 22
  - CarbonFootprint Abstract Class:
    - Polymorphism 831
  - Card dealing program 283
  - card games 296
  - Card Shuffling and Dealing 670
  - card shuffling and dealing simulation 280, 283, 389
  - caret (`^`) **373**
  - carriage return (`'\r'`) 312
  - carry bit 932
  - cascading member function calls **655**, 656, 658
  - cascading stream insertion operations **532**
  - case label **111**, 112, 164
  - case sensitive **29**, 66
  - case study: Date class 700
  - casino 158
  - `<cassert>` header file 534
  - cast 499
    - downcast **792**, 798
  - cast operator 69, **71**, 150, 696, 708 (`float`) 71
  - cast operator function **697**
  - catch a base class object 910
  - catch all exceptions 911
  - catch clause (or handler) 897, 903
  - catch handler **894**



- catch keyword [895](#)
- catch related errors 904
- catch(...) 911
- Catching All Exceptions 917
- Catching Derived-Class Exceptions 917
- cc compilation command [14](#)
- <cctype> header file 534
- ceil function 143
- Celsius 381
- central processing unit (CPU) [4](#)
- cerr (standard error unbuffered) 854, 855
- <cfloat> header file 534
- chaining stream insertion operations [532](#)
- char [109](#)
- char 150, 311
- char \* 361
- char \*\* 319
- char primitive type [109](#)
- CHAR\_BIT symbolic constant [397](#)
- character [418](#)
- character array 207, 208
- character constant 264, [310](#), 361
- character handling library [312](#)
- character handling library functions 312
- character presentation 534
- character set 51, [110](#), [310](#), [331](#), [418](#)
- character string [26](#), 198
- check if a string is a palindrome 175
- check protection 352
- checkerboard 51, 95
- chess 247
- child [478](#)
- cin (standard input stream) [531](#), 531, 854, 855
- cin.clear 878
- cin.eof 858, 877
- cin.get function 860
- cin.tie function 879
- Circle class that inherits from class Point 786
- circumference of a circle 95
- clarity [2](#), 531
- class [11](#), 532, 551, 552
  - attribute [569](#)
  - client-code programmer 588
  - constructor 576
  - data member 562, [569](#)
  - default constructor [576](#), 578
  - define a constructor 578
  - define a member function [562](#)
  - definition [563](#)
  - implementation programmer 588
  - instance of 570
  - interface [583](#), [584](#)
  - interface described by function prototypes [584](#)
  - member function 562
  - member-function implementations
    - in a separate source-code file 586
  - naming convention 563
  - object of 570
  - public services [584](#)
  - services 574
- class Array 685
- class averaging problem 64, 69
- class Complex 720
- class definition [563](#)
- class development 685
- class diagram (UML) [565](#)
- class hierarchy [728](#), 800, 826
- class HugeInt 722
- class-implementation programmer 588
- class keyword 549, 563, 834
- class libraries 12
- class library 611, 772
- class Polynomial 726
- class RationalNumber 725
- class scope [606](#), 609
- class-scope variable is hidden 609
- class template [833](#), 837
  - auto\_ptr 907
  - definition 838
  - explicit specialization [845](#)
  - scope 840
  - specialization [833](#), 838
  - Stack 838, 840
- Classes
  - auto\_ptr [907](#)
  - exception [892](#)
  - invalid\_argument [910](#)
  - runtime\_error [892](#), 903
  - string [567](#)
  - vector 705
- classic stream libraries [853](#)
- clear function of ios\_base [878](#)
- clear\_bitmap IV
- clear\_to\_color IV
- client 712, 713
- client code 781
- client-code programmer 588
- client computer [5](#)
- client of a class [552](#)
- client of an object [574](#)
- client/server computing [5](#)
- <climits> header file 534
- clock 157
- clog (standard error buffered) 854, 855
- <cmath> header file 533
- COBOL (CCommon Business Oriented Language) [10](#)
- Code Search Engines and Code Sites
  - xxviii
- coefficient 726
- coercion of arguments [149](#)
- coin tossing 189
- colon (:) 649
- color depth VI
- column 229
- combining Class Time and Class Date
  - exercise 634
- comma operator (,) [102](#), 105, 173, 674
- comma-separated list 102
- command-and-control software system 10
- command-line arguments 511, 512
- comment 25, 530, 531
- commission 243
- commission problem 90
- CommissionEmployee class header file 811
- CommissionEmployee class
  - implementation file 812
- CommissionEmployee class represents
  - an employee paid a percentage of gross sales 734
- CommissionEmployee class test
  - program 737
- CommissionEmployee class uses
  - member functions to manipulate its private data 757
- CommissionEmployee class with
  - protected data 749
- Common Programming Errors overview
  - xxv
- Communications of the ACM* 56
- commutative 677
- commutative operation 678
- comparing strings [326](#)
- comparing unions 392
- comparison expressions 273
- compilation 12
- compilation error 119
- compile [12](#)
- compile error [30](#)
- compile phase [12](#)
- compile-time error [30](#)
- compiler 7, 12, 16, 24, 25, 27
- compiling multiple-source-file program 589
- complement operator (~) [394](#)
- complete algorithm 57
- \_Complex XC
- complex XC
- Complex class 633, 720, 888
  - exercise 633
  - member-function definitions 721
- complex number LXXXIX
- complex numbers 633, 720
- complex.h XC
- components (software) [9](#)
- composition [609](#), [645](#), 729, 732
- Composition as an Alternative to Inheritance 775
- compound interest 105, 135
- compound literal LXXXV
- compound statement [62](#)
- computation 3
- computer [3](#)
- computer-assisted instruction (CAI) 193, 194
- computer-assisted instruction (CAI):
  - Monitoring Student Performance 194
- computer-assisted instruction (CAI):
  - Varying the Types of Problems 194
- computer-assisted instruction (CAI):Difficulty Levels 194
- computer-assisted instruction (CAI):Reducing Student Fatigue 194
- computer dump 306
- computer network 5
- computer networking 5
- computer program [4](#)
- computer programmer [4](#)
- computer simulator 304
- Computerization of Health Records 416, 600
- computers in education 193
- computing the sum of the elements of an array 202
- concatenate stream insertion operations [532](#)
- concatenating strings [326](#)
- concrete class [799](#)
- concrete derived class 803
- condition [38](#), 116
- conditional compilation [496](#), [499](#)

- conditional execution of preprocessor directives [496](#)
  - conditional expression [60](#), [61](#), [605](#), [896](#)
  - conditional operator (`?:`) [60](#), [80](#)
  - connector symbols [57](#)
  - conserve storage [403](#)
  - consistent state [591](#), [604](#), [616](#)
  - `const` [515](#)
  - `const` [261](#), [262](#), [266](#), [269](#), [279](#), [280](#), [637](#), [681](#)
  - `const` keyword [215](#), [535](#)
  - `const` member function [636](#)
  - `const` member function on a `const` object [640](#)
  - `const` member function on a non-`const` object [640](#)
  - `const` object [636](#), [640](#)
  - `const` objects and `const` member functions [640](#)
  - `const` pointer [684](#)
  - `const` qualifier [261](#)
  - `const` qualifier before type specifier in parameter declaration [540](#)
  - `const` type qualifier [215](#)
  - `const` version of `operator[]` [696](#)
  - constant [489](#)
  - constant integral expression [112](#)
  - constant pointer [266](#), [267](#), [275](#), [654](#)
  - constant pointer to constant data [262](#), [267](#)
  - constant pointer to non-constant data [262](#), [266](#)
  - constant reference [695](#)
  - constant reference parameter [539](#)
  - constant run time [LIX](#)
  - constant string [279](#)
  - constructed inside out [650](#)
  - constructor [576](#)
    - conversion [696](#), [697](#), [709](#)
    - copy [693](#)
    - default [578](#)
    - default arguments [618](#)
    - defining [578](#)
    - explicit [709](#)
    - function prototype [585](#)
    - in a UML class diagram [579](#)
    - naming [578](#)
    - parameter list [578](#)
    - single argument [696](#), [697](#), [708](#), [709](#), [710](#)
  - constructor called recursively [693](#)
  - constructors and destructors called automatically [621](#)
  - constructors cannot be `virtual` [826](#)
  - constructors cannot specify a return type [576](#)
  - Constructors Throwing Exceptions [918](#)
  - container [533](#)
  - container class [612](#), [651](#), [692](#), [844](#)
  - `continue` [114](#), [116](#), [138](#)
  - Continue** command (debugger) [CVIII](#)
  - `continue` debugger command [CXXII](#)
  - control characters [316](#)
  - control statement [59](#)
  - control-statement nesting [58](#)
  - control-statement stacking [58](#)
  - control-structure stacking [59](#)
  - control structures [56](#)
  - control variable [98](#), [104](#)
    - increment [99](#)
    - initial value [99](#)
    - name [99](#)
  - controlling expression in a switch [111](#)
  - controlling the printing of trailing zeros and decimal points for `doubles` [869](#)
  - conversational computing [31](#)
  - conversion [930](#)
  - conversion among fundamental types [696](#)
    - by cast [697](#)
  - conversion constructor [696](#), [697](#), [709](#)
  - conversion operator [696](#)
  - conversion specifications [357](#)
  - conversion specifier [30](#), [32](#), [357](#)
    - e and E [359](#)
    - for `scanf` [370](#)
  - conversion specifier `c` [361](#)
  - conversion specifier `f` [360](#)
  - conversion specifier `g` (or `G`) [360](#)
  - conversion specifier `n` [362](#)
  - conversion specifier `s` [361](#)
  - convert [696](#)
    - a binary number to decimal [930](#)
    - a hexadecimal number to decimal [930](#)
    - among user-defined types and built-in types [696](#)
    - an octal number to decimal [930](#)
    - lowercase letters [534](#)
    - lowercase letters to uppercase letters [152](#)
  - Converting a string to uppercase using a non-constant pointer to non-constant data [263](#)
  - Converting Fahrenheit to Celsius [887](#)
  - Cooking with Healthier Ingredients [354](#)
  - copy [152](#)
  - “copy-and-paste” approach [743](#)
  - copy constructor [628](#), [649](#), [691](#), [693](#), [695](#)
  - Copying a string using array notation and pointer notation [278](#)
  - copying strings [326](#)
  - correction [14](#)
  - `cos` function [143](#)
  - cosine [143](#)
  - counter [64](#), [91](#)
  - counter-controlled loop [73](#)
  - counter-controlled looping [74](#)
  - counter-controlled repetition [64](#), [99](#), [100](#)
  - Counter-controlled repetition with the `for` statement [100](#)
  - counting letter grades [110](#)
  - counting loop [100](#)
  - `cout` (`<<`) (the standard output stream) [854](#), [855](#)
  - `cout` (standard output stream object) [531](#)
  - `cout.put` [857](#)
  - `cout.write` [862](#)
  - CPU [4](#), [14](#)
  - craps (casino game) [158](#), [193](#)
  - “crashing” [68](#)
  - create new data types [532](#), [664](#), [665](#)
  - create sentences [348](#)
  - `create_bitmap` [IV](#)
  - `CreateAndDestroy` class
    - definition [622](#)
    - member-function definitions [622](#)
  - Creating and traversing a binary tree [479](#)
  - credit limit problem [90](#)
  - credit limits [135](#)
  - crossword puzzle [252](#), [937](#)
  - crossword puzzle generator [354](#)
  - `<csdtlib>` header file [533](#), [906](#)
  - `<csdtio>` header file [534](#)
  - `<cstring>` header file [534](#)
  - `<ctime>` header file [533](#)
  - `<Ctrl>` [c](#) [518](#)
  - `<Ctrl>-z` [866](#)
  - `<ctype.h>` header file [312](#), [152](#), [499](#)
  - Cube a variable using call by reference [259](#)
  - Cube a variable using call by value [258](#)
  - custom header [151](#)
  - Cywin [xxvii](#), [LXXX](#)
- ## D
- dangerous pointer manipulation [818](#)
  - dangling `else` problem [93](#)
  - dangling pointer [694](#)
  - dangling reference [541](#)
  - data [4](#)
  - data abstraction [636](#), [664](#), [685](#)
  - data hiding [572](#), [574](#)
  - data hierarchy [418](#)
  - data member [562](#), [569](#), [570](#), [605](#)
    - `private` [572](#)
  - data member of a class [552](#)
  - data representation [665](#)
  - data structure [455](#)
  - data type [664](#)
  - data types in the UML [569](#)
  - data typing [7](#)
  - database [420](#)
  - database management system (DBMS) [420](#)
  - datafile [XLII](#), [XLIII](#), [XLIV](#), [XLVI](#), [LI](#)
  - DATAFILE type [XLVII](#)
  - date [152](#)
  - `Date` class [633](#), [646](#), [699](#)
  - `Date` class (exercise) [599](#)
  - `Date` class definition [646](#)
  - `Date` class definition with overloaded increment operators [700](#)
  - `Date` class member function definitions [646](#)
  - `Date` class member-function and friend-function definitions [701](#)
  - `Date` Class Modification [669](#)
  - `Date` class test program [703](#)
  - `__DATE__`, predefined symbolic constant [501](#)
  - DBMS [420](#)
  - deallocate [682](#)
  - deallocate memory [457](#), [682](#), [907](#)
  - debug [15](#), [56](#)
  - debugger [499](#), [CV](#), [CXXI](#)
    - Autos** window displaying state of objects [CXV](#)
    - `break` command [CXXI](#)
    - `break` mode [CVII](#), [CVIII](#), [CXXI](#)
    - breakpoint [CV](#), [CXIX](#)
    - Continue** command [CVIII](#), [CVIII](#)
    - `continue` command [CXXII](#)
    - convenience variable (GNU debugger) [CXXII](#)

debugger (cont.)

- defined [CV](#), [CXIX](#)
- delete command [CXXIII](#)
- finish command [CXXVII](#)
- g compiler option [CXX](#)
- gdb command [CXX](#)
- help command [CXXI](#)
- info break command [CXXIII](#)
- inserting a breakpoint [CVII](#)
- inserting breakpoints [CXXI](#)
- Locals window [CIX](#)
- Locals window (Visual C++ 2005 debugger) [CX](#)
- logic error [CV](#), [CXIX](#)
- margin indicator bar [CVII](#)
- next command [CXXVIII](#)
- print command [CXXII](#)
- quit command [CXXIII](#)
- run command [CXX](#)
- set command [CXXIV](#), [CXXV](#)
- Solution Configurations
  - combobox [CVII](#)
  - step command [CXXVI](#)
  - Step Into command [CXII](#)
  - Step Out command [CXIII](#)
  - Step Over command [CXII](#)
- suspending program execution [CX](#), [CXXIV](#)
- watch command [CXXVIII](#)
- Watch window (Visual C++ 2005) [CX](#), [CXI](#)

DEC PDP-11 7

dec stream manipulator [863](#), [868](#), [872](#)

decimal 138, 312, 320

decimal (base 10) number system [925](#)

decimal (base-10) number system 868

decimal digits [418](#)

decimal numbers 872

decimal point 857, 869

decision 27, 38, 42, 64

decision symbol 57, [59](#)

decisions [27](#), [38](#)

decisions (made by computers) [2](#)

deck of cards 280, 281

declaration of a function 584

Declaring a loop counter before a for statement in C89 [LXXXII](#)

declaring a static member function const 664

Declaring a variable in a for statement header in C99 [LXXXIII](#)

decomposition 144

decrement [99](#), [103](#), [274](#)

decrement a pointer 273

decrement operator ([--](#)) [78](#)

decrement operators 698

decrypt 96

default access mode for class is private 572

default argument [542](#), [544](#), [615](#)

default arguments with constructors 615

default case 111, 112, 113

default constructor [576](#), [578](#), [615](#), [651](#), [691](#), [693](#), [700](#), [842](#)

- provided by the compiler 578

- provided by the programmer 578

default copy constructor 649

default delimiter 861

default memberwise assignment [627](#)

default memberwise copy 693

default precision [72](#), [360](#)

default to decimal 872

default type for a type parameter [844](#)

define a class [563](#)

define a constructor 578

define a member function of a class [562](#)

#define preprocessor directive 201, 496, [604](#), [834](#)

definite repetition [65](#), [98](#)

definition [29](#), [30](#)

Deitel Buzz Online newsletter [16](#)

delete 694, 695, 907, 909

delete [] (dynamic array deallocation) 684

delete debugger command [CXXIII](#)

delete operator [682](#), [826](#)

deleting a node from a list 466

deleting dynamically allocated memory 694

delimiter (with default value '\n') 859

delimiting characters [336](#)

demonstrating class template Stack 838, 840

DeMorgan's Laws 138

Department of Defense (DOD) 10

depth of a binary tree 492

<deque> header file 533

dequeue [473](#)

dequeue 472

dequeue operation [665](#)

dereferencing a pointer [256](#)

dereferencing a void \* pointer 275

dereferencing operator (\*) [256](#), [386](#)

derive one class from another [609](#)

derived class [728](#), [729](#), [731](#), [771](#)

- indirect 813

derived-class destructor 826

derived-class catch 910

derived data type [383](#)

design a system 553

designated initializer [LXXXIV](#), [LXXXVI](#)

destroy\_bitmap IV, IX

destroy\_font XXVI

destroy\_midi LI

destroy\_sample XVII

destructive [33](#)

destructor [620](#), [744](#)

- called in reverse order of constructors

- 621

- member object 917

- overloading 620

- receives no parameters and returns no value 620

destructor in a derived class 763

destructors called in reverse order 763

determining the length of strings [326](#)

devices 12, 14

diagnostics 152

diagnostics that aid program debugging 534

diameter of a circle 95

diamond symbol [57](#), [59](#), [64](#)

dice game 158

dice rolling 158

dice-rolling program 206

Dice-rolling program using arrays instead of switch 206

dictionary 452

digit 52, [925](#)

Digital Clock application

Autos window displaying the state of localtime [CXV](#)

digital sample XVI

direct base class [728](#)

directly reference a value 254

disk 14, 15

disk drive 853

disk I/O completion 897

disk space 904, 906

displacement [434](#), [821](#)

display 14

display a binary tree 494

display screen 853, 855

Displaying an unsigned integer in bits 395

Displaying Text in Allegro [XXV](#)

Displaying the value of a union in both member data types 393

distance between two points 191

distributed client/server applications 5

distributed computing [5](#)

divide and conquer [141](#), [144](#)

divide by zero 14

DivideByZeroException 897

division 4, 34

division by zero 68, 518

division by zero is undefined 665

do...while repetition statement 57

do...while statement example 114

do/while repetition statement 113

document program [24](#)

document programs [24](#)

dot (.) operator [565](#)

dot operator (.) 386, 610, 655, 793, 908

double 149, 170

double-array subscripting 720

double backslash (\\) 26

double buffering [IX](#), [XIII](#)

double complex XC

double equals 39

double for Sudoku [939](#), [942](#)

double indirection (pointer to a pointer) [463](#)

double primitive type 106

double quote character (") 26

double quotes 32, 361

double-selection statement [57](#), [74](#)

double-subscripted array [229](#), [232](#)

double-subscripted array problem 246

double-subscripted array representation of a deck of cards 281

double-subscripted array 281

"doubly initializing" member objects 651

downcasting [792](#), [798](#)

drawing graphs 135

drawing primitives in Allegro LI

driver program [580](#)

dual-core processor 5

dummy value [67](#)

dump 306

dunning letters 353

duplicate elimination 244, 250, [483](#), [492](#)

duration 162, 164

dynamic array [521](#)

dynamic binding [780](#), [793](#), [818](#), [822](#)

dynamic casting [780](#)

dynamic content 9

dynamic data structure 196, 254, **455**  
 dynamic memory 907  
 dynamic memory allocation **456**, 520  
 dynamic memory management 254, **682**  
`dynamic_cast` **825**, 910  
 dynamically allocate array of integers 692  
 dynamically allocated memory 627, 629, 694, 826, 907  
     allocate and deallocate storage 621  
 dynamically allocated storage 693  
 dynamically determine function to execute 792

## E

EBCDIC (Extended Binary Coded Decimal Interchange Code) **330**  
 Eclipse 12  
 edit phase **12**, 14  
 editor 12, 310  
 editor program **12**  
 efficiency of  
     insertion sort LXVII  
     merge sort LXXII  
     selection sort LXIII  
 Eight Queens 175, 250, 251, 942  
 Eight Queens: Brute Force approach 250  
 element of an array 196  
 elements **196**  
 ellipsis (...) in a function prototype **509**  
 emacs 12  
 embedded parentheses **35**  
`Employee` class 646  
`Employee` class (Exercise) 599  
`Employee` class definition showing composition 648  
`Employee` class definition with a static data member to track the number of `Employee` objects in memory 661  
`Employee` class header file 804  
`Employee` class hierarchy driver program 815  
`Employee` class implementation file 805  
`Employee` class member function definitions, including constructor with a member-initializer list 648  
`Employee` class member-function definitions 661  
 empty exception specification **900**  
 empty member function of `string` **707**  
 empty parameter list 542  
 empty parentheses 564, 565, 568  
 empty statement 63  
 empty string **574**  
 encapsulation **552**, 575, 607, 627, 651  
 encrypt 96  
 end line 531  
 "end of data entry" 67  
 end-of-file 110, 877  
 end-of-file marker **420**, 423  
`END_OF_MAIN` IV  
`#endif` preprocessor directive **604**  
`endl` stream manipulator 531  
 end-of-file indicator 312, 323  
 end-of-file key combination 508  
 Enforcing Privacy with Cryptography 96  
 English-like abbreviations 6  
 Enhancing Class `Date` exercise 633  
 Enhancing Class `Rectangle` exercise 634  
 Enhancing Class Time exercise 632, 633  
 enqueue 665  
 enqueue **472**, **473**  
 enqueue operation **665**  
 Enter key 112, 531  
 enter key 14, **31**  
`enum` **161**, 406  
 enumeration **161**, 406, 407  
 enumeration constant 499  
 enumeration constants **161**, **406**  
 Enumeration example 407  
 environment 12  
 EOF 110, 312, 858, 861  
 eof member function 858, 877, 878  
 eofbit of stream **877**  
 equality and relational operators 275  
 equality operator (==) 685  
 equality operators **38**, 39  
`<errno.h>` 152  
 Erroneous attempt to initialize a constant of a built-in data type by assignment 644  
 error bits 861  
 error checking (in file processing) 436  
 error conditions 152  
 error detected in a constructor 903  
 error message 14  
`#error` preprocessor directive 500  
 error-processing code 891  
 error state of a stream 858, 877  
 errors 14  
 escape character **26**, 369  
 escape sequence **26**, 32, 369, 381  
 Euler 247  
 event **518**  
 ex 143  
 examination results problem 75  
 exception **890**  
 exception class **892**, 909  
     what virtual function **892**  
 exception classes derived from common base class 904  
 exception handler **894**  
 exception handling 534, **890**  
`<exception>` header file 534, **892**, 901, 910  
 exception not listed in exception specification 900  
 exception object **896**  
 exception parameter **895**  
 exception specification **900**  
 Exception-handling example that throws exceptions on attempts to divide by zero 893  
 Exceptions  
     `bad_alloc` **904**  
     `bad_cast` **910**  
     `bad_exception` **910**  
     `bad_typeid` 910  
     `length_error` **910**  
     `logic_error` **910**  
     `out_of_range` **910**  
     `overflow_error` 910  
     `underflow_error` 911  
 executable **27**  
 executable image **14**  
 executable program **27**  
 executable statement 531  
 execute 14

execute phase **12**  
 executes **14**  
 execution-time error 14  
 execution-time overhead 818  
 exhaustive brute force approach 943  
 exit a function **26**  
 exit and `atexit` functions 514  
 exit function **514**, **621**, 906, 911  
`EXIT_FAILURE` **514**  
`EXIT_SUCCESS` **514**  
 exp function 143  
 expand a macro **497**  
 explicit constructor **709**  
 explicit conversion **71**  
 explicit keyword 709  
 explicit specialization of a class template **845**  
 explicit use of the `this` pointer 654  
 exponent 726  
 exponential complexity 174  
 exponential format 358  
 exponential function 143  
 exponential notation **359**, 360  
 exponentiation 37  
 exponentiation operator 106  
 expression 107, 147  
 Extended Binary Coded Decimal Interchange Code (EBCDIC) 331  
 extensibility 781  
 extensibility of C++ 681  
 extensible language **554**, **565**, 665  
 extern **161**, **513**  
 external linkage **513**  
 external variable 163

## F

f or F for a float **516**  
 fabs function 143  
 factorial 95, 135  
 factorial function 168, 175  
 Fahrenheit temperatures 381  
 fail member function **877**  
 failbit of stream **858**, 862, 877  
 false **38**  
 false 874  
 false boolean value (C++) **536**  
 fatal error 14, 51, **68**, 307  
 fatal logic error 63  
 fault-tolerant programs **890**  
 FCB 420, 422  
 fclose function **423**  
`fenv.h` LXXX  
 feof function **422**, 436  
 fetch 305  
 fgetc function **420**, 452  
 fgets function **323**, **420**  
 Fibonacci function 175  
 Fibonacci functions 174  
 Fibonacci series 171, 190  
 field **418**  
 field width 107, **357**, **363**, 365, 374, 862, 865  
 fields larger than values being printed 871  
 FIFO (first-in first-out) **472**, **665**  
 FILE **420**  
 file **418**, **419**  
 file control block (FCB) **420**, 422  
 file descriptor **420**

file-matching program 449  
 file name 12  
 file offset [427](#)  
 file open mode [422](#), [425](#)  
 FILE pointer 426  
 file position pointer [427](#), [435](#)  
`__FILE__`, predefined symbolic constant 501  
 file processing 853, 856  
   error checking 436  
 file scope [164](#), [609](#)  
 FILE structure 420  
 filename extension  
   .h 580  
 file-processing classes 856  
 fill character [606](#), [863](#), [865](#), [870](#), [871](#)  
 fill member function 869, [871](#)  
 fill member function of `basic_ios` 878  
 final value [99](#)  
 final value of a control variable 102, 104  
 find the minimum value in an array 251  
 finish debugger command [CXXVII](#)  
 first-in first-out (FIFO) [472](#), [665](#)  
 first refinement [67](#), [73](#)  
 five-card poker 297  
 fixed notation 857, 868, 873  
 fixed stream manipulator 869  
 fixed stream manipulator 868, [873](#)  
 fixed word size 665  
 flag value [67](#)  
 flags [357](#), 366, 367  
 flags member function of `ios_base` [876](#)  
 flexible array member [XCIV](#)  
 flight simulator 830  
 (float) 71  
 float [516](#)  
 float [69](#), 71, 72, 150  
 <float.h> 152  
 floating point 360, 864, 868, 873  
 floating-point arithmetic 673  
 floating-point conversion specifiers 360, 364, 370  
 floating-point exception [518](#)  
 floating-point number 66, [69](#), 72  
 floating-point number in scientific format 873  
 floating-point size limits 152, 534  
 floating-point values displayed in default, scientific and fixed format 873  
 floor function 143  
 flow of control [42](#)  
 flow of control of a virtual function call 820  
 flowchart [56](#), 59  
 flowcharting C's sequence structure 57  
 flowcharting double-selection if/else statement 60  
 flowcharting the `do...while` repetition statement 114  
 flowcharting the `while` repetition statement 64  
 flowline 59  
 flowlines [57](#)  
 flush buffer 879  
 flush output buffer 531  
 flushing stream 863  
 fmod function 143  
 fmtFlags data type [876](#)

font XXVII  
 FONT type [XXVI](#)  
 fopen function [425](#)  
 for header components 101  
 for repetition statement 57, 103, 943  
 force a decimal point 857  
 forcing a plus sign 870  
 formal type parameter [549](#), [549](#)  
 format control string [30](#), [32](#), [357](#), [358](#), 365, 369  
 format error 877  
 format of floating-point numbers in scientific format 873  
 format state 863, [876](#)  
 format-state stream manipulators 868  
 formatted I/O [853](#)  
 formatted input/output model [430](#)  
 formatting 862  
 form-feed character (\f) 312  
 forming Sudoku puzzles 944  
 FORTRAN (FORmula TRANslator) [10](#)  
 forward class declaration [712](#)  
 fprintf function [421](#)  
 fputc function 420  
 fputs function [420](#), [452](#)  
 fractional parts 71  
 fractions 725  
 fragile software [755](#)  
 fread function [421](#), [431](#)  
 free function 456, [471](#)  
 free store [682](#)  
 friend 676, 833, 845  
 friend function 651, 675, 732  
 friend functions to enhance performance 651  
 friend of class template 845  
 friends are not member functions 652  
 Friends can access private members of class 652  
 friendship granted, not taken 652  
 friendship not symmetric 652  
 friendship not transitive 652  
 front of a queue 455, 665  
 fscanf function [421](#)  
 fseek function [433](#)  
 <fstream> header file 534  
 function [8](#), [13](#), [25](#), 126, [141](#), 532, 552  
   argument [142](#), 157, [566](#)  
   body [146](#), 175  
   call [142](#), 147  
   call and return 152  
   call stack [151](#)  
   caller [142](#)  
   empty parameter list 542  
   empty parentheses 564, 565, 568  
   header [146](#), [147](#), [564](#)  
   invoke [142](#), [145](#)  
   local variable [569](#)  
   multiple parameters 568  
   name 145, 163, 176  
   overloading [545](#)  
   parameter list [568](#), 568  
   parameter list [568](#)  
   prototype [145](#), 147, 148, 163, 538, [584](#)  
   prototype scope 163, [164](#)  
   return a result 573  
   return from [142](#), 143  
   scope [164](#)

function body 564  
 function call 566  
   overhead 535  
 function call operator () 698, 822  
 function call stack 265  
 function definition 568  
 function header 259, 269, 288  
 function in Sudoku 943  
 function name 285  
 function overloading 852  
 function parameter 260, 262, 266  
 function parameter as a local variable 568  
 function pointer 285, 286, [289](#), 819, 822  
 function prototype [107](#), 259, 262, 270, [584](#), 651  
   parameter names optional 585  
   semicolon at end 585  
 function prototype for printf 509  
 function template [548](#), [833](#), 837  
   max 559  
   min 559  
   specialization [548](#)  
 Function Template Overloading 849  
 function validSudoku 944  
 <functional> header file 534  
 functions for manipulating data in the standard library containers 534  
 function-template definition [834](#)  
 function-template specialization [833](#)  
 fwrite [421](#), [431](#), [433](#)

## G

-g command-line compiler option [CXX](#)  
 game of craps 158, 246  
 game players 252, 937  
 game playing 153  
 Game programming xxviii  
 game programming 2, II  
 "garbage value" [66](#)  
 gcc compilation command [14](#)  
 gcount function of `istream` [862](#)  
 gdb command [CXX](#)  
 Gender Neutrality 22, 355  
 general utilities library (stdlib) [317](#)  
 generalities 781  
 generating a Sudoku puzzle 943  
 generating mazes randomly 301  
 Generating the values to be placed into elements of an array 201  
 generic class 838  
 generic pointer 275  
 generic programming [529](#), [833](#)  
 get a value 574  
 get and set functions 574  
 get member function 858, 859  
 get, put and eof member functions 859  
 getc 499  
 getchar [324](#), 324, [420](#), 452, 499  
 getchar() [420](#)  
 getline function of `cin` [860](#)  
 getline function of the string header file [567](#), 574  
 gets 39  
 GFX\_AUTODETECT VI  
 GFX\_AUTODETECT\_FULLSCREEN VI  
 GFX\_AUTODETECT\_WINDOWED VI  
 GFX\_SAFE VI  
 GFX\_TEXT VI

global 586  
 global function 845  
 global function to overload an operator 677  
 global namespace scope 660, 846  
 global object constructors 621  
 global scope 622  
 global variable 162, 163, 164, 270, 392, 512, 544  
 Global Warming Facts Quiz 193  
 global, friend function 681  
 global, non-friend function 675  
 GNU GCC 4.3 xxvii  
 golden mean 171  
 golden ratio 171  
 good function of `ios_base` **878**  
 Good Programming Practices overview xxv  
 goodbit of stream **878**  
 goto 521  
 goto elimination **56**  
 goto-less programming 56  
 goto statement **56**, 164, **521**, 522  
 grabber **XLII**, **XLIII**, **XLVI**  
 graphics 252, 937  
 graphics in Allegro 252, 938  
 graphics package 830  
 Greatest common divisor 175  
 guess the number exercise 189  
 guillemets (« and ») in the UML 579

## H

.h header files 535  
 halt 306  
 halt instruction 304  
 handle on an object **609**  
 hard disk 4, 12  
 hardcopy printer 14  
 hardware **2**, 4, 6  
 hardware independent 7  
 hardware platform **7**  
 hardware registers 162  
 has-a relationship 729, **645**  
 head of a queue **455**, **472**  
 header **25**, 151, 152, 496, 535  
 header file 152, 533, **580**, 588, 604, 772, 822  
   <ctype.h> 312  
   <exception> 534, **892**  
   <fstream> 534  
   <functional> 534  
   <iomanip> 533  
   <iostream> 533  
   <iterator> 534  
   <limits> 534  
   <list> 533  
   <locale> 534  
   <memory> 534, **907**  
   <queue> 533  
   <set> 533  
   <sstream> 534  
   <stack> 533  
   <stdexcept> 534, **892**, 910  
   <string> 534, **567**  
   <typeinfo> 534, **825**  
 Allegro datafile XLVI, XLVII  
 complex.h XC  
 fenv.h LXXX  
 heap **682**  
 help debugger command **CXXI**  
 helper function **612**  
 heuristic 248  
 heuristic problem solving approach 942, 944  
 hex stream manipulator **863**, 868, **872**  
 hexadecimal 137, **313**, 320, 358, 363  
 hexadecimal (base 16) number system **925**  
 hexadecimal (base-16) number 857, 863, 868, 872  
 hexadecimal integer 256  
 hexadecimal notation 857  
 hide an internal data representation 665  
 hide implementation details 651, 712  
 hide private data from clients 611  
 hierarchical boss function/worker function relationship 142  
 hierarchy of exception classes 909  
 hierarchy of shapes 799  
 high-level language **7**  
 highest level of precedence 35  
 high-level I/O 853  
 High-performance card shuffling and dealing simulation 389  
 histogram 135, 205  
 Histogram printing 205  
 history of Sudoku 938  
 horizontal tab (\t) 26, 312  
 host object **646**  
 HourlyEmployee class header file 809  
 HourlyEmployee class implementation file 810  
 Huge integers 725  
 HugeInt class 722  
 HugeInteger Class exercise 634  
 hypotenuse of a right triangle 187

header files (cont.)  
 inttypes.h LXXX  
 iso646.h LXXX  
 location 583  
 name enclosed in angle brackets (< >) 583  
 name enclosed in quotes (" ") 583  
 stdbool.h LXXXVII  
 stdint.h LXXX  
 tgmth.h LXXX  
 wchar.h LXXX  
 wctype.h LXXX  
 implementation inheritance **802**  
 implementation of a member function changes 618  
 Implementing a proxy class 714  
 implicit conversion **71**, 698, 708, 709, 711  
   via conversion constructors 709  
 implicit first argument 654  
 implicit handle 609  
 implicit int LXXXIX  
 implicit, user-defined conversions 698  
 implicitly virtual 793  
 Importing and Playing Sounds in Allegro **XVI**  
 Importing Bitmaps in Allegro **IV**  
 importing fonts in Allegro XXVI  
 improper implicit conversion 708  
 INCITS/ISO/IEC 9899-1999 (C standard document) 8  
 #include preprocessor directive 202, **496**, 535  
 including a header file multiple times 604  
 including headers 151  
 increment 103  
 increment a control variable **99**  
 increment a pointer 273  
 increment of a control variable 102, 104  
 increment operator 698  
 increment operator (++) **78**  
 incremented 274  
 indefinite postponentment **281**, 297  
 indefinite repetition **67**, **98**  
 indent 27  
 indentation 58, 60, 62  
 independent software vendor (ISV) 532, 611, 771, 822  
 index (or subscript) **196**  
 indirect base class **728**, 731  
 indirect derived class 813  
 indirection **254**, 258  
 indirection operator (\*) 152, **256**, 258  
 indirectly reference a value 254  
 inequality operator (!=) 685  
 infinite loop 63, 71, 102  
 infinite recursion 170, 693  
 infix notation **489**  
 infix-to-postfix conversion 489  
 info break debugger command **CXXIII**  
 information hiding **164**, 267, **552**, **664**  
 inherit implementation 830  
 inherit interface 799, 830  
 inherit members of an existing class **728**  
 inheritance **551**, 603, **609**, **728**, 731, 771, 822, 833  
   implementation vs. interface inheritance **802**  
 Inheritance Advantage 775  
 inheritance examples 730  
 inheritance hierarchy 793, 801  
 Inheritance hierarchy for university CommunityMembers 730  
 inheritance relationships of I/O-related classes 856  
 inheriting interface versus inheriting implementation 830  
 initial value of a control variable **99**, 104  
 initialization phase 69  
 initialize a constant of a built-in data type 641



initialize to a consistent state 615  
 initialize with an assignment statement 643  
 initializer 199  
 initializer list 207  
 initializing a reference 540  
 initializing an array 200  
 Initializing multidimensional arrays 230  
 initializing structures 386  
 Initializing the elements of an array to zeros 198  
 Initializing the elements of an array with an initializer list 199  
 inline function 535, 535, 611, 677, 695, XCVIII  
   calculate the volume of a cube 535  
 inline keyword 535  
 inner block 164  
 innermost pair of parentheses 35  
 inorder 479  
 inOrder traversal 482  
 inorder traversal of a binary tree 176  
 input a line of text 860  
 input device 4  
 input from string in memory 534  
 input of a string using `cin` with stream extraction contrasted with input using `cin.get` 860  
 input/output (I/O) 852  
 input/output library functions 534  
 input stream 858, 859  
 input unit 4  
 input/output operators 302  
 input/output stream header (`<iostream>`) 530  
 inputting character data using `cin`  
   member function `getline` 861  
 Inputting characters and strings 372  
 Inputting data with a field width 374  
 Inputting Decimal, Octal and Hexadecimal Values 887  
 inserting a breakpoint CVII  
 Inserting and deleting nodes in a list 459  
 inserting literal characters 358  
 insertion sort algorithm LXIV, LXV, LXVII  
 install\_int XXXVII, XXXVIII  
 install\_keyboard VI, XX  
 install\_sound XVI  
 install\_timer XXXVII, XXXVIII  
 Installing Allegro II  
 instance of a class 570  
 instantiate an object of a class 552  
 instruction 14  
 instruction execution cycle 305  
 instructor resources for *Java How to Program, 8/e* xxvii  
 int 25, 150  
 integer 25, 29  
 integer arithmetic 673  
 integer array 196  
 Integer class definition 907  
 integer constant 267  
 integer conversion specifiers 358  
 integer division 34, 71  
 integers prefixed with 0 (octal) 872  
 integers prefixed with 0x or 0X (hexadecimal) 872  
 IntegerSet class 669

integral size limits 152, 534  
 integrity of an internal data structure 665  
 interactive attention signal 518  
 interactive computing 31  
 interface 552, 583, 780  
 Interface class definition 713  
 Interface class member-function definitions 713  
 interface inheritance 802  
 interface of a class 584  
 internal linkage 513  
 internal spacing 870  
 internal stream manipulator 868, 870  
 international Morse code 353  
 International Standards Organization (ISO) 2  
 Internet 5  
 interpreter 7  
 interrupt 518  
 inttypes.h LXXX  
 invalid access to storage 518  
 invalid\_argument class 910  
 inventory 451  
 inverted scan set 373  
 Invoice class (exercise) 599  
 invoke a function 142, 145  
 invoking a non-const member function on a const object 637  
 <iomanip> header file 533, 854, 863  
 ios\_base base class 877  
 ios\_base class  
   precision function 864  
   width member function 865  
 <iostream> header file 854, 855  
 <iostream> input/output stream header 530  
 <iostream> header file 533  
*is-a* relationship (inheritance) 729, 771, 780  
 isalnum function 312, 313  
 isalpha function 312, 313  
 iscntrl function 313, 316  
 isdigit function 312, 313  
 isgraph function 313, 316  
 islower 314  
 islower function 263, 312, 315  
 ISO 2  
 iso646.h header file LXXX  
 isprint function 313, 316  
 ispunct function 313, 316  
 isspace function 312, 316  
 istream 856  
 istream class  
   peek function 861  
 istream member function ignore 680  
 isupper function 312, 314, 315  
 ISV (independent software vendor) 532, 822  
 isxdigit function 312, 313  
 iteration 174  
 iterative function 225  
 iterator 801  
 iterator class 651, 801  
 <iterator> header file 534  
 ity of the operators 35

## J

Jacobson, Ivar 553, 554

Jacopini, G. 56  
 Java 9, 11, 252, 938  
 justified field 871

## K

keep your options open heuristic 944  
 Kernighan, B. W. 7, 15  
 key XII, XX  
 key value 223  
 keyboard 4, 28, 30, 323, 531, 853, 855  
 Keyboard Input XX  
 Keyboard Input in Allegro XX  
 keyboard symbolic constants, Allegro XX  
 keyword 42  
 Keywords  
   \_bool LXXXVII  
   \_complex XC  
   added in C99 42  
   C++ keywords 537  
   catch 895  
   class 549, 563, 834  
   const in parameter list of function 535  
   explicit 709  
   inline 535, XCVIII  
   private 571  
   public 564, 571  
   restrict XCVI  
   table of keywords 537  
   template 834, 834  
   throw 896  
   try 894  
   typedef 854  
   typename 549, 834  
   void 564

KIS ("keep it simple") 15  
 Knight's Tour 247, 942  
 Knight's Tour: Brute Force approaches 249  
 Knight's Tour: Closed tour test 251  
 Koenig, Andrew 890

## L

label 164, 521  
 Lady Ada Lovelace 10  
 large object 539  
 larger of two numbers 89  
 largest number problem 50  
 last-in-first-out (LIFO) 466  
 last-in, first-out (LIFO)  
   order 837, 842  
 last-in-first-out (LIFO) 151  
 late binding 793  
 leading 0 872  
 leading 0x and leading 0X 872  
 leading 0x or 0X (hexadecimal) 868  
 leading asterisks 352  
 leaf node 478  
 least access privilege 267  
 left brace { } 29  
 left child 478  
 left justification 357, 870  
 left justification and right justification with stream manipulators left and right 870  
 left justified 110  
 left justifying strings in a field 366

left side of an assignment 624, 692  
 left stream manipulator 869  
 left stream manipulator 868, **869**  
 left subtree **478**  
 left-shift operator (<) **394**, 414, 673, 855  
 legacy code 262  
 length member function of class string **590**  
 length modifier **358**  
 length of a substring 698  
 length\_error exception **910**  
 letters **418**  
 level order binary tree traversal 483, 493, **493**  
 library function 8  
 LIFO (last-in, first-out) 151  
     order 837, 842  
 LIFO (last-in-first-out) **466**  
 limerick exercise 349  
 <limits.h> header file 152  
 <limits> header file 534  
 <limits.h> header file 397  
 line XXXI, LI  
 line of text 860  
 \_LINE\_\_, predefined symbolic constant 501  
 #line preprocessor directive **501**  
 linear data structure 458  
 linear data structures **478**  
 linear run time **LIX**  
 linear search 175, **223**, 223, 251  
 link (pointer in a self-referential structure) **456**  
 link phase **12**  
 link to a class's object code 611  
 linkage **161**  
 linkage of an identifier **162**  
 linked list 254, 383, **455**, **458**  
 linked list delete 176  
 linked list insert 176  
 linker **13**, 27, 513  
 linker error 513  
 linking **13**  
 links **458**  
 Linux 5, 12, 14, 508  
 list debugger command **CXXI**  
 <list> header file 533  
 literal **26**, 32  
 literal characters **357**  
 live-code approach xxiii, 2  
 ll length modifier for integer conversion specifiers XCVII  
 -lm command line option for using the math library 106  
 Load 305  
 load a program into memory 302  
 load instruction 304  
 load phase **12**  
 load\_bitmap IV, VII  
 load\_datafile XLVII  
 load\_font XXVI  
 load\_midi LI  
 load\_sample XVII  
 load/store operations 303  
 loader **14**  
 loading **14**  
 local area network (LAN) **5**  
 local automatic object 623

local scope 609  
 local variable **144**, 162, 163, 209, **569**  
 Local Variable Destructors 917  
 locale 152  
 <locale> header file 534  
 <locale.h> 152  
**Locals** window **CIX**  
**Locals** window (Visual C++ 2005 debugger) CX  
 location 33  
 log function 143  
 log10 function 143  
 log<sub>2</sub>*n* comparisons 483  
 logic error 39, 63, 66, 101, 120, 149, 202, 392, CV, CXIX  
 logic\_error exception **910**  
 logical AND operator (&&) **116**, 116, 397  
 logical decision 3  
 logical negation (NOT) operator (!) **117**, 118  
 logical OR operator (||) **116**, 399  
 logical page 369  
 logical unit **4**  
 Logo language 246  
 long 113, 168  
 long double 150, **516**  
 long int 150, 168, **516**  
 long integer **516**  
 long long int XCVII  
 lookahead heuristic for solving Sudoku 944  
 loop 67, 101  
 loop continuation condition 101, 102, 103, 113  
 loop counter 102  
 loop-continuation condition **98**  
 looping 101  
 Lord Byron 10  
 loss of data 878  
 Lovelace, Ada 10  
 lowercase letter 51, 152, 534  
 low-level I/O capabilities 853  
 lvalue ("left value") **120**, 196, 540, 624, 692, 696

## M

Mac OS X 5  
 machine dependent **6**, 394, 665  
 machine independent 7  
 machine language **6**, 12  
 machine language code 12  
 machine language programming 302  
 Macintosh 866  
 macro 152, **496**, **497**, 834  
 macro definition 497  
 macro expansion 498  
 macro identifier **497**  
 macro with arguments **497**  
 Macros  
     complex XC  
 macros **834**  
 macros defined in stdarg.h 509  
 magic drivers VI, XVI  
 magnitude 870  
 magnitude right justified 868  
 main 530  
 main () 25  
 mainframe **3**  
 maintenance of software 12  
 make **514**  
 make program III  
 makecol XXVII  
 Makefile III  
 makefile **514**  
 malloc **456**, 520  
 mangled function name 547  
 "manufacturing" section of the computer 4  
 <map> header file 533  
 margin indicator bar **CVII**  
 mask **396**, 396  
 master file 449  
 matching catch block 895  
 math library functions 152, 192, 533  
 <math.h> header file 106, 143, 152  
 mathematical classes 673  
 mathematical computations 10  
 maximum 91  
 maximum 147  
 maze traversal 175, 300  
 mazes of any size 301  
 m-by-n array **229**  
 mean 218  
 meaningful names 569  
 median 218  
 member 383  
 member function **552**, 562  
     call **562**, 673  
     calls for const objects 637  
     calls often concise 607  
     defined in a class definition 606  
     implementation in a separate source-code file 586  
     that takes no arguments 607  
 member function automatically inlined 606  
 member initializer **641**, 643, 694  
 member initializer for a const data member 643  
 member-initializer list **642**, 646, 648, 649  
 member-initializer syntax 641  
 member name (bit field) **403**  
 member object destructors 917  
 member-object initializer 650  
 member object's default constructor 651  
 member selection operator (.) 610, 655, 793, 908  
 member-function  
     parameter **566**  
 member-function argument **566**  
 members **383**  
 memberwise assignment **627**, 674  
 memberwise copy 693  
 memchr **340**  
 memchr function 337, **340**  
 memcmp function 337, **339**  
 memcpy function 337, **338**  
 memmove function **338**, 339  
 memory **4**, 14, 15, 33  
 memory access violation 262  
 memory addresses 254  
 memory allocation 152  
 memory consumption 818  
 memory functions of the string handling library 337  
 <memory> header file 534, **907**



memory leak **683**, 907, 909  
     prevent 909  
 memory unit 4  
 memory utilization 403  
**memset** function **337**, **340**  
 menu-driven system **289**  
 merge sort algorithm **LXVII**, **LXVIII**, **LXXII**  
 merge two arrays **LXVII**  
 message **26**, 551, 673  
 message (send to an object) **562**  
 method **552**  
 metric conversion program 353  
 Microsoft Visual C++ 2008 Express Edition **LXXIX**  
 Microsoft Visual Studio 12  
 Microsoft's Windows-based systems 5  
 MIDI type LI  
 mileage problem 89  
 MinGW xviii  
 MinGW (Minimalist GNU for Windows) **LXXX**  
 minimum value in an array 175  
 minus sign, – (UML) 575  
 mission-critical computing 896  
 mission-critical situation 911  
 mixed-type expressions **150**  
 mixing declarations and executable code **LXXXI**  
 mobile device Sudoku games 938  
 mode 218, 244  
 modifiable *lvalue* 692, 696, 708  
 modifications to the simpletron simulator 307  
 Modifying Class *GradeBook* (Exercise) 599  
 module **141**  
 monetary calculations 107  
 monetary formats 534  
 Moore's Law **15**  
 Morse code 353  
 mouse 4  
 multi-core processor **5**  
 multidimensional array 229, 230  
 multiple inheritance **728**, 731, 855  
 multiple parameters to a function 568  
 multiple selection statement **57**, 111  
 multiple-source-file program  
     compilation and linking process 588  
 multiple-source-file programs 162, 164  
 multiple source files 512, 513  
 multiple-subscripted array 229, 231  
 multiple-word variable name 30  
 multiples of an integer 94  
 multiplication 34  
 multiplicative operators **72**  
 multiply two integers 175  
 multiprocessor **5**  
 Multipurpose sorting program using function pointers 286  
 multitasking **10**  
 mutator **574**

## N

n **362**  
 n factorial (n!) 168  
 n! 168  
 name 99, **196**

name a control variable **99**  
 name decoration **547**  
 name function of class *type\_info* **825**  
 name handle 609  
     on an object 609  
 name mangling **547**  
     to enable type-safe linkage 547  
 name of a user-defined class 563  
 name of a variable 33  
 name of an array 196  
 natural language of a computer 6  
 natural logarithm 143  
 negative value **932**  
 negative binary numbers 924  
     nested **74**  
 nested building block 121  
 nested control statement 73  
 nested for structure 282  
 nested if...else statement **61**, 62  
 nested iteration structure 942  
 nested parentheses **35**, 37  
 nesting **73**  
 nesting (of statements) 100  
 nesting rule **121**  
 .NET platform **10**  
 network connection 853  
 network message arrival 897  
 new 694  
 new calls the constructor 683  
 new fails 903, 912  
 new failure handler **905**  
 <new> header file 904  
 new operator **682**  
 new returning 0 on failure 905  
 new stream manipulators 866  
 new throwing *bad\_alloc* on failure 904  
 new\_handler function 912  
 newline (\n) **26**, 41, 58, 208, 310, 311, 312, 374, 531, 858  
*noboolalpha* stream manipulator **874**  
 nodes 456, **458**  
 non-static member function 696  
 non-const member function 641  
 non-const member function called on a const object 640  
 non-const member function on a non-const object 640  
 non-constant pointer to constant data **262**, 264, 265  
 non-constant pointer to non-constant data **262**  
 nondestructive **34**  
 nonfatal error 14, 51, 149, 911  
 nonfatal logic error 63  
 nonmodifiable function code 609  
 nonrecoverable failures 878  
 nonrecursive function 190  
 non-static member function 654, 663  
 nontype template parameter **844**  
 nonvirtual destructor **826**  
*noshowbase* stream manipulator 868, **872**  
*noshowpoint* stream manipulator **869**  
*noshowpos* stream manipulator 868, **870**  
*noskipws* stream manipulator 868  
 nothrow object **905**  
 nothrow\_t type 905  
 noun 11  
 nouns in a system specification 552

*nouppercase* stream manipulator 868, **874**  
 NULL 157, 255, 275, 279, **422**, **456**, 464  
 null character ('\0') **207**, 208, 264, 279, **310**, 311, 490, 863  
 NULL pointer 521  
 null pointer (0) 493  
 null-terminated string 280, 857  
 Number Systems Appendix 924  
 numeric codes **330**  
 numerical data type limits 534

## O

*O*(1) **LIX**  
*O*(*n* log *n*) time **LXXIII**  
*O*(*n*) time **LIX**  
*O*(*n*<sup>2</sup>) time **LX**, **LXIII**, **LXVII**  
 object 9, 11, 562  
 object (or instance) **551**  
 object code 6, **12**, 588, 611  
 object code of a class 611  
 object file 822  
 object handle 610  
 object leaves scope 620  
 Object Management Group (OMG) **554**  
 object module 611  
 object of a derived class 782, 787  
 object of a derived class is instantiated 762  
 object orientation 551  
 object-oriented analysis and design (OOAD) 553  
 object-oriented design 9  
 object-oriented design (OOD) **551**, 652  
 object-oriented language 11, **552**  
 object-oriented programming 4  
 object-oriented programming (OOP) **529**, **552**, 553, 603, 728, 3, 9, 144  
 object program 27  
 object's *vtable* pointer 821  
 objects contain only data 609  
 oct stream manipulator **863**, 868, **872**  
 octal 137, 312, 320, 358  
 octal (base-8) number system 863, 868  
 octal number 857, 872  
 octal number system (base 8) **925**  
 off-by-one error **101**  
 offset **276**, **434**, **821**  
 "old-style" header files 533  
 OMG (Object Management Group) 554  
 one's complement **400**  
 one's complement notation **932**  
 ones position 925  
 OOAD (object-oriented analysis and design) 553  
 OOD (object-oriented design) **551**, 552  
 OOP (object-oriented programming) **552**, 553, 728  
 open a file 422  
 open file table **420**  
 operand **31**, 303  
 operating system 5, 7, 32  
 operation (UML) 565  
 operation in the UML **552**, 565  
 operation parameter in the UML 569  
 operations that can be performed on data **665**  
 operator functions 676  
 operator keywords 674

operator overloading [532](#), [548](#), [673](#), [852](#)  
 decrement operators [698](#)  
 increment operators [698](#)  
 Operator Overloads in Templates [849](#)  
 operator precedence [41](#)  
 operator precedence chart [919](#)  
 Operator sizeof when applied to an array name returns the number of bytes in the array [271](#)  
 operator void\* member function [878](#)  
 operator! member function [681](#), [878](#)  
 operator!= [695](#)  
 operator() [720](#)  
 operator[]  
   const version [696](#)  
   non-const version [696](#)  
 operator+ [674](#)  
 operator++ [699](#), [704](#)  
 operator++( int ) [699](#)  
 operator<< [680](#), [692](#)  
 operator= [694](#)  
 operator== [695](#)  
 operator>> [680](#), [692](#)  
 operators [77](#)  
   << (stream insertion operator) [532](#)  
   arrow member selection (→) [610](#)  
   binary scope resolution (::) [586](#)  
   delete [682](#)  
   dot (.) [565](#)  
   member selection (.) [610](#)  
   new [682](#)  
   sizeof [609](#)  
   typeid [825](#)  
   unary scope resolution (::) [544](#)  
 operators that can be overloaded [675](#)  
 optimizations on constants [636](#)  
 optimizing compiler [163](#)  
 order [55](#), [56](#)  
 order in which constructors and destructors are called [623](#)  
 order in which destructors are called [621](#)  
 order of evaluation  
   of operators [35](#)  
   order of evaluation of operands [173](#)  
 order of exception handlers [918](#)  
 order of operands of operators [173](#)  
 original format settings [876](#)  
 ostream class [854](#)  
 out-of-range array subscript [897](#)  
 out-of-range element [692](#)  
 out\_of\_range exception [910](#)  
 outer block [164](#)  
 output a floating-point value [868](#)  
 output buffering [879](#)  
 output data items of built-in type [856](#)  
 output device [4](#)  
 output format of floating-point numbers [873](#)  
 output of char \* variables [857](#)  
 output of characters [857](#)  
 output of floating-point values [857](#)  
 output of integers [857](#)  
 output of standard data types [857](#)  
 output of uppercase letters [857](#)  
 output to string in memory [534](#)  
 output unit [4](#)  
 oval symbol [57](#)  
 overflow [518](#), [897](#)  
 overflow error [664](#)

overflow\_error exception [910](#)  
 overhead of an extra function call [695](#)  
 overload an operator as a nonmember, non-friend function [677](#)  
 overload the addition operator (+) [674](#)  
 overload unary operator ! [681](#)  
 overloaded [] operator [692](#)  
 overloaded << operator [677](#)  
 overloaded addition assignment operator (+=) [700](#)  
 overloaded assignment (=) operator [691](#), [694](#), [698](#)  
 overloaded binary operators [675](#)  
 overloaded cast operator function [697](#)  
 overloaded equality operator (==) [691](#), [695](#)  
 overloaded function [833](#), [836](#)  
 overloaded function call operator () [698](#)  
 overloaded increment operator [700](#)  
 overloaded inequality operator [691](#), [695](#)  
 overloaded negation operator [698](#)  
 overloaded operator += [704](#)  
 overloaded operator[] member function [696](#)  
 overloaded postfix increment operator [700](#), [704](#)  
 overloaded prefix increment operator [700](#), [704](#)  
 overloaded stream insertion and stream extraction operators [679](#)  
 overloaded subscript operator [692](#), [696](#)  
 overloaded unary operators [675](#)  
 overloading [532](#), [545](#)  
   << and >> [548](#)  
   a member function [609](#)  
   function definitions [546](#)  
   operators [548](#)  
 overloading + [676](#)  
 overloading += [676](#)  
 overloading an assignment operator [676](#)  
 overloading binary operator < [682](#)  
 overloading binary operators [682](#)  
 overloading function call operator () [698](#), [720](#)  
 overloading postfix increment operator [699](#), [704](#)  
 overloading prefix and postfix decrement operators [700](#)  
 overloading prefix and postfix increment operators [700](#)  
 overloading resolution [837](#)  
 overloading stream insertion and stream extraction operators [678](#), [691](#), [692](#), [700](#), [704](#)  
 overloading template functions [837](#)  
 override a function [792](#)  
 overtime pay problem [91](#)

**P**

π [50](#), [137](#)  
 %p conversion specifier [362](#)  
 Package Inheritance Hierarchy [830](#)  
 Package inheritance hierarchy [776](#)  
 Package inheritance hierarchy exercise [776](#)  
 packets in a computer network [472](#)  
 pad with specified characters [857](#)  
 padding [404](#)

padding characters [865](#), [868](#), [869](#), [871](#)  
 page layout software [310](#)  
 palettes in Allegro VI  
 palindrome [251](#)  
 palindrome problem [94](#)  
 parallelogram [729](#)  
 parameter [144](#), [566](#), [568](#)  
 parameter in the UML [569](#)  
 parameter list [146](#), [177](#), [568](#), [578](#)  
 parameter of a function [145](#)  
 parameter passing [262](#)  
 parameter types [270](#)  
 parameterized stream manipulator [854](#), [863](#), [866](#)  
 parameterized type [838](#), [850](#)  
 parent node [479](#)  
 parentheses () [35](#), [41](#)  
 parentheses operator (()) [35](#)  
 partitioning step of Quicksort LXXVI  
 Pascal programming language [10](#)  
 Pascal, Blaise [10](#)  
 pass-by-reference [212](#), [537](#), [538](#)  
   with reference parameters [538](#)  
 pass-by-value [537](#)  
 passing an array [213](#)  
 passing an array element [213](#)  
 passing an object by value [629](#)  
 passing arguments by value and by reference [538](#)  
 Passing arrays and individual array elements to functions [213](#)  
 passing large objects [539](#)  
 Payroll System Modification [830](#)  
 Payroll System Modification exercise [830](#)  
 PDP-11 [7](#)  
 peek function of istream [861](#)  
 percent sign (%) [34](#)  
 perfect number [188](#)  
 perform a task [564](#)  
 performance [9](#), [533](#)  
 performance requirements [163](#)  
 persistent [5](#)  
 personal computer [3](#), [5](#)  
 Phishing Scanner [452](#)  
 Pig Latin exercise [349](#)  
 pipe symbol (|) [508](#)  
 piping [508](#)  
 Plauger, P.J. [532](#)  
 play\_fli LII  
 play\_midi LII  
 play\_sample XVII, XX  
 playing .fli format animations in Allegro LII  
 playing MIDI files in Allegro LII  
 plus sign [870](#)  
 plus sign, + (UML) [565](#)  
 Point Class [888](#)  
 Point class represents an x-y coordinate pair [783](#)  
 pointer [254](#), [255](#), [258](#)  
 pointer arithmetic [263](#), [273](#), [276](#), [350](#)  
 pointer arrow (→) operator [386](#)  
 Pointer comparisons [275](#)  
 pointer expression [276](#)  
 pointer handle [609](#)  
 pointer manipulation [818](#)  
 pointer notation [260](#), [276](#), [278](#)  
 pointer parameter [259](#)  
 pointer subscripting [276](#)

- pointer to a function [285](#)
- pointer to an object [606](#)
- pointer to pointer (double indirection) [463](#)
- pointer to the structure [386](#)
- pointer to void (`void *`) [275](#)
- pointer to void (`void *`) [456](#)
- pointer variable [267](#), [268](#), [907](#)
- pointer/offset notation [276](#)
- pointer/subscript notation [276](#)
- pointers to dynamically allocated storage [655](#), [695](#)
- pointers to functions [289](#)
- poker [296](#)
- poker playing program [671](#)
- poll [203](#)
- Polymorphic Banking Program Exercise Using Account hierarchy [831](#)
- Polymorphic Banking Program Using Account hierarchy [831](#)
- polymorphic exception processing [904](#)
- polymorphic programming [799](#), [801](#), [822](#)
- polymorphic screen manager [781](#)
- Polymorphic Screen Manager Using Shape Hierarchy (Project) [830](#)
- polymorphism [773](#), [779](#), [780](#)
- polymorphism and references [819](#)
- polymorphism as an alternative to switch logic [830](#)
- polynomial [37](#)
- Polynomial class [726](#)
- Pong II, IX
- pop [466](#), [467](#), [842](#)
- pop off a stack [151](#)
- portability [9](#), [15](#), [30](#)
- Portability Tips overview [xxvi](#)
- portable [8](#), [15](#)
- portable code [8](#), [532](#)
- portable language [15](#)
- portable programs [7](#)
- position number [196](#)
- positional notation [925](#)
- positional value [925](#), [926](#)
- positional values in the decimal number system [926](#)
- postincrementing [79](#)
- postdecrement operator [78](#)
- postfix increment and decrement operators [78](#)
- postfix notation [489](#)
- postincrement [704](#)
- postincrement operator [78](#)
- postorder [479](#)
- postOrder traversal [482](#), [483](#)
- postorder traversal of a binary tree [176](#)
- pow (power) function [37](#), [106](#), [107](#), [143](#)
- power [143](#)
- `#pragma` processor directive [500](#)
- precedence [35](#), [41](#), [197](#), [256](#)
- precedence not changed by overloading [675](#)
- precedence of arithmetic operators [36](#)
- precision [72](#), [357](#), [358](#), [360](#), [857](#), [862](#)
- `precision` function of `ios_base` [864](#)
- precision of floating-point numbers [864](#)
- precision setting [864](#)
- precompiled object file [713](#)
- predecrement operator [78](#)
- predefined symbolic constants [501](#)
- predicate function [463](#), [612](#)
- prefix increment and decrement operators [78](#)
- preincrement [704](#)
- preincrement operator [78](#)
- preincrementing [78](#)
- preincrementing vs. postincrementing [78](#)
- preorder [479](#)
- preOrder traversal [483](#)
- preorder traversal of a binary tree [176](#)
- preprocess phase [12](#)
- preprocessor [12](#), [151](#)
- preprocessor directive [12](#), [496](#), [496](#), [499](#), [530](#)
  - `#ifndef` [604](#)
  - `#define` [604](#)
  - `#endif` [604](#)
- preprocessor wrapper [604](#)
- prevent class objects from being copied [695](#)
- prevent memory leak [909](#)
- prevent one class object from being assigned to another [695](#)
- preventing header files from being included more than once [604](#)
- primary memory [4](#)
- prime number [188](#)
- primitive types
  - `bool` (C++) [536](#)
- principle of least privilege [162](#), [164](#), [216](#), [261](#), [262](#), [266](#), [269](#), [270](#), [612](#), [636](#)
- print a hollow square [94](#)
- print a linked list backwards [176](#)
- print a square [94](#)
- print a string backwards [175](#), [251](#)
- print an array [175](#), [251](#)
- print an array backwards [175](#)
- Print Array Range [849](#)
- print characters [314](#)
- print debugger command [CXXII](#)
- print patterns [135](#)
- `printArray` function template [834](#)
- printer [853](#)
- `printf` [357](#)
- `printf` [421](#)
- printing a string input at the keyboard backwards [175](#)
- Printing a string one character at a time using a non-constant pointer to constant data [264](#)
- Printing a Table of ASCII Values [888](#)
- printing an integer with internal spacing and plus sign [870](#)
- printing character [316](#)
- printing dates in various formats [352](#)
- printing keyboard inputs in reverse [175](#)
- Printing Pointer Values as Integers [887](#)
- Printing positive and negative numbers with and without the `+` flag [367](#)
- printing the address stored in a char \* variable [857](#)
- printing trees [494](#)
- Printing with Field Widths [887](#)
- `private` access specifier [571](#)
- `private` base class [771](#)
- `private` base-class data cannot be accessed from derived class [744](#)
- `private` inheritance [728](#), [731](#), [770](#)
- `private` members of a base class [731](#)
- `private static` data member [660](#)
- probability [153](#)
- procedural programming language [552](#)
- procedure [55](#)
- Processing a queue [473](#)
- processing phase [67](#), [69](#)
- processing unit [4](#)
- product [48](#)
- program [4](#)
- program clarity [15](#)
- program control [55](#)
- program execution stack [151](#)
- program in the general [779](#), [830](#)
- program in the specific [779](#)
- program termination [623](#)
- Program to simulate the game of craps [158](#)
- programmer [4](#)
- programmer-defined function [142](#)
- programmer-defined header file [535](#)
- Programmer-defined maximum function [147](#)
- programmer-defined termination function [901](#)
- Programming Projects [xxviii](#)
- programming Sudoku puzzle creators [252](#), [937](#)
- programming Sudoku puzzle solvers [252](#), [937](#), [942](#)
- promotion [71](#), [72](#)
- promotion hierarchy [150](#)
- promotion of primitive types [72](#)
- promotion rules [149](#)
- prompt [30](#)
- prompting message [879](#)
- proprietary classes [772](#)
- protected [732](#)
- protected access specifier [603](#)
- protected base class [771](#)
- protected base-class data can be accessed from derived class [753](#)
- protected inheritance [728](#), [731](#), [771](#)
- Protected vs. Private Base Classes [775](#)
- proxy class [611](#), [711](#), [714](#)
- pseudo-random numbers [156](#)
- pseudocode [55](#), [57](#), [77](#)
- `public` access specifier [564](#), [571](#)
- `public` base class [771](#)
- `public` inheritance [728](#), [731](#)
- `public` interface [572](#)
- `public` keyword [564](#), [571](#)
- `public` member of a derived class [731](#)
- `public` services of a class [584](#)
- `public static` class member [660](#)
- `public static` member function [660](#)
- pure specifier [800](#)
- pure virtual function [800](#), [818](#)
- push [466](#), [470](#), [842](#)
- push onto a stack [151](#)
- put member function [857](#), [858](#)
- `putback` function of `istream` [861](#)
- `putchar` [323](#), [420](#)
- `puts` [324](#), [452](#)
- Pythagorean Triples [137](#)

Quadrilateral Inheritance Hierarchy 776  
 qualified name 761  
 queue 254, 383, [455](#), [472](#), 473, [665](#)  
 <queue> header file 533  
*Quick Info* box [CVIII](#)  
 Quicksort LXXVI  
 quicksort 176, LXXVI  
 quit debugger command [CXXIII](#)

## R

r file open mode 425  
 r+ file open mode 425, 426  
 radians 143  
 radius 95  
 raise [518](#)  
 raising an integer to an integer power 175  
 rand 153  
 RAND\_MAX 153, 157  
 random number 152  
 random number generation 280, 348  
 random-access file [430](#), 433  
 randomizing [156](#)  
 range checking 684  
 Rational Class exercise 633  
 Rational Software Corporation 554  
 RationalNumber class 725  
 raw array 684  
 rb binary file open mode 516  
 rb file open mode 425  
 rb+ binary open file mode 516  
 rb+ file open mode 425  
 rdstate function of `ios_base` [878](#)  
 read a line of text 567  
 read characters with `getline` 567  
 read function of `istream` [861](#)  
 read member function 862  
 readability 40, 74, 100, 144  
 readkey IX  
 real number 7  
 reassign a reference 541  
 “receiving” section of the computer 4  
 record [265](#), [419](#), 421  
 record key [419](#)  
 recover from errors 877  
 rectangle 59  
 Rectangle Class exercise 634  
 rectangle symbol [57](#), 64  
 recursion 167, 174  
   recursion step [167](#)  
   recursive call [167](#), 168  
   recursive calls to method `fibonacci` 173  
   recursive definition 168  
   recursive evaluation 169  
   recursive function [167](#)  
   recursive function `gcd` 191  
   recursive function `power` 189  
   vs. iteration 174  
 recursion examples  
   binary search 175  
   binary tree insert 176  
   check if a string is a palindrome 175  
   Eight Queens 175  
   Factorial function 175  
   Fibonacci function 175  
   Greatest common divisor 175  
   inorder traversal of a binary tree 176  
   linear search 175  
   recursion examples (cont.)  
     linked list delete 176  
     linked list insert 176  
     maze traversal 175  
     minimum value in an array 175  
     multiply two integers 175  
     postorder traversal of a binary tree 176  
     preorder traversal of a binary tree 176  
     print a linked list backwards 176  
     print a string backwards 175  
     print an array 175  
     print an array backwards 175  
     printing a string input at the keyboard backwards 175  
     printing keyboard inputs in reverse 175  
     quicksort 176  
     raising an integer to an integer power 175  
     recursive `main` 175  
     search a linked list 176  
     selection sort 176  
     sum of the elements of an array 175  
     sum of two integers 175  
     Towers of Hanoi 175  
     visualizing recursion 175  
 recursive `main` 175  
 Recursive Selection Sort LXXV  
 recursive selection sort LXXV  
 recursive step of Quicksort LXXVI  
 recursively search a list 492  
 red breakpoint circle, solid CVII  
 redirect input from a file [508](#)  
 redirect input or output 357  
 redirect input symbol < [508](#)  
 redirect output symbol > [509](#)  
 redundant parentheses [38](#)  
 reference 852  
 reference parameter [537](#), 539  
 reference to a constant 540  
 reference to a `private` data member 624  
 reference to an automatic variable 541  
 reference to an `int` 538  
 reference to an object 606  
 references must be initialized 541  
 register 161, 162, 256  
 reinventing the wheel 8, 141, 532  
 relational operators [38](#)  
 release dynamically allocated memory 694  
 reliable integer division XCVI  
 remainder 143  
 remainder operator (%) [34](#), 51, 153  
 remove\_timer XXXVIII  
 repetition statement [56](#), [63](#)  
 replacement node [493](#)  
 replacement text [201](#), [497](#)  
 requesting a service from an object [562](#)  
 requirements 163, [553](#)  
 reserved word [42](#)  
 Resource Centers  
   [www.deitel.com/ResourceCenters.html](#) 3  
 resource leak [901](#), 903  
 restore a stream’s state to “good” 878  
 restrict XCVI  
 restricted pointer XCVI  
 resumption model of exception handling [895](#)  
 rethrow an exception [898](#)  
 Rethrowing Exceptions 918  
 return 257  
 return 0 32  
 return a result 25  
 return from a function [142](#), 143  
 return key 14, 306  
 return statement 147, [573](#)  
 return type 270, [564](#)  
   void [564](#), 573  
 return value type [146](#), 177  
 return without expression XCVIII  
 returning a reference from a function 541  
 returning a reference to a `private` data member 624  
 Returning Error Indicators from Class  
   Time’s `set` Functions exercise 634  
 reusability 837, 840  
 reusable componentry 11  
 reusable software 9  
 reuse 553, 579, 609  
 reuse classes [552](#)  
 reusing components 12  
 rewind 517  
 Richards, Martin 7  
 Richer Shape Hierarchy 776  
 right brace { } [25](#), [26](#)  
 right child [478](#)  
 right justification [357](#), 868, 869, 870  
 right justified 107, 363  
 right shift operator (>>) 673  
 right stream manipulator 868, [869](#)  
 right subtree [478](#)  
 right-justifying integers 364  
 Right-justifying integers in a field 364  
 rightmost (trailing) arguments 542  
 right-shift (>>) operator 394, 414  
 right-shift operator (>>) 855  
 rise-and-shine algorithm 55  
 Ritchie, D. 7, 15  
 robust application [890](#), 896  
 roll two dice 245  
 Rolling a six-sided die 6000 times 154  
 root node of a binary tree [478](#), 494  
 rounded [72](#)  
 Rounding 887  
 rounding 48, 167, [357](#)  
 rounding toward negative infinity XCVII  
 rounding toward zero XCVII  
 rows 229  
 RTTI (runtime type information) [780](#), 822, 827  
 rules of operator [35](#)  
 Rumbaugh, James 553, 554  
 run debugger command [CXX](#)  
 runtime error 14, 208  
 runtime type information (RTTI) 534, [780](#), 822, 827  
 runtime\_error class [892](#), 903, 910  
   what function 897  
 rvalue (“right value”) [120](#), 540, 692, 696

## S

SalariedEmployee class header file 806  
 SalariedEmployee class  
   implementation file 807  
 SalesPerson class definition 612

- SalesPerson class member-function definitions 613
- SAMPLE type [XVI](#)
- savings account example 105
- SavingsAccount Class 669
- SavingsAccount class 669
- scalable [202](#)
- scalar [212](#)
- scalars 267
- scaling [153](#)
- scaling factor [153](#), 158
- scan characters 370
- scan set [372](#), 373
- scanf [357](#)
- scanf function [30](#)
- scanning images 4
- scientific notation [359](#), 857, 873
- scientific notation floating-point value 874
- scientific stream manipulator 868, [873](#)
- scope [499](#)
- scope of an identifier [161](#), [162](#), 163, [164](#)
- scope resolution operator (`::`) 660, 840, 846
- Scoping example 165
- screen 4, 14
- screen-manager program 781
- SCREEN\_H [XII](#)
- SCREEN\_W [XII](#)
- scrutinize data 604
- search a linked list 176
- search functions of the string handling library 331
- search key [223](#)
- searching [223](#), 225
- searching a binary tree 483
- searching strings 326
- second-degree polynomial 37
- second refinement [67](#), 68, 74
- secondary storage 15
- secondary storage device 12
- secondary storage unit [5](#)
- security 629
- seed 157
- seed the `rand` function [156](#)
- SEEK\_CUR [436](#)
- SEEK\_END [436](#)
- SEEK\_SET [435](#)
- SEEK\_SET 436
- segmentation fault 33, 262
- segmentation violations [518](#)
- select a substring 698
- selection sort 176, LXXV, LXXVI
  - recursive LXXV
- selection sort algorithm [LX](#), [LX](#), [LXI](#), [LXIII](#)
- Selection Sort Function Template 849
- selection statement 58, 59
- selection structure [56](#)
- self-assignment [694](#)
- self-documenting 655
- self-documenting 30
- self-referential structure [456](#)
- self-documenting 385
- self-referential structure [384](#)
- semicolon (`;`) 26, 39, 568
- sentinel-controlled repetition 68, 69, 98
- sentinel value [67](#), 68, 71, 89
- separate interface from implementation [583](#)
- sequence structure [56](#), 58
- sequential access file 421
- sequential execution [56](#)
- sequential file [420](#), 421
- server [5](#)
- services of a class 574
- set a value 574
- set and get functions 574
- set debugger command [CXXIV](#)
- set function 651
- <set> header file 533
- set\_new\_handler function [904](#), 905
- set\_terminate function [901](#)
- set the value of a private data member 575
- set\_unexpected function [900](#), 910
- set\_color\_depth [VI](#)
- set\_gfx\_mode [VI](#), [VII](#), [XII](#)
- set\_new\_handler specifying the function to call when `new` fails 906
- setbase stream manipulator [863](#)
- setfill stream manipulator [606](#), 869, [871](#)
- <setjmp.h> 152
- setprecision stream manipulator 864
- setw 680
- setw stream manipulator 865, 869
- Shape class hierarchy 731, 776
- Shape hierarchy 830
- Shape hierarchy exercise 830
- shift [153](#)
- Shifted, scaled integers produced by `1 + rand() % 6` 153
- shifting value [158](#)
- “shipping” section of the computer 4
- short 113, 150
- short-circuit evaluation [118](#)
- showbase stream manipulator 868, [872](#)
- showpoint stream manipulator [868](#)
- showpos stream manipulator 868, [870](#)
- shrink-wrapped software 772
- sibling [478](#)
- side effect 173, 537
- side effects [152](#), 163, 834
- Sieve of Eratosthenes 251
- SIGABRT 518
- SIGFPE 518
- SIGILL 518
- SIGINT 518
- sign left justified 868
- signal [518](#)
- Signal handling 519
- signal handling library [518](#)
- signal value [67](#)
- <signal.h> 152, [518](#)
- signal.h 518
- signature 546, 698
- signatures of overloaded prefix and postfix increment operators 699
- signed decimal integer 358
- significant digits 869
- SIGSEGV 518
- SIGTERM 518
- simple condition 117
- simple interest problem 90
- simple solution strategies for Sudoku 252, 937
- simplest flowchart 121
- Simpletron 452
- Simpletron Machine Language (SML) 302, 307
- Simpletron simulator 302, 304, 306
- Simula 11
- simulating call-by-reference [258](#)
- simulation [152](#), 153, 280
- `sin` function 143
- sine 143
- single-argument constructor [696](#), 697, 708, 709, 710
- single entry/single exit control statement 121
- single entry/single exit control structure 59
- single inheritance [728](#)
- single quote (`'`) character 361
- single-selection statement [57](#)
- single-entry/single-exit control statements [58](#)
- single-subscripted array 262, 269
- singleton for Sudoku [939](#), 942
- sinking sort [216](#)
- size\_t [271](#), 327, 331
- sizeof operator [270](#), 271, 385, 433, 452, [456](#), 499, 609, 654
- skipping whitespace 863
- skipping white-space characters 868
- skips stream manipulator 868
- small circle symbol [57](#), 59
- smallest number problem 50
- SML 302, 304, 306, 307
- SMS Language 355
- “sneakernet” 5
- software [2](#), [4](#)
- software asset 553
- software-based simulation 302, 304
- software engineering 116, 164, 270, 563, [583](#)
- data hiding [572](#), 574
- encapsulation 575
- reuse 579, 583
- separate interface from implementation [583](#)
- set and get functions 574
- Software Engineering Observations overview xxvi
- software model 304
- software reusability [8](#), [144](#), 270, 513
- software reuse 532, 728, 834, 837, 838, 840
- Solution Configurations** combobox [CVII](#)
- sort algorithms
  - bucket sort LXXV
  - insertion sort [LXIV](#)
  - merge sort [LXXVII](#)
  - Quicksort LXXVI
  - recursive selection sort LXXV
  - selection sort [LX](#)
- sort function 833
- sort key [LIX](#)
- sorting 216
- sorting algorithm 269
- Sorting an array with bubble sort 217
- sorting data [LIX](#)
- sorting strings 534
- sounds in Allegro 252, 938

- source code 611, 771
- source-code file **580**
- source code of a class 611
- space **41**, 374
- space flag **367**
- spaces for padding 871
- Spam Scanner 355
- speaking to a computer 4
- special characters **310**
- Special Section: Advanced string manipulation exercises 350, 351, 352, 354
- Special Section: Building your own compiler 494
- special symbols **418**
- split the array in merge sort LXVII
- `sprintf` 322, **325**
- `sqrt` function 143
- square brackets ([]) 196
- square root 143, 864
- `srand` 156
- `sscanf` 322, **325**
- `<sstream>` header file 534
- Stack 838
- stack **151**, 254, 383, **455**, **466**, 837, 840
- stack class 833
- Stack class template 838, 844
- stack frame **151**
- `<stack>` header file 533
- stack overflow **151**
- Stack program 467
- stack unwinding **896**, 902, 903, 918
- `Stack<double>` 840, 842
- `stack<int>` 842
- `Stack<T>` 840, 842
- stacked building blocks 121
- stacking rule **121**
- stack-of-Float class 833
- stack-of-int class 833
- stack-of-string class 833
- stacks implemented with arrays 664
- “stand-alone” units 5
- Standard C 2, 252, 937, 938
- standard C functions 8
- standard data types 272
- standard error **420**
- standard error (cerr) **357**
- standard error stream (stderr) **14**
- standard exception classes 910
- standard input 30, 322, 508
- standard input file **420**
- standard input stream (cin) **357**, 854
- standard input stream (stdin) **14**
- standard input stream object (cin) **531**
- standard input/output header (stdio.h) **25**
- standard input/output library (stdio) 322
- standard libraries 13
- Standard Library
  - header files 534
- Standard Library class `string` 705
- Standard Library documentation 8
- Standard Library exception classes 910
- standard library exception hierarchy 909
- standard library header **151**
- standard library headers 151, **496**
- standard output 508
- standard output file **420**
- standard output object (cout) 854
- standard output stream (cout) 357
- standard output stream (stdout) **14**
- standard output stream object (std::cout) **531**
- standard stream libraries **854**
- standard template library (STL) 665, 818
- standard version of C 7
- “standardized, interchangeable parts” 553
- “warehouse” section of the computer 5
- state bits **858**
- statement **26**, **56**, 564
- statement terminator (;) **26**
- static **161**, **512**
- static 163, 164, 209
- static array 200
- Static arrays are automatically initialized to zero if not explicitly initialized by the programmer 210
- static binding **793**
- static data member **659**, 660, 846
- static data member tracking the number of objects of a class 663
- static data members save storage 660
- static data structures **520**
- static local object 621, 623
- static member 660
- static member function **660**
- static storage duration **162**
- status bits 878
- `std::cin` (standard input stream object) **531**
- `std::cout` (standard output stream object) **531**
- `std::endl` stream manipulator 531
- `<stdarg.h>` 152, 509
- `stdbool.h` **LXXXVII**
- `<stddef.h>` 152
- `<stddef.h>` header 255
- `stderr` (the standard error device) **14**, **420**
- `<stdexcept>` header file 534, **892**, 910
- `stdin` (standard input stream) **14**, 322, **420**
- `stdint.h` **LXXX**
- `<stdio.h>` header file **25**, 110, 152, 163, **322**, **357**, 420, 499
- `<stdlib.h>` header file 152, 153, **317**, 496, 514, **521**, 533
- `stdout` (standard output stream) **14**, **420**, 423
- step debugger command **CXXVI**
- Step Into** command (debugger) **CXII**
- Step Out** command (debugger) **CXIII**
- Step Over** command (debugger) **CXII**
- stepwise refinement 281
- stepwise refinement, **67**
- “sticky” setting 606
- `stop_midi` LI
- `stop_sample` XVII
- storage class **161**
- storage class of an identifier **161**
- storage class specifiers **161**
- storage duration **161**, 210
- storage duration of an identifier 161
- storage unit boundary 406
- Store 303
- stored array 458
- straight-line form **35**
- `strcat` function 326, **328**, 328
- `strchr` function **332**
- `strcmp` function **329**, 330, 438
- `strcpy` function 327
- `strcspn` function 331, **332**, 333
- stream **357**, **420**
- stream base 863
- stream extraction operator >> (“get from”) **531**, 548, 673, 678, 692, 855, 858
- stream input 855, 858
- stream insertion operator << (“put to”) **531**, 532, 548, 673, 678, 692, 855, 857
- stream manipulator **862**, 866, 870
- stream manipulator `showbase` 872
- stream manipulators **531**
  - `boolalpha` **874**
  - `boolalpha` and `noboolalpha` **875**
  - `dec` **863**
  - `endl` (end line) **531**
  - `fixed` **873**
  - `hex` **863**
  - `internal` 870
  - `left` **869**
  - `noboolalpha` **874**
  - `noshowbase` **872**
  - `noshowpoint` **869**
  - `noshowpos` 868, **870**
  - `nouppercase` 868, **874**
  - `oct` **863**
  - `right` **869**
  - `scientific` **873**
  - `setbase` **863**
  - `setfill` **606**, **871**
  - `setprecision` 864
  - `setw` 865
  - `showbase` **872**
  - `showpoint` **868**
  - `showpos` **870**
- stream of bytes **853**
- stream operation failed 877
- stream output 855
- `strerror` **341**
- `<string>` header file 582
- string **26**, **310**
- string 705
- string array **280**
- string class **567**, 673, 705, 707
  - at member function **707**
  - from the Standard Library 534
  - length member function **590**
  - substr member function **591**, **707**
- string comparison functions **329**, 329, 350
- string concatenation 350
- string constant **310**
- string conversion functions **317**, 317
- string copy 350
- `<string>` header file 534, **567**
- string is a pointer **311**
- string literal 208, **310**, 311
- string manipulation functions of the string handling library 326, 330, 331
- string object
  - empty string **574**
  - initial value **574**
- string processing 207
- string processing function 152



`<string.h>` header 327  
`<string.h>` header file 152  
`strlen` function 341, **341**, 341  
`strncat` function **327**, 328  
`strncmp` function **329**, 330  
`strncpy` function **327**  
 Stroustrup, B. 11, 833, 890  
 Stroustrup, Bjarne 9  
`strpbrk` **333**  
`strpbrk` function 331, 333  
`strchr` function 331, **334**  
`strspn` function 331, 334  
`strstr` function 331, **335**  
`strtod` function 317, **319**, 319  
`strtok` function 331, **336**, 336  
`strtol` function 317, **320**, 320  
`strtoul` function 317, **321**  
`struct` 196, **383**  
 structure **265**, 383  
 structure definition 384  
 structure member (.) operator **386**, 387, 392  
 Structure member operator and structure pointer operator 387  
 structure pointer (→) operator **386**, 387, 392  
 structure tag name **383**, 384  
 structure type **383**  
 structure variable 385  
 structured programming 2, 4, 10, 11, **24**, 42, 55, 56, 521  
 structured programming summary 121  
 structured systems analysis and design 11  
 Structures **383**  
 Student Inheritance Hierarchy 775  
 Student poll analysis program 203  
 student poll program 203  
 student resources xxvi  
 sub script **196**  
 subclass **728**  
 subscript 205  
 subscript notation 266  
 subscripted name used as an *rvalue* 692  
`substr` member function of class **string** **591**  
`substr` member function of `string` **707**  
 substring 698  
 substring length 698  
 subtract an integer from a pointer 273  
 subtracting one pointer from another 273  
 subtracting two pointers 275  
 subtraction 4  
 Sudoku 252, 937, 942, 943  
     3 by 3 grid 252, 937, 938, 939, 942, 943  
     9 by 9 grid 252, 937, 938  
         array 944  
         beginner's resources 938  
         brute force problem solving approach 942, 943  
         cell 252, 937  
         column 943  
         column numbering 252, 937  
         double **939**, 942  
         exhaustive brute force approach 943  
         forming puzzles 944  
         function 943  
         game players 938  
         generating a puzzle 943

Sudoku (cont.)  
     heuristic problem-solving approach 942, 944  
     hidden double **939**  
     hidden triple **942**  
     history 938  
     keep your options open heuristic 944  
     lookahead heuristic for solving Sudoku 944  
     mobile device games 938  
     nested iteration structure 942  
     player forums 938  
     programming puzzle creators 252, 937  
     programming puzzle solvers 252, 937  
     programming Sudoku puzzle solvers 942  
     programs 252, 938  
     puzzle 252, **937**  
     puzzle maker software 938  
     Resource Center 252, **938**, 938, 942  
     row 943  
     row numbering 252, 937  
     simple solution strategies 252, 937  
     singleton **939**, 942  
     solution strategies 938  
     solver 938  
     strategies 939  
     timer 938  
     triple **941**, 942  
     tutorials 938  
     two-dimensional array 252, 937, 942, 943  
     utility function 943  
     worksheets 938  
 Sudoku Resource Center 252, **938**, 942  
 sum 49  
 sum of numbers 88  
 sum of the elements of an array 175, 202  
 sum of two integers 175  
 superclass **728**  
 supercomputer **3**  
 supermarket simulation 491  
 survey data analysis **218**, 222  
 Survey data analysis program 219  
 swapping values LX, LXIV  
`switch` multiple-selection statement 57, 108, 111  
     logic 799  
     with `break` 111  
 symbol 51, **57**  
 symbol value **925**  
 symbolic constant 110, **201**, **496**, 497, 501  
 synchronize operation of an `istream` and an `ostream` 879  
 synchronous error **897**  
 syntax error 30, **30**, 63, 80, 120  
**T**  
 tab 26, 27, 41, 52, 58, 369, 374  
 table **229**  
 tabular format 198  
 tail of a queue **455**, **472**  
 tan 143  
 tangent 143  
 Target-Heart-Rate Calculator 96, 600  
 Tax Plan Alternatives 139

telephone number program 349  
 telephone-number word problem 451  
 template **833**  
 template definition 549  
 template function 549, 834  
 template keyword 549, **834**  
 template parameter **834**, 842  
 template parameter list **549**  
 templates and friends 845  
 templates and inheritance 845  
 temporary `<double>` representation 107  
 temporary copy 71  
 temporary file **517**  
 temporary object 697  
 terminate 14  
 terminate a program 906  
`terminate` function **898**, 901  
 terminating execution 666  
 terminating NULL character 207, 208, 361  
 terminating null character 311, 312, 323  
 termination housekeeping **620**  
 termination model of exception handling **895**  
 termination phase 69  
 termination request 518  
 ternary conditional operator (?:) 675  
 ternary operator 60, 173  
 test state bits after an I/O operation 858  
 Test-Drive: Body Mass Index Calculator 22  
 Test-Drive: Carbon Footprint Calculator 22  
 Testing error states 877  
 text analysis 351  
 text file 516  
 text manipulation 202  
 text processing 310  
`text_height` XXVI  
`text_length` XXVI  
`textprintf_ex` XXVI, XXVII  
`tgmath.h` LXXX  
 The "FairTax" 139  
*The Twelve Days of Christmas* 111  
 this pointer **654**, 655, 663, 676, 695  
 this pointer used explicitly 654  
 this pointer used implicitly and explicitly to access members of an object 654  
 Thompson, Ken 7  
 throw a conditional expression 896  
 throw an exception **894**  
 throw an `int` 896  
 throw exceptions derived from standard exceptions 911  
 throw exceptions not derived from standard exceptions 911  
 throw keyword **896**  
 throw list **900**  
 throw point **895**  
 throw standard exceptions 911  
`throw()` exception specification 900  
 Throwing Exceptions from a `catch` 917  
 Throwing the Result of a Conditional Expression 917  
 TicTacToe Class exercise 634  
 tie an input stream to an output stream 879  
 tilde character (~) 620

- time 152
  - Time class 633
  - Time class containing a constructor with default arguments 615
  - Time class definition 603
  - Time class definition modified to enable cascaded member-function calls 656
  - Time class member function definitions, including `const` member functions 638
  - Time class member-function definitions 605
  - Time class member-function definitions, including a constructor that takes arguments 616
  - Time Class Modification 670
  - Time class with `const` member functions 637
  - `__STDC__`, predefined symbolic constant 501
  - `__TIME__`, predefined symbolic constant 501
  - `<time.h>` 152
  - time/space tradeoff 266
  - timer in Sudoku 938
  - timers in Allegro XXXVII
  - timesharing 11
  - tmpfile 517
  - token 331, 501
  - tokenizing strings 326
  - tokens 336
  - tokens in reverse 349
  - tolower 314
  - tolower 312, 315
  - top 67
  - top-down, stepwise refinement 67, 69, 73, 74
  - top of a stack 455
  - top-down stepwise refinement 281, 282
  - tortoise and the hare 298
  - total 66
  - toupper 314
  - toupper 263, 312
  - Towers of Hanoi 175, 190
  - trailing zeros 360, 868, 869
  - transaction file 449
  - transaction-processing program 437
  - transaction-processing systems 431
  - transfer of control 56
  - transfer of control operations 303
  - transfers of control 306
  - translation 6
  - translator program 6, 7
  - trap 518
  - trap an interactive signal 519
  - trapezoid 729
  - traversing a binary tree 479
  - Treating character arrays as strings 208
  - tree 36, 254, 383, 478
  - trigonometric cosine 143
  - trigonometric sine 143
  - trigonometric tangent 143
  - triple for Sudoku 941, 942
  - `tripleByReference` 559
  - `tripleCallByValue` 559
  - true 38
  - true boolean value (C++) 536
  - truncated 71
  - truth 117
  - truth table 117
  - try block 894, 898, 903
  - try block expires 895
  - try keyword 894
  - Turing Machine 56
  - turtle graphics 246
  - two's complement 932
  - two's complement notation 932
  - two-dimensional array 252, 280, 937, 942
  - twos position 927
  - tying an output stream to an input stream 879
  - type 33
  - type checking 149, 834
  - type justification 351
  - type mismatch 262
  - type of the `this` pointer 654
  - type parameter 549, 834, 838, 844
  - type-safe linkage 538, 547
  - type template parameter 834
  - `type_info` class 825
  - `typedef` 388
  - `typedef fstream` 856
  - `typedef ifstream` 856
  - `typedef iostream` 854
  - `typedef istream` 854
  - `typedef keyword` 854
  - `typedef ofstream` 856
  - `typedef ostream` 854
  - type-generic macro XCVIII
  - `typeid` 910
  - `typeid` operator 825
  - `<typeinfo>` header file 534, 825
  - typeless language 7
  - typename 834
  - typename keyword 549, 834
  - type-safe I/O 852
  - typesetting systems 310
- ## U
- UML (Unified Modeling Language)
    - xxviii, 551, 553, 565
    - attribute 565
    - class diagram 565
    - constructor in a class diagram 579
    - data types 569
    - guillemets (« and ») 579
    - minus sign (–) 575
    - plus sign (+) 565
    - public operation 565
    - String type 569
  - UML Partners 554
  - unary operator 72, 80, 255
  - unary operator overload 675, 681
  - unary operator `sizeof` 270
  - unary scope resolution operator (`::`) 544
  - unbuffered output 856
  - unbuffered standard error stream 854
  - Uncaught Exceptions 918
  - unconditional branch 521
  - `#undef` preprocessor directive 499
  - `underflow_error` exception 911
  - underscore (`_`) 29
  - unexpected function 900, 910
  - unformatted I/O 853, 854, 861
  - unformatted I/O using the `read`, `gcount` and `write` member functions 862
  - unformatted output 857, 858
  - Unicode 331
  - Unicode character set 853
  - Unified Modeling Language (UML) 551, 553
  - unincremented copy of an object 704
  - uninitialized local reference causes a syntax error 541
  - `union` 391, 392, 393, 414
  - universal-time format 605
  - UNIX 5, 7, 110, 508, 866
  - `unload_datafile` XLVII
  - unmodifiable `lvalue` 708
  - unnamed bit field 404
  - unnamed bit field with a zero width 406
  - unresolved references 513
  - unsigned 156
  - unsigned decimal integer 358
  - unsigned hexadecimal integer 358
  - unsigned `int` 150, 156, 327
  - unsigned integer 394
  - unsigned integer 516
  - unsigned long `int` 516
  - unsigned long integer 321, 516
  - unsigned octal integer 358
  - unsigned short 150
  - unstructured flowchart 125
  - untie an input stream from an output stream 879
  - unwinding the function call stack 901
  - uppercase letter 534
  - uppercase letters 51, 152
  - uppercase stream manipulator 868, 872, 874
  - USENIX C++ Conference 833
  - user-defined class name 563
  - user-defined type 565, 696
  - user-defined types 552
  - user-defined, nonparameterized stream manipulators 867
  - using a function template 549
  - `<utility>` header file 534
  - utility function 152
    - demonstration 614
    - for Sudoku 943
- ## V
- `va_arg` 511
  - `va_copy` macro XCIX
  - `va_end` 511
  - `va_list` 511
  - `va_start` 511
  - validation 590
  - validity checking 590
  - value 30, 33, 196
  - value of a variable 33
  - variable 29
  - variable arguments header `stdarg.h` 509
  - variable initialization 279
  - variable name
    - argument 568
    - parameter 568
  - variable-length argument list 509, 510
  - variable-length array (VLA) XC
  - variables 29
  - `<vector>` header file 533
  - `vector` class 705
  - verbs in a system specification 552



vertical spacing 60, 100  
 vertical tab ('\v') 312  
 vi 12  
 video I/O 854  
 virtual destructor 826  
 virtual function 780, 792, 819, 821  
 virtual function call 821  
 virtual function call illustrated 820  
 virtual function table (*vtable*) 819  
 virtual memory 904, 906  
 virtual memory operating systems 11  
 virtual screen VII  
 Visual Basic 10  
 Visual C# programming language 10  
 Visual C++ xxviii, 10  
 Visual C++ 2008 xxvii  
 Visual C++ 2010 xxvii  
 Visual C++ Express Edition LXXIX  
 Visual Studio 12  
 Visual Studio 2005  
     *Quick Info* box CVIII  
 visualizing recursion 175, 191  
 void \* (pointer to void) 275, 338, 456  
 void keyword 564, 573  
 volatile information 4  
 volatile type qualifier 515  
 volume of a cube 535  
*vtable* 819, 822

*vtable* pointer 822

## W

w file open mode 425  
 w+ file open mode 425  
 w+ file update mode 425  
 waiting line 665  
 “walk off” either end of an array 684  
 watch debugger command CXXVIII  
 Watch window (Visual C++ 2005  
     debugger) CX, CXI  
 wb binary file open mode 516  
 wb file open mode 425  
 wb+ binary file open mode 516  
 wb+ file open mode 425  
 wchar\_t character type 854  
 wchar.h LXXX  
 wctype.h LXXX  
 what virtual function of class exception  
     892, 897, 904  
 while repetition statement 63, 63, 68, 74  
 white space 41, 374, 863  
 white-space character 58, 60, 858, 859,  
     860  
 width implicitly set to 0 865  
 width member function of class  
     ios\_base 865

width of a bit field 403, 406  
 width setting 865  
 Windows 508, 518  
 World Population Growth 139  
 World Wide Web (WWW) 6  
 worst-case runtime for an algorithm LIX  
 wraparound 704  
 Write 304  
 write function of ostream 857, 861  
 writing the word equivalent of a check  
     amount 352  
 writing to a file 423

## X

x 362

## Y

yellow arrow in break mode CVIII

## Z

0 (zero) flag 368  
 zeros and ones 418  
 zeroth element 196

# PEARSON



Thank you for purchasing a new copy of *C<sup>TM</sup> How to Program, Sixth Edition* by P. J. Deitel, H. M. Deitel. The information below provides instruction on how to access the Companion site.

## **To access the Companion Website:**

1. Go to [http://wps.prenhall.com/ecs\\_deitel\\_chtp\\_6](http://wps.prenhall.com/ecs_deitel_chtp_6)
2. From here you can register as a First-Time User or Returning User.
3. Your student access code will be sent to you by CourseSmart. On the registration page, enter your student access code. Do not type the dashes. You can use lower or uppercase letters.
4. Follow the on-screen instructions. If you need help during the online registration process, simply click on Need Help?
5. Once your personal Login Name and Password are confirmed, you can begin viewing the Companion Website.

## **To login to the website for the first time after you've registered:**

Follow step 1 to return to the Companion Website. Then, follow the prompts for "Returning Users" to enter your Login Name and Password.

**Note to Instructors:** For access to the Instructor Resource Center, contact your Pearson Representative.

**IMPORTANT:** The access code on this page can only be used once to establish a subscription to the Companion Website for *C<sup>TM</sup> How to Program, Sixth Edition*. If this access code has already been redeemed, it will no longer be valid. If this is the case, you can purchase a subscription by going to the [http://wps.prenhall.com/ecs\\_deitel\\_chtp\\_6](http://wps.prenhall.com/ecs_deitel_chtp_6) website and selecting "Get Access."